

Anatomy in Surgery

PHILIP THOREK, M.D., F.A.C.S., F.I.C.S.

Assistant Clinical Professor of Surgery (Formerly Assigned to Gross and Topographic Anatomy) University of Illinois College of Medicine Diplomate of the American Board of Surgery Associate Professor of Topographic Anatomy and Clinical Surgery Cook County Graduate School of Medicine Member of the American Association of Anatomists Fellow American College of Chest Physicians Co Surgeon in Chief of the American Hospital Associate Attending Surgeon of the Cook County Hospital Senior Attending Surgeon of the Alex. M. Brothers Hospital

720 Illustrations, 211 in Color


Drawn by Carl T. Linden
*Instructor in Medical Illustration
University of Illinois College of
Medicine Chicago*



Philadelphia

London

Montreal

J.  B. LIPPINCOTT COMPANY

COPYRIGHT 1951
By J B LIPPINCOTT COMPANY

1

THIS BOOK IS FULLY PROTECTED BY COPYRIGHT
AND WITH THE EXCEPTION OF BRIEF EXTRACTS
FOR REVIEW NO PART OF IT MAY BE REPRODUCED
IN ANY FORM WITHOUT THE WRITTEN PERMIS-
SION OF THE PUBLISHERS

THIRD EDITION 1954

PRINTED IN THE UNITED STATES OF AMERICA

TO MY PARENTS

Foreword

In this book on surgical anatomy the author has deviated considerably from the usual plan and has presented the material with a stronger surgical viewpoint. Obviously it will appeal primarily to surgeons and particularly to those in training, because operative technique is included with the anatomy. The entire body is covered in the anatomic discussion and the principles of technique described for the important operations. This method of presentation of anatomic data has an obvious advantage in that it correlates the anatomy with the technical phase of surgery. Without question the young surgeon will find that this integration will make it much easier for him to remember the important anatomic details. The author is to be complimented in the efficiency of the correlation of anatomy and surgery.

The text is written in a clear and refreshing style. It is obvious that the author is a trained and effective teacher. The accuracy of thought and the continuity of expression are definite proof that the author has spent an enormous amount of time in preparing the text as well as in choosing the illustrations.

Another attractive feature in this volume is the caliber of illustrations, all of which have been furnished by one artist. The drawings are excellent and are to be commended for their clarity and accuracy. It is a relief to note the large size of lettering for the labels; this feature makes it easy to find and identify the various details of a drawing. About half of the illustrations are in color—a feature which adds greatly to their value.

Anatomy is an important phase of surgery and is very necessary in the training of a surgeon. Years ago it was perhaps overemphasized in the prerequisites of a surgeon. During recent years when a knowledge of physiology was found to be so important to the surgeon, anatomy has to a great extent been neglected. The pendulum is threatening to swing too far and give the young surgeon the idea that he need not spend time on anatomy. The time will never come when anatomy will be unimportant to the surgeon; the young surgeon must always appreciate this. It may be safe to prophesy that several decades hence the surgeon's work will be confined largely to the correction of congenital deformities and the treatment of traumatic injuries. If this situation should come to pass the relative importance of anatomy to the surgeon will again become very prominent and justly so.

For the above reason the young surgeon should find this volume decidedly helpful in his training period. Since anatomy is a science which unfortunately is readily forgotten the older surgeon likewise should find the contents very useful. The author is to be congratulated on having prepared a volume with so many fine qualities.

WARREN H. COLE

Preface

This book on surgical anatomy is the culmination of seventeen years' experience in teaching gross and topographic anatomy and surgery. I have had the good fortune of constant direct contact with both the undergraduate student at the University of Illinois College of Medicine and the postgraduate student at the Cook County Graduate School of Medicine. It was only through personally appreciating the dilemma of the medical student and his need to know clinical surgery as well as the avidity of the postgraduate student for additional anatomic knowledge that the idea for this book presented itself.

When the text was started twelve years ago, my notes previously prepared for lectures and anatomic demonstrations formed the nucleus for this work. Fifteen years of clinical observation as seen at the operating table provided additional data.

It is intended that *Anatomy in Surgery* might act as a means of narrowing the gap which exists between freshman anatomy and operative surgery. An attempt has been made to unify this complex subject by a simple method of presentation and correlation. Punctilious attention has been given to the anatomic details both in the text and in the illustrations. All of the drawings are original; many are presented in third dimensional views and all are closely analogous to the text. If any reference sources have not been properly acknowledged it is indeed an unintentional oversight.

I am deeply indebted to the artist, Mr. Carl Linden. His untiring efforts, understanding, wholehearted and sincere co-operation have made working with him a memorable experience. The creative talent which he possesses and his ability to depict true anatomic relationships are responsible for the illustrations of this book.

I am most grateful to Mrs. Mary Y. Nugent for her invaluable assistance in preparing the manuscript, arranging material and reading the proof.

I wish to thank the officers and the personnel of the J. B. Lippincott Company, particularly Mr. Walter Kahoe, Mr. Stanley A. Gillet and Mr. Edwin H. Bookmyer, whose splendid co-operation and keen interest have made this work possible.

PHILIP THOREK

A List of Basic References

- 1 Anson *Human Anatomy* Saunders
- 2 Brash and Jamieson *Cunningham's Manual of Practical Anatomy* Oxford
- 3 Brash and Jamieson *Cunningham's Text Book of Anatomy* Oxford
- 4 Braus *Anatomie Des Menschen* Springer
- 5 Callander, *Surgical Anatomy* Saunders
- 6 Corning *Lehrbuch Der Topographischen Anatomie* Bergmann
- 7 Grant *An Atlas of Anatomy* Williams and Wilkins
- 8 Grant *Method of Anatomy* Williams and Wilkins
- 9 Jamieson *A Companion to Manuals of Practical Anatomy* Oxford
- 10 Jamieson *Illustrations of Regional Anatomy* Livingstone
- 11 Jones and Shepard *Manual of Surgical Anatomy* Saunders
- 12 Keibel Mall *Human Embryology* Lippincott
- 13 Lewis *Gray's Anatomy* Lea and Febiger
- 14 McGregor *Synopsis of Surgical Anatomy* Williams and Wilkins
- 15 Patten *Human Embryology* Blakiston
- 16 Schaeffer *Morris Human Anatomy* Blakiston
- 17 Sobotta *Atlas of Human Anatomy* Stechert
- 18 Spalteholz *Hand Atlas of Human Anatomy* Lippincott
- 19 Toldt *An Atlas of Human Anatomy* Macmillan
- 20 Treves and Rogers *Surgical Applied Anatomy* Cassell

Contents

SECTION ONE THE HEAD

1. SCALP	3
Scalp Proper	3
Skin	3
Connective Tissue	3
Aponeurosis	3
Loose Connective Tissue	4
Periosteum	5
Vessel, Nerves and Lymph Vessels	5
Carotid Aneurysm	7
2. SKULL	9
Embryology	9
Fontanelles	9
Skull Proper	9
Norma Verticalis	10
Norma Basalis	11
Norma Frontalis	14
Norma Lateralis	19
Norma Occipitalis	21
Interior of the Skull	22
Skull Cap	22
Base of the Skull and the Cranial Fossae	22
Surgical Considerations	26
Trephining Operations	26
Osteoplastic Craniotomy	26
Subtemporal Decompression	28
Intracranial Hemorrhage	28
3. BRAIN	30
Embryology	30
Brain Proper	30
Cerebral Hemispheres and Lobes	30
Inferior Surface of Brain Cerebellum and Medulla Oblongata	36
Meninges	39
Intracranial Spaces	41
Ventricular System and Cerebrospinal Fluid	42
Surgical Considerations	44
Encephalography	44
Ventriculography	47
Cisternal Puncture	48
Arterial Supply	49

3	BRAIN—(Continued)	
	Veins of the Head and the Brain	
	Emissary Veins	
	Diploic Veins	21
	Cerebral and Cerebellar Veins	
	Venous Dural Sinuses	3
	Hypophysis	
	Embryology	
	Adult Hypophysis	
	Surgical Considerations	
4	CRANIAL NERVES	
5	SPECIAL SENSES	
	The Eye and Its Appendages	
	Lachryal Layers and Practical Considerations	
	Lacrimal Apparatus	13
	Orbit	16
	Eye-ball	18
	Orbital Fascia (Tenon's Capsule)	23
	Muscles	25
	Vessels and Nerves	25
	Nose	29
	External Nose	29
	Internal Nose	30
	Vessels and Nerves	31
	Practical Considerations	36
	Fractures, Rhinocopy, Epistaxis Polypi and Septal Deformities	36
	Paranasal Sinuses	37
	Maxillary Sinus	38
	Frontal Sinuses	101
	Sphenoid Sinus	102
	Ethmoid Sinuses (Cells)	104
	Auditory Apparatus	105
	External Ear	105
	Tympanic Membrane	106
	Middle Ear	109
	Clinical and Surgical Considerations	112
	Mastoiditis Simple and Radical Mastoid Surgery	112
	Internal Ear	113
6	FACE	119
	Embryology	119
	Skin Blood and Nerve Supply	119
	Clinical and Surgical Considerations	125
	Muscles	126
	Parotid Region	129
	Parotid Gland	129
	Surgical Considerations	132
	Parotidectomy	1
	Parotid Abscess	

Temporal and Infratemporal Regions	134
Muscles of Mastication	134
Vessels and Nerves	137
Temporomandibular Joint	141
Mouth and Regions That Surround It	143
Lip Region	143
Surgical Considerations	146
Harelip	146
Carcinoma of the Lip	146
Mouth Proper	147
Surgical Considerations	157
Staphylorrhaphy and Uvuloplasty	157
Practical Considerations	160
Three Muscular Facial Spaces and One Vascular Visceral Space	160
Upper and Lower Lip Infections	162
Pharynx	163
Tonsils	163
Surgical Considerations	165

SECTION TWO

THE NECK

7 THE NECK IN GENERAL	169
Embryology	169
Visceral Arches	169
Cervical Sinus	171
Surgical Considerations	171
Bony Cartilaginous Framework	173
The Sternocleidomastoid Muscle	174
Deep Cervical Fascia (Fascia Colli)	176
Superficial Layer (General Investing or Enveloping Fascia)	176
Middle Layer (Pretracheal Fascia)	178
Deep Layer (Prevertebral Fascia)	178
Buccopharyngeal Fascia	179
Submental Triangle	180
8 THE ANTEROLATERAL REGION OF THE NECK	181
Anterior Triangle	181
Superficial Structures (Skin Superficial Fascia, Platysma and Lymph Nodes)	181
Surgical Considerations	188
Nerves	183
Muscles	191
Vessels and Carotid Sheath	193
Thyroid Gland	203
Innervations of Thyroid Vessels	211
Thyroidectomy	215
Parathyroid Glands	219
Thymus Gland	219

3	BRAIN—(Continued)	
	Veins of the Head and the Brain	50
	Missary Veins	50
	Diploic Veins	51
	Cerebral and Cerebellar Veins	52
	Venous Dural Sinuses	53
	Hypophysis	57
	Embryology	57
	Adult Hypophysis	58
	Surgical Considerations	59
4	CRANIAL NERVES	72
5	SPECIAL SENSES	72
	The Eye and Its Appendages	72
	Ictids, Layers and Practical Considerations	73
	Lacrimal Apparatus	76
	Orbit	78
	I eyeball	83
	Orbital Muscles (Tenon's Capsule)	85
	Muscles	85
	Vessels and Nerves	89
	Nose	89
	External Nose	90
	Internal Nose	95
	Vessels and Nerves	96
	Practical Considerations	96
	Fractures Rhinocopy Epistaxis Polyp and Septal Deformities	97
	Paranasal Sinuses	98
	Maxillary Sinus	101
	Frontal Sinus	102
	Sphenoid Sinus	104
	Ethmoid Sinuses (Cells)	105
	Auditory Apparatus	105
	External Ear	107
	Tympanic Membrane	109
	Middle Ear	112
	Clinical and Surgical Considerations	112
	Mastoiditis Simple and Radical Mastoid Surgery	115
	Internal Ear	119
6	FACE	119
	Embryology	119
	Skin Blood and Nerve Supply	125
	Clinical and Surgical Considerations	126
	Muscles	129
	Parotid Region	129
	Parotid Gland	132
	Surgical Considerations	132
	Parotidectomy	134
	Parotid Abscess	

Aspiration of the Chest	279
Thyroidectomy	279
14 LUNGS (PULMONES)	303
Embryology	303
The Lungs Proper	303
Surfaces	306
Border	307
The Lobes and Fissures and Bronchopulmonary Segment	307
Variations	311
The Root of the Lung (Radix Pulmonis)	312
Blood Vessels	313
Surgical Considerations	315
Pneumothorax	315
Lobectomy and Pulmonary Segmental Resection	316
Lung Abscess	316
15 THE TRACHEA AND EXTRAPULMONARY BRONCHI	318
The Trachea Proper	318
Relations	318
Right and Left Extrapulmonary Bronchi	319
16 MEDIASTINUM (INTERPLEURAL SPACE)	321
Boundaries of the Mediastinum	321
Chief Contents of Each Mediastinal Space	322
Surgical Considerations	325
Drainage of Mediastinal Abscess	323
Carcinoma of the Esophagus	325
Trans thoracic Supradiaphragmatic Section of the Vagus Nerves (Vagotomy)	329
17 PERICARDIUM	330
Pericardial Sac	330
Pericardial Layers	330
Fibrous Pericardium	330
Visceral and Parietal Layers	330
Surgical Considerations	332
Pericardiocentesis	332
Pericardiostomy (Pericardiotomy)	332
18 HEART	335
The Heart Proper	335
The Superior and Inferior Venae Cavae	337
Compartments of the Heart	339
Blood Vessels and Nerves	343
Thoracic Projection of the Heart and Great Vessels	347
Area of Maximum Audibility of Heart Valve Sounds and Their Thoracic Projection	350
Surgical Considerations	352
Exposure of the Heart	352

8	THE ANTEROLATERAL REGION OF THE NECK—(Continued)	
	Surgical Considerations—(Continued)	
	Cervical Portion of Esophagus	221
	Esophageal Diverticulum	222
	Submylohyoid (Digastric) Triangle	224
	Pharynx	228
	Larynx	232
	Posterior Triangle	243
	Practical and Surgical Aspects	247
9	ROOT OF THE NECK	250

SECTION THREE THE THORAX

10	BONY THORAX	257
✓	Ribs (Costae)	258
	Sternum (Breast Bone)	262
	Muscles Which Attach to the Sternum	264
	Sternoclavicular Joint	265
	Articular Relations	265
	Movements	265
	Sternocostal Joints	267
	Intercostal Spaces	267
	Muscles	267
	Blood Vessels	269
	Arrangement of the Twelve Spinal Nerves	271
11	BREAST (MAMMARY GLAND)	274
	Embryology and Embryologic Malformations	274
	Mammary Gland Proper (Structure and Form)	274
	Vessels, Nerves and Lymphatics	277
	Surgical Considerations	281
	Breast Abscess	281
	Radical Mastectomy	281
12	DIAPHRAGM	287
	Embryology	287
	Diaphragm Proper	287
	Nerve and Blood Supply	290
	Actions	290
	Foramina (Openings)	290
	Surgical Considerations	292
✓	Diaphragmatic Hernias	292
13	PLEURAL CAVITIES AND PLEURAE	294
	Visceral and Parietal Pleurae	294
	Surface Markings	295
	Surgical Considerations	297
	Fractured Ribs	297

Stomach (Ventriculus or Gaster)	422
Embryology	422
The Adult Stomach	423
Vessels and Nerves	429
Attachments of the Stomach (Omenta)	434
Surgical Considerations	436
Gastrojejunotomy	436
Gastrectomy	439
Transabdominal Vagus Nerve Section (Vagotomy)	441
Circumcision of the Lower Third of the Esophagus and the Cardiac End of the Stomach	441
Closure of a Perforated Peptic Ulcer	441
Small Intestine	444
Duodenum	445
The Jejunum	454
Meckel's Diverticulum	460
Surgical Considerations	461
Open and Closed Anastomoses	461
Enterotomy	462
Large Intestine (Colon)	462
Embryology	462
The Large Intestine Proper	463
Cecum	465
Verruiform Appendix	468
Appendectomy	470
Ascending Colon	470
Right Colic (Hepatic) Flexure	473
Transverse Colon	473
Left Colic (Splenic) Flexure	476
Descending Colon	476
Ileocecal (Sigmoid) Colon	477
Rectum	477
Anal Canal	480
Vascular Supply of the Colon, the Rectum and the Anal Canal	483
Rectal Surgery	491
Hemorrhoidectomy	491
Ischiorectal Abscess and Fistulas	491
Lymphatics of the Colon	491
Nerve Supply of the Colon	494
Large Bowel Surgery	495
Cecostomy	495
Colostomy	495
Resection of the Colon	496
Mikulicz and Miles Procedures	497
Sliding Hernia	502
THE LIVER (HEPAR)	504
Embryology	504
The Liver Proper	504
Lobes and Surfaces	508
Vessels, Nerves and Lymphatics	510

18	HEART—(Continued)	
	Surgical Considerations—(Continued)	
	Wounds of the Heart	352
	Pericardiectomy	353
	Patent Ductus Arteriosus	353
	Surgery of the Aorta	353
19	THE AZYGOS SYSTEM OF VEINS AND THE SUPERIOR VENA CAVA	354
20	THE THORACIC DUCT	356
	Embryology	356
	The Adult Duct	356
21	THE SYMPATHETIC CHAIN	359
	Surgical Considerations	360
	Thoracic Sympathectomy	360

SECTION FOUR THE ABDOMEN

22	ABDOMINAL WALLS	363
	Anterior Abdominal Wall	363
	Boundaries	363
	Surface Anatomy	363
	Nerves and Superficial Fascia	364
	Arteries, Veins and Lymphatics	367
	Muscles	369
	Surgical Considerations	372
	Abdominal Incisions	372
	Incisional Hernias	376
	Inguinal Region	379
	Inguinal Hernias Indirect and Direct	391
	Umbilical Region	394
	Repair of Umbilical Hernias	397
	Posterolateral Wall (Lumbar or Iliocostal Region)	397
	Musculature (Superficial Middle and Deep Layers)	398
	Kidneys	404
	Surgical Considerations	410
	Nephrectomy	410
	Nephropexy	412
	The Suprarenal Glands	412
23	ESOPHAGOGASTRO INTESTINAL TRACT	413
	Embryology	413
	Rotation and Fixation	413
	Fetal Circulation	417
	The Esophagus	418
	Embryology	418
	Adult Esophagus	418
	Vessels and Nerves	420

37 URETHRA	556
Male	556
Female	557
38 THE URINARY BLADDER	562
The Bladder (Vesica Urinaria)	562
Embryology	562
The Adult Bladder	563
Arteries and Nerves	568
Surgical Considerations	569
Injuries of the Bladder	569
Approaches to the Bladder	569
Suprapubic Cystostomy	570
Pelvic Vessels in the Male	570
Deferent Ducts	571
Seminal Vesicles	573
Prostate Gland	573
Surgical Considerations	578
Prostatic Abscess	578
Prostatectomy	578
Pelvic Vessels in the Female	581
Embryology	581
The Six Ligamentous Supports	582
Uterus	585
Vagina	588
Uterine Tubes (Fallopian Tubes)	591
Ovaries	592
Surgical Considerations	621
39 THE UTERUS	594
Surgical Considerations	598
Exposure of the Uterus	598
40 NEUROVASCULAR STRUCTURES	600
Vessels and Lymphatics	600
Arteries	600
Veins	606
The Lymphatics	607
Surgical Considerations	609
Ligation of the Inferior Vena Cava	609
Nerves	612
The Lumbar Sympathetic Chain	614
Surgical Considerations	616
Lumbar Sympathetic Block	616
Lumbar Sympathectomy	618
Presacral Superior Hypogastric Neurectomy	621
Surgical Considerations of the Uterus and the Adnexae	621
Hysterectomy	621
Salpingectomy and Salpingo Oophorectomy	622
Surgery for Retrodisplacement of the Uterus	623

24	THE LIVER (HEPAR)—(<i>Continued</i>)	
	The Liver Proper—(<i>Continued</i>)	
	Surface Anatomy	511
	Practical and Surgical Considerations	511
	The Six Subphrenic Spaces	511
	Drainage of Subphrenic Abscesses	511
	Portacaval Shunts	511
25	GALLBLADDER AND BILE DUCTS	511
	Embryology	511
	Adult Gallbladder and Bile Ducts (Vessels)	511
	Gallbladder Surgery	512
	Cholecystostomy	512
	Cholecystectomy	512
	Choledochostomy	512
	Cholecysto enterostomy	512
26	THE SPLEEN	529
	Embryology	529
	Adult Spleen	529
	Vessels	531
	Splenectomy	531
27	THE PANCREAS	534
	Embryology	534
	Adult Pancreas	534
	Vessels	536
	Ducts	537
	Surgical Considerations	539
	Pancreatoduodenectomy	539
	Surgery for Pancreatitis	539
28	THE BLOOD SUPPLY OF THE GUT	540
	Celiac Artery (Celiac Axis)	540
	Mesenteric Vessels	541

SECTION FIVE THE PELVIS

29	PELVIC BONES	547
	Hip Bone	547
	Ilium	547
	Ischium	549
	Pubis	550
	Acetabulum	550
	Sacrum and Coccyx	550
	Sacrum	550
	Coccyx	553
	Sacrococcygeal Region	553
	Sacro Iliac Region	553
	Muscular and Ligamentous Attachments	554

SECTION SIX MALE PERINEUM AND EXTERNAL GENITALIA

34	MALE PERINEUM	671
	Embryology	671
	The Urogenital Triangle	627
	The Superficial Perineal Pouch	630
	The Deep Perineal Pouch (Urogenital Diaphragm)	631
35	EXTERNAL GENITALIA	633
	Penis	633
	The Superficial Structures	633
	Urethra	631
	Scrotum	639
	Testis	641
	Spermatic Cord	647
	Vessels and Nerves	643
	Surgical Considerations	643
	Varicocele	645
	Hydrocele	645
	Circumcision	646

SECTION SEVEN FEMALE PERINEUM AND EXTERNAL GENITALIA

36	FEMALE PERINEUM	649
	The Urogenital Region	649
	External Genitalia	649
	Musculature of the Perineum and the Pelvis	655
	The Urogenital Diaphragm	656
	The Pelvic Diaphragm	657
	The Anal Triangle	658
	Surgical Considerations	661
	Vaginal Hysterectomy	661
	Repair of Cystocele (Anterior Colporrhaphy)	663
	Repair of Rectocele (Perineorrhaphy)	664
	Posterior Colpotomy	664
	Vesicovaginal Fistulae	664
	Rectovaginal Fistulae	664

SECTION EIGHT THE SUPERIOR EXTREMITY

37	SHOULDER	669
	Axillary and Pectoral Regions	669
	Axillary Vessels	672
	Brachial Plexus	675




FIG. 2 The vessels and the nerves of the scalp and the side of the face. All the nerves of the scalp are sensory, with the exception of the facial nerve which supplies the epicranius muscle.

PERIOSTEUM

The pericranium (periosteum) refers to the outer or external periosteum of the skull. It is loosely attached to the surface of the skull bones except at the suture lines and over the temporal fossae. At the suture lines it dips between the bones as a suture membrane which is blended with the periosteum of the interior of the skull, this latter being known as the outer layer of the dura. Collections of fluid beneath the pericranium can easily strip it but cannot pass beyond the suture line, and for this reason any swelling such as cephalhematoma will maintain the shape of the bone to which it is related. Surgeons do not hesitate to remove this

layer because the blood supply to the skull can be provided through the attachment of muscles.

VESSELS, NERVES AND LYMPH VESSELS

Arteries. The vessels of the scalp (Fig. 2) are numerous and they anastomose freely. The arteries are derived from both the internal and the external carotids. Anteriorly the supratrochlear and the supraorbital arteries ascend over the forehead accompanied by the nerves of the same name. Both are branches of the ophthalmic artery (internal carotid). Their terminal branches anastomose with each other, with their fel-




FIG 1 Diagrammatic representation of the five layers of the scalp and the deeper structures. The word 'SCALP' is spelled when one recalls the first letter of each layer. The loose connective tissue layer is the 'dangerous area' since the emissary veins are located here and it is in this plane that pus or blood may spread.

attached to the zygomatic arch. At a scalp wound gapes, then the examining physician may be certain that the galea has been divided transversely, since the skin is so firmly attached to this structure that no gaping would otherwise be possible.

LOOSE CONNECTIVE TISSUE

The loose connective tissue has been referred to as the subepicranial connective tissue space. It lies between the aponeurotic layer above and the pericranium below and is really not a true space but a potential one. The important emissary veins connecting the venous sinuses in the skull with the veins of the scalp traverse this area. This loose areolar tissue permits free movements of the scalp and allows large collections of blood or pus to accumulate under the scalp without

undue stretching. The first three layers of the scalp can be easily separated from the pericranium through this space, and the knowledge of this plane permitted the Indians to become so clever at 'scalping'. The space is closed posteriorly by the attachments to the superior nuchal line and laterally to the zygomatic arch, since the frontalis has no attachment to bones anteriorly, it is open in this direction. Due to this lack of attachment anteriorly, bleeding may occur into the loose connective tissue layer in head injuries; after a day or two of slow gravitation downward, the hemorrhage appears first in the upper eyelids and later in the lower. This subaponeurotic space has been called the 'dangerous area of the scalp' because of the presence of the emissary veins which may propagate infections.

lear the supra orbital and the auriculotemporal are branches of the trigeminal the great auricular the lesser and the great occipital are of spinal origin. Any of these may be affected by referred or neuralgic pains the occipital and the supra orbital being most commonly involved.

the lymphadenitis associated with scalp pathology.

CIRSOID ANEURYSM

Reid and Andrus believe that cirsoid aneurysms are abnormal arteriovenous communications. Ligation of the surrounding vessels




FIG. 4. Operation for cirsoid aneurysm. Short individual incisions are placed over the main pulsating vessels which lead to the aneurysm. These are ligated and divided. A continuous lock stitch is placed around the mass and the aneurysm is removed.

Lymph Vessels. The lymph vessels of the scalp and the face (Fig. 3) drain downward from the occipital region to the occipital glands from the parietal and the temporal regions to the pre and the post auricular glands and from the frontal region to the submaxillary glands. Infected wounds, pediculi and furuncles usually cause

improves the condition but rarely cures it. Therefore, excision is the treatment of choice. Hemorrhage is the greatest danger.

Technic (Fig. 4). Short individual incisions are placed over the pulsating vessels leading to the aneurysm. These usually include the superficial temporal artery and vein, the occipital artery and vein, the supra

lows of the opposite side and with the superficial temporal (external carotid) of the same side. Laterally, the superficial temporal artery ascends in front of the ear (tragus), accompanied by the auriculotemporal nerve. It

are arranged in five groups which, considered from before backward, are (1) The *supratrochlear*, appearing through the supratrochlear notch of the frontal bone and supplying the region of the glabella, (2) the *supra*




FIG 3 Regional lymph drainage of the scalp. This represents a general plan which is subject to many variations.

divides into anterior and posterior branches which supply large areas of scalp and then it anastomoses with the corresponding vessels of the opposite side. Posteriorly there are two arteries on each side, the posterior auricular and the occipital. The posterior auricular ascends behind the auricle and supplies that structure and adjoining parts of the scalp. The occipital extends over the occipital area accompanied by the greater occipital nerve.

Veins. The supratrochlear and the supraorbital veins unite to form the anterior facial vein (see p. 120), which makes an important communication with the superior ophthalmic

Nerves. The nerves of the scalp (Fig. 2)

orbital, which emerges through the supraorbital notch or foramen of the frontal bone, runs upward over the forehead and supplies the scalp as far as the crown of the head, (3) the *auriculotemporal*, which passes in front of the tragus of the ear and supplies the side of the scalp, (4) the *posterior auricular*, supplying a small area behind the ear, (5) the *great occipital*, which supplies the large area of skin over the occipital region and extends forward to the vertex. The lesser occipital nerve may or may not extend into the scalp.

All the nerves of the scalp are sensory with the exception of the facial, which supplies the epicranium muscle. The supratroch

2

Skull

EMBRYOLOGY

The brain of the fetus is surrounded by a membranous capsule which is continuous with a similar capsule surrounding the spinal cord. Chondrification begins in the base but ossification begins in the calvarium (supra-orbital portion) before the chondrifying process has progressed very far. Bones which are formed in membrane are the frontal, parietal, squamous temporal, the greater wings of the sphenoid (except their roots) and the occipital above the nuchal lines. Centers appear for these bones about the seventh week. In general the older basal portion of the skull is preformed in cartilage but the facial and the roofing bones are formed intramembranously.

At birth the skull reveals a lack of firmness between the bone sutures so that considerable movement can be produced thus facilitating the molding which takes place during childbirth.

FONTANELLES

The fontanelles (Fig 5) are unossified spaces which appear at the angles of the parietal bones. The *anterior fontanelle* is four sided and is bounded by the margins of the two frontal and the two parietal bones. Intracranial pulsations may be transmitted through this tissue and are usually visible in infants. Extension of the bony margins closes this fontanelle before the age of two years. The *posterior fontanelle* is three sided and is bounded by the occipital and the two parietal bones; its sides pass laterally into the *lambdaoid sutures* and its apex to the *sagittal suture*. It is usually closed during the first year of life. These membranous

areas exist in the midline of the cranium and are of great value in determining the position of the fetal head during labor. Fontanelles are also present at the pterion and the asterion.

The suture between the two frontal bones of the newborn child disappears around the third year of life but may persist indefinitely giving rise to a *metopic suture*.

SKULL PROPER

The word skull refers to the entire skeleton of the head and the face including the mandible. 'Cranium' refers to the skull minus the mandible. 'Calvarium' refers to the skull after the bones of the face have been removed (that portion which is above the supra-orbital ridges).

The skull as a whole is slightly flattened from side to side. When viewed from above it appears to be smooth but from below is very uneven. It is oval in shape wider behind than in front and is composed of flattened or irregular bones that are immovably joined together with the exception of the mandible. The skull is made up of twenty-four bones including the mandible and constitutes the skeleton of the head and the face. The bones consist of two tables or plates of compact substance which enclose a layer of spongy bone between them known as the diploe. In some of the bones the diploe is absorbed leaving cavities which are referred to as air sinuses and are situated between the tables of compact bone. The sinuses communicate with the cavity of the nose and have a mucous lining that is also continuous with the nasal cavity.

The exterior of the skull should be viewed

orbital vessels and the frontal vein. These are ligated and divided. A continuous locked suture is placed around the mass to control bleeding. A U shaped incision is made within the hemostatic suture, and a skin flap is re-

flected upward thus exposing the aneurysm. The mass of vessels is carefully excised. The encircling hemostatic suture is removed bit by bit, all bleeding points are controlled and the skin flap is sutured into place.

lambdoid suture and the sagittal suture with the anterior fontanelle have a definite resemblance to an arrow. The meeting point between the coronal and the sagittal sutures

is less serrated between the two parietal foramina.

NORMA BASALIS

(Fig. 7) This view is obtained when the




FIG. 6 The top of the skull viewed from above (norma verticalis)

is called the *bregma*. At birth the parts of the frontal and the parietal bones around the bregma are not fully ossified because of this a lozenge shaped membranous area results which is called the anterior fontanelle. This yields to the touch and the pulse rate can be counted here. That point at which the sagittal and the lambdoid sutures meet is called the *lambda* and marks the site of the posterior fontanelle. The *vertex* the highest point of the skull is on the sagittal suture near its middle. The *parietal foramen* is a small opening present on either side of the sagittal suture. It is usually big enough to admit a pin and a small artery and vein pass through it. This vein connects the veins of the scalp with the superior sagittal sinus, hence an infection from the scalp may travel along this vein and involve the sinus. It is interesting to note that the sagittal suture

is less serrated between the two parietal foramina. The anterior part of this aspect is occupied by the *bony palate* which is formed by the palatine processes of the maxillae and the horizontal plates of the palatine bones.

In the median plane anteriorly, the *maxillary fossa* receives the openings of the lateral incisive canals which transmit the terminal parts of the greater palatine vessels to the nose and the descending terminal branches of the long sphenopalatine nerves. Anterior and posterior median incisive canals are sometimes present. The *greater palatine fossa* which transmits the greater palatine vessels and nerves is found in the postero-lateral corner near the last molar. The *lesser palatine fossae* lie immediately behind the greater. Behind and above the hard palate are the *choanae* (the posterior bony aper-

from five points, each of which is referred to as "norma" *norma verticalis* (from above) *norma basalis* (from below) *norma frontalis* (from in front) *norma occipitalis*

united by serrated bony seams called sutures, which have interlocking jagged saw-like edges. The suture that unites the frontal to the two parietal bones runs across the




FIG 5 The fetal skull (A) Lateral view, showing average measurements (B) Oblique view showing the sutures and fontanelles

(from behind) *norma lateralis* (from the side)

NORMA VERTICALIS

(Fig 6) The top of the skull shows portions of four bones: the frontal, the occipital, the right and the left parietals. They are

skull from side to side in a crownlike arrangement and is known as the *coronal suture*. That suture which unites the occipital to the two parietal bones resembles the Greek capital letter lambda which looks like an inverted "V" and is known as the *lambdoid suture*. *Sagitta* means arrow, and the

cated at the base of the medial pterygoid plate. The *carotid canal* which is posterolateral to the foramen lacerum is a tunnel in the petrous portion of the temporal bone through which the internal carotid artery travels on its way to the cranial cavity. From its opening the canal leads upward for a short distance, bends to become horizontal and runs in a medial direction and forward to open into the foramen lacerum. The canal is in immediate relationship to the middle and the internal ears. The thumping sounds that one hears in the head during moments of excitement or after violent exertion are due to the beating of the internal carotid artery against the bone that separates it from the internal ear (Fig. 74A).

The *jugular foramen* is a large opening with uneven margins situated directly behind the carotid canal. The largest structure in this foramen is the internal jugular vein. Other structures associated with it will be reviewed when the interior of the base of the skull is discussed. The jugular foramen is opposite the external auditory meatus and that part of the bone which bounds the foramen forms the floor of the middle ear. It is important to keep this relationship in mind since in diseases of the middle ear infection may pass through the bone and attack the internal jugular vein.

Directly lateral to the foramen is the *styloid process*. Two ligaments (the stylohyoid and the stylomandibular) and three muscles (the stylohyoid, the stylohyoid and the stylopharyngeus) are attached to this process. The stylohyoid ligament runs from its tip to the hyoid bone and the stylomandibular ligament extends from the front of it to the posterior border of the mandible. The stylomandibular ligament is a thickened part of the fascia that covers the anteromedial aspect of the parotid gland. The *stylomastoid foramen* is found immediately at the base of the styloid process and is the foramen that transmits the facial nerve from the brain to the exterior of the skull. The stylomastoid branches of the posterior au-

ricular vessels are also transmitted by this foramen.

The *mastoid process* can be palpated under cover of the lobule of the auricle but is not recognizable as a bony structure until the end of the second year. The *mastoid foramen*, which is variable in size and position, is found posterior to the mastoid process. It transmits a vein to the transverse sinus and a small branch of the occipital artery to the dura mater.

The *foramen magnum*, the largest bony foramen in the skull, is the opening through which the medulla oblongata or lowest subdivision of the brain becomes continuous with the spinal cord. Its level is approximately the same as that of the mastoid process on the side of the head and it is opposite a point on the back of the neck midway between the external occipital protuberance and the spine of the second cervical vertebra.

The *occipital condyles* are the large smooth and rather oblong protuberances that lie at the margins of the foramen magnum. They articulate with the atlas, and nodding movements of the head take place at the joints between the atlas and the condyles.

The *anterior condylar canal* is above the lateral margin of the anterior part of the condyle. It is usually hidden by the condyle and the skull must be tilted before the opening can be seen. The anterior condylar is smaller than the jugular foramen and is the opening that transmits the hypoglossal nerve. The *posterior condylar canal* when present passes above the posterior part of the condyle and opens into the posterior fossa. It transmits an emissary vein that connects the sigmoid venous sinus with the suboccipital venous plexus.

Behind the foramen magnum a bony crest is noted known as the *external occipital crest* which ends in an elevation called the *external occipital protuberance* (inion). From the region of the midpoint on this crest the *inferior nuchal line* curves laterally on each side but the line is often poorly defined and difficult to see. The *superior nuchal line* curves laterally on each side from the exter-




FIG 7 The external surface of the base of the skull (norma basalis)

tures of the nose) These are separated from each other by the vomer and are bounded laterally by the medial pterygoid plate

The *pterygoid plates* are a pair of large lateral and medial processes projecting downward from the roots of the greater wings of the sphenoid bones. Between these processes is an interval known as the *pterygoid fossa* which opens posteriorly and is about half an inch in width. The free border of the medial plate ends below in a hook called the *hamulus*. This gives attachment at its tip to the pterygomandibular ligament, and by its posterior border to the upper fibers of the superior constrictor muscle of the pharynx. The tensor palati tendon twists around its lateral and anterior aspects. The lateral plate gives origin to the lateral pterygoid muscle on its lateral surface and to the medial ptery-

goid on its medial surface. Lateral to the structures just described is the roof of the infratemporal fossa.

Posterolateral to the plates the *foramen ovale* is found which is quite large and transmits the mandibular nerve, the accessory meningeal artery and some small veins that connect the cavernous venous sinus with the pterygoid venous plexus. Some lymph vessels from the meninges also pass through this foramen as does the lesser superficial petrosal nerve at times. Posterolateral to the foramen ovale is the *foramen spinosum*, which transmits the middle meningeal vessels. The *zygomatic arch* is a prominent feature of this aspect. At its caudal end is found the articular fossa, which receives the articular process of the mandible. The *foramen lacerum* is a large and jagged aperture lo-

most convex part of each frontal bone and is situated about two fingerbreadths above the lateral end of the superciliary arch.

The *supra orbital foramen* or notch is located immediately above the upper border of the orbital opening at the junction of its

end of the eyebrows and may be a serviceable landmark since it marks a line that curves upward and backward from it and is known as the anterior part of the temporal line. In thin people this line can be both felt and seen.




FIG. 9 X-ray study of the front of the skull (postero-anterior projection) (1) parietal bone (2) coronal suture (3) frontal sinuses (4) crista galli (5) sphenoid bone and sinus (6) zygoma (7) lesser wing of sphenoid bone

medial with its lateral two thirds. It transmits the nerve and the vessels of the same name. The supra orbital margin ends laterally in a prominent projection called the zygomatic process of the frontal bone; it articulates with the zygomatic bone. The zygomatic process is easily felt at the lateral

Orbital Region. Each orbit is a deep cavity which resembles an irregular cone and may be likened to a pyramid having four walls, an apex and a base. The bones that form the orbital pyramid are the maxillary, zygomatic, sphenoid, frontal, palatine, ethmoid and lacrimal. The medial walls are




FIG 8 Front view of the skull (norma frontalis) It is made up of six regions frontal, orbital, nasal, zygomatic maxillary and mandibular

nal occipital protuberance and separates the scalp area above from the area for the neck muscles (nuchal area) below

NORMA FRONTALIS

(Figs 8 and 9) The front of the skull uneven in contour is made up of six regions (1) frontal (forehead) (2) orbital (3) nasal, (4) zygomatic, (5) maxillary (upper jaw) (6) mandibular (lower jaw)

Frontal Region The forehead or frontal region, is formed by the frontal bone. Superiorly it merges into the top of the skull and inferiorly it is limited by the orbits and the roof of the nose. The depression at the nasal root is called the *nasion*, it is found at the

point in the median plane where the two nasal bones articulate with the frontal bone and is opposite the anterior extremity of the brain

Directly above the orbital margins are two elevations the superciliary arches. These give prominence to the eyebrows and are more elevated in the male. The elevation that exists between the superciliary arches (between the eyebrows) is called the *glabella* so designated because the overlying skin is bald or glabrous.

Behind the superciliary arch and in the anterior part of the frontal bone a large air space is usually found. It is known as the *frontal sinus*. The *frontal eminence* is the

the floor of the foramen for the lacrimal sac laterally than the posterior part of the orbit to the middle cranial foramen which labels the temporal lobe of the brain and reaches directly to the anterior part of the temporal foramen.

Nasal Region. The bony part of the external nose is seen from the nostrils from below. The nasal cavity itself is divided obliquely (p. 90). The osseous part of the nose is formed by the two nasal bones in the bridge of the nose and on each side by the frontal process of the maxilla which lies behind the orbital rim. This part of the maxilla also forms the medial margin of the orbital opening. The nasal cavity is divided by a thin cartilaginous partition or *septum* into right and left halves. The principal part of the septum goes through the anterior bony aperture—the perpendicular plate of the ethmoid that forms the upper part; it is usually bent to one side or the other. The side walls of the nasal cavity are uneven because of three rough curled bony plates called *conchae* which project downward from each side wall. That portion of the cavity that lies below and lateral to each concha is called a *meatus* of the nose (superior, middle and inferior). The superior concha is too far back to be seen through the anterior aperture but the middle and the inferior conchae and meatuses are visible. (See p. 92.)

Zygomatic and Maxillary Regions. These form the cheek bones and the upper jaw regions respectively. The upper jaw region is situated between the orbits and the teeth. The *anterior nasal spine* is a sharp spur of bone which projects forward from the two maxillae at the lower margin of the anterior aperture of the nose. The maxilla ends inferiorly in the *alveolar border* which has slight ridges marking the roots of the anterior teeth, the most prominent of which are the canines. The canine tooth is the third counting from the middle in front (Fig. 8).

Near the lower margin of the orbit and almost immediately above the canine fossa is the *infra orbital foramen* which transmits

the infra orbital vessels and nerve and is located about one fingerbreadth lateral to the side of the nose. The *zygomaticofacial foramen* appears as a small opening on the zygomatic bone immediately below the lateral part of the lower margin of the orbit. It transmits the zygomaticofacial branch of the zygomatic nerve and a small branch of the lacrimal artery. The large single air space found inside the maxilla is called the maxillary sinus (antrum of Highmore); it communicates with the nasal cavity. This sinus is of considerable practical importance and will be discussed elsewhere (p. 95).

Mandibular Region. The mandible is the largest and strongest bone of the face and it contains the lower teeth. The bone develops in two symmetrical halves which fuse early and ossify during the first year. It consists of a horse hoe shaped body and a pair of flat broad rami that stand up from the posterior part of the body. Two processes project upward from the upper border of each ramus, an anterior called the *coronoid process* and a posterior designated as the *condylar process* which is divided into a head and a neck (Figs. 8 and 10).

The external surface of the body of the bone is marked in the median line by a faint ridge, the *symphysis menti* or line of junction of the two embryologic pieces of bone. The ridge divides below and encloses a triangular eminence known as the *mental protuberance*, the base of which is depressed in the center but raised on either side to form the mental tubercles. In the region of the protuberance the bone is bent forward to form the *chin*. The alveolar is the upper border so called because it is occupied by a row of pits or alveoli, sixteen in number which form the sockets for teeth. The lower border is the *base* of the mandible. It is smooth and rounded. The mental foramen which transmits the mental vessels and nerves is found about an inch from the symphysis and midway between the upper and lower borders.

The internal surface of the body of the

parallel and separated by the nasal cavity the lateral are at right angles to each other. The apex of the pyramid is marked by the *optic foramen*. Probes passed through these foramina meet at right angles near the dorsum sellae. The base of the pyramid is the opening on the face and the boundaries are the margins of the orbit.

The *roof*, or superior wall of the orbit is concave and is formed mainly by the orbital plate of the frontal bone and posteriorly by the lesser wing of the sphenoid. It separates the orbit from the sinus anteromedially and from the anterior cranial fossa elsewhere. The lacrimal gland occupies a fossa in the anterolateral part of the roof. At the medial angle the trochlea is attached. This is a small fibrocartilaginous ring through which the tendon of the superior oblique muscle passes. The point of attachment is usually marked by a small pit or spicule of bone called the trochlear fossa or spine.

The *floor* or inferior wall, is formed by the orbital plate of the maxilla. This plate also forms the roof of the subjacent maxillary sinus. A great part of the floor is separated from the lateral wall posteriorly by the *inferior orbital fissure*. The anterior end of this fissure is closed but the posterior meets the medial end of the superior orbital fissure at the apex of the orbit. The inferior fissure transmits the maxillary nerve (which becomes the infra orbital nerve), the infra orbital vessels, the zygomatic nerve, nervous twigs from the sphenopalatine ganglion to the lacrimal gland, the periosteum of the orbit, and a vein connecting the ophthalmic veins with the pterygoid venous plexus in the infratemporal fossa. The *infra orbital groove* leads forward on the floor for a short distance from the fissure and then tunnels through the floor to reach the infra orbital foramen, which transmits the nerve and the vessels of the same name.

The *lateral wall* is formed by the orbital process of the zygomatic bone and the orbital surface of the great wing of the sphenoid. Between the lateral wall and the roof, near the apex of the orbit, the *superior orbital*

fissure is found. Through this fissure the oculomotor, the trochlear, the ophthalmic division of the trigeminal and the abducens nerves enter the orbital cavity accompanied by orbital branches of the middle meningeal artery. Passing backward through this fissure are the ophthalmic veins and the recurrent branch of the lacrimal artery which reach the dura mater. The superior orbital fissure separates the lateral orbital wall from the roof and the inferior fissure separates this wall from the floor. Of the four walls the lateral is the thickest and the only one that is not in close contact with the paranasal sinuses. Resection of this wall gives safe access to the contents of the orbital cavity.

The *medial wall* is very frail and is formed from before backward by the frontal process of the maxilla, the lacrimal bone, the lamina papyracea of the ethmoid and a small part of the body of the sphenoid in front of the optic foramen. This wall contains the *lacrimal fossa* which lodges the lacrimal sac, the *anterior ethmoidal foramen* which transmits the nasociliary nerve and the anterior ethmoidal vessels, and the *posterior ethmoidal foramen* which accommodates the posterior ethmoidal nerve and vessels. The medial wall is in close contact with the sphenoid sinus posteriorly and the ethmoid sinuses anteriorly; these sinuses separating the orbit from the cavity of the nose. The *apex*, which is situated at the back of the orbit, corresponds to the *optic foramen*. This short cylindrical canal transmits the optic nerve and the ophthalmic artery. The ophthalmic vein passes through the superior orbital fissure, hence, it does not travel with its artery.

Injury or infection in the orbital cavity may travel in the following ways: superiorly to the frontal sinus or the anterior cranial fossa, which contains the frontal lobe of the brain; inferiorly to the maxillary sinus medially near the apex, to the sphenoid sinus farther forward to the ethmoid sinuses, which separate the orbit from the cavity of the nose and within the orbital margins to

the floor of the foramen for the lacrimal sac laterally through the posterior part of the orbit to the middle cranial foramen which enters the temporal lobe of the brain and more anteriorly to the anterior part of the temporal foramen.

Nasal Region. The lower part of the external nose is best seen from the front or frontally. The nasal cavity itself is discussed elsewhere (p. 92). The lower part of the nose is formed by the two nasal bones in the middle of the nose and covered by the frontal process of the maxilla which lies behind the nasal bone. This part of the maxilla also forms the medial margin of the orbital opening. The nasal cavity is divided by a thin vertical partition or *septum* into right and left halves. The principal part of the septum seen through the anterior bony aperture is the perpendicular plate of the ethmoid that forms the upper part; it is usually bent to one side or the other. The side walls of the nasal cavity are uneven because of three rough, curled bony plates called *conchae* which project downward from each side wall. That portion of the cavity that lies below and lateral to each concha is called a meatus of the nose (superior, middle and inferior). The superior concha is too far back to be seen through the anterior aperture but the middle and the inferior conchae and meatuses are visible. (See p. 92.)

Zygomatic and Maxillary Regions

These form the cheek bones and the upper jaw regions respectively. The upper jaw region is situated between the orbits and the teeth. The *anterior nasal spine* is a sharp spur of bone which projects forward from the two maxillae at the lower margin of the anterior aperture of the nose. The maxilla ends inferiorly in the *alveolar border* which has slight ridges marking the roots of the anterior teeth, the most prominent of which are the canines. The canine tooth is the third counting from the middle in front (Fig. 8).

Near the lower margin of the orbit and almost immediately above the canine fossa is the *infra orbital foramen* which transmits

the infra orbital vessels and nerve and is located about one fingerbreadth lateral to the side of the nose. The *zygomaticofacial foramen* appears as a small opening on the zygomatic bone immediately below the lateral part of the lower margin of the orbit. It transmits the zygomaticofacial branch of the zygomatic nerve and a small branch of the lacrimal artery. The large single air space found inside the maxilla is called the maxillary sinus (antrum of Highmore); it communicates with the nasal cavity. This sinus is of considerable practical importance and will be discussed elsewhere (p. 98).

Mandibular Region. The mandible is the largest and strongest bone of the face and it contains the lower teeth. The bone develops in two symmetrical halves which fuse early and ossify during the first year. It consists of a horse-hoe shaped body and a pair of flat, broad rami that stand up from the posterior part of the body. Two processes project upward from the upper border of each ramus: an anterior called the *coronoid process* and a posterior designated as the *condylar process* which is divided into a head and a neck (Figs. 9 and 10).

The external surface of the body of the bone is marked in the median line by a faint ridge, the *symphysis menti*, or line of junction of the two embryologic pieces of bone. The ridge divides below and encloses a triangular eminence known as the *mental protuberance*, the base of which is depressed in the center but raised on either side to form the mental tubercles. In the region of the protuberance the bone is bent forward to form the *chin*. The *alveolar* is the upper border, so called because it is occupied by a row of pits or alveoli, sixteen in number, which form the sockets for teeth. The lower border is the *base* of the mandible. It is smooth and rounded. The mental foramen which transmits the mental vessels and nerves is found about an inch from the symphysis and midway between the upper and lower borders.

The internal surface of the body of the




FIG. 10 Side view of the skull (norma lateralis). This part of the skull is formed by five bones: frontal, parietal, occipital, temporal, and the great wing of the sphenoid. The face is situated below and in front.

mandible is concave from side to side and contains the mylohyoid line which gives origin to the mylohyoid muscle. The angle of the mandible is that point at which the posterior border of the ramus joins the lower border of the body. It is subcutaneous and is easily felt two or three fingerbreadths below the lobule of the ear. The thin sharp coronoid process gives attachment along its edges and on its deep surface to the temporalis muscle; the more posteriorly situated condyloid process articulates with the articular fossa on the infratemporal surface of the squamous temporal. Articular cartilage covers its superior and anterior aspects but not the posterior. The lateral aspect of the condyloid process is covered by the parotid gland, which is situated immediately in front of the tragus. When a finger is placed

in front of the tragus and when the mouth is alternately opened and closed, the movements of the condyloid process can be felt. The notch, situated between the coronoid and the condyloid processes, is known as the mandibular notch; it transmits the nerve and the vessels to the masseter muscle.

About the center of the medial surface of the ramus of the mandible the mandibular foramen is situated. It leads into the mandibular canal which passes through the body of the mandible to the submental foramen. The submental foramen is situated below the chin. The submental foramen is situated below the chin. The submental foramen is situated below the chin.




FIG. 11 Side view of the skull with the zygomatic arch removed. The infra-orbital and pterygomaxillary fissures are shown.

NORMA LATRALIS

(Figs 10 11 12) Some anatomy text books prefer to discuss a superior and an inferior temporal line but these markings are so indistinct that the term *temporal line* is sufficient for surgical considerations. This line starts at the zygomatic process of the frontal bone, curves upward and backward and is easily felt on the living subject in its anterior and upper parts. Posteriorly it curves downward and forward into the *supramastoid crest*. It gives attachment to the epicranial aponeurosis, the temporal fascia and the uppermost fibers of the temporalis muscle. The *pterion* is that region where the frontal, the great wing of the sphenoid, the parietal and the temporal bones meet. A point on the pterion about 4 cm above the zygoma and 2.5 cm behind the frontal process of the zygomatic bone overlies the anterior division of the middle meningeal artery.

The *infratemporal crest* on the great wing of the sphenoid is a horizontal anteroposterior ridge which separates the temporal fossa above from the infratemporal fossa below. The temporal fossa is a wide space outlined by the temporal line and the zygomatic arch; it contains the temporalis muscle, its vessels and nerves and the zygomaticotemporal nerve. This is the thinnest and weakest region of the skull. Since the middle meningeal artery passes through here, many cases of fractures associated with injury to the vessel are common. The importance of and the approach to this region are discussed in a subsequent section (p. 28).

The *infratemporal fossa* is a wide space behind the maxilla below the infratemporal crest and lateral to the pterygoid plates. It communicates with the temporal fossa through the gap which exists between the zygoma and the rest of the skull. This gap is traversed by the temporalis muscle as it




FIG 10 Side view of the skull (norma lateralis) This part of the skull is formed by five bones frontal parietal occipital, temporal and the great wing of the sphenoid The face is situated below and in front

mandible is concave from side to side and contains the mylohyoid line which gives origin to the mylohyoid muscle The *angle* of the mandible is that point at which the posterior border of the ramus joins the lower border of the body It is subcutaneous and is easily felt two or three fingerbreadths below the lobule of the ear The thin sharp coronoid process gives attachment along its edges and on its deep surface to the temporalis muscle the more posteriorly situated condyloid process articulates with the articular fossa on the infratemporal surface of the squamous temporal Articular cartilage covers its superior and anterior aspects but not the posterior The lateral aspect of the condyloid process is covered by the parotid gland which is situated immediately in front of the tragus When a finger is placed

in front of the tragus and when the mouth is alternately opened and closed the movements of the condyloid process can be felt The notch situated between the coronoid and the condyloid processes, is known as the mandibular notch it transmits the nerve and the vessels to the masseter muscle

About the center of the *medial* surface of the ramus of the mandible the mandibular foramen is found It leads into a canal which passes downward and forward in the substance of the bone and carries the inferior alveolar vessels and nerve to the teeth A spur of bone known as the *lingula* usually overlaps this foramen The mylohyoid groove lodging the mylohyoid nerve and artery commences behind the lingula and runs for about one inch obliquely downward and forward on the ramus




FIG. 13 The upper surface of the base of the skull. The anterior fossa is on a higher plane than the middle fossa and the middle is higher than the posterior; in this way three terraces are formed.

ordinary pencil. It passes in a medial direction and slightly forward and opens into the middle ear in an oblique manner so that the tympanic membrane, which closes the opening, looks downward and forward as well as in a lateral direction. The outer orifice is also oblique, the upper margin overhanging the lower. The medial end of the meatus is closed during life by a tense vibrating membrane called the *tympanic membrane*, which separates the meatus from the tympanic cavity (middle ear).

Between the posterosuperior part of the meatus and the posterior root of the zygomatic arch the *suprameatal triangle* (MacEwen) is found. It lies immediately behind the upper part of the external meatus

and although small and often inconspicuous it is important because the tympanic antrum lies about half an inch medial to it. The antrum is a cavity in the temporal bone which is surgically important in diseases of the *mastoid process*. This process can be palpated under cover of the lobule of the auricle. It is absent at birth and does not begin to appear until the second year of life. A line drawn from one mastoid to the other passes immediately below the foramen magnum.

NORMA OCCIPITALIS

(Fig. 7) The back of the skull is horse shoe-shaped and extends from the tip of one mastoid process over the vault to the tip of

descends to its insertion. The fossa contains the pterygoid muscles, the internal maxillary artery and its middle meningeal branch, the mandibular nerve and its branches, the chorda tympani nerve and the pterygoid venous plexus.

temporal process of the zygomatic bone. The tendon of the temporalis passes medial to the arch to gain insertion into the coronoid process of the mandible. The upper border of the arch gives attachment to the temporal fascia, and the lower border and medial




FIG. 12 X-ray study of the skull (lateral projection) (1) frontal sinus (2) superior orbital plate (3) orbit (4) sphenoid sinus, (5) sella turcica (6) lambdoid suture (7) internal occipital tuberosity (8) coronal suture (9) middle meningeal channel (artery), (10) mastoid, (11) maxillary sinus (12) odontoid process of axis, (13) atlas.

Two fissures are present in the depth of the fossa: the *infra orbital fissure*, which lies horizontally and connects the infratemporal fossa with the orbit; and the *pterygomaxillary fissure*, which is placed vertically and transmits the terminal part of the maxillary artery. The pterygomaxillary fissure leads medially into the pterygopalatine fossa.

The *zygomatic arch* is quite evident and can be felt running from the prominence of the cheek to the tragus. It is formed by the zygomatic process of the temporal and the

surface give origin to the masseter muscle. The posterior root of the process is continued backward above the external auditory meatus as the *supramastoid crest*. Below the posterior root of the arch is an elliptical orifice known as the *external auditory meatus*, which is bounded in front, below and behind by the tympanic part of the temporal bone.

Lateral to this and not seen in the dried skull, the cartilaginous segment of the external auditory meatus is attached. The bony meatus is barely wide enough to admit an

then descend into the nose through the *nasal slit* which is found at the side of the front of the *crista galli*. Anterolateral to the median area the roof of the frontal sinus and the roof of the orbit are found.

Fractures of the anterior fossa may involve the cribriform plate and be accompanied by lacerations of the meninges and mucous membrane of the roof of the nose. Such an injury gives rise to epistaxis accompanied or followed by a discharge of cerebrospinal fluid. There may result some loss of smell due to laceration of the olfactory nerves as they pass upward from the nose and if dural injury is present it affords a route whereby infection can travel to the intracranial region from the nose. Meningitis or abscess in the frontal lobe may be a sequela of this type of fracture. If the cribriform plate does not heal after fracture and if a dural laceration remains unrepaired there may be a continuous discharge of cerebrospinal fluid from the nose known as cerebrospinal rhinorrhea. When the fracture involves the orbital plate of the frontal bone subconjunctival hemorrhage is a characteristic feature and the hemorrhage may seep within the orbit producing an exophthalmos. The frontal sinus may also be involved.

The *middle cranial fossa* is shaped like a butterfly having a small median and two lateral expanded concave parts. The median part is formed by the upper surface of the body of the sphenoid. The *sella turcica* is the saddle-shaped area that accommodates the pituitary gland. Anteriorly is the ridge known as the *tuberculum sellae* on either side of which is an *anterior clinoid process*. Immediately anterior to this process the *optic foramen* is situated at the end of the *optic groove*. The posterior part of the *sella turcica* is formed by the crest of the *dorsum sellae* ending laterally in the *posterior clinoid process* (Fig. 13).

The lateral part of the floor of the middle cranial fossa is formed by the greater wing of the sphenoid the upper aspect of the petrous part of the temporal and a portion of the squamous part of the temporal bone.

These lateral parts lodge the temporal lobes of the brain. The *superior orbital fissure* transmits to the orbital cavity the oculomotor the trochlear the ophthalmic division of the trigeminal and the abducens nerves some filaments from the cavernous plexus of the sympathetic system and the orbital branch of the middle meningeal artery. From the orbital cavity this fissure also transmits the ophthalmic veins and a recurrent branch of the lacrimal artery to the dura mater.

On either side of the sella is the *carotid groove* for the internal carotid artery. Three foramina run almost parallel with this groove. They are from anterior to posterior and from medial to lateral the *foramen rotundum* for the passage of the maxillary nerve the *foramen ovale* for the mandibular nerve the accessory meningeal artery and the lesser petrosal nerve and the *foramen spinosum* for the passage of the middle meningeal vessels and a recurrent branch of the mandibular nerve.

Medial to the *foramen ovale* is the *foramen lacerum* a short wide canal rather than a foramen its lower part being filled by a layer of fibrocartilage. Its upper and inner parts transmit the internal carotid artery which is surrounded by a plexus of sympathetic nerves. The petrous portion of the temporal bone forms a large and important part of the floor of the fossa. The highest part of this bone is known as the *arcuate eminence* and marks the position of the superior semicircular canal. Lateral to the eminence and immediately adjoining the squamous portion of the bone the *tegmen tympani* is found. This is a very thin plate of bone which roofs the tympanic antrum the tympanic cavity and the auditory tube. The important relationship of the thin *tegmen tympani* intervening between the inferior surface of the temporal lobe of the brain and the tympanic cavity cannot be over emphasized. This bone is the only barrier which exists between a diseased middle ear and the membranes of the brain or the brain itself.

The *hiatus* for the *greater superficial pe*

the other. The bones that take part in its formation are parts of the two parietals, the occipital and the mastoid portion of the temporal, with its mastoid process. Some parts have already been seen from the normal verticalis, namely, the parietal eminences, the posterior part of the sagittal suture, the parietal foramina, the lambda and the lambdoid suture.

The *occipitomastoid suture* descends between the occipital bone and the mastoid temporal. The *mastoid foramen* is seen on or near this suture and transmits an emissary vein which connects the veins on the outside of the skull with the sigmoid venous sinus.

The *external occipital protuberance* (inion) is usually well marked in the median plane at the lower part of the back of the skull. It can be felt in the living person immediately above the nape of the neck and acts as a useful guide.

The *superior nuchal line* is the curved ridge that arches laterally to either side of the protuberance. This protuberance together with the right and the left superior nuchal lines marks the division between the back of the head and the back of the neck.

The *lambda* is the point of junction between the sagittal and the lambdoid sutures; it marks the position of the posterior fontanelle in the fetal skull.

INTERIOR OF THE SKULL

SKULL CAP

The inner aspect of the skull has a top part or skull cap and a floor or base (Fig. 13). The *skull cap* is concave and presents depressions for the convolutions of the cerebrum and many furrows for the branches of the meningeal vessels. Along the midline is a longitudinal groove, narrow in front at the frontal crest where it begins but broader behind. This lodges the superior sagittal sinus, and its margins afford attachments for the falx cerebri. Bordering the sagittal groove, granular pits are seen which increase with age and occasionally are of sufficient

depth to pass through the diploe to the outer table. They lodge and are eroded by the arachnoid granulations. In addition there are numbers of minute nutrient foramina.

BASE OF THE SKULL AND THE CRANIAL FOSSAE

The *base* of the skull on its inner surface shows a natural subdivision into *three cranial fossae*, anterior, middle and posterior. Since the anterior fossa is on a higher plane than the middle, and the middle is higher than the posterior, there is a natural tendency toward the formation of three terraces.

The *anterior cranial fossa* is limited posteriorly by the posterior edges of the lesser wings of the sphenoid and in the median part by the anterior edge of the optic groove of the sphenoid. It lodges the frontal lobes of the brain and the olfactory bulbs and tracts. The floor of the fossa is depressed in its median part where it constitutes the roof of the nasal cavity. The median part is formed by the cribriform plate of the ethmoid bone through which the *crista galli*, or cock's comb, rises. It is an upward continuation of the nasal septum and gives attachment to the anterior end of the falx cerebri.

The *foramen caecum* is a small pit found directly in front of the crista. In early life the superior longitudinal sinus communicates with the veins of the nose through this foramen, but in the adult it is usually closed, hence its name—caecum (blind). The cribriform plate is perforated like a sieve by numerous olfactory nerves which are clothed in an arachnoid sheath and arise from the olfactory cells in the nasal mucosa.

At the side of the cribriform plate the *anterior* and the *posterior ethmoidal foramina* are found. They mark the medial ends of two short canals that lead from the orbital cavity and open at the side of the cribriform plate. They transmit the anterior and the posterior ethmoidal arteries and the anterior ethmoidal nerve. The anterior ethmoidal artery and nerve, after passing through the foramina, run on the cribriform plate and

then descend into the nose through the *nasal slit* which is found at the side of the front of the *crista galli*. Anterolateral to the median area the roof of the frontal sinus and the roof of the orbit are found.

Fractures of the anterior fossa may involve the cribriform plate and be accompanied by lacerations of the meninges and mucous membrane of the roof of the nose. Such an injury gives rise to epistaxis accompanied or followed by a discharge of cerebrospinal fluid. There may result some loss of smell due to laceration of the olfactory nerves as they pass upward from the nose and if dural injury is present it affords a route whereby infection can travel to the intracranial region from the nose. Meningitis or abscess in the frontal lobe may be a sequela of this type of fracture. If the cribriform plate does not heal after fracture and if a dural laceration remains unrepaired there may be a continuous discharge of cerebrospinal fluid from the nose known as cerebrospinal rhinorrhea. When the fracture involves the orbital plate of the frontal bone subconjunctival hemorrhage is a characteristic feature and the hemorrhage may seep within the orbit producing an exophthalmos. The frontal sinus may also be involved.

The *middle cranial fossa* is shaped like a butterfly having a small median and two lateral expanded concave parts. The median part is formed by the upper surface of the body of the sphenoid. The *sella turcica* is the saddle-shaped area that accommodates the pituitary gland. Anteriorly is the ridge known as the *tuberculum sellae* on either side of which is an *anterior clinoid process*. Immediately anterior to this process the *optic foramen* is situated at the end of the *optic groove*. The posterior part of the *sella turcica* is formed by the crest of the *dorsum sellae* ending laterally in the *posterior clinoid process* (Fig. 13).

The lateral part of the floor of the middle cranial fossa is formed by the greater wing of the sphenoid, the upper aspect of the petrous part of the temporal and a portion of the squamous part of the temporal bone.

These lateral parts lodge the temporal lobes of the brain. The *superior orbital fissure* transmits to the orbital cavity the oculomotor, the trochlear, the ophthalmic division of the trigeminal and the abducens nerves, some filaments from the cavernous plexus of the sympathetic system and the orbital branch of the middle meningeal artery. From the orbital cavity this fissure also transmits the ophthalmic veins and a recurrent branch of the lacrimal artery to the dura mater.

On either side of the sella is the *carotid groove* for the internal carotid artery. Three foramina run almost parallel with this groove. The first from anterior to posterior and from medial to lateral is the *foramen rotundum* for the passage of the maxillary nerve, the *foramen ovale* for the mandibular nerve, the accessory meningeal artery and the lesser petrosal nerve, and the *foramen spinosum* for the passage of the middle meningeal vessels and a recurrent branch of the mandibular nerve.

Medial to the *foramen ovale* is the *foramen lacerum*, a short wide canal rather than a foramen, its lower part being filled by a layer of fibrocartilage. Its upper and inner parts transmit the internal carotid artery which is surrounded by a plexus of sympathetic nerves. The petrous portion of the temporal bone forms a large and important part of the floor of the fossa. The highest part of this bone is known as the *arcuate eminence* and marks the position of the superior semicircular canal. Lateral to the eminence and immediately adjoining the squamous portion of the bone the *tegmen tympani* is found. This is a very thin plate of bone which roofs the tympanic antrum, the tympanic cavity and the auditory tube. The important relationship of the thin *tegmen tympani* intervening between the inferior surface of the temporal lobe of the brain and the tympanic cavity cannot be overemphasized. This bone is the only barrier which exists between a diseased middle ear and the membranes of the brain or the brain itself.

The *hiatus* for the *greater superficial petrosal*

trosal nerve is a small slit seen lower down on the anterior surface and about midway between the apex of the petrous temporal and the side of the skull. It communicates with the facial canal in the interior of the bone and transmits a slender nerve from which it takes its name. This nerve has its origin from the facial in the substance of the temporal bone and runs in a medial direction forward to the foramen lacerum. The *trigeminal impression* is found at the upper aspect of the apex of the petrous temporal and is represented by a slightly hollowed out area. In it is lodged the trigeminal ganglion which extends forward over the upper and the lateral parts of the foramen lacerum.

The middle fossa is the commonest site of fracture of the skull because of its position and because it is weakened by numerous foramina and canals. The tegmen tympani is frequently fractured and the tympanic membrane torn. Blood and cerebrospinal fluid are then discharged from the external auditory meatus and appear at the ear. The facial and the auditory nerves may be involved. At times the walls of the cavernous sinus are lacerated and cranial nerves three, four and six which lie in relation to its lateral wall may also be injured. Fractures involving the middle cranial fossa may also pass through the sphenoid bone or the base of the occipital bone and cause bleeding into the mouth.


The *posterior cranial fossa* is the largest and deepest of the cranial fossae and lodges the hind brain (cerebellum, pons and medulla oblongata). Its floor is formed by the basilar, the condylar and the squamous parts of the occipital bone, its lateral wall by the posterior surface of the petrous and the medial surface of the mastoid part of the temporal bone.

The *foramen magnum* is the most prominent feature of the fossa. At the anterolateral boundary of the foramen the *anterior condylar canal* is found which transmits the hypoglossal nerve. This nerve arises by several roots of origin and the canal is frequently divided into two parts by a small bar of bone. The foramen magnum transmits a number of structures, the most important being the medulla oblongata, the meninges, the vertebral arteries and the ascending parts of the accessory nerves. This foramen marks the lowest part of the posterior cranial fossa. The *clivus* is the broad, sloping surface that exists between the anterior margin of the foramen magnum and the root of the dorsum sellae; it is related to the pons and the medulla oblongata. The *internal auditory meatus* is found at the posterior aspect of the petrous temporal and runs laterally into the bone. Through it pass the motor and the sensory roots of the facial nerve, the auditory nerve, the internal auditory branch of the basilar artery and the auditory vein which joins the inferior petrosal sinus.

The *jugular foramen* is situated between the lateral part of the occipital and the petrous part of the temporal bone. It is a large aperture with irregular margins and transmits three sets of structures. At times small spicules of bone project from its margin and may partly or completely divide it into corresponding compartments. The anteromedial compartment transmits the inferior petrosal sinus and a meningeal branch of the ascending pharyngeal artery. The middle compartment transmits the glossopharyngeal, the vagus and accessory nerves. The posterolateral compartment is larger than the other two and transmits the sigmoid sinus as it becomes the internal jugular vein and a meningeal branch of the occipi-

FIG. 14 The two methods used to expose the brain, its coverings and vessels. Trephine operation: (A) skin flap formed, turned down and trephine in place; (B) removal of trephined "button" of bone; (C) incision into dura mater; (D) dural flap formed and reflected; (E) closure of dura. Osteoplastic craniotomy: (1) soft tissues incised, bone exposed and trephine openings made; craniotomy divides the bone; (2) bone is fractured at the base of the flap; (3) dura is divided and underlying structures exposed; (4) dural closure.

Trefline operation



Osteoplastic craniotomy

tal artery. The inferior petrosal sinus which passes through the anterior part of the foramen becomes the internal jugular vein immediately outside of the skull. The *transverse groove* begins at the side of the internal occipital protuberance and sweeps around the cranial vault to the lateral end of the upper margin of the petrous temporal. It then joins the *sigmoid groove* which curves downward and descends along the side wall of the skull and extends in a medial direction to end at the jugular foramen. The right transverse groove is wider than the left because it usually receives the sigmoid sinus.

The *mastoid foramen* is an aperture of variable size which leads from the exterior of the skull into the sigmoid groove on the side wall of the posterior cranial fossa. Through it a mastoid vein and the mastoid emissary vein and the mastoid branch of the occipital artery pass. The *aqueduct of the vestibule* (aqueductus vestibuli) is found about half an inch lateral to the internal auditory meatus.

Fractures of the posterior fossa are probably more important than such injuries in the other fossae since it is here that a small fissure fracture may prove fatal. The bone is thin in places and since there is no outlet for the escape of blood or cerebrospinal fluid as in the anterior and middle fossae these fractures may be overlooked. Some days after the injury blood may be noted over the mastoid process. Fractures of the base of the skull involving the hypoglossal canal may be manifested by paralysis of one side of the tongue.

SURGICAL CONSIDERATIONS

TREPHINING OPERATIONS

Two methods are usually employed to expose the brain: trephining and osteoplastic resection (Fig 14).

In trephining operations a circular disk of a cranial bone is removed by use of a trephine. The main indications for such operations are hemorrhage, abscess, fracture, evacuation of cerebrospinal fluid, or as a pre-

liminary step to further brain surgery. A U shaped or linear incision is made. If the former is used, its convexity is placed toward the crown of the head and the pedicle toward the base. The size of the flap is much larger than the bone which is to be removed. The incision passes through the skin, the superficial fascia, the muscle and the periosteum to the bone, and hemostasis is accomplished as the operation proceeds. With the trephine site cleared a piece of bone is removed and, if a larger opening is needed it may be obtained by removing pieces of bone from the circumference with a rongeur forceps. The dura is exposed and can be opened but any large dural vessels should be ligated first. The necessary operative procedure is carried out and the dural flap is sutured back into its normal position. The bone may or may not be replaced, and the wound is closed in layers.

OSTEOPLASTIC CRANIOTOMY

Osteoplastic craniotomy implies the raising of a portion of skull which may be replaced when the operation is completed. Lateral frontal, transfrontal, occipital and suboccipital osteoplastic flaps have been described, depending upon the area to be operated (Fig 14). The incision passes through all the soft tissues down to the bone. Vessels are clamped and ligated, and the periosteum is detached for a short distance along the line of the contemplated bone incision. Openings are made along the bone margins by means of a drill, a burr or a small trephine, and the bone that intervenes is divided by a saw or rongeur forceps. The base of the pedicle is steadied, usually with the left hand. The upper portion of the flap is grasped with a cranial claw forceps, and with a quick jerk the bone is fractured. The flap thus created is turned back and the dura is opened by means of a similar but smaller flap. The necessary operative procedure is carried out, the dura is closed by fine interrupted sutures and the bone flap with its attached soft parts is replaced and sutured into position.




FIG. 15 Subtemporal decompression (A) Line of incision and amount of bone to be removed the incision is placed about three-fifths of an inch in front of the tragus and extends upward and slightly backward for about four inches, (B) temporal muscle and fascia are incised, exposing temporal bone, (C) part of the temporal bone has been removed and the dural hook has been placed (D) dural opening enlarged on a grooved director, (E) and (F) are self explanatory.

3

Brain

EMBRYOLOGY

In the early embryo a primitive neural groove extending along the dorsal surface is converted into a tube by the elevation and the fusion of the neural folds. The cranial end of the neural tube forms the brain; it expands and constricts to form a series of three communicating sacs which are the primary brain vesicles known as the forebrain (prosencephalon), the midbrain (mesencephalon) and the hindbrain (rhombencephalon) the last being continuous with the spinal medulla. The cavity of the tube thus formed subsequently becomes the ventricular system and the central canal of the spinal cord and the walls of the tube become the nerve elements of the brain and the spinal cord. The forebrain becomes the cerebral hemispheres and the optic vesicles; the midbrain develops into the brain stem connecting the cerebrum with the pons and the cerebellum and the hindbrain forms the cerebellum, the pons and the medulla oblongata.

BRAIN PROPER

The average weight of the human brain in the adult male is approximately 1380 grams; of the female, approximately 1250 grams. Increasing rapidly during the first four years of life, the brain reaches its maximum weight about the twentieth year and decreases slowly as age progresses.

When inspected from above the only parts visible are the *cerebral hemispheres*. The *longitudinal fissure* separates the two hemispheres, except in its central part where the *corpus callosum* forms its floor. The fissure contains the *falk cerebri*, which projects into

it from the cranial vault. The surfaces of the cerebral hemispheres are interrupted by many sulci (fissures) that separate the various convolutions (gyri) from one another. The sulci are produced by infolding of the cerebral cortex, in this way increasing the amount of cortical substance without increase in the surface of the hemispheres. Various convolutions are associated with various functions and the different functional areas show structural differences in their cortex (Fig 17).

CEREBRAL HEMISPHERES AND LOBES

(Fig 18) These hemispheres occupy the anterior and the middle cranial fossae, and each is composed of five lobes: frontal, parietal, temporal, occipital and central (island of Reil, insula). The *falk cerebri*, which separates the cerebral hemispheres, is a fold of *dura mater* that projects downward from the vault of the skull. The hemispheres are separated from the cerebellum by another fold of *dura mater* called the *tentorium cerebelli* (Fig 23).

1 The *frontal lobe* on the lateral surface is bounded posteriorly by the *central sulcus* (fissure of Rolando). This sulcus is important because the convolution in front of it contains the higher centers for control of movements of the opposite side of the body. It is easily identified because it is the only sulcus of any length that lies between two parallel and almost vertical convolutions. Its upper end cuts the superomedial border of the hemisphere, and its lower end is separated from the posterior ramus of the lateral sulcus by a bridge of cortex.

Inferiorly the *lateral cerebral sulcus* (fis




FIG 17 Functional localizations of the cerebral cortex

sure of Sylvius) separates the frontal from the temporal lobe. It passes upward and backward and its posterior end bends upward into the parietal lobe.

On the superolateral surface of the frontal lobe the *precentral gyrus* is bounded by the central sulcus around the lower end of which it joins the *postcentral gyrus*. In front it is bounded by the *precentral sulcus* containing the higher centers that control the movements of the opposite side of the body. It should be noted that in the cortex the body is represented in the inverted position; hence the centers for the lower limbs occupy the uppermost part of the convolution. Below the lower limb come the trunk, the upper limb, the neck, and finally the head. Corresponding muscles of opposite sides of the body are connected with the cortex of both

cerebral hemispheres; an example of this is the movements of both eyes. Therefore it is understood that such movements are not affected by unilateral lesions of the internal capsule. Movements and not individual muscles are represented in the cortex. The *superior* and *inferior frontal sulci* run forward from the precentral sulcus and divide this area into *superior middle* and *inferior gyri*. The inferior frontal gyrus reveals the *anterior horizontal* and the ascending ramus of the *lateral sulcus*. The cortical area associated with these two limbs is known as Broca's area and is associated with the function of speech. This area consists of an orbital part below the horizontal ramus, a triangular part between the two ramus, and a posterior part behind the ascending ramus that is directly continuous with the cortex at the lower end

Brain

EMBRYOLOGY

In the early embryo a primitive neural groove extending along the dorsal surface is converted into a tube by the elevation and the fusion of the neural folds. The cranial end of the neural tube forms the brain; it expands and constricts to form a series of three communicating sacs which are the primary brain vesicles known as the forebrain (prosencephalon), the midbrain (mesencephalon) and the hindbrain (rhombencephalon), the last being continuous with the spinal medulla. The cavity of the tube thus formed subsequently becomes the ventricular system and the central canal of the spinal cord, and the walls of the tube become the nerve elements of the brain and the spinal cord. The forebrain becomes the cerebral hemispheres and the optic vesicles; the midbrain develops into the brain stem connecting the cerebrum with the pons and the cerebellum, and the hindbrain forms the cerebellum, the pons and the medulla oblongata.

BRAIN PROPER

The average weight of the human brain in the adult male is approximately 1380 grams; of the female, approximately 1250 grams. Increasing rapidly during the first four years of life, the brain reaches its maximum weight about the twentieth year and decreases slowly as age progresses.

When inspected from above, the only parts visible are the *cerebral hemispheres*. The *longitudinal fissure* separates the two hemispheres, except in its central part where the *corpus callosum* forms its floor. The fissure contains the *fala cerebri*, which projects into

it from the cranial vault. The surfaces of the cerebral hemispheres are interrupted by many sulci (fissures) that separate the various convolutions (gyri) from one another. The sulci are produced by infolding of the cerebral cortex in this way increasing the amount of cortical substance without increase in the surface of the hemispheres. Various convolutions are associated with various functions, and the different functional areas show structural differences in their cortex (Fig. 17).

CEREBRAL HEMISPHERES AND LOBES

(Fig. 18.) These hemispheres occupy the anterior and the middle cranial fossae and each is composed of five lobes: frontal, parietal, temporal, occipital and central (island of Reil, insula). The *fala cerebri*, which separates the cerebral hemispheres, is a fold of dura mater that projects downward from the vault of the skull. The hemispheres are separated from the cerebellum by another fold of dura mater called the *tentorium cerebelli* (Fig. 23).

1. The *frontal lobe* on the lateral surface is bounded posteriorly by the *central sulcus* (fissure of Rolando). This sulcus is important because the convolution in front of it contains the higher centers for control of movements of the opposite side of the body. It is easily identified because it is the only sulcus of any length that lies between two parallel and almost vertical convolutions. Its upper end cuts the superomedial border of the hemisphere, and its lower end is separated from the posterior ramus of the lateral sulcus by a bridge of cortex.

Inferiorly the *lateral cerebral sulcus* (fis-




FIG. 19 Medial aspect of the brain sectioned in the sagittal plane

sonian type of motor convulsions. Optic radiations pass through a portion of the parietal lobe on their way to the visual center; hence a deeply placed tumor may produce a contralateral homonymous visual field defect (half blindness of the corresponding sides of both retinæ).

3 The *temporal lobe* is bounded above by the posterior horizontal limb of the lateral cerebral sulcus. Where this fissure turns up the line of the posterior limb must be continued backward until it cuts the arbitrary line marking off the front of the occipital lobe. Posteriorly this line separates the temporal from the occipital lobe. The temporal lobe has *three gyri* (superior, middle and inferior) which are separated from each other by *two sulci* (superior and inferior temporal sulci). The *superior temporal sulcus* runs parallel to the posterior ramus of the lateral sulcus and its posterior end turns upward and into the parietal lobe where it is surrounded by the angular gyrus (inferior parietal lobule). The *superior temporal gyrus*

lying immediately above the same named sulcus contains the higher auditory centers. Since the temporal lobes occupy the middle fossa of the skull they are susceptible to injury in basal fractures. Lesions involving the superior temporal gyrus may also be associated with an inability to understand the spoken word (word deafness). The *middle temporal gyrus* lies below the superior temporal sulcus and is bounded inferiorly by the *middle temporal sulcus* which is usually interrupted.

4 The *occipital lobe* is arbitrarily marked off by drawing a line downward and a little forward from the parieto-occipital fissure to the inferolateral border of the hemisphere. The surface of the lobe is quite variable. The *transverse* and *lateral occipital sulci* divide this lobe into the *superior*, the *middle* and the *inferior gyri*. The superior occipital gyrus is connected anteriorly to the superior parietal lobule by the parieto-occipital arc. The middle occipital gyrus is continuous above with the inferior parietal lobule and




FIG 18 Lateral surface of the right cerebral hemisphere viewed from the side

of the precentral gyrus. In right handed people the left side of this region is better developed.

2 The *parietal lobe* is limited in front by the central sulcus, behind by the artificial boundary of the occipital lobe and the lateral parieto-occipital sulcus, above by the superomedial border and below by the posterior horizontal limb of the lateral cerebral fissure and its backward prolongation. These boundaries are somewhat artificial and not entirely definite.

The *postcentral sulcus* lies parallel to and a little behind the central sulcus; the *postcentral gyrus*, containing the sensory projection centers, is placed between them. A tumor involving this area produces diminution in various sensations and the patient loses his ability to localize a painful stimulus or to be certain of its intensity. He may have difficulty determining the weight, the size and the texture of various objects and materials.

From the postcentral sulcus the *intraparietal sulcus* passes directly backward and in this way demarcates a *superior parietal lobule* from an *inferior*. Lesions of the inferior parietal lobule produce the interesting

sign of *astereognosis* (inability to correlate and interpret various sensory impressions). This lobule is divided from below by three upturned ends—the posterior ramus of the lateral sulcus and the superior and middle temporal sulci. As a result of this the ends of these sulci are capped by arched gyri which are called the anterior, the middle and the posterior parts of the inferior parietal lobule (supramarginal, angular and postparietal gyri). The postparietal gyrus is not always as evident as the other two. Word blindness—the inability to understand written words—is a characteristic finding associated with a lesion of the angular gyrus of the left side in right handed individuals. Lesions of the upper parietal lobe are associated with inability to recognize the form or nature of objects. Some authorities prefer not to include the postcentral gyrus in the parietal lobe. With lesions of this gyrus the patient loses his ability to localize a painful stimulus or to measure its intensity. If this area is irritated there may be numbness, needle and pin sensation or “shocks of electricity” in his extremities. At times such sensory attacks are initiating symptoms of the Jack




FIG 20 Inferior surface of the brain

lateral wall of the third ventricle. The thalamus is joined to its counterpart by the interthalamic connexus (middle commissure) which is really not a commissure since it is formed by gray matter.

The *posterior commissure* is a layer of white fibers that connects the two thalami posteriorly. It forms the posterior boundary of the third ventricle and is placed just above the upper opening of the aqueduct of the midbrain (Sylvius). The *pineal body* is situated directly above and posterior to the posterior commissure.

The *sulcus cinguli* begins below the rostrum and follows the curvature of the corpus callosum and is separated from it by the

gyrus cinguli. The sulcus turns upward in the region of the splenium and cuts the superomedial border of the hemisphere just behind the upper end of the central sulcus. The *medial gyrus* lies immediately in front of this upper end of the central sulcus, forming the medial surface of the frontal lobe and containing the higher motor centers that control the movements of the lower limb of the opposite side of the body. This latter portion of the gyrus is referred to as the *para central lobule* behind which is found the *precuneus*. The lobule is bounded posteriorly by the parieto-occipital sulcus; it forms the medial surface of the parietal lobe and is separated from the occipital lobe by

in front with the middle temporal gyrus. The inferior occipital gyrus is connected in front with the inferior temporal gyrus.

Investigators believe that the chief function of the occipital lobe is concerned with vision. A destructive lesion in this region produces a contralateral homonymous hemianopsia. Certain visual hallucinations may result from irritation of the occipital lobe and are usually described by patients as colors of the rainbow, bright lines, flashes of light or brilliant lightning patterns.

5 The *central lobe* can be seen only when the edges of the lateral cerebral fissures are pulled apart. Even this maneuver does not completely expose the lobe, since certain parts that will be described later (p. 38) must also be removed. The lobe is surrounded by the *circular sulcus* and is overlapped by parts of cortex which are called *opercula*, of which there are four: temporal, orbital, frontal (pars triangularis) and frontoparietal.

Medial Surface of the Cerebral Hemisphere (Fig. 19) If the two cerebral hemispheres are divided by a main vertical incision, the great (white) commissure known as the *corpus callosum* stands out as a striking landmark. This is about four inches long and extends to within one and a half inches of the anterior and two and a half inches of the posterior extremities of the hemisphere. The anterior part of the corpus callosum known as the *genu* bends upon itself and ends below in a point called the *rostrum*. The hind part of the corpus is called the *splenium*, and the intermediate part forms the *body* (truncus). The fibers that run through it are principally transverse ones and are mainly association fiber tracts that connect the two cerebral hemispheres. Tumors involving the corpus callosum usually produce the same symptoms as those in the frontal lobe because of their close anatomic position.


The rostrum is connected to the upper part of the optic chiasma by a narrow sheet of gray matter called the *lamina terminalis*. The genu contains fibers running forward

and medially into the frontal lobe, thus forming the *forceps minor*.

The body of the corpus lies at the bottom of the longitudinal fissure in the median plane and to each side of this forms the roof of the lateral ventricles. The splenium covers the dorsal aspect of the midbrain and the great cerebral vein separates the splenium above from the pineal body below. The fibers of the splenium arch backward and medially into the occipital lobe on either side, forming the *forceps major*. The intermediate fibers that exist between the forceps major and minor are known as the *tapetum*. Below the middle third of the corpus callosum the body of the *fornix* is found. As this structure passes forward, its anterior pillar arches downward until it is lost in the lower part of the brain, terminating in the mammillary body of its own side. The fornix forms the efferent tract from the hippocampus of one hemisphere to that of the other and to the brain. A thin membrane, *septum lucidum* (septum pellucidum), stretches from the anterior convexity of the fornix to the concavity of the corpus callosum. It consists of two layers with a slitlike cavity between them; it is not lined by ependyma, and forms a partition between the anterior horns of the lateral ventricles.

Behind the fornix and at the most anterior part of its arch, the *interentricular foramen* (foramen of Monro) is found. This appears as an open aperture bounded by the fornix in front and the optic thalamus behind and provides a communication between the lateral and the third ventricles. This is brought about by a V-shaped arrangement in which the two limbs anteriorly communicate with the lateral ventricles on either side, and the junction of the two open into the third ventricle via the foramen of Monro (Fig. 24).

The *anterior commissure*, located a little below the foramen and in front of the fornix, appears as a small rounded bundle of fibers, the posterior aspect of which can be seen in the anterior wall of the third ventricle. The concavity of the fornix arches around the front of the *optic thalamus* and forms the



Falx cerebri

FIG. 21 Diagrammatic frontal section through the scalp, the skull, the meninges and the brain. The arachnoid villi invade the dura, and the subarachnoid space is trabeculated. The four intracranial spaces should be noted.




FIG. 22 The four membranes formed by the infolding of the dura mater (falx cerebri, falx cerebelli, tentorium cerebelli and diaphragma sellae). The venous sinuses and the cranial nerves are also shown.

the parieto occipital sulcus. The gyrus is separated from the parietal lobe by the interrupted suprasplenic (subparietal) sulcus.

The *calcarine sulcus* passes forward from the occipital lobe and just above the inferior medial border of the hemisphere. It joins the parieto occipital sulcus so that these two sulci enclose a triangular area of cortex known as the *cuneus* which forms the medial surface of the occipital lobe. From the point of union of the two sulci the calcarine sulcus runs forward into the gyrus cinguli, the narrow part of which is termed the *isthmus*. The *lingual gyrus* lies below the calcarine sulcus as far back as the occipital lobe.

INFERIOR SURFACE OF BRAIN, CEREBELLUM AND MEDULLA OBLONGATA

(Fig. 20) The inferior surface of the brain consists of two parts: the anterior (orbital) and the posterior (tentorial). The *anterior surface* of the frontal lobe rests upon the floor of the anterior cranial fossa, thereby coming into relationship with the orbit, the frontal sinus and the nasal cavity. It is bounded behind by the stem of the lateral sulcus. The *orbital gyrus* and *sulcus* occupy this area. Very little is known about the functions of this portion of the brain.

The *posterior surface* lies on the floor of the middle cranial fossa and in the tentorium cerebelli, thus coming into relationship with the tympanic antrum. Its medial part is formed by the *hippocampal gyrus* which is continuous posteriorly with the gyrus cinguli at the *isthmus*. The anterior extremity of this gyrus forms a projection called the *uncus* which receives incoming olfactory fibers and is associated with olfactory impressions. The *rhinal sulcus* separates the uncus from the temporal lobe.

The *hippocampal gyrus* is bounded laterally by the *collateral sulcus*. The *lingual gyrus* begins near the occipital pole, lying posterior to the hippocampal gyrus and medial to the collateral sulcus.

The *medial occipitotemporal (fusiform)*

gyrus, lateral to the lingual and hippocampal gyri, is bounded laterally by the occipitotemporal sulcus. Lateral to this sulcus the *lateral occipitotemporal (inferior temporal) gyrus* is found.

The *olfactory bulb* continues backward as the *olfactory tract*, which passes along the medial border of each orbital area and parallel to the great longitudinal sulcus. Inferiorly the olfactory bulb rests upon the cribriform plate of the ethmoid through which the olfactory nerves from the nasal mucous membrane pass. The olfactory tract divides into *medial and lateral olfactory roots*. Directly posterior to these roots is found the *anterior perforated substance* which transmits numerous arteries and veins to and from the interior of the brain.

The *optic chiasma* results from the crossing of the optic nerves and lies posteromedial to the anterior perforated space. The *optic tracts* continue backward from the chiasma and disappear under cover of the uncus. If the *optic commissure* is gently retracted backward a very delicate layer, *lamina terminalis*, is seen. This may be torn easily and if injured the cavity of the third ventricle is exposed. Immediately behind the optic chiasma the *tuber cinereum* is located. While poorly developed in the human, it is particularly well developed in certain types of fish whose sense of taste dominates the sense of smell. The *infundibulum* (stalk of the hypophysis) is at its summit. Behind the tuber cinereum the two small white *mammillary bodies* are seen whose nuclei form important olfactory centers.

The *posterior perforated substance* is situated immediately behind the mammillary bodies and is perforated by branches of the posterior cerebral arteries which supply the thalamus. The *cerebral peduncles*, two large bundles of white substance lying close together at the superior margin of the pons, gradually diverge as they travel upward to form the *interpeduncular fossa* disappearing beneath the optic tracts. These two great bundles associate the cerebral hemispheres with all the structures below them.

per and lower halves, the upper forming the lower part of the floor of the fourth ventricle while the lower is directly continuous with the posterior part of the spinal cord. The medulla, approximately one and a quarter inches long, is pyramidal in shape, having its apex at the spinal cord and its base at the pons. It presents anterior and posterior median fissures that are continuous with those of the cord.

MEINGES

(Figs. 21-23) The brain and the spinal cord are surrounded by three enveloping membranes which are known from inside out as the pia mater, the arachnoid mater, and the dura mater. Their names suggest their qualities: the dura is tough and firm; the arachnoid resembles a spider's web; and the pia represents a very thin, clinging skin-like structure that hugs the surface of the brain and follows its irregularities. The dura and the arachnoid do not dip into the fissures but fit the brain as a child's mitten fits its hand; on the other hand, the pia mater dips into each fissure and fits the brain very much as a glove fits the hand, since each finger has its own indentation (see venous sinuses of the dura mater, p. 53).

The *dura mater* (Figs. 22, 23) is the most external membrane of the brain; it consists of two layers that are firmly blended with each other except in certain locations. The more superficial of these layers is the endocranium, which is a periosteum (endoperiosteum). Through the openings in the skull it is continuous with the external periosteum (pericranium). The endoperiosteum is the layer that is intimately related to the bones of the skull and in no way takes part in the formation of the falx cerebri or the tentorium cerebelli. Bulging arachnoid granulations (enlarged villi of the arachnoid projecting through the layers of dura mater) project from each side of the median sagittal plane and produce the pits found on the parietal bone. The middle meningeal vessel ascends in the dura and produces a groove in the parietal bone. The deeper or inner layer of

dura is smooth and lined by endothelial cells. It resembles a serous membrane and is separated from the superficial layers by a small amount of fibrous tissue. The venous sinuses and the meningeal vessels separate the two layers of dura. By a process of infolding and reduplicating itself, the inner layer of dura forms four membranes that subdivide the cranial cavities. These membranes are the falx cerebri, the falx cerebelli, the tentorium cerebelli, and the diaphragma sellae.

The sickle-shaped *falx cerebri* is placed vertically between the two hemispheres of the cerebrum and since it is a reduplication of the inner layer of the dura, it consists of two layers of serous dura. Its upper border is convex and attached to the crista galli in front; it extends back to the internal occipital protuberance and between these two points is attached to the internal surface of the skull. Its lower border is attached to the tentorium cerebelli behind, but otherwise remains free to project between the cerebral hemispheres in front of the tentorium. The falx is narrow in front and becomes wider as it is traced backward. The superior sagittal sinus appears in its upper border; its lower border contains the inferior sagittal sinus and aids the tentorium in the support of the straight sinus.

The *falx cerebelli* passes vertically from the tentorium to the foramen magnum and separates the two cerebellar hemispheres. It attaches posteriorly to the internal occipital crest where it encloses the occipital sinus. Construction of the falx cerebelli is exactly the same as that of the falx cerebri.

The *tentorium cerebelli* is a tentlike fold of a double layer of serous dura mater forming a partition between the cerebellum and the posterior part of the cerebral hemispheres. It forms a roof for the cerebellum and a floor for the occipital lobe and the posterior part of the temporal lobe of the cerebrum. Anteriorly a wide gap known as the tentorial notch permits the passage of the midbrain. Because of this arrangement the tentorium possesses a free inner and an attached outer border. This outer border has

The structures about to be described can best be seen if the temporal lobe is retracted, and as this is done the optic tract can be followed backward around the lateral side of the peduncle where it broadens and divides into lateral and medial roots. The lateral root ends in the *lateral geniculate body* and the *superior corpus quadrigemum*, which it reaches through the superior brachium. These nuclei constitute the lower visual centers (Fig. 38). The medial root ends in the *medial geniculate body* and has no connection with vision. Behind and above the geniculate bodies is the overhanging hind end of the optic thalamus known as the *pulvinar*. This is associated with the lower visual centers.

The *corpora quadrigemina* are four round bodies that are found on the dorsal aspect of the midbrain immediately below and medial to the pulvinar. The superior corpora quadrigemina (colliculus superior) are larger than the inferior and have the pineal body situated just above them in such a way that the colliculus superior of one side is separated from that of the other. Each of the four corpora has a brachium or ridge running lateral from it.

The lateral geniculate body, the superior corpora quadrigemina and the pulvinar are known collectively as the *lower visual centers*. The lateral geniculate body is the most important component of this group, since it is a relay station on the visual pathway from the retina to the visual cortex. The inferior quadrigeminal bodies are associated with auditory pathways. A medial groove separates the ventral part of the peduncle forming the *basis* or *crusta pedunculi*. The dorsal part of the peduncle is known as the *tegmentum* and contains important afferent pathways and the *red nucleus*. The tegmentum and the base of the peduncle are separated on each side by a band of deeply pigmented gray matter that is known as the *substantia nigra*. The *aqueduct of Sylvius* appears in the midline nearer the dorsal side and the *splenium* (hind end of the corpus callosum) is situated more posteriorly.

The interpeduncular fossa occupies a central position and is bounded in front by the optic chiasm, anterolaterally by the optic tract and posterolaterally by the cerebral peduncles. The contents of this fossa from before backward are the tuber cinereum with its infundibulum, the corpora mammillaria and the posterior perforated space. All these structures take part in the formation of the floor of the third ventricle.

The *cerebral peduncles* attach the cerebrum to the pons, the *cerebellar peduncles* attach the cerebellum to the pons and the medulla (Fig. 19). The *pons varolii* is placed above the medulla, below the cerebral peduncles and between the lateral halves of the cerebellum. It is about one and a half inches long and two inches wide; its ventral surface reveals a midline groove (basilar sulcus) for the basilar artery. The pons also presents transverse markings and openings for the entrance of vessels and forms part of the floor of the fourth ventricle. Its dorsal surface is smaller than its anterior and is continuous with the posterior surface of the medulla.

The *cerebellum* (Fig. 19) occupies the posterior cranial fossa. It is separated from the cerebral hemispheres above by the tentorium cerebelli and in front is related to the pons and the medulla oblongata, from which it is separated by the fourth ventricle. It is closely related to the sigmoid sinus and the tympanic antrum on each side. The cerebellum consists of a median strip called the *vermis* and two hemispheres. It resembles the cerebrum in structure in that gray matter forms a layer of cortex placed on the surface and not centrally, as in the spinal cord and the brain stem.

The *medulla oblongata* extends from the foramen magnum to the lower border of the pons. It connects the spinal cord below to the pons above. Anteriorly it rests upon the basilar part of the occipital bone and posteriorly lies in a depression between the hemispheres of the cerebellum which is called the *vallecula cerebelli*. The posterior aspect of the medulla is conveniently divided into up

brain this network is much reduced and the two membranes are widely separated to form the so-called *subarachnoid cisternae*. The three main cisternae are

(1) The *cisterna cerebromedullaris* (cisterna magna) is a cavity resulting from the arachnoid bridging the inferior surface of the cerebellum and the dorsal surface of the medulla oblongata. It is continuous below with the spinal subarachnoid space. Cerebrospinal fluid passes directly into this cistern from the fourth ventricle by means of the foramen of Magendie (median aperture).

(2) The *cisterna pontis*, a space lying in front of the pons and the medulla oblongata, is continuous with the subarachnoid space about the medulla and has been referred to as Hilton's water bed, since it forms a water cushion to protect the brain. The roots of the lower eight cranial nerves traverse this cavity.

(3) The *cisterna interpeduncularis*, a wide cavity formed by the arachnoid as it extends across and between the two temporal lobes, encloses the cerebral peduncles and contains the arterial circle of Willis. Some consider it part of the *cisterna basalis*, which connects it to a smaller cisterna in front of the optic chiasma. The arachnoid granulations are best seen in old age, where they produce pitting of the parietal bone. When hypertrophied they are called *pachymenian bodies*. Although they appear to originate in the dura, they are really villous processes of the arachnoid that push the dura mater ahead of them. They serve as channels for the passage of cerebrospinal fluid into the venous system and at times may become large enough to produce pressure signs.

The *pia mater* is the innermost of the three meninges and is in reality the membrane of nutrition. It is closely attached to the surface of the brain and dips into the depths of all the sulci, carrying branches of the cerebral arteries with it. The larger blood vessels of the brain lie in the subarachnoid space, but the smaller ones ramify the *pia* and proceed into the substance of the brain proper.

At certain locations the *pia mater* sends strong vascular duplications into the brain; these spread over the cavities of the third and the fourth ventricles and are known as the choroid tela. The choroid tela of the third ventricle extends into each lateral ventricle. The blood vessels on the border projecting into the lateral ventricle are enlarged into a plexus known as the choroid plexus of the lateral ventricle, from which the greater amount of cerebrospinal fluid is formed.

INTRACRANIAL SPACES

(Fig. 21.) The four intracranial spaces are the extradural (exterior to the dura), subdural (beneath the dura), subarachnoid (beneath the arachnoid), the intracerebral (within the brain tissue proper).

1 The *extradural space* is only a potential one because the dura touches the internal surface of the skull. The meningeal vessels (p. 28) are in this space and if they are injured, bleeding takes place between the dura and the skull. If this bleeding is permitted to continue, the dura is slowly stripped away from the bone. Bleeding into this space is usually *arterial* and therefore rapid and often fatal. If the arachnoid is intact and the subarachnoid space has not been entered, there is no blood in the cerebrospinal fluid.

2 The *subdural space* is situated between the dura and the arachnoid. Hemorrhage into this space may result from injury to large arteries such as the middle cerebral or internal carotid, but this is rare, rapidly fatal and of no practical importance. It is much more important to consider subdural hemorrhage as *venous*, since the large sinuses such as the superior longitudinal and lateral, may be torn when the dura is injured. If the arachnoid is also torn, as it may be over the great cisterns at the base of the brain, blood escapes into the subarachnoid space and will appear in the cerebrospinal fluid.

3 The *trabeculated subarachnoid space* is situated between the arachnoid and the *pia mater*. Cerebrospinal fluid circulates here. The space is not wide over the con-




FIG 23 Coronal section through the foramen magnum showing the relationships of the meninges, the venous sinuses and the blood vessels

three attachments to the margins of the groove of the transverse sinus of the occipital bone, to the margins of the groove for the superior petrosal sinus on the petrous portion of the temporal bone to the posterior clinoid process of the sphenoid bone. The free border runs forward to the anterior clinoid process, and the upper layer of the tentorium becomes continuous with the falx cerebri in the median plane.

The *diaphragma sellae* is also a fold of inner layer of dura mater with a foramen in its center. Its lateral border is attached to the clinoid processes; its medial border forms the boundary of the foramen of the diaphragma sellae and also surrounds the infundibulum. The superior surface of the dia-

phragm is in relation to the base of the brain; its inferior aspect is related to the hypophysis which is bound by it to the hypophyseal fossa.

The *arachnoid mater*, a delicate membrane enveloping the brain and medulla spinalis, lies between the pia mater internally, and the dura mater externally. It does not dip into the various sulci on the surface of the brain, but is carried into the longitudinal fissure by the falx cerebri. Over the convolutions the arachnoid and the pia are in close contact but are separated at the sulci by the subarachnoid space which contains the cerebrospinal fluid and is crossed by a gauzy retinaculum of cobweb-like fibers connecting the two membranes (Fig 21). At the base of the



FIG. 25. Photograph and roentgenogram of a hydrocephalic infant. A spina bifida is also present.

respective lateral ventricle. It is situated in the anterior horn and is the only means of exit for the lateral ventricles. The third ventricle empties into the fourth by means of the aqueduct of Sylvius, which is about half an inch long and quite narrow, being only slightly larger than the lead of a pencil. This aqueduct, passing through the mid-brain, enters the anterior part of the fourth ventricle; it is the only source of exit for the third and both lateral ventricles. Because of its location and its small size, it is the weakest and most important point of the entire ventricular system. The fourth ventricle is situated in the posterior cranial fossa, the

cerebellum forming its roof and the pons and the medulla its floor. It connects with the subarachnoid space by three openings: the two lateral foramina of Luschka and a median foramen of Magendie. The two lateral foramina of Luschka open into the cisterna lateralis, and the foramen of Magendie into the cisterna magna (cisterna cerebellomedullaris). In this way, the ventricular system becomes connected with the subarachnoid space. The fluid, having gained entrance into this space and the cisternae, circulates freely around the cerebrum and the cerebellum, finally passing down the spinal subarachnoid space. Cerebrospinal fluid is




FIG 24 The ventricular system The horns and body of the first and the second lateral ventricles are pictured in relation to the brain

vexity of the brain but is quite extensive at the base of the skull where the cisternae are formed. These form a water bed of subarachnoid fluid upon which the brain floats. Only the anterior third of the brain rests directly upon bone (the orbital plates of the frontal bone).

4 Involvement of the *intracerebral space* is really involvement of brain substance proper. Theoretically the subpial space is that potential interval that exists between the pia and the brain and is of no practical importance. Attempts to strip the pia mater from the brain are often unsuccessful, since brain tissue comes away with the intimately attached pia. Bleeding into the brain proper may be traumatic in origin or may be the result of spontaneous rupture of an artery in its interior. Since the pia is frequently torn with these hemorrhages, frank blood appears in the cerebrospinal fluid.

VENTRICULAR SYSTEM AND CEREBROSPINAL FLUID

The circulation of the cerebrospinal fluid is associated with (1) the ventricular system and (2) the subarachnoid space. The spinal fluid is formed in the ventricular system and absorbed in the subarachnoid space.

The *ventricular system* (Fig 24) is composed of four ventricles, two of which are lateral. Normally these spaces communicate freely with each other through well-defined openings. Each lateral ventricle is situated within a cerebral hemisphere and is subdivided into an anterior horn (in the frontal lobe), a body (in the parietal lobe), a posterior horn (in the occipital lobe), and a descending horn (in the temporal lobe). Each communicates with the third ventricle by a single opening known as the foramen of Monro. This foramen has a V-shaped arrangement of two limbs, each draining its



FIG. 27 A Encephalogram in lateral projection (1) anterior horn (2) body of the lateral ventricle (3) posterior horn (4) third ventricle (5) descending horn (6) fourth ventricle, (7) sella turcica




FIG. 27 B Encephalogram in anteroposterior projection (1) anterior horn (2) body of the lateral ventricle (4) third ventricle (8) orbit (9) nasal septum, (10) inferior turbinates

formed by the choroid plexus mainly in the lateral ventricles from this point it passes through the foramen of Monro into the third ventricle and finally into the subarachnoid

in the fourth ventricle (Magendie and Luschka), distention of all ventricles will ensue. The type of block may be determined by ventriculography.




FIG 26 Ventriculography. Two small incisions are made an inch to each side of the midline and two inches above the lambdoid suture. Two burr holes are placed at these points, and the dura is nicked. A ventricular needle then is introduced into the lateral ventricle at the junction of the body and the occipital horn. Cerebrospinal fluid is replaced with air.

space where it comes in contact with the arachnoid villi which absorb it and return it to the venous stream in the dural sinuses.

The total amount of cerebrospinal fluid has been estimated to be between 90 and 150 cc in adults. If there is a block along the route of the ventricular system the condition of hydrocephalus results (Fig 25). If such a block is located at a lateral ventricle entrance into the third ventricle distention of one ventricle would result, if the block is at the aqueduct of Sylvius, a distention of both lateral and the third ventricles would result if the obstruction is at the openings

SURGICAL CONSIDERATIONS

Two procedures, ventriculography and encephalography, are valuable diagnostic aids especially in the localization of brain tumors and obstruction of the ventricular system (Figs 26 and 27).

ENCEPHALOGRAPHY

Encephalography consists of withdrawing cerebrospinal fluid by means of a lumbar puncture needle and introducing air. The air slowly ascends and produces an outline of the ventricular system which can be seen on a roentgenogram. It is important to utilize a manometer during the procedure so that




FIG. 29 The arterial supply as seen from the base of the brain and the formation of the circle of Willis. The cranial nerves are shown in relation to the vessels.

the cerebrospinal pressure is measured. As a rule, from 20 to 25 cc. of air is introduced; the outlines of the ventricles are seen and any abnormality is noted. Encephalography should not be used when there is an increase in intracranial pressure.

VENTRICULOGRAPHY

Ventriculography (Fig. 26) is a more formidable procedure but is the method of choice. It involves two incisions and two perforations of the skull. The technic consists of making two small incisions in the scalp about one inch on either side of the midline and about two inches above the lambdoid suture. The lips of each incision are retracted and a small burr hole is made

The dura is exposed, carefully nicked with a small crucial incision, and a ventricular needle is introduced. This is passed downward, forward and inward in such a way that the lateral ventricle is entered in the region of the junction of its body with the occipital horn. A study of the cerebrospinal fluid is thus permitted, as well as temporary relief from intracranial pressure. Fluid is removed and replaced by a somewhat smaller volume of air, the average amount of air injected being from 50 to 120 cc. After this lateral and anteroposterior roentgenograms are taken (Fig. 27 A and B). The lateral view may show deformity of the anterior or posterior horns by tumors situated in the frontal or occipital regions. The anteroposterior view may reveal a deflection of the ventricles



FIG 27 C Encephalogram in postero anterior projection (2) body of the lateral ventricle, (3) posterior horn, (5) descending horn




FIG 28 Cisternal puncture An imaginary line is constructed between the external auditory meatus and the nasion. The needle enters above the spinous process of the first cervical vertebra, parallels this line and enters the cisterna magna. The medulla is about an inch anterior to the posterior occipito atloid ligament.

ward. The first palpable cervical spinous process is located in the midline, and a point is taken immediately above it. The needle is then inserted in a forward and upward direction. The upward path parallels an imaginary line that joins the external auditory

The *cerebral artery*, a branch of the subclavian, after ascending and perforating the dura, unites with the same vessel of the opposite side to form the *basilar*. This vessel lies in the basilar groove of the pons and at its superior margin divides into two terminal




FIG. 31 The diploic veins. These veins form venous plexuses between the outer and the inner tables of the skull. Four diploic venous trunks drain these plexuses. The outer table of compact bone has been removed to demonstrate the veins.

meatus with the nasion as the needle advances it strikes the posterior *occipito alloid* ligament. In the adult this is at a depth of between 4 and 5 cm. Piercing of the ligament by the needle is usually felt, and then the cistern is entered. The medulla is about one inch anterior to the posterior *occipito alloid* ligament.

ARTERIAL SUPPLY

(Fig. 29) The arterial supply of blood is furnished to the brain by four vessels: two vertebral and two internal carotid arteries.

branches known as the *posterior cerebral arteries*. The *internal carotid*, after penetrating the dura, reaches the base of the brain at the angle between the optic nerve and the optic tract, then divides into two branches: *anterior* and *middle cerebral arteries*. These are connected by communicating vessels to form the *arterial circle of Willis*, which lies within the interpeduncular subarachnoid cistern. The arterial circle is formed in the following way: anteriorly, the anterior communicating artery joins the two anterior cerebral arteries, and the posterior commu-




FIG. 30 Veins of the head and the brain. Three of the emissary veins (parietal, mastoid and ophthalmic) are shown with their intracranial communications. Since the blood flow can travel in either direction infection may also pass both ways. The angular vein, which drains the upper lip or 'dangerous area of the face' is of particular importance because of its communication with the cavernous sinus.

from the midline or a filling defect of the third ventricle. During this procedure it is best to have the patient in the sitting or semisitting position.

CISTERNAL PUNCTURE

In cisternal puncture (Fig. 26) the patient may be in a sitting position or lying on one side with the head placed somewhat for

common facial vein which pierces the deep fascia and ends in the internal jugular at times it may cross the sternocleidomastoid muscle and end in the external jugular vein

canal, the foramen ovale, the foramen lacrum the foramen of Vesalius and the emissary veins accompanying the middle meningeal artery




FIG. 32 Lateral roentgenogram of the skull demonstrating the arterial channels the diploic veins and a fracture line (1) middle meningeal groove (2) plexus of diploic veins (3) fracture line over the squamous portion of the temporal bone (4) coronary suture, (5) lambdoid suture (6) sella turcica (7) sphenoid sinus

That part of the anterior facial vein which passes along the side or angle of the nose has been called the *angular vein*. It is important because it drains the so called dangerous area of the face. Boils and carbuncles commonly occur in this region and should such lesions be opened death may result from involvement of the cavernous sinus the internal jugular vein may also become infected in such cases. Since these veins have no valves infected thrombi become detached as a result of the constant motion brought about by talking and masticating causing a spread of the infection into the interior of the skull.

There are other emissary veins that are of less practical importance namely the veins of the hypoglossal canal, the condyloid

DIPLOIC VEINS

The *diploic veins* (Fig. 31) form venous plexuses between the inner and the outer tables of the skull. In the skull of the child the bone consists of a single layer in which numerous veins grow and communicate with each other. Marrow is found around these branching and communicating vessels, and this ingrowth results in the formation of an outer table of skull an inner table and the diploe situated between them. The veins form a plexus that is drained by four diploic venous trunks on each side the *frontal diploic vein* drains into the supra orbital vein the *anterior parietal (temporal)* drains into the sphenoparietal sinus the *posterior parietal (temporal)* drains into the lateral sinus,

nating artery connects the internal carotid with the posterior cerebral artery, posteriorly, the basilar artery bifurcates into the two posterior cerebral arteries to complete the circle. The so called circle is really heptagonal in shape. Two separate sets of branches arise from the cerebral arteries (1) the *central branches*, which are very numerous and slender, pierce the surface of the brain to supply the internal parts of the cerebrum including the basal nuclei, and do not anastomose with one another, (2) the *cortical branches* ramify over the surface of the cerebrum and supply the cortex, anastomose in the pia and are not sharply cut off from one another. The anterior cerebral artery supplies the superior and the middle frontal convolutions and the entire medial surface of the hemisphere as far back as the parieto occipital fissure. It also supplies the leg center of the paracentral lobule and the highest point of the precentral convolution. The middle cerebral artery is a direct continuation of the internal carotid; it runs upward and outward to the Sylvian fissure and supplies most of the exposed surface of the hemisphere: the insula and the internal capsule. It also supplies the bulk of the motor area of the brain: the cortical center for hearing part of the center for vision and the motor speech area of the left hemisphere. It gives off the lenticulostriate artery which is the vessel most frequently ruptured in cases of cerebral hemorrhage. This vessel has been referred to as the 'artery of apoplexy' (Charcot). The posterior cerebral artery supplies the middle and the inferior temporal gyri, the medial part of the occipital lobe and the lower surface of the temporosphenoidal lobe.

VEINS OF THE HEAD AND THE BRAIN

(Fig 30) The veins of the head and the brain may be divided as follows: (1) the *emissary veins* which connect the veins of the inside of the skull with those of the head, the face and the neck. (2) the *diploic veins*, which form venous plexuses situated

between the inner and the outer tables of the skull, (3) the cerebral and the cerebellar veins, which drain the venous blood of the cerebrum and the cerebellum. (4) the *venous dural sinuses*, which are placed between the layers of the dura mater.

EMISSARY VEINS

The *emissary veins* connect the intra and the extracranial veins. Since blood may flow in either direction, infection may also travel both ways. This double direction of blood flow equalizes the venous pressure in the sinuses and the superficial veins. The more important emissary veins include:

(1) The *parietal vein*, which passes through the parietal foramen at the top of the skull and joins the occipital vein via the superior sagittal sinus. It is of marked surgical importance as the path by which a relatively simple scalp infection may result in a thrombophlebitis or sinus thrombosis involving the superior sagittal sinus.

(2) The *emissary veins of the foramen caecum* connect the beginning of the superior sagittal sinus with the veins of the frontal sinus and the root of the nose. By means of this route infection may travel from either of the latter two structures to the superior sagittal sinus. These veins are seen more constantly in children than in adults.

(3) The *mastoid* is the most constant of the emissary veins; it connects the occipital or posterior auricular vein with the transverse (lateral) sinus. It is of surgical importance because of the frequency with which mastoid disease takes place and may result in infection of the transverse (lateral) sinus.

(4) The *ophthalmic veins* are considered *emissary veins which drain into the cavernous sinus*. Blood can flow in the reverse direction in these vessels and pass to the face and infratemporal fossa.

It is in connection with these emissary veins that the *anterior facial vein* becomes of utmost importance: the latter communicating with the cavernous sinus through the ophthalmic veins. The anterior and the posterior facial veins join in the neck to form the




FIG 34 Venous sinuses at the base of the skull The right internal carotid artery is shown surrounded by the cavernous sinus

toward the superior sagittal sinus turn forward and run parallel with the sinus for a short distance before entering it. The cerebral veins are divided into external and internal groups depending upon whether they drain the outer surface or the inner part of the hemisphere. The external veins are named the middle the superior and the inferior cerebral veins. The internal veins draining the deeper parts of the hemisphere are the terminal ones and the great cerebral vein of Galen (Fig 22)

VENOUS DURAL SINUSES

Venous sinuses of the dura mater (Figs 22 23, 30 34) are spaces between the two

layers of dura mater which collect blood and return it to the internal jugular vein. Into these spaces spinal fluid is also drained from the subarachnoid space through the arachnoid villi and granulations. Sinuses differ from other venous structures in the body in that their walls consist of a single layer of endothelium, as a result of which there is no tendency for them to collapse. Seven of these sinuses are paired and five are unpaired. The unpaired sinuses are the superior sagittal inferior sagittal straight, intercavernous and basilar. The paired sinuses are the sphenoparietal, cavernous superior petrosal, inferior petrosal occipital transverse and sigmoid. Only those that are of practical and surgical importance will be considered




FIG 33 The cerebral veins, viewed from above. The superior sagittal sinus has been opened and the dura mater has been reflected on the left side exposing the subdural space. The intact dura on the right side reveals the relationship of the extradural space and the middle meningeal vessels. A small flap of arachnoid has been reflected to show the position of the cerebral veins.

the *occipital* also drains into the lateral sinus. Diploic markings may be confused with fractures on a roentgenogram of the skull (Fig 32). In the parietal region the so-called "parietal spider" is seen: a spiderlike arrangement of these veins. There are no diploic arteries, since the arterial blood supply comes by way of the meningeal and the pericranial arteries.

CEREBRAL AND CEREBELLAR VEINS

The *cerebral* and the *cerebellar veins* (Fig 33) are veins of the brain proper. They do not accompany the arteries; they have no valves, no muscle tissue around them, and their walls are extremely thin. They are lodged for the greater part in the grooves on the surface of the brain and are covered by arachnoid. The superior veins run upward




FIG 34 Venous sinuses at the base of the skull. The right internal carotid artery is shown surrounded by the cavernous sinus

toward the superior sagittal sinus turn forward and run parallel with the sinus for a short distance before entering it. The cerebral veins are divided into external and internal groups depending upon whether they drain the outer surface or the inner part of the hemisphere. The external veins are named the middle, the superior and the inferior cerebral veins. The internal veins draining the deeper parts of the hemisphere are the terminal ones and the great cerebral vein of Galen (Fig 22).

VENOUS DURAL SINUSES

Venous sinuses of the dura mater (Figs 22, 23, 30, 34) are spaces between the two

layers of dura mater which collect blood and return it to the internal jugular vein. Into these spaces spinal fluid is also drained from the subarachnoid space through the arachnoid villi and granulations. Sinuses differ from other venous structures in the body in that their walls consist of a single layer of endothelium, as a result of which there is no tendency for them to collapse. Seven of these sinuses are paired and five are unpaired. The unpaired sinuses are the superior sagittal, inferior sagittal, straight, intercavernous and basilar. The paired sinuses are the sphenoparietal, cavernous, superior petrosal, inferior petrosal, occipital, transverse and sigmoid. Only those that are of practical and surgical importance will be considered.

The *superior sagittal (longitudinal) sinus* is in a somewhat exposed position along the insertion of the falx cerebri. It begins in front of the crista galli at the foramen caecum, where it occasionally communicates with the veins of the nasal mucous membrane. It then passes upward and backward in the upper border of the falx cerebri until it reaches the internal occipital protuberance where it lies a little to one side of the median plane usually on the right. Here it forms a dilation known as the *confluence of sinuses* (torcular Herophili) at which point the superior sagittal, the transverse, the occipital and the straight sinuses all meet. Here the superior sagittal bends acutely to the right occasionally to the left, and becomes continuous with the transverse sinus. Lateral expansions of the sinus (*lacunae laterales*) are found on each side. These lacunae receive meningeal and diploic veins, and the superior sagittal sinus receives emissary veins, diploic veins and those veins which drain the cerebral hemispheres. As the superior sagittal sinus runs posteriorly it grooves the internal aspect of the skull and its surface marking may be indicated by a line drawn over the median line of the vertex from the root of the nose to the external occipital protuberance.

The *inferior sagittal sinus* passes backward in the lower border of the falx cerebri. It unites with the great cerebral vein at the free margin of the tentorium cerebelli to form the straight sinus.

The *straight sinus* travels backward along the attachment of the falx cerebri to the tentorium. At the internal occipital protuberance it bends acutely to the left, occasionally to the right, to form the transverse sinus. It receives tributaries from the posterior part of the cerebrum, the cerebellum and the falx cerebri.

The *transverse (lateral) sinus* which is a paired structure, begins at the internal occipital protuberance. The right is usually continuous with the superior sagittal sinus and the left with the straight sinus. It receives the superior petrosal sinus and a few

inferior cerebral and cerebellar veins. It is bounded by the two layers of tentorium and the outer layer of dura mater and runs horizontally at first in a lateral direction and then forward. It lies in the transverse groove of the skull and in the attached margin of the tentorium.

The *sigmoid sinus* is a continuation of the transverse sinus and receives its name from the S shaped curves which it makes. Some authors believe the term "transverse" should be restricted to that part of the sinus that passes between the internal occipital protuberance and the posterior inferior angle of the parietal bone. The remaining part of the sinus (to the jugular foramen) is known as the sigmoid sinus, which curves downward leaves the tentorium, passes between the two layers of dura and ends at the jugular foramen, where it becomes the internal jugular vein. The continuation of the sinus as the internal jugular explains the propagation of a transverse sinus thrombosis. This justifies the ligation of the internal jugular to prevent the spread of septic emboli to the heart. The superior petrosal sinus joins it at its first bend, and the inferior petrosal at its termination. It forms an important posterior relation of the tympanic antrum. In suppurative conditions of the tympanic antrum or cavity this sinus may become the site of a septic process that travels through the cerebellar tributaries and forms a cerebellar abscess. It is separated from the mastoid cells by only a very thin plate of bone hence diseases from the middle ear into the mastoid cells can form a suppurative process that involves the sinus (sinus thrombosis). Its communications are numerous and important. It is connected by the mastoid emissary vein with the occipital vein, by the occipital sinus with the transverse sinus and by the posterior condylar emissary vein with the suboccipital plexus.

The *cavernous sinus* is situated to either side of the body of the sphenoid bone and is continuous with the ophthalmic veins in front. Posteriorly it divides into the superior and the inferior petrosal sinuses. t sur






FIG 35 The hypophysis (A) embryogenesis (B) sagittal section showing the hypophysis in the sella turcica and its relations to the optic chiasma (C) frontal section through the hypophysis and the cavernous sinus showing the normal relations between these and four of the cranial nerves

rounds the internal carotid artery. Injury in this area may result in the formation of an arteriovenous aneurysm which produces stasis in the superior ophthalmic vein. This

may bring about a pulsating exophthalmus due to pulsations of the carotid artery transmitted to the engorged venous spaces. Cavernous sinus thrombosis may follow inflam-



A
Intracranial approach



B
Transphenoidal approach

matory lesions of the face and the upper lip, the extension taking place through the facial, the nasal and the ophthalmic veins. This sinus is intimately related to the cavernous plexus and may be injured during operations on the latter. Infections involving the cavernous sinus are frequently accompanied by basilar meningitis.

The *circular sinus* consists of the two transverse venous connections between the cavernous sinuses. The *sphenoparietal sinus* runs along the lesser wing of the sphenoid to the superior sagittal sinus. The *occipital sinus* is extremely variable in size and lies in the attached border of the folia cerebelli. The *basilar sinus* is a wide trabeculated space behind the dorsum sellae which unites the cavernous and the inferior petrosal sinuses of opposite sides. It also communicates below with the spinal veins.

HYPOPHYSIS

EMBRYOLOGY

(Fig 35) The hypophysis or in older terminology the pituitary body developmentally consists of two different parts: a buccal or glandular portion which is derived from the roof of the mouth and lies anteriorly, and a nervous portion derived from the brain. The anterior part is an upgrowth (Rathke's pouch) from the roof of the primitive pharynx (stomodaeum). Normally the stalk that connects the anterior lobe to the roof of the mouth disappears completely because of the rapid growth of the body of the sphenoid bone, but occasionally this stalk may persist as the craniopharyngeal canal. At the site of Rathke's pouch or along the persisting craniopharyngeal canal, cysts may develop that are lined with squamous epi-

thelium (craniopharyngomas). After the anterior lobe has become isolated, a rapid proliferation of its cells takes place which displaces the gland. The posterior lobe is of nervous origin and is derived from the brain. It grows in a downward direction from the floor of the third ventricle and forms the infundibulum.

ADULT HYPOPHYSIS

The adult gland measures 13x8 mm and can be compared with an apple: the stem is the infundibulum that connects it to the brain, and the skin is the dura mater that encloses it. The *anterior lobe* consists of a pars anterior and a pars intermedia which are separated from each other by a narrow groove, a remnant of the diverticulum from which this lobe developed. The anterior lobe is the larger of the two and grows backward around each side of the posterior; it is hollowed out posteriorly to accommodate that lobe and therefore assumes a kidney shape. It is very vascular, blood vessels reaching it along the infundibulum from the arterial circle.

The *pars intermedia*, the middle part, contains a few blood vessels, small masses of colloid material, and some finely granulated cells.

The *posterior lobe*, arising as a downgrowth from the brain, contains no nerve cells but has numerous neuroglial cells and fibers and small collections of colloid material. Pituitrin is secreted in this lobe, but the secretion of the anterior lobe is concerned with growth and the production of prolans which are intimately related to the other endocrine glands.

The hypophysis lies in the sella turcica

FIG 36 Two approaches to the hypophysis. (A) The intracranial approach: an osteoplastic flap is formed through a frontoparietal approach. The dura is incised, the cortex protected and the frontal lobe gently elevated. The tumor and the optic nerves are exposed. (B) The transphenoidal operation: an incision is made between the upper lip and the gum. The mucoperiosteum is separated from each side of the septum and the latter is removed. The anterior wall of the sphenoid sinus is nibbled away until the floor of the sella turcica is encountered. The latter is removed, the dura is exposed and the hypophysis, with its pathology, is identified.

within duplications of the dura, which forms an osteofibrous compartment. The deep layer of dura dips into the sella; laterally it meets the superficial leaf, which passes over the gland to form the diaphragm. The lateral walls of the fossa form the medial walls of the cavernous sinuses. The superficial layer of dura forming the diaphragma sellae, produces a roof for the gland; the roof contains a central aperture and through it the infundibulum connects the posterior lobe to the tuber cinereum. The two anterior and the two posterior clinoid processes surround the gland as a four poster bedstead in which the pituitary body rests.

Four venous sinuses form a square that encloses the gland: the cavernous on each side and the anterior and the posterior intercavernous sinuses in front and behind. In the outer wall of the cavernous sinus lie the third, the fourth, the ophthalmic branch of the fifth, and the sixth cranial nerves. The internal carotid artery is situated beneath and within the meshes of the sinus. Anteriorly the gland is related to the sphenoid sinus. When the sinus is large only a thin plate of bone separates it from the gland; hence, the larger the sinus the more extensive is its relation to the hypophysis.

The optic chiasma lies superior to the hypophysis and, therefore, is related to the infundibulum rather than the gland proper. As the infundibulum passes upward posterior to the chiasma, it is in contact with its posterior edge and undersurface. The chiasma is not in direct contact with the bone.

SURGICAL CONSIDERATIONS

Two main routes are utilized to expose the hypophysis: an intracranial and a nasal

(Fig. 36). Most authorities believe that the nasal route is impractical since the exposure of the gland is poor and the danger of infection is increased.

Intracranial and Transphenoidal Operations. The *intracranial approach* takes the transfrontal route or one of its modifications. A more lateral approach in which an osteoplastic flap is utilized (Fig. 36 A) is described by Heuer. This begins 3 cm behind the external angle of the orbit, is carried just within the hair line to about one inch from the longitudinal sinus, where it turns backward and then curves downward posteriorly to the parietal eminence to a point 4 cm behind the helix. In reality this is a frontoparietal approach that combines both frontal and lateral routes. The dura is incised, the cortex protected and the frontal lobe gently elevated, exposing the optic nerve or the optic commissure and the hypophysis. Some authors describe an extradural approach but this is not as useful since certain tumors may be missed because of the lack of exposure and because the region posterior to the optic nerve and the internal carotid artery cannot be seen properly.

In a *transphenoidal operation* (Fig. 36 B) an incision is made in the mucous membrane between the upper lip and the gum. The anterior edge of the nasal septum is exposed, the mucoperiosteum is separated from each side of the septum and the latter is removed. The anterior wall of the sphenoid sinus is encountered and nibbled away until the bulging floor of the sella turcica is exposed. When this has been removed, the dura is incised, and the pituitary gland with its pathology is revealed and treated.

Cranial Nerves

The cranial nerves are twelve pairs of symmetrically arranged nerve trunks that are attached to the base of the brain. They leave the skull via various foramina at its base and are distributed for the greater part to the head. Some of the nerves may be described as traveling in a direction away from the brain, some of them convey impulses in a reverse direction. On leaving the brain each cranial nerve is invested by a sheath of pia mater, traverses the subarachnoid space, pierces the arachnoid and receives an additional sheath from the latter mentioned membrane. It next enters a canal in the dura mater; this leads to the foramen in the skull through which the nerve leaves the cranium. It is invested by a sheath of dura which is continuous with the epineurium covering the nerve trunk proper. The dural aperture and the foramen do not necessarily correspond to each other in location since some of the nerves (the fourth and the sixth) run in intradural course of some length before they leave their foramina. These nerves are not only numerically designated from before backward but are also distinguished by their specific names which are based upon their distributions or functions.

1 The olfactory nerves (Fig 37) about fifteen to twenty in number arise from the upper third of the nasal mucous membrane, pass through the cribriform plate of the ethmoid bone and enter the substance of the olfactory bulb which lies in contact with the orbital surface of the frontal lobe of the brain. The olfactory tract runs backward from the bulb and

ends in the corpus callosum; the lateral portion of the tract terminates in the uncus. Lesions that affect the uncinate area of the temporal lobe may start with unpleasant olfactory prodromes which are followed by a dreamy state; such attacks have been called uncinate gyrus fits.

2 The optic nerve (Fig 38) extends from the posterior aspect of the eyeball to the optic chiasma. In its course it passes through the optic foramen, accompanied by the ophthalmic artery, which lies to its outer and lower side. After gaining entrance to the cranium it converges toward the nerve of the opposite side which it joins to form the *optic chiasma*. In the optic chiasma those fibers that arise from the nasal side of the retina decussate with the corresponding fibers of the opposite side but the fibers arising from the temporal side of the retina do not. The *optic tracts* arise on each posterolateral angle of the chiasma and are continuations of the optic nerves. Each tract consists of fibers arising in the temporal half of the retina of the same side and the nasal half of the retina of the opposite side. The tracts divide into lateral and medial roots; the lateral ending in the gray matter of the lateral geniculate body and the superior corpus quadrigeminum. The medial root ends in the medial geniculate body and has no connections with vision. From the lateral geniculate body new fibers arise and enter the internal capsule; here they assume the name of optic radiations and pass backward and terminate in the *higher visual centers* in the visual cortex (postcalcarine and calcarine




FIG 37 The olfactory nerve




FIG 38 The optic nerves viewed from the base of the brain. A lesion at A would involve the nerve and result in blindness. At B the chiasma would be involved resulting in bitemporal hemianopsia. At C injury to the optic tract would produce a homonymous hemianopsia.

sulci). As the optic nerve passes from the brain it receives its perineural sheath from the pia mater, an outer covering from the dura, and an inner covering from the arachnoid. These sheaths remain separated and the two enclosed spaces may be involved separately. Increased pressure from the subarachnoid space in the cranial

cavity is transmitted to the subarachnoid space around the optic nerve; the central vein and artery become compressed, resulting in an engorgement of the retinal veins and a diminution of the artery. This condition is known as papilledema.

3 The oculomotor nerve (Figs 39-41) travels from the cavernous sinus to




FIG 39 The oculomotor nerve (diagrammatic)

the orbit. After reaching the orbit through the lower part of the superior orbital fissure it immediately divides into superior and inferior divisions. The superior division supplies the superior rectus and the levator palpebrae superioris muscles; the inferior supplies the inferior oblique and the medial and inferior recti. From the inferior division a short nerve passes to the ciliary ganglion, the ciliary muscle and the sphincter pupillae. The oculomotor nerve supplies all the extrinsic muscles of the eye with the exception of the external rectus and the superior oblique. A lesion of the third nerve results in ptosis of the upper lid (paralysis of the levator palpebrae superioris), dilated pupil (the sympathetic fibers are unopposed), loss of accommodation (paralysis of the ciliary muscle) and external strabismus (unopposed action of the external rectus and the superior oblique muscles).

4 The trochlear nerve (Fig 40) is the smallest of the cranial nerves. It lies a little below and lateral to the oculomotor nerve and supplies the superior oblique muscle. Its course is almost the same as that of the third nerve. At the superior orbital fissure it lies above the muscles. The trochlear nerve is rarely involved alone but when this does occur the patient experiences difficulty in moving the eye in an outward and downward

direction. It has been stated that this nerve supplies the down and out muscle since the action of the superior oblique is to rotate the eye outward and downward. This is an excellent test for the fourth nerve since the patient in attempting to look downward and outward will see double.

5 The trigeminal nerve (Figs 41,




FIG 40 The right trochlear nerve seen from above. Its fibres enter the superior oblique muscle.




FIG. 41 The trigeminal nerve and the semilunar (gasserian) ganglion. The lateral wall of the orbit has been removed, and the maxillary sinus has been opened.

42) is the thickest of the cranial nerves and has a wide distribution. It has a large sensory root upon which the semilunar (gasserian) ganglion is situated, the ganglion resting in a fossa on the superior surface of the petrous bone near its apex. The three main divisions of the nerve—ophthalmic, maxillary and mandibular—arise from this ganglion. The motor root lies inferolateral to the sensory root and does not enter the ganglion. Both roots arise from the lateral part of the inferior surface of the pons. The fifth nerve resembles a spinal nerve in that it has two roots, a sensory and a motor, with a ganglion on the sensory. The nerve provides the sensory supply to the face and the anterior half of the scalp and sends motor branches to the four muscles of mastication (except the buccinator) and to four

other muscles: tensor palati, tensor tympani, mylohyoid and anterior belly of the digastric. There are five ganglia on the fifth nerve: the semilunar on the nerve trunk, the ciliary on the ophthalmic division, the sphenopalatine on the maxillary division, the otic on the mandibular division and the submaxillary (Langley's) also on the mandibular division. All these ganglia, with the exception of the semilunar, receive motor, sensory and sympathetic fibers.

The *semilunar (gasserian) ganglion*, the sensory ganglion of the fifth nerve, occupies a space between the outer and the inner layers of dura known as the *cave of Meckel* (cavum trigeminale), which is in reality a diverticulum of the inner layer of dura. There are two layers of dura above and two layers below the ganglion,




FIG. 42 Diagram of the trigeminal nerve and the semilunar (Gasserian) ganglion

the two layers being fused. The foramen which transmits the middle meningeal artery is on the outer side of the ganglion and must be encountered before the ganglion is reached by the temporal route. The cavernous sinus and internal carotid artery are found medially. The motor root makes no connections with the ganglion but passes through the foramen ovale and on the outside of the skull joins the mandibular division. Posterior to the cave the superior petrosal sinus is located as it widens to join the cavernous sinus. The sphenoparietal sinus is found anteriorly as it joins the cavernous sinus. Because of these relationships the ganglion should be approached through the middle region of the outer aspect of the cave.

The ophthalmic is the smallest division of the fifth nerve. After giving off a small twig to the dura mater it passes forward in the lateral wall of the cavernous sinus and enters the orbit through the superior orbital fissure. In the fissure it splits into

three branches: frontal, nasociliary, and lacrimal. The lacrimal and the frontal branches enter the orbit above the muscles; the nasociliary passes between the two heads of the lateral rectus. The lacrimal nerve travels along the lateral part of the orbit and supplies the lacrimal gland, the conjunctiva, and the skin of the upper eyelid. The frontal nerve divides into supra-orbital and supratrochlear nerves that lie beneath the roof of the orbit. The supra-orbital nerve reaches the scalp after passing through the supra-orbital notch (foramen) and then divides into medial and lateral branches that supply the scalp. The supratrochlear nerve runs above the pulley of the superior oblique muscle. The frontal nerve supplies the mucous membrane of the frontal sinus, the skin of the upper eyelid, the scalp, and the forehead. The nasociliary nerve leaves the orbit by the anterior ethmoidal foramen and then changes its name to the anterior ethmoidal nerve. It passes over the cribriform




FIG 41 The trigeminal nerve and the semilunar (gasserian) ganglion. The lateral wall of the orbit has been removed, and the maxillary sinus has been opened

42) is the thickest of the cranial nerves and has a wide distribution. It has a large sensory root upon which the semilunar (gasserian) ganglion is situated, the ganglion resting in a fossa on the superior surface of the petrous bone near its apex. The three main divisions of the nerve—ophthalmic, maxillary and mandibular—arise from this ganglion. The motor root lies inferolateral to the sensory root and does not enter the ganglion. Both roots arise from the lateral part of the inferior surface of the pons. The fifth nerve resembles a spinal nerve in that it has two roots, a sensory and a motor with a ganglion on the sensory. The nerve provides the sensory supply to the face and the anterior half of the scalp and sends motor branches to the four muscles of mastication (except the buccinator) and to four

other muscles: tensor palati, tensor tympani, mylohyoid and anterior belly of the digastric. There are five ganglia on the fifth nerve: the semilunar on the nerve trunk, the ciliary on the ophthalmic division, the sphenopalatine on the maxillary division, the otic on the mandibular division and the submaxillary (Langley's) also on the mandibular division. All these ganglia, with the exception of the semilunar, receive motor, sensory and sympathetic fibers.

The *semilunar (gasserian) ganglion*, the sensory ganglion of the fifth nerve, occupies a space between the outer and the inner layers of dura known as the *cave of Meckel* (cavum trigeminale), which is in reality a diverticulum of the inner layer of dura. There are two layers of dura above and two layers below the ganglion,

artery and ends muscular branches to the tensor tympani and the tensor palati. The submaxillary (Langley's) ganglion is also associated with the mandibular division lying on the outer surface of the hyoglossus muscle and joining the lingual nerve. Although the fifth nerve is mainly sensory it may be tested by utilizing its motor branches to the masseter muscle. When the nerve is involved the masseter will not protrude on the affected side if the patient clenches his teeth.

6. The abducent nerve (Fig. 43) the sixth cranial nerve supplies only one muscle the lateral rectus and resembles the fourth nerve in that it is very slender. It originates at the base of the pons and emerges from its lower border. Soon after its origin it crosses either superficial or deep to the antero-inferior cerebellar artery. This is an important relation because a hardened and arterio-sclerotic artery in this region may press upon the nerve causing its paralysis. The nerve passes almost vertically up the back of the petrous portion of the temporal bone where it may be involved in fractures of the base of the skull; it then takes a sharp bend enters the cavernous sinus and after leaving the sinus passes through the superior orbital fissure into the orbit with the third and the fourth nerves. Involvement of the sixth nerve paralyzes the lateral rectus muscle of the same side. This means that the now unopposed medial rectus can displace the eyeball inward resulting in an internal strabismus. This nerve may also be involved in cases of increased intracranial pressure.

7. The facial nerve (Fig. 44) is seen when the cerebellum is removed. It is the motor nerve to the face and contains no cutaneous branches. Leaving the brain at the lower border of the pons and accompanying the auditory (eighth) nerve into the internal auditory meatus it passes through the temporal bone and leaves the skull through the stylomastoid foramen. In the temporal bone it gives off the *great*




FIG. 43 The right abducent nerve (diagrammatic)

superficial petrosal nerve which sends sensory fibers to the mucous membrane of the soft palate and secretory fibers to the mucous glands, the *nerve to the stapedius* muscle and the *chorda tympani* which passes through the tympanic cavity, joins the lingual nerve and thus supplies taste and sensation fibers to the anterior two-thirds of the tongue and secretory fibers to the submaxillary and sublingual glands.

At the exit from the stylomastoid foramen the facial nerve gives off the posterior auricular nerve and a branch which divides into two twigs supplying the stylohyoid muscle and the posterior belly of the digastric. The *posterior auricular nerve* ascends behind the ear and supplies the posterior and the superior auricular

plate of the ethmoid bone and enters the nose through the nasal slit. In the nose it gives off a medial branch to the nasal septum and a lateral branch which reaches the face after passing between the nasal bone and the upper cartilage. This nerve supplies the skin on the lower part of the nose. The branches of the nasal nerve in the orbit are the twigs to the ciliary ganglion, the ciliary nerves to the eyeball and the infratrochlear nerve. The *ciliary ganglion* is a small reddish body, situated between the lateral rectus and the optic nerve; it receives a sensory root from the nasociliary branch of the ophthalmic and a motor root from the lower division of the oculomotor, and a sympathetic nerve from the plexus around the internal carotid artery. It gives off from twelve to fourteen short ciliary nerves which supply the muscles and the iris.

The *maxillary division* of the trigeminal nerve resembles the ophthalmic in that it is purely sensory. It leaves the middle cranial fossa through the foramen rotundum and reaches the pterygopalatine fossa. After crossing the fossa the nerve leaves by way of the inferior orbital fissure to occupy the inferior orbital groove and canal. It appears on the face at the *infra orbital foramen* as the *infra orbital nerve*; here it divides into the following terminal branches: a small meningeal branch to the dura mater, two ganglionic branches to the sphenopalatine ganglion, zygomatic branches to the orbit through the inferior orbital fissure which divides into the zygomaticotemporal and zygomaticofacial, posterior superior alveolar to the molar teeth, infra orbital which supply the three molars, canine and incisors, and facial, which supply the lower eyelids (palpebral), the side of the nose (nasal) and upper lip (labial). The *sphenopalatine ganglion* (Meckel) is associated with the maxillary division of the fifth nerve. The sensory roots of the ganglion arise from the maxillary division of the trigeminal nerve, and the motor

and the sympathetic fibers from the nerve of the pterygoid canal (Vidian). The branches of the ganglion are orbital (secrete motor fibers to the lacrimal gland), pharyngeal, nasal and palatine.

The *mandibular nerve* is the largest division of the trigeminal. It consists of a sensory portion derived from the trigeminal ganglion and a motor root, these two portions passing separately through the foramen ovale but rejoining immediately to form a common trunk. After giving off a meningeal branch, the nervous spinosus which enters the cranium through the foramen spinosum, the trunk furnishes a twig to the medial pterygoid and divides into anterior and posterior divisions. The anterior division consists mainly of motor fibers and divides into deep temporal nerves, the nerves to the masseter, the lateral pterygoid nerves and the buccal nerve. The posterior division gives off the two roots of the auriculo-temporal and divides into the lingual and the inferior alveolar nerves. The only motor fibers in this division are those that form the mylohyoid branch of the inferior alveolar. The anterior division has been referred to as the lingual division and the posterior has often been called the inferior dental. As both of these divisions run downward they are concealed by the external pterygoid muscle and the ramus of the mandible and are distributed to the tongue, the gums, the lower teeth and the muscles of mastication. The *lingual nerve* travels forward to the anterior two thirds of the tongue, to which it is distributed. The *inferior alveolar nerve*, larger than the lingual, enters the mandibular canal through the mandibular foramen, passes through the ramus and the body of the mandible and distributes its branches to the lower teeth. Two ganglia, the otic and the submaxillary, are associated with the mandibular division of the fifth nerve. The otic is very small and difficult to find; it lies immediately below the foramen ovale in front of the middle meningeal




FIG. 45 The auditory nerve (diagrammatic)

buccal the mandibular and the cervical branches. The buccal branch appears at the anterior border of the gland and supplies the buccinator and the orbicularis oris muscles. The mandibular branch supplies the lower lip and the chin. The cervical branch appears at the lower border of the gland and supplies the platysma and the depressors of the lower lip. Intracranial lesions of the facial nerve are characterized by involvement of only the lower half of the face. Cranial lesions may result from middle ear diseases or fractures of the face or the skull. Intracranial lesions result in facial paralysis as seen in Bell's palsy in which condition the involved side of the face is flat and expressionless; the patient is unable to whistle, blow out his cheeks, wrinkle his forehead or show his teeth. In its course the facial nerve makes connections with the auriculotemporal and the great auricular nerves.

8 The auditory (acoustic) nerve (Fig. 45), which is the eighth nerve, consists of two parts: the cochlear which carries auditory impulses and the vestibular which has to do with equilibrium. At the lower border of the pons the roots are combined into a single trunk which

leaves the posterior cranial fossa by way of the internal auditory meatus where it divides into an upper part with only vestibular fibers. The cochlear nerve is distributed to the cochlear duct and the spiral organ; the vestibular fibers are distributed to the semicircular ducts, the utricle and the saccule. Lesions of the eighth nerve may produce complete deafness on the same side and a loss of equilibrium.

9 The glossopharyngeal nerve (Fig. 46) which is the ninth nerve emerges from the brain in such a way that its uppermost rootlets of origin are situated just below the eighth nerve and the lowermost are practically continuous with the tenth. It passes upward and outward to the jugular foramen through which it leaves the skull. In this foramen it is enclosed in a special dural compartment, and the tenth and the eleventh nerves and the jugular vein are posterior to it. The glossopharyngeal then passes downward and forward between the internal and the external carotid arteries, winds around the stylopharyngeus muscle and reaches the under surface of the base of the tongue going beneath the hyoglossus muscle. It supplies taste and sensations to the pos-

muscles and the occipital belly of the occipitofrontalis. Having given off its branches in the temporal bone and at the exit from the stylomastoid foramen the facial nerve supplies its terminal branches

the anterior border of the parotid gland and radiate over the side of the face in a fanlike manner (Figs 87 and 88). The temporofacial division gives rise to two terminal branches: *temporal* and *zygomatic*. A tem




FIG. 44. The facial nerve. It divides into two divisions: the temporofacial and the cervicofacial. These give rise to the five terminal branches which form the *pes anserinus* (goose's foot). Its relations to the parotid gland are seen in Figures 87 and 88.

to the face. Here it divides into two main divisions: a temporofacial and a cervicofacial. Recent work on the parotid gland and the facial nerve shows that no part of the nerve actually runs within the parotid gland substance (p. 132). It is believed that these two divisions embrace the isthmus of the parotid gland so that the facial nerve really runs in a "parotid sandwich." The two divisions break up into a nerve plexus which has been called the *pes anserinus* (goose's foot). These terminal nerves forming the plexus emerge at

the anterior border of the parotid gland and radiate over the side of the face in a fanlike manner. The zygomatic branches are divided into a smaller upper branch, which passes forward from the upper anterior border of the parotid to the zygomatic bone and supplies the adjoining facial muscle, and a lower zygomatic branch, which appears at the anterior border of the gland and runs with the transverse facial vessels to the muscles of the upper lip and the nose. The cervicofacial division gives rise to the




FIG 45 The auditory nerve (diagrammatic)

buccal the mandibular and the cervical branches. The buccal branch appears at the anterior border of the gland and supplies the buccinator and the orbicularis oris muscles. The mandibular branch supplies the lower lip and the chin. The cervical branch appears at the lower border of the gland and supplies the platysma and the depressors of the lower lip. Intracranial lesions of the facial nerve are characterized by involvement of only the lower half of the face. Cranial lesions may result from middle ear diseases or fractures of the face or the skull. Extracranial lesions result in facial paralysis as seen in Bell's palsy in which condition the involved side of the face is flat and expressionless; the patient is unable to whistle, blow out his cheeks, wrinkle his forehead or show his teeth. In its course the facial nerve makes connections with the auriculotemporal and the great auricular nerves.

8 The auditory (acoustic) nerve (Fig 45) which is the eighth nerve consists of two parts: the cochlear which carries auditory impulses and the vestibular which has to do with equilibrium. At the lower border of the pons the roots are combined into a single trunk which

leaves the posterior cranial fossa by way of the internal auditory meatus where it divides into an upper part with only vestibular fibers. The cochlear nerve is distributed to the cochlear duct and the spiral organ; the vestibular fibers are distributed to the semicircular ducts, the utricle and the saccule. Lesions of the eighth nerve may produce complete deafness on the same side and a loss of equilibrium.

9 The glossopharyngeal nerve (Fig 46) which is the ninth nerve emerges from the brain in such a way that its uppermost rootlets of origin are situated just below the eighth nerve and the lower most are practically continuous with the tenth. It passes upward and outward to the jugular foramen, through which it leaves the skull. In this foramen it is enclosed in a special dural compartment and the tenth and the eleventh nerves and the jugular vein are posterior to it. The glossopharyngeal then passes downward and forward between the internal and the external carotid arteries, winds around the stylopharyngeus muscle and reaches the under surface of the base of the tongue going beneath the hyoglossus muscle. It supplies taste and sensations to the pos-

terior third of the tongue and supplies the epiglottis the soft palate the tonsils and the pillars of the fauces. Lesions of this nerve produce anesthesia of the posterior third of the tongue as well as of the pharynx.

10 In the vagus (pneumogastric) nerve (Fig 47) the rootlets of origin are continu-

ary and reaches the thorax behind the right innominate vein. In the superior mediastinum it is found to the right of the innominate artery and the trachea, and posterior to the superior vena cava. It continues along the lateral aspect of the trachea to the posterior mediastinum where it splits into several branches at




FIG 46 The glossopharyngeal nerve. Its communications with surrounding nerves are shown.

ous above with those of the ninth. The nerve leaves the cranium through the middle compartment of the jugular foramen and occupies the same sheath of dura as does the accessory nerve. The vagus descends between the internal carotid artery and the internal jugular vein; it enters the carotid sheath and travels downward, lying behind and between the common carotid artery and the internal jugular vein. The right vagus passes over the first part of the subclavian

the back of the root of the lung; these form the posterior pulmonary plexus. From this plexus the vagus continues as two cords which pass on to the esophagus to unite with the vagus of the opposite side forming the esophageal plexus. The nerve leaves this plexus as a single trunk, descending behind the esophagus and passing through the corresponding opening in the diaphragm to become distributed to the posterior surface of the stomach. Com-




FIG 47 The right and the left vagus nerves. Although an esophageal plexus is demonstrated in the illustration nevertheless it is believed by some anatomists that the vagi do not form a true plexus in this region, but rather reveal individual nerve filaments.

municating fibers are furnished to the celiac the splanchnic and the renal plexuses. The *left* vagus enters the thorax

between the left common carotid and the subclavian arteries posterior to the left innominate vein and the left phrenic

nerve After crossing to the left of the aortic arch it breaks up at the back of the root of the lung into the posterior pulmonary plexus From this plexus the two efferent nerves pass over the descend

spinal cord, hence its name, spinal accessory nerve The cerebral part arises from the medulla oblongata and leaves in company with and below the vagus, the spinal part arises from the anterior column of




FIG 48 The spinal accessory nerve

ing thoracic aorta and reach the esophagus as the esophageal plexus The continuing nerve passes through the esophageal orifice and travels over the anterior surface of the stomach, sending branches into the gastrohepatic ligament to form the hepatic plexus The laryngeal nerves that arise from the vagus will be discussed in the section on the larynx (p 232) The most typical sign of a lesion of the vagus is paralysis of its recurrent laryngeal branch Such a lesion produces an immobile vocal cord fixed in the cadaveric position on the affected side

11 The spinal accessory nerve (Fig 48), the eleventh cranial nerve originates partly from the brain and partly from the

gray matter of the spinal medulla and leaves the cord as low as the sixth cervical nerve The spinal portion ascends in the spinal canal to enter the cranium through the foramen magnum joins the accessory part and then leaves the skull through the middle compartment of the jugular foramen lying posterior to the vagus and the glossopharyngeal nerves It passes over the internal jugular vein beneath the posterior belly of the digastric muscle then pierces the sternocleidomastoid muscle and runs over the posterior triangle of the neck to enter the trapezius In the sternocleidomastoid it communicates with the second cervical, and in the trapezius with the third and the fourth cervical nerves Lesions of this

nerve paralyze the sternocleidomastoid but paralysis of the trapezius varies according to how much of it is supplied by the third and the fourth cervicals also the scapula is displaced downward and its vertebral

submandibular triangle At this point it disappears beneath the mylohyoid muscle and runs upon the hyoglossus muscle just beneath the submandibular duct Lying medial to the lingual artery, it reaches the




FIG. 49 Plan of the hypoglossal nerve

border is imperfectly approximated to the midline when the shoulders are braced back. The nerve may be injured in operations on the neck, especially in removal of tuberculous glands that surround it.

12 The hypoglossal nerve (Fig. 49) leaves the skull through the anterior condylar canal and enters the neck behind the internal jugular vein and the internal carotid artery. It passes beneath the posterior belly of the digastric muscle, crosses the external carotid artery on the first part of the lingual artery, and then enters the

tongue. The descending branch of the twelfth nerve passes down in the anterior wall of the carotid sheath where it joins with the descending cervical nerves (second and third) to form the ansa hypoglossi. The twelfth nerve is the motor nerve to the tongue and also supplies the sternohyoid, the sternothyroid, and the omohyoid muscles. When it is involved, the corresponding half of the tongue becomes atrophied, and if the patient is asked to protrude his tongue, the healthy side causes it to deviate toward the paralyzed side.

Special Senses

THE EYE AND ITS APPENDAGES

EYELIDS, LAYERS AND PRACTICAL CONSIDERATIONS

The *eyelids* (palpebrae) are two thin, movable folds the upper being the larger more movable and furnished with a muscle known as the *levator palpebrae superioris* which elevates the lid. Both eyelids are covered by skin superficially and mucous membrane (conjunctiva) over the deep aspect. When the eye is opened an elliptical space, the *palpebral fissure* remains between the lid margins. The lids are united laterally and medially by corresponding palpebral commissures (canthi). The *lateral palpebral commissure* (external canthus) is more acute than the medial and is placed directly against the globe (Fig. 50). The *medial commissure* or internal canthus, is prolonged for a short distance toward the nose and here the two eyelids are separated by a triangular space known as the *tear lake* (*lacus lacrimalis*). This lacus is bounded above and below by the lacrimal parts of the eyelid and laterally by a crescentic fold of conjunctiva known as the *plica semilunaris* which is considered as a remnant of the third eyelid. In the lacus there is a reddish elevation, the *caruncle* composed of modified skin and containing a few fine hairs, sebaceous and sweat glands.

Near the medial angle of the eye where the eyelids meet the eyelashes abruptly stop at this point are found rounded elevations known as *lacrimal papillae*. When the eyelid is everted the small opening (punctum lacrimale) is seen on the summit of each papilla. The puncta are

in close apposition with the conjunctivae and each leads into the *lacrimal canaliculus (duct)*, which passes medially to the lacrimal sac. The eyelashes arise from the mucocutaneous junction of the lids, and directly behind them the opening of the *tarsal gland* can be seen.

The eyelids have six layers (Fig. 51)

1 *Skin* The skin of the eyelids is extremely thin, there probably being no thinner skin at any other place in the body. The eyelashes project from the lid margin at the mucocutaneous border. Associated with these hairs are sebaceous glands, called the *glands of Zeis*, which open into each hair follicle. The *glands of Moll* are sweat glands and likewise open into or beside the hair follicles.

2 *Loose Subcutaneous Tissue Layer* This subcutaneous tissue layer is extremely loose and easily distended with blood or exudate so that any effusion into it becomes immediately apparent. Involvement of the sebaceous glands of hair follicles in the skin and subcutaneous tissues results in the common condition known as a sty (*hordeolum*). There is little or no subcutaneous fat in the eyelids.

3 *Layer of Striped Muscle* The layer of striped muscle is made up of the palpebral fibers of the *orbicularis oculi muscle*. It acts as the sphincter of the palpebral fissure. (The levator palpebrae situated in the upper lid is attached along the upper margin of the tarsal plate.)

4 *Areolar Layer (Submuscular)* The sensory nerves lie in this layer therefore, in producing anesthesia of the lid it is necessary to inject deeply to the orbicularis muscle. This areolar space is continuous

above with the dangerous area of the scalp.

5 *Tarsal Plate* The tarsae are two thin plates of dense connective tissue about one inch long. They are present in each eyelid. They contribute to the form and the support of the lids and are connected with the lateral wall of the orbit by the lateral (external) tarsal ligament and with the medial wall by the medial (internal) tarsal ligament. The tarsae are further connected with the upper and the lower orbital margins by an aponeurotic layer of connective tissue called the *palpebral fascia* (orbital septum). The superior tarsal plate receives the insertion of the levator palpebrae superioris. The meibomian sebaceous glands (tarsal glands) are located in the plate proper and are identified as yellow streaks when the lid is examined from the conjunctival side. The glands open on the lid margin and their secretion guarantees an airtight closure of the lid thus preventing maceration of the skin by tear moisture. An obstructed hair follicle (sty) will protrude on the front of the lid but an obstructed tarsal (meibomian) gland or chalazion will protrude onto the globe of the eye as a tarsal cyst.

6 *Conjunctiva* The conjunctiva is a layer of mucous membrane which attaches the eyeball to the lid. The lines along which the reflection of the conjunctiva takes place from lid to eyeball are termed the *superior* and the *inferior fornices*. The area where the conjunctiva lines the posterior surface of the lid is known as the *palpebral conjunctiva* and where it covers the globe of the eye it is called the *bulbar conjunctiva*. The conjunctiva is firmly adherent to the tarsal plate but is loosely attached to the sclera over the globe of the eye.

The *arterial supply* of the lids is derived from the superior and the inferior palpebral branches of the ophthalmic artery which form a rich vascular anastomosis. The *veins* of the lids drain into the ophthalmic veins by way of subconjunctival or retrotarsal veins. The *lymphatics* drain

laterally to the preauricular glands and medially to the facial and the submaxillary groups. The chief *motor nerve* of the lids is the facial to the orbicularis oculi muscle, if this nerve is injured it impairs the important sphincter action of the muscle in closing the lids. The oculomotor nerve supplies the levator palpebrae muscle, and in the event of its paralysis, a ptosis or inability to lift the lid results.

LACRIMAL APPARATUS

The *lacrimal apparatus* consists of the lacrimal glands, two lacrimal ducts, the lacrimal sac and the nasolacrimal duct (Figs 50, 52).

The *lacrimal gland* is situated in a depression in the superolateral angle of the orbit. It is oval in shape, about the size and the shape of an almond and is divided by the aponeurosis of the levator palpebrae superioris into two portions, a superior and an inferior. The *superior* or orbital portion is longer and is fixed to a depression in the orbital plate of the frontal bone. In front it lies against the orbital septum, through which access is gained for removal of this portion of the gland. Behind it rests on the tendon of the levator palpebrae muscle. The *inferior* or palpebral portion is smaller and joins the orbital portion behind. It lies on the palpebral conjunctiva to which it is adherent and through which its ducts open. These two portions of the glands pour tears into the upper fornix by means of eight to twelve tiny ducts. The tears travel over and lubricate the eyeball, pass into the lacrimal ducts to the lacrimal sac, then down the nasolacrimal duct and into the nose.

The *lacrimal ducts (canaliculi)* are situated one in each eyelid starting at tiny orifices called the *puncta lacrymalia*. The ducts are about 1 cm long, passing first vertically and then almost horizontally inward to join the lacrimal sac. The course of the duct is important to know when one is attempting to pass a probe.

The *lacrimal sac* is situated in the lacri-




FIG 50 The right eye and the lacrimal apparatus




FIG 51 Diagram of the six layers that form the eyelids




FIG 52 The lacrimal apparatus The right half of the upper eyelid and part of the right frontal bone and nose have been removed

mal fossa formed by the frontal process of the superior maxilla and the lacrimal bone. The dome of the sac known as the fundus projects above the internal tarsal ligament. This ligament may be rendered prominent by drawing on the skin laterally immediately behind it the sac will be found.

The *nasolacrimal duct* is the downward continuation of the lacrimal sac. It is about three quarters of an inch long and descends in a bony groove that is formed by the superior maxilla, the lacrimal and the inferior turbinate bones. In the region of the maxilla the duct is in close contact with the maxillary sinus; its direction is backward, outward and downward and may be identified by a line from the

inner angle of the eye to the first upper molar tooth of the same side. The continuity of the duct with the mucous membrane of the nose explains the extension of diseases from the nose into the lacrimal passages. Its opening in the nose is under cover of the anterior part of the inferior nasal concha.

Surgery of the Gland, the Sac and the Ducts. Although infections and tumors of the lacrimal gland are somewhat unusual, involvement of the tear conducting passages is common. This is known as *dacryocystitis* and as a rule some obstructing agent in the nasolacrimal duct is the cause of the inflammatory process. Obstruction of the duct may be produced by infections of the nasal fossa or the paranasal sinuses.

A prominent symptom in all diseases of the tear conducting apparatus is epiphora or tearing

Normally the *lacrimal duct* admits a probe about 3.5 mm in diameter, which can be passed medially through the lower punctum. Probing has been used to relieve obstructions but it should not be attempted in inexperienced hands. If this procedure fails then more radical ones may be advised such as establishing a communication between the sac and the middle nasal passage (Toti's operation) or extirpation of the lacrimal sac.

Removal of the lacrimal sac is performed as a last resort in persistent cases of dacryocystitis. The incision begins at a point about 3 mm above and internal to the inner canthus and is carried downward and outward about an inch. After division of the skin the margins are dissected and an attempt is made to locate the anterior lacrimal crest. The fascia is incised and when the sac is exposed it is separated from the periosteum of the lacrimal fossa. The ducts are divided, the extremities of the sac freed and excised as low as possible in the nasolacrimal duct.

Excision of the lacrimal gland is reserved for those cases where the lacrimal sac has been removed leaving no channel for drainage of tears and resulting in troublesome watering of the eye. Excision of the superior portion of the gland may be made through a curved incision parallel to the outer half of the orbital margin. The incision passes through the skin, the connective tissue and the orbital fascia down to the periosteum. The wound edges are retracted bringing into view the lacrimal gland which is grasped by forceps and brought as far into the wound as possible. The gland is then freed, and the lacrimal artery is clamped and ligated. To remove the inferior or accessory lacrimal gland, a small horizontal incision is made over the contour of that gland. Retraction of the wound edges brings the

gland into view, it is then dissected from its bed and removed.

ORBIT

The orbital cavity has been likened to a quadrilateral pyramid the base being in front and the summit behind. The orbits are bony cavities, situated between the anterior portion of the cranium and the face and are separated by the nasal fossa. Each orbit contains the globe of one eye and its appendages. The orbital cavity is closed in front by the eyelids which are separated from the globe of the eye by folds of conjunctiva. The eyeball occupies the anterior part of the orbit, and the posterior portion is filled with fat, fascia, muscles, vessels and nerves, which are appendages of the eye. The anterior and the posterior portions are divided from each other by the so called capsule of Tenon (p. 83) which is the membranous sac enveloping the posterior portion of the eyeball and forming a socket in which it moves. The walls of the orbit are very thin and are lined with periosteum, called *periorbita* which is continuous through the optic foramen with the dura mater. Pathologic effusion may detach the periosteum from the bone since it is only loosely attached. At the lacrimal groove it splits to enclose the lacrimal sac. The four walls are in contact with four fossae: the anterior cerebral above the maxillary sinus below, the nasal medially and the temporal laterally. Involvement of the orbital cavity there fore, may encroach upon any of these four regions and vice versa. Since, with the exception of its frontal aspect, the orbit is surrounded by bone tumors developing here will take the path of least resistance and push the eyeball forward, producing the condition of exophthalmos.

Lateral Temporal and Intracranial Approaches. *Kronlein's operation* affords a lateral temporal orbital approach to the retro ocular space and is a procedure by which an orbital tumor may be removed.




FIG 53 Horizontal section of the right eye. The eyeball has three coats (fibrous, pigmented, and nervous) and three refractive media (aqueous humor, vitreous humor, and lens).

leaving the eye in place. An appropriate incision which extends to the bone is made; the central part of the incision exposing the orbital margin. The periosteum is separated from the outer wall of the orbit, and the contents of the latter are gently retracted. The sphenomaxillary fissure is located and marked. An incision through the bone is then made by means of a chisel or an electric saw from a point a little above the external angular process of the frontal bone extending to the anterior end of the fissure; a second incision extends from the base of the orbital process of the malar bone backward to the

same point. The resulting wedge-shaped piece of bone can be swung outward, exposing the periosteum lining the lateral wall of the orbit, thus permitting exploration of the orbital contents. If greater access is required, the external rectus muscle can be divided and later united. After removal of the tumor, the bone is rotated into place, the periosteum is sutured, and the skin incision is sewed in the usual manner.

For *orbital decompression*, Naffziger and Jones have described an *intracranial approach* to the orbit. The operation gives adequate space for such conditions as pro-

gressive exophthalmos In this procedure bilateral frontal flaps are resected, the dura is elevated over the frontal lobe and the roof of the orbit is removed together with the superior portion of the optic foramen The projection of the frontal and the ethmoidal sinuses into the orbital plate should be determined preoperatively by means of roentgenograms Any orbital contents under pressure bulge through the newly made opening in the bone The orbital fascia is also opened This approach has been utilized in operative procedures involving the retro ocular space

EYEBALL

The eyeball is situated in the anterior part of the orbit nearer the roof than the floor and somewhat closer to the outer than the inner wall It is approximately one inch in all diameters Behind it rests upon the capsule of Tenon which forms a socket in which it may move freely and in front it comes in contact with the posterior surface of the eyelid It has least protection on its outer side

Coats and Media The eyeball consists of three coats which enclose three refractive media (Fig. 53) The first coat is fibrous and contains the sclera and the cornea the second is pigmented and contains the choroid the ciliary body and the iris the third coat is nervous and contains the retina The refractive media are the aqueous humor the vitreous humor and the lens

The sclera forms a tough fibrous external capsule which encloses the posterior five sixths of the eyeball and is continuous in front with the cornea Although it is a thick nondistensible membrane it thins out where the optic nerve enters and becomes a sieve-like membrane called the lamina cribrosa Around the entrance of the optic nerve several small openings are seen these permit passage of the ciliary nerves and arteries These arteries arise from the posterior ciliary branches of the

ophthalmic artery The long ciliary branches pass between the choroid and the sclera to supply the iris and the ciliary regions the short ciliary arteries terminate in the choroid The smaller veins come together to form four or five main trunks the venae vorticosae, which perforate the sclera and leave it midway between the cornea and the optic nerve where they drain into the ophthalmic veins Beyond the margin of the cornea the sclera can be seen through the conjunctiva is the "white" of the eye The anterior ciliary arteries pierce the sclera near the corneoscleral junction (Fig. 59)

The cornea is the anterior transparent part of the outer coat of the eyeball, it occupies about one sixth of the circumference of the globe and is continuous with the opaque sclera It has been compared with a little watch glass whose curvature is greater than that of the sclera It has no blood vessels but derives its nutrition from the lymph which circulates in its numerous lymphatic spaces At the corneoscleral junction is an important line known as the limbus In operations on the iris and the lens incisions are made close to it The superficial surface of the cornea is covered by a layer of stratified epithelium that is continuous with the conjunctiva posteriorly it is limited by a posterior elastic membrane (Descemet's membrane) which is covered by a layer of mesothelium this being in contact with the aqueous humor (Fig. 54) At the peripheral margin the fibers of this membrane divide into three groups the innermost fibers turn medially into the iris and form the ligamentum pectinatum iridis which have been referred to as the pillars of the iris, the middle fibers form the site of origin of the ciliary muscle the outermost fibers become continuous with the sclera At the corneoscleral junction a circular venous space is seen this occupies the region of the anterior chamber in the deeper part of the coat It is known as the sinus ven

canal of Schlemm (canal of Schlemm) it communicates with the scleral veins and with the aqueous humor the latter communication taking place through the spaces of Fontana. The cornea is supplied by

been referred to as the iridociliary choroidal tunic or the uveal tract.

The *choroid* extends from the optic nerve to the *ora serrata*, the latter being the jagged edge where the true retina ends.




FIG. 54. Sagittal section through the upper half and the front of the eyeball.

the ophthalmic division of the fifth nerve via surrounding conjunctival and ciliary branches. The 5th nerve gives the warning of an injury or a foreign body in the eye. If this nerve should be injured or divided as in removal of a gasserian ganglion the cornea becomes insensitive, may ulcerate and eventually the eye may be lost.

The second coat of the eyeball is the vascular tunic which consists from behind forward of the choroid, the ciliary body and the iris, all of which are continuous with each other and therefore are often simultaneously affected. This layer has also

Externally the choroid is in contact with the sclera and internally it is attached to the retina. It is the nourishing coat of the eyeball and is composed mainly of blood vessels; its internal layer contains pigment cells which may give rise to melanoma. The vessels in the choroid may be visible in ophthalmoscopic examinations; in the fundus of the eye they produce the red background against which the retinal vessels stand out. The veins of the choroid are external to the arteries and form four or five principal trunks, the *venae vorticosae*.

The *ciliary body* consists of the ciliary muscle and the ciliary processes. The body is triangular on sagittal section and is a continuation of the choroid which it connects to the margin of the iris. The body has been referred to as the 'dangerous area' of the eye since wounds here can involve the iris, the choroid, the retina or the cornea. Inflammation of the body in one eye may be followed by sympathetic ophthalmia involving the ciliary body of the opposite eye. The *ciliary muscle* makes up the outer side of the triangle of the ciliary body and consists of flat bundles of unstriated muscle, the outermost running anteroposteriorly and the inner circularly. The nerve to this muscle originates from the oculomotor. The fibers of the muscle run backward from the corneoscleral junction to the choroid when they contract they pull the choroid forward thus relaxing the suspensory ligament which in turn allows the lens to become more convex. The ciliary muscle therefore is the muscle of accommodation. The *ciliary processes*, about seventy in number, are of the same structure as the rest of the choroid and consist essentially of blood vessels that are forward continuations of those of the choroid. They also have a good deal of pigment and some glandlike structures which according to one theory are supposed to form the aqueous humor.

The *iris* corresponds to the diaphragm of a camera and has a central opening, the *pupil*, which regulates the amount of light to reach the retina. The iris separates the anterior chamber of the eye from the posterior and has been called a 'curtain' which divides the space between the cornea and the lens into anterior and posterior chambers. It is visible through the cornea and the pigment in it determines the color of the individual's eye. It is attached at its periphery to approximately the middle of the anterior surface of the ciliary body and does not arise from the corneoscleral junction but farther back. This fact is

utilized in a number of operations in this region.

The iris is composed of a delicate stroma of connective tissue which contains blood vessels, nerves, pigment cells and two groups of involuntary muscle fibers. The first set of muscle fibers is the circular sphincter group (sphincter pupillae), contraction of which narrows the pupil. The nerve supply is by the oculomotor via the short ciliary nerves. This first set of muscle fibers is approximately 1 mm broad and is situated around the pupillary margin. The second group is a less clearly defined dilator set of muscles (dilator pupillae) which lies near its posterior surface. Its fixed point is at the root of the iris and it is supplied by the sympathetic nerves. In inflammatory lesions that affect the iris (iritis) adhesions may form either in front of the cornea (anterior synechia) or posteriorly to the capsule of the lens (posterior synechia). The vessels to the iris arise from the long and the short anterior ciliary arteries. The nerve supply is derived from the long and the short ciliary nerves.

The *retina* is the expanded termination of the optic nerve that forms the innermost coat of the eye. It should be considered a part of the brain since it arises from a hollow outgrowth of the forebrain. The optic nerve therefore, is a nerve tract that connects one part of the brain with another; it extends forward almost as far as the ciliary processes at which point it ends in an irregular edge known as the *ora serrata*. From this point forward it continues as a thin layer as far as the ciliary processes. This prolongation contains no nerve fibers and is known as the ciliary part of the retina. The retina is attached to the choroid at only two points, the entrance of the optic nerve and the *ora serrata*; this accounts for its easy separation from the choroid. Under normal conditions the retina is transparent and not visible, making the subjacent choroid visible as the red background of the eye.

as seen through the ophthalmoscope (Fig. 55). The point of entrance of the optic nerve is known as the *optic disk* (papilla); this is located a little below and to the medial side of the posterior pole of the

the disk and forms a yellowish circular area that is devoid of blood vessels. In contradistinction to the disk it is the area of "most distinct vision." The macula is from 1 to 2 mm in diameter and has in its




FIG. 55 (A) The right eyeground (B) Horizontal section of the terminal part of the optic nerve and its entrance into the eyeball

eyeball. The normal disk presents a slight central depression, the physiologic cup or excavation, which marks the point of divergence of entering optic nerve fibers and the entry of retinal vessels. At the edge of the disk a variable amount of pigment is normally present. The disk is considered the physiologic "blind spot" of the retina. The *macula lutea* (yellow spot) is found above and to the lateral side of

center a tiny depression called the *fovea centralis*. The *central artery of the retina* is a branch of the ophthalmic entering the optic nerve about 2 cm from the eyeball and running within it as far as the retina, which it enters about the middle of the disk. In the fetus this vessel extends as far as the lens and passes through the vitreous, but previous to birth that portion which is beyond the retina disappears and

remains as the hyaloid canal (Fig 53) After emerging through the disk the central artery divides into superior and inferior branches each of which subdivides into temporal and nasal branches The branches and the central artery are end vessels and if an embolus plugs them sudden blindness results Because of the transparency of the retina these vessels are clearly visible through the ophthalmoscope and afford an ideal opportunity for study The veins follow the same distribution as the arteries, are somewhat broader and empty into the ophthalmic veins that form the cavernous sinus in the retro-orbital region Pulsation is normal in these veins but is not normal in the arteries The retina proper consists essentially of nuclei and processes of three layers of nervous tissue which have been placed one on top of the other and form synapses They have been referred to as the visual cells (rods and cones) the bipolar cells and the ganglion cells

Detachment of the retina results in blindness in the corresponding field of vision Operations have been devised to reattach it One such procedure is the use of small electropunctures that are placed in the sclera This results in adhesions which should bind the previously separated retina to the choroid

The *aqueous humor* (Fig 53) is a clear fluid that occupies the space between the cornea in front and the lens behind The iris divides this space into two chambers the anterior and the posterior The *anterior chamber* is bounded in front by the cornea behind by the iris and opposite the pupil by the anterior part of the lens The *posterior chamber* is situated between the posterior aspect of the iris and the lens The aqueous humor that fills these two chambers should be regarded as the lymph of the eye although its composition is not that of true body lymph since it contains less albumin and does not clot unless pathologically altered The two chambers communicate freely with each other through

the pupil It is believed that the aqueous humor is secreted into the posterior chamber by the ciliary body and then passes through the pupil into the anterior chamber, from which it is drained away by the sinus venosus sclerae (canal of Schlemm) to the anterior ciliary veins

The *vitreous body* is a soft, gelatinous substance that fills the whole of the eyeball behind the lens This jellylike material supports the retina behind and is hollowed in front for the reception of the lens It is enclosed in a delicate and transparent structure called the *hyaloid membrane* which is in contact with the retina but from which it may be readily separated except at the optic disk As this membrane passes anteriorly it becomes thickened and irregular where it receives the ciliary processes that fit into its corresponding furrows At the margin of the lens the membrane divides into a posterior layer, which lines the hollowed anterior aspect of the vitreous body and an anterior layer which is attached to the anterior aspect of the lens The *hyaloid canal* extends from the optic disk through the vitreous as far as the capsule of the lens and is the remnant of a passage for the central artery of the retina that was present in the fetus

The *lens* is a biconvex transparent, colorless body that is situated between the aqueous humor in front and the vitreous humor behind It is in contact with the iris anteriorly and is about one third of an inch in diameter and one fifth of an inch thick A capsule surrounding it is attached to the ciliary processes in the neighborhood of its circumference by the *suspensory ligament* (zonula ciliaris) The latter is derived from the hyaloid membrane Contraction of the ciliary muscle draws the hyaloid membrane forward this relaxes the suspensory ligament resulting in a greater convexity of the anterior surface of the lens The ability of the lens, by virtue of its elastic structure to change its refractive power is known as the *power of*

accommodation Loss of such elasticity is known as *presbyopia*. The lens may be displaced anteriorly into the aqueous chamber from which location it can be removed through a corneal incision, it may be dis-

placed posteriorly into the vitreous chamber usually resulting in *glaucoma*. If the sclera is ruptured the lens can be seen immediately below the conjunctiva. Opacity of the lens results in *cataract* formation.

The *fascia of the bulb* is a reduplication of the orbital fascia that surrounds the posterior two thirds of the eyeball. It sur-




FIG 56 The orbital fascia and its principal parts (Tenon's capsule, check ligaments and muscle sheaths)

placed posteriorly into the vitreous chamber usually resulting in *glaucoma*. If the sclera is ruptured the lens can be seen immediately below the conjunctiva. Opacity of the lens results in *cataract* formation.

ORBITAL FASCIA (TENON'S CAPSULE)

(Fig 56) The *orbital fascia* is a thickened aponeuroticlike connective tissue that suspends the structures of the orbit. It extends from the optic foramen forward to the circumference of the orbit, blends with the periosteum and gives rise to prolongations that ensheath almost every structure contained in the bony orbit. The principal parts of the aponeurosis are the fascia of the bulb (Tenon's capsule),

rounds the optic nerve behind, merges into its sheath and furnishes tubular sheaths to the orbital muscles where they attach to the globe. Anteriorly it is in contact with the outer surface of the sclera; posteriorly it is in relation to the orbital fat. The fascia is important because (1) it forms a partition that divides the orbital cavity into anterior and posterior compartments; (2) it provides a practical joint in which the eyeball moves like the head of a bone; (3) it permits an enucleation of the eye without opening the posterior compartment and therefore lessens the danger of meningeal infection; (4) it acts as a barrier to the spread of infection or hemorrhage between the eyeball and the retroocular space; (5) it is an efficient socket

for a prosthesis (artificial eye) after enucleation of the eyeball

At that point where the lateral and the medial recti perforate the fascia, strong cap-ular expansions spread to the corres-

eyeball or a tenotomy. They are connected to each other by a thickened hammock of fascia that is situated below the eye. This thickened part is known as the suspensory ligament of Lockwood. This band, with




FIG 57 The muscles of the orbit. (A) Viewed from above with the orbital roofs removed. On the right side the orbital fat has been dissected away. (B) Left side lateral view with the muscles intact. (C) Left side, lateral view. The levator palpebrae superioris and the lateral rectus muscles have been severed. The optic nerve has also been cut, revealing the medial rectus muscle.

ponding walls of the orbit. This arrangement checks lateral and medial rotation of the eye; hence the name "check ligaments." These ligaments are of surgical importance because they limit the degree of retraction of the muscles after an enucleation of the

the orbital periosteum aids in the support of the eyeball after excision of the maxilla; therefore it should be identified and preserved. The posterior compartment of the orbit or that part that is behind Tenon's capsule contains the muscles of the eye.

the ophthalmic artery and vein, the nerves of the orbit and fat

MUSCLES

(Fig 57) The muscles of the orbit include the four recti (superior inferior medial and lateral) the two obliqui (superior and inferior) and the levator palpebrae superioris. Six of the seven orbital muscles arise from the margins of the optic foramen each by a single head except the lateral rectus which has two heads. A common tendinous ring is found around the circumference of the optic foramen for the origin of these muscles. The lower inner portion of this ring is known as the *ligament of Zinn*. The four rectus muscles insert into the sclera as at the four points of the compass the tendon of each piercing the *fascia bulbi* (Tenon) as it inserts. They pass forward from their common origin at the tendinous ring to form a cone-like muscular capsule for the optic nerve and posterior half of the eyeball. The lateral rectus pulls the eye laterally (outward) and the medial does the reverse. The actions of the superior and inferior recti however are not so simple. Because of the relationship to the vertical axis and the line of pull the superior rectus does not produce pure upward movement but a combination of upward and medial rotation. In a similar manner the inferior rectus produces a combination of downward and medial rotation. The *superior oblique muscle* arises a little above the upper margin of the optic foramen. It passes to the inner angle of the orbit where it becomes a rounded tendon and then continues through the fibrocartilaginous ring (pulley) that is situated in the trochlear fossa. It then makes a sharp hairpin turn passes beneath the superior rectus and inserts into the outer and posterior part of the globe of the eye either between the superior and lateral recti muscles or under the superior rectus. Contraction of this muscle rotates the eyeball

so as to make the pupil look downward, but in addition to this it produces a certain degree of lateral rotation. Pure downward rotation of the eyeball can be produced only when the superior oblique and the inferior rectus work together. The *inferior oblique muscle* arises from the orbital floor just lateral to the opening of the nasolacrimal canal and inserts either under the lateral rectus or between the lateral and superior recti. Its action makes the pupil look upward and lateral. If it is desired to look straight upward the inferior oblique and the superior rectus must work together. The *levator palpebrae superioris* is situated immediately under the orbital roof. It arises from this roof anterior to the optic foramen and inserts into the upper lid. Its fibers fuse with the orbital septum and the upper border of the superior tarsal plate and skin. Its action is to raise the lid thus working in opposition to the *orbicularis oculi* muscle. The *orbicularis* has been considered the sphincter, and the levator the dilator of the eye.

VESSELS AND NERVES

(Figs 58 59) The *ophthalmic artery* arises from the internal carotid immediately after the latter leaves the cavernous sinus. It passes forward through the optic foramen below and lateral to the optic nerve. In the orbit the artery turns around the lateral side of the nerve crosses directly above it and then travels forward parallel to the nasolacrimal nerve. It ends at the medial angle of the eye by dividing into the supraorbital and supratrochlear branches. The branches of the ophthalmic artery are

The *central artery of the retina* (*arteria centralis retinae*) (Fig 59) arising from the ophthalmic while it still lies below the optic nerve runs in the substance of the nerve to the optic disk where it divides into branches that supply the retina. These are end arteries and can be identified in the living eye with the ophthalmoscope.

The *ciliary arteries* form a posterior and an anterior group. The posterior group ramifies in the choroid coat, two of them, the long posterior ciliary arteries, run forward to the ciliary zone, where they form

in number the superior and the inferior. The *superior ophthalmic vein* accompanies the artery. Beginning at the union of the supratrochlear and supra orbital veins and anastomosing with the anterior facial vein,




FIG 58 The right ophthalmic artery and the optic nerve as seen from above

an anastomotic circle with the anterior ciliaries. The anterior group pierces the sclera near the corneoscleral junction thus forming an arterial ring that supplies branches to the ciliary body and iris.

The *supratrochlear and supra orbital arteries* leave the orbit with the supratrochlear and supra orbital nerves respectively. They supply the superficial tissues of the forehead where they anastomose with branches of the superficial temporal (external carotid) artery.

The ophthalmic artery also gives off muscular and palpebral branches and a branch to the lacrimal gland.

It passes through the superior orbital fissure and ends in the cavernous sinus. The *inferior ophthalmic vein* lies below the optic nerve and one of its branches communicates with the pterygoid plexus via the inferior orbital fissure. The other branches of the ophthalmic vein leave the orbit through the lower part of the superior orbital fissure and terminate by joining the cavernous sinus.

The *orbital nerves* (Fig 58) are the optic (the third, fourth and the sixth, constituting the motor nerves to the eye muscles), and the ophthalmic division of the fifth, which is the sensory supply to the orbit.

The *ophthalmic veins* (Fig 30) are two

The *optic nerve* is about two inches long, and extends from the optic chiasma to the eyeball. In its course it may conveniently be divided into three parts: the intra-cranial (in the cranial cavity), the intra-

orbital (in the orbit), and the intra-ocular (in the eyeball). In the optic foramen the nerve is surrounded by a continuation of the dura, the arachnoid and the pia which accompany it to the posterior aspect of the eyeball. Since the nerve is separated from




FIG. 59. Vessels of the ocular globe (diagrammatic after Leber)

orbital (in the orbit) and the intra-cranial (in the cranial cavity). In the cranial cavity the nerve lies on the front part of the diaphragma sellae and then on the anterior portion of the cavernous sinus. The anterior perforated substance, the olfactory nerve and the anterior cerebral nerve all cross and lie above this nerve. The internal carotid artery is at first below and then becomes lateral to it. The ophthalmic artery arises from the internal carotid inferomedial to the nerve but soon crosses to its lateral

side. In the optic foramen the nerve is surrounded by a continuation of the dura, the arachnoid and the pia which accompany it to the posterior aspect of the eyeball. Since the nerve is separated from the sphenoid air sinus by only a thin plate of bone a retrobulbar neuritis may develop in diseases affecting the sinus. In the orbit the nerve is surrounded by the orbital fat and at the optic foramen it is surrounded by the origin of the ocular muscles. The nasociliary nerve, the ophthalmic artery and the superior ophthalmic vein cross the nerve superiorly from without inward; the nerve to the inferior oblique muscle lies below it. The ciliary ganglion can be located on the outer side

of the nerve, between it and the lateral rectus muscle. Where the nerve enters the eyeball, it is surrounded by the long and the short ciliary nerves (Fig 59). The central artery of the retina arises from the oph

ththalmic artery may become compressed, resulting in an engorgement of all the retinal vessels, diminution of the size of the arteries, and later exudation that produces the condition known as choked disk or papilledema. The




FIG 60 Enucleation of the eyeball (A) division and separation of the conjunctiva, (B) division of the ocular muscles (C) severing the optic nerve, (D) closure of conjunctiva

thalmic artery near the optic foramen and passes forward in the dural sheath of the nerve. With its accompanying vein, it then crosses the subarachnoid space to enter the nerve on its under and inner aspect and runs directly in its substance. The subarachnoid space of the cranial cavity is directly continuous with the subarachnoid space around the optic nerve because of this continuity, an increase of pressure in the intracranial subarachnoid space may be transmitted to the intra orbital space. As a result of this, the central vein and

having spread through the sclerotic and the choroid coats spreads out to form the inner layer of the retina. The muscles of the orbit are supplied by three cranial nerves: the third (oculomotor), the fourth (trochlear) and the sixth (abducent).

The oculomotor nerve (Fig 39) supplies all the muscles of the orbit with the exception of the superior oblique and the lateral rectus. Through the ciliary ganglion it also supplies the sphincter muscle of the nerve pierces the sclera at a point medial to the posterior pole of the eyeball and

iris and the ciliary muscle (the muscle of visual accommodation). If this nerve is involved the following conditions will result: ptosis or drooping of the upper eyelid because of a paralysis of the levator palpebrae superioris; an external strabismus due to unopposed action of the external rectus and inability to turn the eyeball up or down; dilation of the pupil because of paralysis of the sphincter of the pupil; loss of accommodation due to paralysis of the ciliary muscle; and at times a slight prominence of the eyeball because of unopposed action of the superior oblique plus paralysis of all but one rectus muscle. The oculomotor nerve passes forward in the upper part of the lateral wall of the cavernous sinus to the superior orbital fissure and enters the orbit between the two heads of the lateral rectus muscle.

The *trochlear nerve* (Fig. 40) takes a course similar to the oculomotor but lies slightly below and to the lateral side of the third nerve. It enters the orbit at the superior orbital fissure above the muscles and supplies only the superior oblique muscle.

The *abducent nerve* (Fig. 43) lies below the artery as it approaches the superior orbital fissure. Here it enters the orbit between the two heads of the lateral rectus which it supplies.

The *ciliary ganglion* has a sensory supply (nasociliary branch of the ophthalmic nerve), a motor supply (inferior division of the oculomotor nerve) and sympathetic fibers (cavernous plexus on the internal carotid artery). If a local anesthetic is injected into the region of the ciliary ganglion the resulting anesthesia will permit surgery upon the eyeball.

Surgery (Enucleation of the Eyeball) (Fig. 60). The object of enucleation of the eyeball is to remove the eyeball and leave the muscles to coalesce and form a stump upon which the artificial eye may rest and move. As much conjunctiva as possible should be preserved. The lids are retracted by means of a retention specu-




FIG. 61 The external nose

lum and the conjunctiva is grasped in such a way as to form a fold radiating toward the limbus. This fold is divided, as is the remaining conjunctiva in its entire extent adjacent to the limbus. The conjunctiva is separated from the globe beyond the insertion of the ocular muscles. Tenon's capsule is divided over the insertion of one of the muscles and the tendon of that muscle is picked up, drawn away from the eyeball and divided. The other muscles are handled in similar fashion. The eyeball is retracted toward the nose and a pair of curved blunt scissors is passed backward until the optic nerve is encountered. The nerve is divided; the eyeball is delivered from its socket and the oblique muscles are severed near the sclera. After control of hemorrhage the conjunctiva is closed, and the operation is completed.

NOSE

EXTERNAL NOSE

(Fig. 61) The external nose forms a triangular pyramid, its upper angle which connects directly with the forehead is referred to as the *root* and its free angle as the apex or *tip*. The mobile lateral walls of the pyramid expand to form the wing (alae), which are supplied with sebaceous and sweat glands. The *base* of the nose presents two elliptical orifices (*nares*) which are separated from each other by an anteroposterior *septum* called the *columna*. Small stiff hairs (*vibrissae*) found along the margins of the nares arrest the passage

of foreign substances that may be carried in during inspiration. The *dorsum* of the nose is formed by the union of the two lateral surfaces in the midline, and the *bridge* is the upper part of the dorsum

the side of the nose, the alar and the septal branches to the septum and the alae, and the ophthalmic artery which sends branches to the root and the dorsum. The *veins* follow the course of the arteries,




FIG. 62 Paramedian sagittal section through the left nasal fossa, showing the roof, the floor and the nasal septum of the nasal cavity

that is supported by the nasal bones. The skin is thin and lax over the root and the greater part of the dorsum but over the alae it becomes thick and very adherent to the deeper parts. It has a rich blood supply so it is well suited for plastic surgery. Wounds in this region heal well. The skin over the root of the nose is supplied by the nasal branch of the first division of the fifth nerve which also supplies the skin over the alae and the region of the nostrils. The greater part of the side of the nose is supplied by the second division of the fifth nerve and is the seat of painful neuralgia when that trunk is involved. The anatomic fact that the nasal nerve is a branch of the ophthalmic trunk and has intimate connections with the eye explains the lacrimation that follows painful infections about the nostrils. The arteries of the nose are derived from the facial, which supplies

those at the root emptying into the ophthalmic veins and then into the cavernous sinus. Inflammation in this region, such as furunculosis and erysipelas, may travel by means of this communication into the intracranial circulation and send septic emboli into the brain.

INTERNAL NOSE

The nasal cavities are two chambers that are situated one on each side of the median plane. They are especially adapted for detecting odors and warming and filtering the air that passes to the lungs. The cavities communicate in front with the exterior by means of the *anterior nares* and behind with the nasal part of the pharynx by means of the *choanae* (posterior nares) (Fig. 156). Inside the aperture of the nostrils is a slight dilation known as the *estibule*. The nasal cavities are placed




FIG. 63 The lateral wall of the nasal cavity (A) The middle and the inferior meatuses have been labeled but cannot be seen because the middle and the inferior conchae conceal them (B) Portions of the conchae have been removed and the communications with the paranasal sinuses are represented diagrammatically

below the middle part of the anterior cranial fossa and above the mouth being separated from the latter by the palate laterally they are in relation to the orbit and the maxillary antrum. The nasal cavities present a roof a floor a medial wall (septum) a lateral wall and anterior and posterior openings. The roof (Fig. 62) of each

nasal cavity or fossa is about one eighth of an inch in width is horizontal in the middle and slopes in front and behind. The sloping anterior part is formed by the frontal and the nasal bones and the nasal cartilages; the central portion is horizontal and is formed by the cribriform plate of the ethmoid; the sloping posterior part is formed

by the anterior and lower surface of the body of the sphenoid. The interior part corresponds with the slope of the bridge of the nose. The intermediate part is thin and delicate, is perforated by olfactory nerves and ethmoidal vessels and is located immediately beneath the anterior cranial foramen. Fracture of this part may result in meningitis. The posterior sloping part of the sphenoid sinus is located over the posterior aspect of the roof in the body of the sphenoid. Traction on a polyp attached to the roof of the nasal cavity may cause a breaking of this thin wall resulting in a communication with the cranial cavity. Meningoceles that may project through the roof into the nasal cavity have been mistaken for nasal polyps.

The floor of the nasal cavity represents its larger part and is much wider than the roof. It is concave from side to side and its anterior three fourths is formed by the palatine process of the maxilla and the posterior fourth by the horizontal plate of the palatine bone (Fig. 62). The incisive canal is located inferiorly and is pierced by the so-called foramina of Stensen and Scarpa which transmit the nasopalatine nerve. The floor is horizontal and measures about three inches in length from the tip of the nose to the posterior border of the septum. It is about half an inch wide.

The medial wall or septum forms a median vertical partition between the two nasal cavities. It is usually deflected from the median plane thus reducing the size of one nasal cavity and increasing the other. It is formed posteriorly by the vomer, anterosuperiorly by the perpendicular plate of the ethmoid and anteriorly by the septal cartilage. As this cartilage extends backward it fits into the angle between the ethmoid and the vomer. Tiny projections or crests of the palatine, maxillary, frontal, nasal and sphenoid bones form peripheral parts of the bony septum. The mucous membrane of the septum is not particularly adherent. The

olfactory nerve supplies the upper part of the septum, and trigeminal branches are distributed over the entire septal area. These branches include an inferior nasal branch (ophthalmic nerve) and the long sphenopalatine (trigeminopalatine) nerve that arises from the maxillary (sphenopalatine ganglion) (Fig. 65). This nerve travels downward and forward on the septum, its branches passing through the incisive foramen to supply the mucous membrane of the anterior part of the hard palate.

The lateral wall (Fig. 63) reveals three elevations caused by the superior, the middle and the inferior conchae (turbinate bones). Below and lateral to each concha the corresponding nasal passage or meatus is found. Above the superior concha is the *spheno-ethmoidal recess*, a narrow space into which the sphenoid sinus opens. The scroll-shaped conchae project in a more or less horizontal direction from the lateral wall so that their free margins point downward and inward. The superior and the middle conchae arise from the ethmoid bone but the inferior is an independent bone. The lateral nasal wall is formed by the frontal process of the maxilla, lacrimal bone, ethmoid, nasal surface of the maxilla, inferior nasal concha, perpendicular plate of the palatine bone and the medial pterygoid plate of the sphenoid. The *superior concha*, the smallest, is situated on the upper and back part of the lateral wall. Its anterior extremity lies beneath the middle of the cribriform plate of the ethmoid bone. It does not overhang sufficiently to obscure the superior meatus of which it forms the upper boundary. The *middle concha* extends farther than the superior and has free anterior and inferior borders. It reaches as far forward as the anterior extremity of the cribriform plate and overhangs and completely conceals the middle meatus. The *inferior concha* is an independent bone that articulates with the maxilla and the perpendicular plate of the palatine, in this way forming part of the

medial wall of the maxillary sinus. Its overhanging free border covers the inferior meatus and almost reaches the floor of the nasal cavity. Its posterior end lies about 1 cm. in front of the pharyngeal orifice of the auditory (eustachian) tube. This bone may interfere with the introduction of an instrument into the eustachian tube. Its anterior end is about three quarters of an inch behind the orifice of the nostril. Swelling of the inferior concha usually signifies a sinus disease most commonly the antrum since pus from the antrum runs over it and results in inflammatory changes. The posterior end of the concha at times reveals a polypoid growth that fills the surrounding space.

The *superior meatus* is a short narrow fissure in the front of which the posterior ethmoidal cells open. The *middle meatus* is situated below and lateral to the middle concha and cannot be seen unless that concha has been detached or displaced upward. The meatus continues anteriorly to a shallow depression the *atrium* located above the vestibule. On the lateral wall of this meatus appears the *ethmoid bulla* a rounded elevation that is caused by the bulging of the middle ethmoid cells that open immediately above the meatus. The size of the bulla varies with that of the contained cell. Below and in front of the bulla is a groove called the *hiatus semilunaris* whose anterior end leads into the *infundibulum*. The latter is a short passage by means of which the frontal sinus enters the middle meatus. The anterior ethmoidal sinuses may open into the infundibulum or directly into the hiatus. The maxillary sinus opens into the posterior aspect of the hiatus but its orifice is usually hidden by the lower border of the groove. There may be an accessory opening of this sinus into the middle meatus behind the hiatus. The middle ethmoid air cells usually open directly onto the bulla. In summary then it may be stated that the anterior and the middle ethmoid

cells the frontal and the maxillary sinuses and the infundibulum all open into the middle meatus. The *inferior meatus* lies between the inferior concha and the floor of the nose. The *nasolacrimal duct* opens into it under cover of the anterior part of the inferior concha this opening being about three quarters of an inch above the nasal floor. The sphenoidal recess has been referred to as the 'highest meatus' and lies between the superior concha and the roof of the nose. Into this space the sphenoidal sinus opens.

The *cartilages* of the nose (Fig. 64) are five in number: one septal, two upper and two lower. Additional small flakes of cartilage are found in the upper part of the alar but the lower has none. The *septal cartilage* (Fig. 62) is broad and quadrangular with the following attachments: the postero-superior border is attached to the perpendicular lamina of the ethmoid; the postero-inferior to the vomer and the maxilla; the antero-superior to the nasal bone above and the fibrous tissue below; the antero-inferior to the septal process of the lower nasal cartilage. The *upper nasal cartilage* is triangular and has these attachments: superior border to the nasal bone and frontal process of the maxilla; inferior to the lower cartilage; the anterior border is continuous with the septal cartilage above but separated from it by a fissure below. The *lower nasal cartilage* is large and oval and is located above the anterior part of the nostril. It has a septal process that turns backward in the lower part of the septum.

The *anterior aperture* of the nose is pear-shaped and is formed by the nasal bones and the anterior border of the maxilla that ends in the anterior nasal spine. The *posterior nares* (Fig. 156) (choanae) are each bounded laterally by the internal pterygoid lamina; medially by the vomer above by the body of the sphenoid and the ala of the vomer, and below by the horizontal plate of the palate. The *vestibule* of the nose is the dilation inside the nostril that

is lined by a squamous epithelium and from the lower border of which the vibrissae grow, it is bounded above by a ridge that separates it from the atrium, a depressed area in front of the middle meatus which

columnar epithelium that is ciliated in the respiratory portion but nonciliated in the olfactory part. The respiratory part of the nasal mucous membrane enables the air to obtain warmth and moisture in its pas-




FIG. 64 The cartilages of the nose

is in turn bounded by another ridge called the *aggr nasi* (Fig. 63). The latter is formed by the superior turbinate crest on the frontal process of the superior maxilla.

The mucous membrane of the nose is continuous with all the cavities communicating with it. The superior or olfactory portion is thin and less resistant; it covers the cribriform plate of the ethmoid and contains the endings of the olfactory nerves. The respiratory portion is thicker, more vascular, and at times forms a little padlike mass of mucous membrane that is often mistaken for a polyp. The thickness of this membrane, especially over the middle and the inferior conchae, makes nasal cavities and apertures of the nose smaller in the living than they appear in the skeleton. The mucous membrane is lined by

squamous epithelium that is ciliated in the respiratory portion but nonciliated in the olfactory part. The respiratory part of the nasal mucous membrane enables the air to obtain warmth and moisture in its passage through the nose, and it also accounts for the manner in which the nasal cavity becomes occluded in the early stages of a common cold. The membrane is supplied by many glands that are most conspicuous over the lower and back parts of the outer wall and over the posterior and inferior parts of the septum. These glands may hypertrophy and become very active and they are capable of providing a copious watery secretion. When filled with blood the mucous membrane of the nose swells and obliterates the interval between the bone and the septum. If the membrane becomes the seat of chronic inflammation the upper part may become edematous and protrude from the ethmoidal region or from the middle turbinate in the form of polyps. The mucous membrane has been looked




FIG. 65. Vessels and nerves of the nose. (A) blood supply to the lateral wall of the right nasal cavity. (B) nerve supply to the right lateral wall and the septum of the nose.

upon the mucoperiosteum and perichondrium because it is closely adherent to the underlying bone and cartilage by a fibrous layer.

VESSELS AND NERVES

The blood supply of the nasal mucous membrane (Fig. 65A) is derived chiefly from the terminal part of the internal maxillary artery by its largest branch, the sphenopalatine artery. This vessel enters the nasal cavity through the sphenopalatine foramen and, after supplying branches to the lateral wall, travels downward and forward on the septum, accompanied by its corresponding nerve. An additional blood supply is provided by the ophthalmic artery through its anterior and posterior ethmoidal branches. The veins accompany the arteries and form a rich network beneath

the mucous membrane, especially in the region of the middle and the inferior conchae. The ethmoidal veins drain into the superior sagittal sinus. The nasal veins drain into the ophthalmic veins and then into the cavernous sinuses. In this way, an intracranial and intranasal communication is made, explaining the danger of an infected process in the nose that may extend to the meninges and the brain.

The lymph drainage is by way of the deep cervical glands, following the path of the internal jugular vein.

The nerves (Fig. 65B) associated with the nasal cavities are derived from two sources: (1) the olfactory nerves, which pass through the openings in the cribriform plate of the ethmoid and supply the mucous membrane of the upper third

(olfactory portion) of the nasal cavities these are nonmedullated fibers and pass to the olfactory bulb (2) the *sensory nerves* for the nasal cavity which arise from the ophthalmic branch of the trigeminal. The ophthalmic nerve, by means of its *anterior ethmoidal branch* gives off a branch to the septum which runs downward on the inner surface of the nasal bone over the atrium and the middle meatus. It supplies the mucous membrane in this region and the cutaneous lining of the vestibular part, and appears between the nasal bones and the upper nasal cartilages to supply the skin. The *maxillary nerve* also aids in the sensation of this part of the respiratory tract via the sphenopalatine ganglion.

PRACTICAL CONSIDERATIONS

FRACTURES RHINOSCOPY EPISTAXIS POLYPI AND SEPTAL DEFORMITIES

In nasal fractures the nasal bones are frequently broken by direct violence. The fracture most commonly found is through the lower third of the bones where they are thinnest and least supported. Since there is no muscle pull the deformity that occurs is entirely due to the direction of the force. If the mucous membrane of the nose is torn there might be an associated emphysema. Union takes place with great rapidity.

Anterior rhinoscopy is achieved by means of a light from a forehead mirror or lamp shining through a speculum introduced into the anterior cartilaginous part of the nose. The structures that may be seen and examined through this view are the inferior meatus, the anterior end of the inferior and the middle turbinates and the septum. The superior turbinate does not protrude far enough to be visualized.

Posterior rhinoscopy is accomplished by passing a small mirror over the tongue and behind the soft palate into the pharynx. Reflected light is used and the following structures are seen: the posterior nares, the septum, the middle turbinate, part of the superior and the inferior turbi-

nates, part of the inferior meatus, the middle meatus, the eustachian tube, the mucous membrane of the roof and the upper part of the nasopharynx.

The vascularity of the nose is great and trauma frequent, which explains the frequency of nose bleeds (epistaxis) although many other causes exist. If the bleeding originates from the anterior portion of the septum, as it most frequently does, it may be stopped by pressure through the anterior nares. Packing of the posterior nares is accomplished by passing a soft rubber catheter into the nostril until it appears in the pharynx where it is grasped and drawn out through the mouth. A strong ligature is then attached to the tip of the catheter and a pledget of gauze to the other end of the ligature about one foot from the tip of the catheter. Both catheter and ligature are then withdrawn from the nostrils. The silk ligature is drawn out of the nostril and traction put upon it so that the gauze pack is forcibly applied to the bleeding area in the posterior region. This traction can be maintained by tying the ligature over a pledget of gauze at the nostril. A second ligature can be attached to the posterior pledget and this is left hanging out of the mouth so that removal of the pack can be accomplished by traction on the second ligature. These ligature ends may be placed over the ear for convenience.

Polypi have a predilection for the nasal fossae and may block the nostrils, thus interfering with respiration. They may press outward, widen the nose and project through the anterior or posterior nares. If the nasal duct is pressed upon by a growth in the nose epiphora or tearing may be an early symptom. Polypi have been known to press on the palate and encroach upon the mouth. Their removal can be accomplished by grasping the polyp in a forceps, applying a snare wire about its base and dividing it. Very often polypi are the result of disease of the bone and then require procedures that include removal of the bone or drainage of the sinus.




FIG 66 Submucous resection for the correction of a deviated septum

Deformities of the septum (Fig 66) to some degree are the rule rather than the exception among civilized people. Only in a small proportion are symptoms present that require correction. Submucous resection is now the accepted procedure. The incision is usually convex forward and should be so placed that a sufficient piece of cartilage is left in front to support the tip of the nose. A suitable elevator is then inserted between the mucoperichondrium and the cartilage and the former carefully is lifted over the whole extent of the cartilaginous deviation. The necessary part and amount of cartilage is then removed. The

flaps are allowed to fall together and packing is inserted into each nasal cavity. This insures apposition of the raw surfaces.

PARANASAL SINUSES

(Figs 67, 68, 69) The *paranasal sinuses* are irregular air spaces or diverticula originating from buds of mucous membrane that sprout from the nasal cavities and grow into the diploic layer of certain bones. Each sinus takes its name from the bone in which it is situated: maxillary (antrum of Highmore), frontal, ethmoid, and sphenoid. These sinuses are enclosed in compact bone, communicate with the

nasal cavities with which their mucous membranes are continuous and are filled with air. They communicate with the nasal cavities by means of narrow orifices that may become occluded because of congested mucous membrane. Like the mucous

month of intra uterine life it continues to grow in the adult, acquiring its maximum development in the second or the third decade. The sinus varies considerably in size in different individuals, but the following have been given as the average dimensions




FIG 67 The paranasal sinuses (A) surface projection of the sinuses (B) sagittal section (semidiagrammatic), showing the four paranasal sinuses

lining of the nose the membrane lining the sinuses is covered with ciliated epithelium. The anatomy of the paranasal sinuses is somewhat inconstant since there is no definite constancy in their size, shape and type. Under normal conditions during respiration there is an interchange of air between them.

MAXILLARY SINUS

The *maxillary sinus* (antrum of Highmore) is the largest of the paranasal sinuses and is the first to appear. Although it begins to develop about the fourth

anteroposterior, one and a quarter inches, transverse one inch, vertical, one and a half inches. Situated in the interior of the superior maxilla the base of this pyramidal cavity is formed by the lateral wall of the nasal cavity and the apex extends to the zygomatic process; its roof is formed by the orbital wall which is frequently ridged by the infra orbital canal, and its floor by the alveolar process. In front the pyramid is bounded by the facial surface of the superior maxilla and behind by the zygomatic surface of the same bone. This sinus lies lateral to the lower half of




FIG 68 Normal X ray appearance of the paranasal sinuses in a lateral projection (1) frontal sinuses (2) ethmoid cells (3) sphenoid sinus (4) maxillary sinuses (5) anterior clinoid processes of the sella turcica (6) posterior clinoid processes of the sella turcica (7) sella turcica

the nasal cavity in front of the pterygo palatine and the infratemporal fossae below the orbit and above the molar teeth. The infra orbital nerves and vessels lie in the roof of the sinus and their branches to the incisor the canine and the premolar teeth descend in the anterolateral wall. This nerve produces infra orbital facial pain when the maxillary sinus is diseased. The floor formed by the alveolar margin is about half an inch below the nose and in it are seen elevations produced by the roots of some of the upper teeth the most usual being the first and the second molars



FIG 69 X ray projection for the upper half of the orbit showing an effusion in the right maxillary and the frontal sinuses. These should be compared with the normal sinuses on the left side (1) right frontal sinus obliterated by effusion (2) left frontal sinus normal appearance (3) roof of the orbit (4) lesser wing of the sphenoid (5) sphenoidal fissure (6) greater wing of the sphenoid (7) right maxillary sinus, obliterated by effusion (8) left maxillary sinus normal appearance (9) zygoma

It is possible that all true maxillary teeth (canine to the wisdom) may be in relation to it. At times the roots actually project into the sinus but as a rule they produce a bulge into the floor and are separated from the cavity by a thin layer of spongy bone. This relationship between teeth and sinus explains the production of maxillary disease by infected teeth and also the establishment of drainage for an empyema of the sinus by removal of one of these teeth. The floor of the sinus is not smooth, since it prevents incomplete septa that form pockets in which inflammatory products may stagnate. Such pockets may be inaccessible to treatment and must be handled individually. The nerves and the vessels to the molar teeth descend in the lower part of the posterior wall of




FIG 70 Surgery of the maxillary sinus (A) via the natural opening, (B) through the naso antral wall, (C) the outer oral wall approach, (D) dental approaches

the antrum. The sinus drains into the infundibulum of the middle meatus of the nose by means of a maxillary ostium, this opening varies from a tiny slit to a complete replacement of the floor of the infundibulum. The maxillary sinus is more fre-

quently the site of disease than are any of the other accessory sinuses (Fig 69). Infection may take place through the upper molar alveoli and by way of the nose. Tumors of the antrum are not too uncommon hence knowledge of the surrounding

atomy is important. A malignant tumor may grow rapidly and by pressure upward can encroach upon the eyeball. Growth downward may involve the palate and loosen the teeth. Inward extension would obstruct the nostril and backward involvement would invade the pharynx. Such growths should be treated by excision of the superior maxilla.

Surgery (11, 70) Acute nasal infections that are severe or have a tendency to persist may extend to the maxillary sinus as well as to any of the other sinuses. Carious teeth projecting into the sinus cavity may also be the cause of such infections or extension from adjacent sinuses (frontal, sphenoid and ethmoid) can be the inciting agent. If pus is present in the maxillary sinus it may be visible at the middle meatus.

Of all the nasal sinuses the maxillary is the easiest to irrigate. This can be done by one of four methods: by entering the natural opening (ostium) or by perforating the nasotransverse wall directly beneath the inferior turbinate. Since the natural opening is placed at too high a level for pus to escape it may remain stagnant. If therefore becomes necessary to explore or drain the antrum via another route. A needle is introduced through the nostril and is passed outward and backward. It pierces the bone under cover of the inferior turbinate (inferior nasal concha) and enters the sinus at a much lower level than the natural orifice of the cavity.

The sinus may also be entered through the region of a tooth which is at fault after that tooth has been extracted and a hole drilled upward through its socket and into the sinus. This dental approach was used for many years in empyema of the antrum but unfortunately infections recurred from the mouth. This plus insufficient drainage has resulted in its being discarded by some authorities.

Another approach to the maxillary sinus—by many believed to be the best—is that

which passes through the outer oral wall. The head is turned to the sound side and the lip is retracted upward and backward. An incision is made over the roots of the teeth from the canine to the second molar, and the periosteum is divided in the same line and separated from the bone. The facial wall of the antrum is opened by means of a small chisel and the interior is curetted. Drainage into the nares may be instituted by removing the anterior part of the inferior turbinate.

FRONTAL SINUSES

The *frontal sinuses* bilaterally placed cavities of variable extent situated anteriorly between the two plates of the frontal bone have been considered as extensions of the anterior ethmoid cells. The anterior wall of each sinus is responsible for the prominence of the forehead which is situated above the eyebrow. Although not present at birth and not usually recognizable until the seventh year of life this sinus may appear as early as the age of two years. It is separated from its fellow by a complete bony septum which is often deviated to one side so that one sinus is larger. The septum thins as the sinuses grow and at times may even disappear by absorption. This sinus is about one inch in both height and width but may be much wider and considerably higher and has been known to extend backward between the two tables of the roof of the orbit. In its peripheral parts there are small partitions that form loculae and produce an irregular outline. The sinus presents a posterosuperior wall, an anterior wall and a floor. The posterosuperior wall is thin, contains no diploe and separates the sinus from the meninges and the frontal convolutions of the brain. The anterior wall looks onto the forehead and contains diploe. Because of the presence of these diploe infectious processes involving the bone (osteomyelitis) spread more readily in this wall than in the posterior

The floor in the frontal sinus separates it from the orbit, the nose and the anterior ethmoid sinuses. The sinus opens into the nose via the infundibulum a narrow canal that passes between the anterior ethmoid air cells. The sinus then opens into the hiatus semilunaris (Fig 63). Due to the close relationship of sinuses and their openings an infection in one sinus can and usually does spread to another. It is not uncommon therefore for an opening of the maxillary sinus to receive pus from the frontal and the anterior ethmoid cells as it travels along the hiatus semilunaris. The maxillary sinus thus becomes involved and produces its usual symptoms which may divert attention from the true source of the infection (frontal or anterior ethmoid sinus disease). A fracture over the frontal sinus can be depressed without injuring the cranial contents but such fracture may be associated with emphysema of the surrounding tissues due to communication with the nose. Inflammation of the mucous lining of the frontal sinus may be secondary to an infection in the nose conversely when pus forms within this sinus it may drain into the nasal fossa. If the communication with the nose is blocked because of swelling of the lining membrane, it may give rise to serious complications by destroying the internal table and infecting the cranial contents; it may even perforate the wall of the orbit and produce serious eye complications. An early diagnosis of the presence of pus in the frontal sinus calls for opening into the sinus by trephining over the supra orbital margin.

Extranasal and Intranasal Approaches

Interference with the normal ventilation or drainage of the frontal sinus is usually associated with marked edema in the region of the middle meatus and the middle turbinate becomes tightly compressed against the lateral wall. A deviation of the nasal septum also aggravates the condition and if the inflammatory process becomes purulent, empyema of the sinus results.

When the frontal duct is open, pus passing along the semilunar hiatus may involve the opening of the maxillary sinus and produce a sinusitis here. Since the anterior ethmoidal cells open with the frontal duct into the infundibulum of the semilunar hiatus these cells too may become involved in frontal sinus disease. Osteomyelitis or abscess of the frontal bone may result and can terminate in meningitis.

An *intranasal operation for sinus disease* is utilized by some and is described under surgery of the ethmoid cells (p 104).

The *extranasal* or external approach is usually performed in the following way (Fig 71) the eyebrow is shaved and an incision is made beginning at the temporal end extending to the middle of the root of the nose and then curving downward to the base of the nasal bone. The soft parts are freed from the bone and then two incisions are made in the periosteum. The first is placed just above and parallel with the supra orbital margin the second passes over the frontal process of the maxillary bone. These two incisions do not meet. The frontal sinus is opened thoroughly, curetted and its floor removed. The frontal process of the frontal bone and as much of the lacrimal bone as is necessary are removed through the second incision. This gives access to the ethmoid cells and the ethmoid sinus is curetted. The operation also permits access to the anterior wall of the sphenoid sinus. Drainage is instituted by means of a tube that is placed in the upper wound, carried under the bridge of the bone through the nose and out at the nostril.

SPHENOID SINUS

The *sphenoid sinus* a large cavity situated in the body of the sphenoid bone, is divided into right and left halves by a complete bony septum usually bent to one side (Fig 67). Each half has been referred to as a sphenoid sinus and each has its own opening. The sinus may be limited to the anterior part of the bone but usually occu




FIG 71 Extranasal approach to a diseased frontal sinus

pies the whole of its body extending into the wings of the sphenoid the pterygoid process and even into the basilar process of the occipital bone. Formation of the sinus begins in the fifth month of intra uterine life as a recess of the nasal cavity, but does not extend into the body of the sphenoid until the seventh year. Both sinuses have important relationships above, below, in front and laterally. Above the sphenoid sinus the pituitary body and the optic nerve are found the nerve at times forming a ridge inside the sinus. This close relationship causes the optic nerve

to be involved in sphenoid sinusitis giving rise to sudden loss of vision (retro bulbar neuritis). The sinus is bounded below by the nose. In front the wall of the sinus separates it from the ethmoid air cells and laterally the cavernous sinuses containing the internal carotid artery and the sixth nerve are located. The abducens, the oculomotor and the trochlear nerves and the ophthalmic and the maxillary divisions of the trigeminal nerve may be involved in disease of the sphenoid sinus which is considered a "danger spot" in the skull because of these important sur-

rounding structures. Each half of the sinus has an orifice of its own that opens into the highest meatus, the sphenoid ethmoid recess.

Surgery The sphenoid sinuses may be drained by an external route as described

ETHMOID SINUSES (CELLS)

There are from eight to ten very thin walled intercommunicating cavities occupying the greater part of the ethmoid labyrinth and known as the *ethmoid sinuses*. The boundaries of these sinuses are com-




FIG 72 Surgery of the sphenoid and ethmoid sinuses (A) nasal approach to the ethmoid sinuses (cells) (B) nasal approach to the sphenoid sinus

in operations involving the frontal sinuses or through a nasal route (Fig 72B). In the *nasal route* the posterior half of the middle turbinate is removed and a small hook or curette is introduced upon the anterior superior wall of the nasal cavity. The point of this curette is carried downward and then turned forward and outward toward the eye of the involved side. It is firmly pressed into the posterior ethmoid labyrinth and then drawn forward and downward. The posterior wall of the labyrinth is entirely broken down. The sphenoid sinus is located entered, and its anterior wall removed.

pleted by the frontal, the palatine, the sphenoid bones and the superior maxilla. They have been arbitrarily divided into three sets: anterior, middle, and posterior. The anterior ethmoid sinuses open into the middle meatus on the floor of the hiatus semilunaris; the middle ethmoid sinuses open into the middle meatus on the surface of the bulla ethmoidalis; the posterior into the superior meatus. Above the ethmoid sinuses are the meninges and the frontal convolutions in the anterior cranial fossa. In the front is the frontal sinus; behind is the sphenoid; below the nose; and laterally the orbit. The ethmoid cells in each

labyrinth may vary from four large cells to seventeen small ones, the average number being nine. These spaces are separated from their surrounding structures by extremely thin plates of bone (lamina papyracea) because of this infection may spread to the surrounding parts quite readily. This explains why ethmoiditis is the most common cause of orbital cellulitis. The relations of the ethmoid air sinuses to the cranial cavity are more extensive than those of the frontal and sphenoid hence meningitis, subdural abscess, cerebral abscess and sinus thrombosis may complicate ethmoiditis. It should be recalled that the frontal sinus has been considered as one of the anterior ethmoid cells.

Nasal Approach. Acute inflammation of the ethmoid cells at times is associated with acute rhinitis (common cold) and diseases of the frontal and maxillary sinuses. The diseased ethmoid sinus can be opened and drained externally by procedures that have been described for frontal sinus drainage but more frequently the nasal route is used (Fig. 72A). A curette is introduced into the nasal cavity through the vestibule and carried to the anterior attachment of the middle turbinate. This is pressed firmly downward from the orbit and removes the anterior aspect of the turbinate. The curette is carried through the turbinate, the hiatus semilunaris removed and entrance gained to the anterior ethmoid labyrinth. These cells are removed from before backward by the curette usually the entire middle turbinate is removed.

AUDITORY APPARATUS

For the purpose of description the ear is divided into three parts: external, middle and internal.

EXTERNAL EAR

The *external ear* (Fig. 73) is made up of the *auricle* (pinna) and the *external auditory meatus*; its purpose is to collect and convey sound waves to the tympanic membrane (ear drum).




FIG. 73 The external ear

The *auricle* contains a cartilaginous framework that permits it to retain its characteristic form but at its most dependent point, the lobule, the cartilage is replaced by fibrofatty tissue. The *helix* is the outer margin or rim of the auricle that forms the rolled superior and posterior margins and continues into the lobule. On the postero-superior aspect of the helix a small tubercle known as *Darwin's tubercle* is found. The *antihelix* forms a curved ridge that runs somewhat parallel with the helix, ends below in a small tubercle called the *antitragus* and bifurcates above into two limbs that form the boundary of a shallow depression known as the *fossa triangularis*. The *concha* is the centrally placed deep cavity of the auricle; this is divided into an upper and a lower part by a ridge known as the *crus helices*, the upper part lying over *Macewen's triangle*. If a fingertip is placed into this upper part of the concha it will come into contact with a depressed area of bone that forms the floor of Macewen's triangle, which is bounded above by the suprameatal crest. The lower part of the concha leads into the external auditory meatus and is bounded by the *tragus*, which forms a backward projection somewhat semilunar in shape, and partially obscures the opening of the meatus. The *incisura intertragica*, a notch, bounds the tragus inferiorly and separates it from the antitragus. The antihelix forms the posterior boundary of the concha. The




FIG 74 Diagram of a frontal section through the right external the middle and the inner ear (A) external, middle and internal ear, coronal section, (B) enlarged diagram of the middle and the internal ear, with the cochlea cut

skin of the lateral surface of the auricle is supplied by the great auricular nerve over its lower third and the auriculotemporal nerve over its upper two thirds; the medial surface is supplied over its lower third by the great auricular and over its upper two-thirds by the lesser occipital nerves. There are intrinsic and extrinsic ligaments in the auricle: the former maintaining the cartilage in position and the latter attaching the auricle to the temporal bone. There are also intrinsic and extrinsic muscles that are rudimentary and of no practical importance. The small intrinsic muscles are six in number and all are supplied by the facial nerve. The auricle receives its arterial supply from the external carotid by way of the posterior auricular artery behind and the superficial temporal artery in front. Its venous drainage is by means of the superficial temporal veins in front and the external jugular below. The lymph vessels of the ear rarely drain into the retroauricular glands but drain into the mastoid glands which are situated at the tip of the mastoid process where the efferent lymphatics pierce the sternocleidomastoid and enter the deep cervical chain. The external aspect of the auricle drains into the preauricular gland then into the deep cervical chain.

The *external auditory meatus* (Fig 74) is a canal that extends from the concha to the tympanic membrane: it is about one and a quarter inches long: the first half being cartilaginous and the remainder osseous. On looking into this tube its entire length cannot be visualized because its floor rises for a short distance and then recedes: in its midportion there is a slight backward and inward curve. The lower wall of the canal is longer than its upper and it is narrowest about its middle. If examination of the external auditory meatus is desired it is necessary to straighten out its tortuous course by pulling upward and backward on the auricle. The skin of

the cartilaginous portion is supplied with hair follicles and sebaceous and ceruminous glands. Since it is firmly bound down to the perichondrium and periosteum infections of the canal give rise to severe pain but little swelling. The cutaneous nerve supply to this region is derived from the auriculotemporal nerve and the auricular branch of the vagus nerve.

The meatus has superior, anterior and posterior relationships. The *superior wall* is separated from the middle cranial fossa by a thin plate of bone: hence suppuration in the meatus may penetrate this bone and cause meningitis. The *anterior wall* is in relation to the parotid gland and abscesses of this gland can extend into the meatus. The lower jaw also lies in front of the canal so that injuries such as falls upon the chin may fracture this wall and produce hemorrhage from the meatus which may be confused with bleeding from the ear as seen in basal skull fracture. The *posterior wall* is bony and separates the meatus from the mastoid cells: pus from these cells may discharge into it.

TYMpanic MEMBRANE

The *tympanic membrane* (ear drum) separates the external and the middle ears and consists of outer (cutaneous), inner (mucous) and intermediate (fibrous) layers. The cutaneous layer is continuous with the skin of the external auditory canal, and the inner mucous membrane is continuous with the lining of the tympanic cavity.

The tympanic membrane forms the lateral protecting wall of the tympanic cavity and transmits the vibrations of sound waves along the auditory ossicles to the labyrinth. It is placed obliquely so that its outer or lateral surface faces downward, forward and laterally, forming an angle of about 45° with the floor of the meatus (Fig 74). As a result of this obliquity, the floor and the anterior wall of the mea-




FIG 75 The right tympanic membrane (ear drum)

tus are longer than the roof and the posterior wall. The membrane bulges into the middle ear; hence its lateral surface is concave. The deepest part of this concavity is called the *umbo* and corresponds to the tip of the handle of the malleus.

Otoscopic Examination On otoscopic examination a healthy tympanic membrane is of a pearly gray color (Fig 75). Its circumference, except in the upper part, is somewhat thickened and fits into a groove in the temporal bone. The unattached upper part of the circumference measures about 5 mm and forms a "gap" known as the *tympanic notch* or *incisura*. Over this area the membrane has no strong fibrous partition but is merely represented by the continuation of the covering of the auditory canal which overlies the mucosa lining the tympanic cavity. The upper part of the membrane, therefore, is thin and loose and is called the *pars flaccida* or *Shrapnell's membrane*. From the umbo the handle of the malleus can be seen through the membrane running upward and forward to the periphery.

When the tympanic membrane is examined by reflected light the "cone of light" is seen which has its apex at the umbo and extends downward and forward to the periphery. This luminous triangle undergoes changes in diseases of the ear. A rather

constant landmark is a small bulge that lies in the anterosuperior region and is known as the *malleolar prominence*, from this anterior and posterior malleolar folds emerge, forming the boundaries for the flaccid portion of the membrane.

The handle of the malleus runs from the malleolar prominence downward and backward as far as the umbo. The long crus of the incus, although lying on a deeper plane, can be seen lying behind and parallel to the handle of the malleus. The chorda tympani passes across the upper portion of the membrane. The ear drum is divided into four quadrants by two imaginary oblique lines, one is drawn downward and backward along the line of the handle of the malleus, the other at right angles to the first, downward and forward through the umbo. In this way two superior and two inferior quadrants are developed.

The membrane is normally held taut by the tensor tympani muscle. If the membrane ruptures from violent pressure, it usually gives way at the antero-inferior quadrant or in the region of the malleus. Perforations of the inferior quadrants are usually caused by otitis media. Since the largest blood vessels are found in the region of the handle of the malleus, redness is most frequently seen here. The ear drum is supplied by two nerves: the auriculo-temporal, which supplies its anterior half, and the auricular branch of the vagus, which supplies the posterior half.

Myringotomy The incision of the drum membrane (*myringotomy*) (Fig 76) should be made under direct vision. It starts at the bottom and follows the periphery of the drum backward and upward. Starting at six o'clock it passes through seven, eight, nine, ten and stops at eleven o'clock, thus avoiding important structures and providing adequate drainage. At its starting point such an incision avoids an abnormal jugular bulb and at its upper end avoids the incudostapedial articulation and the chorda tympani.

MIDDLE EAR

The middle ear (*tympenic cavity*) (Fig 77) an air space in the petrous portion of the temporal bone is lined by mucous membrane and contains the auditory ossicles (malleus, incus and stapes) which

it from the middle cranial fossa and the temporal lobe of the brain. The floor is narrow and consists of thin bone separating the tympanic cavity from the jugular fossa. The lateral wall is formed mainly by the tympanic membrane, which does



FIG 76 Paracentesis of the right tympanic membrane (myringotomy). The incision extends between six and eleven o'clock.

transmit sound vibrations from the tympanic membrane to the internal ear. The tympanic cavity is about a half inch in length and height and about one tenth to one sixth of an inch wide. Its upper most part the *epitympanic recess* or attic lies above the level of the tympanic membrane and contains the head of the malleus and the body of the incus. In the walls of this recess are found several small compartments that may harbor infections which become chronic because of inadequate drainage. The roof of the epitympanic recess is a thin plate of bone called the *tegmen tympani* which separates the recess from the middle cranial fossa.

The middle ear has a roof a floor and four walls lateral medial anterior and posterior. The roof is formed by the *tegmen tympani* a thin plate of bone separating

not reach the roof of the cavity the upper part of this wall being formed by the squamous portion of the temporal bone.

The medial wall (Fig 74) separates the tympanic cavity from the internal ear and presents the following: the *foramen ovale* (*fenestra vestibuli*), which leads into the vestibule and is occupied by the base of the stapes; the *promontory*, a rounded projection formed by the first turn of the cochlea and placed below the foramen ovale; the *foramen rotundum* (*fenestra cochlea*) lying at the bottom of a funnel shaped depression that is situated behind the promontory, and being closed by a membrane known as the secondary tympanic membrane which covers an aperture in the bone leading to the *scala tympani* of the cochlea, and, finally, the *prominence of the facial canal* produced by the




FIG 77 Sagittal section of right tympanic cavity (middle ear) viewed from within

facial nerve running backward along the upper part of the medial wall then turning downward in the medial wall of the aditus.

The anterior wall opens directly into the auditory (Eustachian) tube. This tube runs downward forward and medially into the nasopharynx except in children where the direction of the tube is practically horizontal. The middle ear is most commonly infected by microorganisms which pass along the Eustachian tube from an infected nasopharynx. Above the tube lodges the tensor tympani muscle and the bone to its medial side makes up the lateral wall of the carotid canal.

The posterior wall presents a large aperture above known as the aditus, this leads to the tympanic antrum. Below this the pyramid is found just behind the foramen ovale and contains the stapedius muscle the tendon of which projects through the apex.

Since the middle ear is frequently diseased its relation to important structures and various paths through which infection may travel becomes important. Infection may result in (1) erosion through the

roof causing meningitis or intracranial abscess (2) involvement through the tympanic floor encroaching upon the internal jugular vein and causing fatal hemorrhage or septic thrombophlebitis (3) erosion of the anterior wall followed by ulceration into the carotid artery with fatal hemorrhage (4) extension to the prominence of the facial canal on the medial wall resulting in permanent facial paralysis (5) involvement of the internal ear with resultant permanent deafness (6) infection of the mastoid antrum and cells (mastoiditis).

The muscles of importance in this region are the tensor tympani and the stapedius. The tensor tympani muscle lies in a small canal above the Eustachian tube taking its origin from the cartilage of this tube. Its tendon bends at right angles around a bony pulley, runs laterally across the cavity of the middle ear and is inserted into the medial side of the manubrium of the malleus. It is innervated by the mandibular nerve (otic ganglion) and its action is indicated by its name. The stapedius muscle is lodged in the pyramid from the apex of which its tendon issues, and is

inserted into the posterior part of the neck of the stapes. This muscle draws the neck of the stapes backward and is innervated by the facial nerve.

Auditory Ossicles (Fig 77) There are three auditory ossicles: malleus, incus and stapes. They form a bony chain across the middle ear, passing from the tympanic membrane to the foramen ovale.

The *malleus* (hammer) has five parts: (1) a head which is the thickened upper part and contains a facet on its posterior surface for articulation with the body of the incus; (2) a neck, which is a constriction below the head; (3) the handle (manubrium) which is a long tapering process passing downward and backward closely attached in its whole extent to the tympanic membrane and continuing backward to the umbo; (4) the lateral process, which arises from the root of the handle and projects laterally; it attaches to the tympanic membrane by the anterior and the posterior malleolar folds that bound the flaccid part of the ear drum; (5) the anterior process, a slender spicule that passes from the neck downward and forward to the squamotympanic fissure.

The *incus*, or anvil, is a bone that has been likened to a two-fanged tooth that has three parts: (1) a body that articulates in front by a funnel-shaped facet with the head of the malleus; (2) the short process attached to the margin of the aditus; (3) the long process which passes downward behind and parallel with the handle of the malleus. The tip projects medially and terminates in the lentiform nodule that articulates with the head of the stapes. The shadow of the long process at times may be seen in the posterior part of the membrane on otoscopic examination.

The *stapes* or stirrup consists of a head that faces laterally and articulates with the lentiform nodule of the incus; the neck, where the tendon of the stapedius is inserted; the limbs that arise from the con-

stricted neck and pass medially to the extremities of the base; the anterior limb being shorter and straighter than the posterior; the base that dips into the foramen ovale is kidney-shaped, the more convex border of the kidney appearing uppermost, and is held firmly in place in the foramen by an annular ligament. The bones are connected by joints lined by synovium and are bound together and secured to the walls of the cavity by the following ligaments: the anterior ligament of the malleus passing between the lateral process and the posterior malleolar fold; the superior ligament of the malleus passing between the head of the malleus and the roof of the tympanic cavity; the posterior ligament of the incus passing between the short process of the incus and the posterior wall of the tympanic cavity; the annular ligament of the stapes connecting the base of the stapes with the apex of the foramen ovale.

The tympanic cavity contains folds of mucous membrane that extend from the inner walls to the ossicles. The continuation of this mucous membrane with that lining the auditory tube, the mastoid antrum and the mastoid air cells explains the ever present danger of pharyngeal infections spreading to the tympanic cavity, ear bones and air spaces.

Tympanic (Mastoid) Antrum The *tympanic antrum* is a large recess situated in the posterior part of the petrous portion of the temporal bone. It is about the size of a small pea and is really a large mastoid air cell (Fig 77). The *aditus* (aditus ad antrum) an oval slit with its long axis nearly vertical and measuring about a quarter of an inch connects the epitympanic recess with the antrum. Any obstruction of this narrow aperture favors stasis and retention of inflammatory exudates that may find their way to the mastoid cells. Both the aditus and the antrum lie just below the tegmen tympani since the aditus opens close to the roof of the

antrum it is not in an efficient place to drain that cavity. The tympanic antrum is relatively larger and more superficial in the child than in the adult. *Superiorly* it has a roof that is the backward continuation of the tegmen tympani and is therefore in close relationship to the middle cranial fossa and the temporal lobe of the brain. Involvement of this wall may cause a subtemporal abscess. Its *anterior* wall has in its upper part an opening which communicates with the epitympanic recess; this opening has been referred to above as the aditus. Its *posterior* wall opens into mastoid air cells and separates the antrum from the sigmoid (transverse) sinus and the cerebellar hemisphere. The *lateral* wall is formed by the squamous part of the temporal bone; is about a half inch thick in the adult; is the wall of surgical approach and projects laterally in that part of the temporal bone that is covered by the auricle.

Above the promontory and even above the fenestra vestibuli is found the *canal for the facial nerve* (aqueduct of Fallopius). This canal contains the facial nerve as it travels in its intrapetrous portion. It also forms a ridge the wall of which is so extremely thin that the nerve may be seen through it. Above the fenestra ovalis the facial canal together with the external semicircular canal form the inner boundary of the aditus. This is an important relationship and should be kept in mind in any operative procedure in this region. At the medial wall of the aditus the facial canal curves downward and opens on the inferior surface of the temporal bone at the stylomastoid foramen.

The *chorda tympani nerve* passes forward between the handle of the malleus and the long process of the incus, reaching a small opening in front of the upper part of the tympanic ring.

The *mastoid process* does not exist at birth but begins its development at the end of the first year. As it grows its diploe is gradually replaced by air cells.

The *mastoid cells* usually occupy the whole of the mastoid process which has a very thin coating of compact bone. In the upper part the cells communicate with the antrum; at the middle of the mastoid process they increase in size. Since the mastoid cells are developed as outgrowths from the mucous membrane of the middle ear and antrum they are lined by the membrane and are filled with air from these cavities. The cells near the apex of the mastoid are smaller and do not communicate with those above; the lowermost cells contain marrow and not air and represent the unaltered diploe of the cranial bones. Infection from the tympanic cavity may invade these cells, spread down the mastoid process and invade the deeper lying cells. If the formation of air cells (pneumatization) is complete the entire mastoid process is composed of these large air spaces; this is known as the pneumatic type of mastoid. If however pneumatization is interfered with so that the cells do not develop, the diploic type of mastoid process results in which the structure resembles the other cranial bones (outer and inner tables with diploe between). When this occurs, the antrum is the only cell present. The sclerotic type of mastoid process is one in which the process is composed of very dense compact bone and is usually the result of a chronic infection that has interfered with the absorption of the diploe and the pneumatization process. It results in an acellular mastoid that is extremely hard.

CLINICAL AND SURGICAL CONSIDERATIONS

MASTOIDITIS SIMPLE AND RADICAL MASTOID SURGERY

In *mastoiditis*, suppurating mastoid cells can involve the lateral sinus. This involvement may be the result of contamination of the small veins that reach the sinus through the bone or by direct infection from a perisinus abscess. From the lateral sinus extension can take place to the internal jugular vein or even to the other side of the skull.




FIG 78 Simple mastoid operation (antrotomy) The two uppermost figures reveal the surgical anatomy in the region to be explored Note the level at which the section is taken in the figure on the right and then shown in cross section in the figure on the left Figures A to E depict the steps in the operation

antrum it is not in an efficient place to drain that cavity. The tympanic antrum is relatively larger and more superficial in the child than in the adult. *Superiorly* it has a roof that is the backward continuation of the tegmen tympani and is, therefore, in close relationship to the middle cranial fossa and the temporal lobe of the brain. Involvement of this wall may cause a subtemporal abscess. Its *anterior* wall has in its upper part an opening which communicates with the epitympanic recess; this opening has been referred to above as the aditus. Its *posterior* wall opens into mastoid air cells and separates the antrum from the sigmoid (transverse) sinus and the cerebellar hemisphere. The *lateral* wall is formed by the squamous part of the temporal bone, is about a half inch thick in the adult, is the wall of surgical approach and projects laterally in that part of the temporal bone that is covered by the auricle.

Above the promontory and even above the fenestra vestibuli is found the canal for the facial nerve (aqueduct of Fallopius). This canal contains the facial nerve as it travels in its intrapetrous portion. It also forms a ridge, the wall of which is so extremely thin that the nerve may be seen through it. Above the fenestra ovalis the facial canal, together with the external semicircular canal, form the inner boundary of the aditus. This is an important relationship and should be kept in mind in any operative procedure in this region. At the medial wall of the aditus the facial canal curves downward and opens on the inferior surface of the temporal bone at the stylomastoid foramen.

The *chorda tympani nerve* passes forward between the handle of the malleus and the long process of the incus, reaching a small opening in front of the upper part of the tympanic ring.

The *mastoid process* does not exist at birth but begins its development at the end of the first year. As it grows, its diploe is gradually replaced by air cells.

The *mastoid cells* usually occupy the whole of the mastoid process, which has a very thin coating of compact bone. In the upper part the cells communicate with the antrum; at the middle of the mastoid process they increase in size. Since the mastoid cells are developed as outgrowths from the mucous membrane of the middle ear and antrum, they are lined by the membrane and are filled with air from these cavities. The cells near the apex of the mastoid are smaller and do not communicate with those above; the lowermost cell contains marrow and not air and represents the unaltered diploe of the cranial bones. Infection from the tympanic cavity may invade these cells, spread down the mastoid process and invade the deepest lying cell. If the formation of air cells (pneumatization) is complete, the entire mastoid process is composed of these large air spaces; this is known as the pneumatic type of mastoid. If, however, pneumatization is interfered with so that the cells do not develop, the diploic type of mastoid process results in which the structure resembles the other cranial bones (outer and inner tables with diploe between). When this occurs, the antrum is the only cell present. The sclerotic type of mastoid process is one in which the process is composed of very dense compact bone and is usually the result of a chronic infection that has interfered with the absorption of the diploe and the pneumatization process. It results in an cellular mastoid that is extremely hard.

CLINICAL AND SURGICAL CONSIDERATIONS

MASTOIDITIS, SIMPLE AND RADICAL MASTOID SURGERY

In *mastoiditis*, suppurating mastoid cells can involve the lateral sinus. This involvement may be the result of contamination of the small veins that reach the sinus through the bone or by direct infection from a perisinus abscess. From the lateral sinus extension can take place to the internal jugular vein or even to the other side of the skull.




FIG 79 The middle and the internal ear seen from above
The inset shows the area of bone removed

INTERNAL EAR

The *internal ear (labyrinth)* is situated in the petrous portion of the temporal bone and is concerned with sound perception orientation and balancing (Figs 79-80). It consists of two labyrinths: a bony labyrinth which contains a membranous one or the greater part, the membranous labyrinth is not in contact with its bony labyrinth but is surrounded by a fluid known as perilymph.

The *bony labyrinth* is about 3 mm thick, is as hard as ivory and consists of the cochlea, the vestibule and the semicircular canals (Fig 80).

The *cochlea* resembles a small shell that makes two and a half turns. It may also be likened to a spiral staircase that makes

its turns around a central pillar called the *modiolus*. The promontory on the medial wall of the tympanic cavity is formed by the first coil of the cochlea. The base of the cochlea passes backward and medially to form part of the floor of the meatus. The apex of the cochlea is directed forward and lateralward. A spiral ledge of bone projects from the modiolus and divides the cochlea into a *scala vestibuli* in front and a *scala tympani* behind (Fig 74). The aqueduct of the cochlea passes from the scala tympani through the petrous bone to the notch at the margin of the jugular foramen. This duct brings the perilymph of the bony labyrinth and the cerebrospinal fluid of the subarachnoid space into communication. The cochlea

by way of the confluence of sinuses. Mastoid disease may extend upward through the roof of the antrum, involve the brain and the meninges and result in meningitis extradural or brain abscesses.

Mastoiditis usually follows an acute disease of the tympanic cavity because of the mucous membrane continuity. Once the mastoid cells have become involved the infection may spread in one of many ways, traveling either to the transverse sinus or to the meninges and brain. The facial nerve may become involved or the cortex of the mastoid process itself might be perforated.

In performing a simple mastoid operation (*mastoidectomy or antrotomy*) it is possible to injure vital structures (Fig. 78). If the opening in the antrum extends too far upward the middle cranial fossa may be opened; if too far backward the transverse sinus is entered and if the opening is placed too deep the facial nerve may be injured. In doing this operation an incision is made about half an inch posterior and parallel to the insertion of the auricle. Separation of the soft parts from the bone subperiosteally is carried anteriorly to the posterior margin of the auditory canal superiorly and anteriorly to the suprameatal spine and posteriorly far enough to expose the mastoid process. Chiseling is begun in an angle formed by the temporal line above and the posterior bony wall of the canal in front. The chisel should always chip in a direction parallel with the auditory meatus. After the antrum is opened it is explored and the opening enlarged as desired. The diseased cells and carious bone are removed. The wound is irrigated, dried and packed. Closure with drainage follows.

The *radical mastoid operation* converts the mastoid antrum, the cells and the middle ear into a single cavity and all the ossicles except the stapes are removed.

Auditory (Pharyngotympanic Eustachian) Tube. The *pharyngotympanic tube* is an osseocartilaginous tube about one and a half inches long which connects the tym-

panic cavity with the nasopharynx (Fig. 74). The posterior third is bony, and the anterior two thirds partly cartilaginous and partly fibrous. The mucous membrane lining the tube is continuous with that of the middle ear and the pharynx. Through this tube the air pressure on both sides of the ear drum is equalized; should the tube become obstructed by edema, etc., air cannot enter and a negative pressure results in the tympanic cavity. With the atmospheric pressure on the outer side of the drum the membrane retracts into the cavity and a sensation of fullness in the ear results. The course of the tube is downward medially and forward from the tympanic cavity. Its narrowest part, the isthmus, lying at the junction of the cartilaginous and bony parts. The cartilaginous portion opens from the lateral wall of the nasal fossa close to the pharyngeal opening and presents medial and lateral wall which lie so close together that only a slitlike cavity results. The bony part of the tube is in relation superiorly to the canal of the tensor tympani muscle anterolaterally to the petrotympanic fissure and posteromedially to the carotid canal and its contents (Fig. 77). Normally the pharyngeal orifice is closed, during swallowing and yawning it opens by means of the action of the tensor veli palatini muscle. The tympanic orifice is located in the anterior wall of the tympanic cavity below the canal for the tensor tympani muscle.

Inflation of the middle ear may be accomplished by Valsalva's method. The patient closes the mouth and the nose and forcibly blows out the cheeks. This drives air through the auditory tube, a sense of fullness is felt in the ears and hearing is diminished because of the resulting distention of the tympanic membrane. The same may be accomplished by the Politzer method where the nozzle of a Politzer bag is inserted into the nostril and the nose is closed. The patient then swallows and the bag is compressed, forcing air into the tympanum.

of the vestibule close to the dura mater on the posterior surface of the petrous portion of the temporal bone.

The semicircular ducts are about one third the size of the semicircular canals but in number, shape and form they are

the utricle the semicircular ducts receive the terminal branches of the vestibular nerve. The ducts of the utricle and the saccule are all held in position by numerous fibrous bands which stretch across the space between them and the otic capsule walls.




FIG. 80. The internal ear (labyrinth). (A) lateral view of the right bony labyrinth. (B) interior of the right bony labyrinth. (C) the membranous labyrinth.

similar and each presents an ampulla at one end. They open by five orifices into the utricle, one opening being common to the medial end of the superior duct and the upper end of the posterior duct. With

The various parts of the membranous labyrinth communicate with each other and contain a fluid called endolymph. It represents a closed system and does not communicate with the subarachnoid space.

opens posteriorly into the bony vestibule, which contains the membranous saccule and the utricle.

The *vestibule* is the central part of the bony labyrinth that is situated behind the cochlea in front of the semicircular canals and medial to the tympanic cavity. On its lateral (tympanic) wall is the *fenestra vestibuli* which is closed by the stapes. Medially it communicates with the posterior cranial fossa through the aqueduct of the vestibule. The five openings of the semicircular canals are found in the posterior part of the vestibule. On the lateral wall the secondary tympanic membrane closes the fenestra of the cochlea thus separating the perilymphatic space from the tympanic cavity.

The *three bony semicircular canals* are horseshoe shaped, contain the membranous semicircular ducts and open into the posterior part of the vestibule. They are from 12 to 22 mm in length and each is less than 1 mm in diameter except at one end where they form a bulge known as the *ampulla*. They are named superior, posterior and lateral. The superior is nearly coronal, the posterior nearly sagittal, the lateral nearly horizontal. The anterior part of the lateral canal lies in the medial wall of the *rudus* immediately above the canal for the facial nerve. These three canals open into the vestibule by only five apertures because the medial end of the superior joins the upper end of the posterior forming a single canal known as the *common crus*.

The *membranous labyrinth* lies within the bony labyrinth and consists of sacs that contain a fluid known as *endolymph* (Fig. 80C). It has the same general form as has the bony labyrinth, but is somewhat smaller and is separated from the bony walls by a fluid known as *perilymph*. It differs in form slightly from the bony labyrinth in the region of the osseous vestibule where the membranous labyrinth consists of two membranous sacs, the utricle and the saccule. This labyrinth con-

sists of the cochlear duct, the saccule and the utricle and three semicircular ducts.

The *cochlear duct* contains the spiral organ of Corti, which is the essential part of the organ of hearing. The membranous cochlea is a membranous tube which consists of three parts: scala tympani, scala vestibuli and duct of the cochlea. The latter contains the spiral organ to which the cochlear nerve is distributed. The cochlear duct lies lateral to the scala vestibuli and is separated from it by the *vestibular membrane* which passes from the spiral lamina upward and laterally to the roof of the scala. A triangular section results; this is bounded medially by the vestibular membrane, laterally and above by the lateral wall of the cochlea and below by the basilar lamina. The elongated *spiral ganglion* is situated in a canal that runs around the modiolus at the base of the spiral lamina. The peripheral branches from the ganglion pass to the organ of Corti; the central branches leave the bone through the foramina at the base of the internal auditory meatus and constitute the cochlear part of the auditory nerve. The organ of Corti presents the important functional element in the hearing cells which receive the ending of the cochlear nerve. Posteriorly the duct of the cochlea is connected with the saccule by the *canalis reuniens* and it terminates in a blind cone shaped extremity.

The *utricle* and the *saccule* are two membranous sacs situated in the bony vestibule and indirectly connected to each other. The utricle, the larger of the two sacs, is situated in the posterior and upper parts of the vestibule and receives the apertures of the membranous semicircular canals posteriorly; a narrow duct called the *ductus utriculosaccularis* leaves it. The saccule is smaller and rounder, and the narrow *ductus endolymphaticus* leaves its posterior end to join the ductus utriculosaccularis. The junction of these two ducts ends in a small blind sac called the *sacculus endolymphaticus* which is situated in the aqueduct

of the vestibule close to the dura mater on the posterior surface of the petrous portion of the temporal bone.

The *semicircular ducts* are about one third the size of the semicircular canals but in number, shape and form they are

the utricle the semicircular ducts receive the terminal branches of the vestibular nerve. The ducts the utricle and the saccule are all held in position by numerous fibrous bands which stretch across the space between them and the osseous walls




FIG. 80. The internal ear (labyrinth). (A) lateral view of the right bony labyrinth (B) interior of the right bony labyrinth (C) the membranous labyrinth.

similar, and each presents an ampulla at one end. They open by five orifices into the utricle, one opening being common to the medial end of the superior duct and the upper end of the posterior duct. With

The various parts of the membranous labyrinth communicate with each other and contain a fluid called endolymph. It represents a closed system and does not communicate with the subarachnoid space.

opens posteriorly into the bony vestibule, which contains the membranous saccule and the utricle

The *vestibule* is the central part of the bony labyrinth that is situated behind the cochlea in front of the semicircular canals and medial to the tympanic cavity. On its lateral (tympanic) wall is the *fenestra vestibuli* which is closed by the stapes. Medially it communicates with the posterior cranial fossa through the aqueduct of the vestibule. The five openings of the semicircular canals are found in the posterior part of the vestibule. On the lateral wall the secondary tympanic membrane closes the fenestra of the cochlea thus separating the perilymphatic space from the tympanic cavity.

The *three bony semicircular canals* are horseshoe shaped, contain the membranous semicircular ducts and open into the posterior part of the vestibule. They are from 12 to 22 mm in length and each is less than 1 mm in diameter except at one end where they form a bulge known as the *ampulla*. They are named superior, posterior and lateral. The superior is nearly coronal, the posterior nearly sagittal, the lateral nearly horizontal. The anterior part of the lateral canal lies in the medial wall of the *aditus* immediately above the canal for the facial nerve. These three canals open into the vestibule by only five apertures because the medial end of the superior joins the upper end of the posterior, forming a single canal known as the *common crus*.

The *membranous labyrinth* lies within the bony labyrinth and consists of sacs that contain a fluid known as *endolymph* (Fig. 80C). It has the same general form as has the bony labyrinth but is somewhat smaller and is separated from the bony walls by a fluid known as *perilymph*. It differs in form slightly from the bony labyrinth in the region of the osseous vestibule where the membranous labyrinth consists of two membranous sacs, the utricle and the saccule. This labyrinth con-

sists of the cochlear duct, the saccule and the utricle and three semicircular ducts.

The *cochlear duct* contains the spiral organ of Corti, which is the essential part of the organ of hearing. The membranous cochlea is a membranous tube which consists of three parts: *scala tympani*, *scala vestibuli* and *duct of the cochlea*. The latter contains the spiral organ to which the cochlear nerve is distributed. The cochlear duct lies lateral to the *scala vestibuli* and is separated from it by the *estibular membrane*, which passes from the spiral lamina upward and laterally to the roof of the *scala*. A triangular section results; this is bounded medially by the vestibular membrane, laterally and above by the lateral wall of the cochlea and below by the basilar lamina. The elongated *spiral ganglion* is situated in a canal that runs around the modiolus at the base of the spiral lamina. The peripheral branches from the ganglion pass to the organ of Corti; the central branches leave the bone through the foramina at the base of the internal auditory meatus and constitute the cochlear part of the auditory nerve. The organ of Corti presents the important functional element in the hearing cells which receive the ending of the cochlear nerve. Posteriorly the duct of the cochlea is connected with the saccule by the *canalis reuniens* and it terminates in a blind cone shaped extremity.

The *utricle* and the *saccule* are two membranous sacs situated in the bony vestibule and indirectly connected to each other. The utricle, the larger of the two sacs, is situated in the posterior and upper parts of the vestibule and receives the apertures of the membranous semicircular canals posteriorly. A narrow duct called the *ductus utriculosaccularis* leaves it. The saccule is smaller and rounder and the narrow *ductus endolymphaticus* leaves its posterior end to join the *ductus utriculosaccularis*. The junction of these two ducts ends in a small blind sac called the *sacculus endolymphaticus* which is situated in the aqueduct

6

Face

EMBRYOLOGY

At the anterior end of the embryo an opening called the stomodeum appears during the latter part of the first month of intra uterine life. The face is formed from five processes surrounding this opening: one frontal, two maxillary and two mandibular processes (Fig 81). The mandibular processes grow medially, fuse and unite in the midline forming the lower jaw or mandible. When a failure of fusion of these processes occurs a fissure of the lower lip results. The fusion of the upper processes converts the single stomodeal orifice into the cheeks, the whole upper lip except the philtrum (the vertical groove in the middle of the upper lip) most of the upper jaw and the palate. The appearance of an olfactory pit divides the frontal process into a medial and two lateral nasal processes. The medial process forms the septum of the nose, the philtrum and premaxilla; the lateral processes form the side of the nose but take no part in the formation of the upper lip. By imperfect fusion various defects result such as harelip, macrostoma, microstoma, cleft palate, etc.

SKIN, BLOOD AND NERVE SUPPLY

The skin of the face is thin, vascular, movable and abundantly supplied with sebaceous and sweat glands. The absence of deep fascia in the anterior aspect of the face permits muscles arising from the bone to be inserted directly into the skin. The glands situated in the skin lie in immediate relationship to the subjacent loose areolar tissue and it is the presence of

this loose tissue, unsupported by deep fascia, that permits the rapid spread of edema. Over the lower part of the nose, however, the skin is firmly bound to the underlying cartilage and inflammations here are extremely painful. The skin over the chin resembles the integument of the scalp in that it is very dense and adherent to the parts beneath.

Because of its mobility and vascularity, the skin of the face is especially adaptable to plastic operations and sound healing. The dangerous area of the face is triangular and bounded by lines that join the root of the nose with the angles of the mouth. The venous drainage from this area enters the angular vein which communicates with the cavernous sinus via the superior ophthalmic vein. Boils or carbuncles therefore in this region may produce a cavernous sinus thrombosis (Fig 30).

The blood supply of the face is free and anastomoses are numerous (Fig 2). The arterioles have a rich supply of sympathetic vasomotor nerves from the superior cervical ganglion and because of this blushing and blanching occur readily in emotional states. The main artery of the face is the *facial (external maxillary)* which is a branch of the external carotid. It appears at the base of the jaw immediately in front of the masseter muscle, passes upward in a tortuous manner toward the angle of the mouth and the side of the nose, and terminates near the inner canthus of the eye where it anastomoses with the nasal branch of the ophthalmic artery. It crosses the lower jaw, the buccinator muscle, the upper jaw and

The acoustic nerve (Fig 79) divides in the internal auditory meatus into two main branches the vestibular and the cochlear. The posterior or vestibular branch supplies the utricle the saccule and the ampullae of the semicircular canals. The inferior or cochlear branch is distributed to the cochlea. The cochlear nerve divides into numerous filaments which pass through foramina which lead to small canals, these canals pass through the modiolus and then radi-

ate laterally between the bony layers of the spiral lamina to the spiral organ of Corti.

For practical purposes all pyogenic involvement of the labyrinth results from middle ear infections. Functional changes in the labyrinth indicate invasion and possible meningeal involvement. Since the labyrinth is so small and the nerve endings so close, diffuse suppuration would destroy them and abolish their activity.

portion of the upper eyelid and then ascends to innervate the skin of the forehead and the scalp as far back as the vertex. It is accompanied by the supra-orbital branch of the ophthalmic artery. (2) The *supratrochlear nerve* emerges about one fingerbreadth from the median plane and supplies the medial part of the upper eyelid and a small area of the forehead above the root of the nose. (3) The *infratrochlear nerve* emerges from the orbit above the medial palpebral ligament and supplies a small area of skin around the upper eyelid and the adjacent part of the nose. (4) The *external nasal nerve* emerges on the face at the lower border of the nasal bone and supplies the skin of the nose as far down as its tip. (5) The *lacrimal nerve* supplies the lateral part of the upper eyelid and the corresponding part of the conjunctiva.

At times a nasociliary division of the ophthalmic nerve is described; it has been referred to in this text as the infratrochlear or the external nasal nerve.

The *maxillary* or second division of the trigeminal nerve has the following branches: (1) The *infra-orbital nerve* a direct continuation of the maxillary emerges from the infra-orbital foramen, passes under cover of the levator labii superioris and is accompanied by a small artery. It divides into terminal branches: the palpebral for the lower lid, nasal for the posterior part of the nose, labial for the upper lip and buccal for the cheek. (2) The *zygomaticofacial nerve* appears through the foramen of the same name as a twig and supplies the skin over the bony prominence of the cheek. (3) The *zygomaticotemporal nerve* pierces through the foramen of the same name, pierces the temporal fascia near the zygomatic bone and supplies the skin of the anterior part of the temple.

The *mandibular* or third division of the trigeminal nerve has three branches which reach the skin: (1) The *mental nerve* emerges through the mental foramen and

is situated deep to the depressor angulorum, it sends its terminal branches to the lower lip, the chin and the skin over the body of the mandible. (2) The buccal nerve appears at the anterior border of the ramus of the jaw below the level of the parotid duct and travels almost to the angle of the mouth. It supplies the skin over the cheek and the branches that pierce the buccinator supply the mucous membrane of the cheek. (3) The *auriculotemporal nerve* is accompanied by the superficial temporal artery and passes under cover of the parotid gland. As its name implies it supplies cutaneous branches to the auricle and the temporal region but it also supplies the modified skin which lines the external auditory meatus and covers the outer surface of the tympanic membrane. The terminal branches on the scalp may reach as high as the vertex.

The mandibular nerve supplies the skin over the lower jaw but extends onto the external ear and upward to the side of the head.

The branches of the fifth nerve which appear on the face communicate with branches of the seventh. For this reason a lesion in the territory of the fifth may cause a reflex spasm involving the facial muscles and producing a so-called *facial tic*. These conditions are best treated by removing the irritating cause but they may require temporary interruption of the reflex arc by crushing the seventh nerve where it leaves the stylomastoid foramen. *Trigeminal neuralgia* is manifested by acute pain in the parts supplied by branches of the fifth nerve and may be due to carious teeth, sinus disease or irritative lesions within the cranium. In some cases of intractable neuralgia where all sources of possible peripheral irritation have been removed it may be necessary either to resect nerves where they leave their bony canals, or inject them with alcohol. If a lesion completely involves the fifth nerve an extensive anesthesia of the same side of the face results which extends exactly to




FIG 81 Embryogenesis of the face (A) before the appearance of the olfactory pit (B) after the appearance of the olfactory pit

the levator anguli oris it is covered superficially by the platysma risorius zygomaticus major and minor and the levator labii superioris. In its lower part the artery rests directly on the mandible and is covered only by skin and the risorius muscle. Leaving the mandible it travels on the surface of the buccinator and a little higher is crossed by the zygomaticus major muscle. In the interval between these two muscles it is covered only by skin and superficial fascia. Its accompanying veins lie behind it on the masseter. The cervical branch of the facial nerve enters the face superficial to the artery. A rich anastomosis occurs between the vessels of the two sides, and an additional anastomosis exists between the facial artery and the arteries which accompany the cutaneous branches of the fifth nerve on the face (ophthalmic and internal maxillary arteries).

The facial artery supplies superior and inferior labial arteries which pass medially in the upper and the lower lips they are situated in the submucous tissue about a quarter of an inch from the mucocutaneous junction, where their pulsations can easily be felt. Each anastomoses with its fellow of the opposite side and forms an

arterial ring around the lips. During operations these vessels may be controlled by grasping the lip between the fingers and thumb. The superior labial artery supplies a small branch to the nasal septum.

Because of the marked vascularity, extensive areas of facial skin, torn in lacerating wounds, often retain their viability and may be sutured back into place.

The anterior facial vein is the companion vein of the facial artery. It is formed near the inner angle of the eye by the union of the supra-orbital and supratrochlear veins and passes behind the artery, taking a less tortuous but more superficial course. It makes three important connections: with the diploic veins through the frontal diploic veins; with the pterygoid plexus through the deep facial veins; and with the cavernous sinus through the superior ophthalmic vein. The vein itself terminates in the internal jugular vein. The important relationship between this vessel and the dangerous area of the face has been stressed.

The nerves of the face are branches of the facial which supplies the muscles of expression and the trigeminal, which supplies the integument and the muscles of mastication (Figs 41 and 44).

The entire skin of the face, with the exception of the area over the lower half of the ramus of the mandible which is supplied by the great auricular nerve, is innervated by the three divisions of the trigeminal nerve. Since the face is developed from three rudiments, the frontonasal, the maxillary and the mandibular processes, each possesses its own sensory nerve. These nerves make up the three divisions of the trigeminal: the ophthalmic, the maxillary and the mandibular (Fig 41).

The ophthalmic or first division of the trigeminal nerve has five cutaneous branches.

(1) The supra-orbital nerve leaves the orbit through the supra-orbital notch or foramen about two fingerbreadths from the median line. It divides into lateral and medial branches which supply the central





FIG. 83 Injection of the gasserian ganglion

and the face including the buccinator and the platysma it provides secretory fibers to the salivary glands and sensory (taste) fibers to the tongue and the palate. Developmentally the seventh is the nerve of the hyoid arch therefore it supplies all the muscles derived from it. It leaves the skull at the stylomastoid foramen turns

forward laterally and slightly downward then enters the parotid isthmus and passes between the superficial and the deep lobes of the gland. It lies superficial to the external carotid artery and the posterior facial vein and may be injured in operations in this region or on the parotid gland. The terminal branches of the nerve




FIG 82 Injection of the maxillary and the mandibular nerves (A) direction of needle for the injection of the maxillary and the mandibular nerves, (B) injection of the mandibular nerve

the midline. The muscles of mastication of the same side are also paralyzed, but the buccinator, which is supplied by the seventh nerve, remains intact. If only the first and the second divisions of the fifth nerve are severed, the loss is entirely sensory, but if the third division is cut there

is a sensory loss as well as a paralysis of mastication.

The facial nerve supplying motor branches to the muscles of expression (Fig 86) also sends fibers to the stapedius, the stylohyoid, the posterior belly of the digastric, the scalp muscles, the auricle

various branches of the facial nerve so that the fibers meant for one group find their way to another

CLINICAL AND SURGICAL CONSIDERATIONS

Trigeminal Neuralgia Trigeminal neuralgia (tic douloureux, facial neuralgia) is a neuralgia of the fifth cranial nerve which is associated with severe pain along one or more of its division. Some surgical measures have been adopted to alleviate or cure the condition among them alcohol injection into the nerve or into the gasserian ganglion and if this fails division of its sensory route. Most authorities have abandoned operations upon the ganglion since good results are obtained by section of the sensory root. The first division of this nerve is rarely at fault but involvements of the second and the third divisions are frequent.

Injection of the Maxillary Nerve In injection of the maxillary nerve should be done where the nerve emerges from the foramen rotundum into the pterygopalatine fossa. Two points should be marked (Fig 82 A) the first is marked in the angle between the anterior border of the coronoid process and the lower border of the zygomatic arch the second is marked in the angle between the upper border of the zygoma and its frontal process. The two lines are then joined by a straight line and a needle is inserted at the first point and passed upward and inward at an angle of 45° with the horizontal. The needle is kept in the direction of the line constructed and passes behind the mandible to enter the pterygopalatine fossa. It will strike the bone which forms the margin of the foramen rotundum about two or three inches from the surface. The injection first of procaine and then of alcohol is made at this point.

Injection of the Mandibular Nerve

Injection of the mandibular nerve (Fig 82 A, B) is made at the foramen ovale. The needle is inserted at the center of and

under the zygomatic arch and then directed slightly forward. It will strike the outer lamella of the pterygoid process. The needle is then slightly withdrawn and directed backward where it will enter the foramen ovale.

Injection of the Gasserian Ganglion

Injection of the gasserian (semilunar) ganglion (Fig 83) is made through the foramen ovale and is done in the following way: a mark is made on the skin of the face about 3 cm to the side of, and a similar distance above the angle of the mouth. An imaginary line is drawn from this proposed point of entrance to the pupil and a second line is drawn from this point to the auricular tubercle of the same side. The needle is introduced and advanced toward the center of the zygomatic arch in the plane joining the point of entry of the needle to the pupil when the patient is viewed from the front. The needle strikes the infratemporal bony plane and then is gently withdrawn and pushed up in a more posterior direction. This is continued until when viewed from the front the needle is in the plane of the first line and when viewed from the side in the plane of the second line. It then enters the foramen ovale and there will encounter the ganglion.

Division of the sensory root of the fifth nerve (Fig 84) was perfected by Frazier.

A vertical incision is made which divides the skin, the temporal fascia and the underlying muscle. The periosteum is incised and detached from the temporal bone by means of a periosteal elevator. A burr hole is made through the temporal bone and enlarged with bone forceps. The dura is separated from the base of the skull and a retractor elevates the brain from the base of the middle fossa. The middle meningeal artery is exposed, cut and ligated as it emerges into the middle fossa through the foramen spinosum. The dura is stripped until the third division of the fifth nerve and the edge of the foramen ovale are exposed, the sheath of the nerve is incised and gently pushed upward and backward.

appear at the margins of the parotid and spread like the rays of an open fan or a goose's foot (*pes anserinus*). The five terminal branches are—(1) The *temporal branch*, which appears at the upper border

and the *orbicularis oris* it communicates with the buccal branch from the mandibular division of the trigeminal nerve. (4) The *mandibular branch* emerges still lower and supplies the muscles of the chin




FIG 84 Division of the sensory root of the trigeminal nerve

of the gland runs upward and forward to supply the facial muscles above the zygoma and the frontalis muscle. (2) The *zygomatic branch* emerges from the anterior border of the parotid above the parotid duct and supplies the muscles below the eye. (3) The *buccal branch* passes below the duct and supplies the buccina

and the lower lip. (5) The *cervical branch* appears at the lower end of the parotid passes within a fingerbreadth of the angle of the jaw between the platysma and the deep fascia, supplies the platysma and then sends twigs up to the muscles of the lower lip.

Coleman believes that there is a complicated and intricate intermingling of the




FIG 86 The parotid gland (A) superficial relations (B) the most common pattern formed by the fine branches of the facial nerve

started. Since these fibers have no lateral attachments they draw the lids medially. They are responsible for the "crow's feet" usually seen at the lateral angles of the eye. The *palpebral portion* arising from the medial palpebral ligament, which is a short fibrous cord stretched horizontally from the medial commissure of the eye lids to the adjoining part of the maxilla curves laterally in both eyelids. The fibers of this part are inserted into the lateral palpebral raphe and are located within the

lid proper and in front of the palpebral fascia. They usually act involuntarily and close the lids in sleeping and in blinking. The *lacrimal part* (Horner's muscle tensor tarsi) is made up of fibers which pass medially behind the tear sac and attach to the posterior lacrimal crest keeping the lids closely applied to the eyeballs. This part of the orbicularis oculi can also contract independently of the other two portions and by this independent action wrinkles the skin around the eye, giving




FIG 85 The muscles of the face

until the gasserian ganglion is seen. A small flap of arachnoid is turned downward exposing the fan shaped fibers of the sensory root. The sensory fibers are drawn outward exposing the motor root. The sensory root is divided behind the ganglion.

MUSCLES

The facial muscles are placed around the orifices of the eye, the ear, the nose and the mouth and act as sphincters or dilators (Fig 85). They all are innervated by the seventh (facial) nerve. It is extremely difficult to memorize this confusing group hence, it is best to locate *two* landmarks around which the muscles are

arranged. The *two* landmarks are the *two* orbicularis muscles namely, the orbicularis oculi and the orbicularis oris. *Two* muscles are associated with the nose, *two* muscles with the zygoma, *two* are levators of the lip, *two* are at the angle of the mouth, *two* are placed at the lower lip, and the *two* remaining muscles are associated with the chin and the cheek.

The *orbicularis oculi* has three parts, namely the orbital the palpebral and the lacrimal. The *orbital portion* passes in circular form from the medial palpebral ligament and the adjacent part of the frontal bone across the forehead the temple the cheek and back to the medial ligament where it

groove on the lip leaving a triangular space which is filled by the mentalis.

The two remaining muscles are associated with the chin and the cheek. The mentalis muscle passes from the lower incisor downward to the skin over the chin. When it contracts it raises the skin over this area thereby accentuating the transverse fold. The buccinator muscle is more deeply situated and forms the fleshy stratum of the cheek. Its fibers pass horizontally forward to the angle of the mouth. The mucous membrane of the cheek and the lips lines its inner surface. The muscle arises from the alveolar margins of both upper and lower jaws external to the molar teeth and more posteriorly from the pterygomandibular raphe. The uppermost and lowermost fibers pass directly into the upper and the lower lips respectively but the middle fibers decussate the upper half running into the lower lip and the lower half into the upper lip. At the angle of the mouth the muscle blends with the orbicularis oris. It retracts the mouth angle and is therefore considered as the antagonist of the orbicularis oris. Since the buccinator is supplied by the facial nerve it is not classified as a muscle of mastication however it is used during mastication to press the cheek against the teeth and to prevent the food from escaping into the vestibule of the mouth. It also aids in the action of blowing and sucking. The buccopharyngeal fascia is a thin sheet that clothes the surface of the buccinator muscle and extends backward to cover the constrictor muscles of the pharynx. The parotid duct on its way to the vestibule of the mouth pierces this fascia the buccinator and the mucous membrane of the mouth. The buccal fat pad also referred to as the suctorial pad is situated on the buccinator muscle. It is a mass of fat encapsulated in fascia which lies on the muscle partly tucked in between the buccinator and the masseter. The buccal nerves, small vessels and the parotid duct pierce it. It thickens the cheek and helps to reduce atmos-

pheric pressure during sucking. It is much larger in infants than in adults and the rounded fullness of a baby's cheek is largely due to it.

PAROTID REGION

Although the parotid gland may be considered as a constituent of the neck its relations to the face are more numerous and of greater practical importance.

PAROTID GLAND

(Figs 86-87) The parotid gland is the largest of the salivary glands. It fills the parotid space and sends a process forward over the masseter muscle. Its fibrous capsule sends septa into the interior of the gland dividing it into lobules and making removal difficult at times. In this respect it differs from the submandibular gland which is loosely enveloped and easily shelled out. In front of the styloid process and from the medial surface of the gland is a pharyngeal prolongation which is closely related to the wall of the pharynx and to the great vessels in the parapharyngeal space. The fascial septum separating this aspect of the gland from the carotid sheath may be broken through by pathologic erosions or malignant tumors as well as sharp instruments.

The parotid gland has the following relationships: superficially it is covered by skin, superficial fascia, lymph glands, fibrous capsule and branches of the great auricular nerve. The upper border is in contact with the external auditory meatus and the temporomandibular joint. Abscesses of the gland may perforate into either of these structures. The anterior border is grooved by the masseter, the ramus of the mandible and the internal pterygoid muscle. The posterior border is in contact with the mastoid process and the sternocleidomastoid muscle. The lower border overlaps the internal and the external carotid arteries and the internal jugular vein. The deep surface is in contact with the digastric and the styloid muscles, the internal and the

partial protection from light or wind. Those fibers which insert into the skin of the eyebrow draw it down as in frowning and also draw the eyebrows closer together producing one or more vertical furrows in the middle of the forehead.

The *orbicularis oris* is the sphincter muscle of the mouth and forms the greater part of the substance of the lips. Its fibers encircle the oral aperture and extend upward to the nose and downward to the groove which is situated between the lower lip and the chin. Many of its fibers are derived directly from the buccinator others from the depressors and the elevators of the angles of the mouth. This complex arrangement makes possible the varied movements of the lips such as pressing, closing, pursing, protruding, inverting and twisting.

The two muscles associated with the nose are the procerus and the compressor nares. The *procerus* muscles unite. They arise from the fascia covering the lower parts of the nasal bones, broaden and insert into the skin between and above the eyebrow. Their fibers interlace with the frontal bellies of the occipitofrontalis. By their contraction they draw down on the skin of the root of the nose and produce transverse wrinkling. The *compressor nares* muscle originates from the side of the bony aperture of the nose and spreads out as a fan shaped muscle just above it. It joins its fellow of the other side thus forming a sling across the bridge of the nose. It compresses the nostril and its action is especially well demonstrated in the crying of infants. (Two other muscles, the dilator naris and the depressor septi nasi are also found in this area but are small and clinically unimportant.)

The two muscles associated with the zygomatic area are the zygomaticus minor and the zygomaticus major. The *zygomaticus minor* arises from the zygomatic bone and is closely related to the lateral margin of the levator labii superioris. This is a mere muscular slip and is often absent. The *zygomaticus major* is both longer and

thicker than the minor and runs obliquely from the zygomatic bone to the angle of the mouth. The major has been referred to as the "smiling muscle."

The two lip elevators are the levator labii superioris alaeque nasi and the levator labii superioris alaeque nasi. The *levator labii superioris alaeque nasi* is a small muscle lying along the attachment of the nose it divides and inserts into the ala and the upper lip. It aids in dilation of the nostril and elevates the upper lip. The *levator labii superioris* muscle is thin fairly wide and descends from the infra orbital margin into the upper lip. It is overlapped by the orbicularis oculi.

The two muscles associated with the angle of the mouth are the levator anguli oris (caninus) and the depressor anguli oris (triangularis). The *levator anguli oris* lies deep to the levator superioris. It arises from the upper jaw below the infra orbital foramen, inserts partly into the skin of the angle of the mouth and blends with the orbicularis oris. It also lies deep to the zygomatic major. The *depressor anguli oris* muscle is placed superficially. It is triangular in shape its base corresponding to its insertion in the neighborhood of the angle of the mouth.

The two muscles associated with the lower lip are the risorius and the depressor labii inferioris. The *risorius* lies horizontally opposite the angle of the mouth but may be continuous with the posterior fibers of the platysma or may arise independently from the fascia covering the masseter muscle. Its fibers converge at the angle of the mouth where they are inserted into the skin. By drawing the angle of the mouth in a lateral direction the muscle plays a large part in the production of a smile and has been referred to as the "grinning muscle." The *depressor labii inferioris* muscle is short and wide, lies in front of the depressor anguli and is overlapped by it. Its medial groove meets and decussates with that of its fellow above the transverse




FIG 89 The six muscles of mastication (A) Viewed from the left side the zygomatic arch and part of the mandible have been removed. The temporal muscle has been cut for the purpose of exposing the pterygoid muscles (B) Viewed from below to show the course and the attachments of the external and internal pterygoid muscles

teeth or during the cutting of a lower wisdom tooth

The masseter muscle is firmly held by the masseter fascia which binds it to the

margins of the ramus and the body of the mandible. The muscle covers nearly the entire lateral surface of the ramus of the mandible. An expansion of the fascia over

external carotid arteries and the ninth the tenth the eleventh and the twelfth cranial nerve. The modern concept of the parotid considers it as having a superficial lobe connected by a rather narrow isthmus with a deep lobe. The facial nerve passes around the isthmus between both lobes but is not imbedded in the parotid tissue proper. The *sacra parotidis* is an accessory part of the parotid gland which lies immediately above its duct and on the masseter muscle.

The *fibrous capsule* of the parotid is derived from the investing layer of deep cervical fascia which splits at the lower pole of the gland to ensheath it. The deeper of these two layers passes under the gland and attaches to the base of the skull; the superficial layer passes anterior to the masseter muscle and attaches to the lower border of the zygomatic arch. This layer has been referred to as the *parotideomasseteric fascia* and accounts for the intense pain caused by inflammatory swellings of the gland. That part of the fascia which connects the styloid process to the angle of the mandible has been called the *stylomandibular ligament* and separates the parotid and the submaxillary glands.

Nerve and Blood Supply. The *auriculotemporal nerve* is an accessory branch of the mandibular division of the fifth which supplies the skin in front of the ear. Its course is as follows: ascending upward through the temporal region to the vertex of the skull the nerve emerges from the upper border of the parotid, crosses the root of the zygoma between the external ear and the condyle of the jaw and divides into its temporal branches. It may be compressed by tumors or swellings in the parotid gland and produce exquisite pain radiating over the temple as high as the vertex.

The *scenith* or *facial nerve* emerging from the stylomastoid foramen divides into its two main branches which embrace the isthmus of the parotid gland. From here these branches redivide and radiate from the border of the gland in the form of

a goose's foot (*pes inserinus*) (Fig. 86 B). This has been discussed elsewhere (p. 66). This new concept of the facial nerve running around the isthmus rather than in the substance of the gland has been stressed by Hamilton Bailey, McWhorter, McCormack, Cauldwell and Anson. Hamilton Bailey believes that a total extirpation of the gland is possible without a resulting facial paralysis.

Although *veins* are variable (Fig. 87 B) they follow a fairly constant course in the substance of the parotid gland. The *posterior facial vein* aids in the formation of two other veins, the external jugular and the common facial. At its lower end and while in the parotid the posterior facial divides into an anterior and a posterior branch. The anterior branch joins the anterior facial vein to form the common facial and the posterior joins the posterior auricular to form the external jugular vein.

The *external carotid artery* ascends from under cover of the digastric and the stylohyoid muscles and comes into relationship with the posteromedial surface of the parotid. Here it gives rise to a posterior auricular artery and then enters the gland passing from the posteromedial to its anteromedial surface. At the back of the neck of the mandible it divides into internal maxillary and superficial temporal branches. The *superficial temporal artery* arises under cover of the parotid gland, emerges at its upper border accompanied by a corresponding vein and the auriculo-temporal nerve (Fig. 2). It ascends across the root of the zygoma where its pulsations may readily be felt; continues upward on the temporal fascia and divides into anterior and posterior branches which supply the scalp. In addition to many small branches which supply the parotid gland, the auricle and the facial muscles, the superficial temporal supplies a *transverse facial artery* which runs forward on the masseter muscle, emerges at the anterior border of the gland and continues parallel with and above the parotid duct.

VESSELS AND NERVES

The *internal maxillary artery* (Fig 90) arises from the external carotid opposite the neck of the mandible and under cover of the parotid gland. It passes forward deep to the neck of the lobe and superficial to the sphenomandibular ligament. Between the mandible and the sphenomandibular ligament it is accompanied by its vein and lies superficial to the inferior alveolar (dental) nerve. It goes upward and forward superficial to the external pterygoid between it and the temporal muscle or deep to the external pterygoid between it and branches of the mandibular division of the fifth nerve. It then passes medially between the two heads of the pterygoid and through the pterygomaxillary fissure into the pterygopalatine fossa to end in its numerous terminal branches.

The external pterygoid muscle divides the maxillary artery into three parts. The first is known as the mandibular portion; it lies between the neck of the mandible and the sphenomandibular ligament taking a horizontal course forward nearly parallel with and a little below the auriculotemporal nerve. In this location it is imbedded in the parotid gland and usually crosses in front of the inferior alveolar nerve. The second part is called the pterygoid portion and here the artery may lie lateral or medial to the external pterygoid muscle. This part of the artery usually runs obliquely forward and upward under cover of the ramus of the mandible and passes on the superficial surface of the muscle. The vessel then passes between the two heads of origin of this muscle and enters the pterygopalatine fossa. Part three of the vessel the pterygopalatine portion lies in the pterygopalatine fossa in relation to the sphenopalatine ganglion. The branches which arise from the first part of the artery are associated with foramina those which come from the second part are associated with muscles and the branches of the third part are again associated with foramina.

The branches of the first part of the internal maxillary artery are (1) the *deep auricular artery* which passes to the external auditory meatus (2) the *anterior tympanic*, which enters the petrotympanic fissure to the middle ear (3) the *middle meningeal* which arises from the upper border of the maxillary bone and runs upward and deep to the external pterygoid muscle. As it ascends it is embraced by the two heads of the auriculotemporal nerve; it enters the middle cranial fossa through the foramen spinosum and upward and forward on the squamous temporal and great wing of the sphenoid lobe toward the antero-inferior angle of the parietal bone where it divides into anterior and posterior branches. The anterior branch travels upward across the great wing of the sphenoid toward the pterion and then on the parietal bone behind the coronal suture near the motor cortex. The posterior branch passes upward and backward on the squamous temporal to the middle of the lower border of the parietal bone and then breaks up into its terminal branches. (4) The *accessory meningeal* also referred to as the *small meningeal artery* has a similar course and may be a branch of the above mentioned vessel; it enters the middle cranial fossa through the foramen ovale and supplies the dura mater and the trigeminal ganglion. (5) The *inferior alveolar (dental) artery* passes downward behind the inferior alveolar nerve and between the sphenomandibular ligament and the mandible. It supplies a mylohyoid branch and then enters the mandibular foramen to supply the teeth and the lower jaw. Its terminal branch appears on the face accompanied by the mental nerve.

There are four branches of the second portion of the internal maxillary artery. (1) the *masseteric artery* passes laterally through the mandibular notch to the masseter muscle and also supplies the mandibular joint. (2) the *deep temporal* has two branches anterior and posterior which ascend between the temporalis muscle and

lies the fat pad of the cheek and holds it against the buccinator muscle. The parotid duct lies within the fascia and is protected by it. The muscle arises by two closely associated heads—a superficial and a deep—which arise from the surface of the zygomatic arch. It is inserted into the lateral surface of the ramus and the coronoid process of the mandible. The muscle raises and protrudes the mandible and its fibers may be felt well if the jaws are firmly clenched. The transverse facial vessels, the parotid duct and branches of the facial nerve all lie on its lateral surface and the parotid gland overlaps it posteriorly. The muscle does not cover the head and the neck of the mandible (Fig. 2).

The *pterygoid muscles* (Fig. 89B) lie on a deeper plane and are almost completely hidden by the ramus of the mandible. Only a small part of the external pterygoid can be seen through the mandibular notch.

Many authors prefer to consider the *internal (medial) pterygoid muscle* as being associated with the masseter and these two muscles have been likened to the two bellies of the digastric. The fibers of the internal pterygoid originate from the medial surface of the lateral pterygoid lamina and by a small slip from the tuberosity of the maxilla. They pass downward and backward and insert into the medial surface of the ramus of the mandible from the mandibular foramen to the angle. The muscle elevates the mandible, protrudes it and pulls it to the opposite side. Superficial to this muscle is the ramus of the mandible, the external pterygoid, the lingual and the inferior dental nerves, the maxillary and the inferior dental vessels and the sphenomandibular ligament. Deep to it are the tensor palati and the levator palati, the superior constrictor of the pharynx and the eustachian (auditory) tube.

The *external (lateral) pterygoid muscle* originates by two heads—the lower from the lateral surface of the lateral pterygoid lamina and the upper from the under sur-

face of the great wing of the sphenoid. The fibers are directed backward and become inserted in the digital fossa on the front of the neck of the mandible and to the capsule and the disk of the mandibular joint. In this way its contraction opens the mouth by sliding the condyle forward and protruding the jaw. One muscle acting alone pulls the chin over the opposite side. The internal maxillary artery crosses the lower head of the muscle obliquely and, as a rule, runs superficial to it.

The *buccinator* forms the muscle layer of the cheek and is discussed here for the sake of completion. It arises from the outer alveolar margins of both the upper and the lower jaws in the region of the molar teeth and passes to the angle of the mouth where it blends with the orbicularis oris. The middle fibers decussate at the angle of the mouth, so that the uppermost fibers pass to the lower lip and vice versa. It is supplied by the buccal branches of the facial nerve. By its action of retracting the angle of the mouth and flattening the cheek it compresses the cheek so that during mastication food is pushed beneath the molar teeth. Compression of the cheek against the gums prevents masticated food from becoming lodged there. In paralysis of the facial nerve it becomes necessary for the patient constantly to dislodge the food with his finger. This muscle also aids in the act of blowing and whistling. Its superficial surface is covered with buccal pharyngeal fascia and its deep surface is lined with the mucous membrane of the cheek. Posteriorly it is covered by the buccal fat pad which separates it from the masseter and the temporal muscles anteriorly by the superficial fascia, which contains the facial artery, the anterior facial vein, the buccal nerve and artery and the buccal branches of the facial nerve. The muscle is pierced by the parotid duct and twigs from the buccal nerve.

and the medial angle of the orbit (3) The *greater palatine artery* passes through the greater palatine canal with the nerve of the same name then along the hard palate in a groove about a half inch from

membrane of the nasal cavity, the adjacent sinuses and the pharynx. At the back part of the superior meatus it supplies posterior lateral nasal branches which spread forward over the conchae and the meatus,




FIG. 91 The lingual and the inferior alveolar (dental) nerves

the teeth and finally through the lateral incisive foramen to the nose (4) The *pharyngeal artery* is very small and passes backward through the pharyngeal canal accompanied by the pharyngeal nerve. It is distributed to the upper part of the pharynx and the auditory tube (5) The *artery of the pterygoid canal (Vidian)* passes backward along the pterygoid canal with its corresponding nerve. It is distributed to the upper part of the pharynx and to the auditory tube, sending a small branch into the tympanic cavity which anastomoses with the other tympanic artery (6) The *sphenopalatine artery* enters the nasal cavity through the sphenopalatine foramen and supplies the mucous

anastomosing with the ethmoidal arteries and nasal branches of the descending palatine artery. It ends on the nasal septum as posterior septal branches which anastomose with the ethmoidal arteries and the septal branches of the superior labial. One branch descends in a groove on the vomer to the incisive canal and anastomoses with the descending palatine artery.

The *pterygoid enous plexus* is a rich network of veins which is located around the lateral pterygoid muscle. Veins corresponding to the maxillary artery empty into it. From its posterior end a maxillary vein passes backward to unite with the superficial temporal forming the posterior facial vein. The plexus makes the follow




FIG 90 The internal maxillary artery. The vessel is divided into three parts by the external pterygoid muscle. Part one is known as the mandibular portion, part two the pterygoid, and part three the pterygopalatine portion. The branches of each part are numbered and represented.

the pericranium they supply the muscle and anastomose with the middle temporal artery (3) the pterygoid arteries are irregular in number and origin and supply the pterygoid muscles (4) the buccinator (buccal) artery travels forward with the buccal nerve between the internal pterygoid and the jaw to supply the buccinator muscle, the skin and the mucous membrane of the cheek.

The six branches of the third portion of the internal maxillary artery are (1) The posterosuperior alveolar, which descends

over the posterior surface of the maxilla sending branches to the gums the buccinator muscle through the bone to the molars the premolars and the maxillary sinus (2) The infra orbital artery, really a continuation of the parent trunk is accompanied by the maxillary nerve through the infra orbital canal appearing on the face beneath the levator labii superioris. In the canal it sends branches to the orbit and an anterior dental branch which accompanies the nerve and supplies the front teeth. On the face it supplies the lacrimal

supply taste fibers to the same region of the tongue (Fig. 98). Resection of the lingual nerve is at times necessary for the relief of intense pain which is associated with carcinoma of the tongue.

belly of the digastric. In the inferior dental canal it sends branches to the roots of the lower teeth and gums. The nerve finally emerges through the mental foramen as the mental nerve (Fig. 91).




FIG. 92 The temporomandibular joint (A) lateral view, right side (B) exposure of the joint and the articular disk following removal of the temporomandibular ligament and part of the condyle of the mandible (C) medial view showing the stylo-mandibular and the sphenomandibular ligaments

The *inferior alveolar (dental) nerve* passes downward deep to the external pterygoid muscle but superficial to the sphenomandibular ligament and is accompanied by the dental vessels. Immediately before entering the mandibular foramen it gives off the nerve to the mylohyoid muscle; this descends in a groove on the deep surface of the mandible in company with the mylohyoid vessels. This nerve reaches the posterior edge of the mylohyoid; passes superficial to that muscle and ends by supplying the mylohyoid and the anterior

TEMPOROMANDIBULAR JOINT

The *temporomandibular (temporomaxillary mandibular)* is a synovial joint that is formed by the head of the mandible with the articular fossa and the eminence of the temporal bone. The articulating surfaces are completely separated by an *articular disk* which divides the joint cavity into an upper and a lower chamber (Fig. 92 B). The joint is surrounded by a lax capsule which envelops the bony articular surface and furnishes attachment to the interposed cartilage. The laxity of this

ing communications with the cavernous sinus through the foramen ovale with the interior facial through the deep facial vein, with the inferior ophthalmic veins through the inferior orbital fissure (Fig 30)

In the parotid region the *mandibular division of the trigeminal nerve* plays an important role. It leaves the skull through the foramen ovale in the greater wing of the sphenoid bone and differs from the other two divisions in that it is a mixed nerve (Fig 41). The sensory part arises from the gasserian ganglion and the motor part is the motor root of the fifth nerve. The two roots pass through the foramen ovale and almost immediately unite into one trunk which is covered by the external pterygoid muscle. It lies on the surface of the tensor palati (veli palatini) muscle which separates the nerve from the auditory (Eustachian) tube and the nasopharynx. The middle meningeal artery lies lateral to and a little behind it. The trunk divides into anterior and posterior divisions. The undivided trunk gives off a recurrent nerve and the nerve to the internal pterygoid muscle. The recurrent nerve (*nervus spinosus*) passes back into the foramen spinosum and supplies the dura and the mastoid air cells. The nerve to the internal pterygoid muscle is self-explanatory. From the anterior division mainly muscular, are derived the deep temporal, the masseteric, the external pterygoid and the long buccal branches. From the posterior division mainly sensory are derived the auriculo-temporal, the inferior dental (alveolar) and the lingual nerves. Although the anterior division of this nerve gives off muscular branches to the temporal, the masseter and the external pterygoid muscles, the long buccal nerve is essentially sensory. It passes down between the two heads of the external pterygoid muscle, pierces the anterior part of the temporal muscle, traverses the submental fat pad and then branches outward to the skin of the face and inward to the mucous membrane of the cheek.

The *auriculotemporal nerve* has been discussed elsewhere (p 6). It is a sensory branch of the mandibular nerve which forms an anastomosis with the facial nerve and otic ganglion. It emerges from the upper border of the parotid and crosses the root of the zygoma between the external ear and the condyle of the jaw, where it divides into its temporal branches. This nerve is sometimes resected in persistent neuralgias, and is easily found where it crosses the zygoma, lying between the ear and the temporal artery. By means of its communication with the otic ganglion, secretory fibers result. These supply the parotid gland, hence, the rationale for division of it in an attempt to close a parotid fistula. Auricular branches of this nerve pass to the upper ear and the external auditory meatus. Referred pain from these branches may be so severe that the ear drum may be opened unnecessarily when one of the molar teeth is at fault.

The *lingual nerve* (Fig 91) passes downward deep to the external and on the surface of the internal pterygoid muscle. In this part of its course it is in front of the inferior alveolar nerve and is joined by the chorda tympani (seventh nerve), which contains taste fibers that are carried by the lingual to the anterior two thirds of the tongue. As the nerve continues downward and forward it lies between the mandible and the internal pterygoid, and farther forward is under cover of the mucous membrane of the mouth on the superior constrictor and the styloglossus muscles. It passes forward between the mylohyoid and the hyoglossus and arrives between the sublingual gland and the genioglossus muscle, where it crosses the submandibular duct and supplies the gums and the anterior two thirds of the tongue (Fig 106 A). One should not be confused between taste and sensation if he recalls that the lingual nerve supplies the anterior two thirds of the tongue with its sensory fibers, but this nerve carries fibers from the facial nerve by way of the chorda tympani which




FIG 93 Anterior dislocation of the mandible. The condyle has been drawn over the articular eminence into the zygomatic fossa by the contraction of the external pterygoid. The mandible is then drawn upward and fixed in place by masseter, internal pterygoid and temporalis muscles.

matic fossa and the interarticular cartilage remains behind. As soon as it reaches its new position it is immediately drawn up by the internal pterygoid, the temporalis and the masseter muscles and is thereby passively fixed in place (Fig 93).

MOUTH AND REGIONS THAT SURROUND IT

LIP REGION

The *lips* are two fleshy folds that circumscribe the mouth and close the buccal cavity in front. At the sides they unite to form the commissures. The lips consist of five layers (Fig 94).

- 1 **Skin** The layer of skin is fairly thick and adherent to the subjacent connective tissue and muscular layers. It contains hair follicles and sebaceous glands and is frequently the site of furuncles. The lower lip is a favorite site for epitheliomas.

- 2 **Superficial Fascia** This fascia is a connective tissue layer which contains some fat. Since it is loosely arranged considerable edema may take place when the lips are bruised or inflamed.

- 3 **Orbicularis Oris Muscle** This essential muscle of the lips is arranged in an elliptical manner around the buccal orifice, the extremities of the upper and the lower

capsule enables free joint movements. Over its lateral aspect the capsule is markedly thickened and strengthened by the *temporomandibular ligament* (external lateral ligament) (Fig 92 A) which stretches from the zygoma and the tubercle at its root to the lateral and the posterior surfaces of the neck of the mandible. The ligament is covered by the upper part of the parotid gland and is in relation to the superficial temporal vessels. The articular disk is attached around its circumference to the capsular ligament. There is an exception to this attachment however since the disk receives part of the insertion of the external pterygoid muscle in front. The lower disk surface is concave to fit into the head of the mandible but its upper surface undulates to fit the fossa and the eminence. The disk can become loose or detached and as it slips back and forth may produce an audible click (clicking jaw). At times it may become detached at one end and is then apt to double on itself in which event it becomes impacted between the joint surfaces and causes locking. The symptoms may become so discomforting and embarrassing that removal of the disk is necessary.


Two accessory ligaments described as bands and giving additional ligamentous support to the joint are the *sphenomandibular* and the *stylomandibular*. The *sphenomandibular ligament* (*internal lateral ligament*) lies on a deeper plane than the joint distinct from the medial part of the articulation and is a thin and fairly long band stretching from the spine of the sphenoid bone to the edge and margins of the mandibular foramen (Fig 92 C). Medially its upper part is separated by fat from the wall of the nasopharynx and its lower part lies on the internal pterygoid muscle. Laterally it is related to the mandibular joint and the mandible is separated from the ligaments from above downward by the auriculotemporal nerve, the external pterygoid muscle, the maxillary vessels

and the inferior dental vessels and nerves. Although these structures separate the ligament from the joint, the chorda tympani nerve lies deep to the ligament. The *stylomandibular ligament* is a thickened part of the cervical fascia that covers the deep surface of the parotid gland. It extends from the styloid process to the posterior border and angle of the mandible and separates the parotid from the submandibular gland.

The *synovial membrane* is in two separate parts since it has two separate cavities to line. The upper synovial cavity is the more extensive because of the greater size of the articular fossa of the temporal bone. The membrane although reflected onto the articular disk disappears from this part in the adult.

The construction of the temporomandibular joint permits a wide range of movements. Elevation is produced by the *masseter*, the *internal pterygoid* and the *temporalis muscles*; depression by the *digastric*, the *mylohyoid*, the *geniohyoid* and the *platysma*; protrusion by the *pterygoids*; the anterior part of the *temporalis* and fibers of the *masseter*; retraction by the posterior fibers of the *temporalis* and the deeper fibers of the *masseter*. Grinding movements are produced by the *pterygoids* of opposite sides acting alternately. The construction of the joint permits a forward dislocation either unilateral or bilateral which can occur when the mouth is widely opened. Such dislocations have occurred during a blow struck upon the lower front teeth, or during laughing, yawning, vomiting, and also in the dentist's chair. When the mouth is widely opened the condyles and the interarticular fibrocartilage glide forward. Normally the condyles should not reach as far as the summit of the articular eminence, but when the mouth is opened widely all parts of the capsule except the anterior are made tense, and if at this time the external pterygoid muscle contracts vigorously, the condyle is drawn over the articular eminence onto the zygoma.

Operation for single harelip



Operation for double harelip




FIG 96 Operations for single and double harelip

grasping the lip between the finger and the thumb. This circle provides a rich blood supply for the lips and is nearer the free than the attached border. Since the arteries and veins are free, it is well to tie both ends when they are severed. Due to their vascularity, the lips are often the site of nevi and other vascular tumors. The mucous glands situated in this layer are large, numerous, and can be felt with the tip of the tongue and seen when the lip is everted. The ducts of the glands open into the mucous membrane and

should they become occluded, an opalescent bluish mucous cyst develops as a result of distention of the gland. The veins accompany the arteries and flow into the facial vein. By means of this flow, a communication of importance, of which has been stressed before, exists between the lips and the intracranial circulation. The *Lymphatics* (Fig 95) of the upper lip drain into the submaxillary nodes; those of the median portion of the lower lip drain into the submental glands, and those of the lateral portion pass directly into the sub




FIG 94 Sagittal section through the upper lip The five layers which constitute each lip are shown




FIG 95 Lymph drainage of the lips That portion of the upper lip which is associated with the "dangerous area of the face" is illustrated in Figure 30

portions meeting at the lip commissures. It acts as a sphincter of the mouth. Because the general direction of the muscle fibers is circular, a vertical incision in this area causes separation of the wound edges. Since it is supplied by the facial nerve, paralysis interferes with articulation, prevents tight closure of the mouth and as a result allows

saliva to drip from the paralyzed corner.

4 **Submucous Tissue** The submucosa is the layer that contains vessels and mucous labial glands. An arterial circle is formed in this tissue; this arises from the upper and the lower labial branches of the facial artery (external maxillary). The pulsations of these vessels can be felt by




FIG 98. The sublingual and the submaxillary salivary glands—sagittal section showing the relations between the glands, ducts, vessels and nerves

cutaneous junction and is almost always found on the lower lip. The treatment may be surgical or by irradiation. If surgery is chosen a V-shaped excision is employed extending well into healthy tissue. This method however is advisable only for small and early growths. For larger lesions not only must the primary growth be removed but also the associated glands, the submaxillary, the submental and at times the deep cervical chain. Enlarged nodes of the neck may involve one or both sides and are usually removed at a second stage by a radical operation en bloc. This involves an extensive suprathyroid dissection.

MOUTH PROPER

The mouth cavity is conveniently divided by the arch formed by the teeth and the

gums into the vestibule which lies between the gums and the cheeks and the mouth proper which lies behind and within the arch of the teeth.

The mouth proper lies within the arch of the teeth and communicates with the vestibule by means of an interval situated behind the last molar tooth. It is bounded in front and at the sides by the gums and the teeth above by the hard and the soft palates below by the tongue and the sublingual region and opens posteriorly into the pharynx via the isthmus.

Sublingual Region (Fig 97) The two sublingual regions make up the floor of the mouth. Each is represented as a deep groove lying between the mandible and the root of the tongue and placed upon the mylohyoid and the hyoglossus muscles.




FIG 97 The sublingual region The mucosa has been removed on the right side to expose the deeper structures

maxillary Metastatic involvement of the submental and submaxillary nodes continues to the superior and inferior chains of deep cervical glands. The motor nerves of the lips are derived from the facial and the sensory branches supply the skin and the mucous membrane through the trigeminal by way of the infra orbital, the buccal and the mental branches.

5 Mucous Membrane This constitutes the innermost layer of the lip and is covered with stratified epithelium.

SURGICAL CONSIDERATIONS

HARELIP

Operations for unilateral harelip (Fig 96 A B) depend upon the size of the defect. If small and if the parts are freely movable all that is necessary is to pare the margins and approximate the wound. The incision should include skin, mucous mem-

brane and all the intervening tissue. If the parts are immobile and the defect more complete then more complicated and involved procedures must be done.

Operation for double harelip (Fig 96 C D) is a rather extensive one and the surgeon should be specially trained and ready to meet any difficulties that arise. The central defect is prepared by incising its edges throughout its entire length and thickness. The lateral margins are then incised so that their approximation with the central part of the defect and with each other becomes possible.

Harelip is frequently associated with clefts in the hard and the soft palates and surgical correction for this condition is described elsewhere (p 157).

CARCINOMA OF THE LIP

Carcinoma of the lip is usually of the squamous cell type, arises from the muco-

the facial and the trigeminal nerves (3) the *muscular layer* (buccinator) is covered with the buccopharyngeal fascia and is pierced by the parotid duct (4) the *submucous layer* contains the mucous buccal

in glands, on the surface of and in the parotid gland

The *nerves* of the cheek are branches of the facial supplying the muscles the labial branches of the infraorbital the




FIG. 99 The sixteen adult teeth of the right side
The roots have been represented in phantom

glands and (5) the *mucous membrane* is made up of stratified epithelium

In the region of the cheek the subcutaneous fat increases to form the so called *suctorial fat pad* located on the buccinator muscle and partly under and in front of the masseter it is larger in the child where it gives rotundity to the baby's cheeks and is useful in the act of sucking. This fat is continuous with the temporal and the lateral regions of the face

The *lymphatics* from the anterior part of the cheek end in glands below the mandible those from the posterior part end

buccal and the mental nerve supply the skin and the mucous membrane with sensory fibers

The *external maxillary (facial) artery* is the only important vessel to the cheek it crosses forward on the buccinator muscle and becomes the angular artery at the corner of the mouth

Gums The *gums (gingivae)* consist of dense vascular fibrous tissue which is covered by mucous membrane and is attached to the alveolar margins of the jaw. They are continuous with the mucosa of the oral vestibule externally and the palate or floor

The anterior two thirds of the tongue rises from the floor and the *frenulum linguae* appears as a median fold which connects the tongue to the floor. On each side of the frenulum the lingual vein appears as a prominent blue line. If the frenulum is made prominent by pressing the tip of the tongue against the hard palate, two small papillae will be noted to either side and at its summit each representing the openings of the ducts of the submaxillary glands. The sublingual fold a ridge of mucous membrane passes laterally and backward from the papilla and overlies the sublingual gland. Each sublingual compartment contains the sublingual gland an anterior prolongation of the submaxillary gland the submaxillary duct the lingual and the hypoglossal nerves and the sublingual vessels.

The *sublingual gland* is indicated by the sublingual fold (plica) which is found between the alveolus and the anterior part of the tongue. It takes an oblique forward and inward course to the *sublingual caruncle* near the frenulum. It not only indicates the position of the sublingual gland but also marks the line of the submaxillary (Wharton's) duct and the lingual nerve. The sublingual is the smallest of the salivary glands and rests upon the mylohyoid muscle in the sublingual fossa close to the symphysis (Fig 98). Its posterior end is in contact with the anterior prolongation of the submaxillary gland. The submaxillary duct the lingual and the hypoglossal nerves and the sublingual vessels are situated between the sublingual gland and the root of the tongue. When the submaxillary gland is pressed upon from the outside its anterior prolongation can be felt through the mucous membrane slightly in front of the angle of the jaw. This prolongation forms a continuous glandular mass with the sublingual gland. The many *sublingual ducts* open separately into the floor of the mouth one of the larger ones on the posterior part opens into or by the side of the submandibular

gland. *Ranula* is a term that has been loosely applied to all cysts appearing in the floor of the mouth but many observers believe that it should be restricted to cysts that originate in connection with the ducts of the salivary glands. It is a retention cyst which appears as a bluish mass filled with a mucous-like substance and is associated with a blockage of the submaxillary (Wharton's) or sublingual duct. The *submaxillary duct* arises from the medial surface of its gland and accompanies it under the mylohyoid muscle. It passes diagonally across the medial aspect of the sublingual gland and adheres to it. In its course the hyoglossus and the genioglossus muscles lie medial to it, the hypoglossal nerve below and the lingual nerve at first above crossing it superficially at the anterior border of the hyoglossus and then turning upward and deep. The lingual artery is under cover of the mylohyoid muscle but is crossed superficially by branches of the hypoglossal nerve and at its termination by the lingual nerve and the submaxillary duct.

Vestibule and Buccal Cavity The *vestibule* lying between the gums and the cheeks communicates with the mouth behind the last molars. *Stensen's duct* opens into the vestibule opposite the second upper molar on a small papilla which can be felt with the tip of the tongue. About the circumference of the vestibule the superior and the inferior cul de sacs are formed by the reflection of the mucous membrane of the lips and the cheeks upon the upper and the lower alveolar arches.

The *buccal cavity* is an area between the inferior margin of the orbit and the lower jaw, extending from the masseter muscle to the fold of the nose and the commissure of the lip. The cheeks (buccae) resemble the lips in their structure having the same five layers: (1) the *skin*, (2) *superficial fascia* containing the zygomatic major the risorius and the platysma muscles, the parotid duct is surrounded by mucous glands, vessels and branches of

in the upper jaw bites against two lower teeth (2) The *canine* teeth are distinguished by their somewhat pointed crowns. The labial surface is convex, and the lingual slightly concave. The root is single and long, that of the upper canine being longer than that of any other tooth, thereby producing the canine eminence on the anterior surface of the maxilla. The upper canines are larger than the lowers and are known as the *eye teeth*. (3) The *bicuspid*s, or premolars, acquired their name because of the two cusps which they present, one being lingual and the other labial. Each has a single root which shows a tendency to divide, especially in the first upper bicuspid. (4) The *molars* are distinguished as the first, the second and the third. They are the grinding teeth. The upper molars have four cusps and the lower have five. All are characterized by their large crowns and are the largest of all the teeth but diminish in size from the first to the third. Each has two or three roots, which occasionally are united in the last molar. As a rule a difference may be noticed between the molars of the maxilla and those of the mandible. Normally the upper molars possess three roots and the lower have two. The upper molars have either three or four projecting tubercles and the lower usually have five.

(Fig. 100) Each tooth has a *crown* covered with enamel, a *neck* encircled by gum and a *root* imbedded in the jaw. At the apex of each root is found the *apical foramen* which is a pin point opening leading through a widening canal to the *pulp cavity*. This is filled with tooth pulp, a vascular connective tissue with numerous little nerves and vessels which reach it via the apical foramen. Each tooth consists of (1) *enamel* which is the insensitive covering of the crown, (2) *dentine* the exquisitely sensitive yellowish basis of the tooth, (3) *cement* (crusta petrosa) a bony covering for the root and the neck of the tooth, (4) *pulp* which is a fibrous mate-




FIG. 100 Vertical section of a tooth, showing its structure

rial containing the nerves and the vessels, (5) *periodontal membrane* which is continuous with the lamina propria of the gum and is attached to both the cement and the alveolar wall.

The teeth are rooted in the alveolar cavities or sockets and are firmly maintained there. These sockets and particularly the lower ones are much nearer the outer than the inner table, as evidenced by their palpable bulging into the vestibule. The thinness of this outer plate explains the perforation of root abscesses onto the vestibular surfaces and also the fractures of the outer plate during tooth extractions.

The maxillary teeth are supplied by branches of the *maxillary* and the *infraorbital nerves*. The *lymph vessels* of these teeth end in glands on the surface of the parotid and below the mandible. The mandibular teeth are supplied by the *mandibular nerve* and their lymph vessels end

FIRST DENTITION

	MOLAR	MOLAR	CANINE	INCISOR	INCI OR	INCISOR	INCISOR	CANINE	MOLAR	MOLAR
Upper	2nd	1st	1	2nd	1st	1st	2nd	1	1st	2nd
Lower	2nd	1st	1	2nd	1st	1st	2nd	1	1st	2nd
Month of appearance	24	12	18	9	7	7	9	18	12	24

SECOND DENTITION

	MOLARS		PREMOLARS		CANINE	INCISORS		INCISORS		CANINE	PREMOLARS		MOLARS	
Upper	3rd	2nd	2nd	1st	1	2nd	1st	1st	2nd	1	1st	2nd	1st	2nd
Lower	3rd	2nd	2nd	1st	1	2nd	1st	1st	2nd	1	1st	2nd	1st	2nd
	1st												3rd	
													1st	2nd
													3rd	
Year of appearance	18	12	10	9	11	8	7	7	8	11	9	10	6	12
		6												18

of the mouth internally. The submucous base is continuous with the alveolar periosteum which dips into each tooth socket, thus forming the root membrane (pericementum). Although quite vascular the gums are not very sensitive. A portion of gingivæ projects into each interdental space and surrounds the necks of the teeth. When caries attacks a tooth the infection may spread and give rise to a subperiosteal abscess known as a gum boil. Because of the dense membrane under which the pus forms intense pain results.

The term *epulis* is applied to a class of tumors connected with the gums and the alveolar processes. This may be a simple hypertrophy of the fibrous tissue of the gums and is then known as a fibrous epulis or may spring from the periosteum, then becoming a malignant tumor.

Teeth The *teeth* begin to appear at the sixth month of life but the rudiments of both temporary and permanent teeth are present at birth. They are developed from the skin, the dentine being derived from the dermis and the covering enamel from the epidermis. There are two periods of dentition.

The result of the *first dentition* is twenty temporary or so called deciduous (milk) teeth which appear between the sixth and the twenty fourth months the lower ones preceding the uppers. There are four incisors, two canines and four molars in each

jaw but no premolars. The table above is a dental formula for the temporary teeth with the dates of eruption expressed in months.

An interval of four years follows the first dentition, and at the age of six the *permanent teeth* (*second dentition*) begin to erupt and continue to appear until the twenty fifth year. These statements can be simplified by saying that the first temporary teeth appear in the sixth or seventh months and the first permanent teeth in the sixth or seventh year. In the second dentition, the first or six year molars erupt first, the twelve year molars second, and the eighteen year molars or wisdom teeth third. Wisdom teeth may erupt late in life or not at all, failure of eruption often being the cause of cysts of the jaw.

The table at the top of this page is a dental formula for the permanent teeth, with the date of eruption expressed in years.

There are thirty two permanent teeth sixteen in each jaw, consisting of four varieties (Fig 99). (1) The *incisors* or cutting teeth. The crown of these is chisel shaped the labial surface, convex and the lingual concave. The upper and particularly the central upper incisors are large, but the lower ones are the smallest of all the teeth. The roots of the incisors are single. The upper incisors overlap the lower, and from this point onward with the exception of the last molar, every tooth

hand a thrombophlebitis of the pterygoid plexus may travel through the veins which communicate with the inferior ophthalmic vein. In cavernous sinus thrombosis following infections of the anterior teeth there is a tendency for the infection to spread via the anterior route, the anterior facial and angular veins through the orbit via the ophthalmic veins and especially by the way of the superior

In the condition known as *pyorrhea alveolaris* a purulent inflammation of the dental periosteum is present. The process involves the gingivae and the walls of the alveoli. Recession of the gums takes place until the teeth and their gingival and alveolar connections become loosened and finally fall out. As soon as the tooth is removed the inflammatory symptoms usually subside.

Hard and Soft Palates (Fig. 103). The *palate* forms the superior wall or roof of the buccal cavity. It consists of two portions, in front a hard palate which has an osseous base and posteriorly a soft palate composed of fibrous tissue.

The *hard palate* is covered by mucous membrane and forms a partition between the buccal and the nasal cavities. It is formed by the palatine processes of the maxilla and the horizontal plate of the palatine bone. The mucous membrane is peculiar in that it is practically one with the periosteum which covers the bone (mucoperiosteum). Therefore in dissecting it the bone is laid bare since the mucous membrane and the periosteum cannot be separated. The membrane is thin in the midline but thicker at the sides, the increased thickness being due to the presence of numerous glands that lie beneath the surface laterally but are absent toward the midline. Because of its toughness the membrane is easy to manipulate when flaps are being formed in the operation for cleft palate.

The main *blood supply* of the hard palate is derived from the descending palatine branches of the internal maxillary

artery, which emerges from the posterior palatine canal near the inner side of the last molar. It then passes forward and inward ending in the anterior palatine canal. The artery is so situated that it is easily injured when incisions are made for operations in cleft palate. Should this occur delayed healing or even sloughing of the flap may result. Therefore in dissecting such flaps the vessel may be spared if the incision is placed as close as possible to the gingival border and as it is extended posteriorly, it should wind about the last molar. The artery runs closer to the bone than to the mucous surface. Some surgeons advocate that the vessel be ligated deliberately as a preliminary step in the treatment of cleft palate and that actual repair be postponed for some weeks until a collateral circulation has become established.

The mucous membrane of the hard palate is noted for its numerous rugosities. The median *raphe* is very distinct and terminates in front in the incisive papilla which overlies the anterior palatine foramen. On each side of the raphe are the transverse ridges which form the *palatine rugae*. These vary in number and in prominence and become less distinct as age advances.

The *soft palate* or *vellum* is attached to the posterior edge of the hard palate and consists of connective tissue, muscles, blood vessels, nerves and glands. It is a fleshy curtain that hangs down in the isthmus of the fauces and shuts the mouth from the pharynx during nasal breathing. In deglutition or mouth breathing it is raised to a horizontal position to close the buccal portion of the pharynx from the nasopharynx and in this way prevents food from entering the nasopharynx. If the palate is paralyzed and cannot be raised the nasopharynx is unprotected and fluids are liable to be regurgitated through the nose. Although the anterior border of the palate is attached its posterior is free and presents in the midline a downward projec-




FIG 101 Alveolar abscesses and their possible paths of invasion. In the upper jaw, the infection may spread to the external bony plate into the mouth the nasal cavity or the maxillary sinus. In the lower jaw abscesses may burrow between periosteum and soft tissue or between periosteum and bone and then discharge on the neck between the jaw and the chin pus may also find its way to the floor of the mouth resulting in Ludwig's angina (see Fig 107)

in glands below the mandible and in the carotid triangle

An *alveolar abscess* (Fig 101) is a collection of pus located at the apex of the tooth. The infection in the pulp cavity invades the space between the root and the socket. The pus escapes through the surface offering the least resistance usually the external alveolar plate lateral to the apex of the tooth. It may burrow however and form a sinus some distance from the point of origin. Abscesses are less likely to occur in the upper jaw, where the blood supply is good. If such an abscess forms it may extend into the maxillary sinus or the nasal cavity. In the lower jaw pus may make a path between the periosteum and the soft tissue or between the periosteum and the bone. Pus burrowing in

such directions may discharge on the neck beneath the jaw and the chin, or into the floor of the mouth producing a Ludwig's angina (p 163). An abscess of the wisdom tooth may penetrate the lateral tissues at the angle of the jaw or occasionally pass downward into the neck, forming a large abscess in the submaxillary region.

Veins of the lower jaw (Fig 102) drain into the inferior dental vein which in turn drains into the pterygoid plexus. Those from the upper jaw drain in two directions: the anterior veins drain into the anterior facial, and the posterior into the pterygoid plexus. Following tooth extraction ascending infections may involve the pterygoid or pharyngeal plexuses from here they may travel to the cavernous sinus via the vein of Vesalius (Fig 30). On the other




FIG 103 The palate The palatine glands have been removed on the left side to show the vascular supply

petrous bone and the medial surface of the eustachian tube. It inserts into the upper aspect of the palatal aponeurosis.

2 The *tensor palati muscle* originates from the sphenoid fossa of the sphenoid bone and the lateral aspect of the eustachian tube. Its tendon winds around the hamulus and pierces the buccinator to form a broad attachment to the palatal aponeurosis and to the posterior border of the hard palate.

3 The *palatoglossus* or *glossopalatinus muscle* arises from the under surface of the palatine aponeurosis, descends in front of the tonsils in the glossopalatine arch and is inserted into the posterior aspect and side of the tongue.

4 The *palatopharyngeus* or *pharyngo-palatinus muscle* arises from the posterior border of the bony palate and from the palatine aponeurosis. It then descends behind the tonsil in the pharyngopalatine arch. It is inserted partly into the posterior border of the thyroid lamina and partly into the posterior wall of the pharynx. As it descends, it is in intimate contact with the inner surface of the constrictor muscles and lies posteromedial to the stylopharyngeus.

5 Each *musculus uvulae* arises from the posterior nasal spine and the palatine aponeurosis and inserts into the uvula. Two small muscular slips lie on either side of the midline in the substance of the uvula.




FIG 102 The venous drainage of the teeth and possible paths of extension of a thrombophlebitis. The veins of the upper jaw drain in two directions: the anterior drains into the anterior facial vein, and the posterior into the pterygoid plexus. Following a tooth extraction, these infections may travel to the pterygoid or the pharyngeal plexus. Pterygoid plexus infections can extend to the inferior ophthalmic veins or through the foramina lacerum and ovale. In cavernous sinus thrombosis following anterior teeth infections, the thrombophlebitis usually spreads from the anterior facial vein through the orbit via the ophthalmic veins, usually the superior.

tion called the *uvula*. The soft palate is attached to the lateral wall of the pharynx on each side and is uniformly about a quarter of an inch thick. Its framework is formed by the *palatal aponeurosis* which is attached to the posterior edge of the bony palate, is joined by the tendons of the palatal muscles and finally becomes lost between the muscles.

There are five muscles of the soft palate: two descend from it to the tongue and the pharynx (glossopalatine and pharyngopalatine); two descend to the palate from the base of the skull (levator palati and tensor palati); and one lies in its substance (musculus uvulae) (Fig 103).

1. The *levator palati* muscle originates from the lower surface of the apex of the




FIG. 103 The palate. The palatine gland, have been removed on the left side to show the vascular supply.

petrous bone and the medial surface of the eustachian tube. It inserts into the upper aspect of the palatal aponeurosis.

2 The *tensor palati muscle* originates from the sphenoid foramen of the sphenoid bone and the lateral aspect of the eustachian tube. Its tendon winds around the hamulus and pierces the buccinator to form a broad attachment to the palatal aponeurosis and to the posterior border of the hard palate.

3 The *palatoglossus* or *glossopalatinus muscle* arises from the under surface of the palatine aponeurosis, descends in front of the tonsils in the glossopalatine arch and is inserted into the posterior aspect and side of the tongue.

4 The *palatopharyngeus* or *pharyngopalatinus muscle* arises from the posterior border of the hard palate and from the palatine aponeurosis, then descends behind the tonsil in the pharyngopalatine arch. It is inserted partly into the posterior border of the thyroid lamina and partly into the posterior wall of the pharynx. As it descends, it is in intimate contact with the inner surface of the constrictor muscles and lies posteromedial to the stylopharyngeus.

5 Each *musculus uvulae* arises from the posterior nasal spine and the palatine aponeurosis and inserts into the uvula. Two small muscular slips lie on either side of the midline in the substance of the uvula.




FIG 102 The venous drainage of the teeth and possible paths of extension of a thrombophlebitis. The veins of the upper jaw drain in two directions: the anterior drains into the anterior facial vein, and the posterior into the pterygoid plexus. Following a tooth extraction these infections may travel to the pterygoid or the pharyngeal plexus. Pterygoid plexus infections can extend to the inferior ophthalmic veins or through the foramina lacerum and ovale. In cavernous sinus thrombosis following anterior teeth infections the thrombophlebitis usually spreads from the anterior facial vein through the orbit via the ophthalmic veins, usually the superior.

tion called the *uvula*. The soft palate is attached to the lateral wall of the pharynx on each side and is uniformly about a quarter of an inch thick. Its framework is formed by the *palatal aponeurosis* which is attached to the posterior edge of the bony palate, is joined by the tendons of the palati muscles and finally becomes lost between the *muscles*.

There are five *muscles* of the soft palate: two descend from it to the tongue and the pharynx (*glossopalatine* and *pharyngopalatine*), two descend to the palate from the base of the skull (*levator palati* and *tensor palati*) and one lies in its substance (*musculus uvulae*) (Fig 103).

1. The *levator palati* muscle originates from the lower surface of the apex of the




FIG. 105 The tongue (A) viewed from above (B) the extrinsic muscles
The glossopalatine muscle is shown in Figure 103

the palatoglossus by the hypoglossal nerve which also supplies the muscles of the tongue the tensor palati is supplied together with the tensor tympani by the third division of the fifth nerve through the otic ganglion.

The nerve supply to the mucous membrane of the soft palate is derived from branches descending from the sphenopalatine ganglion (maxillary nerve). These have been referred to as the lesser and the middle palatine nerves.

The blood supply of the soft palate is derived from branches of the ascending pharyngeal, maxillary and facial arteries.

SURGICAL CONSIDERATIONS

STAPHYLORHAPHY AND URANOPLASTY

(Fig. 104) Different types of cleft palate require different management. The name staphylorrhaphy is given to the operation that approximates a cleft in the soft

tissue and uranoplasty to that which corrects a defect in the bone. The soft parts are divided on the hard palate to the bone and then separated from it. The soft and the hard tissue edges are freed, the edges of the soft tissues are separated from the underlying bone and smoothly trimmed with a sharp scalpel. The soft parts are brought together by sutures, the periotom being included. At times retention sutures are necessary to maintain proper tension. The important features of the operation are proper mobilization and freeing of the margins of the cleft is aided with approximation of the soft parts to close the defect.

Tongue (Vessels and Nerves) The tongue is a solid mass of muscle covered by mucous membrane and attached to the floor of the mouth, the hyoid bone and the mandible. Situated below the palate above the floor of the mouth proper and in front of the pharynx it is divided into two parts




FIG 104 The surgical correction of cleft palate

The actions of the tensor and the levator palatoglossi muscles are indicated by their names. The palatoglossi muscles aid in the elevations of the dorsum of the tongue and in the closure of the oropharyngeal isthmus during the first stage of deglutition. The palatopharyngeal muscles aid in the elevation of the larynx and thus shorten the

pharynx in the second stage of deglutition. The uvular muscle shortens and raises the uvula.

The muscles of the soft palate are supplied by several nerves. The levator palati, muscle uvulae and the palatopharyngeus are supplied, with the muscles of the pharynx, by the spinal accessory nerve,




FIG 106 The nerves and vessels of the tongue (A) the nerves and blood supply the lingual vein is formed by four veins (B) the lymph drainage of the tongue the central group of lymph vessels is not shown

carotid and arises between the superior thyroid and the facial arteries. It makes a characteristic short upward hook and disappears under cover of the posterior

border of the hyoglossus muscle. Before reaching this muscle it is applied to the middle constrictor of the pharynx and then passes between the hyoglossus and the

which differ developmentally, structurally and functionally, in nerve supply and in appearance. The anterior two thirds called the oral part or *body*, has also been referred to as the buccal portion. The posterior third is the pharyngeal part or *root*. The boundary between the oral and the pharyngeal parts is marked on the dorsum of the tongue by an inverted V shaped groove called the terminal sulcus, the apex of which corresponds to a depression known as the *foramen caecum* (the upper end of the thyroglossal tract).

The *dorsal surface* (Fig 105 A) of the buccal part of the tongue presents a rough mucous membrane with numerous papillae but the dorsal surface of the pharyngeal portion is relatively pale and presents masses of lymphoid nodules called "lingual tonsils". These form the lowest part of the ring of lymphatic tissue that encircles the pharynx (Waldeyer's ring).

The three types of *papillae* characteristic of the mucous membrane of the anterior two thirds of the tongue are

1. The *vallate papillae* ten to twelve in number which lie immediately in front of the sulcus terminalis. Since they run anteriorly and parallel to the sulcus, they too are arranged as an inverted V. Each is a short cylinder surrounded by a circular trench, the outer wall of which is raised to resemble a collar. Serous glands open into the trench and taste buds lie in their walls.

2. The *fungiform papillae* are smaller than the vallate and appear as bright red spots more numerous at the tip and the margin. They are furnished with taste buds and consist of a rounded head attached by a narrow base.

3. The *filiform papillae* are the smallest and most numerous of the lingual papillae. They cover the anterior two thirds of the tongue and give it its characteristic velvety appearance. Posteriorly they are arranged in rows parallel with the sulcus terminalis but are transverse in the middle of the tongue and become irregular anteriorly. They contain the touch corpuscles.

The *inferior surface* of the tongue (Fig 97) has no papillae and is smooth. It is connected with the floor of the mouth by the frenulum on each side of which is the lingual (ranine) vein. The vessel is visible through the mucous membrane. Laterally there is a fringed fold called the *fimbriated fold*. These folds converge toward the tip and indicate the position of the deep lingual (ranine) artery which is placed deeper than the vein.

The *muscle substance* of the tongue (Fig 105 B) is divided into right and left halves by a median fibrous septum, each half being made up of both intrinsic and extrinsic muscles. The extrinsic muscles move the tongue and alter its shape but the intrinsic only alter its shape. The four *extrinsic muscles* are the *genioglossus* which protrudes the tongue, the *styloglossus* which retracts it, the *hyoglossus* which depresses it and the *glossopalatine* which elevates the root of the tongue. The four *intrinsic muscles* are the longitudinalis superior, the longitudinalis inferior, the transverse and the verticalis.

The motor nerve of the tongue (Fig 106 A) is the *hypoglossal* which supplies the entire musculature except the glossopalatine which is supplied by the pharyngeal plexus. The *glossopharyngeal nerve* supplies both taste and sensory fibers to the posterior third of the tongue. The *lingual nerve* (trigeminal) supplies sensory fibers to the anterior two thirds but the *chorda tympani* (facial) is incorporated in the lingual and supplies part of the tongue with taste fibers. Because of this arrangement the semilunar ganglion may be removed and taste remain unaffected. If the hypoglossal nerves are injured, as may occur in excision of the tongue for carcinoma or in fracture of the jaw, the *genioglossus* become paralyzed and the tongue falls backward and may produce suffocation. If only one *genioglossus* is paralyzed the protruded tongue is thrust to the paralyzed side, thus indicating the side of the lesion.

The *lingual artery* supplies the tongue (Fig 106 A), it is a branch of the external

The *massicator space* the second space is occupied by the ramus of the mandible. It is bounded externally by the masseter, internally by the pterygoids and superiorly by the temporal muscle. Infections in this

are involved resection of either may be necessary.

The *parotid* is the third fascial space of the face. It is occupied by the parotid gland. Drainage of this space can be ac-




FIG. 107. Infections about the face and the mouth. (A) the three muscular fascial spaces. (B) approach to abscesses above and below the geniohyoid muscle.

space may travel upward either to the so-called superficial or deep temporal spaces. The temporal spaces may be drained by incisions that are carried through the skin, the subcutaneous tissue and the temporal fascia. If the malar bone or the zygoma

is involved, resection of either may be necessary. The *parotid* is the third fascial space of the face. It is occupied by the parotid gland. Drainage of this space can be accomplished by an incision which is made in front of the ear and passes downward behind and below the jaw. The external surface of the parotid is thus exposed without injury to the facial nerve if the dissection is kept external to the glandular

genioglossus The hyoglossus separates it from the twelfth nerve. The artery turns upward and after supplying branches to the sublingual gland, terminates as the *profunda artery* running forward in the lower part of the tongue as far as its tip. Its only anastomosis is at the tip and because of this the tongue can be bisected almost bloodlessly.

Four veins pass backward to form the lingual vein. They are (1) the *ramus*, the chief vein of the tongue which crosses the inferior surface of the hyoglossus muscle obliquely (2) an accompanying vein which runs with the hypoglossal nerve on the outer surface of the hyoglossus muscle (3) and (4) two *venae comites* of the lingual artery which accompany the artery on the deep surface of the hyoglossus muscle. After these four veins converge to form the lingual they cross the loop of the lingual artery and both carotids and end in the internal jugular. At times they may terminate in the common facial vein.

The *lymph drainage* (Fig. 106 B) of the tongue may be divided into four groups: apical, marginal, central and posterior or basal.

1 **Apical Group** These lymph vessels start at the tip of the tongue and pass in two directions, directly to the submental glands and to the jugulo omohyoid (supra omohyoid) gland.

2 **Marginal Group** Many of these vessels pass down on the outer surface of the hyoglossus muscle. The group drains the side of the tongue and passes to the submandibular gland and to the glands of the deep cervical chain. There may be lymph nodes lying on the hyoglossus in relation to these vessels; these may be palpated if a finger is placed in the floor of the mouth and the fingers of the other hand placed beneath the jaw bone.

3 **Central Group** These are the vessels that drain the area of the tongue immediately to either side of the median raphe. They pass directly downward in the midline between the genioglossus mus-

cles and then to either the right or the left deep cervical glands.

4 **Posterior (Basal) Group** The vessels of this group drain the posterior part of the tongue, many of them passing freely from one side to the other. They enter the deep cervical chain.

In carcinoma of the tongue cancer cells may pass freely to the lymph vessels, then to the lymph glands, and may involve both sides of the neck. It is therefore necessary that all glands receiving lymph from the tongue be eradicated.

PRACTICAL CONSIDERATIONS

THREE MUSCULAR FASCIAL SPACES AND ONE VASCULAR VISCERAL SPACE

Coller and Yglesias have emphasized the fact that the fasciae in this region are attached to periosteum, enclose facial muscles and form closed spaces. In this way the spaces are separated from cervical fascial spaces, and infections do not spread into the neck but remain limited. The fasciae, however, which surround the viscera and the vessels are continuous between face and neck so that infections may travel from one to the other. These authors have described three muscular fascial spaces and one vascular visceral space (Fig. 101 A).

The *space of the body of the mandible* is that fascial space which exists between the superficial and the deep divisions of the middle muscular fasciae. It has an important bearing upon infections of this bone and because of the fascial attachment, osteomyelitis of the body of the mandible is prevented from spreading either superficially or deep. An infection in this location may do one of three things: discharge into the mouth, spread to the maxillary space, or remain localized. The space is drained through the mouth by means of an incision that goes through the gingival mucous membrane of the vestibule or by an incision through the skin along the inferior border of the body of the bone.




Fig. 109 The relations of the palatine tonsil to its capsule and the surrounding structures

oid and the mylohyoid muscles. It too is divided in the middle by a fascial septum. *Ludwig's angina* constitutes involvement of the c spaces with elevation of the tongue and inflammation of the mucous membrane over the involved area. If the infection is unilateral the tongue is pushed to the opposite side but if bilateral it is pushed upward toward the roof of the mouth. The treatment of Ludwig's angina consists of early drainage instituted in the involved space hence it is important to determine whether the abscess is below or above the geniohyoid. If the abscess is below this muscle the region under the chin is prominent and an incision should be made through the skin the subcutaneous tissue and the mylohyoid muscle into the abscess cavity. If the swelling is diffuse the incision should follow the lower border of the mandible in order that both sides of the fascial septum or both sides of this space can be properly dealt with. If the infection is situated above the geniohyoid muscle it usually points under the tongue and then can be drained through the floor of the mouth the incision passing through the mucous membrane and the genioglossus muscle. Both sides of the fascial septum should be explored.

PHARYNX

TONSILS

(Figs. 108, 109) The term tonsil usually applies to the faucial or palatine tonsils. The tonsillar region although anatomically located in the anterolateral pharynx and properly belonging to it is considered an intermediate area between the buccal cavity and the oral division of the pharynx. The tonsils are two masses of lymphoid tissue placed in the *fossa tonsillaris* and located on the surface at a point a little above the angle of the mandible. They lie between the palatoglossal and the palatopharyngeal arches above the back part of the tongue and below the soft palate. Each tonsil has *two* surfaces (medial and lateral), *two* borders (anterior and posterior), and *two* poles (superior and inferior).

The *medial surface* is free and can be seen through the mouth when the tongue is depressed. It faces inward and presents from twelve to thirty rounded or slitlike openings called the *tonsillar crypts*. Tiny plugs of food debris or pus often fill and identify these openings. This surface is covered with mucous membrane in the form of squamous epithelium which invades the substance and lines the crypts.




FIG 108 The palatine tonsil and its relations, shown in sagittal section

substance If it is desirable to drain the space between the masseter muscle and the superficial part of the parotid gland a horizontal incision is made at the level of and parallel with the superior border of the mandible

The *visceral vascular fascial space* is the lateral pharyngeal space It is bounded anteriorly by the medial wall of the masseter space laterally by the parotid space posteriorly by the carotid sheath and medially by the submaxillary gland Since this is not one of the enclosed facial fascial spaces infection may travel and involve the internal carotid artery producing severe hemorrhage or it can produce septic thrombosis of the internal jugular vein Drainage may be external through the parotid space or internal through the lateral pharyngeal wall Infection in this space can spread readily to the viscerovascular spaces of the neck and the mediastinum

UPPER AND LOWER LIP INFECTIONS

Infections in the upper lip should not be incised or squeezed Many surgeons advocate ligation of the angular vein, but this is still a moot question If pus is present some advise drainage Meningitis and the occurrence of cavernous sinus thrombosis should always be kept in mind (Fig 30)

Infections in the lower lip are less dangerous than those of the upper Cavernous sinus thrombosis rarely occurs from infections in this region because the veins lie at a deeper level and are more efficiently splinted by muscle and bone Two anatomic spaces are formed in the floor of the mouth (Fig 107 B) The superficial space lies between the geniohyoid and the geniohyoid muscles and is divided into two compartments by a median fascial septum The second space lies at a deeper level and is situated between the geniohyoid




FIG 111 Tonsillectomy

formed by the junction of the common facial with the internal jugular vein and has been referred to as the jugulodigastric gland (tonsillar gland of Wood). This may be enlarged not only in nonspecific infections but by the tubercle bacillus when it gains entrance by way of the tonsil.

The nerve supply to the tonsil is derived from the glossopharyngeal nerve and the pharyngeal plexus.

SURGICAL CONSIDERATIONS

Tonsillectomy and Peritonsillar Abscess When a tonsil is removed its cap




FIG 110 The blood supply of the tonsil

The *lateral* is the attached surface. It is covered by a fascia derived from the pharyngeal aponeurosis which is referred to as the capsule of the tonsil. This is attached laterally by loose areolar tissue to the inner surface of the superior constrictor of the pharynx. Lateral to the superior constrictor are the ascending palatine, pharyngeal and tonsillar arteries; the medial pterygoid muscle is situated lateral to these. One or more veins descend over the lateral surface of the capsule. The superior constrictor separates the tonsil from the facial artery at that point where the artery begins to arch downward.

The *upper pole* of the tonsil invades the lateral surface of the soft palate, and the *lower* is continuous with the lingual tonsil.

The *anterior border* is in contact with the palatoglossus muscle and the *posterior* with the palatopharyngeus muscle.

The *blood supply* (Fig 110) of the tonsil is very profuse, the main vessel being the *tonsillar artery*, a branch of the facial (external maxillary). This vessel enters the tonsil from its lateral aspect and near its lower pole. Other small vessels aid in the blood supply, anastomosing freely with one another. They are the ascending palatine (facial) dorsalis linguae (lingual) greater palatine (maxillary) and the ascending pharyngeal arteries.

The *veins* form a plexus which surrounds the capsule, pierce the superior constrictor and end in the pharyngeal plexus, which is a tributary of the internal jugular vein.

The *lymphatics* leave the gland, pierce the superior constrictor and end in the superior deep cervical chain. One gland is situated below the posterior belly of the digastric and the angle of the jaw. It lies on the carotid artery in the angle




FIG 111 Tonsillectomy

formed by the junction of the common facial with the internal jugular vein and has been referred to as the jugulo-facial gland (tonsillar gland of Wood). This may be enlarged not only in nonspecific infections but by the tubercle bacillus when it gains entrance by way of the tonsil.

The nerve supply to the tonsil is derived from the glossopharyngeal nerve and the pharyngeal plexus.

SURGICAL CONSIDERATIONS

Tonsillectomy and Peritonsillar Abscess. When a tonsil is removed its cap-

sule should remain attached to it. This exposes the constrictor muscle and not the aponeurosis of the pharynx. The capsule therefore is removed with the tonsil because it is firmly blended with that organ.

In tonsillectomy traction on the gland pulls it forward without dragging the pharyngeal wall and the internal carotid artery. This is explained by the laxity of the tissue which exists between the gland and the superior constrictor. However in patients who have suffered repeated attacks of quinsy this lax tissue may be replaced by dense adhesions. Tonsillar hemorrhage following surgery is the result of bleeding from the tonsillar vessels proper, since the possibility of injuring the internal carotid is most remote and the external carotid lies still farther externally.

In tonsillectomy (Fig. 111) after proper exposure with a mouth gag and tongue depressor a tenaculum is applied to the palatal pole and traction made downward and medially. This maneuver makes visible the interval between the tonsil and its anterior pillar. A sharp dissector enters this space along the anterior pillar and incises just beneath the mucous membrane which covers the tonsil. Retraction of the

anterior pillar with blunt dissection will expose the blue white capsule. If sharp dissection is preferred the point of the scissors is applied toward the tonsil side and an attempt is made to remain in the vascular cleavage plane. The tonsil is freed down to its lingual pole. A snare is then applied as low as possible on its base tightened, and the base divided. A retractor is applied to the anterior pillar for the purpose of inspection and pledgets of gauze or cotton are introduced for hemostasis by pressure. If active arterial bleeding is present the severed artery is grasped and tied with a fine suture.

In the treatment of *peritonsillar abscess*, an imaginary line should be drawn from the base of the uvula to the last molar of the same side. An incision is made at the junction of the anterior one third with the posterior two thirds along the *arcus palatinus*. This incision is spread with forceps and the pus allowed to flow out. Some surgeons advocate entering the tonsillar fossa (Fig. 108) with a curved sharp pointed forceps. The approach between the tonsil and the anterior pillar seems to be an easier method of draining the supratonsillar fossa.

SECTION TWO

THE NECK

sule should remain attached to it. This exposes the constrictor muscle and not the aponeurosis of the pharynx. The capsule therefore is removed with the tonsil because it is firmly blended with that organ.

In *tonsillectomy* traction on the gland pulls it forward without dragging the pharyngeal wall and the internal carotid artery. This is explained by the laxity of the tissue which exists between the gland and the superior constrictor. However in patients who have suffered repeated attacks of quinsy this lax tissue may be replaced by dense adhesions. Tonsillar hemorrhage following surgery is the result of bleeding from the tonsillar vessels proper, since the possibility of injuring the internal carotid is most remote and the external carotid lies still farther externally.

In *tonsillectomy* (Fig. 111), after proper exposure with a mouth gag and tongue depressor a tenaculum is applied to the palatal pole, and traction made downward and medially. This maneuver makes visible the interval between the tonsil and its anterior pillar. A sharp dissector enters this space along the anterior pillar and incises just beneath the mucous membrane which covers the tonsil. Retraction of the

anterior pillar with blunt dissection will expose the blue white capsule. If sharp dissection is preferred the point of the scissors is applied toward the tonsil side and an attempt is made to remain in the avascular cleavage plane. The tonsil is freed down to its lingual pole. A snare is then applied as low as possible on its base, tightened, and the base divided. A retractor is applied to the anterior pillar for the purpose of inspection and pledgets of gauze or cotton are introduced for hemostasis by pressure. If active arterial bleeding is present, the severed artery is grasped and tied with a fine suture.

In the treatment of *peritonsillar abscess*, an imaginary line should be drawn from the base of the uvula to the last molar of the same side. An incision is made at the junction of the anterior one third with the posterior two thirds along the arcus palatinus. This incision is spread with forceps and the pus allowed to flow out. Some surgeons advocate entering the tonsillar fossa (Fig. 108) with a curved sharp pointed forceps. The approach between the tonsil and the anterior pillar seems to be an easier method of draining the supra tonsillar fossa.

The Neck in General

EMBRYOLOGY

VISCERAL ARCHES

The branchial (visceral) arches are best developed in the human embryo about the last half of the third week of intra uterine life at which time they appear as parallel bars (11, 112). Six such arches are present and they occupy a region which later becomes the neck. They represent the gill apparatus mechanism of water breathing vertebrate in which the respiratory function is performed by means of a rich vascular tissue that lines the clefts. Water passes through these fringes permitting the exchange of the oxygen of the water and the carbon dioxide of the blood. In higher vertebrate with the acquisition of aerial respiration a loss of function in these gill arches takes place and the number is reduced from seven as seen in fish to six in man. The fifth and the sixth arches are blended with the surrounding structures so that they are not visible externally as distinct bars. Each arch has an outer covering of ectoderm (squamous epithelium) an inner covering of entoderm (columnar epithelium) and an intermediate mass of mesoderm. Between the bars internal and external depressions are found. The internal depressions are called *visceral pouches* and the external are known as *visceral clefts*. The cleft membrane is formed between the two depressions. Each arch is supplied with a plate of cartilage, a muscle mass, a nerve and an artery.

The first, or *mandibular arch* is supplied by the mandibular branch of the fifth

The numerous vessels, nerves and visceral structures found in the neck make this region both interesting and important to the surgeon. The upper limits of the neck are the lower border of the jaw, a line extending from the angle of the jaw to the mastoid process and the superior curved line of the occipital bone. The lower limits are the sternal notch, the clavicles and a transverse line from the acromioclavicular joint to the spinous process of the seventh cervical vertebra. The contour of the neck varies with age and sex being well rounded in women and children but more angular in men hence the landmarks are more conspicuous in the male. In extension the anterior part of the neck is lengthened and in flexion it is shortened so that the distance between its movable parts from the sternum to the lower jaw varies as does the relationship of these parts to the vertebrae. It is therefore necessary in giving relative positions of landmarks to suppose that the neck is midway between flexion and extension this being the natural upright position unless otherwise stated. The anterior portion of the neck contains the respiratory tube (larynx and trachea) and the alimentary tube (pharynx and esophagus); the great vessels and nerves are located on the sides and the posterior portion contains the cervical segment of the spine and surrounding musculature. The infrahyoid region extends from the hyoid bone above to the suprasternal notch below and is limited laterally by the anterior border of the sternomastoid muscles.

The Neck in General

The numerous vessels, nerves and visceral structures found in the neck make this region both interesting and important to the surgeon. The upper limits of the neck are the lower border of the jaw, a line extending from the angle of the jaw to the mastoid process, and the superior curved line of the occipital bone. The lower limits are the sternal notch, the clavicles and a transverse line from the acromioclavicular joint to the spinous process of the seventh cervical vertebra. The contour of the neck varies with age and sex, being well rounded in women and children but more angular in men; hence the landmarks are more conspicuous in the male. In extension the anterior part of the neck is lengthened and in flexion it is shortened so that the distance between its movable parts from the sternum to the lower jaw varies as does the relationship of these parts to the vertebrae. It is therefore necessary in giving relative positions of landmarks to suppose that the neck is midway between flexion and extension, this being the natural upright position unless otherwise stated. The anterior portion of the neck contains the respiratory tube (larynx and trachea) and the alimentary tube (pharynx and esophagus); the great vessels and nerves are located on the sides and the posterior portion contains the cervical segment of the spine and surrounding musculature. The infrahyoid region extends from the hyoid bone above to the suprasternal notch below and is limited laterally by the anterior border of the sternomastoid muscles.

IMPROVISED

VISCERAL ARCHES

The branchial (visceral) arches are best developed in the human embryo about the first half of the third week of intra-uterine life at which time they appear as parallel bars (Fig. 112). Six such arches are present and they occupy a region which later becomes the neck. They represent the gill apparatus mechanism of water-breathing vertebrates in which the respiratory function is performed by means of a rich vascular tissue that lines the clefts. Water passes through these fringes permitting the exchange of the oxygen of the water and the carbon dioxide of the blood. In higher vertebrates with the acquisition of aerial respiration a loss of function in these gill arches takes place and the number is reduced from seven as seen in fish to six in man. The fifth and the sixth arches are blended with the surrounding structures so that they are not visible externally as distinct bars. Each arch has an outer covering of ectoderm (squamous epithelium), an inner covering of entoderm (columnar epithelium) and an intermediate mass of mesoderm. Between the bars internal and external depressions are found. The internal depressions are called *visceral pouches* and the external are known as *visceral clefts*; the cleft membrane is formed between the two depressions. Each arch is supplied with a plate of cartilage, a muscle mass, a nerve and an artery. The first or mandibular arch is supplied by the mandibular branch of the fifth




FIG. 112 Arrangement and structure of the visceral arches in the fetus. Each arch has a nerve, an artery, a plate of cartilage and a muscle mass. The structures to which each of these gives rise have been named in the drawing.

nerve and the external maxillary artery. Its muscle mass develops into the muscles of mastication which are supplied chiefly by the mandibular nerve. This arch becomes differentiated into a shorter upper maxillary process and a longer lower mandibular one, both of which play a large part in the formation of the face. The cartilage of the first arch, referred to as Meckel's cartilage, is almost entirely replaced by the mandible, but its end persists and forms two of the ear bones, the malleus and the incus.

The *second*, or *hyoid*, *arch* is supplied by the facial nerve and its artery is the external carotid. Its muscle mass becomes the muscles of facial expression and the platysma. The cartilage of the second arch is known as the cartilage of Reichert. From it are developed the stapes, the styloid process, the stylohyoid ligament and the smaller cornu of the hyoid bone; hence it can be called the "S" arch.

The *third*, or *thyrohyoid* *arch* is supplied by the glossopharyngeal nerve and

the internal carotid artery. The muscle mass of this arch becomes the stylopharyngeus muscle and the cartilage develops into the body and the greater cornu of the hyoid bone.

The *fourth*, the *fifth* and the *sixth* arches are unnamed and somewhat indefinite. However, the fourth arch gives rise to the cricothyroid muscle which is supplied by the external branch of the superior laryngeal nerve. The muscle mass of the fifth arch forms some of the intrinsic muscles of the larynx which are supplied by the recurrent laryngeal nerve. The cartilages of the fourth and the fifth arches become the framework of the larynx. The thyrohyoid cartilage originates from arches four and five; the cricoid, the arytenoids, the rings of the trachea and the bronchi are formed from the sixth arch.

The arches enclose the primitive pharynx within which develop the important 'T' structures: Tongue, Tonsils, Tube (eustachian), Thyroid, Thymus and paraThyroids.

CERVICAL SINUS

The second visceral arch growing faster than the arches below it soon overhangs them and forms a deep groove known as the cervical sinus (Fig. 113). The downgrowing second arch eventually meets and fuses with the fifth resulting in a space lined by squamous epithelium which normally disappears. However if this space persists a *branchial cyst* results. If the second arch fails to meet the fifth an opening called a *branchial fistula* is found along the anterior border of the sternocleidomastoid muscle which is most commonly placed above the sternoclavicular joint. The cleft membrane always forms a septum between such a cyst or fistula and the pharynx. Since a branchial fistula is situated below the second arch and above the third its course can be readily understood passing between the internal and the external carotid arteries (Fig. 114). The facial and the hypoglossal nerve lie superficial to the fistulous tract and the glossopharyngeal nerve lies deep to it. If the fistula extends upward to the pharyngeal recess it will pass between the stylohyoid and the stylopharyngeus muscle.



FIG. 113 Formation of a branchial cyst and a branchial fistula in the embryo

dinal incision along the anterior border of the sternocleidomastoid muscle is advised which extends from the external fistulous opening below to the angle of the jaw. The fistulous tract is dissected from below upward and the great vessels and the surrounding nerves are protected. An assistant's finger may be inserted through

SURGICAL CONSIDERATIONS

Branchial Cysts Branchial cysts should be completely excised and since there is little adherence to the surrounding structure these procedures are usually quite simple. A transverse incision is made in a skin crease of the neck so that there is minimal scarring; the proper cleavage plane is found and the cyst is removed.

Branchial Fistulae Excision of *branchial fistulae* (lateral cervical fistulae), tends to be more difficult since there is adherence to surrounding tissues (Fig. 115). It is wise to inject such a fistula with methylene blue and determine whether or not the dye appears inside the pharynx; this also marks the fistulous tract. These operations may be long and difficult. Since complete exposure is necessary, a longitu-




FIG. 114 The course of a branchial fistula (diagrammatic)




FIG 112 Arrangement and structure of the visceral arches in the fetus. Each arch has a nerve, an artery, a plate of cartilage and a muscle mass. The structures to which each of these gives rise have been named in the drawing.

nerve and the external maxillary artery. Its muscle mass develops into the muscles of mastication which are supplied chiefly by the mandibular nerve. This arch becomes differentiated into a shorter upper maxillary process and a longer lower mandibular one, both of which play a large part in the formation of the face. The cartilage of the first arch referred to as Meckel's cartilage is almost entirely replaced by the mandible, but its end persists and forms two of the ear bones—the malleus and the incus.

The second or hyoid arch is supplied by the facial nerve and its artery is the external carotid. Its muscle mass becomes the muscles of facial expression and the platysma. The cartilage of the second arch is known as the cartilage of Reichert. From it are developed the Stapes, the Styloid process, the Stylohyoid ligament and the Smaller cornu of the hyoid bone; hence, it can be called the "S" arch.

The third, or thyrohyoid arch is supplied by the glossopharyngeal nerve and

the internal carotid artery. The muscle mass of this arch becomes the stylopharyngeus muscle and the cartilage develops into the body and the greater cornu of the hyoid bone.

The fourth, the fifth and the sixth arches are unnamed and somewhat indefinite. However, the fourth arch gives rise to the cricothyroid muscle which is supplied by the external branch of the superior laryngeal nerve. The muscle mass of the fifth arch forms some of the intrinsic muscles of the larynx which are supplied by the recurrent laryngeal nerve. The cartilages of the fourth and the fifth arches become the framework of the larynx. The thyrohyoid cartilage originates from arches four and five; the cricoid, the arytenoids, the rings of the trachea and the bronchi are formed from the sixth arch.

The arches enclose the primitive pharynx within which develop the important "T" structures: Tongue, Tonsils, Tube (eustachian), Thyroid, Thymus and paraThyroids.

the mouth to press the region of the internal opening of the fistula toward the surgeon. The incision is deepened through the skin, the superficial fascia and the platysma. The superficial layer of deep cervical fascia is then incised along the anterior border of the sternocleidomastoid which is freed and retracted posteriorly. The fistulous tract is dissected from below upward to the lower border of the posterior belly of the digastric which is retracted upward. The fistula may pass lateral to both carotids or may dip between them. The pharyngeal part of the dissection requires exact anatomic exposure. Some surgeons have suggested a step-ladder type of operation making multiple transverse incisions.

BOXY CARTILAGINOUS FRAMEWORK

The *bony cartilaginous framework* of the neck consists of the hyoid bone, the thyrohyoid membrane, the thyroid cartilage, the cricothyroid membrane, the cricoid cartilage and the trachea (Fig. 116).

The *hyoid bone* has no immediate relation with the skeleton; it lies in the soft part of the neck at the root of the tongue and possesses great mobility. Moher has noted the importance of the greater cornu and has stated that sixteen major structures of the neck (the glossopharyngeal, the recurrent laryngeal and the phrenic nerves excepted) are in close relation to it. The hyoid bone is on a level with the third cervical vertebra and its body is approximately on a level with the angles of the jaw. The upper borders of the cornu are excellent guides to the lingual arteries. The hyoid bone is therefore of great surgical importance as a landmark. The external laryngeal muscles and several muscles of the tongue and the floor of the mouth attach to it.

The *thyrohyoid membrane* is situated between the hyoid bone and the thyroid cartilage. It acts as a ligament which suspends the larynx from the hyoid and




FIG. 117 The sternocleidomastoid muscle. This structure is the most important surgical landmark in the neck.

attaches to the posterior border of the bone and its greater cornu. The interval between the bone and the cartilage varies from one to one and a half inches.

The *thyroid cartilage* consists of two laminae which are separated behind but united in front to form a projection called the *laryngeal prominence* or *Adam's apple*. The anterior borders of the laminae are joined at their lower halves but the upper halves are separated and form the V-shaped *thyroid notch* which can be felt through the skin. This is an important landmark since the common carotid arteries usually bifurcate at this level. An oblique line is usually visible on the posterior part of the lateral aspect of the lamina and it is to this line that the sternothyroid muscle inserts.




FIG 115 Excision of a branchial fistula. The incision extends along the anterior border of the sternocleidomastoid muscle from the fistulous opening below, to the angle of the jaw above. The posterior belly of the digastric muscle and the anterior border of the sternocleidomastoid muscle are retracted in opposite directions, giving adequate exposure. In this case the fistula passes between the external and internal carotid arteries. The tract is dissected from below upward.




FIG 116 The bony and cartilaginous framework of the neck.

ond and the third cervical nerves. When both muscles contract the head becomes flexed on the vertebral column but contraction of one muscle rotates the head to the opposite side and draws it down toward the chest. The sternocleidomastoid

terior muscle and the cervical plexus. The triangular interval existing between the sternal and the clavicular heads is very evident in thin individuals and appears as a slight depression. Beneath the lower end of this depression and just above the ster-




FIG. 119 The deep cervical fascia in longitudinal section. The same color identification of the three layers as was used in Figure 118 is utilized here.

separates the anterior from the posterior triangle of the neck, and many structures which are considered contents of these triangles actually lie under the muscle. These structures are the common and the internal carotid arteries, the internal jugular vein, the vagus nerve, the scalenus an-

noclavicular joint lies the common carotid on the left side and the bifurcation of the innominate artery on the right. The carotid sheath is under cover of its lower part and along its anterior border above. Along its posterior border the nerves of the cervical and the brachial plexuses are found.

and the thyrohyoid muscle takes its origin

The *cricothyroid membrane* closes the space separating the cricoid and the thyroïd cartilages. It is lozenge shaped, is widest in the midline and tapers toward

omohyoid muscle. It is also a useful guide in controlling serious hemorrhage from either carotid artery, since at this level pressure may be maintained against the tubercle of the sixth cervical vertebra.




FIG 118 The deep cervical fascia in cross section. The first or superficial investing layer has been colored red, the second or pretracheal layer is yellow, the third or prevertebral layer is blue.

the side. Through this space the simplest and most rapid tracheotomy may be performed for the immediate relief of suffocation.

The *cricoid cartilage* forms a complete ring encircling the larynx below the thyroïd cartilage. Its narrow anterior part or arch is easily felt through the skin and lies on a level with the sixth cervical vertebra. The posterior part or lamina, is much deeper, projects upward and occupies the lower part of the gap between the two laminae of the thyroïd. At this level is the junction of the pharynx and the esophagus, the larynx and the trachea, and here also the common carotid is crossed by the

THE STERNOCLEIDOMASTOID MUSCLE

The *sternocleidomastoid muscle* is the most important surgical landmark in the neck (Fig 117). It arises by two heads: the sternal head originates in front of the manubrium sterni by means of a rounded tendon and the clavicular head takes origin from the upper border and front of the medial third of the clavicle by muscle fibers. The muscle inserts on the outer surface of the mastoid process and the lateral third of the superior nuchal line. Its nerve supply is derived from the spinal part of the spinal accessory and the sec-




FIG 121 The pretracheal fascia. This fascia is a part of the general investing fascia, it arises from the deep surface of the sternocleidomastoid muscle. After passing in front of the carotid system it attaches to the thyroid gland and then splits into two layers: an anterior prethyroid layer and a posterior pretracheal layer. The thyroid has been removed to show the distribution of the fascia. The insert shows the division of the fascia into two layers.

triangle. It divides again at the posterior border of the sternocleidomastoid muscle, the two layers joining at its anterior border to form the roof of the anterior triangle.

This layer of fascia is attached above to the external occipital protuberance, the superior nuchal line, the mastoid process (base), the zygomatic arch and the lower border of the mandible. Below it is at-

tached to the acromion process and spine of the scapula, the clavicle and the manubrium sterni. Its enveloping of the submaxillary gland is accomplished by a splitting of the fascia at the lower border of the gland, the superficial layer attaching to the lower border of the mandible and the deep layer to the mylohyoid line (Figs 120 and 118). The submaxillary lymph glands are inside of this sheath and in




FIG 121 The pretracheal fascia. This fascia is a part of the general investing fascia, it arises from the deep surface of the sternocleidomastoid muscle. After passing in front of the carotid system it attaches to the thyroid gland and then splits into two layers, an anterior prethyroid layer and a posterior pretracheal layer. The thyroid has been removed to show the distribution of the fascia. The insert shows the division of the fascia into two layers.

triangle. It divides again at the posterior border of the sternocleidomastoid muscle, the two layers joining at its anterior border to form the roof of the anterior triangle.

This layer of fascia is attached above to the external occipital protuberance, the superior nuchal line, the mastoid process (base), the zygomatic arch and the lower border of the mandible. Below it is at

tached to the acromion process and spine of the scapula, the clavicle and the manubrium sterni. Its enveloping of the submaxillary gland is accomplished by a splitting of the fascia at the lower border of the gland, the superficial layer attaching to the lower border of the mandible and the deep layer to the mylohyoid line (Figs 120 and 118). The submaxillary lymph glands are inside of this sheath and in

immediate contact with the submaxillary salivary gland, therefore in the removal of the lymph glands for tuberculosis or carcinoma the salivary gland should also be sacrificed

The parotid investment is brought about by a splitting which takes place at the lower border of the parotid gland, the deeper layer passing deep to the gland and attaching to the base of the skull. The superficial layer passes superficial to the gland and attaches to the zygomatic arch, this layer is very dense and any swelling of the underlying parotid causes considerable tension and pain (mumps)

The superficial fascia splits below to form two spaces the first is over the lower part of the *posterior triangle* where it is attached to the clavicle between its layers are found the descending supraclavicular veins and part of the external jugular vein. The second space is over the lower part of the *anterior triangle* where it splits and attaches to the front and the back of the manubrium sterni forming the *suprasternal space of Burns* (Figs 119-120). This contains the sternal head of the sternocleidomastoid muscle, the communication of the anterior jugular veins (jugular arch), lymph glands and fat

MIDDLE LAYER (PRETRACHEAL FASCIA)

This layer is part of the general investing fascia and arises from the deep surface of the sternocleidomastoid muscle. It passes in front of the carotid system (internal jugular vein, common carotid artery and vagus nerve) and then divides into the prethyroid and the pretracheal layers or laminae (Figs 121 and 118)

Prethyroid Layer The *prethyroid layer* is a thin lamina which passes in front of the thyroid gland and attaches along an irregular line at the middle and posterior superficial surfaces of each lobe. It is attached to the thyroideus anteriorly and posteriorly and continues into the thorax

from the surface of the gland and from the pretracheal fascia proper by an interval filled with loose areolar tissue which has been aptly referred to by Sloan as the *posterior thyroid space* (Fig 118). This is a triangular space limited anteriorly by the *prethyroid lamina*, posteriorly by the pretracheal layer proper and medially by the thyroid gland. It is necessary to enter this space before attempting to mobilize the lobe and dislodge it medially.

Pretracheal Layer Proper The *pretracheal layer proper* passes in front of the trachea and extends behind the posterolateral border of the thyroid, thus forming the posterior boundary of the posterior thyroid space. Its fibers converge on the thyrotacheo-esophageal area where they become dense and thick and fix the thyroid gland to this area. There is no cleavage plane at this point. This has been called the *pedicle of the thyroid* and from here the fascia continues medially over the trachea and the larynx to join the pretracheal layer of the opposite side.

The vertical extent of the pretracheal fascia is from the hyoid bone above to the superior mediastinum below, where it blends with the fibrous pericardium (Fig 119).

The *suspensory ligaments of the thyroid gland* are thickened portions of the pretracheal fascia that run from the upper and inner parts of the gland to the cricoid cartilage. The ligaments form a sling that anchors the gland to the larynx which must be severed before the thyroid can be properly mobilized.

DEEP LAYER (PREVERTEBRAL FASCIA)

The *prevertebral fascia* (Figs 118, 119) also arises from the general investing fascia and is much thicker than the pretracheal. It passes behind the carotid system and covers the muscles that are applied to the cervical vertebrae (longus colli, longus scalenus anterior, medial and posterior). It is attached to the base of the occiput and continues into the thorax




FIG. 122 The buccopharyngeal fascia. (A) This fascia binds the upper part of the pharynx to the prevertebral fascia directly in the midline. (B) Acute retropharyngeal abscess involves the lymph glands in front of the prevertebral fascia and because of the attachment of the buccopharyngeal fascia presents to either side of the midline. (C) The chronic abscess usually from tuberculosis of a cervical vertebra is behind the prevertebral fascia and appears in the midline.

where it blends with the anterior longitudinal ligament of the spine. The great vessels of the neck lie on this fascia and the phrenic nerve and the anterior rami of the cervical nerves are behind it. As the roots of the brachial plexus and the subclavian artery pass under the scalenus anterior muscle they carry the prevertebral fascia with them into the axilla as the axillary sheath.

BUCCOPHARYNGEAL FASCIA

The *buccopharyngeal fascia* (Fig. 122) is a layer of connective tissue that passes around the sides and the back of the pha-

ryn timer and binds the middle of the back of the pharynx to the prevertebral fascia. This anatomic fact aids in the diagnosis and the treatment of retropharyngeal abscesses.

In the *unilateral* variety of acute retropharyngeal abscess a group of inflamed lymph glands break down which lie in the interval between the prevertebral and the buccopharyngeal fasciae. They drain the pharynx and bulge on one side of the midline because of the midline attachment of the two fasciae. The *midline* variety or chronic retropharyngeal abscess usually results from tuberculosis of a cervical vertebra and starts behind the prevertebral

The Anterolateral Region of the Neck

ANTERIOR TRIANGLE

The *anterior triangle* (Fig. 124) of the neck is bounded in front by the midline of the neck which extends from the symphysis of the mandible above to the sternal notch below behind by the anterior border of the sternocleidomastoid above by the lower border of the mandible and a line drawn backward from its angle to the posterior boundary. This triangle is subdivided into three subsidiary triangles by the anterior and the posterior bellies of the digastric and the superior belly of the omohyoid. The *digastric triangle* is bounded by the anterior belly of the digastric in front the posterior belly of the same muscle behind and the border of the mandible above. The *carotid triangle* is bounded by the superior belly of the omohyoid below the sternocleidomastoid behind and the posterior belly of the digastric above. The *muscular triangle* is bounded by the superior belly of the omohyoid above the sternocleidomastoid below and the midline of the neck in front. That region of the neck which is bounded by the body of the hyoid bone below and the anterior bellies of the digastric on each side forms the *submental triangle*.

SUPERFICIAL STRUCTURES (SKIN SUPERFICIAL FASCIA PLATYSMA AND LYMPH NODES)

The *skin* of the neck is loosely attached especially anteriorly. Since it is well supplied with blood vessels it favors plastic surgery. The skin that covers the posterior region is very thick adherent and contains numerous sebaceous glands which explains

the frequency of furuncles and carbuncles in this area.

The *superficial fascia* of the neck consists of fat and connective tissue. It is not clearly defined and is difficult to demonstrate.

The *platysma myoides* is a rhomboidal muscle lying in the superficial fascia of the neck (Fig. 125). It originates from the fascia of the pectoralis major and the deltoid and inserts into the lower border of the mandible; its fibers converge as they pass upward and medially. Some of the fibers reach the face and mingle with the risorius and other depressor muscles. Its posterior border is free covers the lower anterior part of the posterior triangle and continues across the base of the jaw to the angle of the mouth. Its anterior border decussates behind the chin. Since it is a muscle of expression it is supplied by the cervical branch of the facial nerve which reaches its deep surface. Branches of the anterior cutaneous nerve of the neck pierce it. In some individuals it is well developed and in others it is difficult to find. It is lacking in the midline of the neck and therefore cannot be sutured in this location. Between the muscle and the underlying superficial layer of deep cervical fascia lie the anterior and the external jugular veins and the cutaneous nerves of the neck. Incisions in the neck bleed freely before the deep fascia is cut because the retraction of the divided platysma holds the cut veins open and prevents them from retracting. When the deep fascia is divided however, the veins are able to retract and most of the oozing stops.




FIG 125 The submental triangle. The superficial layer of deep cervical fascia has been incised to show the lymph drainage of the triangle.

fascia. Should it bulge into the pharynx it would be centrally located; it may then travel laterally behind the prevertebral fascia and point at the posterior border of the sternocleidomastoid muscle.

SUBMENTAL TRIANGLE

The *submental triangle* (Fig 125) has as its base the body of the hyoid bone and as its apex the symphysis of the mandible. It is bounded laterally by the anterior bellies of the digastric muscles. The roof of the triangle is made up of the investing layer of deep cervical fascia and its floor is formed by the mylohyoid muscles with their median raphe. The triangle contains the *submental lymph glands* which

drain the superficial tissue below the chin, the central part of the lower lip, the adjoining gums, the anterior part of the floor of the mouth and the tip of the tongue. The efferent vessels from these glands pass to join the submandibular (submaxillary) lymph glands. When they enlarge or become abscessed they are usually prevented from rising into the mouth by the mylohyoid muscles.

Wide incisions may be made into this area because there are no important structures that can be injured. After incising the investing layer of deep cervical fascia, location of the digastric and the mylohyoid muscles will immediately orient the surgeon.




FIG 126 The four superficial nerves of the neck. These are cutaneous nerves and all of them are related to the posterior border of the sternocleidomastoid muscle. The insert shows the plan of the veins in this region

The external jugular lymph nodes are usually found as a cluster lying upon and near the external jugular vein as it approaches the region of the parotid gland. They are superficial to the superficial layer of the deep cervical fascia and when not diseased are small or even absent. They receive lymph from the external ear in the parotid region and drain into the deep nodes which lie upon the carotid sheath

beneath the sternocleidomastoid muscle. Since they are on and not under the deep fascia it is a safe and simple procedure to eradicate or incise them but the position of the external jugular vein should be kept in mind.

NERVES

There are four superficial nerves associated with the posterior border of the




FIG 124 The triangles of the neck




FIG 125 The platysma muscle. A wedge of muscle has been cut out on the left to show the underlying nerves. The insert shows the true position of the platysma, in the superficial fascia.

crossed superficially by the common facial vein passes deep to the posterior belly of the digastric and the submaxillary gland and enters the submandibular region where it is distributed to the muscles of the tongue. As the nerve continues forward it comes to lie superficial to the hyoglossus muscle which separates it from the lingual artery, then continues in an intermuscular cleft between the hyoglossus and the mylohyoid to the muscles of the tongue (Fig. 106 A). The *ascending branch* of the hypoglossal nerve leaves its parent trunk where it bends forward to cross the carotid vessel. The *descending branch* continues downward on the surface of the internal and the common carotid arteries and is imbedded in the anterior wall of the carotid sheath. From its lateral side it is joined by the descending cervical nerve (second and third cervicals) which arises from the cervical plexus and the nerve loop so formed constitutes the *ansa hypoglossi*. Branches from this anastomosis are distributed to the sternohyoid, the sternothyroid and both bellies of the omohyoid. The thyrohyoid receives its own nerve from the first cervical via the hypoglossal.

The *cervical plexus* should not be confused with the cervical sympathetic groups (Fig. 128). The plexus lies on the scalenus medius and the levator anguli scapulae under cover of the sternocleidomastoid muscle. It is formed by the upper four cervical nerves, all but the first of which divides into two parts. A branch from each nerve joins the superior cervical ganglion. These nerves are combined in irregular series of loops under cover of the sternocleidomastoid. The roots of the plexus lie deep to the prevertebral fascia and are frequently injured in radical neck surgery. The terminal branches pierce the fascia and continue to the muscles which they supply and the nerves with which they connect. The superficial cutaneous branches radiate from the plexus and appear in the supraclavicular region as they wind around the posterior margin of the sternocleidomastoid muscle.

Of the muscular or deep branches the *phrenic* is the most important. It is derived from the fourth cervical but receives additional fibers from the third and the fifth. It passes downward in the neck and lies deep to the prevertebral fascia traveling on the anterior scalene muscle. It enters the thorax at the root of the neck on its way to the diaphragm.

The *superficial branches* of the cervical plexus, all cutaneous, are the cutaneous colli, the lesser occipital, the great auricular and the descending, supraclavicular nerves (Fig. 126). The *deep branches* are muscular and divide into anterior and posterior branches. The *anterior branch* supplies the thyrohyoid, the geniohyoid, the rectus capitis lateralis, the rectus capitis anterior, the longus capitis, the longus colli, the scalenus anterior and the intertransversarius. The *posterior branch* supplies the sternocleidomastoid, the levator scapulae, the trapezius and the scalenus medius muscles. Communicating branches also are found which travel to the sympathetics and the hypoglossal muscle.

The *cervical sympathetic group* (Fig. 128) consists of three ganglia with connecting branches which form a chain lying behind the carotid sheath and upon the prevertebral fascia. It extends from beneath the mastoid process to the first rib. The ganglia are known as the superior, the middle and the inferior and have been called respectively carotid, thyroid and vertebral from their almost constant association with the carotid arteries. The *superior* or *carotid* is the largest ganglion in the neck. It lies in front of the transverse processes of the second and the third cervical vertebrae on the longus capitis and behind the carotid sheath. It is fusiform in shape and sends a branch downward to connect with the middle ganglion. The *middle* or *thyroid* ganglion is the smallest of the three and some authors state that it is inconstant or absent. This error may be due to the fact that the ganglion some

sternocleidomastoid muscle which supply the skin of this region (Fig. 126). They are derived from the anterior primary rami of the second, the third and the fourth cervical nerves through the branches of the cervical plexus, which lies under cover of the muscle. The *lesser occipital* nerve (second cervical) appears at the junction of the middle and upper thirds of the posterior border of the sternocleidomastoid where it hooks around the accessory nerve; it passes upward and backward along the posterior border of that muscle to supply the skin over the lateral part of the occipital region. The *great auricular* nerve (second and third cervicals) appears at a slightly lower level, runs parallel with the external jugular vein and enters the nuchal region posterior to the ear; it supplies the skin over the angle of the jaw, the parotid gland, the postero-inferior half of the lateral and medial aspects of the auricle and the skin over the mastoid region. The *anterior cutaneous* nerve (cutaneous colli; second and third cervicals) appears close to the great auricular nerve but runs transversely forward across the sternocleidomastoid and beneath the external jugular vein; it supplies the region about the hyoid bone and the thyroid cartilage. The *supraclavicular* nerve (third and fourth cervicals) appears at a slightly lower level than the preceding ones. The anterior (medial) supraclavicular travels downward and medially across the lower part of the sternocleidomastoid; the middle (intermediate) runs across the clavicle and the posterior (lateral) extends downward and laterally across the trapezius and the acromial end of the clavicle.

The *last four cranial nerves*, in their extracranial courses, are located in the region of the digastric muscle (Fig. 127). The *vagus* (tenth cranial) nerve leaves the skull through the jugular foramen and at its exit is closely related to the ninth, the eleventh and the twelfth nerves; the internal jugular vein lies posterior to it and the internal carotid artery is anterior. In the

neck, the *vagus* supplies the alimentary and the respiratory tubes by means of its branches, the pharyngeal, the superior and the recurrent laryngeal. The *glossopharyngeal* nerve (ninth cranial) leaves the skull through the jugular foramen with the *vagus* and the accessory, but in its own sheath of dura mater. It descends between the internal jugular and the internal carotid vessels to the lower border of the stylopharyngeus around which it winds and then passes forward between the internal and the external carotid arteries. Its one motor branch supplies the stylopharyngeus muscle. The *spinal accessory* nerve (eleventh cranial) has a double origin, spinal and cranial. The spinal part arises from the upper five or six segments of the spinal cord and the cranial is accessory through the *vagus*. It makes an abbreviated appearance in the carotid triangle between the digastric and the sternocleidomastoid muscles. As it enters the deep surface of the sternocleidomastoid about two inches below the tip of the mastoid process, it is surrounded by lymph glands and is accompanied by the sternocleidomastoid branch of the occipital artery. It appears about the middle of the posterior border of the sternocleidomastoid muscle and here again is surrounded by lymph glands. The accessory nerve supplies the sternocleidomastoid and the trapezius; its cervical branches are entirely sensory. The *hypoglossal* nerve (twelfth cranial) is the motor nerve of the tongue. It emerges from the skull through the anterior condylar (hypoglossal) canal in the occipital bone and is in close contact with the ninth, the tenth and the eleventh cranial nerves. It lies between the internal jugular vein and the internal carotid artery and as it descends is closely related to the *vagus* until it appears at the lower border of the posterior belly of the digastric. Here it turns forward and medially and crosses in turn the internal carotid, the occipital and the external carotid arteries and the loop of the lingual artery. As it crosses the lingual artery, the hypoglossal nerve is




FIG 128 The cervical sympathetics. This group consists of three ganglia with their connecting branches. The ganglia are known as superior, middle and inferior and have been called carotid, thyroid and vertebral, respectively, from their almost constant association with these arteries. The insert shows these relationships. The cervical plexus should not be confused with the cervical sympathetic group. The plexus is formed by the upper four cervical nerves and lies on the scalenus medius muscle.




FIG. 127 The last four cranial nerves in their extracranial courses. These nerves are closely related to the posterior belly of the digastric muscle. The formation of the ansa hypoglossi is also shown.

times occupies a lower position nearer the inferior ganglion of which it has been considered a part. It lies on a level with the sixth cervical vertebra in front of or behind the inferior thyroid artery. The inferior or vertebral ganglion is next in size to the superior. It is found behind the vertebral artery between the neck of the first rib and the transverse process of the seventh cervical vertebra. At times it

unites with the first thoracic sympathetic ganglion to form the stellate ganglion. Since it is beneath the vertebral artery just as the latter is given off from the subclavian it makes surgical approach to the ganglion difficult. Some of the fibers that connect the middle with the inferior cervical ganglion descend in front of the subclavian artery and then upward behind it to form the so called *ansa subclavia*.

the subclavius muscle are the most common varieties of accessory phrenics found. During avulsion the phrenicopericardial vessels may be torn producing an internal hemorrhage. An incision about two inches long is made starting at the posterior border of the sternocleidomastoid muscle and placed about a fingerbreadth above the clavicle (Fig 129A). This will be situated over the scalenus anterior muscle which is easily palpable. The incision is deepened through the platysma where the superficial cervical nerve and the external jugular vein come into view; these may be divided or retracted. The posterior border of the sternocleidomastoid is identified and cleansed; as is the belly of the omohyoid. The deep cervical fascia which forms a cover for the scalenus anterior is identified and incised and the underlying adipose tissue is noted. This fat is an important guide since the muscle is not immediately visualized when the cervical fascia has been severed. The subfascial fat is dissected free and the scalenus anticus is exposed. As the muscle is cleared the phrenic nerve appears toward its medial aspect as a thin white cord running downward and slightly toward the midline. The transverse cervical and supra-scapular arteries clamp the phrenic nerve down onto the scalenus anterior in this fatty tissue (Fig 129B). These vessels should be looked for and retracted since they might cause annoying hemorrhage and make exposure difficult (p 246). Pinching the phrenic produces pain in the neck, the shoulder or the arm and dilation of the corresponding pupil. After proper identification the nerve can be divided, retracted, injected or avulsed by slowly winding the distal end upon a hemostat (Fig 129C). The thoracic duct should be protected while operating on the left phrenic nerve.

Stellate Ganglionectomy. This is particularly useful in dealing with amputation stump neuralgia, painful traumatic arthritis and causalgia when these are associated with vasospasm which responds to diagnostic procaine injections. It has also been utilized in angina pectoris, bronchial asth-

ma and hyperhidrosis. Many techniques have been used in cervical sympathectomies and ganglionectomies but the following is one of the most common methods employed. A transverse incision is made about a fingerbreadth above the clavicle and carried laterally two inches from the sternal head of the sternocleidomastoid muscle (Fig 130A). The clavicular head of the muscle is divided thus centering the incision over the vertebral artery. The omohyoid which travels obliquely across the field is divided and the deep cervical fascia exposed and incised. The carotid sheath is retracted anteriorly and the phrenic nerve is located on the scalene anterior muscle; this too is retracted toward the midline (Fig 130B). The anterior scalene muscle is cut just above its insertion into the first rib which exposes the upper three thoracic ganglia and the proximal portion of the subclavian artery with its thyrocervical trunk and vertebral branches. The thyroïd axis is ligated and cut and the subclavian artery is retracted downward. The stellate ganglion can now be visualized; it is adherent to the lateral surface of the seventh cervical and the first thoracic vertebrae. The thoracic duct should be protected when the operation is performed on the left side. Sibson's fascia which attaches the apex of the pleura to the posterior part of the first rib is cut. The entire apical pole can then be freed by blunt dissection to about the level of the third rib. This should permit visualization of the inferior cervical and the first thoracic ganglia (Fig 130C). It should be remembered that this may appear as a double ganglion which is shaped like a dumb bell with an isthmus or may appear as a single mass. Its lower part lies in front of and against the head of the first rib; its upper pole is connected with the lower trunk of the brachial plexus by fine rami which give it a star-shaped appearance hence the name "stellate." It is dissected free and the nerve chain is followed down as far as the third thoracic ganglion. The incision is closed in layers.




FIG 129 Phrenic avulsion (A) The incision starts at the posterior border of the sternocleidomastoid muscle, one fingerbreadth above the clavicle (B) The deep cervical fascia is incised and the subfascial fat, which is an important guide is identified. The transverse cervical and suprascapular arteries clamp the phrenic nerve onto the scalenus anterior muscle (C) The phrenic nerve is avulsed

SURGICAL CONSIDERATIONS

Phrenic Avulsion The phrenic nerve is usually described as originating from the fourth cervical, however, it has been found originating from the first, second, third,

fifth and sixth cervicals and the first dorsal nerves. Accessory phrenics are present at times and for this reason the operation of avulsion is to be preferred. Fibers of the fifth cervical traveling with the nerve to




FIG 131 The four infrahyoid muscles (A) the two superficial muscles are seen on the right side and the two deeper ones on the left (B) the nerve supply

MUSCLES

The *infrahyoid* muscles have been referred to as the depressors of the larynx and also as the strap or ribbon muscles. The four muscles making up this group are the sternohyoid, the omohyoid, the sternothyroid and the thyrohyoid. The first two lie side by side and cover the other two (Fig 131A). All are supplied by branches of the anterior rami of the first, second and third cervical nerves by means of the hypoglossal nerve and the ansa hypoglossi which approach the muscles from

the lateral side. The nerves pass between the superficial and the deep muscles and enter their opposed surfaces (Fig 131B).

The sternohyoid muscle arises from the posterior surface of the manubrium sterni and the adjoining part of the clavicle continues upward and medially and inserts into the medial part of the lower border of the body of the hyoid bone. At its origin it is separated from its fellow of the opposite side by an interval of 4 to 6 cm. but as they ascend they gradually converge so that at the point of insertion both muscles




FIG. 130 Stellate ganglionectomy (A) Transverse incision placed a fingerbreadth above the clavicle and continued laterally two inches from the sternal head of the sternocleidomastoid muscle (B) The clavicular head of the sternocleidomastoid (the omohyoid and the deep cervical fascia) have been divided exposing the scalenus anticus muscle and the phrenic nerve. The subfascial fat is the important landmark in this part of the dissection (C) The scalenus anticus muscle has been divided and the thyrocervical trunk ligated and severed. With downward retraction of the subclavian artery and the apex of the lung, the stellate ganglion becomes visible (D) Anatomic relations in the root of the neck.

the hyoglossus muscle and is overlapped by the submaxillary gland. The latter is a good guide to the intermediate tendon and the intermediate tendon in turn is a good guide to the hyoglossus muscle. The nerve

their origin are found the common carotid artery, the internal jugular vein and the vagus nerve. The fascia immediately surrounding these structures, the pretracheal in front and the prevertebral behind, form




FIG. 132 The carotid sheath. This is formed by the pretracheal fascia in front and the prevertebral fascia behind, both fasciae originate from the general investing layer of deep cervical fascia.

supply of the muscle is derived from two sources. The posterior belly is supplied by the facial nerve as it leaves the stylomastoid foramen and the anterior belly by the nerve to the mylohyoid from the trigeminal nerve. Therefore the posterior belly receives its nerve supply from the seventh cranial and the anterior belly from the fifth cranial nerve.

VESSELS AND CAROTID SHEATH

The general investing layer of the deep cervical fascia gives rise to two sheaths which originate from the deep surface of the sternocleidomastoid (Fig. 132). These two offshoots are the pretracheal and prevertebral layers. Between them and near

the carotid sheath which extends from the base of the skull to the root of the neck. The sympathetic trunk is imbedded in its posterior wall, the descendens hypoglossi in the anterior wall and the descendens cervicalis, the cervical branches of the vagus and the internal jugular vein pierce it. Although the structures are surrounded by this tubelike fascia they also are imbedded in fibrous tissue that is derived from it so that each structure has its own coat. The vein is external to the artery and almost entirely covers it. The sheath is applied to the side of the cervical vessels, namely the esophagus, the pharynx and the thyroid gland.

Carotid Arteries (Fig. 133) The com

lie in contact with each other. The interval between the two muscles is filled by the pretracheal fascia. Contraction of this muscle depresses the hyoid bone. The *omohyoid* muscle consists of an inferior belly, an intermediate tendon and a superior belly. It lies in the same plane as the sternohyoid. The inferior belly arises from the upper border of the scapula and the suprascapular ligament crosses the posterior triangle of the neck and passes deep to the sternocleidomastoid and ends as the *intermediate tendon*. It lies on the surface of the carotid sheath and is bound to the clavicle by the deep cervical fascia which forms a fascial sling. Its tendon gives origin to the superior belly which passes upward and medially superficial to the common carotid artery and along the lateral border of the sternohyoid. It becomes inserted into the lower border of the body of the hyoid bone. The *omohyoid* abruptly bends away from the sternohyoid below the level of the cricoid cartilage. Unlike the digastric the two bellies of the omohyoid are supplied by the same nerve since the inferior belly is a backward extension of the superior. Its action depresses the hyoid bone and draws it backward and laterally.

The two deeper muscles *thyrohyoid* and *sternothyroid* are divided into a muscle above and one below the oblique line of the thyroid cartilage where both attach (Fig. 131). The *sternothyroid* is of considerable surgical importance. It is perhaps the most important surgical landmark in thyroid surgery and, if properly identified, can aid in finding the correct cleavage plane. It must be emphasized that a distinct cleavage plane exists between the sternohyoid and the sternothyroid muscles and very often the surgeon believes that he has cut both muscles when in reality only the more superficial sternohyoid has been severed. If the thyroid gland is enlarged the sternothyroid becomes so thin that it is not clearly visualized. If this should occur, then the true capsular structures and the cleavage planes

are lost, and the operation proceeds with great difficulty and much hemorrhage. The muscle arises from the posterior aspect of the manubrium sterni, extends upward deep to the sternohyoid and covers the lobe of the thyroid gland. It is inserted into the oblique line on the lamina of the thyroid cartilage. The lower border converges on its fellow as it descends until their medial borders just meet at the center of the manubrium. Its contraction depresses the larynx. The *thyrohyoid* muscle is a short quadrilateral structure which appears to be a continuation of the sternothyroid. It arises from the oblique line on the thyroid cartilage passes upward and is inserted into the lower margin of the hyoid bone. The muscle is fairly thick, covers the thyrohyoid membrane and projects laterally to the omohyoid. It depresses the hyoid bone but when the bone is fixed by the suprathyoid muscles it acts as an elevator of the larynx.

The *digastric muscle* constitutes another important surgical landmark and guide in the upper part of the neck. Its name suggests that it has two bellies that are connected by a common tendon. The *anterior belly* runs forward medially and upward from the common tendon to attach to the lower border of the mandible near the midline. It is placed on the surface of the mylohyoid muscle and is partly overlapped by the submaxillary gland. The *posterior belly* arises from the mastoid part of the temporal bone and is covered by the mastoid process and the sternocleidomastoid muscle, but as it passes downward, forward and medially it becomes visible. It crosses superficially to the internal jugular vein, the accessory, the vagus and the hypoglossal nerves, the occipital, the internal and the external carotids and the facial (external maxillary) arteries. The common or so called *intermediate tendon* is attached to the body of the hyoid by a pulley like band of fascia. This tendon perforates the stylohyoid muscle, lies on

cover of the anterior border of the sternocleidomastoid muscle in the direction of the mandible. When it reaches the level of the upper border of the thyroid cartilage it forms a dilation known as the *carotid bulb* and then divides into its two terminal branches the internal and the external carotid arteries. Throughout its course it is imbedded with the internal jugular vein and the vagus nerve in the connective tissue that constitutes the carotid sheath. The vein lies on the lateral side of the artery and when full of blood overlaps it anteriorly. The vagus nerve lies posteriorly between the artery and the vein. Usually the only branches of the common carotid are its terminal ones but occasionally when its bifurcation is at a higher level the ascending pharyngeal or the superior thyroid may arise from it. *Internally* in addition to the superficial structures this artery is covered by the anterior border of the sternocleidomastoid muscle. Between the muscle and the artery in the lower part of the neck the following structures intervene the superior belly of the omohyoid the sternohyoid and the sternothyroid muscles. In the upper part of its course the descending ramus of the hypoglossus and the ansa hypoglossi are imbedded in the anterior wall of the sheath and the common facial vein usually crosses the artery at its termination. *Posteriorly* the artery is related to the anterior tubercles of the transverse processes of the lower four cervical vertebrae and the muscles that attach here namely the scalenus anterior and the longus capitis. It is separated from these structures by the prevertebral fascia and the sympathetic trunk. In the lower part of the neck it lies in front of the vertebral artery as it ascends to the foramen and the transverse process of the sixth cervical vertebra and in front of the inferior thyroid artery which arches medially to the thyroid gland. On the left side the thoracic duct crosses behind the vessel and below the inferior thyroid artery. *Medially*, it is

related to the inferior constrictor muscle of the pharynx and the thyroid gland. The lobe of the thyroid lies either medial to the artery separating it from the esophagus the pharynx the trachea and the larynx or it may form a direct anterior relation. *Laterally* it is related to the internal jugular vein and the vagus nerve.

The *internal carotid artery* is the larger of the two terminal branches of the common carotid. It is distributed to the brain and to the eye and its appendages. From its origin at the upper border of the thyroid cartilage it passes to the carotid canal of the temporal bone. It turns forward in the cavernous sinus perforates the dura mater on the inner side of the anterior clinoid process and divides into the anterior and the middle cerebral arteries. Below the posterior belly of the digastric the artery is overlapped by the anterior border of the sternocleidomastoid and the more superficial structures the hypoglossal nerve the occipital artery and the common facial vein are interposed between it and the muscle. Above the artery ascends under cover of the posterior border of the digastric and the stylohyoid and is crossed by the posterior auricular artery. It passes beneath the styloid process and the stylopharyngeus muscle. These two structures are placed between the artery and the parotid gland in which the external carotid artery and the posterior facial vein are imbedded. The internal carotid has no branches in the neck. It may be difficult to distinguish between the internal and the external carotid arteries. Even in a well planned operation for ligation one has been mistaken for the other hence the following points should be noted the internal carotid furnishes no branches in the neck but the external has three anterior branches the vessel is not really internal but at its origin is posterolateral to the external vessel as it ascends it passes to the medial side of the external carotid toward the lateral wall of the pharynx.




FIG 133 The carotid arteries. The internal carotid is more posterolateral than internal, and as it ascends it lies medial to the external carotid. The external carotid has eight branches: five of which are below and three above the digastric muscle.

Common carotid artery arises differently on the two sides: the right arises as a terminal branch of the innominate behind the sternoclavicular joint; the left originates in the thorax from the arch of the aorta, passes

upward and to the left and enters the neck behind the left sternoclavicular joint. This is the largest artery in the neck and as it passes from behind the sternoclavicular joint, it runs upward and backward under

triangle the vessel is partially covered by the angle of the mandible and is crossed by the posterior belly of the digastric and the stylohyoid muscles. Within the substance of the parotid gland the posterior facial vein is superficial to the artery and both of these vessels are crossed in turn by branches of the facial nerve. In its entire course the vessel is accompanied by numerous sympathetic ganglia which constitute the *external carotid plexus*.

Collateral anastomoses between the internal and the external carotids are usually adequate to maintain circulation after ligation of either of the vessels. Many anastomotic connections exist between the arteries of the ophthalmic region of the internal carotid and the facial region of the external. Communications exist between the external carotid artery and the thyrocervical trunk through the superior thyroid branch of the former and the inferior thyroid branch of the latter. A communication between the vertebral and the internal carotid arteries via the posterior communicating artery of the circle of Willis is also present. Other communications between the lingual the facial the occipital the posterior auricular and the ascending pharyngeal arteries connect the external carotids of the two sides. The internal carotid arteries communicate across the base of the brain by the anterior communicating artery and with the basilar trunk. When the common carotid is ligated circulation is not interfered with anatomically or clinically unless the anastomotic paths are disturbed by vascular degenerative changes due to age or other pathologic processes.

External and Internal Jugular Veins (Figs 134-135) The *external jugular vein* varies in size. It is formed below the lobule of the ear by the union of the posterior auricular vein with a branch of the posterior facial. It begins at the lower part of the parotid gland runs almost vertically downward crosses the sternocleidomastoid muscle obliquely and in the angle between

the clavicle and the posterior border of that muscle pierces the deep cervical fascia to which it is firmly bound. It then joins the subclavian vein. It lies upon the superficial layer of deep cervical fascia beneath the platysma muscle and at times may be absent or very small. It is so closely associated with the platysma that when the latter is reflected the vein remains attached to it. If one external jugular is large the other is small and if both are large then the internal jugulars are correspondingly small. The external communicates with the internal jugular via a branch which turns around the anterior border of the sternocleidomastoid. At times it receives a posterior jugular vein from the back of the neck. At its termination the external jugular is joined by the transverse cervical the suprascapular and the anterior jugular veins.

The *internal jugular vein* begins at the jugular foramen about half an inch below the base of the skull as a continuation of the sigmoid (transverse) sinus. It passes downward and forward through the neck and ends behind the upper border of the sternal end of the clavicle where it meets the subclavian and forms the innominate vein. It is markedly dilated at its origin forming the superior bulb that lies in the jugular foramen and the fossa. This bulb is larger on the right side because the superior sagittal sinus usually turns to the right. The inferior bulb is a dilation of the vein below a bicuspid valve which is situated about half an inch above the clavicle. The junction of the internal jugular and the subclavian veins is separated from the lower part of the sternoclavicular joint by the two infrahyoid muscles.

The *tributaries* (Fig. 134B) of the veins in this region are (1) the *inferior petrosal sinus* which helps to drain the cavernous sinus and leaves the skull through the anterior part of the jugular foramen to join the upper end of the internal jugular. (2) The *pharyngeal veins* from the plexus on the side of the pharynx pass either super-

The *external carotid artery* is the smaller of the two terminal branches of the common carotid and extends from the upper part of the thyroid cartilage to the neck of the mandible where it divides into its two terminal branches the superficial temporal and the maxillary (internal) arteries. This carotid has been called "external" not because of its location which is really internal and superficial to the internal carotid, but because of the fact that it is distributed to parts outside of the skull. Near the angle of the jaw it is crossed by the posterior belly of the digastric and the stylohyoid muscles. Above this it is at first deep to and then enclosed by the substance of the parotid gland where it terminates opposite the neck of the mandible by dividing into its two terminal branches. In its short course before entering the substance of the parotid it is applied to the inferior and the middle constrictor muscles. The vessel has eight branches: five below the digastric muscle and three above it (Fig. 133).

The five branches below the digastric muscle are: (1) the *superior thyroid artery*, which arises from the anterior aspect of the external carotid near its origin. It passes downward and forward under cover of the omohyoid, the sternohyoid and the sternothyroid muscles parallel with but superficial to the external laryngeal nerve. It reaches the upper pole of the thyroid gland to which it is distributed. Its branches are the infrahyoid, the superior laryngeal, the sternocleidomastoid, the cricothyroid, the isthmus, the glandular and the muscular. (2) The *lingual artery* arises opposite the greater cornu of the hyoid bone, makes an upward loop, disappears under cover of the hyoglossus muscle and enters the submandibular (submaxillary) region (p. 158). The loop of this artery is crossed superficially by the hypoglossal nerve. (3) The *facial (external maxillary) artery* arises near the angle of the mandible, is directed upward and forward on the superior constrictor muscle, beneath the digastric, it continues in a groove on

the deep surface of the submandibular gland to the body of the mandible and ascends to the face, anterior to the masseter muscle (p. 119). (4) The *ascending pharyngeal artery* arises from the deep aspect of the external carotid close to its origin and continues upward, medial to the internal carotid on the side wall of the pharynx. It is usually small and supplies the pharynx, the soft palate and the meninges. (5) The *occipital artery* arises from the posterior aspect of the external carotid opposite the facial and continues upward and backward deep to the posterior belly of the digastric. It is crossed by the transverse part of the hypoglossal nerve at its origin, follows the posterior belly of the digastric and is in contact with the skull medial to the mastoid notch, lying deep to the process in the muscles that attach to it. It anastomoses with the deep cervical branch from the costocervical trunk and thus forms a link between the subclavian and the carotid systems.

The branches of the external carotid artery above the digastric muscle are three in number. The *posterior auricular artery* generally arises at or above the upper border of the muscle and in the parotid region. It becomes superficial as it crosses the base of the mastoid process and ascends behind the auricle. It supplies the area of the auricle on the back of the scalp. The two terminal branches of the carotid, the *superficial temporal* and the "*internal*" *maxillary* have been discussed elsewhere (p. 157).

The *superficial relations* of the external carotid artery are in the carotid triangle: the vessel is covered by skin, superficial fascia, platysma, branches of the anterior cutaneous nerve of the neck, the cervical branch of the facial nerve and the deep fascia. Beneath the deep fascia, the artery is crossed by the common facial and lingual veins and the hypoglossal nerve. At the upper part of the triangle the anterior branch of the posterior facial vein crosses the artery, and after leaving the carotid




FIG 135 The anterior external and internal jugular veins. The sternocleidomastoid muscle has been cut and reflected on the left side

utaries of this vein which form a trunk at a higher level. It crosses superficially to the common carotid artery and joins either the common facial or the internal jugular vein. (6) The middle thyroid vein passes laterally and deeply to the infrahyoid muscles. It crosses superficially to the common carotid artery and ends in the internal jugular at the level of the cricoid cartilage.

The internal jugular vein is enclosed in the carotid sheath. Its uppermost part lies

behind the internal carotid artery and posterolateral to the last four cranial nerves. As the vein descends it lies laterally to the common carotid and overlaps it; hence in exposing the artery its sheath should be opened toward the inner side to avoid injuring the vein. Its superficial relations are the most complicated and the most important surgically. Throughout the greater part of its course the internal jugular lies under the sternocleidomastoid muscle but in




FIG 134 Lateral view of the veins of the neck. (A) the platysma has been reflected to show the external jugular vein and the sternocleidomastoid has been cut to show the internal jugular (B) tributaries of the internal jugular vein

ficially or deeply to the internal carotid artery and join the internal jugular vein in the upper part of the neck (3) The common facial vein is the largest and most important tributary of the internal jugular. It is formed by the union of the anterior and the posterior facial veins and continues downward and backward just above the level of the upper border of the thyroid cartilage. It passes superficially to the hyoglossal nerve as that structure crosses

the loop of the lingual artery. At times it receives the thyroid and the lingual veins and then is referred to as the "thyrolingual facial trunk". (4) The lingual vein when it does not form a tributary of the common facial enters the internal jugular opposite the greater cornu of the hyoid bone. (5) The superior thyroid vein ascends from the upper pole of the thyroid gland in company with the corresponding artery. At the pole there are numerous small trib

its extreme upper portion it is deep to the parotid gland. Inferiorly the infrahyoid muscles are situated between the vessel and the sternocleidomastoid. In its upper part it is separated from the parotid gland by the styloid process, the stylopharyngeus and the stylohyoid muscles and the posterior belly of the digastric. In this region it is crossed superficially by two arteries and a nerve (posterior auricular and occipital arteries and accessory nerve). At a lower level it is crossed by the sternocleidomastoid branch of the occipital artery. After leaving the parotid and the digastric at the upper angle of the carotid triangle it disappears under the sternocleidomastoid but is separated from the muscle by many structures, namely, numerous lymph glands along its entire course, the descendens cervicalis nerve at the level of the thyroid cartilage, the sternocleidomastoid branch of the superior thyroid artery, the intermediate tendon of the omohyoid at about the level of the cricoid cartilage and lastly the sternohyoid and the sternothyroid muscles. Medially the vein is related to the vagus nerve and the common carotid artery below and to the ninth, tenth, eleventh and twelfth cranial nerves and the internal carotid artery above. Posteriorly as the vein descends it crosses the transverse process of the atlas and lies lateral to the tips of the lower transverse processes. In succession it rests upon the levator scapulae, the scalenus medius and the scalenus anterior muscles and is separated from them by the carotid sheath and the prevertebral fascia. The latter named fascia is situated between the vein and the loops of the cervical plexus above and the phrenic nerve below.

SURGICAL CONSIDERATIONS

Ligations of Carotid Arteries and Internal Jugular Vein (Fig. 136). The indications for ligation of the *common carotid artery* are wounds of the carotid artery or its branches, aneurysms, angiomas, inoperable tumors of the face, the neck and the skull, hemorrhage from distal branches and at

times hydrocephalus and epilepsy. Ligation of the common carotid artery can be dangerous, especially in elderly people, since it may be followed by diplopia, blindness, convulsions, coma, hemiplegia or death. The point of election is above the omohyoid muscle; however, ligation below may be necessary in injuries of the artery. Collateral circulation takes place by means of the communications between the carotids of the two sides, both inside and outside the skull and by the enlargement of branches of the subclavian artery. The chief communications outside the skull are the superior thyroid above with the inferior thyroid below and the descending branch of the occipital above with the deep cervical and the ascending branch of the transverse cervical below. Within the skull the vertebral artery compensates for the carotid. In ligation *above the omohyoid* the head is rotated toward the opposite side and at the anterior border of the sternocleidomastoid muscle a three inch incision is made, the center of which is placed at the level of the cricoid cartilage. Superficial vessels are ligated and if necessary, the anterior and the external jugular veins are tied and divided. The deep fascia is severed, the sternocleidomastoid is retracted in an outward direction. The omohyoid muscle is exposed and the carotid tubercle is felt where it lies in the angle between the sternocleidomastoid and the omohyoid. Pulsations of the artery can be felt in this angle. The jugular vein lies to the lateral side of the artery and overlaps it, the superior thyroid, the lingual and the facial veins may cross the artery at its upper end and it may be necessary to ligate them. Some authorities believe that the internal jugular vein should also be ligated. The descending branch of the hypoglossal nerve may be identified on the anterior aspect of the carotid sheath and it is exposed and displaced medially. If the omohyoid muscle interferes with exposure or ligation it may be severed or retracted in a downward direction. The sheath is opened to the





FIG 136 Ligation of the common carotid artery (A) ligation above the omohyoid muscle this is the site of choice (B) ligation below the omohyoid muscle

After ligation below the digastric muscle the collateral circulation is brought about by the inferior with the superior thyroid arteries the deep cervical from the costocervical with the occipital, the transverse cervical with the occipital branches of the two vertebrals and branches of the two internal carotids through the circle of Willis.

The usual site of ligation is between the superior thyroid and the lingual trunks but it may be performed proximally to the superior thyroid. Since the latter vessel may arise from the common carotid it is wise to expose the origin of both carotids. A skin incision is made extending for about three inches from the angle of the jaw to the upper border of the thyroid cartilage in front of the anterior border of the sternocleidomastoid muscle. Skin platysma and superficial fascia are divided exposing the anterior border of the sternocleidomastoid. Since the common facial and lingual veins often cross the operative field they are sought ligated and divided. The superficial layer of deep cervical fascia is incised to mobilize the sternocleidomastoid muscle which is drawn backward. The carotid sheath is exposed and opened. In the connective tissue of the sheath the descending branch of the hypoglossal nerve is seen and is displaced medially and the internal jugular vein is retracted laterally. Between them the bifurcation of the common carotid artery can usually be seen. Since the first part of the external carotid lies medial to the internal the two vessels may be mistaken unless it is remembered that the external carotid is the only vessel that gives off branches. After the latter is exposed it is ligated on a level with the greater cornu of the hyoid bone. It is best to pass the ligatures from the internal carotid side and to guard against including the descending hypoglossal nerve as well as the superior laryngeal nerve. The wound is closed in layers.

Ligation of the internal carotid artery has been done for wounds aneurysms or pulsating exophthalmus due to an arteriovenous aneurysm between the artery and the cavernous sinus. Collateral circulation takes place through the circle of Willis. The internal carotid running to the base of the occiput without giving off any lateral branches can be exposed in its lower part in the same manner described for the external carotid artery (p. 202). If it must be ligated near the base of the skull however the operation is a most extensive one since exposure must take place above the posterior belly of the digastric and here the vessel lies very deep. The internal carotid artery is identified near the bifurcation of the common carotid and then traced upward. The digastric muscle is retracted upward and the external carotid inward. The ligature is passed from without inward avoiding the internal jugular vein the vagus nerve and the sympathetic trunk. Some authorities advise primary placement of a ligature around the common carotid to be used only in case of absolute necessity.

Ligation of the internal jugular vein has been resorted to in such conditions as transverse sinus thrombosis to prevent extension of infection into the general circulation. In its lower portion the vein is found quite easily but identification becomes more difficult as it travels cephalad since its tributaries become more numerous. The ligation of one or both jugular veins has been carried out without any appreciable difficulty. The vein may be found readily by incising along the anterior border of the sternocleidomastoid muscle it is the most superficial structure in the carotid sheath.

THYROID GLAND

Embryology (Fig. 138) At the junction of the posterior third with the anterior two-thirds of the tongue the *foramen*




FIG 137 Ligation of the external carotid artery, the usual site is between the superior thyroid and the lingual arteries

inner side, and the artery is exposed. A ligature should be passed from without inward keeping close to the artery, especially in back, so that the vagus nerve is not included in the ligature. Ligation below the omohyoid is much more difficult and is only done in case of necessity. The skin incision is longer and is usually extended to the jugular notch. If the sternocleidomastoid protrudes, it may be detached in the region of its sternal or clavicular head after severing the superficial layer of deep cervical fascia. The ribbon muscles that cover the thyroid gland are exposed, and the lateral margin of the sternothyroid is retracted medially with the thyroid and the trachea which lie be-

hind it. The middle layer of deep cervical fascia forming a sheath for the omohyoid muscle is incised along the inferior margin of the muscle, this space reveals a few thyroid veins which usually require ligation. The inferior thyroid artery, passing beneath the carotid sheath, can usually be spared. The internal jugular vein is retracted laterally, the artery is freed, and a ligature is passed around it. If one hugs the artery, the recurrent laryngeal nerve can be avoided.

Ligation of the external carotid artery (Fig 137) is indicated for wounds, aneurysms as a palliative measure for malignant growths and as a preliminary step to operations in the field supplied by its branches.

After ligation below the digastric muscle the collateral circulation is brought about by the inferior with the superior thyroid arteries the deep cervical from the costo cervical with the occipital the transverse cervical with the occipital, branches of the two vertebrals and branches of the two internal carotids through the circle of Willis.

The usual site of ligation is between the superior thyroid and the lingual trunks but it may be performed proximally to the superior thyroid. Since the latter vessel may arise from the common carotid it is wise to expose the origin of both carotids. A skin incision is made extending for about three inches from the angle of the jaw to the upper border of the thyroid cartilage in front of the anterior border of the sternocleidomastoid muscle. Skin platysma and superficial fascia are divided exposing the anterior border of the sternocleidomastoid. Since the common facial and lingual veins often cross the operative field they are sought ligated and divided. The superficial layer of deep cervical fascia is incised to mobilize the sternocleidomastoid muscle which is drawn backward. The carotid sheath is exposed and opened. In the connective tissue of the sheath the descending branch of the hypoglossal nerve is seen and is displaced medially and the internal jugular vein is retracted laterally. Between them the bifurcation of the common carotid artery can usually be seen. Since the first part of the external carotid lies medial to the internal the two vessels may be mistaken unless it is remembered that the external carotid is the only vessel that gives off branches. After the latter is exposed it is ligated on a level with the greater cornu of the hyoid bone. It is best to pass the ligatures from the internal carotid side and to guard against including the descending hypoglossal nerve as well as the superior laryngeal nerve. The wound is closed in layers.

Ligation of the internal carotid artery has been done for wounds, aneurysms or pulsating exophthalmus due to an arteriovenous aneurysm between the artery and the cavernous sinus. Collateral circulation takes place through the circle of Willis. The internal carotid running to the base of the occiput without giving off any lateral branches can be exposed in its lower part in the same manner described for the external carotid artery (p. 202). If it must be ligated near the base of the skull however the operation is a more extensive one since exposure must take place above the posterior belly of the digastric and here the vessel lies very deep. The internal carotid artery is identified near the bifurcation of the common carotid and then traced upward. The digastric muscle is retracted upward and the external carotid inward. The ligature is passed from without inward avoiding the internal jugular vein the vagus nerve and the sympathetic trunk. Some authorities advise primary placement of a ligature around the common carotid to be used only in case of absolute necessity.

Ligation of the internal jugular vein has been resorted to in such conditions as transverse sinus thrombosis to prevent extension of infection into the general circulation. In its lower portion the vein is found quite easily but identification becomes more difficult as it travels cephalad since its tributaries become more numerous. The ligation of one or both jugular veins has been carried out without any appreciable difficulty. The vein may be found readily by incising along the anterior border of the sternocleidomastoid muscle; it is the most superficial structure in the carotid sheath.

THYROID GLAND

Embryology (Fig. 138) At the junction of the posterior third with the anterior two thirds of the tongue the *foramen*




FIG 138 Embryology of the thyroid gland (A) course of the thyroglossal duct (B) lateral view of the thyroglossal duct and possible locations of accessory thyroid glands

caecum is noted as a small depression. From this site at an early stage of fetal life a solid column of cells grows downward, becomes canalized and forms the *thyroglossal duct* from which the thyroid gland is formed. The duct passes down exactly in the midline between the genio-glossi muscles as far as the upper border of the thyroid cartilage where it turns to one or the other side of the midline. From this point on its course is represented by the pyramidal lobe. The question whether the thyroglossal duct passes in front of, through or behind the body of the hyoid bone seems to have been answered by Frazer who has shown that it is placed in front of the bone and then takes a recur-

rent course up behind the hyoid before continuing downward. For this reason many advocate removal of the midportion of the hyoid to make certain that the entire tract is eliminated. If the duct remains open after birth, thyroglossal cysts develop either above the thyroid cartilage where they are usually centrally placed, or below the cartilage where they are usually found to the left of the midline. Since the thyroglossal duct never opens onto the surface of the neck at any stage of its development, congenital thyroglossal fistula is impossible. Fistulae do occur, however, as a result of bursting or opening of a thyroglossal cyst onto the surface. Accessory thyroid glands may occur anywhere along the line of the




FIG. 139 The thyroid gland. (A) The gland has been presented as a transparent structure to show the relations of the vessels and nerves. The path of the inferior thyroid artery can be followed. (B) Cross section through the isthmus of the thyroid gland. (C) The thyroid gland viewed from the left side. The gland is in relation to two nerves (recurrent and external laryngeal), two tubes (esophagus and trachea) and two muscles (inferior constrictor and cricothyroid).

duct and are sometimes found at the back of the tongue (lingual thyroids)

Thyroid Gland Proper (Fig 139) The adult thyroid is a ductless gland. It is a highly vascular solid organ related to the pretracheal fascia that binds it to the larynx and causes it to rise and fall during the act of swallowing. It possesses its own true fibrous capsule which is continuous with the stroma of the gland. The thyroid consists of a pair of lateral lobes which are joined across the median line by the isthmus. Each lateral lobe extends from the middle of the thyroid cartilage to the sixth tracheal ring, is pyramidal in shape with its apex upward and measures two inches in length an inch and a quarter in width and three quarters of an inch in thickness. These measurements are greatly altered by pathologic conditions. The lobe is related medially to the thyroid and the cricoid cartilages, the cricothyroid and the inferior constrictor muscles, the trachea, the esophagus and the external and the recurrent laryngeal nerves. Some describe the medial surface as being related to two tubes (esophagus and trachea), two nerves (recurrent and external laryngeal) and two muscles (inferior constrictor and cricothyroid) (Fig 139C). The lobe is related posteriorly to the common carotid and the inferior thyroid arteries and the longus cervicis muscle. Superficially it is covered by the sternohyoid, the omohyoid and the sternothyroid, and is overlapped by the sternocleidomastoid muscle.

The *isthmus*, which occasionally is absent, is a bar of thyroid tissue varying in width and lying under cover of the skin and the fascia in the median line of the neck. It is situated on the second, the third and the fourth tracheal rings and is nearer the lower than the upper pole. A triangular projection or *pyramidal (mid-dle) lobe* extends upward usually from the left side of the upper border of the isthmus and is connected to the hyoid bone by a fibromuscular slip called the *levator glandular thyroidae*.

Vessels and Nerves The *arteries* of the thyroid gland are two pairs, the superior and the inferior thyroids and sometimes a single artery the *thyroidea ima* (Figs 139, 140). The *superior thyroid artery* is the first branch of the external carotid; it supplies infrahyoid, laryngeal and sternocleidomastoid branches in the carotid triangle. It passes down under cover of the "strap" muscles and at the superior pole of the thyroid gland trifurcates into an anterior branch that supplies the front of the gland, a posterior that goes behind and an isthmic (arcuate) branch that joins its fellow of the opposite side along the upper border of the isthmus. The superior laryngeal nerve is situated only a little higher than the superior thyroid artery and, if the vessel is grasped too high the nerve may be included in the ligature. The *inferior thyroid artery* is a branch of the thyrocervical trunk which arises from the first part of the subclavian. Although the superior vessel enters the superior pole, the inferior thyroid does not enter at the inferior pole of the gland. It travels upward along the medial border of the scalenus anterior muscle as far as the level of the sixth cervical vertebra and turns medially behind the vagus nerve and the common carotid artery; it passes in front of the vertebral vessels and, continuing downward, reaches the posterior border of the gland to which it is finally distributed. To do this it makes a hairpin turn the summit of which varies considerably as to its level. It also supplies the larynx, the pharynx, the trachea, the esophagus and the surrounding muscles. As the artery reaches the thyroid it is crossed either in front or behind by the recurrent laryngeal nerve. A large branch of the vessel ascends along the posterior border of the gland to anastomose with a descending branch from the superior thyroid artery. The *thyroidea ima* is a branch from the innominate or the aortic arch. It varies in size from a tiny arteriole to a vessel as large as the inferior thyroid, which it may replace. It




FIG 140 The vessels of the thyroid gland (A) the isthmus has been cut and the lower part of the left lobe removed to show the relationships of the superior and the inferior thyroid arteries and the recurrent laryngeal nerve (B) the lymph drainage of the thyroid gland (C) the veins of the thyroid

passes upward over the anterior surface of the trachea under cover of the thymus and reaches the inferior border of the isthmus. Its presence should be kept in mind when performing a low tracheotomy and during thyroid surgery. The accessory thyroid

arteries are small vessels supplying the esophagus the trachea and the thyroid gland. The four major thyroid arteries may be ligated but the blood supply to the gland remains surprisingly good because of these accessory vessels.




FIG 141 The nerve supply of the thyroid gland (A) the thyroid isthmus has been cut to show the course of the recurrent laryngeal nerve (B) the nerves are shown on the left and the arteries are shown on the right

The veins of the thyroid form a rich plexus situated in front of the gland. As they leave the gland they form three main trunks in the form of superior middle and inferior thyroid veins. The superior thyroid vein is the only venous trunk that accompanies the artery of the same name. It leaves the upper part of the gland taking as its guide the outer border of the omohyoid muscle crosses the common carotid artery and ends in the internal jugular vein.

The middle thyroid vein has no accompanying artery. It leaves the gland about its midportion, follows the inner border of the omohyoid crosses the common carotid artery and ends in the internal jugular vein. The inferior thyroid veins commence at the lower pole of the gland and at the lower border of the isthmus they pass downward in front of the trachea and may be connected by several transverse branches and end in the left innominate vein.




FIG 143 Simon's triangle This aids in the identification of the recurrent laryngeal nerve. It is bounded anteriorly by the recurrent nerve, posteriorly by the common carotid artery, and the inferior thyroid artery forms its base. The inferior horn of the thyroid cartilage also makes an excellent guide to the nerve.

border of the inferior constrictor muscle it passes deeply to it so as to gain access to the muscles of the larynx. It supplies the muscles that act on the vocal folds but also supplies sensory branches to the mucous membrane of the larynx below these folds. It is therefore both sensory and motor. On the left side the nerve arises within the thorax after turning around the arch of the aorta and then ascends in the neck in the tracheoesophageal groove. Damage to one recurrent nerve produces permanent huskiness of the voice since it is impossible to locate an exact anatomic position of the nerve; it is a good plan to make a deliberate search for it. The inferior cornu of the thyroid cartilage acts as the guide. To aid in the exposure of the recurrent laryngeal nerve, M. M. Simon has constructed an anatomic triangle which can readily be identified (Fig 143). It is bounded by the recurrent laryngeal nerve anteriorly, the common carotid artery posteriorly, and the inferior thyroid artery

forms its base. The triangle is dependent upon the variations and the anomalies that may take place. The recurrent laryngeal nerve supplies all the intrinsic muscles of the larynx with the exception of the cricothyroid. If both recurrent nerves are cut (bilateral abductor paralysis) the vocal cords become lax and cannot be tensed (Fig 144B). This results in immediate impairment of voice but rarely causes difficulty in breathing. It is interesting to note that within three to five months the voice begins to return. This is due to a fibrosis and shrinking of the vocal cords which were previously lax (Fig 144C). A few weeks later the fibrotic process results in fixation of the vocal cords as they approach each other. The fibrotic contraction causes the cords to approach the midline narrowing the glottic space to a thin slit. As a result of this dyspnea begins to make its appearance especially on exertion resulting in a marked limitation of physical effort.




FIG. 142 Possible locations of the recurrent laryngeal nerve (A) behind the inferior thyroid artery, (B) in front of the inferior thyroid artery, (C) high origin, this accounts for the inability to find the nerve during thyroidectomy (D) origin around the inferior thyroid artery, (E) extralaryngeal division. In some instances the nerve may pass between the branches of the artery.

Two nerves are related to the thyroid gland the superior and the recurrent (inferior) laryngeal. Both are branches of the vagus nerve (Fig. 141). The *superior laryngeal nerve* arises from the inferior ganglion (nodosum) passes downward and medially and crosses behind the internal carotid artery. It divides into the internal and the external laryngeal nerves. The *internal laryngeal nerve* the larger of the two branches is accompanied by the superior laryngeal branch of the superior thyroid artery and with it pierces the thyrohyoid membrane at the posterior border of the thyrohyoid muscle. It is purely sensory and supplies fibers to the floor of the piriform fossa and the mucous membrane of the larynx above the vocal cord. The *external laryngeal nerve* accompanies the superior thyroid artery but is placed on a deeper plane. It passes deeply to the upper pole of the thyroid gland and is distributed to the cricothyroid and the inferior constrictor muscles. During ligation of the superior thyroid vessels, the external laryngeal nerve (nerve to the cricothyroid) is in danger. It may be included in the ligature and such inclusion would cause a weakness or huskiness of the voice.

This condition is temporary however and becomes normal within a few months. The *recurrent (inferior) laryngeal nerve* is a structure of vital importance in thyroid surgery. Considerable variations in its position may take place so that the nerve may penetrate and traverse the gland proper may be behind the gland or may remain in the tracheo-esophageal groove (Fig. 142). During thyroid surgery, when the gland is dislocated forward and medially the nerve usually hugs the side of the trachea. It is then located not in the tracheo-esophageal groove but on the posterolateral aspect of the trachea. It always passes posterior to the joint that exists between the inferior cornu of the thyroid and the cricoid. This cartilaginous prominence formed by the joint is a valuable guide to the nerve. On the right side the recurrent leaves the vagus nerve as it crosses the first part of the subclavian artery turns upward and medially behind that artery and the common carotid and travels in the groove between the trachea and the esophagus. It ascends in this groove to the lobe of the thyroid gland and crosses or is crossed by the *inferior thyroid artery*. Upon reaching the lower




FIG 143 Simon's triangle. This aids in the identification of the recurrent laryngeal nerve. It is bounded anteriorly by the recurrent nerve, posteriorly by the common carotid artery, and the inferior thyroid artery forms its base. The inferior horn of the thyroid cartilage also makes an excellent guide to the nerve.

border of the inferior constrictor muscle it passes deeply to it so as to gain access to the muscles of the larynx. It supplies the muscles that act on the vocal folds but also supplies sensory branches to the mucous membrane of the larynx below these folds. It is therefore both sensory and motor. On the left side the nerve arises within the thorax after turning round the arch of the aorta and then ascends in the neck in the tracheoesophageal groove. Damage to one recurrent nerve produces permanent huskiness of the voice since it is impossible to locate an exact anatomic position of the nerve; it is a good plan to make a deliberate search for it. The inferior cornu of the thyroid cartilage acts as the guide. To aid in the exposure of the recurrent laryngeal nerve, M. M. Simon has constructed an anatomic triangle which can readily be identified (Fig 143). It is bounded by the recurrent laryngeal nerve anteriorly, the common carotid artery posteriorly, and the inferior thyroid artery

forms its base. The triangle is dependent upon the variations and the anomalies that may take place. The recurrent laryngeal nerve supplies all the intrinsic muscles of the larynx with the exception of the cricothyroid. If both recurrent nerves are cut (bilateral abductor paralysis) the vocal cords become lax and cannot be tensed (Fig 144B). This results in immediate impairment of voice but rarely causes difficulty in breathing. It is interesting to note that within three to five months the voice begins to return. This is due to a fibrosis and shrinking of the vocal cords which were previously lax (Fig 144C). A few weeks later the fibrotic process results in fixation of the vocal cords as they approach each other. The fibrotic contraction causes the cords to approach the midline, narrowing the glottic space to a thin slit. As a result of this dyspnea begins to make its appearance, especially on exertion, resulting in a marked limitation of physical effort.




FIGURE 146 (Legend on facing page)




FIG 145 Ligations of the superior and inferior thyroid arteries (A) incisions (B) ligation of the superior thyroid artery, (C) ligation of the inferior thyroid artery (D) transverse section showing the ligation of the inferior thyroid artery

FIG 146 (Facing page) Subtotal thyroidectomy (A) The incision is placed in a transverse skin crease (B) The investing layer of deep cervical fascia is opened along the anterior border of the sternocleidomastoid muscle (C) Division of the sternohyoid and omohyoid muscles on the right. The same is done on the left side. These muscles should be severed high so that their nerve supply (ansa hypoglossi) is not injured (D) The sternohyoid and omohyoid muscles have been dissected upward and downward. The sternohyoid on the right side has been severed (E) Isolation and division of the middle thyroid vein. This permits entrance into the posterior thyroid space (F) Ligation of the superior thyroid vessels

carried through the superficial layer of deep cervical fascia the omohyoid muscle is identified retracted medially and the sternocleidomastoid laterally. Deeper dissection will bring the upper pole of the thyroid into view (Fig. 145B). The superior thyroid artery trifurcates and there are usually two veins for each artery hence there may be as many as nine small vessels at each upper pole. The pole is used as a guide and this is followed cephalad until the vessels are clearly visualized. The superior laryngeal nerve is usually situated above the point of ligation.

The most common approach for ligation of the inferior thyroid artery is along the medial border of the sternocleidomastoid but it has been approached along the lateral border. For the medial approach an incision is made along the anterior border of the sternocleidomastoid muscle (Fig. 145A). Transverse incisions produce less scarring. The incision is made through the superficial layer of deep cervical fascia and the sternocleidomastoid muscle is retracted laterally. Dissection is continued in the interval between the carotid sheath and the thyroid gland (Fig. 145C,D). The middle thyroid vein is severed before the proper cleavage plane is found and the recurrent laryngeal nerve must be avoided. Isolation and ligation of this vessel as it is done in routine thyroidectomies is described in detail elsewhere (p. 216).

THYROIDECTOMY

Subtotal thyroidectomy is an operation (Figs. 146-147) that is performed frequently and since technical errors might result in disaster any anatomic points that make for a safer operation should be stressed. The incision should be so placed that the average string of beads will cover

the scar. No fixed point can be mentioned since necks vary in their length but generally the incisions should be one or two fingerbreadths above the sternal notch and extending from one sternocleidomastoid to the other (Fig. 146A). This is deepened until the subplatysmal cleavage plane is reached. Having found this vascular plan the upper flap consisting of skin, subcutaneous fat and platysma is grasped and dissected upward, well above the level of the notch of the thyroid cartilage. This exposes the superficial layer of deep cervical fascia and the anterior jugular veins. The anterior borders of the sternocleidomastoid muscles are now identified the investing layer of deep cervical fascia is incised here (Fig. 146B). In this way the prethyroid muscles are separated from the sternocleidomastoid which is mobilized. The latter is retracted outward and adequate exposure of the prethyroid muscles is obtained. A vertical incision is made in the midline between the two prethyroid muscle bundles and is extended from the thyroid notch to the level of the sternal notch. The sternohyoid and the omohyoid are clamped and divided high thus protecting their nerve supply (Fig. 146C). It is an error to state that the prethyroid muscles have been severed since the underlying sternothyroid usually remains intact after this step. A distinct cleavage plane exists between the sternohyoid and the sternothyroid. The sternohyoid and the omohyoid having been incised, are dissected both upward and downward. The sternothyroid muscle is severed transversely exposing the thyroid gland (Fig. 146D). The last maneuver opens the so-called "surgical capsule" (p. 178). The gland is grasped by forceps rotated medially and the internal jugular vein in the carotid sheath is re-

FIG. 147 (Facing page) Subtotal thyroidectomy (continued). (G) The identification of the recurrent laryngeal nerve and the ligation of the inferior thyroid artery. (H) Ring of forceps placed into the right lobe. Each hemostat bites into thyroid tissue proper and in this way protects the recurrent laryngeal nerve and the parathyroid glands. (I) Removal of the right lobe the isthmus and the pyramidal lobe. (J) Protective ring of forceps in place each hemostat is replaced by a ligature. (K) Approximation of the thyroid remnant. (L) Closure.




FIGURE 147 (Legend on facing page)




FIG 148 Removal of a thyroglossal duct (A) course of a patent thyroglossal duct and cyst (B) incision (C) dissection to the hyoid bone, (D) cutting the hyoid bone (E) an assistant's finger placed in the mouth and pressing on the tongue makes the deeper part of the duct more accessible (F) dissection completed

tracted laterally. This maneuver places the thin pretracheal fascia on the stretch where it attaches to the thyroid gland, and in this tissue the middle thyroid vein is sought. It is severed and ligated and the posterior thyroid space is entered (Fig 146E). This permits medial dislocation of the gland. With medial traction on the thyroid and lateral traction on the carotid sheath dissection takes place in the proper cleavage plane. The upper pole is identified as is the entrance of the superior thyroid vessels. These are doubly ligated off the pole and severed (Fig 146F). Careful separation of the pretracheal layer of pretracheal fascia will reveal the recurrent laryngeal nerve and the inferior thyroid artery (Fig 147G). If deemed necessary the artery is ligated. A ring of forceps is placed around the right thyroid lobe which includes the isthmus; each forceps grasps thyroid tissue proper. The lobe, the isthmus and the pyramidal lobe are removed above this protective ring (Fig 147H I J). The clamped thyroid tissue is ligated and the thyroid that remains is approximated to itself or sutured to the pretracheal fascia (Fig 147K). The left lobe is removed in similar fashion. The severed muscles are resutured and the skin, the superficial fascia and the platysma are approximated as one layer (Fig 147L).

Total Thyroidectomy is usually done for carcinoma of the thyroid. On the involved side the sternocleidomastoid muscle, internal jugular vein, the thyroid vessels and all demonstrable lymphatics are included in the dissection and are removed en bloc. Included in this dissection are the prethyroid muscles.

Thyroglossal Duct The *thyroglossal duct* originates at an early stage in fetal life as a depression in the midline of the posterior third of the tongue which is known as the *foramen caecum*. From it a solid cord of cells grows downward which becomes canalized to form the duct that passes downward in the midline of the neck

between the geniohyoid muscles (Fig 138). It extends as far as the upper border of the thyroid cartilage and then turns to either side of the midline. This part of its course is represented after birth by the pyramidal lobe of the thyroid gland and a musculofibrous band connecting that lobe to the hyoid bone. Frazer seems to have settled the question as to whether the duct runs in front of, behind or through the hyoid bone. His works demonstrate that the duct passes in front of the body of the hyoid and then curves up behind the bone before again continuing downward. It, therefore, is important to remove this section of the hyoid bone when removing a patent duct. After passing the thyroid cartilage the thyroglossal duct expands to form the thyroid gland.

If the duct remains patent a *thyroglossal cyst* develops. Such a cyst is found usually above the thyroid cartilage and in the midline. Hamilton Bailey has stated that if these cysts develop below the thyroid cartilage they naturally follow the course of the duct and appear to one or the other side of the midline, usually to the left. Normally the thyroglossal duct does not open onto the surface of the skin of the neck. Therefore a congenital thyroglossal fistula is not possible and if a fistula does develop it must be secondary and brought about by a bursting of or an opening into a thyroglossal cyst.

Since the thyroid gland develops from the thyroglossal duct, an accessory or misplaced thyroid may develop anywhere along the line of the duct. The *lingual thyroids* are sometimes found at the back of the tongue in the region of the foramen caecum. The term "ectopic thyroid" means thyroid tissue found in an incorrect position thus differing from the accessory thyroid (Fig 138B).

If a thyroglossal duct swelling appears above the hyoid bone it is necessary only to split the mylohyoid muscle along its raphe, separate the geniohyoid muscle and remove the tumors. However, if these cysts

PARATHYROID GLANDS

The parathyroid glands (Fig. 149) are yellowish brown bodies the number and the position of which are variable. A superior and an inferior parathyroid are usually present on each side occupying any position from the back of the pharynx to the superior mediastinum. They are about the size of a small pea and usually lie between the posterior aspect of the lateral lobe of the thyroid and the pretracheal lamina of pretracheal fascia. The parathyroids lie entirely or partially within the substance of the thyroid gland this being particularly true of the superior, which are then easily removed in thyroidectomy. The anatomy of the inferior parathyroids is more complex than that of the superior, and the inferior lie in intimate relationship to the inferior thyroid arteries and veins. Their position is variable. Walton has described three rather typical positions of the parathyroids in relation to their surrounding fascial plane. (1) the gland lies below the inferior thyroid artery and is then anterior to the pretracheal fascia. (2) the gland lies above the artery and is then frequently situated deep to the pretracheal fascia and visible only upon incising the fascia. (3) the parathyroids may be in the substance of the thyroid gland proper. If a tumor develops in a parathyroid in the first described position it may pass between the two capsules of the thyroid along the inferior thyroid veins in front of the common carotid artery and finally come to lie behind the sternum. If such a tumor is situated behind the pretracheal fascia it cannot be seen until the fascia is incised and an inspection made even around the circumference of the esophagus. It may even pass into the thorax behind the esophagus. The superior and the inferior parathyroid glands receive their blood supply from the corresponding thyroid vessels.

THYMUS GLAND

Embryologically the thymus (Fig. 150) appears as two entodermal diverticula

which arise one on either side of the third branchial pouch. A ventral diverticulum of the fourth pouch may take part in the formation of the gland or entirely disappear. As the two diverticula grow they meet and become joined by connective tissue, but there is never any real fusion of thymus tissue proper. Actually, therefore, there are two asymmetrical thymus glands, a right and a left, which are easily separated by blunt dissection.

The *adult thymus gland* is a temporary organ that is 'sandwiched' between the sternum and the great vessels in the region of the superior mediastinum. It is essentially an organ of the growing period of life which undergoes gradual atrophy after puberty. From birth to puberty it grows relatively slowly there being tremendous individual variations at any given age. At birth it ranges in weight from 2 to 17 Gm., the average being 13 Gm., at puberty its average weight is about 37 Gm., but cases have been reported in which it has scarcely been recognizable at this age. In the young adult the average weight is usually reduced to about 25 Gm. The thymus gland is located partly in the neck and partly in the mediastinum, and it is roughly pyramidal in shape with its apex directed upward. In the infant this apex may be in actual contact with the thyroid gland. It is soft in consistency and its shape varies with its size and the age of the individual. In infants with short thoraces it is broad and squat but in adults with long thoraces it is drawn out into two irregular flattened bands. It is of pinkish gray color and has a lobulated surface.

Anteriorly, the thymus gland is related to the sternum and the lower end of the sternothyroid muscles. In the young child its lateral margins may be insinuated between the pleura and the upper costal cartilages. *Posteriorly*, it is related from below upward to the pericardium the ascending aorta the left innominate vein, the trachea and the inferior thyroid veins. It is surrounded by a fibrous capsule that separates it from

or tumors appear subhyoid the dissection must be more radical and include removal of a portion of the hyoid bone

Thyroglossal cysts fistulae and sinuses must be radically removed to accomplish a cure (Fig 148) The cyst is exposed by a

patient's mouth and passed over the back of the tongue enables him to push the foramen cecum and any remaining portion of the sinus tract within reach of the operator Since the duct is small and cannot be seen clearly it is best to dissect some of the




FIG 149 The parathyroid glands (A) Posterior view, in position one the inferior parathyroid is below the inferior thyroid artery, but in position two it is above the artery. The superior parathyroid in this instance is intra glandular (B) Cross section in position one, the gland is anterior to the pretracheal fascia in position two it is posterior to this fascia and in position three it is intra glandular

transverse incision that is carried down to the sternohyoid muscles. These are divided vertically in the midline and the cyst is dissected free to the level of the hyoid bone. To expose the sinus completely a small portion of hyoid bone must be removed in the midline. An assistant's finger placed in the

surrounding tissue with it. Therefore in the removal it is necessary to include some small portion of the mylohyoid, the geniohyoid and the genioglossus muscles. Deep structures are sutured, divided edges of the hyoid bone are approximated, the wound is closed with or without drainage.




FIG 151 The esophagus The cervical part of the esophagus begins opposite the inferior margin of the cricoid cartilage at the level of the body of the sixth cervical vertebra (Inset) Cross section at the level of the first thoracic vertebra The trachea does not cover the esophagus completely, but leaves a part of its left anterior margin exposed this makes surgical access easier from this side

CERVICAL PORTION OF ESOPHAGUS

(Fig 151) The entire esophagus is about ten inches long and extends from the end of the pharynx through the lower part of the neck and through the superior and the posterior mediastinum It pierces the dia

phragm and enters the stomach opposite the ninth thoracic spine about an inch to the left of the midline The *cervical esophagus* is a direct continuation of the pharynx It commences opposite the inferior margin of the cricoid cartilage at the level of the body




FIG. 150 The thymus gland (A) enlarged thymus gland extending in front of the pericardium (B) development of the thymus

these structures. It is connected to the thyroid by a strand of tissue called the *thyrothymic ligament*.

The *arterial supply* of the thymus is received through inconstant branches derived chiefly from the internal mammary artery or its branches. Its veins are irregular and drain mainly into the internal mammary or the left innominate. The gland has a

profuse *lymphatic drainage* and certain of the lymphatics open directly into veins without first traversing lymph glands.

Occasionally the thymus retains its infantile size in the adult and for some unknown reason does not atrophy. In such cases there is a large quantity of lymphoid tissue throughout the body, and the condition is then known as *status lymphaticus*.




FIG 152 Esophageal diverticulectomy (one stage) (A) A longitudinal incision is made along the anterior border of the sternocleidomastoid muscle (B) The omohyoid muscle is severed and the thyroid gland is retracted medially, the sternocleidomastoid muscle and the carotid sheath are retracted laterally. The inferior thyroid artery is exposed, ligated and severed as it crosses the diverticulum (C) Fibers of the inferior constrictor muscle are severed and the sac is mobilized (D) The sac is ligated close to the pharynx (E) Closure is effected in layers

of the sixth cervical vertebra. An excellent landmark which locates this point is the carotid tubercle (Fig 709). The trachea does not cover the esophagus completely but leaves a portion of its left anterior margin exposed making surgical access easier on this side. As the esophagus descends from the level of the sixth cervical vertebra it lies in front of the vertebral column and overlaps both longus cervicis (colli) muscles. At the inlet of the thorax the left common carotid is anterior to its left border, the thoracic duct, the left subclavian artery and the pleura are situated on its left side. Higher up the common carotid is also on its left side and both are overlapped by the thyroid gland. At times the posterior part of the lateral thyroid lobe may enlarge and insinuate itself upon the anterior surface of the esophagus causing difficulty in swallowing.

The esophagus and the pharynx are loosely attached to the prevertebral fascia and in this way form the retropharyngeal and the retro esophageal spaces. Abscesses in these spaces are hindered from extending laterally and thus take the path of least resistance which is downward toward the mediastinum. Because of its loose connection with the prevertebral fascia and because of its elasticity this portion of the esophagus can be displaced upward and laterally for a considerable distance.

When the esophagus is empty it is flattened anteroposteriorly and its lumen appears only as a slit but when distended it becomes irregularly cylindrical and presents its typical constriction points, the first and narrowest of which is at its commencement.

SURGICAL CONSIDERATIONS

ESOPHAGEAL DIVERTICULUM

Shallow and Lahey have done extensive work in this field and the former has reported a series of cases in which one stage diverticulectomy has been accomplished with excellent results (Fig 152). A longitudinal incision is made along the anterior border

of the sternocleidomastoid muscle and is carried through the skin, the superficial fascia and the superficial layer of deep cervical fascia. The sternocleidomastoid is retracted backward until the omohyoid muscle is demonstrated, this is severed at the point where it disappears beneath the sternocleidomastoid. With the omohyoid retracted, the thyroid gland is separated from the internal jugular vein and the common carotid artery. The thyroid gland is then pulled toward the midline, and the inferior thyroid artery is exposed. This often crosses over the diverticulum or gets in the way of its dissection, hence it is best to ligate and sever it. Since a diverticulum is a herniation of mucous membrane through muscle fibers it should be remembered that there are two weak points in the musculature of the posterior aspect of the pharynx and the esophagus, these two points are at the level of the lower fibers of the inferior constrictor, and where the cricopharyngeal muscle diverges from the lowest fibers of the inferior constrictor. These are the two locations where diverticula are most commonly found; however, the approach is usually through the left side of the neck because the esophagus passes to the left of the vertebral bodies. Shallow has made successful use of the esophagoscope to isolate and aid in the dissection of the diverticulum which is closely bound to the longitudinally running esophagus by the enveloping fibers of the cricopharyngeal muscles. These are separated at the lowest angle of the sac, the fundus is grasped with blunt forceps and traction is made. The remaining fibers of the cricopharyngeal enveloping the diverticulum are cut. When the neck of the sac is reached the fibers of the inferior constrictor are seen along the lower border of the neck, the esophagus must be severed to mobilize it completely. The neck of the sac is transfixed and ligated and the sac is removed. This ligation should take place close to the pharynx. The cricopharyngeus and the inferior constrictor should be closed over the ligated and invaginated sac to prevent a recurrence of the hernia.




FIG 154 The floor of the submaxillary triangle (A) the floor is trimuscular and is formed by the mylohyoid the hyoglossus and the middle constrictor muscles (B) the middle constrictor muscle seen from within (C) the hyoglossus muscle

pass directly upward to the lateral surface of the tongue where they attach and interdigitate with the styloglossus (Fig 154C). The posterior fibers form a free margin which overlaps the middle constrictor muscle of the pharynx. The fibers of the

latter originate from the cornu of the hyoid bone and are directed horizontally and backward to the median raphe (Fig 158).

During dissection of this triangle the following structures are encountered: the skin, the superficial fascia, the platysma




FIG 153 The submaxillary (digastric) triangle (A) The superficial layer of deep cervical fascia has been removed exposing the floor and the contents of the triangle. The submaxillary gland which overflows the triangle, also has been removed (B) Coronal section, showing the superficial layer of deep cervical fascia investing the submaxillary gland

SUBMAXILLARY (DIGASTRIC) TRIANGLE

(Figs 153-154) The *submaxillary*, or *digastric*, triangle is bounded by the anterior and the posterior bellies of the digastric and the inferior border of the mandible. The roof is fascial being formed by the investing (superficial) layer of deep cervical fascia as it passes between the mandible and the hyoid bone. Three muscles make up the floor: the mylohyoid, the hyoglossus and the middle constrictor muscle of the pharynx. These muscles constitute important

surgical landmarks and can be identified by the direction of their fibers and the fact that they lie on successively deeper planes. The fibers of the *mylohyoid* muscle arise from the mylohyoid line of the mandible, run downward and medially and insert into a median raphe which extends from the chin to the hyoid bone. With its fellow of the opposite side it forms a diaphragm of the oral cavity. The free oblique posterior fibers reach the hyoid bone and overlap the *hyoglossus* muscle, whose fibers arise from the hyoid,




FIG 136 The pharynx viewed from behind with the three constrictor muscles removed

face passes forward deeply to the sublingual gland and opens into the floor of the mouth on the sublingual papilla at the side of the frenulum linguae. When the submaxillary gland is freed and retracted upward the *mylohyoid nerve* is visible; it is accompanied by the *submental branch of the facial artery*. If the free posterior border of the mylohyoid muscle is identified the *lingual* and the *hypoglossal nerves* are seen passing behind this border. These nerves are separated by the oral part of the submaxillary gland and its forward

running Wharton's duct. The lingual nerve, Wharton's duct and the hypoglossal nerve run behind the mylohyoid muscle and on the hyoglossus muscle. The hypoglossal nerve is usually accompanied by one or two veins. These relationships may be seen when the superficial part of the submaxillary gland is cut away and the mylohyoid muscle is detached at the hyoid bone and median raphe. If the hyoglossus muscle is cut parallel with and above the hyoid bone the *lingual artery* is exposed lying deep to the hyoglossus muscle while the




FIG 155 The pharynx viewed from behind, with the three constrictor muscles intact

and the *cervical branch of the facial nerve* which passes down behind the angle of the mandible and lies between the platysma and the deep cervical fascia. Incisions made behind the angle of the jaw may injure this nerve and, since it supplies the quadratus labii inferioris a drop in the angle of the mouth may result. This usually disappears within three months. The *anterior facial vein* crosses the triangle superficially and at the lower margin of the mandible accompanies the *external maxillary artery*. The deep cervical fascia (investing layer) en-

velops or invests the *submaxillary salivary gland* which overflows the triangle and conceals the *trismuscular floor* and the *digastric muscle* (Fig 153B). The gland is separated posteriorly from the parotid by the *stylomandibular ligament* which is the thickened part of the parotid fascia between the styloid and the angle of the mandible. The *submaxillary gland* is indented by the posterior free edge of the *mylohyoid muscle* and in this way is divided into a superficial and deep (oral) part (Fig 98). Its duct (Wharton's) leaves its deep sur-




FIG. 156 The pharynx viewed from behind with the three constrictor muscles removed

face passes forward deeply to the sublingual gland and opens into the floor of the mouth on the sublingual papilla at the side of the frenulum linguae. When the submaxillary gland is freed and retracted upward the *mylohyoid nerve* is visible; it is accompanied by the *submental branch of the facial artery*. If the free posterior border of the mylohyoid muscle is identified the *lingual* and the *hypoglossal nerves* are seen passing behind this border. These nerves are separated by the oral part of the submaxillary gland and its forward

running Wharton's duct. The lingual nerve, Wharton's duct and the hypoglossal nerve run behind the mylohyoid muscle and on the hyoglossus muscle. The hypoglossal nerve is usually accompanied by one or two veins. The relationships may be seen when the superficial part of the submaxillary gland is cut away and the mylohyoid muscle is detached at the hyoid bone and median raphe. If the hyoglossus muscle is cut parallel with and above the hyoid bone the *lingual artery* is exposed lying deep to the hyoglossus muscle while the

vein accompanying the hypoglossal nerve lies on this muscle. The vein should not be confused with the artery. An additional vein usually accompanies the lingual artery.

PHARYNX

(Figs 155 156 157) The pharynx is a large vestibule that is common to the respiratory and the digestive tracts. It is a vertically placed musculomembranous tube that extends from the base of the skull to the cricoid cartilage where it becomes continuous with the esophagus. The sixth cervical vertebra marks its lower border posteriorly. It is about five inches long and has a transverse diameter greater than the anteroposterior. The widest part (one and three fourths inches) is opposite the hyoid bone and the narrowest (three fourths of an inch) is at the esophageal orifice. Since it communicates with the nose the mouth and the larynx it has been divided into three parts: nasopharynx oropharynx and laryngopharynx.

The *nasopharynx* (*epipharynx*) is somewhat cube shaped and is placed behind the cavity of the nose, above and behind the soft palate. It is part of the respiratory and not of the digestive tract. Its walls, with the exception of the soft palate, are incapable of movement therefore the cavity remains patent and its form never changes. Its *anterior wall* is formed by the posterior apertures of the nose (choanae) through which it opens into the nasal cavities. These apertures are a pair of oblong openings that slope from the base of the skull downward and forward to the posterior border of the hard palate and are separated by the vomer. By looking through them with a postnasal mirror a view is obtained of the posterior end of the inferior and the middle conchae and the two lower meatuses. Each opening is about one inch long and half an inch wide. The *roof* and the *posterior wall* are considered together as an obliquely sloped surface formed by

the body of the sphenoid, the basilar process of the occipital bone and a thick layer of ligamentous fibrous tissue which fills in the angle between the latter and the vertebrae. The roof and the posterior wall are supported by the inferior surface of the body of the sphenoid the basilar part of the occipital bone and the anterior arch of the atlas below. The posterior wall, especially in childhood, presents a mass of lymphoid tissue known as pharyngeal tonsils (adenoids) which may fill the nasopharynx and hinder or completely block nasal breathing. The *floor* is made up of the soft palate and the uvula and is the only movable boundary of the nasopharynx. It prevents food from being regurgitated into the nose. Behind the soft palate the nasopharynx is continuous with the oral pharynx through the *isthmus*. The *lateral wall* presents the opening of the pharyngotympanic tube (eustachian) which is on a level with and about half an inch behind the inferior nasal concha. The entire side wall measures a little over an inch in diameter. The posterior boundary of the eustachian opening presents a prominent elevation (eustachian cushion) which is derived from the cartilaginous portion of the tube, behind which lies the pharyngeal recess (Rosenmüller's fossa). A fold of mucous membrane the salpingopharyngeal fold descends from the posterior lip of the orifice and contains the salpingopharyngeus muscle which gradually disappears as it passes downward.

When adenoids occlude the orifice of the tube the air in the tympanic cavity gradually becomes absorbed and deafness may result. The tympanum can be inflated through the pharyngeal orifice of the tube by means of a eustachian catheter. The instrument is passed backward along the floor of the inferior meatus until it reaches the posterior wall of the nasopharynx. If the catheter is rotated laterally through a right angle its point rises in the pharyngeal recess. It may then be withdrawn from the nose until the point catches the tubal




Fig. 157 Sagittal view of the pharynx. The three parts of the pharynx have been subdivided.

projection. When a mirror is introduced through the mouth so that the nasopharynx is illuminated by reflected light, a view is obtained of the four orifices that open into

the nasal part of the pharynx: the middle and the superior meatuses of the nose, and the middle and the superior conchae can be brought into view and their pathology




FIG 158 The muscular coat of the pharynx (side view) The origin of the three constrictor muscles is along a continuous line from above downward

determined. The side walls and the orifices of the pharyngotympanic tubes also can be fully inspected.

The *oropharynx* (mesopharynx) is partly respiratory and partly alimentary. It is the posterior continuation of the mouth cavity that lies behind the mouth and the tongue. The *anterior wall* presents the opening into the mouth; the lower portion being the pharyngeal part of the dorsum of

the tongue that faces directly backward. The epiglottis, which belongs to the laryngeal part of the pharynx and is situated immediately behind the tongue, appears as a leaflike plate of cartilage enveloped in mucous membrane with its upper part standing prominently up and behind the tongue. The *posterior wall* is smooth and is supported by the body of the axis, which is separated from the pharynx by the pre-

vertebral foramen. The *lateral wall* is formed by the interval between the palatoglossal and the palatopharyngeal arches that is occupied by the tonsils. A retropharyngeal abscess produces a swelling of the posterior pharyngeal wall that may bulge forward and obstruct the air passages during respiration.

The *laryngopharynx* (hypopharynx) is the longest of the three subdivisions; it lies behind the larynx and diminishes in width from above downward. Its upper part is common to the digestive and the respiratory tracts but its lower part opposite the cricoid is entirely digestive. Its anterior and posterior walls are in contact except when food is swallowed. The *anterior wall* is formed by the inlet of the larynx and the posterior aspect of the arytenoid and the cricoid cartilage. The *posterior wall* is in contact with the anterior and is supported by the bodies of the third, fourth, fifth and sixth cervical vertebrae. The *lateral walls* are supported by the posterior part of the lamina of the thyroid cartilage and present a small fossa, the *piriform recess*, which is bounded on its medial side by the aryepiglottic fold. The mucous membrane of this area is supplied by the internal laryngeal nerve; hence if a crumb or a small particle of food lodges in the fossa, uncontrollable coughing results.

The *pharyngeal wall* presents four rather distinct layers: buccopharyngeal fascia, muscular, fibrous and mucous coats. (1) The *buccopharyngeal fascia* is a layer of fibrous tissue covering both the buccinator and the pharyngeal muscles. It also invests the constrictor muscles of the pharynx and between it and the prevertebral fascia a loose areolar tissue is found which forms an easily distensible space in which pus may spread (Fig. 122). This layer contains the venous plexus which drains the pharynx and communicates with the pterygoid plexus. It enters the jugular vein near the angle of the jaw.

(2) The *muscle coat* of the pharyngeal wall is made up of five paired voluntary

muscles: the three constrictors (superior, middle and inferior) which constitute an outer circular layer and the stylopharyngeus and the palatopharyngeus which constitute an inner longitudinal layer (Fig. 154). The *three constrictor muscles* are incomplete in front but each widens posteriorly and joins its fellow in the median plane at the median raphe. Each muscle is somewhat fan-shaped and is attached by its front end or handle to the side wall of the nasal, the oral or the laryngeal cavity. Each partly overlaps externally the muscle above it so that the inferior overlaps the middle, and the middle overlaps the superior. The origin of these muscles is continuous from above down: the *superior constrictor* originates from the lower third of the posterior border of the medial pterygoid plate, the pterygomandibular ligament, the side of the tongue, the mucous membrane of the mouth and the mylohyoid line; the *middle constrictor* originates from the stylohyoid ligament and the hyoid bone; the *inferior constrictor* arises from the oblique line of the thyroid cartilage and the fascia covering the cricothyroid muscle. They are inserted into a median raphe situated posteriorly and all are supplied by the pharyngeal plexus through the accessory part of the spinal accessory nerve. The inferior constrictor receives two additional nerves: the external and the recurrent laryngeal branches of the vagus. The *stylopharyngeus muscle* enters the wall of the pharynx between the superior and the middle constrictors (Fig. 155). It meets the *palatopharyngeus muscle* and is inserted with it into the posterior border of the thyroid cartilage. This is only visible after cutting the inferior constrictor muscle. The *stylopharyngeus* is supplied by the glossopharyngeal nerve and the palatopharyngeus by the accessory nerve.

(3) The *fibrous coat* has been called the pharyngobasilar fascia, the pharyngeal aponeurosis and also the submucous coat. It is strong in its upper part and takes the place of muscle tissue where the superior




FIG 159 Posterior view of the pharynx. The posterior wall has been cut open to show the internal and the recurrent laryngeal nerves and the superior laryngeal artery.

constrictor is absent. As it passes downward it gradually becomes weaker until it is finally lost as a distinct fiber. It forms the principal attachment between the pharynx and the base of the skull.

(4) The *mucous coat* consists of a columnar ciliated epithelium in the nasopharynx and stratified squamous in the lower part.

The various structures pass in a definite arrangement between the constrictor muscles. Between the base of the skull and the superior constrictor are the tensor palati, the pharyngotympanic tube and the levator palati; between the superior and the middle constrictors are the stylopharyngeus muscle and the glossopharyngeal nerve; between the middle and the inferior con-

strictors are the internal laryngeal nerve and the superior laryngeal artery; and between the inferior constrictor and the esophagus are the recurrent laryngeal nerve and the inferior laryngeal artery (Fig 159).

LARYNX

Fig 160

The *larynx* is the upper and specialized portion of the windpipe that extends from the epiglottis to the cricoid; it forms the organ of the voice. At birth it lies opposite the third and the fourth cervical vertebrae, but gradually descends until in the adult, it lies opposite the third, fourth, fifth and sixth cervical vertebrae. It is situated in the front and upper part of the neck, below the tongue and the hyoid bone and between the great vessels of the neck. Above, it




FIG 160 The larynx four views and a disarticulated larynx are shown

opens into the pharynx and below into the trachea. In the midline it is covered by skin and cervical fascia but laterally is overlaid by the sternohyoid and the sternothyroid,

the thyrohyoid and the origin of the inferior constrictor muscles. It consists of cartilages, ligaments and muscles and is lined by mucous membrane. Laterally, it is em

braced by the lateral lobes of the thyroid gland, above which it is related to the carotid sheaths. Behind, it rests upon the pharynx which separates it from the body of the third to the sixth cervical vertebrae. After puberty the larynx is smaller in the female than in the male, the vocal cords in the former being about two thirds the length of the latter.

The cartilages of the larynx are nine in number (Fig. 160): the epiglottis, the thyroid, the cricoid, two arytenoids, two corniculates and two cuneiforms. The *epiglottis* is a leaf-shaped lamina of yellow fibrocartilage covering the superior aperture of the larynx. It guards the entrance to the larynx and is situated behind the median thyrohyoid ligament, the hyoid bone and the back of the tongue. Its pointed lower end is firmly attached by the *thyroepiglottic ligament* to the posterior surface of the fused alae of the thyroid cartilage just below the thyroid notch. Its expanded upper end projects upward beyond the hyoid bone and presents a free border covered by mucous membrane both anteriorly and posteriorly. The anterior surface is connected to the dorsum of the tongue by a *median glossoepiglottic* and *right and left pharyngoepiglottic folds*. The corresponding depression on each side of the median plane forms the *vallecula*. The floor of the vallecula lies immediately above and behind the hyoid bone. The posterior surface of the epiglottis lies in the anterior wall of the vestibule of the larynx.

The *thyroid cartilage* is the largest of the laryngeal cartilages and its name is derived from the Greek which means 'like a shield'. It is formed by a pair of broad quadrilateral laminae that are fused together in front but are widely separated behind. The fusion of these two laminae anteriorly in the midline of the neck has a more marked angulation in males and is known as the 'pomum Adam' (laryngeal prominence or Adam's apple). The anterior borders of these laminae are united only in their lower halves, the upper halves being

separated by a V-shaped *thyroid notch*. The laryngeal prominence and the thyroid notch can be felt easily subcutaneously and thus serve as valuable landmarks. The free and rounded posterior border projects upward as a superior horn and downward as an inferior horn. The superior horn is attached to the tip of the greater cornu of the hyoid bone by a lateral thickened border of the thyrohyoid membrane called the *lateral thyrohyoid ligament*. The inferior horn articulates at its extremity with the side of the cricoid cartilage. An important *oblique line* begins on the lateral surface of the cartilage in front of the root of the superior horn, extends downward and forward and ends behind the middle of the inferior border. This line gives insertion to the sternothyroid muscle and origin to the thyrohyoid muscle. The area in front of it is covered by the thyrohyoid and the narrower posterior area gives origin to a part of the inferior constrictor muscle of the pharynx. The inferior border of this cartilage is in relation to the circumference of the cricoid cartilage to which it is attached by the cricothyroid membrane. As life progresses this cartilage begins to ossify and may become fractured.

The *cricoid cartilage* is shaped like a signet ring with the wide part posterior. It is a palpable landmark that indicates the beginning of the trachea and the level of the superior border of the esophagus. Its narrow anterior part which is palpable through the skin is called the *arch* and lies on a level with the sixth cervical vertebra. The posterior part, the *lamina*, is much deeper, projects upward and occupies the lower part of the gap between the two laminae of the thyroid cartilage. The arch is attached to the thyroid cartilage by the *cricothyroid membrane* and below is fixed to the first tracheal ring by an elastic membrane known as the *cricotracheal ligament*. The two *arytenoid cartilages* appear as triangular pyramids whose apices are directed upward and whose bases articulate




FIG 161 The intrinsic muscles of the larynx, four views are shown

with the upper aspect of the posterior portion of the cricoid. They help fill the gap between the two laminae of the thyroid cartilage. The posterolateral angle of the base is called the *muscular process* because it provides attachment to the cricoarytenoid muscles. The anterior angle of the base is prolonged forward as a spine-like process called the *vocal process* because the true vocal cords attach here. The two *corniculate cartilages* have been referred to as the cartilages of *Santorini*. They are small and conical and are attached to the apex

of each arytenoid cartilage. They give attachment to the aryepiglottic folds. The two *cuneiform cartilages* have been referred to as the cartilages of *Wrisberg*. They are a pair of little rod-shaped cartilages that are placed in the aryepiglottic folds in front of the corniculate cartilages.

The *membranes* that make up the chief connecting bands of the larynx are the thyrohyoid and the cricothyroid. The *thyrohyoid membrane* connects the upper border of the thyroid cartilage to the upper part of the posterior surface of the hyoid bone

in this way suspending the larynx from the hyoid. The median portion of this membrane is thickened and is called the *median thyrohyoid ligament*, its cordlike right and left margins are referred to as the *lateral thyrohyoid ligaments*. The median thyrohyoid membrane is pierced by the internal laryngeal nerve and the superior laryngeal vessels on each side. The lateral thyrohyoid ligament passes from the superior horn of the thyroid to the tip of the greater cornu of the hyoid bone where a small cartilaginous nodule, the *cartilago triticea* is found. The *cricothyroid membrane* occupies the interval between the cricoid and the thyroid cartilages and consists of a central and two lateral portions. The central portion connects the cricoid and the thyroid cartilages and presents a hole in the midline through which the *cricothyroid artery* sends a branch. This vessel is used as a landmark in laryngeal surgery. The lateral part of the membrane (*conus elasticus*) is attached below to the upper border of the cricoid cartilage but is free above except at its extremities. It is fixed in front in the angle between the thyroid laminae and behind to the vocal processes of the arytenoids. The free border of the cricothyroid membrane which results is covered by mucous membrane and forms the *true vocal cord*. The ventricular band that is covered by mucous membrane and forms the *false vocal cord* extends from the angle between the thyroid laminae to the anterolateral surface of the arytenoids. These lie above the true vocal cords.

The *muscles* of the larynx are extrinsic and intrinsic. The *extrinsic* muscles have been described elsewhere (p. 191) they act upon the voice box as a whole. They are the omohyoid, the sternohyoid, the sternothyroid, the thyrohyoid and certain suprahyoid muscles (stylopharyngeus, palatopharyngeus, inferior and middle constrictors of the pharynx). The *intrinsic* muscles, on the other hand, confine themselves entirely to the larynx and act upon its parts

to modify the size of the laryngeal aperture (*rima glottidis*) and also control the degree of tension of the vocal ligaments. The principal intrinsic laryngeal muscles are the cricothyroid, the arytenoids (transverse and oblique), the posterior cricoarytenoids, the lateral cricoarytenoid and the thyroarytenoid. All of these, with the exception of the transverse arytenoid, are in pairs (Fig. 161).

The *cricothyroid muscle* is the only intrinsic muscle that lies on the exterior of the larynx. It arises from the lateral surface of the cricoid, runs upward and backward and is inserted into the inferior horn of the thyroid cartilage. It bridges the lateral portion of the cricothyroid interval. The cricothyroid muscles are the chief tensors of the vocal ligaments, this action is accomplished by pulling the arch of the cricoid upward around its articulation with the inferior horn of the thyroid cartilage thus forcing the arytenoids backward and stretching the vocal cords (Fig. 162B). The *posterior cricoarytenoid* is probably the most important of the laryngeal muscles since its action separates (abducts) the vocal cords, thus widening the *rima glottidis*. All the other muscles close the larynx by a more or less sphincteric (adduction) action. The *cricoarytenoid* arises from the back of the cricoid runs upward and outward to the muscular process of the arytenoid where it inserts. By pulling backward on this process the vocal cords are separated (Fig. 162A). Bilateral abductor paralysis of these muscles results in suffocation. When both recurrent laryngeal nerves are injured bilateral abductor paralysis results and the vocal cords become lax and cannot be abducted. At first this rarely results in dyspnea, but the loss of voice is immediate. Within three to five months the voice begins to improve but, unfortunately, dyspnea also makes its appearance. This is the result of atrophy and fibrosis. Within a few weeks the voice becomes more improved but as the vocal cords continue to fibrose and gradually

approach each other the dyspnea becomes severe, especially on exertion. The laryngo-
scope will reveal the presence of a mere slit. The *transverse arytenoid* is the only
unpaired muscle of the larynx. It is a

swallowing (Fig. 162C). The *oblique ary-*
tenoid muscles are a pair of weak muscular
slips that lie on the back of the transverse
muscle and cross each other forming a
letter X. This muscle continues on as the




FIG. 162 The action of the intrinsic muscles of the larynx (A) The action of the posterior crico-arytenoid muscles separating the vocal cords (B) By the contraction of the cricothyroid muscle the vocal ligaments are tensed (C) Adduction of the vocal cords is brought about by the contraction of the oblique and transverse arytenoid muscles

thin flat muscular band passing from the back of one arytenoid cartilage to the other. When it contracts it draws the posterior parts of the arytenoids together, helping to close the laryngeal inlet during

aryepiglotticus in the aryepiglottic fold in which it reaches the epiglottis. Its action draws the arytenoids together and shortens the aryepiglottic fold. This approximates the arytenoids and the epiglottis. The

in this way suspending the larynx from the hyoid. The median portion of this membrane is thickened and is called the *median thyrohyoid ligament*; its cordlike right and left margins are referred to as the *lateral thyrohyoid ligaments*. The median thyrohyoid membrane is pierced by the internal laryngeal nerve and the superior laryngeal vessels on each side. The lateral thyrohyoid ligament passes from the superior horn of the thyroid to the tip of the greater cornu of the hyoid bone where a small cartilaginous nodule, the *cartilago triticea*, is found. The *cricothyroid membrane* occupies the interval between the cricoid and the thyroid cartilages and consists of a central and two lateral portions. The central portion connects the cricoid and the thyroid cartilages and presents a hole in the midline through which the cricothyroid artery sends a branch. This vessel is used as a landmark in laryngeal surgery. The lateral part of the membrane (*conus elasticus*) is attached below to the upper border of the cricoid cartilage but is free above except at its extremities. It is fixed in front in the angle between the thyroid laminae and behind to the vocal processes of the arytenoids. The free border of the cricothyroid membrane which results is covered by mucous membrane and forms the *true vocal cord*. The ventricular band that is covered by mucous membrane and forms the *false vocal cord* extends from the angle between the thyroid laminae to the anterolateral surface of the arytenoids. These lie above the true vocal cords.

The *muscles* of the larynx are extrinsic and intrinsic. The *extrinsic* muscles have been described elsewhere (p. 191). They act upon the voice box as a whole. They are the omohyoid, the sternohyoid, the sternothyroid, the thyrohyoid and certain suprahyoid muscles (stylopharyngeus, palatopharyngeus, inferior and middle constrictors of the pharynx). The *intrinsic* muscles on the other hand, confine themselves entirely to the larynx and act upon its parts

to modify the size of the laryngeal aperture (*rima glottidis*) and also control the degree of tension of the vocal ligaments. The principal intrinsic laryngeal muscles are the cricothyroid, the arytenoids (transverse and oblique), the posterior cricoarytenoids, the lateral cricoarytenoid and the thyroarytenoid. All of these, with the exception of the transverse arytenoid, are in pairs (Fig. 161).

The *cricothyroid muscle* is the only intrinsic muscle that lies on the exterior of the larynx. It arises from the lateral surface of the cricoid, runs upward and backward and is inserted into the inferior horn of the thyroid cartilage. It bridges the lateral portion of the cricothyroid interval. The cricothyroid muscles are the chief tensors of the vocal ligaments; this action is accomplished by pulling the arch of the cricoid upward around its articulation with the inferior horn of the thyroid cartilage thus forcing the arytenoids backward and stretching the vocal cords (Fig. 162B). The *posterior cricoarytenoid* is probably the most important of the laryngeal muscles, since its action separates (abducts) the vocal cords, thus widening the *rima glottidis*. All the other muscles close the larynx by a more or less sphincteric (adduction) action. The *cricoarytenoid* arises from the back of the cricoid, runs upward and outward to the muscular process of the arytenoid where it inserts. By pulling backward on this process the vocal cords are separated (Fig. 162A). Bilateral abductor paralysis of these muscles results in suffocation. When both recurrent laryngeal nerves are injured, bilateral abductor paralysis results and the vocal cords become lax and cannot be abducted. At first this rarely results in dyspnea, but the loss of voice is immediate. Within three to five months the voice begins to improve but unfortunately, dyspnea also makes its appearance. This is the result of atrophy and fibrosis. Within a few weeks the voice becomes more improved but as the vocal cords continue to fibrose and gradually




FIG 163 The inlet of the larynx as seen through a laryngeal mirror
The insert shows the structures magnified and identified

into three compartments: vestibule (supraglottic), middle compartment (glottic area), and an infraglottic area. Some authors have likened the superior aperture of the larynx to a triangle, the base of which is at the epiglottis, the sides formed by the arytenoid epiglottic folds, and the apex located at the arytenoid commissure posteriorly.

The *inlet* or upper aperture, of the larynx faces almost directly backward so that it is set at right angles to the long axis of the laryngeal tube. It is bounded above by the free margin of the epiglottis, on either side by the aryepiglottic folds of

mucous membrane which stretch from the epiglottis to the arytenoid cartilage, and below by the short interarytenoid fold of mucous membrane (Fig 163). Two small elevations are noted at the posterior extremity of the aryepiglottic fold. The most anterior protrudes to a higher plane and is the cuneiform cartilage (Wrisberg). The posterior, which is set on a slightly lower plane, is produced by the corniculate cartilage (Santorini) which is situated on the apex of the arytenoid cartilage. These two small elevations are easily visible on laryngoscopic examination. The anterior

muscle acts as a sphincter for the laryngeal inlet during swallowing (Fig 162C). The *lateral cricoarytenoid* muscle arises from the upper aspect of the lateral part of the cricoid runs upward and backward and is inserted into the muscular process of the arytenoid. These muscles are adductors of the vocal cords and reduce the width of the rima glottidis. The *thyroarytenoid* is an upward continuation of the lateral cricoarytenoid. It arises from the deep surface of the thyroid lamina passes backward and inserts into the anterolateral surface of the arytenoid cartilage. It pulls the arytenoid cartilage forward and slackens the vocal folds. The uppermost fibers of this muscle curve upward into the aryepiglottic fold are called the thyroepiglottic muscles and join with the aryepiglottic muscles to insert in the edge of the epiglottis. Some of the deepest fibers of the thyroarytenoid form a muscle bundle, the *vocal muscle*; this cannot be separated from the rest of the muscle and actually is the inner constant part that lies in the vocal lip lateral to the vocal ligament. It draws the vocal process forward relaxing the vocal ligaments.

The *action* of the laryngeal muscles is threefold: (1) they open the glottis and permit breathing; (2) they close the glottis and vestibule during swallowing; (3) they regulate the tension of the vocal cords. The first two actions are automatic and are controlled by the medulla, but the third is voluntary and is controlled by the cerebral cortex. The posterior cricoarytenoids are the only abductors. The lateral cricoarytenoids adduct the cords. The muscles that close the vestibule are the thyroarytenoid, the aryepiglottic and the thyroepiglottic. The muscles that effect the tension of the cords are the cricothyroid, the *vocals* and the thyroarytenoid.

The *nerve supply* to the larynx is derived from the vagus nerve by way of its two branches, the superior and the inferior (recurrent) laryngeal, both of which are mixed nerves (Fig 141). After a short course,

the *superior laryngeal nerve* divides into a thin external and a stouter internal branch. The *external laryngeal nerve* is applied to the inferior constrictor muscle and passes deeply to the insertion of the sternohyoid. In its course it passes to and is accompanied by the superior thyroid artery; it sends a few twigs to the inferior constrictor, pierces it and ends by supplying the cricothyroid muscle. The *internal laryngeal nerve* is sensory and pierces the thyrohyoid membrane as several diverging branches. It crosses the anterior wall of the piriform recess and supplies sensory fibers to the larynx above the vocal cords. Nordland and other investigators believe that this nerve innervates the interarytenoid muscle in most cases. Division of the superior laryngeal nerves results in a loss of sensation to the laryngeal mucous membrane, making it difficult or impossible for the patient to perceive a foreign body in the larynx. There is also a weakening or paralysis of the cricothyroid, which produces a huskiness of the voice. The *inferior (recurrent) laryngeal nerve* arises at different levels on the two sides. On the right it arises in the root of the neck and winds around the subclavian artery, but on the left it arises in the superior mediastinum and winds around the arch of the aorta. It ascends anterior to the tracheoesophageal groove and can be felt on the lateral aspect of the trachea. It continues upward and becomes intralaryngeal by passing deep to the lower border of the inferior constrictor muscle. The point at which this nerve becomes intralaryngeal is on a level with the inferior horn of the thyroid cartilage.

The *vascular supply* of the larynx is derived from the superior laryngeal branch of the superior thyroid artery and the inferior laryngeal branch of the inferior thyroid artery. The *lymphatics* from the upper part end in glands in the carotid triangle and from the lower part in the glands in front of and beside the larynx and the trachea.

The *cavity* of the larynx may be divided




FIG 164 Thyrotomy laryngotomy and tracheotomy incisions

nosed and almost asphyxiated patient can be immediately relieved by this operation in which a transverse incision is made across the midline of the neck at the level of the upper border of the cricoid cartilage. If the incision is kept close to the upper border, the cricothyroid artery will be avoided. It is then deepened to and through the cricothyroid membrane and a laryngotomy tube is inserted. It should be remembered that the cricothyroid space in

children is so small that it is usually unsuitable for this operation. In extreme emergencies where death from asphyxia appears imminent the blade of a pocket knife has been successfully plunged directly through the cricothyroid membrane and the opening kept patent by rotating the handle of the knife.

Tracheotomy (tracheostomy) may be an elective or emergency procedure. If elective, it is usually a preliminary step to laryn-

wall of the vestibule is longer than the posterior and is formed throughout by mucous membrane which covers the posterior aspect of the epiglottis. Its central point is marked by a rounded elevation, the *tubercle* of the epiglottis, which is important because it is the most noticeable feature on laryngoscopic examination and is frequently the only structure that is visible in the hands of a novice. The aryepiglottic folds contain the aryepiglottic muscles between its two layers of mucous membrane. Posteriorly the vestibule is bounded by the arytenoid cartilages and the interarytenoid fold containing the transverse arytenoid muscle. The aryepiglottic and transverse arytenoid muscles are of great importance because they close the inlet of the larynx during the act of swallowing. The *vestibular fold* of mucous membrane passes backward and laterally from the thyroid angle. It contains a small fibrous band the vestibular ligament (false vocal cord) which stretches from the thyroid angle to the arytenoid cartilage. This fold narrows the lower end of the vestibule.

The *glottis*, or middle compartment, is the narrowest part of the interior of the larynx. It measures nearly an inch anteroposteriorly in the adult male and about three fourths of an inch in the female. It consists of a small sinus, the ventricle or recess and is situated between the vestibular and the vocal folds. The arytenoid cartilages are posterior and are separated by the interarytenoid notch. Approximately two thirds of the anterior part of the glottis consists of the true vocal cords; the posterior third consisting of the interval between the arytenoid cartilages. The *muco-sa* uniting the two arytenoid cartilages forms the posterior or arytenoid commissure and is the usual site of tuberculosis of the larynx. The *true vocal cords* diverge as they pass posteriorly and extend from the vocal process of the arytenoid to the thyroid angle. They appear as short straight folds that are characterized by the pallor

of the covering mucous membrane. This pallor is produced by the absence of loose submucous tissue as well as the absence of blood vessels. The *rima glottidis* (glottic slit) is that fissure which separates the true vocal cords and the arytenoid cartilages, it is triangular when at rest, linear during phonation and lozenge shaped in respiration. The glottis is closed after inspiration, thus aiding fixation of the diaphragm during efforts of expulsion (parturition, defecation, urination and vomiting).

The *infraglottic*, or lowest compartment of the larynx extends from the true vocal cords to the first tracheal ring. Its walls are made up of the thyroid and the cricoid cartilages and the cricothyroid membrane. In emergency laryngotomy this membrane is incised to gain entrance into the larynx.

SURGICAL CONSIDERATIONS

The incision for a *thyrotomy* (*laryngofissure*) (Fig 164) extends from the hyoid bone above to the cricoid cartilage below, it is placed exactly in the midline and deepened until the isthmus of the thyroid gland is exposed. If necessary, this is divided. When the thyroid cartilage is visualized a vertical incision is made in the midline through it and the thyrohyoid membrane. Through this incision tumors of the larynx can be removed and treated when removal of the entire larynx is unnecessary. At times this operation also has been used for the removal of foreign bodies that could not be dislodged by other means. The two segments of thyroid cartilage and membranes are sutured together. Some authorities permit the divided cartilage to fall together without suturing.

Laryngotomy has been used as an emergency procedure when the presence of a foreign body or edema necessitates the rapid admission of air into the larynx. It has also been used as a preliminary step in extensive operative procedures. A cya




FIG 164 Thyrotomy laryngotomy and tracheotomy incisions

no ed and almost asphyxiated patient can be immediately relieved by this operation in which a transverse incision is made across the midline of the neck at the level of the upper border of the cricoid cartilage. If the incision is kept close to the upper border the cricothyroid artery will be avoided. It is then deepened to and through the cricothyroid membrane and a laryngotomy tube is inserted. It should be remembered that the cricothyroid space, in

children is so small that it is usually unsuitable for this operation. In extreme emergencies where death from asphyxia appears imminent, the blade of a pocket knife has been successfully plunged directly through the cricothyroid membrane and the opening kept patent by rotating the handle of the knife.

Tracheotomy (tracheostomy) may be an elective or emergency procedure. If elective it is usually a preliminary step to laryn-




FIG 165 Tracheotomy

gectomy for malignant disease. If, however, it is done as an emergency operation it is utilized where there has been sudden obstruction of the airway as a result of aspiration of a foreign body, edema of the larynx, infections and edema about the throat, or postoperative vocal cord paraly-

sis following injury to both recurrent nerves. Distinction has been made between low and high tracheotomy the low being below the isthmus of the thyroid and the high above it. Most authorities are of the opinion that the low operation is preferable (Fig 165). Here an incision is made extending

from the lower border of the thyroid cartilage downward for about three inches in the midline of the neck. The skin and the subcutaneous tissues are divided and the inferior jugular vein is either ligated or retracted. The sternohyoid muscles are then separated in the midline and retracted laterally exposing the isthmus of the thyroid gland. This in turn is either cut between hemostats or retracted upward since a low tracheotomy is desirable. At this stage a sharp hook is usually placed beneath the cricoid cartilage in the midline to steady the trachea and pull it forward. Usually the third, fourth and fifth tracheal rings are divided from above downward, the opening held open and a tracheotomy tube inserted.

POSTERIOR TRIANGLE

The *posterior triangle* of the neck is formed as the result of a longitudinal cleavage of what in embryonic life was a single muscle plate. This single muscle later becomes the sternocleidomastoid and trapezius which have a continuous attachment above, extending from theinion to the tip of the mastoid. The attachment is aponeurotic and produces the roughened superior nuchal line. Below and because of the cleavage the attachments become disconnected so that the trapezius attaches to the lateral third of the clavicle and the sternocleidomastoid to the medial third.

The posterior triangle is bounded by the posterior border of the sternocleidomastoid muscle below by the middle third of the clavicle and behind by the anterior border of the trapezius (Fig 166). The apex of the triangle is the meeting point of the trapezius and the sternocleidomastoid, and when anterior and posterior borders fail to meet on this line the area is occupied by part of the splenius capitis muscle. The inferior belly of the omohyoid muscle crosses the lower part of the posterior triangle separating it into an upper larger occipital triangle and a lower smaller supraclavicular one. The roof of the posterior triangle is made

up of the investing layer of the deep cervical fascia. The floor is muscular and is formed by the following three muscles from above downward: the *plenius capitis*, the *levator scapulae* and the *scalenus medius*. This muscular floor is carpeted by the prevertebral fascia (Fig 166).

The triangle is related to the following structures from superficial to deep: skin, superficial fascia, platysma, external jugular vein, posterior border of the sternocleidomastoid muscle, four cutaneous nerves that pierce the investing fascia: the spinal accessory nerve, the posterior belly of the omohyoid muscle, the transverse cervical artery and vein, the transverse scapular artery and vein, the prevertebral fascia, the muscular floor and the nerves that lie upon it.

The *skin* of the posterior triangle of the neck is thicker over the upper and posterior part of the triangle than over the lower and anterior part. The *superficial fascia* is usually thin; fat in this region tends to accumulate under the deep fascia rather than superficially.

The *platysma muscle* lies in the superficial fascia of the side of the neck (Fig 125). It arises from the deep fascia covering the pectoralis major and the deltoid muscles as low as the second rib. Its fibers pass upward and medially and become inserted into the lower border of the mandible. Some of the upper fibers reach the face, decussate and mingle with the muscles of the lower lip. It can be seen from its course that the platysma leaves the middle line of the neck and the lower part of the anterior triangle uncovered. The nerve supply of the platysma is by way of the cervical branch of the facial nerve. If a skin incision is made along the sternocleidomastoid muscle and the skin and the superficial fascia carefully are reflected either backward or forward the platysma appears as a very delicate sheet. There is a definite cleavage plane below it which is filled by loose areolar tissue and in which the external jugular vein is found.




FIG 166 The posterior triangle (A) The floor is trimuscular, being made up of the splenius capitis, the levator scapulae and the scalenus medius. The prevertebral fascia forms a carpet for this floor, the fascia has been incised and retracted in this figure. Four nerves pierce the investing fascia, and four nerves lie deep to it. (B) Cross section, the fascia is represented in blue.

The *external jugular vein* travels subcutaneously. It varies greatly in size and is formed by the union of the posterior auricular with a branch of the posterior facial vein. It begins in or at the lower part of the parotid gland, passes vertically downward and across the sternocleidomastoid muscle. In the angle between the clavicle and the posterior border of the sternocleidomastoid it pierces the deep fascia and joins the subclavian vein. It receives the following branches: posterior jugular, anterior jugular, oblique jugular, transverse scapular and transverse cervical.

The *posterior border of the sternocleidomastoid muscle* should be noted because of the nerves in relation to it.

Four superficial nerves pierce the investing layer of deep cervical fascia which is not a strong layer and at times is difficult to display. They can be remembered easily if the landmarks are named from above downward: occiput, ear, neck and clavicle. Thus there are the lesser occipital, the greater auricular, the anterior cutaneous and the supraclavicular nerves. They all appear from approximately the same point, namely, the posterior border of the middle of the sternocleidomastoid muscle. The *lesser occipital nerve* passes upward and along the posterior border of the sternocleidomastoid muscle to reach and supply the skin of the lateral part of the occipital region. The *greater auricular nerve* runs parallel with the external jugular vein and supplies the skin that covers the angle of the jaw, the parotid gland, the ear and the skin over the mastoid region. The *anterior cutaneous nerve* of the neck appears close to the great auricular nerve and runs transversely forward across the sternocleidomastoid muscle; it divides into ascending and descending branches and supplies most of the skin of the side and the front of the neck. In its course across the sternocleidomastoid it lies either superficially or deeply to the external jugular vein. The *supraclavicular nerves* arise a little below the preceding nerve as a single trunk that

divides into three branches: lateral, intermediate and medial supraclavicular nerves which diverge from one another. The medial branch descends over the medial third of the clavicle and supplies the skin of the front of the chest down to the level of the sternal angle. The intermediate crosses the clavicle and descends on the thoracic wall as far as the second rib. The lateral branch passes over the trapezius muscle and the acromion and innervates the skin on the upper and back parts of the shoulder region.

The *spinal accessory nerve* is the highest and most important structure in the triangle. It is placed very superficially, lying immediately beneath the investing layer of fascia. It appears at about the middle of the posterior border of the sternocleidomastoid muscle running under this muscle. Here some small lymph glands surround it and the lesser occipital nerve takes a recurrent course below it. Branches from the third and the fourth cervical nerves run parallel with the accessory and may be mistaken for it. These cervical nerves also sink into the trapezius muscle and aid in its innervation. The fact that the accessory nerve is the highest structure in the triangle should avoid confusion.

The *inferior (posterior) belly of the omohyoid muscle* springs from the upper border of the scapula and the suprascapular ligament under cover of the trapezius muscle. It is located about an inch above the clavicle, passes upward and enters the posterior triangle at its lower and posterior angle. As it continues forward and slightly upward it crosses the brachial plexus, continues to the sternocleidomastoid muscle, crosses the scalenus anticus and joins the tendon that connects it to the superior belly of the muscle. The tendon lies under cover of the sternocleidomastoid and on the internal jugular vein. The inferior belly, as it crosses the posterior triangle, lies superficial to the suprascapular nerve, the transverse cervical artery and the brachial plexus. The muscle can

be felt through the skin and the fascia a little above the clavicle. Its movements may be seen in a thin person while he is talking. It lies between the investing and the prevertebral layers of the deep cervical fascia and is covered by a specially thickened part of the pretracheal layer. This thickened fascia binds the muscle to the posterior surface of the clavicle and to the first rib. In order to dislocate the inferior belly its fascia should be incised along its upper border and the muscle pulled downward. The nerve supply to the omohyoid is through the *ansa hypoglossi*.

The *transverse cervical artery* lies under the omohyoid muscle (Fig 168). It is a branch of the thyrocervical trunk, and as it passes backward it crosses the scalenus anticus and the phrenic nerve. In its course it also crosses the brachial plexus and the suprascapular nerve. In the occipital triangle it divides into a superficial and deep branch, the superficial supplying the deep surface of the trapezius muscle, and the deep branch accompanying the levator scapulae muscle to the scapula and taking part in the scapular anastomosis. Occasionally the transverse cervical artery is small and spends itself in the trapezius; it then is referred to as the superficial cervical artery. The *transverse scapular*, or *suprascapular, artery* is also found in the lowermost portion of the supraclavicular triangle and it too is a branch of the thyrocervical trunk. It runs laterally and downward under cover of the sternocleidomastoid across the scalenus anticus muscle and the phrenic nerve. It passes laterally behind the middle third of the clavicle and in front of the subclavian artery toward the posterior angle of the triangle. From this point on it accompanies the supraclavicular nerve to the scapula. Behind the clavicle it is closely accompanied by one or two veins. The suprascapular and the transverse cervical veins run quite superficial to their arteries. The arteries therefore, are accompanied not by their own veins but by slender venules as they cross

the scalenus anticus muscle. The veins end in the external jugular. The supraclavicular and the transverse cervical arteries clamp the phrenic nerve onto the scalenus anticus muscle.

The *prevertebral fascia* forms a carpet that covers the cervical part of the brachial plexus and the subclavian vessels and provides a fascial sheath for them as they enter the axilla. The carpet also covers four motor nerves: those to the levator scapulae, the rhomboids, the serratus anterior and the diaphragm. Since the spinal accessory is the highest nerve in the posterior triangle, one may dissect cephalad to it without much risk since the only other structure in the region of the apex of the posterior triangle is the occipital artery.

The *floor* of the triangle is muscular. The *levator scapulae muscle* occupies the most central position of the three muscles named. It arises from the posterior tubercles of the transverse processes of the upper four cervical vertebrae and is inserted into the vertebral border of the scapula between the root of the spine and the superior angle. Cephalad to the levator and parallel with it is the *splenius capitis muscle* which arises from the lower half of the ligamentum nuchae and the succeeding vertebral spines. It passes upward and laterally, forming the upper part of the floor, and is inserted into the mastoid process and the adjoining part of the occipital bone under cover of the sternocleidomastoid muscle. Caudad to the levator scapulae and parallel with it are the three scalenus muscles. The *scalenus medius* arises from the posterior tubercles of all the cervical transverse processes (second and third, fourth, fifth and sixth) and is inserted into the upper part of the first rib between the groove for the subclavian artery and the neck of the rib. It is best not to consider the *scalenus posterior* as a separate muscle but as that portion of the scalenus medius that passes on to the second rib and inserts there (Fig 128). The *scalenus anterior* is separated from the medius and the posterior by the brachial

plexus and the subclavian artery. It arises from the anterior tubercles of all the transverse processes (third, fourth, fifth and sixth). Its posterior border is parallel with and therefore hidden by the posterior border of the sternocleidomastoid muscle. It is not considered actually a part of the floor of the posterior triangle since it is hidden from view. The scalenus anterior inserts into the scylene tubercle (Lisfranc), which is situated on the upper surface of the first rib. Of the structures that lie between the accessory nerve and the omohyoid, the largest and most outstanding is the brachial plexus. Its upper part lies in the occipital triangle but most of the plexus, as it passes through the neck, lies behind the inferior belly of the omohyoid and in the supraclavicular triangle. The formation of this plexus has been discussed on page 675. When the posterior border of the sternocleidomastoid is drawn forward the nerves forming the plexus are seen emerging from between the scalenus anterior and the medius. This relationship is a useful landmark as it enables the two muscles to be identified. The supraclavicular nerve is quite thick and runs downward and backward immediately above the plexus. The nerve to the rhomboids is found a little higher; it pierces the substance of the scalenus medius muscle, runs downward and disappears under cover of the levator scapulae muscle to which it usually gives a branch. Its terminal branches supply the rhomboid muscle. If the upper part of the brachial plexus is pulled forward the nerve to the serratus anterior commonly called the *long thoracic nerve* is seen. It arises from the back of the brachial plexus and disappears under cover of it. The nerve to the subclavius can be identified here.

PRAC T I C A L A N D S U R G I C A L A S P E C T S

Cervical Rib and Scalenus Syndrome
Adson and Coffey believe that tenotomy of the scalenus anticus muscle is preferable to the more radical resection of the cer-

vical rib. The typical syndrome may occur when there is no cervical rib present, and in the absence of such a rib, the condition is referred to as the *scalenus anticus syndrome* (Naffziger). Ochsner, Gage and DeBakey believe that the scalenus anticus syndrome is produced by spasms and contractions of the muscle. They have been able to relieve the symptoms temporarily by injecting the muscle with procaine. The symptoms of compression of the brachial plexus and the subclavian artery are usually pain, numbness, atrophy and circulatory changes (cyanosis, ulcers, gangrene).

A cervical rib attached to the transverse process and body of the seventh cervical vertebra may vary from a simple bony bulge to a full and well developed rib (Fig. 167C). If such a projection is small its outer extremity may be free and unattached but if it is longer it may be joined to the first thoracic rib by fibrous attachments.

The operative procedure that has given most success for both cervical rib and scalenus anticus syndrome is executed through an anterior approach that has been described by Adson (Fig. 167). An oblique incision is made about 5 cm. in length extending upward and backward from the sternoclavicular articulation into the posterior triangle of the neck. The incision is deepened through the fat and the platysma, the tendon of the sternocleidomastoid muscle is exposed at its clavicular attachment and is divided between forceps, the muscular portion being reflected medially. The tendon of the omohyoid is found and may be either retracted or severed. The scalenus anticus muscle is identified as is the phrenic nerve which runs obliquely across it from lateral to medial; the nerve is retracted. The borders of the scalenus muscle are dissected free and its tendinous and muscular fibers are divided close to its insertion. The subclavian artery is lateral to the scalenus anticus and the pleura medial. As soon as the muscle has been

be felt through the skin and the fascia a little above the clavicle. Its movements may be seen in a thin person while he is talking. It lies between the investing and the prevertebral layers of the deep cervical fascia and is covered by a specially thickened part of the pretracheal layer. This thickened fascia binds the muscle to the posterior surface of the clavicle and to the first rib. In order to dislocate the inferior belly, its fascia should be incised along its upper border and the muscle pulled downward. The nerve supply to the omohyoid is through the ansa hypoglossi.

The *transverse cervical artery* lies under the omohyoid muscle (Fig 168). It is a branch of the thyrocervical trunk and as it passes backward it crosses the scalenus anticus and the phrenic nerve. In its course it also crosses the brachial plexus and the suprascapular nerve. In the occipital triangle it divides into a superficial and deep branch: the superficial supplying the deep surface of the trapezius muscle and the deep branch accompanying the levator scapulae muscle to the scapula and taking part in the scapular anastomosis. Occasionally the transverse cervical artery is small and spends itself in the trapezius; it then is referred to as the superficial cervical artery. The *transverse scapular or suprascapular artery* is also found in the lowermost portion of the supraclavicular triangle and it too is a branch of the thyrocervical trunk. It runs laterally and downward under cover of the sternocleidomastoid across the scalenus anticus muscle and the phrenic nerve. It passes laterally behind the middle third of the clavicle and in front of the subclavian artery toward the posterior angle of the triangle. From this point on it accompanies the supraclavicular nerve to the scapula. Behind the clavicle it is closely accompanied by one or two veins. The suprascapular and the transverse cervical veins run quite superficial to their arteries. The arteries therefore, are accompanied not by their own veins but by slender venules as they cross

the scalenus anticus muscle. The veins end in the external jugular. The supraclavicular and the transverse cervical arteries clamp the phrenic nerve onto the scalenus anticus muscle.

The *prevertebral fascia* forms a carpet that covers the cervical part of the brachial plexus and the subclavian vessels and provides a fascial sheath for them as they enter the axilla. The carpet also covers four motor nerves: those to the levator scapulae, the rhomboids, the serratus anterior and the diaphragm. Since the spinal accessory is the highest nerve in the posterior triangle, one may dissect cephalad to it without much risk since the only other structure in the region of the apex of the posterior triangle is the occipital artery.

The *floor of the triangle* is muscular. The *levator scapulae muscle* occupies the most central position of the three muscles named. It arises from the posterior tubercles of the transverse processes of the upper four cervical vertebrae and is inserted into the vertebral border of the scapula between the root of the spine and the superior angle. Cephalad to the levator and parallel with it is the *splenius capitis muscle* which arises from the lower half of the ligamentum nuchae and the succeeding vertebral spines. It passes upward and laterally, forming the upper part of the floor, and is inserted into the mastoid process and the adjoining part of the occipital bone under cover of the sternocleidomastoid muscle. Caudad to the levator scapulae and parallel with it are the three scalenus muscles. The *scalenus medius* arises from the posterior tubercles of all the cervical transverse processes (second, third, fourth, fifth and sixth) and is inserted into the upper part of the first rib between the groove for the subclavian artery and the neck of the rib. It is best not to consider the *scalenus posterior* as a separate muscle but as that portion of the scalenus medius that passes on to the second rib and inserts there (Fig 128). The *scalenus anterior* is separated from the medius and the posterior by the brachial

sults during the course of a complicated delivery with marked downward traction resulting in a widening of the angle between the head and the shoulder. The injury usually occurs where the fifth and the sixth cervical nerves join to form the upper trunk of the plexus; this is known as Erb's point, which is the spot where six nerves meet: fifth cervical, sixth cervical root, anterior division of upper trunk, posterior division of upper trunk, supra-scapular nerve and the nerve to the subclavius. The hand hangs at the side in internal rotation with the forearm pronated and the fingers and the wrist flexed. This is referred to by some as the "head waiter's tip hand." Internal rotation and abduction are lost at the shoulder as are flexion and supination of the forearm. Some authorities are of the opinion that when this lesion occurs later in life there is some associated dulling of sensation over the lower part of the deltoid, the arm and the forearm. The clinical appearance is produced by a paralysis of the abductors and the lateral rotators of the shoulder (deltoid, supraspina-

tus and infraspinatus) plus a paralysis of the flexors of the elbow (biceps brachialis and brachioradialis); a weakness of the adductors and the medial rotators of the shoulders (pectoralis major, *teres major* latissimus dorsi, subscapularis) also results. The pronator teres, the supinator, the flexors of the wrist and the thenar muscles may be slightly involved. The *middle arm type lesion* involves the seventh cervical nerve and produces a paralysis of the entire radial nerve except its branch to the brachioradialis; there is also a paralysis of the coracobrachialis. *Arm plexe (lower arm) paralysis* is usually the result of upward traction on the shoulder. It may also be found in injuries or during breech presentations when the arms are placed over the head. The lesion involves the eighth cervical and the first thoracic nerve. It results in a paralysis of the intrinsic muscles of the hand and a paralysis of the flexors of the digits; a "claw hand" results. There is also diminished sensation over the medial side of the arm, the forearm and the hand.




FIG 167 Sectioning of the scalenus anticus muscle and the removal of a cervical rib (A) incision (B) exposure of the scalenus anticus muscle after cutting the clavicular attachment of the sternocleidomastoid muscle (C) a cervical rib causing pressure on the brachial plexus (D) removal of a cervical rib

divided the subclavian artery can be dissected free and will drop forward. A cervical rib if present, is examined and if it is causing no pressure, further operative procedure is unnecessary. However if the rib or its tendinous attachment to the first rib is producing posterior pressure upon the brachial plexus a portion of the rib and the tendon must be removed.

Brachial Plexus Lesions Brachial plexus lesions are divided into those lesions that involve the entire plexus or only the

upper, middle or lower portions of the plexus (p 678). When the entire plexus is involved either from injury or pressure the following features are noted: complete anesthesia of the lower part of the arm, the forearm and the hand; flaccid paralysis of the superior extremities with eventual wasting of the muscles. *Erb-Duchenne (upper arm) paralysis* is the commonest type of nerve injury occurring at birth and involving the fifth and the sixth cervical nerves. Upper arm palsy usually re-




FIG 168 The arteries in the root of the neck (A) the subclavian artery is divided into three parts by the scalenus anticus muscle (B) the subclavian artery and vein are separated by the scalenus anticus muscle (side view)

structures Posteriorly, it is in contact with the cervical dome of the pleura and the apex of the lung. It is located in that triangular space that exists between the anterior and the middle scalene muscles the base or floor of which corresponds to the first rib (Fig 168B). Above and lateral

to it are the trunks of the brachial plexus to see these relationships and this part of the artery it is necessary to cut the anterior scalene muscle transversely. Because of the presence of the phrenic nerve dissection of this muscle cannot be complete if the nerve is not properly protected. The

Root of the Neck

The region referred to as the *root of the neck* is really the thoracocervical region that forms a boundary between the neck and the thorax and is occupied by structures that enter or leave the thoracic cavity

(Fig 168) The *right common carotid* and the *subclavian arteries* arise from the innominate immediately behind the right sternoclavicular joint which is made up of the sternal end of the first costal cartilage, the medial end of the clavicle and the clavicular notch of the manubrium sterni (p 265) The joint and the scalenus anterior muscle are landmarks in this region The *left common carotid* and the *subclavian arteries* arise directly from the aortic arch and after a course of about an inch pass into the neck behind the left sternoclavicular joint On the right side the two infrahyoid muscles intervene between the arteries and the joint, but on the left side the left innominate vein intervenes On both sides the common carotid is placed in front of the subclavian artery at the entrance to the neck and ends in the carotid triangle by dividing into the internal and external carotids It has no collateral branches

The *subclavian artery* courses through the neck and describes a gentle curve with the convex portion in an upward direction The scalenus anterior muscle crosses the artery, dividing the vessels into three parts the *prescalenus* (a part before) *retroscalenus* (a part behind) and *postscalenus* (a part after) The artery therefore, not only occupies the root of the neck but the superior mediastinum as well and becomes the axil-

lary artery at the lateral border of the first rib The *prescalenus portion* of the artery passes upward and laterally to the medial border of the scalenus anterior Anteriorly, the following structures are encountered in a lateral direction the common carotid artery, the *ansa subclavii*, the *vagus nerve* and the *internal jugular vein* the latter being separated in part from the artery by the vertebral vein and on the left side by the phrenic nerve Posteriorly the artery is intimately related to the cervical dome of the pleura and the apex of the lung The branches from this part of the vessel are the vertebral the thyrocervical trunk and the internal mammary Grant has described a "triangle of the vertebral artery" which has as its base the first part of the subclavian artery, its lateral side is the scalenus anterior and its medial side the longus cervicis, the apex being made up of the anterior tubercle of the sixth cervical transverse process (Fig 169) The triangle is anatomically best seen when the common carotid artery and the internal jugular vein are divided low The posterior wall of the triangle, from above downward is made up of the transverse process of the seventh cervical vertebra the anterior ramus of the eighth cervical nerve, the neck of the first rib, and the cervical pleura which rises to the neck of the first rib The triangle contains the vertebral artery, the vertebral vein which descends in front of the artery and crosses the subclavian artery, the inferior thyroid artery and the ganglionated sympathetic trunk The *retroscalenus portion* of the subclavian artery lies behind the scalenus anterior and its superimposed




FIG 169 The vertebral triangle and its contents

ess of the sixth cervical vertebra it is surrounded by a plexus of sympathetic nerve fibers and is covered by the vertebral and the internal jugular veins. The second part ascends through the foramina in the transverse processes of the upper six cervical vertebrae. The third part emerges from the foramen transversarium of the atlas and passes almost horizontally backward and medially behind the lateral mass of the atlas. The fourth part pierces the spinal dura mater and travels upward into the cranial cavity through the foramen magnum, joining the internal carotid artery

to form the circle of Willis. The *vertebral em* descends in front of the artery and may hide it. As it descends, it deviates to the lateral side of the artery and crosses in front of the first part of the subclavian artery. It ends in the posterior aspect of the innominate vein near its origin. The *thyrocervical trunk* also arises from the upper part of the subclavian artery at the medial border of the *scalenus anterior* muscle and at once breaks up into three branches: the *suprascapular*, the *transverse cervical* and the *inferior thyroid* arteries. Only the *inferior thyroid* occupies

costocervical trunk arises from the posterior aspect of this part of the subclavian artery passes backward above the pleura to the neck of the first rib where it divides into the superior intercostal and the deep cervical arteries (Fig 168A) The *post scalene portion* of the subclavian artery extends from the lateral border of the scalenus anterior to the outer border of the first rib Aneurysm of the subclavian, as a rule involve this portion and appear as a swelling in the posterior triangle of the neck just above the clavicle Because of the close proximity of the subclavian vein, an edema of the upper extremity may result Ligation of this artery is best carried out in its third part

The *subclavian vein* has only two parts that correspond to the second and the third parts of the artery the beginning of the innominate vein substitutes for the first part This is understandable if it is remembered that the internal jugular vein crosses the first part of the subclavian artery in order to make that union known as the innominate vein The termination of the internal jugular then crosses and conceals the pre-scalenus portion of the subclavian artery hence no similar part of the subclavian vein exists the subclavian is a continuation of the axillary vein At the junction of the sternum with the clavicle the subclavian vein unites with the internal jugular to form the innominate It begins at the outer border of the first rib runs medially and almost transversely behind the clavicle lying in front of the subclavian artery which it accompanies throughout its course with the exception of that point where the artery and the vein are separated by the anterior scalene muscle The vertebral and the internal mammary veins pass directly into it there being no thyrocervical or costocervical venous trunks The inferior thyroid veins drain into the innominate vein the transverse cervical and suprascapular veins open into the external jugular vein The deep cervical, the ascending cervical and the vein

from the first intercostal space drain into the vertebral before it crosses the subclavian artery to end in the innominate vein

The *right innominate vein* lies deeply to the inner end of the right clavicle from which it is separated by the sternohyoid and the sternothyroid muscles It is related to the medial surface of the right pleura and partly overlies the innominate artery It passes vertically downward into the superior vena cava The *left innominate vein* passes downward behind the upper part of the manubrium to the lower margin of the first right costal cartilage where it ends in the superior vena cava It is covered in front by the left sternoclavicular joint and on the right is overlapped by the right pleura Remnants of the thymus intervene between it and the sternum The vein is on the level of or at times slightly above the upper margin of the manubrium and is endangered in removal of tumors at the root of the neck or in low tracheotomy

The *scaleno-vertebral angle* takes the form of an inverted V, is bounded laterally by the scalenus anterior muscle and medially by the longus cervicis (colli) muscle These two muscles meet at the carotid tubercle (Chassaignac's), which is the well developed anterior tubercle of the transverse process of the sixth cervical vertebra and forms the apex of the triangle (Fig 169) The roof is formed by the sternocleidomastoid muscle

The lower part of this angle is crossed by the *subclavian artery* which disappears behind the scalenus anterior muscle but before disappearing it gives rise to two large branches from its upper border the vertebral artery and the thyrocervical trunk As these two vessels ascend they fill the gap in the scaleno-vertebral angle The *vertebral artery* is the first and largest branch of the subclavian (Fig 170) It is divided into four parts the first part passes upward and backward between the scalenus anterior and the longus cervicis muscles and through the foramen in the transverse proc

SECTION THREE

THE THORAX




FIG 170 The vertebral artery the artery is divided into four parts

the scalenovertebral angle. It reaches the level of the sixth cervical transverse process, turns medially and downward and terminates at the posterior border of the lobe of the thyroid gland. The course of this vessel resembles an inverted U. As the artery curves medially it passes over the vertebral vessels and below the carotid system.

The *thoracic duct* occupies the left side of the scalenovertebral angle. Its course is similar to that of the inferior thyroid artery, but it loops in the reverse direction and at a lower level than does the vessel. In the neck the duct forms an arch that

reaches as high as the seventh cervical vertebra, arching behind the carotid system (internal jugular vein, vagus nerve and common carotid artery), and in front of the vertebral system (vertebral vessels). As it passes to the left it also crosses the scalenus anterior muscle and the phrenic nerve. Continuing its course it crosses the transverse cervical and transverse scapular arteries and usually ends as a single vessel entering the junction of the subclavian and left internal jugular veins. The duct sometimes divides, one vessel entering the vein on the right and the other entering on the left side.

SECTION THREE

THE THORAX

10

Bony Thorax

The thorax is shaped like a truncated cone which is flattened from before backward and contains important organs of respiration, circulation and digestion. Its anterior wall is the shortest and is formed by the sternum and the anterior portions of the first ten pairs of ribs with their corresponding costal cartilages. The lateral walls are formed by the ribs which slope obliquely downward and forward. The posterior wall is made up of the twelve thoracic vertebrae and the ribs as far as their angles (Figs 171-172). At birth and about two years thereafter the thorax is circular and does not resemble the oval-shaped adult thorax (Fig. 173). Because of this difference the adult thorax may be increased in thoracic breathing but this is impossible in the child since the circumference remains constant in the latter. For this reason breathing in the first two years of life is almost entirely abdominal (diaphragmatic) but as the individual grows older breathing becomes intercostal (thoracic). Because children's breathing is not thoracic they are supposed to be more susceptible to postoperative pneumonia. The child restricts his abdominal movements because of pain thereby interfering with excursions of the diaphragm; this results in poorly aerated lungs which become filled with accumulated secretions. The child's thorax may be referred to as the normal barrel chest of early life. The thorax has a small kidney-shaped superior aperture and a large irregular inferior one.

The *superior aperture* is the inlet and measures approximately two by four inches (Fig. 173). It slopes from behind downward

and forward. Its boundaries are formed by the body of the first thoracic vertebra, the first rib, the first cartilages and the upper border of the manubrium sterni. It is kidney-shaped; the first thoracic vertebra representing the hilum. Because of the downward slope of this aperture the anterior part of the apex of the lung rises above the anterior boundary of the inlet but its posterior part rises only to the level of the neck of the first rib. The diaphragm of the aperture is fascial and is called *Sibson's fascia* (Fig. 171B). It is pyramidal-shaped and extends from the transverse process of the seventh cervical vertebra to the inner border of the first rib and in this way protects the cervical dome of the pleura which is closely associated with its under surface. The scalene muscles replace intercostal muscles in this area and are internally lined by Sibson's fascia.

The *inferior aperture* is the outlet of the thorax. It is large and irregular and bounded by the twelfth thoracic vertebra, the lowest ribs, the seventh to the twelfth costal cartilages and the xiphisternal joint. It is much wider than the inlet and is occupied by the diaphragm.

Certain *conventional longitudinal lines* are used for the purpose of description and orientation. They run parallel with the long axis of the body and are (Fig. 171):

- 1 The *midsternal line*—bisects the sternum and corresponds to the midline of the back.

- 2 The *mammary line*—this is dropped from the inner aspect of the clavicle and usually passes through the nipple.

- 3 The *parasternal line*—lies midway be-




FIG 171 The bony thorax (A) Anterior view with the conventional longitudinal lines shown (B) Sibson's fascia, which forms the diaphragm for the superior aperture

tween the midsternal and the mammary lines

4 The *anterior axillary line*—this runs through the anterior axillary fold

5 The *posterior axillary line*—passes through the posterior axillary fold

6 The *midaxillary line*—this is dropped from the middle of the axillary space

7 The *scapular line*—this runs through the apex of the inferior angle of the scapula

8 The *paravertebral line*—opposite the tips of the transverse processes of the vertebrae (used in radiology)

RIBS (COSTAE)

The 12 pairs of ribs form a series of obliquely placed bony arches which constitute the greater part of the wall of the thoracic cage. They overhang the upper part of the abdomen articulate with vertebrae posteriorly and end in costal cartilages anteriorly. They increase in length from the first to the seventh and then become progressively shorter. The first 7 pairs are called *true ribs* because their cartilages articulate with the sternum; the cartilages of the last 5 pairs, however, are known as




FIG 172 Posterior view of the bony thorax




FIG 173 The bony thorax as viewed from above The small inserts show the transverse section of a child's thorax as compared with that of an adult

false ribs The eighth the ninth and the tenth pairs end by turning upward to join the costal cartilage above but the eleventh and the twelfth are free at their extremities and are known as *floating ribs*. All the ribs can be felt through the overlying soft structures with the exception of the first, which

is hidden by the clavicle, and occasionally the twelfth which may be absent or very short. The second rib always can be identified where its cartilage reaches the sternum at the sternal angle. Therefore, when it is necessary to locate a given rib, the second should be found and the succeeding

ribs should be counted from above downward following a line about one inch from the sternum which passes downward and slightly laterally. The ribs vary in length, the longest (seventh or eighth) being two

hind this is a rough area for the lateral costotransverse ligament. The *shaft* is compressed laterally, giving it internal and external surfaces, which are separated by superior and inferior borders. It not only




Fig 174 A typical rib (A) the individual parts of the rib are identified, (B) the nutrient artery enters just beyond the tubercle

or three times as long as the shortest (first or twelfth). The typical ribs are the third to the ninth inclusive but the first, the second, the tenth, the eleventh and the twelfth have special characteristics.

The so called *typical rib* (Fig 174) articulates with two vertebrae namely, the vertebra to which it numerically corresponds and the vertebra above this. It has a head, a neck, a tubercle and a shaft; the last named structure has an angle posteriorly and a costal groove inferiorly. The *head* presents a kidney shaped articular surface which is divided into two facets by a transverse crest. These facets articulate with the contiguous facets on the lateral aspect of the bodies of the two adjacent vertebrae. From the intervening crest or ridge, an interarticular ligament passes to the intervertebral disk. The *neck* is constricted and is about one inch long; its upper border is raised into a *crest*. The *tubercle* is located on the back of the junction of the neck and the shaft; below, it reveals a smooth round facet for articulation with the corresponding transverse process, and above and be-

hind this is a rough area for the lateral costotransverse ligament. The *shaft* is compressed laterally, giving it internal and external surfaces, which are separated by superior and inferior borders. It not only has a curved but also a twisted appearance. The curvature is greatest posteriorly, and its maximum point is known as the *angle*, which is marked by a ridge on its external surface; the latter being smooth and covered with muscles. The internal surface is also smooth but is covered with pleura; the superior border is rounded and the inferior border is grooved. The costal groove contains the intercostal vessels and nerves which are protected by its sharp overhanging outer margin. The *anterior (sternal) extremity* of the shaft is oval in shape and concave for the reception of the costal cartilage.

The *special ribs* are the first, the second, the tenth, the eleventh and the twelfth; they are so called because they possess special features by which they may be identified.

The *first rib* has been called the 'superlative' rib because it is the highest, broadest, strongest, flattest, most curved and, with the occasional exception of the twelfth, the shortest of all the ribs (Fig 175). Its angle coincides with its tubercle. It is placed

almost horizontally so that its surfaces face upward and downward and it articulates with only one vertebra. The head is small and has only one facet, which articulates with the body of the first thoracic vertebra.

is intermediate in size and shape. It lies between the first and the lower ribs, although sharply curved, it is not twisted (Fig. 175). Its angle is just lateral to its tubercle and its surfaces are oblique. This




FIG. 175. The first and the second ribs as seen from above, the muscular attachments have been identified.

the neck is relatively long. The tubercle is fairly large and articulates with the first thoracic transverse process. The lower surface of this rib is smooth and devoid of any important landmarks, but the upper surface presents several important features. A roughened area is present for the insertion of the scalenus medius and the origin of the first digitation of the serratus anterior. The front of this rib is crossed by a wide shallow groove, which lodges the subclavian artery. Along the inner border and anteriorly this arterial groove is limited by the scalene tubercle (*Isfranc*) where the scalenus anterior muscle inserts. The size of the tubercle varies, in some cases forming a prominent point while in others it is barely recognizable. Anterior to this a shallow groove is noted which lodges the subclavian vein. The rib does not contain a costal groove; its lower smooth surface is covered with pleura, and its sternal end is enlarged to receive the lateral extremity of the first costal cartilage. The second rib

has a poorly marked costal groove and a rough elevation near the middle of its outer surface where the lower part of the first digitation and the whole of the second digitation of the serratus anterior attach. The scalenus posterior is attached behind this point. The tenth rib resembles a typical rib but is shorter and its head usually presents only one facet for the body of the tenth thoracic vertebra. It is the uncertain rib since it may articulate with the ninth cartilage, which may be connected to it by a ligament or may remain free as a floating rib. The eleventh rib is short and has only a single facet on its head for the eleventh thoracic vertebra; it does not have a neck or tubercle and its costal groove is difficult to see. The twelfth rib is very short and has only one facet on its head; it lacks a tubercle, an angle, and a costal groove. It should be noted that the inner surfaces of both the eleventh and the fourth ribs look upward as well as inward.

The blood supply reaches each rib through

its own nutrient vessel which enters just beyond the tubercle and runs forward as far as the inner extremity of the bone (Fig 174B). An additional supply is obtained from the periosteal vessels. The periosteum of the ribs strips easily from the bone but that of the sternum does not. H. A. Harris has pointed out that no anastomosis occurs between the vessels of the diaphysis and the epiphysis of the ribs and that the vessels of the former are virtually "end arteries".

Ossification resembles the long bones of the limbs and the bodies of the vertebrae, since it begins to take place in the second fetal month. The process begins near the angle and continues in both directions but fails to reach the sternal end resulting in costal cartilages.

The ribs, the vertebrae, the sternum and the diploe of the skull are filled with the red blood forming marrow. It is in these bones and not in the limbs that the blood elements are formed after puberty.

The *costal cartilages* continue the costal arches in front of the anterior extremities of the ribs. The first 7 cartilages are continued forward and articulate with the sternum. The eighth, the ninth and the tenth anterior extremities end by joining with the costal cartilage above. These form a continuous cartilaginous ridge known as the *subcostal margin* which forms a part of the inferior aperture of the thorax. The cartilages increase in length from the first to the seventh and below this point they diminish. When traced downward the intervals between the cartilages diminish.

STERNUM (BREAST BONE)

The *sternum* (Fig 176) is an elongated flat bone which is situated in the midventral line of the thorax and forms the anterior boundary of the thoracic cavity. It is shaped much like an old Roman sword having a short handle called the *manubrium*, a longer blade called the *body* and a small piece of cartilage at its lower end known as the *xiphoid (ensiform) process*.

In early fetal life the sternum is represented by right and left cartilaginous plates with which the rib cartilages articulate (Fig 176D). Later, these two plates fuse but this may be incomplete, resulting in a foramen. Although the bone becomes ossified in late fetal life the constituent parts of the body do not begin to fuse until puberty. During its early development it consists of 6 segments (*sternebrae*) but in the adult the 4 middle *sternebrae* become fused, resulting in the 3 mature sternal parts named above.

The *manubrium* is irregularly quadrilateral in shape and is the broadest and most massive part of the bone. Its anterior surface is rough but the posterior is smooth. The upper border presents 3 notches 2 of which are called *clavicular notches* which articulate with the clavicles, and a centrally placed *suprasternal (jugular) notch*. The latter can be felt easily through the skin and lies on the same horizontal plane as the disk between the second and the third thoracic vertebrae. At times, the left innominate vein and the "right" innominate artery barely reach above this notch. The manubrium, which is about 2 inches long, lies about 2 inches in front of the second thoracic vertebra (Fig 176E).

The *body* of the sternum is about 4 inches long and is made up of 4 *sternebrae*. In the adult lines can be noted which mark the sites of fusion of the *sternebrae* as they cross the anterior surface of the body, between angular depressions on the sides. The lateral borders show a series of facets for the anterior extremities of the costal cartilages. They are arranged in the following manner: a small facet above with which a similar facet of the manubrium forms a cavity for the anterior extremity of the second costal cartilage; a facet opposite the extremity of the first transverse ridge for the third costal cartilage which is formed partly by the first and partly by the second piece; a facet opposite the second ridge, partly on the second segment and partly on the third, for the fourth costal cartilage, a




FIG 176 The sternum. Muscular origins have been colored red and insertions blue. (A) Front view: the four sternabrae and the articulating facets are shown. (B) Side view: The formation of the sternal angle is best seen from this view. (C) Posterior view: This surface is smooth and is related to the pericardium and pleurae. (D) The two embryonic cartilaginous plates from which the sternum is formed. (E) Side view to show the thoracic levels of the jugular notch, the manubrio-sternal joint and the xiphoid process.

facet for the fifth costal cartilage partly on the third and partly on the fourth segment opposite the third transverse ridge and a facet at the side of the fourth segment for

the sixth costal cartilage. At the lowest part of the lateral border a small facet is noted which is completed by a similar one on the xiphoid for the seventh costal cartilage.

its own nutrient vessel which enters just beyond the tubercle and runs forward as far as the inner extremity of the bone (Fig 174B). An additional supply is obtained from the periosteal vessels. The periosteum of the ribs strips easily from the bone, but that of the sternum does not. H. A. Harris has pointed out that no anastomosis occurs between the vessels of the diaphysis and the epiphysis of the ribs and that the vessels of the former are virtually "end arteries."

Ossification resembles the long bones of the limbs and the bodies of the vertebrae since it begins to take place in the second fetal month. The process begins near the angle and continues in both directions but fails to reach the sternal end resulting in costal cartilages.

The ribs, the vertebrae, the sternum and the diploe of the skull are filled with the red blood forming marrow. It is in these bones and not in the limbs that the blood elements are formed after puberty.

The *costal cartilages* continue the costal arches in front of the anterior extremities of the ribs. The first 7 cartilages are continued forward and articulate with the sternum. The eighth, the ninth and the tenth anterior extremities end by joining with the costal cartilage above. These form a continuous cartilaginous ridge, known as the *subcostal margin* which forms a part of the inferior aperture of the thorax. The cartilages increase in length from the first to the seventh, and below this point they diminish. When traced downward the intervals between the cartilages diminish.

STERNUM (BREAST BONE)

The *sternum* (Fig 176) is an elongated flat bone which is situated in the midventral line of the thorax and forms the anterior boundary of the thoracic cavity. It is shaped much like an old Roman sword having a short handle called the *manubrium*, a longer blade called the *body* and a small piece of cartilage at its lower end known as the *xiphoid (ensiform) process*.

In early fetal life the sternum is represented by right and left cartilaginous plates with which the rib cartilages articulate (Fig 176D). Later, these two plates fuse but this may be incomplete, resulting in a foramen. Although the bone becomes ossified in late fetal life, the constituent parts of the body do not begin to fuse until puberty. During its early development it consists of 6 segments (sternabrae), but in the adult the 4 middle sternabrae become fused, resulting in the 3 mature sternal parts named above.

The *manubrium* is irregularly quadrilateral in shape and is the broadest and most massive part of the bone. Its anterior surface is rough but the posterior is smooth. The upper border presents 3 notches, 2 of which are called *clavicular notches* which articulate with the clavicles, and a centrally placed *suprasternal (jugular) notch*. The latter can be felt easily through the skin and lies on the same horizontal plane as the disk between the second and the third thoracic vertebrae. At times, the left innominate vein and the "right" innominate artery barely reach above this notch. The manubrium which is about 2 inches long, lies about 2 inches in front of the second thoracic vertebra (Fig 176E).

The *body of the sternum* is about 4 inches long and is made up of 4 sternabrae. In the adult, lines can be noted which mark the sites of fusion of the sternabrae as they cross the anterior surface of the body, between angular depressions on the sides. The lateral borders show a series of facets for the anterior extremities of the costal cartilages. They are arranged in the following manner: a small facet above, with which a similar facet of the manubrium forms a cavity for the anterior extremity of the second costal cartilage, a facet opposite the extremity of the first transverse ridge for the third costal cartilage, which is formed partly by the first and partly by the second piece, a facet opposite the second ridge, partly on the second segment and partly on the third, for the fourth costal cartilage, a

lique, internal oblique and transversus muscles—to the lateral border of the xiphoid

8 The *rectus abdominis*—to the anterior surface of the xiphoid

Fractures of the sternum are rare but when present they occur most frequently at the junction of the manubrium with the body. At this point the bone is thinnest. The ligamentous attachments usually protect underlying structures but at times the upper fragment may pass behind the lower and compress the trachea or injure the aorta.

STERNOCLAVICULAR JOINT

The line of the *sternoclavicular joint* (Fig. 177) passes from above downward and laterally. The articular surface of the clavicle is larger than the sternal facet; therefore it comes in contact below with the first costal cartilage. In this way the sternal end of the first cartilage takes part in the articulation in addition to the medial end of the clavicle and the clavicular notch of the manubrium sterni. The joint is surrounded by a rather loose *capsular ligament* which is lined with synovial membrane and is attached to the margins of the articular surfaces. This ligament is strengthened behind and in front by the *anterior* and *posterior sternoclavicular ligaments* whose fibers pass downward and medially from the clavicle to the manubrium and first cartilage. The *interclavicular ligament* stretches from clavicle to clavicle across the upper surface of the capsule and dips in the center to become attached to the floor of the suprasternal (jugular) notch. It is a thickened ligamentous band which is believed to be homologous with the wishbone of the bird. The *costoclavicular ligament* extends upward backward and laterally from the first costal cartilage to an impression on the lower surface of the sternal end of the clavicle. It forms an important accessory ligament of the joint and helps to limit clavicular movements.

The joint is divided into a medial (infe-

rior) and a lateral (superior) compartment by an articular disk, which is attached to the clavicle in front and behind. This fibrocartilaginous disk in addition to acting as a buffer which diminishes the shock of blows on the point of the shoulder, also assists in the limitation of movement of the joint and prevents a medial displacement of the clavicle. Synovial membrane lines the two compartments of the joint, and if the articular disk is perforated the two become continuous.

ARTICULAR RELATIONS

The joint may feel subcutaneous but in reality it is crossed by the tendon of the sternal head of the sternocleidomastoid muscle. The sternohyoid and sternothyroid muscles separate it from the great vessels and vagus nerve. Many large vessels occupy the position behind the joint because of its great obliquity and the extent of its articulating surfaces. Therefore on both sides the internal jugular and subclavian veins unite to form the innominate vein directly behind the joint. On the right side the innominate artery divides into the right common carotid and subclavian and on the left side the left common carotid and the left subclavian arteries ascend. On both sides the vagus nerve descends between the veins and the arteries (Fig. 168).

MOVEMENTS

The movements of the sternal ends of the clavicle are always accompanied by movements of the acromial end of that bone but in the opposite direction. Therefore when the shoulders are pulled backward the sternal ends of the clavicle are pushed forward when the point of the shoulder is depressed the sternal ends of the clavicle are tilted upward. The movements are associated with those at the acromioclavicular joint. When the shoulder is elevated or depressed the clavicle moves on the articular disk. Elevation of the shoulder is limited by tension of the costoclavicular liga-

The *sternal angle* (angle of Louis or Ludwig) is that slight angle which is formed where the body and the manubrium meet (Fig 176B). It is easily palpated beneath the skin and forms a most important land

pressed or bent, and it sometimes has a bifid extremity or even may exhibit a perforation. It articulates with the body of the sternum above, but below it ends in a pointed extremity to which the *linea alba*




FIG 177 The sternoclavicular joint. A coronal section is shown on the left half of the illustration. A sternocostal joint is also shown.

mark, since it lies over a number of important structures inside the thorax; its surface marks the place of attachment of the second costal cartilage. It forms a convenient starting point to determine the number of a given rib and is on the same horizontal plane as the disk between the fourth and the fifth thoracic vertebrae. The sternomanubrial joint is important in the mechanism of respiration, since it allows the body of the sternum to move forward and backward like a door while the manubrium remains stationary.

The medial attachments of the pectorales majores converge from the sternoclavicular joints in front of the manubrium to meet in the midline at the sternal angle; they then pass downward together along the middle of the body and diverge at the level of the sixth costal cartilage. The posterior surface is smooth and related to the pericardium and pleurae.

The *xiphoid (ensiform) process* is the smallest of the 3 sternal divisions and is variable in its appearance; it may be de-

pressed or bent, and it sometimes has a bifid extremity or even may exhibit a perforation. It articulates with the body of the sternum above, but below it ends in a pointed extremity to which the *linea alba*

MUSCLES WHICH ATTACH TO THE STERNUM

- 1 The *pectoralis major*—to the marginal area of the anterior surface of the manubrium and the body.
- 2 The *sternocleidomastoid*—to the anterior surface of the manubrium.
- 3 The *sternohyoid*—to the posterior surface of the manubrium.
- 4 The *sternothyroid*—to the posterior surface of the manubrium on a slightly lower level than the forementioned muscle.
- 5 The *transversus thoracis*—to the posterior surface of the last segment of the body of the xiphoid.
- 6 The *diaphragm*—to the posterior surface of the xiphoid.
- 7 The *aponeuroses of the external ob*

STERNOCOSTAL JOINTS

These joints are 7 in number and connect the superior 7 pairs of costal cartilages to the lateral margins of the sternum. Each is enclosed and reinforced by broad anterior and posterior sternocostal ligaments (Fig. 177). The medial supraclavicular nerves (C3-C4) supply the joint and branches from the internal mammary and the clavicular branch of the thoracoacromial artery anastomose around it.

INTERCOSTAL SPACES

MUSCLES

The muscles which are associated with the intercostal spaces are the external intercostal, the internal intercostal and the transversus thoracis. Corresponding intercostal nerves and vessels supply them (Figs. 178-179).

The *external intercostal muscle* fibers are the thoracic representative of the external abdominal oblique. They pass downward and forward between adjacent borders of two ribs and become membranous in the intercartilaginous portion of the space where they assume the name of the *anterior intercostal membrane*. The fleshy interosseous parts extend as far as the tubercles of the rib posteriorly. The *internal intercostal muscle* is the thoracic representative of the internal abdominal oblique. These fibers run in the opposite direction to those of the external. The fleshy fibers extend from the sternal ends of the spaces as far as the angles of the ribs posteriorly; here they become membranous and continue as the *posterior intercostal membrane* which merges with the anterior costotransverse ligaments.

The *transversus thoracis muscle* is the thoracic representative of the transversus abdominis and should be considered as having three parts: the *sternocostalis*, the *innermost intercostal* and the *subcostal*. The *sternocostalis* part has also been referred to as the transversus thoracis and the tri-

angularis sterni. It is the most constant part of the muscle and is located on the back of the anterior wall of the thorax. It arises from the back of the xiphoid and the body of the sternum as high as the third costal cartilage and inserts into the costochondral junction from the second to the sixth rib. Its lowest fibers are horizontal and continuous with the uppermost part of the transversus abdominis muscle. The muscle has three important features: it fails to cross the first two intercostal spaces; the internal mammary vessels descend in front of it; the pleura is immediately behind it. These relations are important during ligation of the internal mammary artery (p. 271). The *innermost intercostal* part is incomplete and variable and passes from rib to rib deep to the internal intercostal. Its fibers pass in the same direction as those of the internal intercostal and can only be distinguished from it when separated by the intercostal nerves and vessels. Occasionally some of the bundles skip over a rib and insert on the rib below. By its fascia it is connected to the sternocostal part anteriorly and the subcostal part posteriorly. The *subcostal (part) muscle* is made up of slips that vary greatly in size and number. They lie on the internal surface of the lower ribs near their angles and may be looked upon as parts of the innermost intercostal which cover two intercostal spaces.

There are 11 intercostal spaces; the upper 9 are closed but the lower 2 remain open anteriorly. They are all wider in front than behind; the widest is the third followed by the second and then the first. The seventh, the eighth, the ninth and the tenth are very narrow. The spaces are wider in inspiration than in expiration, and their width can be increased by bending the body to the opposite side.

The *subcostal groove* in a typical rib is situated on the deep surface of its sharp lower border. It contains from above downward the respective intercostal vein, artery and nerve (VAN). In the posterior part of the space the nerve is situated midway




FIG 178 An intercostal space a diagrammatic presentation of two views, showing the relations of muscles, vessels and nerves. In the posterior part of the space, the nerve is situated almost between the ribs, but from the angles of the ribs forward, it lies in the subcostal groove.

ment, and depression by the articular disk and the interclavicular ligament.

In a dislocation involving the joint, the force is usually directed along the long axis of the clavicle so that the sternal end passes forward, tearing the anterior sterno-clavicular ligament. The clavicle passes upward and comes to lie in the suprasternal notch, between the sternocleidomastoid in front and the sternohyoid and the sternothy-

roid behind. If such a dislocation is complete, the costoclavicular ligament is ruptured, then it is difficult to obtain reduction because of the obliquity of the articular surfaces. Backward dislocation is rare, but if this does occur the posterior sterno-clavicular ligament is torn, and the clavicle compresses the innominate vein, the trachea and, on the left side, the esophagus as well.




FIG. 180 An intercostal artery and a spinal nerve (diagrammatic). The intercostal vessels and nerves pass in an intermuscular plane between the transversus thoracis (innermost intercostal) and internal intercostal muscles.

BLOOD VESSELS

Since there are 11 intercostal spaces there must be 11 intercostal arteries. These originate posteriorly and are designated as the *posterior intercostal arteries*. The anterior intercostal arteries arise from the internal mammary (Fig. 180). Not all 11 posterior arteries arise from the aorta since only the lower 9 have this origin; the upper 2 are branches of the *highest intercostal*, a branch of the costocervical trunk of the subclavian

The right aortic intercostals are longer than the left because of the position of the aorta to the left of the vertebral column. Each vessel divides into anterior and posterior branches. The posterior supplies the spinal canal, the back musculature and the overlying skin. It is the anterior branch of the posterior intercostal artery which passes forward in the subcostal groove. The intercostal vessels and their corresponding nerves pass anteriorly in the plane between the innermost intercostal and the internal intercostal muscles. The lower intercostal vessels and nerves occupy a corresponding




FIG 179 The transversus thoracis muscle. This has three parts, namely, the sternocostalis, the innermost intercostal and the subcostal. The innermost intercostal is shown in Figure 178. The sternocostalis is the most constant in position and the innermost intercostal the least constant. (A) Anterior wall viewed from within, (B) posterior wall viewed from within.

innominate vein and the sternoclavicular articulation and then passes vertically downward on the deep surface of the thoracic wall about one quarter of an inch from the outer border of the sternum. It is covered by skin, fascia, pectoralis major muscle, anterior intercostal membrane, internal intercostal muscle and costal cartilage. In the region of the sixth intercostal space it ends by dividing into superior epigastric and musculophrenic branches. Opposite each of the upper six intercostal spaces the internal mammary gives off *perforating* branches which pass forward through the intercostal spaces. In females the second and the third perforating branches are much larger, since they supply not only the overlying muscles and skin but the mammary gland as well. Corresponding to each perforating artery the internal mammary also gives rise to *two anterior intercostal arteries*. These small vessels pass laterally, one lying near the lower border of the rib above and the other lying near the upper margin of the rib below; they anastomose with the posterior intercostals. Therefore each intercostal space has *three intercostal arteries*, one posterior and two anterior; however this is not true for the lowest two spaces since they remain open and have no anterior branches.

Of surgical importance is the fact that the internal mammary artery lies directly on the pleura in the first two intercostal spaces. Below this level the transversus thoracis separates the vessel from the pleural membrane. Therefore in order to avoid injury to the pleura it is advisable to ligate the vessel below the first two interspaces. The vessel also supplies a slender branch the pericardiophrenic which accompanies the phrenic nerve. Because of its close relation to the nerve the artery may be injured in the operation of phrenic avulsion and produce a hemorrhage large enough to necessitate ligation of the internal mammary artery.

The *superior epigastric artery* continues

in the original direction of the internal mammary; it descends through the diaphragm and enters the rectus sheath to anastomose with the inferior epigastric (external iliac). The musculophrenic passes downward and laterally along the costal margin of the diaphragm which it perforates. It ends much reduced in size, opposite the first intercostal space and supplies intercostal branches to spaces 7, 8 and 9.

Ligation of the internal mammary artery is performed through a transverse incision in the anterior end of the third interspace. The pectoralis major is divided in the line of its fibers and the anterior intercostal membrane is exposed. This is incised exposing the internal intercostal muscle. The vessel and its veins are found lying between the internal intercostal and the transversus thoracis (sternocostal part) muscles.

The *internal mammary veins* (venae comitantes of the internal mammary artery) unite opposite the third costal cartilage or a little lower to form a single venous trunk which ascends along the medial side of the artery and enters the innominate vein at the thoracic inlet. These veins possess numerous valves and receive branches from the anterior intercostal veins of the upper six spaces, perforating branches, muscular branches, mediastinal, pericardial and thymic veins as well as the superior epigastric and musculophrenic venae comitantes. The internal mammary vessels are covered in their lower portions posteriorly by the transversus thoracis muscle but in the upper part are in direct contact with the parietal pleura. The internal mammary vessels are crossed anteriorly by the intercostal nerves and are associated with lymph glands.

ARRANGEMENT OF THE TWELVE SPINAL NERVES

The *spinal nerves* (Fig. 180) are segmentally arranged and are attached to the spinal cord by two roots, an anterior which is motor (efferent) and a posterior which is sensory (afferent). The posterior root has




FIG 181 The internal mammary vessels

plane in the abdominal wall. Anteriorly the vessel divides into superior and inferior (collateral) branches which unite with those from the internal mammary artery. Since the lowest two intercostal spaces remain open, the lowest two intercostal arteries continue on into the abdominal wall. The

subcostal artery is the same as any intercostal artery but since there is no twelfth space, it assumes a separate name.

The *internal mammary artery* arises from the under surface of the first portion of the subclavian artery opposite the thyrocervical trunk (Fig 181). It descends behind the

costal nerves run in oblique course, but the area supplied by any one of them is horizontal. Head has shown that before anesthesia is evident in the region of their nerve

distribution, at least 3 contiguous nerves must be divided since the overlapping from the nerve above and the nerve below would compensate for any injury

a *ganglion* on it. These roots leave the vertebral canal via the intervertebral foramina and immediately join to form a spinal nerve. Since this nerve has both sensory and motor fibers, it is spoken of as a mixed nerve. It divides into anterior and posterior rami. The *anterior rami* are larger and have a tendency to form plexuses (cervical, brachial, lumbar, sacral and pudendal), but the smaller *posterior rami* supply the muscles of the back and in addition, the overlying skin.

An *intercostal nerve* is the anterior nerve ramus. There are 12 pairs of such thoracic or intercostal nerves, 11 of which are truly intercostal and one subcostal. The twelfth is the *subcostal* since it has to run its course in the abdominal wall and not in an intercostal space. The first intercostal nerve also differs somewhat because the greater part of it goes into the formation of the brachial plexus. Each nerve sends a *white ramus communicans* to a corresponding sympathetic ganglion and receives a *gray ramus communicans* from it. A typical intercostal nerve continues forward and supplies muscular and two cutaneous branches. The cutaneous branches are: (a) the *lateral cutaneous nerve* which emerges in the mid axillary line, divides into anterior and posterior branches and supplies the side of the chest; (b) the *anterior cutaneous nerve* which is the termination of the intercostal, appears at the inner end of an intercostal space where it supplies the skin over the sternum and the front of the chest. Since the first thoracic nerve is mainly given to the formation of the brachial plexus it is very small and supplies neither lateral nor anterior cutaneous branches. The second intercostal nerve has lateral and anterior cutaneous branches but its lateral branch does not divide in two since it crosses the axilla as the *intercostobrachial nerve* which supplies the skin of the posteromedial aspect of the arm as far as the elbow. The seventh supplies the region of the epigastrium, the tenth, the umbilical region and the twelfth innervates that region which is

situated midway between the umbilicus and the pubis. Nerves 2, 3, 4, 5 and 6 run typically intercostal or thoracic courses, but 7, 8, 9, 10 and 11 travel partly in the thoracic and partly in the abdominal wall, thus taking a thoracico abdominal course.

The typical thoracic nerves 2 to 6 are separated from the pleura by the innermost intercostal muscle and the transversus thoracis. After supplying the intercostal muscles, they cross in front of the internal mammary artery and in company with the perforating artery, pierce the internal intercostal muscle, the anterior intercostal membrane and the pectoralis major, terminating as an anterior cutaneous nerve of the thorax.

In the abdominal course, the thoracico abdominal nerves (seventh to eleventh) leave their interspaces between the diaphragm and the transversus abdominis and pass between the internal oblique and the transversus abdominis to the back of the rectus sheath. After piercing the sheath they travel in front of the superior or inferior epigastric artery, supply and pierce the rectus abdominis muscle and continue to the anterior abdominal wall, finally, in company with a cutaneous branch of the epigastric artery they end as anterior cutaneous nerves of the abdominal wall.

The intercostal and subcostal nerves supply the following muscles: external and internal intercostals, subcostals, transversus thoracis, levator costarum, external and internal oblique, transversus abdominis, rectus abdominis, and pyramidalis. Dorsally, these nerves supply the serratus posterior superior and the serratus posterior inferior.

The upper 6 intercostal nerves do not reach the midline of the body but end at the inner side of the intercostal space. This is of some diagnostic importance since a swelling over the center of the sternum could not be a cold abscess which has tracked around from the spine along the course of the intercostal nerve, because such a collection could not extend beyond the lateral edge of the sternum. These inter




FIG 182 The milk lines These ridges consist of potential mammary tissue and their failure to disappear would result in accessory breasts

Spence (Fig 186) This is a prolongation of breast tissue from the upper outer part of the breast which passes through an opening in the axillary fascia called the foramen of Langer. Therefore although the breast proper is superficial to the axillary fascia the axillary tail is deep to this fascia. Such a process is in direct contact with the axillary glands and therefore if enlarged it may be mistaken for an axillary tumor or axillary lymph adenopathy.

Since the breast is a modified sebaceous gland it lies in the superficial fascia and not upon or deep to it. The deep surface




FIG 183 The development of the mammary gland (A) ectoderm (B) mesoderm (subcutaneous tissue) (C) pectoralis major muscle (1) At the second month (2) at the third month, (3) at the fifth month (4) at birth

rests upon the fasciae which cover the pectoralis major and the serratus anterior muscles. The gland is made up of lobes (usually 12) which are subdivided into lobules and these in turn are composed of acini. The lobes are arranged like the spokes of a wheel which converge on the nipple, and each lobe is drained by a lactiferous duct. From 12 to 20 such ducts open onto the nipple (Fig 187A). The organ is fixed to the overlying skin and the underlying pectoral fascia by fibrous bands known as Cooper's ligaments (Fig 187B). These are clinically important because cancer cells invade them and subsequently cause their contraction which results in dimpling of the skin or fixation of the growth. By the same process, a malignant tumor may be fixed to the underlying pectoral fascia and then cannot be moved in the long axis of the muscle. The ducts open independently of each other on the surface of the nipple and each has a dilated ampulla just before it ends. The nipple is conical in shape and

Breast (Mammary Gland)

EMBRYOLOGY AND EMBRYOLOGIC MALFORMATIONS

Although the mammary glands do not come into use until adult life they are nevertheless, the first of all the glands which arise from the epidermis to appear during the development of the embryo. In a 6 weeks old human embryo an ectodermal ridge known as the milk line or primary ridge is noted. This thickening extends along the body wall on either side from the axilla to the groin. In the human it atrophies but a small portion remains in each pectoral region which becomes the mammary gland. Since these ridges consist of tissue which is potentially mammary failure of their normal disappearance will result in the persistence of accessory breast tissue. Such tissue remains along the line and can appear anywhere from the axilla to the inner aspect of Scarpa's triangle (Fig 182). The rare presence of accessory breast tissue in locations such as the gluteal region and the shoulder can be explained only by an ectopic placement of the milk ridge. Normally, that portion of the ridge which is located in the pectoral region starts to grow inward in the shape of buds, which form slender tubes and from them the ducts and the secreting tissues of the breast eventually develop. The nipple is either flat or depressed at birth and only later does it evert so that it projects above the surrounding skin (Fig 183).

The *congenital abnormalities* which may occur are (Fig 184)

1 *Polymastia* This condition presents more than one breast on one or both sides and is due to the persistence of part of the milk ridge. The accessory breast may be well developed or tiny, and instances have been noted where these breasts have been used for suckling. As many as ten have been recorded in one individual.

2 *Polythelia* This condition is one in which supernumerary nipples are found over a given breast and not necessarily on the milk ridge.

3 *Gynecomastia* This is the presence of a female breast or breasts in the male.

Congenital absence amastia, either unilateral or bilateral has also been recorded. Unilateral amastia is believed to be due to pressure of an arm in utero against the pectoral region. When this exists the pectoral muscles on the affected side are also atrophic or absent.

MAMMARY GLAND PROPER (STRUCTURE AND FORM)

The *mammary gland* extends vertically from the second to the sixth rib inclusive and horizontally from the side of the sternum (parasternal) to the midaxillary line. The greater part of the breast, about two-thirds, rests upon the pectoralis major muscle and the rest, about one third, upon the serratus anterior (Fig 185). The breast is hemispherical in shape, but tongue-like processes may extend upward, downward or medially from it. The most common of such processes is the so called *axillary tail* of




FIG 182 The milk lines These ridges consist of potential mammary tissue and their failure to disappear would result in accessory breasts

Spence (Fig 186) This is a prolongation of breast tissue from the upper outer part of the breast which passes through an opening in the axillary fascia called the foramen of Langer. Therefore although the breast proper is superficial to the axillary fascia the axillary tail is deep to this fascia. Such a process is in direct contact with the axillary glands and therefore if enlarged it may be mistaken for an axillary tumor or axillary lymph adenopathy.

Since the breast is a modified sebaceous gland it lies in the superficial fascia and not upon or deep to it. The deep surface




FIG 183 The development of the mammary gland (A) ectoderm (B) mesoderm (subcutaneous tissue) (C) pectoralis major muscle (1) At the second month (2) at the third month (3) at the fifth month (4) at birth

rests upon the fasciae which cover the pectoralis major and the serratus anterior muscles. The gland is made up of lobes (usually 12) which are subdivided into lobules and these in turn are composed of acini. The lobes are arranged like the spokes of a wheel which converge on the nipple and each lobe is drained by a lactiferous duct. From 12 to 20 such ducts open onto the nipple (Fig 187A). The organ is fixed to the overlying skin and the underlying pectoral fascia by fibrous bands known as Cooper's ligaments (Fig 187B). These are clinically important because cancer cells invade them and subsequently cause their contraction which results in dimpling of the skin or fixation of the growth. By the same process a malignant tumor may be fixed to the underlying pectoral fascia and then cannot be moved in the long axis of the muscle. The ducts open independently of each other on the surface of the nipple and each has a dilated ampulla just before it ends. The nipple is conical in shape and




FIG 184 Congenital abnormalities of the breast




FIG 185 The normal, adult, female breast




FIG 186 The axillary tail of Spence




FIG 187 Cross section of an adult female breast (A) the breast has been dissected layer by layer, (B) attachments of Cooper's ligaments

usually is found in the fourth intercostal space. Its base is surrounded by a circular pigmented area called the *areola* which has many small rounded elevations (cutaneous glands) known as the *areolar glands of Montgomery*. These are sebaceous glands for lubrication of the nipple during lactation.

VESSELS, NERVES AND LYMPHATICS

The arterial supply is derived chiefly from two sources, namely the anterior per-

forating branches of the internal mammary artery and mammary rami of the axillary or one of its main branches (Fig 188). Anson, Wright and Wolfer are of the opinion that no mammary branches are derived from the anterior intercostal arteries. The *anterior perforating arteries* are branches of the internal mammary. The first four or five of these supply the breast but only two, usually the first and the fourth (or the second and the third) are well developed; however, almost all of these vessels have a




FIG 188 The arterial supply of the breast (A) The arterial supply of the breast is derived from two sources anterior perforating branches of the internal mammary artery and the lateral thoracic artery (B) The thoracoacromial artery supplies the pectoralis major muscle and not the breast

tendency to travel transversely and cephalad to the nipple. The *lateral thoracic artery*, a branch of the second part of the axillary, descends along the lateral margin

of the breast and sends small branches into the gland but its larger branches are distributed to the thoracic wall. Mammary branches of this latter vessel also have a




Fig 189 The lymph drainage of the breast (A) the cutaneous and glandular lymphatics (B) the areolar lymphatics

tendency to travel transversely across the breast and in this way anastomose with the mammary rami of the perforating arteries. The thoracoacromial artery also a branch of part two of the axillary is usually described as being one of the vessels which supply the breast tissue. This apparently

is incorrect since the pectoral branches of this vessel remain on the deep aspect of the pectoralis major, supply it and do not enter the gland (Fig 188B).

Therefore blood is supplied to the breast from two arterial sources (1) the anterior perforating branches of the internal mam

mary and (2) the lateral thoracic arteries. Since these vessels pass cephalad to the nipple and in a transverse direction, the blood supply of the gland is mainly located at its superomedial and superolateral as

breast, with the exception of the areola and the nipple, and converge in collecting trunks, which flow into the axillary glands of the same side. At the inner quadrants and especially those near the sternum, lym




FIG 190 Transverse section through the thorax, showing paths of lymph drainage from the breast

pects. Therefore an incision into the breast should be placed below the nipple to preserve the blood supply and to make the scar less visible. Since no major vessels reach the gland from its inferior aspect, plastic procedures upon the pendulous breast as well as diagnostic incisions into the breast should be placed in the inferior quadrants.

Although the main veins follow the arterial pattern just described, many of the smaller veins resemble the lymphatics and form a plexus beneath the areola. These are especially visible in the lactating breast. Large veins pass from the plexus toward the periphery and end in the axillary and internal mammary veins.

✓ The lymph drainage consists of three parts: cutaneous, areolar, and glandular (Fig 189). The cutaneous lymphatics carry the lymph from the integument of the

breast or axillary glands of the opposite side. The areolar lymphatics drain the nipple and the areola and pass into the subareolar plexus of Sappey (Fig 189B). The plexus is drained by two main lymph channels: one for the inner part and one for the outer. They usually unite into one main trunk, which passes to the anterior group of axillary glands. The anterior axillary (pectoral or superficial) set is really the main group and is placed under the anterior axillary fold following the course of the lateral thoracic vein. These glands are found in the region of the third rib. From this set the glands drain to the central axillary set, which is situated in the fat of the upper part of the axilla under the axillary tuft of hair and along the inner border of the axillary vein. The intercostohumeral nerve passes outward between these glands and

enlargement of the latter may produce pressure on the nerve resulting in pain along the axilla or inner border of the arm. From here the lymph vessels pass to the *deep axillary glands* part of which form a lateral group which passes along the course of the axillary vein the other part forms the *apical group* which has also been referred to as the *infravicular glands*. These glands lie behind the costocoracoid membrane. It is therefore impossible to free them adequately unless the whole region of the costocoracoid membrane is removed. The deep axillary glands become continuous with the *deep cervical glands* in the *supravicular fossa*.

✓ Although the above path is the usual one taken there are other lymphatic zones of cancer spread. Some of the lymphatics from the upper and the outer quadrants of the breast form a trunk that pierces the pectoralis major muscle and directly enters the gland along the axillary vein thereby short-circuiting the axilla. Lymphatics also leave the inner quadrant of the breast and reach the glands inside of the chest cavity lying on each side of the internal mammary artery (Fig 190). Occasionally a few vessels pass to the *cephalic gland* which lies in the deltopectoral groove. In some instances breast cancer may spread downward in the lymphatics to the epigastric region and there invade the abdominal wall. Development of metastases in the liver and in the pelvic cavity can be explained by such permeation. It is possible for cancer from one breast to spread across the midline to the other subpectoral plexus, then to the opposite axilla and finally to the opposite breast. The pectoral lymph plexuses should not be regarded as separate systems but rather as communicating networks.

The nerve supply of the skin of the breast is derived from the anterior and lateral branches of the fourth to the sixth intercostal nerves which reach it by way of the second to the sixth intercostals.

SURGICAL CONSIDERATIONS

BREAST ABSCESS

Breast abscesses may be subcutaneous, intramammary or submammary. The incision for a subcutaneous or intramammary abscess should be so placed that it radiates from the nipple but never transversely across the breast. If the abscess is deeper, sub- or retromammary this incision is not utilized but instead a thoracomammary approach in the inframammary fold is used. This is the same incision that is utilized for benign tumors of the breast since practically any portion of the gland can be examined through it (Fig 191). With the breast retracted upward and medially the incision is placed in the pigmented line. It is then carried down to the underlying muscle and the breast is displaced upward. The necessary procedure is done be it draining an abscess or removing a tumor. The breast is then permitted to fall back into its normal position where it is sutured.

RADICAL MASTECTOMY

Radical mastectomy can be outlined in six anatomic steps each having three sub-steps. This is only a plan and may be altered to fit any standard technic (Figs 192-193). The plan is outlined as follows.

- 1 Incision
 - a Coraco-umbilical line
 - b Mobilization of skin medially to the midline of the sternum
 - c Mobilization of skin laterally to the latissimus dorsi (posterior axillary fold)
- 2 Axillary Fascia Step
 - a Incision of axillary fascia along the lower border of pectoralis major
 - b Division of the pectoralis major near its insertion, leaving the clavicular part intact
 - c Division and ligation of the thoraco-acromial vessels and nerves

mary and (2) the lateral thoracic arteries. Since these vessels pass cephalad to the nipple and in a transverse direction, the blood supply of the gland is mainly located at its superomedial and superolateral as

breast, with the exception of the areola and the nipple, and converge in collecting trunks, which flow into the axillary glands of the same side. At the inner quadrants, and especially those near the sternum, lym




FIG 190 Transverse section through the thorax, showing paths of lymph drainage from the breast

pects. Therefore an incision into the breast should be placed below the nipple to preserve the blood supply and to make the scar less visible. Since no major vessels reach the gland from its inferior aspect, plastic procedures upon the pendulous breast as well as diagnostic incisions into the breast should be placed in the inferior quadrants.

Although the main veins follow the arterial pattern just described, many of the smaller veins resemble the lymphatics and form a plexus beneath the areola. These are especially visible in the lactating breast. Large veins pass from the plexus toward the periphery and end in the axillary and internal mammary veins.

The lymph drainage consists of three parts: cutaneous, areolar, and glandular (Fig 189). The cutaneous lymphatics carry the lymph from the integument of the

breast or axillary glands of the opposite side. The areolar lymphatics drain the nipple and the areola and pass into the subareolar plexus of Sappey (Fig 189B). The plexus is drained by two main lymph channels: one for the inner part and one for the outer. They usually unite into one main trunk, which passes to the anterior group of axillary glands. The anterior axillary (pectoral or superficial) set is really the main group and is placed under the anterior axillary fold following the course of the lateral thoracic vein. These glands are found in the region of the third rib. From this set the glands drain to the central axillary set, which is situated in the fat of the upper part of the axilla, under the axillary tuft of hair and along the inner border of the axillary vein. The intercostohumeral nerve passes outward between these glands, and




FIGURE 192 (Legend on facing page)




FIG 191 Inframammary approach to breast pathology (A) incision in inframammary fold (B) removal of small benign tumor, (C) closure

FIG 192 (Facing page) Radical mastectomy (A) The incision extends around the breast from the coracoid process to the umbilicus. The musculature in this region is shown (B) A finger is placed through an incision in the axillary fascia; it emerges at the clavicular groove of the pectoralis major and not at the deltopectoral groove. This permits the clavicular portion of the muscle to remain intact and in this way protects the cephalic vein (C) A finger is placed through an incision in the clavipectoral fascia. The finger passes under the pectoralis minor muscle, which is severed close to the coracoid process. The thoracoacromial vessels have been divided and tied.

3 Clavipectoral Fascia Step

- a Incision into the clavipectoral fascia along the lower border of the pectoralis minor
- b Division of the pectoralis minor muscle
- c Insertion of the pectoralis minor utilized as an axillary vein splint

4 Axillary Vein Dissection

- a Clamp cut and ligate all venous tributaries
- b Axillary glands and fat dissected downward
- c Subscapular vessels used as a guide to the thoracodorsal nerve

5 Posterolateral Dissection

- a Exposure of the subscapular muscle
- b Exposure of the latissimus dorsi
- c Exposure of rectus abdominis

6 Medial Dissection

- a Dissection of pectoralis major and minor muscles
- b Clamp and ligate perforating vessels (especially Number 2)
- c Remove mass en bloc and close

Many incisions have been advised however the one described extends from the coracoid process above which is always palpable to the umbilicus below which is always visible (Fig 192A). Forceps are placed in the breast which is elevated and traction is then made laterally the incision is placed along the coraco umbilical line. Traction is then made to the opposite side and the incision is completed along the coraco umbilical line. The lateral and medial skin flaps are formed they extend medially past the midline of the sternum and laterally to the latissimus dorsi.

The second step is the *axillary fascia*

phase. This fascia provides a covering for the pectoralis major muscle. An incision is placed into the fascia along the lower border of the pectoralis major (Fig 192B). The index finger of the left hand is placed through the defect and is guided not to the deltopectoral groove, which seems natural, but rather to the clavicolosternal groove, which is not as well marked. If the clavicular portion of the pectoralis major muscle remains intact it protects the cephalic vein which runs in the deltopectoral groove. In the course of the operation it might become necessary to ligate or remove the axillary vein if the cephalic vein is intact the venous return of the superior extremity will not be impaired. The pectoralis major is cut near its insertion and its sterno abdominal part is reflected medially. As the pectoralis major is reflected medially the thoracoacromial vessels and the anterior thoracic nerves appear as a neurovascular bundle along the medial border of the pectoralis minor. These are clamped severed and ligated.

The third step is the *clavipectoral fascia* phase. This fascia provides the covering for the pectoralis minor muscle. It is incised along the lower border of the pectoralis minor so that the index finger of the left hand may be slipped under it and around the muscle (Fig 192C). The pectoralis minor is divided but a small part is left attached to the coracoid process this acts as a splint for the axillary vein. With both pectoral muscles divided and retracted medial and downward the axilla is exposed and ready for dissection of its contents.

In the *axillary vein phase* the axillary sheath which covers the vein is carefully opened and the vascular branches below

FIG 193 (Facing page) Radical mastectomy (continued) (D) The axillary vein is exposed by dividing the axillary sheath. The vessels below this vein are individually identified severed and tied and the axillary fat and lymph glands are dissected distally. (E) The entire mass is dissected downward. The attachments of the pectoral muscles are divided and the perforating vessels are cut and ligated. If possible the long thoracic and thoracodorsal nerves are saved. The rectus sheath is exposed and at times removed. (F) Closure.




FIGURE 193 (Legend on facing page)

12

Diaphragm

The word diaphragm is derived from the Greek *dia* (in between) and *phragma* (fence). It is a dome-shaped musculo-aponeurotic partition which is located between the thorax and the abdomen.

EMBRYOLOGY

The embryology of the diaphragm is complicated because the diaphragmatic elements are derived from several sources. The anterior, lateral and central parts which make up the greater portion are formed from the transverse septum and fused ventral mesentery. The posterolateral portion is formed by the fusion of the dorsal mesentery and the mesoderm derived from the receding wolffian body and the pleuroperitoneal membrane. Some embryologists divide diaphragmatic development into 3 stages.

In the first stage the coelomic space is a continuous one until the growth of the organs divide it into pericardial, pleural and peritoneal cavities. The septum transversum forms the ventral part of the diaphragm; the pericardial cavity lies ventral to it. Since this septum is confined to the ventral half of the embryo, the pleural space remains continuous with the peritoneal cavity posteriorly. This resulting continuity is the pleuroperitoneal canal, and the developing esophagus, stomach and its mesentery pass through it. Should the development proceed only to this point, the abdominal organs would have a direct route into the thorax. A hernia formed during this stage would have no sac.

In the second stage the pleuroperitoneal canal becomes obliterated by the prolifera-

tion of the primitive dorsal mesentery of the stomach and esophagus. The pleural and peritoneal cavities are now fully formed and if a herniation should occur during this phase a sac would be present.

During the third or final phase the phrenic nerve with a muscle mass invades the diaphragm. This muscle replaces the membranous structures; the latter area to be muscularized is the dorsal part. If the ingrowth of muscle is incomplete, the posterior part will be closed only by pleura and peritoneum. In these cases the crura of the diaphragm, which form the back of the muscle, will be absent in whole or in part.

DIAPHRAGM PROPER

The *adult diaphragm* is a musculotendinous partition which is located between the pleurae and pericardium above and the peritoneal cavity below. When relaxed and viewed from below, it forms a dome-shaped roof for the abdomen. Its circumferential part is fleshy, and these muscle fibers curve upward and inward from every side to join the edges of an aponeurotic sheath called the *central tendon* (Fig. 194). It is this tendon which acts as the site of insertion for the diaphragm. The central tendon is strong; its tendinous bundles passing in different directions and interlacing with one another, giving it a pleated appearance. Its median part is wide and is called the median lobe; the extremities or horns of the tendon are referred to as the right and left lobes. The latter is the narrower. The tendon is inseparably blended above with the fibrous layer of the pericardium.

The *origin* of the diaphragm is quite

the vein are individually identified, cut and tied (Fig 193D). These usually include the short thoracic vein, the lateral thoracic artery, the long thoracic vein, the subscapular vein, the lateral thoracic vein and the subscapular artery. The axillary lymph glands and fat are dissected downward. The subscapular vessels act as a guide to the thoracodorsal nerve, and the lateral thoracic artery is the guide to the long thoracic nerve. If possible, these nerves should be saved, but if they are involved they must be sacrificed.

Posterolateral dissection is carried out next. After the axillary cleansing has been accomplished, the subscapular muscle, the

teres major and the latissimus dorsi come to view, the rectus sheath is also exposed.

Medial dissection is the final stage. The origins of the pectoralis major and minor are severed, the mass is retracted laterally and downward, and the perforating vessels are sought in the intercostal spaces, they are found close to the lateral margin of the sternum (Fig 193E). These must be clamped, cut and ligated, with special emphasis being placed on perforating branch Number 2, which has been discussed thoroughly (p 277). The entire mass is removed en bloc, and the wound is closed (Fig 193F). At times skin grafts may be necessary.




FIG 196 The diaphragm viewed from the left. The three main apertures are shown and their thoracic levels are labeled

extensive and takes place at the circumference of the thoracic outlet. It is best to consider it as originating at 4 points: sternal, costal, the crura, and the medial and lateral arcuate ligaments (Figs 194-195).

The *sternal origin* consists of short right and left slips from the posterior aspect of the xiphoid process which are separated from each other by a little areolar tissue. These fibers pass upward and backward to the anterior margin of the central tendon where they insert. The *costal origin* is extensive and rises at a very steep angle. It usually consists of 6 fleshy muscle bundles which arise from the deep surface of the lower 6 costal cartilages interdigitating with the costal origin of the transversus ab-

dominis muscle. These fibers insert into the lateral and anterior borders of the central tendon. The *crura* are long tapering bundles which are fleshy above and tendinous below. The right crus arises from the sides of the bodies of the upper three lumbar vertebrae and the intervertebral disks; the left arises from the upper two lumbar vertebrae. The medial fibers of the two crura decussate in front of the commencement of the abdominal aorta; the fibers of the right crus encircle the esophagus. Both crura ascend forward and reach the posterior border of the central tendon. The *lateral and medial arcuate ligaments* (lumbocostal arches) are lateral to the crura. The medial arcuate ligament is the upper thickened




FIG 194 The diaphragm viewed from below. The central tendon consists of three lobes and is the site of insertion of the diaphragm. The four points of origin have been identified.




FIG 195 The diaphragm viewed from in front. The lower costal cartilages have been removed to show the four points of origin.




FIG 198 Two approaches to a diaphragmatic hernia. Below the diaphragm (A) long left rectus incision (B) repair of hernial orifice. Above the diaphragm (A) incision in sixth intercostal space (B) repair of hernial orifice.

smaller ones. The large openings accommodate the aorta, esophagus, and the inferior vena cava (a, e, i) (Fig 196). The thoracic levels at which these structures

pass are the inferior vena cava at the eighth thoracic, the esophagus at the tenth, and the aorta at the twelfth.

The aortic opening is located in the me-




FIG 197 The diaphragm seen from above. The three major orifices and the structures passing through them are shown

border of the psoas fascia which stretches between the side of the body of the second and the tip of the transverse process of the first lumbar vertebrae. The lateral arcuate ligament is the thickening of the anterior lamella of the lumbar fascia which extends from the tip of the first lumbar transverse process to the lower border of the last rib. From this origin the muscle fibers arch upward to reach the posterior border of the lateral part of the central tendon.

NERVE AND BLOOD SUPPLY

The nerve supply of the diaphragm is derived from the right and left phrenic nerves (C 3, 4, 5). The arteries which supply it

are the pericardiophrenic, inferior phrenic, musculophrenic and intercostals.

ACTIONS

The diaphragm is the chief muscle of respiration and it is in the abdominal type of breathing that it plays its greatest role. When its fibers contract, they straighten out so that the domelike appearance is lost. In deep inspiration the central tendon descends for a short distance.

FORAMINA (OPENINGS)

The continuity of the diaphragm is broken by 3 large apertures and several

compleished through abdominal thoracic or combined abdominal and thoracic incisions (Lick 193)

Interruption of the phrenic nerve on the involved side can be either temporary or permanent and is of value as a procedure performed preliminary to radical operative repair. It prevents spasm and movement of the muscle and causes relaxation of the hernial ring hence is of value in the closure of the opening.

The *transthoracic route* rarely requires rib resection. The incision is usually placed in the sixth or seventh intercostal space and extends from the costochondral junction backward to the posterior axillary line. The ribs are separated. At times reduction of the hernia may be impossible via this route, and an abdominal incision then be

comes necessary for bimanual manipulation and replacement of the viscera. The opening in the diaphragm is closed by imbrication, its margin. Usually a double row of sutures are used and the individual incisions are then closed in layers.

The *abdominal route* utilizes a long left rectus incision (Lick 1931). The left lateral ligament of the liver should be cut so that the left lobe of the liver can be retracted. This affords excellent exposure. The herniated viscera are freed of adhesions and reduced. At times it becomes necessary to enlarge the hernial ring for this reduction. The opening in the diaphragm is closed, usually by an imbrication method using interrupted sutures. Harrington has advised the use of fascia lata sutures for reinforcement.

dian plane in front of the lower border of the twelfth thoracic vertebra and between the crura. It is bounded anteriorly by a tendinous arch which connects the medial borders of the crura to each other. Through this orifice pass the *aorta*, *thoracic duct* and *azygos vein* (Fig 197). The *thoracic duct* and *azygos vein* are covered by the right crus. The *esophageal opening* is an oval aperture which lies opposite the tenth thoracic vertebra in front to the left of the aortic opening and behind the central tendon. The *descussating fibers* seem to act as a sphincter for the cardiac end of the stomach and prevent its contents from returning to the esophagus. In addition to the esophagus it transmits the right and left *vagus nerves* and the esophageal branches of the left gastric artery with its companion veins. In cirrhosis of the liver when an obstruction to the portal system is present, these veins at the lower end of the esophagus become dilated and varicose and frequently rupture. The *vagi* do not run to either side of the esophagus but are situated so that the left *vagus* passes anteriorly and the right posteriorly. The left, being anterior, supplies the anterosuperior surface of the stomach and the right innervates the postero-inferior. The position of this opening is somewhat variable since it may be found in the median plane or even to the right of it and may be very close to the aortic opening. The *inferior vena cava opening* is wide and about one inch to the right of the median line on a level with the eighth thoracic vertebra. It is in the central tendon between the right and median lobes, as this tendon stretches when the diaphragm contracts the flow of venous blood into the thorax is facilitated. The opening transmits the inferior vena cava, some branches of the right phrenic nerve and a few lymph vessels from the liver. The phrenic nerve first pierces the muscle and then supplies it on its abdominal surface.

The numerous smaller orifices transmitting vessels and nerves found in the diaphragm are (1) the superior epigastric ves-

sels between the sternal and costal origins, (2) the musculophrenic vessels, which pass between the slips from the seventh and eighth costal cartilages, (3) the lower 5 intercostal nerves accompanied by small vascular twigs, which pass between the slips from the seventh costal cartilage down, (4) the last thoracic (subcostal) nerve and the subcostal vessels which pass behind the lateral arcuate ligament, (5) the sympathetic trunk, which passes behind the medial arcuate ligament, (6) each crus is pierced by the great, lesser and least splanchnic nerves, and (7) the *inferior hemiazygos vein* pierces the right crus.

The *costophrenic recess* is that portion of the pleural cavity which is unoccupied by lung except after full inspiration. Here the diaphragmatic pleura is in contact with the costal pleura. When in full inspiration, the inferior border of the lung insinuates itself into this recess, and retraction of the overlying intercostal spaces is seen externally as the diaphragm descends and opens the costophrenic recess.

SURGICAL CONSIDERATIONS

DIAPHRAGMATIC HERNIAS

Abnormal openings through the diaphragm which permit herniation of abdominal viscera into the thoracic cavity constitute the most common lesions of this structure which require surgery. Diaphragmatic hernias are classified as *congenital*, *acquired* and *traumatic*. All the traumatic, and many of the congenital hernias have no sacs. Therefore they are not true hernias, but it is convenient to adhere to common usage and utilize the term. Most of the congenital hernias pass through the pleuroperitoneal canal (Bochdalek) and have no sacs. The majority of acquired (nontraumatic) hernias are located at the esophageal hiatus and have sacs. Since the liver affords protection to the right half of the diaphragm hernias are rarely found here.

Diaphragmatic hernioplasty may be ac-




FIG 199 The pleural cavities and the pleurae (A) Diagrammatic presentation showing an early stage of development and the end result The lung invades the pleural cavity so completely that only a potential pleural space remains The process divides the pleura into visceral and parietal portions (B) Side view seen from the left The lung has been removed and a window cut in the costal pleura The four parts of the parietal pleura are identified as are the pulmonary root and ligament (C) The sternal and vertebral reflections

diaphragmatic recess It is about 2 inches deep behind 3 inches deep in the midaxillary line and a little over 1 inch deep in front

SURFACE MARKINGS

The surface markings of the lungs and pleurae are of diagnostic value and can be constructed in the following way (Fig

200) The junction of the costal and mediastinal pleurae (costomediastinal line of pleural reflection) is not the same on both sides of the body On the right it starts about $1\frac{1}{2}$ inches above the sternoclavicular joint and passes to the middle of the manubrium opposite the second costal cartilage From this point it drops vertically near the midline of the sternum to the xiphosternal

Pleural Cavities and Pleurae

VISCERAL AND PARIETAL PLEURAE

The thoracic cavity is divided into right and left pleural cavities and a region situated between these called the mediastinum. The lung invaginates the pleural cavity so completely that only a potential space remains and by this process the pleura becomes divided into *visceral* (lung) and *parietal* (wall) layers (Fig. 199A).

The *visceral pleura* invests the lung, dips into its fissures and adheres so firmly that it is impossible to strip it from lung tissue. The *parietal pleura* is subdivided according to location into 4 parts: costal, cervical, diaphragmatic and mediastinal (Fig. 199B). The *costal pleura* lines the ribs and their cartilages, the sides of the vertebral bodies and the back of the sternum. This is the thickest of all the parietal pleurae and is separated from the thoracic wall by the thin endothoracic fascia. It is directly continuous above with the *cervical pleura* (*cupola*) which covers the apex of the lung. This portion of the pleura extends upward into the root of the neck behind the interval between the two heads of the sternocleidomastoid muscle. Posteriorly it reaches the level of the head of the first rib but anteriorly it rises about $1\frac{1}{2}$ inches above the sternal extremity of that rib. Hence it is protected by the rib posteriorly but not so anteriorly. This is explained by the fact that ribs do not run horizontally but obliquely; there is a drop of about $1\frac{1}{2}$ inches between the vertebral and sternal attachments of the first rib. The upper aspect of the cervical pleura is covered by a layer of connective tissue called Sibson's fascia.

This fascia forms the internal lining of the scalene muscles and spreads out, fanlike from the transverse process of the seventh cervical vertebra to the inner border of the first rib (Fig. 171). It separates the pleura from the first part of the subclavian artery, phrenic nerve and internal mammary artery. The *diaphragmatic pleura* is thin and very adherent to the diaphragm; it covers that part of the diaphragm not covered by the diaphragmatic pericardium. It is continuous with the costal pleura laterally but medially it becomes continuous with the *mediastinal pleura*. The diaphragmatic pleura meets the costal pleura in 2 places: behind the sternum (sternal reflection) and in front of the bodies of the thoracic vertebrae (vertebral reflection) (Fig. 199C). At the point at which the visceral pleura meets the mediastinal layer of parietal pleura there forms a pleural passageway. The upper part of this passageway contains those structures constituting the root of the lung (pulmonary vessels and bronchus). The lower part is empty; hence its walls approximate each other and form the *pulmonary ligament*.

Only after deep inspiration are the lungs and parietal pleurae completely in contact with each other. In ordinary breathing the lungs are not completely expanded, therefore the edges of the pleurae fall together preventing the formation of a cavity. This touching of the pleurae takes place mainly along the anterior and lower borders. During quiet respiration the costal and diaphragmatic pleurae remain in apposition below the lower border of the lung. The space thus formed is known as the costo-

which starts at the xiphosternal joint and passes posteriorly to the twelfth thoracic vertebra, the line being convex downward. It crosses the tenth rib in the midaxillary line, lies about 2 inches above the costal margin

of cardiac dullness. This curving line ends opposite the sixth costal cartilage about $1\frac{1}{2}$ inches from the midline. The summit of this space is in the fourth interspace about 2 inches from the midline. The lower bor-




FIG 201 Fractured ribs and their complications. The sharp end of a broken rib may injure the pleura, the lung, the liver, the spleen or the diaphragm.

and marks the lowest level of the pleural sac (not lung). It ascends slightly after passing this point and terminates opposite the twelfth thoracic vertebra.

The lungs may also be marked on the surface of the body. The apices lie about $\frac{1}{2}$ inch above the inner third of the clavicles, then descend behind the sternoclavicular joints toward the midline of the sternum (level of the second rib). At this point the lungs almost touch each other. The anterior border of the right lung follows the line of its pleura directly downward to the sixth costal cartilage. The anterior border of the left lung descends as far as the fourth costal cartilage where it curves to the left, exposing an area of pericardium called the area

of the lungs are practically at the same level on both sides. They lie at a higher level (about 3 inches) than their corresponding pleural sacs (the costodiaphragmatic line). The lower border of each lung can be marked by a line which passes laterally behind the seventh rib in the midclavicular line and the eighth rib in the midaxillary line. The latter is its lowest level. From here it terminates posteriorly opposite the tenth thoracic spine.

SURGICAL CONSIDERATIONS

FRACTURED RIBS

The ribs which are usually fractured are the third to the eighth. Ribs one and two and those below the eighth are infrequently




FIG. 200 The surface markings of the lungs and pleurae (A) anterior view, (B) left lateral view (C) right lateral view (D) posterior view

joint where it becomes continuous with the costodiaphragmatic line of reflection. On the left side the line of pleural reflection is the same until the fourth interspace. Here it curves outward to the left border of the sternum along which it descends to the

xiphosternal junction. It becomes continuous with the costodiaphragmatic line of reflection just as it does on the opposite side.

The junction of the costal and diaphragmatic pleurae (costodiaphragmatic line of pleural reflection) may be marked by a line

ASPIRATION OF THE CHEST

The chest is aspirated as either a diagnostic or therapeutic procedure (Fig. 202). It is best performed with the patient seated and with the arm of the involved side placed on the opposite shoulder. If this is impossible the aspiration may be done with the patient lying on the uninvolved side. The site of election is usually a little posterior to the posterior axillary line in the sixth, seventh or eighth intercostal space. Some prefer the midaxillary line. The needle should be passed a little towards the superior surface of the lower rib so that the intercostal artery and nerve are not injured.

THORACOSTOMY

Thoracostomy is an opening made through the chest wall for the purpose of drainage. It may be a *closed* (interspace) or an *open* (rib resection) drainage. The indication for such drainage is usually empyema.

Closed Method

The *closed method* is usually made in the seventh or eighth interspace in the midaxillary line or in line with the angle of the scapula. Procaine is injected at the selected site and a small stab incision made (Fig. 203). A trocar is inserted just over the rib, thus avoiding the intercostal artery, vein and nerve which lie on the under sur-




FIG. 203 Closed (interspace) thoracostomy

involved (Fig 201) The fracture of the bone proper is of no great importance with the exception of the local discomfort which it produces However, complications such as puncture of the pleura, lung, liver or spleen, as well as diaphragmatic hernia, sec

ondary pleural effusion and surgical emphysema may result in serious sequelae Little displacement or shortening occurs in rib fractures because of the attachment of the intercostal muscles and fixation of both rib extremities




FIG 202 Aspiration of the chest (A) Diagrammatic presentation of the relation between the aspirating needle and the fluid level (B) Aspiration in the midaxillary line




FIG 205 Thoracoplasty (A) and (B) show the posterior approach (1) and (2) demonstrate the anterolateral approach. The cross section shows the effect of this procedure which permits the chest wall to fall in and meet the collapsed lung.




FIG 204 Open (rib resection) thoracostomy

face of the rib. This is advanced into the pleural space where the fluid is located. The obturator is withdrawn and a catheter inserted. The trocar is then drawn over the catheter which fits snugly and which may be fixed by pins or a suture.

Lungs (Pulmones)

EMBRYOLOGY

Embryologically the pulmonary system arises as an outgrowth of the digestive tract. It begins as a small bud which grows from the ventral part of the pharynx (Fig 206). The bud increases in length to form the trachea which in turn divides into right and left primary bronchi (Fig 207). The ends of these bronchi continue to grow and divide until eventually a complex bronchial tree with the terminal alveoli is formed. At first the pleural cavity is in direct communication with the abdominal cavity; the two together forming the celom. These are later separated by a transverse partition, the diaphragm.




FIG 206 Embryogenesis of the pulmonary system. This system arises as a bud from the ventral part of the digestive tract (pharynx).

THE LUNGS PROPER

The *lungs* are a pair of comparatively light organs which are conical in shape, each of which possesses an apex, a base, 2 surfaces, 3 borders (anterior, inferior and posterior) and a root. Although they lie within the pleural cavities they do not fill all the available space during normal respiration. The weights of the ordinary, healthy adult lungs containing the average amount of blood are about 620 grams for the right lung and about 570 grams for the left. If the lungs are in a healthy state, they lie free in the pleural cavity and are attached at only two points: at their roots and at the pulmonary ligaments. Healthy




FIG 207 Embryogenesis of the lungs.

Open Method (Rib Resection) and Thoracoplasty

The *open method* necessitates the resection of a piece of rib. The angle of the scapula is palpated and then the patient's arm is elevated and placed to the opposite side. The rib immediately below this point is usually selected as the one suitable for resection (Fig 204). If the rib above is chosen, the scapula may act as a shutter, if a rib much lower is selected, an inadvertent transthoracic laparotomy may be performed. An incision is made directly over the rib selected; the soft tissues are divided to the periosteum, which is completely freed and about 2 to 4 cms of rib is removed. The pleural cavity is aspirated to make sure that pus is present. The aspirating needle may be left in place and an incision made adjacent to it. The cavity is explored and drainage instituted.

In *chronic, nontuberculous empyema* the lung is compressed by intrapleural fluid. At times a draining sinus results. Radical surgical intervention is necessary. Even after evacuation of the pus, expansion of the lung is not possible, and a pleural dead space results which is difficult to obliterate. Two procedures have been advised which aim at approximating the lung surface and the chest wall, thus eliminating the dead space. The first is *pulmonary decortication* in which one attempts to mobilize the lung. If this is sufficiently accomplished, the lung gradually expands and fills the pleural cavity. The other procedure is *thoracoplasty* which consists of subperiosteal removal of usually six ribs, to permit the chest wall to fall in and meet the collapsed lung. This may be accomplished by either a posterior or an anterolateral approach (Fig 205). Another method which has been utilized to obliterate such a cavity is the use of a muscle flap.




FIG. 209 The medial surface of the right lung (A) Grooves and impressions made by structures in immediate contact with this surface viewed from the left (B) The lungs and the heart seen from in front

right side from the liver and on the left from the stomach, liver and spleen. Because the right dome of the diaphragm is higher and more convex than the left, the right lung is shorter and its base more concave.

Laterally and behind the base is bounded by a thin sharp margin which projects into the phrenocostal sinus of the pleura between the lower ribs and the costal attachments of the diaphragm.

lungs however are rarely found in dissecting rooms since adhesions due to pleurisy are usually present between the visceral and parietal layers of pleura. The two lungs are not exactly symmetrical in shape because of the higher level of the diaphragm on the right, the projection of the heart to the left of the midline and the impressions made by surrounding structures. At birth, the lungs are pinkish white; in adult life dark grey, and as age advances the mottling assumes a black color due to carbonaceous deposits. As a rule the posterior border is darker than the anterior.

The apex of the lung is examined in the lower part of the neck because of the obliquity of the thoracic inlet (Fig 208). It is rounded and rises into the root of the neck for about an inch and a half above the level of the anterior part of the first rib. It is situated behind and above the medial

third of the clavicle, and is crossed by the subclavian artery which makes a groove on its anterior border slightly below its summit. The lung is separated from the artery by the pleura and a thin membrane known as Sibson's fascia (Fig 171). The summit of the apex is in front of the neck of the first rib. The lung apex lies behind the clavicle, the anterior scalene muscle, the subclavian vessels and Sibson's fascia, which is attached along the inner border of the first rib and strengthens the pleura over the apex. The pleura in this region may be inadvertently opened during surgery near the subclavian vessels and can also be torn while removing deep seated tumors from the depth of the neck. The pleura and lungs may be injured in stab wounds of the neck or by fragments of bone in comminuted fractures of the clavicle.

The base (diaphragmatic surface) is concave. The diaphragm separates it on the




FIG 208 The apex of the lung. This is associated with the root of the neck. The insert shows the subclavian artery crossing the apex.

different relationships on the two sides of the body and must be considered separately.

On the *right* side, the *hilum* is occupied by the *eparterial* and the *hyparterial* bronchi, the right pulmonary artery and the upper and lower right pulmonary veins (Fig. 209A). In the hilum, numerous lymph glands and nerves are also found. Below and in front of it the mediastinal part presents a cardiac impression which is formed by the right atrium and a groove for the phrenic nerve. The superior vena cava is in contact with the right lung in front of the hilum and the impression made by this vessel is continuous with the groove made by the right innominate vein above and the cardiac impression below (Fig. 209B). Above the hilum a groove is sometimes visible which runs into the groove for the superior vena cava; it is produced by the vena azygos. The groove produced by the esophagus is found immediately behind this. The vertebral part of the medial surface of the right lung is in relation to the heads of the ribs, the sympathetic trunk, the vertebral bodies, the splanchnic nerve and the aortic intercostal arteries and veins.

On the *left* side the hilum reveals a single left bronchus, the left pulmonary artery, upper and lower left pulmonary veins, numerous lymph glands and nerves. The ventricles of the heart produce a deep cardiac impression below and in front of the hilum (Fig. 210A). The arch of the aorta passes backward above the root of the lung and is continuous behind the hilum, along with the groove produced by the descending thoracic aorta (Fig. 210B). Above the groove for the aortic arch the subclavian artery passes upward in contact with the lung and then turns laterally in front of the apex. The vertebral part of the medial surface of the left lung is grooved by the descending thoracic aorta which separates the lung from the bodies between the fourth to the ninth thoracic vertebrae. Other relationships in this area are the same as those described for the right lung.

BORDERS

The three borders of the lungs are the anterior, inferior and posterior (Figs. 209, 210).

The anterior borders of the lungs are thin and sharp because they are squeezed between the body of the sternum and the pericardium. On the right side, the border is straight and coincides with the costal mediastinal line of pleural reflection. On the left side, however, the anterior border presents a deep notch opposite the fourth and fifth intercostal spaces known as the *cardiac notch*. Here the border of the lung falls short of the sternum by about an inch, leaving part of the pericardium separated from the chest wall by pleura alone. This area which is unoccupied by lung has been referred to as the 'area of superficial cardiac dullness'.

The inferior border separates the base of the lung from the costal and medial surfaces. Laterally and behind, it is sharp and projects down to the upper part of the costodiaphragmatic recess. The inferior borders of both lungs are practically at the same level and during quiet respiration lie at a higher level than the costodiaphragmatic line of pleural reflection.

The posterior border is indistinct and rounded due to the confluence of the medial and costal surfaces which occupy the deep hollow of the thoracic cavity. It projects into the phrenocostal sinus.

THE LOBES AND FISSURES AND BRONCHOPULMONARY SEGMENTS

Each lung presents a complete *oblique fissure* which passes through the costal diaphragmatic and mediastinal surfaces as far as the root. This fissure crosses the posterior border about $2\frac{1}{2}$ inches below the apex and the inferior border about 2 inches from the median plane. The right lung reveals a second fissure known as the *transverse fissure*; it runs horizontally at the level of the fourth costal cartilage and meets the oblique fissure in the midaxillary




FIG 210 The medial surface of the left lung (A) Grooves made by structures in contact with the surface viewed from the right (B) The left thoracic cavity seen from the left

SURFACES

The two surfaces of the lungs are the costal and medial (mediastinal)

The costal surface is smooth convex and includes the bulky posterior part of the lung. It is related to the inner surfaces of

the ribs, costal cartilages, intercostal spaces and to a slight degree, the back of the sternum.

The medial surface of each lung is divided into anterior (mediastinal) and posterior (vertebral) parts. Both parts present




FIG 212 Lobes and fissures of the lungs (A) Seen from below The relationship of the middle lobe on the right and the superior lobe on the left should be noted (B) Seen from above The relationship of fissures to lobes is shown

line The left lung therefore is divided into two lobes a superior and inferior by the interlobar fissure (oblique) the right is divided into three lobes superior, middle and inferior by the two (oblique and transverse) interlobar fissures (Figs 211 212)

The superior (upper) lobe lies above and in front of the oblique fissure and includes the apex, anterior border a large part of the costal surface and the greater part of the mediastinal surface of the lung

The inferior (lower) lobe is the larger





FIG 211 Lobes and fissures of the lungs (A) Front view the usual arrangement of three lobes on the right and two lobes on the left is shown (B) The right lung seen from the right side (C) The left lung seen from the left side (D) The two accessory lobes which may be found associated with the right lung. The infracardiac lobe is constant in quadrupeds, but in man the pericardium fuses with the diaphragm and suppresses its development. The lobe of the azygos vein (Wrisberg) is also shown

of the two, and is situated below and behind the fissure it includes almost all of the base a large part of the costal surface, and the greater part of the posterior border

In the right lung, the *middle lobe* is the smallest is wedge shaped and includes the lower part of the anterior border and the anterior part of the base of the lung. It lies in the front part of the thorax and is entirely anterior to the midaxillary line. The cardiac notch is formed by a deficiency of the upper lobe of the left lung

The lobes are subdivided into smaller units called *bronchopulmonary segments* which may be defined as the area of distribution of a bronchus. The various descriptions of the anatomy of the tracheobronchial tree have resulted in much confusion hence we have chosen the nomenclature used by Jackson and Huber which seems to be acceptable to the surgeon the bronchoscopist the radiologist and the anatomist (Fig 213). It may be listed as shown at the bottom of the page

At times two branches which generally constitute separate major segmental bronchi may have a common trunk. This would explain the variation in descriptions of the right upper lobe which is described as having 4 segments by some and by others as having only 3. Since fissures may be quite inconstant it is far better to subdivide the lungs according to bronchial distribution

The *right lung* usually presents 3 lobes an upper, a middle and a lower. The upper lobe consists of 3 segments the apical, the posterior and the anterior. The middle lobe has 2 segments the lateral and the medial. The lower lobe has 5 segments which are known as the superior, the medial basal, the anterior basal, the lateral basal and the posterior basal. The *left lung* usually consists of 2 lobes an upper and a lower. The upper lobe moreover has 2 subdivisions which are known as the upper and the lower divisions the lower division of the upper lobe is also called the *lingular division*. Two segments make up the upper division these are known as the apical (apical posterior) and the anterior. The lingular division is made up of 2 segments the superior and the inferior. In the left lower lobe the segments are similar to those on the right except that the medial basal is a branch of the anterior basal rather than a separate branch of the lower lobe bronchus. It has been suggested that the term anterior medial basal be used to call attention to this fact

VARIATIONS

Variations are found in the number of lobes of the lungs which may be either decreased or increased. The right upper and middle lobes may be fused and the left lung may have 1 or even 3 lobes. The right lung sometimes has 5, since 2 accessory

RIGHT LUNG		LEFT LUNG	
LOBES	SEGMENTS	LOBES	SEGMENTS
<i>Upper</i>	{ Apical Posterior Anterior	<i>Upper</i>	{ Upper Division { Apical posterior Anterior
<i>Middle</i>	{ Lateral Medial	<i>Upper</i>	{ Lower (Lingular) Division { Superior Inferior
<i>Lower</i>	{ Superior Medial Basal Anterior Basal Lateral Basal Posterior Basal		
		<i>Lower</i>	{ Superior Anterior medial Basal Lateral Basal Posterior Basal




FIG. 213 Nomenclature for the lungs and the bronchi (After Jackson and Huber) The numbers in parentheses relate to the numbers on the illustration. The lobes are divided into smaller units called bronchopulmonary segments, each of which is determined by the area of distribution of a bronchus. The *right lung* presents three lobes: an upper, a middle and a lower. The upper has been colored blue, the middle yellow and the lower red. The upper lobe has three segments: (1) apical, (2) posterior and (3) anterior. The middle lobe has two segments: the lateral (4) and the medial (5). The lower lobe consists of five segments: a superior (6), a medial basal (7), an anterior basal (8), a lateral basal (9) and a posterior basal (10). The *left lung* is divided into two lobes: an upper, colored blue, and a lower, colored red. The upper lobe is divided into two divisions: an upper and a lower (lingular). The upper division has two bronchopulmonary segments: they are known as the apical which is also called the apical posterior (1 and 2) and an anterior (3). The lingular division also has two segments: a superior (4) and an inferior (5). The left lower lobe segments are similar to those on the right except that the medial basal is a branch of the anterior basal rather than a separate branch of the lower lobe bronchus. The term anterior medial basal (7 and 8) is used to call attention to this fact. The other numerical representations are the same as those of the right side. The colors and numbers which have been used on the bronchi correspond to the colors and numbers of the individual bronchopulmonary segments.

the pulmonary artery pulmonary veins and bronchi. Associated with these are the bronchial vessels, nerves and lymph glands. The *pulmonary ligament* (p. 294) is also considered with the root. Although there are some differences in the right and left roots, it is well to remember that the bronchi lie posterior to the vessels, and the pulmonary veins usually lie below the corresponding right or left pulmonary arteries. Many anomalies in this region have been recorded.

The right root has the following boundaries (Fig. 209): anteriorly the superior vena cava and phrenic nerve; superiorly the arch of the azygos vein; posteriorly the azygos vein proper. The left root is bounded in the following way (Fig. 210): anteriorly by the phrenic nerve; superiorly, by the aortic arch; posteriorly by the descending thoracic aorta. It might help to recall that on the right side an inverted

U is formed by the phrenic nerve and azygos vein, while on the left side a similar inverted U is formed by the phrenic nerve and aorta. The structures of each root are bound together by connective tissue and pleura which surround them like a cuff.

BLOOD VESSELS

The *pulmonary veins* usually two on each side, consisting of an upper and a lower, return oxygenated blood to the heart. Two main venous trunks from each lung open into the left atrium on its lateral border. After leaving the right ventricle the *pulmonary artery* passes superiorly for about 4 cm. and a little to the left of the ascending aorta. The right branch goes to the right lung behind the aorta and the left branch to the left lung in the concavity of the aortic arch (Fig. 218). In the lung pedicle the right divides into 2 branches and the left remains single. These vessels end in a capillary network over the alveolar tissues carrying the impure venous blood from the right ventricle to the lung. A thrombus of the right side of the heart of

systemic venous origin can release an embolism which blocks a branch of the pulmonary artery causing a suppression of part of the lung. A pulmonary infarct may then result which might degenerate and become a pulmonary abscess.

The *bronchi* are easily identified by the firm elastic fibrocartilaginous plates. On the right side there is an additional bronchus which receives the name of the *eparterial bronchus* because it is at a higher level than the artery. This is in contrast to the hyparterial bronchi which are found on both sides below the pulmonary artery. The cuff or sleeve of pleura which surrounds these structures is quite narrow in its inferior or lower portion because it is traversed only by a few lymph vessels and therefore remains collapsed. Its anterior and posterior walls are applied to each other and form the pulmonary ligament.

The *bronchial arteries* which supply the lung stroma are found on the posterior surfaces of the bronchi. They arise from the aorta or from an intercostal artery and pass behind the bronchi. Bronchial veins accompany them.

SURGICAL CONSIDERATIONS

PNEUMONECTOMY

Nissen, Overholt, Rienhoff, Graham and Alton Ochsner have pioneered in pneumonectomy and have shown the advisability of performing this operation for primary pulmonary malignancies. Several types of incisions may be employed, the choice depending upon the presence or absence of adhesions, and the location of the pathology (Figs. 215-216). Some surgeons think that anatomic planes exist in the pulmonary hilus and state that a venous plane is found more superficially than an arterial plane or a bronchial plane. However, there are so many variations in the hilar structures that the method is not practical, especially since the inferior pulmonary vein may often be the most posterior structure.

The anterior approach usually consists of

lobes may be associated with the 3 usual ones. One such accessory lobe is the *infra cardiac lobe* which is constant in quadrupeds, in these animals it separates the pericardium from the diaphragm (Fig. 211D). In man, since the pericardium fuses with the dia-

This condition was first described by Wrisberg in 1777. When the apex of the right lung is split by the arch of the azygos vein a bifid apex results. The vein is suspended by a pleural "mesentery" which is referred to as a double pleural septum or "meso-



FIG. 214 Azygos lobe seen on a roentgenogram. The apex of the right lung is split by the arch of the azygos vein. Since the vein is suspended by pleural "mesentery" a meso azygos results; this appears as a fine line running from the apex downward, with its convexity outward (see arrow). It ends in a small dense pea sized shadow which represents the azygos vein.

phragm, the infracardiac lobe is completely suppressed. The most important accessory lobe is the so called *lobe of the azygos vein* (Wrisberg). The azygos vein travels upward in front of the vertebral column arches forward above the root of the lung and ends in the superior vena cava before the latter pierces the pericardium. The arch of the azygos vein therefore, crosses laterally in respect to the esophagus, trachea and right vagus nerve. During development, the right lung bud has to pass outwards under the arch formed by the anterior end of the future azygos vein (right posterior cardinal vein). If the lung bud does not clear it, part of the lung remains lateral and part medial to it. The vein therefore, becomes embedded in the developing lung tissue, and the part medial to it becomes the lobe of the azygos vein (Fig. 211D).

If this is seen on the roentgenogram the meso azygos appears as a fine line running from the apex of the lung downward with the convexity outward as it approaches the mediastinum at about the level of the second costal cartilage. This line ends in a small dense pea sized shadow, which represents the azygos vein (Fig. 214). Such an accessory lobe is important to identify, since it might cause confusion in the interpretation of a roentgenogram, in pulmonary surgery or during post mortem examinations. It may form the entire apex of the lung part of it or may be entirely dissociated from it depending upon the location of the vein.

THE ROOT OF THE LUNG (RADIX PULMONIS)

The root of the lung is a short but broad pedicle consisting of 3 essential structures,




FIG 216 Pneumonectomy (left side) (A) incision (B) isolation of hilar structures

a transverse incision over the third intercostal space extending from the lateral border of the sternum to the anterior axillary line (Fig 215). The pectoral muscles are divided and the pleural cavity entered through the third intercostal space. Greater exposure can be gained by separating the third and fourth ribs after disarticulating their costochondral junctions and by ligating the internal mammary vessels both above and below. The pleural cavity is opened and adhesions divided by sharp dissection. The hilar structures are exposed in the mediastinum by incising the mediastinal

pleura anteriorly and superiorly. The phrenic nerve may be crushed by an artery forceps. This facilitates surgery and also aids the early postoperative course. It is important to isolate and ligate the hilar structures individually and not by mass ligations. On the right side, the isolation, ligation and division of the azygos vein is the first structure to be dealt with; it extends over the right main bronchus. The pulmonary artery is then isolated, doubly ligated and divided. The bronchus is usually ligated next but it may be necessary to isolate, transfix, ligate, and divide the supe-




FIG 215 Pneumonectomy (right side) (A) Anterior approach through a transverse incision over the third intercostal space (B) Exposure of hilar structures by incising the mediastinal pleura anteriorly and superiorly (C) Ligation and division of the azygos vein (D) Ligation and division of hilar structures followed by removal of the lung (E) Pleuralization




FIG 216 Pneumonectomy (left side) (A) incision (B) isolation of hilar structures

a transverse incision over the third intercostal space extending from the lateral border of the sternum to the anterior axillary line (Fig 215). The pectoral muscles are divided and the pleural cavity entered through the third intercostal space. Greater exposure can be gained by separating the third and fourth ribs after disarticulating their costochondral junctions and by ligating the internal mammary vessels both above and below. The pleural cavity is opened and adhesions divided by sharp dissection. The hilar structures are exposed in the mediastinum by incising the mediastinal

pleura anteriorly and superiorly. The phrenic nerve may be crushed by an artery forceps. This facilitates surgery and also aids the early postoperative course. It is important to isolate and ligate the hilar structures individually and not by mass ligations. On the right side, the isolation, ligation and division of the azygos vein is the first structure to be dealt with; it extends over the right main bronchus. The pulmonary artery is then isolated doubly ligated and divided. The bronchus is usually ligated next but it may be necessary to isolate, transfix, ligate, and divide the supe-




FIG 215 Pneumonectomy (right side) (A) Anterior approach through a transverse incision over the third intercostal space (B) Exposure of hilar structures by incising the mediastinal pleura anteriorly and superiorly (C) Ligation and division of the azygos vein (D) Ligation and division of hilar structures followed by removal of the lung (E) Pleuralization

The periosteum is raised from the 2 adjacent ribs which will be resected later. Gauze is packed beneath the denuded rib to form adhesions between the visceral and parietal

pleurae. At the end of a week or 10 days, the wound is reopened, the abscess is located with a needle and entered. Drainage is then instituted.

rior pulmonary vein first. The bronchus is then freed, ligated and divided; it is usually closed by interrupted sutures. The short inferior pulmonary vein is next found transfixed, ligated and severed. The posterior mediastinal pleura is then incised and the lung is removed. Careful pleuralization of the mediastinum is all important. The edges of the divided mediastinal pleura are approximated, covering the stumps of the ligated hilar structures. When a large amount of mediastinal pleura has been extirpated, it might be necessary to utilize the adjacent pericardium to cover the ligated stump. The thoracic wall is closed in layers by passing heavy nonabsorbable sutures around the adjacent ribs. Following this, the pleura and intercostal muscles are approximated either with or without drainage. A posterolateral approach is preferred by some surgeons.

LOBECTOMY AND PULMONARY SEGMENTAL RESECTION

Both of these procedures have been used for such conditions as bronchiectasis, pulmonary tuberculosis, chronic lung abscesses and metastatic lesions. Clagett and Deterling have described a technic of lingulectomy in bronchiectasis. Churchill and Belsey and Overholt and Langer have stressed the importance of pulmonary segmental resection. They state that bronchiectasis is a segmental disease and rarely involves an entire lobe. Nelson stressed the point that each bronchopulmonary segment possesses an independent bronchovascular structure and is separated from adjacent pulmonary tissue by an avascular cleavage plane. Segmental resection therefore not only eradicates all of the diseased tissue, but spares the uninvolved segment.

LUNG ABSCESS

A nontuberculous lung abscess is a circumscribed pyogenic infection of the lung. It is usually associated with a history of

tonsillectomy or aspiration of a foreign body such as teeth, peanuts, etc. *Fusiform* bacilli, Vincent's spirochetes, and streptococci may be aspirated with the foreign body or blood. The right lower lobe is most commonly involved.

Treatment may be instituted in one of 3 ways: intercostal drainage, costectomy with drainage, or a 2 stage operation.

Intercostal drainage is accomplished by means of an incision made parallel to the overlying muscle fibers which are separated and retracted. The incision is extended through the intercostal muscles and to the parietal pleura. Evidence of motion of the lung is noted. If the pleura is thickened and normal gliding movements of the lung cannot be seen, one concludes that the visceral and parietal pleurae have become adherent by adhesions, and opening of the abscess is safe. If adhesions have not been formed between the pleural surfaces, the operation is interrupted, and the wound packed with gauze to promote the formation of adhesions. After a week or 10 days, pleural adhesions are usually present in sufficient amount to protect the pleural cavity from contamination and the abscess is then opened. An aspirating needle usually locates the abscess first, and when pus is found, the needle is followed with a scalpel or cautery into the abscess cavity. Drainage is then instituted.

Costectomy with drainage is usually the operation of choice, since it provides adequate drainage. The abscess is located by several roentgenograms, and the skin incision placed as close to the pathology as possible. A section of rib is resected, usually from 5 to 8 cm long which overlies the abscess. The pleura is exposed and if the pleurae are adherent, the abscess is entered; if not, a 2 stage operation is performed.

The 2 stage operation with rib resection is considered by many to be a safer procedure. The periosteum is stripped from two or three ribs for a distance of 8 or 10 cm. The middle one of these 3 ribs is resected




FIG 217 The trachea and the extrapulmonary bronchi (A) relations as seen from in front (B) viewed from the left side (C) the trachealis muscle seen in cross section

glands are associated with the trachea at its bifurcation the paratracheal glands lie on each side of it in the superior mediastinum

RIGHT AND LEFT EXTRAPULMONARY BRONCHI

The bronchi diverge from each other on their way to the roots of the lungs and

differ in size length and the direction in which they run The right bronchus is shorter wider and more vertical Because of this foreign bodies from the trachea usually pass to the right side It is about 1 inch long and since it supplies the larger lung is larger in size Anterior to it are the right pulmonary artery, the pericar-

The Trachea and Extrapulmonary Bronchi

THE TRACHEA PROPER

The *trachea* begins where the larynx ends that is at the lower border of the cricoid cartilage which is on a level with the seventh cervical vertebra (Fig 217). It is from 4 to 5 inches long half of which is in the neck (cervical portion) and the other half in the thorax (thoracic portion). The trachea enters the thoracic inlet opposite the upper border of the manubrium sterni and ends at its lower border (Fig 217A and 217B) the latter point is situated on a level between the third and fourth thoracic spines where it divides into right and left primary bronchi. Its thoracic portion is opposite the manubrium and wholly within the superior mediastinum. It occupies the median plane except at its lower end where the aortic arch pushes it slightly to the right. About 15 or 20 horseshoe shaped rings of hyaline cartilage keep its lumen open and support the lateral and anterior aspects but are deficient posteriorly where the wall is flattened. The posterior portion is closed by the trachealis muscle, which is made up of transverse plain fibers supplied by the recurrent laryngeal nerve (Fig 217C). Anteriorly, the trachea is crossed by the isthmus of the thyroid (second to fourth ring) and below that structure it is related to the inferior thyroid veins which pass downward upon it, frequently communicating with each other and opening into the innominate veins. In young children the left innominate vein may appear above the level of the manu-

brium sterni forming an anterior relation of the trachea.

RELATIONS

Posteriorly the trachea is in contact with the esophagus. *Interiorly*, in the neck, the isthmus of the thyroid gland covers the second, third and fourth tracheal rings (Figs 217 218). In its lower part, it is crossed by the arch of the aorta, with the deep cardiac plexus intervening. Also in front of the trachea, are the roots of the innominate and left common carotid arteries which separate it from the left innominate vein. As these two arteries travel upward they diverge, and in the interval which is made by this divergence, the remains of the thymus gland are found. More anteriorly the manubrium sterni is situated with the lower part of the sternohyoid and the sternothyroid muscles which arise from the back of it.

On the *right side* the trachea is in relation to the right pleura and lung the right vagus nerve and the arch of the azygos vein. In the neck it is related to the right lobe of the thyroid gland from the commencement of the trachea to the sixth ring. The right recurrent laryngeal nerve passes along its lateral posterior aspect. On the *left side* it is related to the left common carotid and subclavian arteries, the phrenic and vagus nerves and the lower part of the arch of the aorta where it is separated from the left pleura and lung. The left recurrent laryngeal nerve has the same relationship as the right. Many tracheobronchial lymph

Mediastinum (Interpleural Space)

BOUNDARIES OF THE MEDIASTINA

The mediastinum is the middle compartment of the chest which is situated between the two pleural cavities. Its boundaries are (Fig. 219) anterior the sternum posterior the bodies of the twelve thoracic vertebrae superior the thoracic inlet inferior the diaphragm. The sides are formed by the mediastinal pleurae. It is divided into superior and inferior mediastina by an imaginary line which extends from the sternal angle (manubriosternal joint) to the disk between the fourth and fifth thoracic vertebrae. The inferior mediastinum is subdivided into 3 mediastina by the heart which acts as the key structure in this subdivision. That part of the inferior mediastinum which contains the heart is called the middle mediastinum; that part in front of it makes up the anterior and the part situated behind the heart constitutes the posterior mediastinum.

Each of the four mediastina have their own boundaries. The *superior mediastinum boundaries* are superior the thoracic inlet inferior an imaginary line extending from the sternal angle to the disk between the fourth and fifth thoracic vertebrae; anterior the manubrium sterni; posterior the bodies of the upper four thoracic vertebrae. The *anterior mediastinum boundaries* are superior the imaginary line separating it from the superior mediastinum; inferior the diaphragm; anterior the body of the sternum; posterior the anterior aspect of the pericardium. The *middle mediastinum boundaries* are superior and inferior the same as the anterior mediastinum; anterior the anterior

part of the pericardium; posterior, the posterior part of the pericardium. The *posterior mediastinum boundaries* are superior, same as the anterior and middle mediastina; inferior same as the anterior and middle mediastina; anterior, the posterior aspect of the pericardium; posterior the bodies of the lower eight thoracic vertebrae.




FIG. 219 Diagrammatic sagittal section of the mediastinum. An imaginary line which extends from the sternal angle to the disk between the fourth and the fifth thoracic vertebrae divides the mediastinum into superior and inferior mediastina. The inferior mediastinum is divided by the heart into anterior, middle and posterior mediastina.




FIG. 218 The relations of the trachea and primary bronchi. The eparterial and hyparterial branches of the right bronchus have been identified. A bronchoesophageal muscle was present in this specimen.

dium the lower part of the superior vena cava and the ascending aorta. The arch of the azygos vein is placed above and the bronchial vessels and posterior pulmonary plexus are posterior. The upper pulmonary vein is anterior, the lower pulmonary vein is below. The right bronchus gives off a branch which is called the *eparterial branch* so named because it arises above the right pulmonary artery; it passes to the upper lobe of the right lung. The bronchus continues as the *hyparterial branch* which passes below the artery and divides into two, one branch for the middle lobe and one for the lower (Fig. 218). The *left bronchus* has further to travel than the right since the left lung hilum is farther from the median plane. It is, therefore, nearly twice

as long as the right and less vertical. The arch of the aorta passes backward and over it, and the descending thoracic aorta runs downward and behind it. Anteriorly are the left pulmonary artery, and the pericardium which separate the bronchus from the left atrium. The posterior pulmonary plexus, esophagus and bronchial vessels are situated behind this bronchus. Occasionally a muscle band exists between the esophagus and the left bronchus, called the *bronchoesophageal muscle*.

The *carina* is a sagittal spur located at the margin of the primary bronchus and is easily seen through the bronchoscope as it passes upward into the lumen. It is employed as a landmark by the bronchoscopist.




FIG 221 Contents of the superior and middle mediastina viewed from behind

pulmonary artery dividing into right and left branches the right and left pulmonary veins the phrenic nerves the bronchial lymph glands

The posterior mediastinum contains the esophagus the descending thoracic aorta, the vagi the thoracic duct the azy

gos hemiazygos and accessory hemiazygos veins (Fig 222)

SURGICAL CONSIDERATIONS

DRAINAGE OF MEDIASTINAL ABSCESS

Most mediastinal abscesses (mediastinitis), are drained through a right supra




FIG. 220 Contents of the superior and middle mediastina viewed from in front

CHIEF CONTENTS OF EACH MEDIASTINAL SPACE

The superior mediastinum contains the arch of the aorta and its branches (innominate left common carotid and left subclavian arteries) the innominate veins the upper half of the superior vena cava the vagus phrenic and left recurrent nerves the esophagus trachea and thoracic duct, the thymus or its remains in the adult

with some lymph glands (Figs 220 and 221)

The anterior mediastinum contains a few lymph glands (anterior mediastinal glands), and a little areolar tissue

The middle mediastinum contains the heart enclosed in the pericardium the ascending aorta the lower half of the superior vena cava (with the azygos vein entering it) the bifurcation of the trachea, the

Rarely is it necessary to perform an anterior or posterior mediastinotomy.

CARCINOMA OF THE ESOPHAGUS

Carcinoma of the midthoracic esophagus has been treated quite successfully by Churchill Garlock, Sweet and others. The lesion has been eradicated successfully by radical resection with high intrathoracic esophago-gastrostomy. The essential steps in the operation are as follows (11, 224): the usual incision is placed at the left costal margin anteriorly, extends posteriorly over the eighth or ninth rib and then curves upward for a short distance between the spine and the left scapula. The eighth or ninth rib is resected. If greater exposure is necessary, the fifth, sixth or seventh ribs are divided posteriorly. The left thoracic cavity is entered, the mediastinal pleura incised and dissection begun anterior to the esophagus. Resectability depends upon whether or not the growth has invaded the left main bronchus, aortic arch or inferior pulmonary vein. If these structures can be safely mobilized, dissection posterior to the esophagus is begun. The posterior dissection is left until last to avoid interfering with the blood supply resulting from the division of the esophageal arteries arising from the aorta. When the posterior dissection is completed, the tumor is freed from the right mediastinal pleura. The esophagus is mobilized from the aortic arch downward and the abdomen is entered through an incision in the diaphragm which extends from the esophageal hiatus to the insertion at the costal margin. Phrenic nerve crushing immobilizes the diaphragm. The greater curvature of the stomach is mobilized by dividing the gastrohepatic ligament and ligating the left gastroepiploic vessels and vasa brevia. The gastrocolic omentum is divided as far as the pylorus, but the right gastric and gastroepiploic vessels are protected. In the region of the lower esophagus and cardia, it may be necessary to ligate branches of the superior suprarenal inferior phrenic and pericardiophrenic vessels.

The gastrohepatic ligament is severed next, and occasionally a hepatic branch of the right inferior phrenic artery is found in this structure. The left gastric vessels are ligated. The stomach is divided distal to the cardia, and the distal portion is inverted with sutures. An incision is made in the mediastinal pleura above the aortic arch, and the attachments of the esophagus behind the arch are freed. These are usually small vessels which arise from the aorta and bronchial arteries. When the esophagus has been fully mobilized, it may be pulled up from behind the aortic arch and prepared for the anastomosis. The esophagus and tumor are resected and the anastomosis is completed. To relieve tension upon the anastomotic suture line, interrupted sutures fix the stomach to the parietal pleura and the diaphragm, which is closed. The stomach now receives its blood supply from the right gastric and right gastroepiploic arteries. If the anastomosis is placed below the aortic arch, an adequate blood supply to the esophagus is maintained by the small arteries from the aorta and bronchial vessels. However, if it is necessary to dissect the esophagus above the aortic arch, the blood supply is entirely dependent upon the descending branches from the inferior thyroid artery. The thoracic duct may be encountered or injured in these high dissections; it is important to ligate this structure to prevent a leakage of chyle.

Ivor Lewis states that carcinoma in the middle third of the esophagus should be approached through a *right* transpleural route. His reasons for this are the following: this offers easier accessibility; only the vena azygos major requires ligating and the aortic arch instead of being an obstacle becomes a safety barrier between the surgeon and the opposite pleural cavity. He concludes, therefore, that to operate on this part of the esophagus through the left side is un-anatomical. His operation is usually performed in 2 stages. The first stage is done through an upper left paramedian incision, the abdomen being carefully explored. If




FIG 222 Contents of the posterior mediastinum (A) cross section, (B) seen from behind

clavicular incision which is made in a transverse direction (Fig 223A). This is deepened between the thyroid gland and trachea medially, and the carotid sheath and sterno-

cleidomastoid muscle laterally. A finger is introduced along the right side of the esophagus and follows this downward until the abscess is reached and opened (Fig 223B).




FIGURE 224 (Legend on facing page)




FIG 223 Drainage of a mediastinal abscess (A) right supraclavicular transverse incision (B) the abscess is sought in a space between the trachea medially and the carotid sheath laterally

there are no metastases on the greater curvature of the stomach this structure is mobilized as has been described above. A jejunostomy is done to improve the patient's nutrition. From 10 to 15 days later, the second stage is accomplished by removing

the right sixth rib and entering the chest. The vena azygos major is divided and the procedure progresses much in the same way as has been described. Lewis claims that the cardia of the stomach can readily be delivered into the right thoracic cavity.

FIG 224 (Facing page) Resection for carcinoma of the midthoracic portion of the esophagus (A) The incision is placed at the left costal margin anteriorly extends posteriorly over the eighth or the ninth rib and curves upward between the spine and the left scapula (B) Anterior dissection of the esophagus (C) The esophagus and the stomach have been mobilized and prepared for resection (D) The anastomosis between the esophagus and the stomach is made high in the thoracic cavity (E) To relieve tension on the anastomotic suture line interrupted sutures fix the stomach to the parietal pleura and the diaphragm


TRANSSTHORACIC SUBCOSTAL BRACHIAL SECTION OF THE VAGUS NERVES (VAGOTOMY)

Dragstedt and others have advocated this procedure (Fig. 225) as a therapeutic measure for duodenal ulcers in the absence of pyloric stenosis, gastrojejunal ulcers and gastric ulcers where the diagnosis is certain.


The incision is placed over the eighth rib on the left side and the rib is widely resected. Greater exposure may require the additional removal or fracture of adjacent ribs. The left pleural cavity is entered through the rib bed and the collapsed lung is retracted upwards. The inferior pulmonary ligament is identified and severed. The lower end of the esophagus will be found in an *anatomic triangle* which is bounded in front by the heart, behind by the de-

scending aorta and below by the diaphragm (Fig. 225D). Cutting the inferior pulmonary ligament exposes this triangle and the esophagus. The vagus nerves are identified by palpation since they have no elastic fibers and feel like taut cords. In most cases, they appear as two main trunks but recent work on vagal anatomy reveals that considerable variation in the arrangement of the nerves takes place. The *left* vagus appears anterior to the esophagus and extends to the lesser curvature of the stomach. The *right* vagus is situated posteriorly. A large communicating branch between the vagi is a rather constant finding. Additional small fibers may be found on the esophagus. All the nerves and fibers are severed, and the large ones are ligated. The esophagus is returned to its bed and the pleura closed.

A
Incision
8th rib



B



D
Esophageal
triangle

Esophagus
Right(post) vagus n
Left(ant) vagus n




FIG 225 Transthoracic vagus nerve section (vagotomy) (A) Incision over the left eighth rib (B) Removal of a section of the left eighth rib (C) Mobilization of the esophagus and exposure of the vagus nerves. A communicating nerve branch which is quite constant is noted in this subject (D) The esophageal triangle. The esophagus can be found readily in a triangle bounded in front by the heart, behind by the descending aorta and below by the diaphragm.




FIG. 226 The pericardium. This fibrous sac encloses the heart and the roots of the great vessels. The pericardium has been cut open to reveal these structures.

of the left atrium where it is reflected downward as the *parietal* layer of serous pericardium. This reflection forms the upper limit of a cul-de sac known as the oblique sinus of the pericardium (p. 335). The pari-

etal layer follows and adheres to the fibrous pericardium.

The pericardial sac can be marked on the surface of the thorax as extending from the second costal cartilage above

Pericardium

PERICARDIAL SAC

The *pericardium* is a fibroserous sac which is located in the middle mediastinum and which encloses the heart and roots of the great vessels. It has the appearance of a truncated cone with its base resting on and fused with the central portion of the diaphragm. Its blunt apex reaches the level of the second costal cartilage (Figs 226-227). The outline of the pericardium corresponds to that of the heart except that it reaches the second costal cartilage on both sides whereas the heart extends only to the third cartilage on the right.

PERICARDIAL LAYERS

The *pericardium* has 3 layers so arranged that the fibrous pericardium is entirely parietal but the serous has both visceral and parietal layers.

FIBROUS PERICARDIUM

The fibrous pericardium is applied to and is firmly fused with the outer surface of the parietal layer of serous pericardium. It is a sheet of considerable strength which fuses with the central tendon of the diaphragm inferiorly, and can be separated from it only by sharp dissection. Superiorly and posteriorly, it blends with the outer coats of the great vessels as they enter or leave the pericardial sac. It is by means of the outer fibrous coat of the arch of the aorta that the fibrous pericardium blends with the pretracheal layer of deep cervical fascia.

Relations The fibrous pericardium lies behind the body of the sternum and the costal cartilages from the second to the sixth in

clusive. Its anterior surface is separated from these structures by the lungs and pleurae except at two places. One point of contact is in the median plane, where the fibrous sac is attached to the upper and lower parts of the body of the sternum. This is brought about by two condensations of mediastinal areolar tissue which are called the upper and lower *sternopericardial ligaments*; these are of clinical importance in adhesive pericarditis. The other point of contact is in the region of the *bare area of the pericardium* which has no covering of lung. This is located at the sternal end of the left fifth costal cartilage (Fig 227). Here the cardiac notch leaves a deficient area of left pleura, and the pericardium comes in direct relation to the left sternocostalis muscle and the sternum. This area is of importance to the surgeon since he may tap the pericardial sac at this point without injury to the pleura. Both side walls of the pericardium are in relation to the mediastinal pleura.

VISCERAL AND PARIETAL LAYERS

The *visceral* layer of *serous pericardium* is usually called the *epicardium*. It is exceedingly thin and is so closely adherent to the outer surface of the heart that any attempt to detach it results in injury to the superficial layers of cardiac musculature. However, over the right side and the anterior surface of the ventricular portion of the heart a certain amount of fat, even in thin individuals, occurs between the muscular tissues and the epicardium. The visceral layer covers the anterior and inferior surfaces of the heart and ascends on the ¹




FIG 226 The pericardium. This fibrous sac encloses the heart and the roots of the great vessels. The pericardium has been cut open to reveal these structures.

of the left atrium where it is reflected downward as the *parietal* layer of serous pericardium. This reflection forms the upper limit of a cul de sac known as the oblique sinus of the pericardium (p. 335). The pari-

etal layer follows and adheres to the fibrous pericardium.

The pericardial sac can be marked on the surface of the thorax as extending from the second costal cartilage above




FIG 227 The pericardium seen from within and behind

to the sixth below. On the right, it extends for $\frac{1}{2}$ inch beyond the right margin of the sternum and to the left, it forms a line which passes upward and medial from the cardiac apex to the second left costal cartilage about $1\frac{1}{2}$ inches from the mid line. The latter is convex upward and to the left.

When the anterior wall of pericardium is opened it is noticed that its outer wall appears fibrous (fibrous pericardium), but its inner wall is lined with a thin, glistening serous membrane (parietal layer of serous pericardium). The parietal and visceral layers of pericardium are continuous with each other anteriorly where the great arteries leave the heart, and posteriorly where the great veins enter it. That space which exists between the two layers of serous pericardium is a potential cavity called the pericardial cavity. It contains sufficient serous fluid to minimize friction between its two surfaces during heart action.

SURGICAL CONSIDERATIONS

PERICARDIOCENTESIS

Aspiration of the pericardial cavity is done for diagnostic purposes or to release pressure in the pericardial cavity. Even with large effusions, the heart remains anterior and may be injured during this procedure. The aspirating needle should be placed to the left of the xiphoid thus avoiding the internal mammary artery. It should then be directed upward, backward and to the left, so that the heart is avoided and the left lateral pouch of dilated pericardium entered. If the needle is passed straight back the left coronary artery may be injured (Fig 228).

PERICARDIOSTOMY (PERICARDIOTOMY)

C. S. Beck and others have emphasized the importance of the subatmospheric pressure which exists in the mediastinum. When the pericardium is opened, this is raised to




FIG 228 Aspiration of the pericardial cavity (pericardiocentesis)
 (A) The aspirating needle is placed to the left of the xiphoid thus avoiding the internal mammary vessels (B) The needle is directed upward backward and to the left so that the left coronary vessels are not injured

atmospheric pressure and the resultant compression upon the heart causes a rise in venous and a slight transient fall in arterial pressures. A normal heart may tolerate these changes but should the heart be damaged the patient might succumb.

Many incisions and approaches for the purposes of draining the pericardial cavity have been described. One of the more common extends from the junction of the left fifth costal cartilage and sternum downward over the cartilages of the fifth, sixth

and seventh ribs. About an inch of cartilage of the fifth, sixth and seventh ribs is removed, and the internal mammary vessels ligated. The pericardium lies beneath and the pleural space is to the left. An incision is made into the pericardium, and the fluid

aspirated from each lateral pericardial recess and from the oblique sinus. The pericardium is left open to drain. Soft rubber tubes are introduced into the opening; this, however, is to be avoided in tuberculous pericarditis.

18

Heart

THE HEART PROPER

With the pericardium opened the heart (Fig 229) presents a fixed posterosuperior portion the atria (auricles) and a free antero-inferior portion—the ventricles. A groove containing fat the auriculoventricular groove (coronary sulcus) marks the line of separation between atria and ventricles. It contains the right coronary artery. Passing downward and to the left a similar groove is found which divides the ventricular portion of the heart as seen in front into a larger right and a smaller left ventricle. This groove corresponds to the attachments of the anterior margin of the septum between the right and left ventricles and is known as the *anterior inter-ventricular groove* (anterior longitudinal sulcus). It contains the anterior descending branch of the left coronary artery. All four chambers of the heart are visible from the front view; however only a very small portion of the left atrium is visible; the auricle of the left atrium.

The right border of the heart which is convex is formed by the right atrium; the left border is formed almost entirely by the left ventricle. The auricle of the left atrium aids in the formation of the left border at its uppermost part. Between the two auricles the lower part of the pulmonary trunk covers the ascending aorta. That part of the right ventricle which is immediately below the pulmonary trunk is called the *infundibulum*.

If the left index finger is passed in front of the superior vena cava it can be directed from right to left behind the aorta and

pulmonary artery. The finger now lies in the *transverse sinus of the pericardium* (Figs 230 and 231). If the thumb is brought into contact with this index finger the *arterial end* (aorta and pulmonary artery) of the heart lies between the two digits. All large vessels below the transverse pericardial sinus constitute veins (superior and inferior venae cavae and pulmonary veins). The sinus is bounded in front by the aorta and pulmonary artery and behind by the superior vena cava and left atrium. It is possible to pass a finger through the sinus because the aorta and pulmonary artery are enclosed in a complete sheath of visceral pericardium; the superior and inferior venae cavae and the pulmonary veins are only partially covered (front and sides) by this layer. The transverse sinus connects the right and left upper portions of the pericardial cavity. It is through this sinus that a rubber catheter is placed in the Trendelenburg operation for pulmonary embolus.

If the fingers of the right hand are placed behind the apex of the heart and passed upward and to the right they are stopped in a cul de sac of pericardium which lies behind the heart between the left atrium and pericardium. This is known as the *oblique sinus of the pericardium*. It is really an inverted U bounded below and on the right by the inferior vena cava and right pulmonary veins and above and on the left by the pulmonary veins. The sinus lies in front of the esophagus and descending thoracic aorta (Fig 231). Fingers placed in the transverse and oblique sinuses can not touch each other because they are sepa-





FIG 229 Heart and great vessels (A) seen from in front, (B) seen from behind




FIG 230 The transverse and oblique sinuses (Top) A catheter is placed in the transverse sinus (Bottom) The transverse sinus (in green) seen from above The structures in front of the green line constitute the arterial flow of the heart (aorta and pulmonary artery), those behind the green line are veins (venae cavae and pulmonary veins)

rated by 2 layers of serous pericardium surrounding the veins as they enter the left atrium

THE SUPERIOR AND INFERIOR VENAE CAVAE

The superior vena cava measures about 7 cm in length and is formed by the junction of the two innominate veins draining the blood from the upper half of the body (Figs 226-229 and 231) It begins im-

mediately below the cartilage of the second right rib, close to the sternum it descends vertically behind the first and second intercostal spaces and ends in the upper part of the right atrium opposite the upper border of the third right costal cartilage The lower half of the vessel lies within the pericardium and is devoid of valves at its orifice The intrapericardial portion lies entirely within the fibrous pericardium and is




FIG. 231 The transverse and oblique sinuses. A window has been cut in the pericardium to show the posterior relation of the esophagus, the aorta and the left vagus nerve. The small arrows represent the flow of blood to and from the heart.

covered in front and on either side by the serous pericardium which binds it to the fibrous layer. On its right side it is separated from the right phrenic nerve and its companion vessels by the pericardium on its left and overlapping it slightly anteriorly, is the ascending aorta. Because of its close relationship to the ascending aorta, it may be compressed by aortic aneurysms. The transverse sinus intervenes between the superior vena cava and the ascending part of the aorta. In front of the vein, at its termination, is the right auricular ap-

pendix and higher it is separated from the right lung and pleura by the pericardial wall. Behind the vein, is the fibrous pericardium which separates it from the root of the right lung. The vena azygos enters the back of the superior vena cava immediately before it pierces the fibrous pericardium (Fig. 217).

The inferior vena cava (Figs. 229 and 231) is formed by the junction of the two common iliac veins on the right side of the fifth lumbar vertebra, and returns the blood from the parts below the diaphragm to the

heart. This vessel ascends along the front of the vertebral column to the right side of the *vorta* passes in a groove on the posterior surface of the liver, and then perforates the diaphragm between the median and right portions of its central tendon. It pierces the fibrous pericardium passes behind the serous pericardium and opens into the lower posterior part of the right atrium. Therefore only a small part of this vessel, about $\frac{1}{2}$ inch is intrathoracic. Near its atrial orifice is a semilunar valve which has been called the valve of the inferior vena cava (Fig. 232). This is usually rudimentary in the adult but may be large in the fetus where it performs an important function. In the fetus this valve serves to direct the blood from the inferior vena cava through the foramen ovale into the left atrium. In its intrathoracic portion the following relationships are noticed: the diaphragm is in front of it, the vena azygos and the greater splanchnic nerve are behind it, the phrenic nerve, right pleura and lungs are lateral. The latter two structures also lie behind it.

COMPARTMENTS OF THE HEART

The *compartments of the heart* may be studied in the order in which they are traversed by the blood (Fig. 234).

Right Atrium

If the heart is pulled to the left a good view is obtained of the right side of the auricular portion and of the superior and inferior venae cavae. The right atrium (Figs. 232 and 234) begins at the orifice of the inferior vena cava behind the sixth right cartilage. Immediately in front of the opening of the superior and inferior venae cavae an indistinct line might be seen which is called the *sulcus terminalis*. This line is of interest because it indicates the junction between the sinus venosus and the right auricle and marks a ridge which is on the inside of the right auricle called the *crista terminalis*. The sinus venosus is represented in the adult human heart by that part of the right auricle which lies

behind the sulcus and receives the superior and inferior venae cavae. If a window is cut in the right auricle, the *crista terminalis* is seen extending from the front of the orifice of the superior vena cava to the front of the orifice of the inferior vena cava. The atrium behind the *crista* is smooth and in front it is trabeculated. The rugose appearance of the auricle in front of the *crista* is brought about by muscle bands which resemble the teeth of a comb, hence the name *musculi pectinati*. The posterior wall of the atrium represents the *atrial septum* which separates the right atrium in front from the left behind. Near its center is noted a shallow oval depression which is bounded by a thickened ridge everywhere except below. This depression is the *fossa ovalis*, and the ridge surrounding it is the *annulus ovalis* (*limbus fossae ovalis*). From the anterior horn of the annulus there will usually be seen a crescentic membrane which passes forward and to the right reaching the anterior wall of the auricle immediately in front of and to the right of the opening of the inferior vena cava. It is called the *cuspidian valve* (valve of the inferior vena cava) which directed blood in the fetus from the inferior vena cava to the fossa ovalis, and was known as the *foramen ovale*. The *tricuspid orifice* (right atrioventricular orifice) occupies the lower portion of the anterior wall of the right atrium. It is large enough to admit the tips of three fingers, opens into the lower and posterior part of the right ventricle and is bounded by the tricuspid valve. The surface projection of this aperture lies obliquely behind the sternum close to the midline and extends from the level of the fourth left costal cartilage to the level of the sixth right cartilage. Medial to the opening of the inferior vena cava, the coronary sinus may be found. The opening of the sinus points to the left and is guarded by a small pocket like valve called the *coronary valve* (*Thebesius*) which turns the blood of the coronary sinus forward into the atrioventricular orifice.




FIG. 232 The right atrium and the right ventricle. Windows have been cut into these two heart chambers to show their internal structure. The arrow passes through the right atrioventricular orifice.

Right Ventricle

This chamber (Fig. 232) has a thick muscle wall and is somewhat triangular in outline. The *infundibulum* (conus arteriosus) is the uppermost part of the right ventricle, the walls of which are smooth and have no projecting muscular bundles; it leads into the pulmonary artery. The inner surface of the right ventricle is extremely irregular because of a lacework of muscular ridges which are called the *trabeculae carneae*. Some of these are attached to the wall only at each extremity, but they are free elsewhere. A number of conical muscular projections are

also found; these are the *papillary muscles*. They are attached at their bases to the wall of the ventricle and their apices are connected to the cusps of the tricuspid valve by a number of tendinous strands called the *chordae tendinae*. There is usually a large inferior papillary muscle which is attached to the anterior wall. One of these trabeculae, which is unusually strong and well marked, passes across the right ventricle from the septum to the base of the anterior papillary muscle; it is called the *moderator band*. The entrance to the right ventricle is by way of the right atrioventricular orifice,




FIG. 233 The left atrium and the left ventricle. Windows have been cut into these chambers, and arrows indicate the course of the blood stream.

and the exit is the pulmonary orifice. The right atrioventricular orifice is situated at the lower and posterior part of the ventricle, is about an inch in diameter and surrounded by a fibrous ring. It usually admits the tips of 3 fingers and is guarded by a valve which possesses 3 cusps; hence the name tricuspid valve. One of the cusps is anterior, another

medial and the third inferior; they are semi-lunar in shape. The atrial surfaces of the cusps are smooth, but their ventricular surfaces are roughened by the attachments of the chordae tendinae. The pulmonary orifice in the upper posterior part of the ventricle at the apex of the infundibulum is surrounded by a thin fibrous ring to which




FIG 234 Diagram of heart chambers, valves and vessels. The arrows indicate the direction of blood flow, and the colors designate oxygenated and nonoxygenated blood.

the bases of the 3 cusps of the pulmonary valve are attached.

Left Atrium

Only the auricle of the left atrium (Figs 233-234) can be seen from in front and to view the remainder of this chamber one must lift the apex of the heart upward and examine the posterior surface of the organ. The left atrium is quadrilateral in shape, and its interior reveals the openings of the 4 pulmonary veins usually 2 on either side. These veins are unguarded by valves. The interior of the chamber is quite smooth except in its auricular portion where muscular pectinati are present. In a fresh heart the interior of the left atrium looks much paler

than that of the other chambers, because of the greater thickness of the endocardium, which can be stripped off easily, though it is quite difficult to do this in any other cardiac chamber. Blood leaves the left atrium and enters the left ventricle via the left atrioventricular orifice. This is smaller than the one on the right and admits only two fingers.

Left Ventricle

The cavity of the left ventricle (Fig 233) is longer and narrower than that of the right, and the walls are much thicker. Its interior reveals a dense meshwork of trabeculae carneae which are finer but more numerous than those of the right. The papillary mus-

cles of this ventricle, however, are less numerous and much stronger the chordae tendinae from each papillary muscle pass to both cusps of the mitral valve. The left atrioventricular orifice is surrounded by the bicuspid (mitral) valve which consists of a larger anterior cusp and a smaller posterior one. Blood leaves the left ventricle via the aortic orifice which is at the upper right and posterior part and (like the pulmonary orifice) is surrounded by a fibrous ring to which the bases of the cusps of the aortic valve are attached. The aortic valve like the pulmonary has 3 semilunar cusps (Fig 235).

BLOOD VESSELS AND NERVES

The trunk of the pulmonary artery (Figs 226 and 229) arises from the infundibulum of the right ventricle passes upward and backward and carries the blood from the right ventricle to the lung. It is about 2 inches long and nearly 1 inch in diameter and lies within the fibrous pericardium being enclosed with the ascending aorta in a sheath of serous pericardium. As it passes upward it lies between the right and left auricles which embrace it and being in front of the aorta conceals the roof of this vessel. It is behind the sternal extremity of the third left costal cartilage and as it travels upward and backward it bifurcates below the arch of the aorta like the letter T into right and left pulmonary arteries. This bifurcation takes place opposite the sternal end of the second left costal cartilage.

The *ligamentum arteriosum* is a fibrous band which extends from the bifurcation of the pulmonary trunk to the lower aspect of the aortic arch. It represents the remains of the ductus arteriosus of the fetus a vessel which short circuits the blood from the pulmonary circulation into the aorta. The left recurrent laryngeal nerve hooks around the left side of the ligament.

The pulmonary artery has the following relations anterior the pericardium and left pleura and lungs posterior the ascending aorta and left atrium superior is the arch of

the aorta and *ligamentum arteriosum* laterally the corresponding coronary arteries and auricles, on the right side, the ascending aorta.

The right pulmonary artery is longer than the left it commences below the arch of the aorta and passes to the hilum of the right lung. In its course it travels behind the ascending aorta and superior vena cava and in front of the esophagus and the stem of the right bronchus. It divides into three primary branches one for each lobe. The left pulmonary artery passes directly to the left in front of the descending aorta and the left bronchus. At the root of the left lung it divides into 2 primary branches one for each lobe.

The aorta is the great arterial trunk of the body, and is situated partly in the thorax and partly in the abdomen. It commences at the left ventricle arches over the root of the left lung descends in front of the vertebral column through the diaphragm and enters the abdomen. It ends opposite the left side of the body of the fourth lumbar vertebra by bifurcating into two common iliac arteries. It is conveniently divided into 4 parts the ascending aorta the arch of the aorta the descending aorta and the abdominal aorta. The ascending aorta springs from the left ventricle at the aortic orifice and travels upward and to the right. It is about 2 inches long and extends from the lower border of the third left costal cartilage to the level of the second right cartilage. At the second right costal interspace it is covered only by a thin layer of right lung therefore the aortic sounds can be heard best at this point. The superior vena cava lies to its right and the pulmonary artery to its left its branches are the right and left coronary arteries (p 347). The arch of the aorta is directed to the left but the principal inclination is backward. It begins at the level of the second costal cartilage at the right border of the sternum and extends to the left of the body of the fourth thoracic vertebra. Since aneurysms may involve this part of the




FIG 235 The heart valves seen from above The origins of the coronary arteries are shown

vessel its relations become clinically important

Relations of the arch to the aorta Five structures lie posterior and to the right (1) the trachea, (2) the esophagus, (3) the left recurrent laryngeal nerve (4) the thoracic duct and (5) the vertebral column Five structures lie anterior and to the left (1) the lung and pleura, (2) the left phrenic nerve (3) the left vagus nerve (4) the cardiac nerve and (5) the superior intercostal vein Five structures lie below (1) the left bronchus (2) the right pulmonary artery, (3) the ligamentum arteriosum (4) the left recurrent laryngeal nerve and (5) the superficial cardiac plexus Five structures lie above (1) the left common carotid artery (2) the left subclavian artery, (3) the innominate artery, (4) the thymus, and (5) the left innominate vein

The arch of the aorta supplies 3 branches in the order named the innominate, the left

common carotid and the left subclavian arteries (Fig 229)

The *innominate artery* arises from the aorta in front of the trachea, and then passes upward backward and to the right At the posterior aspect of the sternoclavicular joint, it divides into the right subclavian and the right common carotid arteries Anteriorly, it is separated from the manubrium sterni by the remains of the thymus and the left innominate vein the vein crosses the artery near the origin of the latter To the right side of the artery lie the right innominate vein and the superior vena cava which intervenes between the artery and the right pleura and lung To its left side, it is related to the left common carotid artery and the trachea Posteriorly, it lies on the trachea below, and the longus cervicis muscle above

The *left common carotid artery* arises from the aortic arch immediately to the left




FIG 236 The arteries and the veins of the heart (A) the coronary arteries (B) the venous drainage of the heart

of the innominate artery. It passes upward and to the left and enters the neck behind the left sternoclavicular joint. At their origins the left common carotid and the innominate arteries lie side by side but they diverge as they ascend. Anteriorly the artery is crossed by the left innominate vein, and the remains of the thymus intervene between it and the manubrium. Posteriorly

it is in contact with the trachea, the left recurrent laryngeal nerve and the esophagus. On its left side it is related to the left phrenic and vagus nerves, the left subclavian artery and the left lung and pleura. On its right side is the innominate artery.

The *left subclavian artery* arises from the aortic arch behind and to the left of the common carotid. It arches upward and lat




FIG 235 The heart valves seen from above The origins of the coronary arteries are shown

vessel its relations become clinically important

Relations of the arch to the aorta *Five* structures lie posterior and to the right (1) the trachea, (2) the esophagus (3) the left recurrent laryngeal nerve (4) the thoracic duct and (5) the vertebral column *Five* structures lie anterior and to the left (1) the lung and pleura (2) the left phrenic nerve (3) the left vagus nerve (4) the cardiac nerve, and (5) the superior intercostal vein *Five* structures lie below (1) the left bronchus (2) the right pulmonary artery (3) the ligamentum arteriosum (4) the left recurrent laryngeal nerve and (5) the superficial cardiac plexus *Five* structures lie above (1) the left common carotid artery (2) the left subclavian artery, (3) the innominate artery, (4) the thymus and (5) the left innominate vein

The arch of the aorta supplies 3 branches in the order named the innominate, the left

common carotid and the left subclavian arteries (Fig 229)

The *innominate artery* arises from the aorta in front of the trachea, and then passes upward, backward and to the right. At the posterior aspect of the sternoclavicular joint, it divides into the right subclavian and the right common carotid arteries. Anteriorly, it is separated from the manubrium sterni by the remains of the thymus and the left innominate vein, the vein crosses the artery near the origin of the latter. To the right side of the artery lie the right innominate vein and the superior vena cava which intervenes between the artery and the right pleura and lung. To its left side, it is related to the left common carotid artery and the trachea. Posteriorly, it lies on the trachea below, and the longus cervicis muscle above.

The *left common carotid artery* arises from the aortic arch immediately to the left

which passes from its right to its left side (Fig. 151). Throughout its course the thoracic duct and *azygos* vein lie on its right posterolateral side, and these structures pass with it through the thoracic orifice in the diaphragm at a level between the twelfth thoracic and first lumbar vertebrae. The *hemiazygos* vein is on its left posterolateral side. Branches arise from both the front and back of the descending aorta. The posterior branches consist of 9 pairs of posterior intercostal arteries of the lower nine intercostal spaces and one pair of subcostal arteries (p. 324). Those branches which arise from the front of the vessel are 2 left bronchial arteries, 4 esophageal and some small mediastinal, phrenic and pericardial branches.

The *coronary arteries* are the nutrient vessels of the heart (Figs. 235, 236A). They arise from dilations of the root of the aorta which are called the sinuses of the aorta. There are 3 such sinuses, 1 anterior and 2 posterior but only 2 coronary arteries, a right and a left. The right coronary arises from the anterior sinus and the left from the left posterior sinus. The origins of these vessels are hidden anteriorly by the right auricular appendix and the pulmonary artery. The vessels pass forward one on either side of the pulmonary artery and have the corresponding auricular appendix to their lateral sides. The right artery travels in the right atrioventricular sulcus to the back of the heart until it reaches the beginning of the posterior interventricular groove where it gives rise to a well developed *posterior descending inter-ventricular branch*. The left coronary artery reaches the anterior interventricular sulcus into which it sends an *anterior descending inter-ventricular branch* and the main trunk of the artery (circumflex artery) continues around the left side of the heart to reach its posterior aspect. The course of this vessel may be obscured by fat in the left auriculoventricular sulcus.

The *cardiac veins* accompany the arteries

in the sulci, and usually are superficial to the arteries (Fig. 236B). The companion of the left coronary artery is the *great cardiac vein*. It follows the course of the interventricular branch of the left coronary artery and the circumflex branch. The companion of the interventricular branch of the right coronary artery is the *middle cardiac vein*. Most of the venous blood of the heart enters the *coronary sinus*, which lies in the atrioventricular sulcus at the lower end of the oblique pericardial sinus. It is about an inch and a half long and opens into the right atrium at the left of the orifice of the inferior vena cava.

The *nerves* which supply the heart are derived from the vagus and the cervical ganglionated chain (p. 69). They spread over the aortic arch and the heart, and are distributed with the branches of the coronary vessels.

THORACIC PROJECTION OF THE HEART AND GREAT VESSELS

The heart and great vessels may be projected onto the anterior chest wall in the following way (Fig. 237). Four points are marked on the thorax. Two of these are placed in the middle of each second intercostal space, and an inch lateral to either sternal margin. If a line joins these two points it identifies the clinical base of the heart (superior border) and demarcates it from the great vessels. The third point is placed just below and medial to the nipple in the left fifth intercostal space and the fourth mark is located at the junction of the upper and middle thirds of the xiphoid. If these four points are joined the heart area is quite accurately outlined. The great vessel area is outlined by drawing a horizontal line across the manubrium about $\frac{1}{2}$ inch below the suprasternal notch. This line extends a little less than an inch lateral to either sternal margin. Two vertical lines connect these points to the cardiac area.

The internal jugular and subclavian veins unite behind the sternoclavicular articula-




FIG 237 Thoracic projection of the heart and the great vessels (A) the structures in situ, (B) the heart and the great vessel areas are projected by marking six points on the anterior chest wall (p 347)

erally and enters the neck. Except at its origin where it is crossed by the left innominate vein this artery lies in a groove on the left lung.

The *descending aorta* is continuous with the arch at the lower border of the left side of the fourth thoracic vertebra. Its length varies with the length of the thorax but averages from 7 to 8 inches. It travels on the left side of the body of the upper poste-

rior mediastinal vertebrae (the fifth, the sixth and the seventh) into which it usually forms a groove. It then inclines to the median plane and at this level passes through the diaphragm and enters the abdomen. Throughout its course it is in close contact with the left mediastinal pleura and the left lung and as it descends, passes behind the root of the left lung and the pericardium. It is crossed obliquely by the esophagus,




FIG 239 The Duval Barastey incision. This provides excellent exposure of the heart and protects the pleural cavities

higher in children (fourth interspace), lower in older people and is changed in pathologic conditions of the heart. The line indicating the division of the right atrium from the right ventricle (atrioventricular

sulcus) is drawn from the third left to the sixth right sternocostal joints. The left auricle can be indicated by drawing a small circle approximately the size of a dime at the sternal margin of the second left inter




FIG 238 Surface projection of the heart valves and their areas of maximum audibility

tion to form the innominate vein. The left innominate vein is longer because it must pass obliquely behind the upper half of the manubrium to join the right innominate vein, thus forming the superior vena cava. This junction takes place behind the middle of the right border of the manubrium. The superior vena cava is thus formed in the region of the angle of Louis and continues as far as the right third costal cartilage. At this point, the right atrium begins and continues from the third costal cartilage to the sixth, making a slight convex bulge outward, this represents the right border of the heart. The inferior vena cava enters the right atrium approximately at the level

of the sixth costal cartilage. A straight line, therefore, can be drawn 1 or 2 cm laterally to the right border of the sternum which connects the right internal jugular vein with the inferior vena cava. This line would mark the right internal jugular vein, the superior vena cava, the right atrium and the inferior vena cava. The inferior margin of the heart extends from the sixth costal cartilage on the right, near the entrance of the inferior vena cava, to the apex of the heart. It is convex and lies on the diaphragm. The cardiac apex is located in the fifth left intercostal space, approximately $3\frac{1}{2}$ inches from the median plane. This, however, is a variable point since it lies




FIG 241 Operation for patent ductus arteriosus




FIG 240 Spangaro's incision. This approach provides rapid access to the heart, but at times inadequate exposure

costal space. The left ventricle is marked as a small strip which extends between the third and sixth left costal cartilages to the apex. All four chambers of the heart, therefore, may be mapped out over the sterno-costal surface.

The veins in this area usually lie superficial to the arteries. The ascending aorta overlaps the superior vena cava as it passes upward and to the right. The arch of the aorta passes backward and to the left, behind the lower half of the manubrium; it is below the left innominate vein. The latter crosses in front of the vein the left common carotid and left subclavian arteries. The pulmonary artery passes upward and to the left between the auricles. It lies in front of and hides the root of the aorta, and below the aortic arch it divides into a right and a left pulmonary artery.

The veins of the sternocostal area consist of the right and left innominates.

The right innominate vein passes almost vertically downward for about an inch, but the left, which is nearly three times as long, runs almost horizontally behind the upper half of the manubrium. It joins the right

vein behind the lower part of the first right costal cartilage near its junction with the manubrium. At times, the left innominate vein may appear above the suprasternal notch. This happens more frequently in children. If this should be the case the vein is in danger in operations about the root of the neck. To the left side of the vein is the innominate artery, but the vein somewhat overlaps the artery. It is separated from the sternoclavicular joint by the sternohyoid and sternothyroid muscles.

The left innominate vein begins behind the left sternoclavicular joint, and ends by joining the right innominate to form the superior vena cava. In its oblique course, it passes behind the remains of the thymus and in front of the left subclavian, left common carotid and innominate arteries.

AREAS OF MAXIMUM AUDIBILITY OF HEART VALVE SOUNDS AND THEIR THORACIC PROJECTION

The audibility of the heart valves (Fig 238) is dependent upon the depth of the valves from the surface of the chest, the

intrapericardial fluid which will accumulate. Muscle, fascia and skin are closed in layers.

PERICARDIOTOMY

Warren, Cole, Weber and Keeton have described a technique of pericardiectomy for constrictive pericarditis. They state that the excision of the scar should be started over the left ventricle and an attempt should be made to find a cleavage plane between the scar and cardiac musculature. Dissection continues in this plane. Since all landmark marks are usually obliterated, the coronary vessels may be difficult to find and injury to these vessels is dangerous. Harrington has stressed the importance of epicardiectomy as well.

PATENT DUCTUS ARTERIOSUS

A patent ductus should be ligated or divided to improve circulatory function and to diminish the hazards of blood stream infection. The operation is performed usually through an incision in the left mammary fold as advocated by Gross (Fig. 241). This extends from the sternum to the anterior axillary line. The breast is reflected cephalad and the soft tissues divided so that the third and fourth costal cartilages are exposed. The pleural cavity is entered through the third intercostal space; the third and fourth cartilages are divided and the ribs retracted. The lung is retracted; the mediastinal pleura incised and the arch of the aorta and pulmonary artery exposed. The phrenic and vagus nerves are identified and mobilized and the patent ductus completely exposed. The latter is divided between clamps and carefully sutured. Harrington has expressed the belief that the older an individual gets the shorter the ductus becomes so that in adults the duct has really become an arteriovenous fistula. The parietal pleura of the mediastinum is sutured and closure of the chest wall is accomplished in layers.

Blalock and Russig introduced a new surgical procedure for anoxemia caused by pulmonary stenosis or pulmonary atresia. By anastomosing the subclavian or innominate artery to either the right or left pulmonary artery, the flow of blood to the lungs is increased. Potts, Smith and Gibson have described a technique in which the aorta has been successfully anastomosed to the pulmonary artery in certain types of congenital heart disease.

SURGERY OF THE AORTA

Alexander and Byron have reported a case of aortectomy. The problem of collateral circulation is interesting. Gitlow and Sommer have reported a case of complete coarctation in which the collateral circulation took place chiefly by way of the internal mammary, superior intercostal and subscapular arteries. Bramwell and Jones studied the collateral circulation in a case of complete aortic coarctation which occurred just distal to the left subclavian artery. They conclude that the main anastomoses were (1) the musculophrenic branches of the internal mammary to the inferior phrenic branches of the abdominal aorta and the superior phrenic branches of the thoracic aorta which formed a network above and below the diaphragm; (2) via the scapular and cervical branches of the subclavian and axillary arteries to the lateral dorsal branches of the aortic intercostals; (3) via the superior intercostals through the upper two to the next lower intercostals. Alexander and Byron however have stressed that in their case much of the collateral circulation took place through the superior and inferior epigastric arteries.

Ochsner and Dixon have reviewed cases of *superior vena cava thrombosis* rather extensively and have reported on personal experiences with this condition. They have advised exploratory superior mediastinotomy, which is also used as a decompressive measure.

sound transmitting quality of tissue and the direction of blood flow in the heart chambers. The *tricuspid* valve is heard best at the lower left quarter of the body of the sternum. This is where the right ventricle is nearest the surface. The *pulmonary* valve is heard best at the third left costal cartilage close to the sternum. This is opposite the valve proper, since the pulmonary trunk recedes from the surface as it travels upward. The *mitral* valve is placed deeper than the valves of the right side of the heart; it is located posterior to the left half of the sternum on a level with the fourth costal cartilage. Its auscultatory area is in the direction of the blood flow as it passes from auricle to ventricle and is over the cardiac apex. The *aortic* valve sound is heard best in the second right intercostal space at the sternal margin and is projected along the course of the blood stream. The ascending aorta passes forward, upward and to the right.

SURGICAL CONSIDERATIONS

EXPOSURE OF THE HEART

Many incisions have been described but only the more popular ones are considered.

The Duval-Barastý incision to the pericardium and heart gives excellent exposure and protects the pleural cavities (Fig. 239). Its only drawback is that it takes time to open and close and may be associated with shock. The incision is made in the midline from the second rib to the xiphoid process. The xiphoid is removed and the sternum split to the second interspace where it is cut transversely. The split halves of the sternum are retracted, the pleurae pushed aside and the pericardium opened anteriorly. The diaphragm and anterior pericardium are incised, making the incision a thoracoabdominal one.

Spangaro's incision is really an intercostochondral thoracotomy which provides a rapid approach to the heart, but not as good exposure as does the Duval-Barastý (Fig. 240). The incision is made through

the fourth intercostal space from the margin of the sternum to the anterior axillary line. The internal mammary vessels are ligated and divided. The fourth and fifth ribs and cartilages are separated and the left lung retracted. The pericardium is incised in the long axis of the heart and the pathology exposed and treated.

Parasternal and semicircular incisions which utilize flaps have also been advocated.

WOUNDS OF THE HEART

The immediate dangers in heart wounds are tamponade and hemorrhage. Aspiration while preparations for the operation are being made may be life saving. D. C. Elkin has reviewed this subject and emphasizes that if time permits, all efforts should be made to avoid entering the pleural cavity since a pneumothorax adds to the shock. One of the above mentioned incisions is utilized, and the wound in the pericardium is located and enlarged. If this is not found, the pericardium is opened between stay sutures. When the intrapericardial pressure is released, the bleeding becomes profuse and the contractions of the heart increase in force. The greatest difficulty is encountered in placing the first stitch. When the cardiac wound is located, the index finger of the left hand is placed over it, and the surrounding blood removed by suction. The first suture is placed directly beneath the finger and may be used for traction and hemostasis. The wound is then closed with unabsorbable suture material, the sutures passing into the muscle but not into the heart chambers. Claude Beck has emphasized the fact that wounds located in the edges of the heart, on its posterior surface, or behind the sternum are best reached by placing an apex suture. By this method the heart may be rotated so that the injury can be properly exposed. Beck's control suture steadies the heart while the other sutures are being placed. The pericardium should be loosely closed with interrupted sutures so that space is allowed for drainage of the




FIG 242 The azygos system of veins

tributary of the hemiazygos and either crosses the body of the eighth thoracic vertebra emptying into the azygos or ends in the hemiazygos. If it is very small or entirely absent the left superior intercostal extends as low as the fifth or sixth intercostal space.

If the inferior vena cava is obstructed the azygos and hemiazygos veins are one of the principal means by which collateral venous circulation is carried out since they connect the venae cavae and communicate with the common iliac veins via the ascending

lumbar and with many tributaries of the inferior vena cava.

The superior vena cava is about 2 inches long and commences at the lower border of the right first costal cartilage where it is formed by the union of the 2 innominate veins. It pierces the pericardium opposite the second right costal cartilage and ends in the upper and back part of the right atrium behind the third right cartilage. It has no valves and its tributaries are the two innominate veins, the vena azygos and a few small mediastinal and pericardial veins.

The Azygos System of Veins and the Superior Vena Cava

The azygos system (Fig. 242) consists of 3 veins which form longitudinal collecting trunks into which the intercostal veins drain the azygos (vena azygos major) the hemiazygos (vena azygos minor inferior) and the accessory hemiazygos (vena azygos minor superior). The azygos is located on the right side and the hemiazygos and accessory hemiazygos on the left. The right and left ascending lumbar veins constitute the most caudal portion of the system and drain into the azygos and hemiazygos respectively. These veins by linking together the superior and inferior venae cavae form important anastomosing channels.

The azygos vein begins in the abdomen approximately where the renal vein enters the inferior vena cava. Its origin is variable, but most anatomists are of the opinion that it arises from the posterior aspect of the inferior vena cava; others however, have described its origin as being formed by the union of the right ascending lumbar and subcostal veins, whereas still others consider it a branch of the right renal vein. It enters the thorax on the right side of the thoracic duct and descending aorta, passes upwards in front of the vertebral bodies and is overlapped by the right edge of the esophagus. It passes into the thorax through the aortic opening of the diaphragm. At the upper border of the root of the right lung, it emerges from under cover of the esophagus arches forward above the right bronchus and terminates in the superior vena cava. This vein, therefore, has vertical and horizontal portions, and is related to the mediastinal as

pect of the right lung and pleura. Although it has imperfect valves, its tributaries have complete ones. The tributaries are formed by numerous small veins such as the esophageal, pericardial, bronchial and mediastinal, in addition to these, it receives the two hemiazygos veins, the lower eight posterior intercostals (subcostal) of the right side, and the right superior intercostal vein. The latter is the common trunk formed by the union of the veins from the second and third intercostal spaces.

The hemiazygos vein (vena azygos minor inferior) begins in the left ascending lumbar or renal vein. It enters the thorax through the left crus of the diaphragm, ascending on the left side of the vertebral column as high as the ninth thoracic vertebra where it passes across the column and behind the aorta, esophagus and thoracic duct to end in the azygos vein. In its course it crosses 3 or 4 of the lower left intercostal arteries and is covered by the pleura. It receives the lower 4 or 5 left intercostal veins, at times the lower end of the accessory hemiazygos, the small left mediastinal and the lower left esophageal veins.

The accessory hemiazygos vein (vena azygos minor superior) varies much in size, position and arrangement since it is often continuous with or drained by the left superior intercostal vein. It varies inversely, therefore, in size with the left superior intercostal. It descends on the left side of the vertebral column and receives veins from the three or four intercostal spaces between the superior left intercostal and the highest




FIG 243 Thoracic duct (A) adult duct, (B) and (C) embryology of the thoracic duct

The Thoracic Duct

EMBRYOLOGY

In the fetus the thoracic ducts are a pair of vessels which ascend through the posterior mediastinum on each side of the descending thoracic aorta (Figs 243B and 243C). They continue through the superior mediastinum on each side of the esophagus, to the root of the neck where each arches laterally, immediately behind the carotid sheath, and opens into the angle between the subclavian and internal jugular veins. Because of pressure from the aorta, the left duct atrophies; the right persists, crosses to the left side and empties into the left subclavian vein. The disappearance and persistence of the ducts is subject to great variation, so that any arrangement of anastomoses may result.

THE ADULT DUCT

The adult duct (Fig 243A) is approximately the same length as the spinal cord, about 18 inches. It begins in the abdomen at the upper end of the *cisterna chyli*, which is an elongated sac placed under the right crus of the diaphragm. Three major lymph trunks drain into the cisterna: the right and left lumbar and the intestinal. The 2 lumbar trunks are short vessels which convey the lymph from the lower limbs, pelvis (viscera included), kidneys, suprarenals and deep lymphatics of the abdominal walls. The left lumbar trunk reaches the cisterna by passing behind the aorta. The intestinal trunk carries lymph from the stomach, spleen, most of the liver and the intestines. The thoracic duct has abdominal, thoracic and cervical parts. The abdominal part leaves

the cisterna, passes to the aortic orifice of the diaphragm, and, with the vena azygos on its right, enters the thorax. In the thorax, it passes up in the posterior mediastinum with the azygos vein on the right and the aorta on the left. Behind it are the vertebrae, the right intercostal vessels, the hemiazygos and accessory hemiazygos veins. In front are the diaphragm, the esophagus and the pericardium. At the level of the seventh thoracic vertebra, the duct begins to cross obliquely to the left until it reaches the left side of the body about at the level of the fifth thoracic vertebra. It then continues up along the left border of the esophagus, medial to the pleura and behind the left subclavian artery into the neck. The cervical part forms an arch which reaches as high as the seventh cervical vertebra; it arches behind the carotid system (internal jugular vein, vagus nerve and common carotid artery). As it travels to the left, it crosses the scalenus anterior muscle, phrenic nerve and transverse scapular vessels. The so-called vertebral system (vertebral artery, vein and sympathetic trunk) lies behind it. The duct ends medially, usually as a single vessel which enters the junction of the left internal jugular and subclavian veins; this opening is guarded by valves which prevent the regurgitation of blood. It sometimes divides into two but these usually re-form into a single duct again. This is important to recognize in wounds of the neck. In its course the duct returns lymph from both lower limbs, the abdomen (except the upper surface of the right lobe of the liver), the left side of the thorax, the left side of the head and neck, and the left upper limb.

21

The Sympathetic Chain

The ganglionated sympathetic chain is the most lateral structure in the posterior mediastinum. It is covered by costal pleura and lies upon the heads of the ribs. The thoracic

part of this chain has 10 or 11 ganglia, the first of which may be fused with the inferior cervical ganglion (115, 169). These ganglia connect with thoracic spinal nerves via rami




FIG 244 Thoracic sympathectomy (posterior approach)

The right lymph duct is a short vessel, about an inch long which passes down on the scalenus anterior muscle and enters the junction of the right internal jugular and the subclavian veins. It is formed by the union of the right jugular, subclavian and

bronchomediastinal trunks, these, however, may open separately. The right duct returns lymph from the upper surface of the right lobe of the liver, from the right lung and the pleura, and also from the right side of the heart.

SECTION FOUR

THE ABDOMEN

communicantes Aortic and pulmonary sympathetic plexuses as well as splanchnic trunks are derived from this chain

SURGICAL CONSIDERATIONS

THORACIC SYMPATHECTOMY

Thoracic sympathectomy is frequently helpful in dealing with causalgia, painful posttraumatic arthritis painful amputation stump and the phenomenon of phantom limb In these conditions the upper thoracic ganglia can be temporarily blocked with procaine and the effect recorded When pain recurs within a few hours after such injections the sympathetic connections should be permanently destroyed It is best to employ the preganglionic type of sympathectomy as the effect of this operation is believed to be due to the elimination of vasomotor impulses and not to interruption of sensory fibers The physiologic reasons for this have been well described by White and Smithwick Sympathectomy as a form

of treatment for hypertension has been discussed elsewhere (p 618)

Whether it is desired to resect the upper thoracic sympathetic ganglia or to sever their central connections, the exposure is the same (Fig 244) The patient is placed on the operating table face down, with several pillows under the chest The incision is made 5 cm lateral and parallel with the spinous processes, it is 10 cm in length and centered over the ribs to be resected The trapezius rhomboid minor and major, and serratus posterior superior muscles are divided The lateral border of the erector spinae and overlying muscles are retracted This exposes the rib and the transverse process to be resected The rib is separated from the intercostal muscles and the underlying pleura and is cut off 4 cm lateral to its articulation The pleura is stripped away and the sympathetic chain located It is best to divide the trunk below the third thoracic ganglion first and then work upward, freeing it from the sides of the vertebrae and cutting its ram

Abdominal Walls

ANTERIOR ABDOMINAL WALL

BOUNDARIES

The anterior abdominal wall is bounded above by the costal margins and the xiphoid process of the sternum only the costal cartilages of ribs seven eight nine and ten take part in this boundary for the eleventh and the twelfth ribs do not reach the margin. It is bounded below and on each side by the portion of the iliac crest lying between the iliac tubercle and the anterior superior iliac spine by the inguinal ligament the pubic crests and the upper end of the pubic symphysis. The xiphoid process lies at the bottom of the depression between the two seventh costal cartilages, and its edges and tip afford attachment for the aponeurosis of the transversus abdominis muscle. Since it is painful and at times difficult to palpate the xiphoid the lower end of the body of the sternum serves as a preferable landmark.

SURFACE ANATOMY

The lines of tension of the abdominal skin are nearly transverse therefore, vertical scars tend to stretch but transverse incisions become less conspicuous with time. The skin of the abdomen is loosely attached to the underlying structures except at the umbilicus where it is normally firmly adherent. The *linea alba* extends in the midline from the xiphoid to the symphysis pubis it is divided by the umbilicus into a supra umbilical portion which is a band about a half inch wide and an infra umbilical part, which is so narrow that the recti almost touch. This is important surgically since a midline incision placed above the umbilicus comes

directly onto this broad band, but in an infra umbilical midline incision it is difficult to find the threadlike midline. The *linea alba* is a fibrous raphe formed by the decussation of the three lateral abdominal muscles since it contains few or no blood vessels, it can be incised with very little bleeding.

Clinically the anterolateral abdominal wall has been divided into nine regions created by two horizontal and two vertical lines (Fig 245). The two horizontal lines are constructed in the following way the upper line is placed at the level of the ninth costal cartilages and the lower at the top of the iliac crests. The two vertical lines extend upward from the middle of the inguinal (Poupart's) ligament to the cartilage of the eighth rib. The nine regions thus constructed are three upper regions—left hypochondriac epigastric and right hypochondriac three middle regions—left lumbar umbilical and right lumbar, three lower regions—left iliac hypogastric and right iliac. Identifying the regions in this way aids in the description and the location of the viscera and abdominal masses.

The *umbilicus* or navel is located in the *linea alba* a little nearer the symphysis than the xiphoid. Usually its level is between the disks of the third and the fourth lumbar vertebrae but since it may vary in position it is not too reliable a landmark. It is a puckered scar which marks the site of the umbilical cord through which four tubes passed in fetal life they are the urachus the right and the left umbilical arteries and the left umbilical vein (Fig 273). They are situated in the peritoneal fat layer




FIG 246 The superficial nerve distribution of the anterolateral abdominal wall




FIG 247 Distribution and attachments of Scarpa's fascia

of the anterior abdominal wall and produce peritoneal folds. When the peritoneal aspect is studied in the adult these four tubes are present as four atrophic fibrous cords. In the embryo a structure called the vitello intestinal duct is present, this connects the

and the discharge of bile and pus and may be the location of new growths such as papillomas or meta-stases from gastro-intestinal carcinomas. The well known but infrequently seen caput medusae is located in this region and is the result of the communica-




FIG. 245 The nine regions of the anterolateral abdominal wall

small bowel with the umbilicus. If this structure is not obliterated at the time of birth, feces will discharge at the umbilicus. If the urachus is not completely obliterated at birth, urine will be noted at the same site. The hypogastric arteries of the fetus become the obliterated hypogastric arteries of the adult and pass over the lower abdominal wall as they proceed from the internal iliac arteries to the umbilicus. They may remain open and supply superior vesical branches to the urinary bladder. The umbilical vein becomes the round ligament or ligamentum teres of the liver. The physiologic communication between the peritoneal cavity and the umbilical cord may persist, resulting in umbilical hernias (p. 396). The umbilicus may be the site for the collection

between the portal and the systemic circulations when the former is impaired.

The rectus abdominis muscle (p. 369) stands out on each side of the median line in the well-developed individual and forms a longitudinal prominence which is broader above than below. Its lateral margin, which is slightly convex, is indicated by a groove on the skin known as the *linea semilunaris*. This line extends from the pubic tubercle to the costal margin of the ninth costal cartilage.

NERVES AND SUPERFICIAL FASCIA

The skin of the anterior abdominal wall is supplied by the lower six thoracic and first lumbar nerves (Fig. 246). The lower six thoracic nerves give off anterior and lat-

Tobin and Benjamin are of the opinion that the subcutaneous tissue is made up of only one layer and that the concept of an outer fatty and inner membranous layer is not justified.

nerves are derived from the superior and the inferior epigastric vessels. In addition to these three small branches of the femoral artery are found in the superficial fascia of the groin. They are the superficial ex-




FIG 249 The rectus abdominis muscle (A) The anterior layer of the rectus sheath has been partially removed on the left and the lower end of the cut rectus muscle is retracted upward; this exposes the posterior layer of the sheath (B) The origin and the insertion of the muscle

ARTERIES, VEINS, AND LYMPHATICS

The *superficial arteries* accompany the cutaneous nerves; those which accompany the lateral cutaneous nerves are branches of the posterior intercostal arteries, while those which travel with the anterior cutaneous

tertiary pudendal, the superficial epigastric and the superficial circumflex iliac arteries (p. 380).

The *superficial veins* on each side of the anterior abdominal wall are divided into two groups: an upper and a lower. The upper group returns the blood via the lateral tho-

eral branches but the lateral branch of the last thoracic nerve crosses the iliac crest to supply the skin of the buttocks. The first lumbar nerve becomes the *iliohypogastric nerve*, which pierces the external oblique

known as *Camper's fascia* and (2) a deeper membranous layer called *Scarpa's fascia*, which is in contact with the deep fascia. The superficial layer contains small blood vessels and nerves, and it is this fatty con-




FIG. 248 The superficial veins and lymphatics of the anterolateral abdominal wall

aponeurosis about one inch above the superficial inguinal ring, and the *ilio inguinal nerve*, which passes directly through the superficial inguinal ring. The level of the umbilicus marks the tenth thoracic nerve.

The *superficial fascia* appears as a single layer in the upper part of the anterior abdominal wall, but in the lower region especially between the umbilicus and the symphysis pubis, it is easily divided into two distinct layers. (1) a superficial layer of superficial fascia, which is a fatty stratum

nective tissue which gives roundness to the body thus preventing unsightly angularity. The deep layer of superficial fascia is quite devoid of fat and blood vessels and descends on each side in front of the inguinal ligament to blend with the fascia lata of the thigh immediately below and nearly parallel with the ligament (Fig. 247). In the region of the pubic bone it is carried downward over the spermatic cords, the penis and the scrotum into the perineum where it is known as *Colles fascia*.

into supra and infra umbilical groups. The supra umbilical vessels drain into the pectoral lymph glands and the infra umbilical into the superficial inguinal glands (Fig 248)

MUSCLES

In addition to the three lateral flat muscles of the anterior abdominal wall (external and internal obliques and transversus abdominis) there are the recti and the pyramidalis. The three lateral muscles have been discussed elsewhere (p 380)

The *rectus abdominis muscle* appears as a long broad muscular band which stretches between the pubis and the thorax on each side of the linea alba (Fig 249). It originates by tendinous fibers from the pubic crest and the anterior pubic ligament. As it ascends it widens and becomes thinner. It inserts on the thorax as fleshy muscular fibers. This insertion takes place along the anterior surfaces of the fifth, the sixth and the seventh costal cartilages and the xiphoid process (Fig 249 B). The insertion which is onto the front of the chest can be visualized along a horizontal line that extends from the xiphoid process to the end of the fifth rib; it is approximately three times as broad (three inches) as the origin from the front of the symphysis. Its medial border is separated from that of its fellow by the linea alba. Below the umbilicus, where the linea alba is a fine line, the two recti are practically in contact with each other but above the umbilicus they are about a half inch apart. The anterior surface of the muscle is crossed by three tendinous intersections: one at the costal margin, one at the umbilicus and one between these two. A fourth may be present below the umbilicus but it is not constant. The muscle is adherent to the anterior wall of the rectus sheath where these intersections appear, but since they do not penetrate the entire muscular depth the rectus is nowhere adherent posteriorly. By this arrangement a long muscle is divided into a number of shorter ones, thus increasing its strength and efficiency.

The actions of the recti are shared with the abdominal oblique and the transversus. The 6 muscles act as efficient protectors of the abdominal viscera, and by their tonicity they maintain intra abdominal pressure and help keep the viscera in place. They are also muscles of respiration, since their contraction causes them to press upon the abdominal viscera forcing them upward and thus elevating the diaphragm. They also play a part in defecation, since their contraction increases intra abdominal pressure and helps the rectum to evacuate its contents. The rectus is a flexor of the vertebral column, pulling the thorax downward toward the symphysis; in this action its antagonist is the sacrospinalis. The rectus receives its nerve supply from the lower six intercostal nerves.

The *rectus sheath* may be divided into three parts, each having a different construction: (1) above the costal margin, (2) from the rib margin to midway between the umbilicus and the pubis and (3) from midway between the umbilicus and pubis to the pubis (Fig 250).

1 Above the rib margin. This part of the sheath is incomplete. The anterior wall is made up of the aponeurosis of the external oblique, since this is the only one of the lateral abdominal muscles which extends above the costal margin. The posterior wall is absent and as a result of this the rectus muscle lies directly on the cartilages.

2 From the rib margin down to midway between the umbilicus and pubis. This part of the sheath is complete. The internal oblique aponeurosis divides at the lateral border of the rectus muscle into an anterior layer and a posterior layer. The anterior wall of the sheath consists of the aponeurosis of the external oblique plus the anterior layer of the aponeurosis of the internal oblique. The posterior wall consists of the posterior layer of aponeurosis of the internal oblique, the aponeurosis of the transversus abdominis and the transversalis fascia. The transversus where it extends behind the rec

racic and the internal mammary veins to the superior vena cava the lower group returns its blood via the femoral vein to the inferior vena cava. Both groups anastomose freely through the thoraco epigastric vein, the superficial veins may dilate and compensate for an obstruction of either the supe-

rior or the inferior vena cava or for an obstruction of the external or the common iliac veins. The para umbilical veins communicate with both of these groups and constitute an important connection between the portal and the systemic venous system.

The superficial lymph vessels are divided




FIG. 250 The rectus sheath. Above the rib margin the anterior wall of the sheath is made up of the aponeurosis of the external abdominal oblique muscle; the posterior wall is absent, since the rectus muscle lies directly on cartilage. From the rib margin to midway between the umbilicus and the pubis the anterior wall of the sheath consists of the aponeurosis of the external oblique plus the anterior layer of the aponeurosis of the internal oblique; the posterior wall consists of the posterior layer of the aponeurosis of the internal oblique, the aponeurosis of the transversus abdominis muscle and the transversalis fascia. From midway between the umbilicus and the pubis to the pubis the anterior wall is formed by the aponeuroses of the external and the internal obliques and the transversus, the posterior wall is formed by the transversalis fascia.




FIG 252 The paramedian incision. This incision may be made in the upper or the lower abdomen and either on the right or the left side. (A) The incision in longitudinal section with the medial border of the right rectus muscle retracted laterally. (B) Cross section, showing the repair on the left side.

tus, is muscular almost to the midline. Where the posterior sheath ends, midway between the umbilicus and the pubis, an arched lower border which is called the *linea semicircularis* (Douglas), is formed

formed by the transversalis fascia (p. 359).

The contents of the rectus sheath are (1) the rectus and the pyramidalis muscles, (2) the superior and the inferior epigastric vessels, (3) the termination of the lower five




FIG. 251. Abdominal incisions. The incisions most commonly used are the rectus, the oblique, the vertical and the transverse. Examples of each are depicted in the illustration.

(Fig. 249 A) This line is an important dividing point since cephalad to it the internal oblique aponeurosis splits into its two leaves but below this point no such division takes place. The inferior epigastric artery enters the sheath by crossing this edge.

3. From midway between the umbilicus and the pubis to the pubis. The anterior wall is formed by the aponeuroses of the external and the internal obliqui and the transversus; here all the aponeuroses pass in front of the rectus. The transversus and the internal oblique are fused but the external oblique does not fuse until it nearly reaches the midline. The posterior wall is

intercostals and the twelfth thoracic nerves with their accompanying vessels.

The nerves enter the sheath by piercing the posterior wall near the lateral margin and then run for a short distance between the posterior sheath and the rectus before entering the muscle proper.

The superior epigastric artery enters the rectus sheath behind the seventh costal cartilage and anastomoses with the inferior epigastric artery, which enters in front of the arcuate line. In this way, the vessels of the upper and the lower limbs are brought into communication. Their branches are cutaneous, muscular and anastomotic.




FIG 252 The paramedian incision. This incision may be made in the upper or the lower abdomen and either on the right or the left side. (A) The incision in longitudinal section with the medial border of the right rectus muscle retracted laterally. (B) Cross section, showing the repair on the left side.

The *pyramidalis muscle* is a triangular muscle which lies in front of the rectus, it is frequently absent. It arises from the front of the pubis and is inserted into the lower part of the linea alba between the rectus and the anterior wall of its sheath. It is supplied by the last thoracic nerve and acts as a tensor of the linea alba.

SURGICAL CONSIDERATIONS

ABDOMINAL INCISIONS

Numerous abdominal incisions have been described but only those which are commonly used will be discussed. They may conveniently be divided in the following way (Fig 251)

- 1 Rectus
 - A Paramedian
 - B Pararectus
 - C Transrectus (muscle splitting)
- 2 Oblique
 - A McBurney
 - B Kocher's subcostal
 - C Iliac
- 3 Vertical Midline
 - 1 Above the umbilicus
 - 2 Below the umbilicus
- 4 Transverse
 - A Epigastric
 - B Pfannenstiel

Rectus Incisions Incisions through the rectus sheath and muscle may be used either above or below the umbilicus.

The *paramedian incision* is made about an inch to the right or the left of the midline (Fig 252). The skin and the fascia are divided to the rectus sheath; the opening of the sheath exposes the rectus muscle. The medial border of the rectus is retracted laterally, exposing the posterior rectus sheath and the peritoneum; these are divided in the same line as the skin. The wound is sutured in three layers, namely (1) the peritoneum and the posterior rectus sheath (2) the anterior rectus sheath and (3) the skin. The muscle returns of its own accord (trap door action) over the posterior suture line. In

jury to vessels and nerves is minimal, and the exposure of pelvic structures is excellent.

The *pararectus incision* is similar to the paramedian, except that the approach to the abdominal cavity is along the lateral border instead of the medial border of the rectus muscle (Fig 253). This incision has the disadvantage of encroaching upon the nerves which enter and supply the rectus muscle laterally. The closure is accomplished in three layers as described above. If the incision must be enlarged downward toward the pubis, the deep epigastric vessels may be encountered. Should this be the case the artery and its two accompanying veins can be ligated and divided.

A *transrectus (muscle splitting) incision* is performed in the same manner as the other two rectus incisions but differs in that the muscle is divided longitudinally through its medial third. The medial third is chosen in order to minimize injury to the nerve fibers. The muscle is divided in the line of its fibers; the tendinous inscriptions are clamped and ligated and the posterior sheath and the peritoneum are incised. The incision is closed in layers.

Oblique Incisions Oblique incisions have been utilized, especially in surgery upon the appendix and the gallbladder.

The *McBurney incision* (Fig 254) is an oblique muscle splitting incision which passes through the lateral abdominal musculature and is supposed to minimize postoperative weakness of the abdominal wall by incising the individual muscles in the direction of their fibers. The level and the length of this incision will vary according to the position of the appendix and the size of the patient. In a general way however, it may be stated that it is made at the junction of the middle and the outer thirds and at right angles to an imaginary line joining the anterior superior iliac spine with the umbilicus. One third of the incision is placed above this line and two thirds below it. The incision is usually about three inches long. The skin is incised in the direction of the fibers of the external abdominal oblique,

this incision is carried through the superficial fascia until the fibers of the external oblique aponeurosis are seen. The latter is divided and retracted from the underlying

internal oblique. A distinct cleavage plane exists between these two muscles. The freed edges of the external oblique aponeurosis are retracted, and the horizontal fibers of




FIG 253 The pararectus incision. (A) The eleventh and the twelfth intercostal nerves are shown passing along, the retracted lateral border of the rectus muscle. (B) Cross section showing the lateral border of the rectus muscle retracted medially.




FIG 254 The McBurney incision (A) The skin incision is placed at the junction of the outer and middle thirds of a trisected line extending from the umbilicus to the anterior superior iliac spine the aponeurosis of the external abdominal oblique muscle is incised in the line of its fibers (B) The internal oblique and the transversus abdominis muscles are incised (C) The peritoneum is incised, and the cecum is exposed

the internal oblique muscle are exposed. The transversus abdominis muscle and the internal oblique have fibers which run in almost the same direction in this area; the cleavage between the two muscles is not too distinct. As soon as the transversalis fascia is exposed it is incised in the direction of the internal oblique opening. This exposes the preperitoneal fat and the peritoneum; these are incised. Various methods of enlarging the incision have been described, but since these do not adhere to the McBurney or grid-iron principle and since they encroach upon the weak semilunar lines such descriptions have been avoided intentionally. Usually this incision is closed in three layers: the first including the peritoneum and transversalis fascia; the second the aponeurosis of the external oblique; and the third closes the skin. Some surgeons prefer to put a few approximating sutures in the internal oblique and transversus muscles.

The *Kocher's subcostal incision* is used for operations on the biliary tract, but a similar incision may be placed on the left side for operations upon the spleen or the cardiac end of the stomach. The incision is made parallel with and about one inch from the costal margin; it commences at the base of the xiphoid and is carried into the flank as far as is deemed necessary. The rectus muscle and the external abdominal oblique are divided. The posterior rectus sheath and the internal oblique are exposed and are divided in the line of the incision; the peritoneal cavity is entered. The incision is closed in layers.

The *iliac incision* is utilized in exposure of the ureter or the larger pelvic vessels. It is made parallel with and directly in front of the anterior portion of the iliac crest; it aims to reach the extraperitoneal structures below the brim of the pelvis. It is carried directly through the musculature and the transversalis fascia. The peritoneum is not opened but is mobilized and retracted medially. The necessary procedures are carried out extraperitoneally.

Vertical Incisions The *midline incision*

above the umbilicus is made directly in the linea alba, which can be located easily by the depression or pigmentation present. It begins just below the xiphoid cartilage, extends to the umbilicus and is usually four to five inches long. The skin and the superficial fascia are incised to the aponeurosis. The advantages of this incision are that it is almost bloodless, no muscle fibers are encountered, no nerves are injured, and it gives access to both sides of the abdomen. However, it has a disadvantage in that only one layer is available for repair because of the fusion of the aponeuroses in the midline; therefore it cannot be relied upon and may result in weakness and herniation.

The *midline incision below the umbilicus* is employed almost routinely in gynecologic operations. Since the recti below the umbilicus are so close together and because the linea alba is only a fine line, the right or the left rectus sheath is routinely entered and the muscle is retracted laterally. Because of this, it is not exactly in the midline and the repair is made in layers. Such a repair will result in a strong abdominal wall and does not have the disadvantage of weakness that a midline incision above the umbilicus would have.

Transverse Incisions Transverse abdominal incisions give excellent exposure but entail more time in execution and repair. They result in nicer looking scars and produce less injury to the nerves and the blood vessels, since they run parallel to them.

The *transverse epigastric incision* extends from the lateral edge of one rectus to the lateral edge of the other. The underlying anterior rectus sheath, the rectus muscles, the posterior rectus sheath and the peritoneum are divided transversely on each side. If further exposure is required the incision may be extended laterally beyond the lateral edge of the recti by splitting the oblique muscles. The individual layers of the abdominal wall are sutured separately, but it is to be recalled that only one fused layer is found in the region of the linea alba. This same incision has been modified by

Sanders, who utilizes lateral retraction of the recti rather than division of these muscles

The *Pfannenstiel incision* is a suprapubic transverse incision which is placed at or in the upper pubic hair line and in this way

exposed recti are freed from the underlying transversalis fascia and are then retracted laterally. The transversalis fascia, the preperitoneal fat and the peritoneum are incised longitudinally. In closing the wound,




FIG 255 The Pfannenstiel incision. (A) The skin and the anterior layer of the rectus sheath have been divided transversely. (B) The recti are drawn laterally, and the transversalis fascia, the preperitoneal fat and the peritoneum (the only structure labeled) are incised vertically.

becomes concealed (Fig 255). The skin, the subcutaneous tissue and the right and the left anterior rectus sheaths are divided transversely. The cut edges of the sheaths are dissected upward and downward for a short distance; this exposes the recti and the pyramidalis when the latter is present. The

the layers are sutured separately in the line of their division.

INCISIONAL HERNIAS

Cattell has described a method which results in a five layer repair in which the various components of the abdominal wall




FIG 256 Repair of incisional hernia. This method results in a five layer repair (Cattell). (A) Excision of old scar by means of an elliptical incision. (B) Identification and freeing of sac. (C) The sac has been opened and the first suture line placed which includes the hernial ring and the inner surface of peritoneum. All but an inch of redundant sac is removed. This constitutes suture layer number two. (D) and (E) show the utilization of the rectus sheath and muscle in layers three, four and five.

are not separated at the hernial ring. It has the advantage that no dissection is carried out at a point where it is most difficult to identify the layers, and its repair results in great strength at the point of greatest potential weakness (Fig 256).

The old scar is excised by an elliptical incision and the sac which usually lies immediately subcutaneous is identified, this is freed down to the hernial ring. The fascia

is exposed. The sac is opened and the contents are freed carefully and reduced, frequently, resection of the omentum is necessary. The first suture line includes the hernial ring and the inner side of the peritoneum. By everting the peritoneum, a smooth peritoneal surface remains in the peritoneal cavity. The redundant part of the sac is re-ected, but about one inch is left, this constitutes the second layer of




FIG 257 The nine layers which make up the anterolateral abdominal wall




FIG 258 The inguino abdominal region. On the right side the superficial vessels and nerves are shown and on the left the deeper structures (musculature) are depicted in their relations to the inguinal canal

repair. An elliptical incision then is placed through the rectus sheath fascia. This extends to the muscle. The fascial flaps are dissected free on either side and a third layer of sutures is placed. The sutures approximate the inner side of the two edges of cut fascia thereby covering the peritoneal suture line. Suture line number four approximate the muscles and number five the lateral edges of the incised fascial flaps. The skin then is approximated.

INGUINAL REGION

The Nine Abdominal Layers. This region has been called the inguino abdominal region and the inguinal triangle the trigone being bounded by the inguinal ligament, the lateral margin of the rectus muscle and a

horizontal line drawn from the anterior superior iliac spine to the rectus margin. Nine abdominal layers make up this region. The layers appear and are discussed in the following order (Fig 257).

- 1 Skin
- 2 Superficial fascia (Camper's layer)
- 3 Superficial fascia (Scarpa's layer)
- 4 External oblique muscle
- 5 Internal oblique muscle
- 6 Transversus abdominis muscle
- 7 Transversalis fascia
- 8 Properitoneal fat
- 9 Peritoneum

The skin of this region is smooth and movable and presents three particular landmarks for surface anatomy. They are the anterior superior iliac spine, which is readily




FIG 259 The external abdominal oblique muscle

palpable the pubic tubercle which is less easily palpated especially in the obese the umbilicus

The *superficial fascia* is divided into two layers a superficial layer of superficial fascia and a deep layer of superficial fascia. The superficial layer is known as *Camper's fascia*, and the deep layer as *Scarpa's fascia*. They usually are separable below the um-

bilicus but are fused above this point (Fig 257)

Camper's fascia is the fatty layer which is continuous with the adipose tissue covering the body generally. It is also called the *panniculus adiposus*, its thickness depending upon the amount of fat present, the cutaneous vessels and nerves run in this layer (Fig 258). The arteries found here are derived from the femoral artery and ascend from the thigh. They are the superficial epigastric which bisects the inguinal ligament and runs toward the navel, the superficial external pudendal, which runs medially across the spermatic cord and supplies the scrotum, the superficial circumflex iliac artery, which passes laterally below the inguinal ligament.

Scarpa's fascia is the membranous layer of superficial fascia. It contains no fat. The attachments of this fascia are clinically important because it is under this layer that extravasations of urine and blood take place. *Scarpa's fascia* passes over the inguinal ligament and attaches to the deep fascia of the thigh (*fascia lata*). This attachment takes place about a finger's breadth below and parallel with the inguinal ligament (Fig 247). Medially, it attaches along a line that passes with, but lateral to, the spermatic cord, this line extends from the pubic tubercle to the pubic arch. The fixation occurs lateral to the pubic tubercle. Urine, blood or an exploring finger cannot extend beyond this attachment. Medial to the tubercle, *Scarpa's fascia* does not attach but continues over the penis and the scrotum, it continues as *Colles' fascia* which covers the superficial compartment of the perineum.

The *external abdominal oblique muscle* arises from the lower eight ribs (5 to 12). Its fibers are directed downward, forward and medial (Fig 259). It interdigitates with the serratus anterior above, a continuous sheet of fascia covers both muscles. The most posterior fibers run vertically downward and insert into the anterior half of the iliac crest. Between the last rib and the iliac crest a free border forms the lateral




FIG 260 The ligaments in the inguinal region (A) Poupart's ligament and its relations to Cooper's ligament and the lacunar ligaments (B) The reflected inguinal ligament. The aponeurosis of the external oblique has been reflected laterally.

boundary of the lumbar (Petit's) triangle (p 400). The muscle fibers become tendinous below the line joining the anterior superior iliac spine to the umbilicus. From the anterior superior iliac spine to the pubic spine the aponeurosis forms a free border which is called the inguinal (Poupart's) ligament, under which vessels, nerves, and muscles pass from the abdomen to the thigh.

The external oblique aponeurosis forms the inguinal, the lacunar, Cooper's, and the reflected inguinal ligaments (Figs 260 and 261).

The inguinal ligament (Poupart's) is a tendinous part of the external oblique aponeurosis which extends from the anterior superior iliac spine to the pubic tubercle. The muscles which lie below it are the iliac,




FIG 261 Posterior view of the inguino abdominal and inguino-femoral regions. The peritoneum and the transversalis fascia have been removed




FIG 262 The superficial inguinal 'ring'. The external oblique aponeurosis has been severed and retracted, but the 'ring' remains intact

the pons major and the pectineus. The ligament folds back on itself, forming a groove. The lateral half of this is not seen because it is obscured by the origin of the internal oblique and transversus muscles. The medial half however forms the gutter-like floor of the inguinal canal.

The *lacunar ligament* (Gimbernat's) is that part of the inguinal ligament which is reflected downward, backward and lateral. It attaches to the pectineal line and its free crescentic margin forms the medial boundary of the femoral ring. It is the pectineal part of the inguinal ligament.

Cooper's ligament is the lateral continuation of the lacunar ligament. It extends from the base of the lacunar ligament laterally along the pectineal line to which it is attached.

The *reflected inguinal ligament* (triangular ligament) consists of reflected fibers which take their origin from the inferior crus of the superficial inguinal ring and the lacunar ligament (Fig 260B). They pass medially behind the spermatic cord and continue medially between the superior crus of the superficial inguinal ring and the conjoined tendon. They insert into the linea alba. Because of its triangular shape this ligament has been called the triangular fascia.

The *superficial inguinal ring* (subcutaneous inguinal ring, external abdominal ring) (Fig 262) has had the term 'ring' unfortunately applied to it. In reality it is a triangular thinned out part of the aponeurosis of the external oblique muscle through which the spermatic cord in the male and the round ligament in the female pass. The apex of the triangle lies lateral to the pubic tubercle; its base, formed by the lateral half of the pubic crest, lies medial to the tubercle. The two sides are called the crura. The inferior crus (external pillar) is the medial end of the inguinal ligament, it attaches to the pubic tubercle. The superior crus (internal pillar) is that part of the aponeurosis which attaches to the pubic crest and the symphysis. The 'ring' is not

an open defect since it is covered by the intercrural (intercolumnar) fibers which pass from one crus to the other. As the testicle made its descent, it encountered these intercrural fibers at the external 'ring'. The fibers were pushed ahead by the descending testicle and formed a covering for the cord which is known as the external spermatic fascia.

The *internal abdominal oblique muscle* (Fig 263) lies between the external oblique and the transversus abdominis muscles. This fan shaped muscle has a narrow origin and a broad insertion. It originates from the outer half of the inguinal ligament, from the intermediate line on the iliac crest and from the posterior lamella of the lumbo-dorsal fascia through which it gains attachment to the lumbar spines. Because of this last fact, the muscle has no free posterior border.

The uppermost fibers run almost vertically upward and are inserted into the lower four ribs and their cartilages. The intermediate fibers form an aponeurosis which divides above the semicircular line (of Douglas) into two lamellae at the lateral border of the rectus muscle (Fig 249). The anterior lamella accompanies the external oblique aponeurosis to form the anterior rectus sheath, and the posterior lamella accompanies the aponeurosis of the transversus abdominis to form the posterior rectus sheath. Below the semicircular line the combined aponeuroses of all three lateral abdominal muscles fuse and pass in front of the rectus muscle as the anterior rectus sheath.

Those fibers which originate from the inguinal ligament arch above the spermatic cord in the male and the round ligament in the female and become tendinous. They insert conjointly with those of the transversus abdominis into the crest of the pubis. It is this fusion of the tendinous portions of the internal oblique and transversus muscles that results in the structure known as the *conjoined tendon* (inguinal aponeurotic fold). In recent publications however Zieglman, Zimmerman, Anson, McVay and




FIG 263 The internal abdominal oblique muscle

been impressed with the rarity with which the conjoined tendon can be demonstrated at the operating table. If the observations are correct, then the conjoined tendon plays an unimportant role in the etiology of inguinal hernia and a still less important role in the cure of this condition. It should be emphasized that although the fibers of the internal oblique arch over the spermatic cord, they insert behind it.

The *transversus abdominis* (*transversalis*) muscle (Fig 264) is the deepest of the three lateral abdominal muscles. Only a little areolar tissue exists between it and the internal oblique muscle. It arises from the outer third of the inguinal ligament from the inner lip of the iliac crest, from the middle layer of the lumbodorsal fascia and from the inner surface of the lower six costal cartilages where it interdigitates with the fleshy slips of the diaphragm. It is inserted into the linea alba and through the conjoined tendon into the pubic crest. Its aponeurosis passes behind the rectus muscle to the level of the linea semicircularis but from this level downward it passes in front of that muscle. Most of the fibers pass in a horizontal direction hence, its name transversus.

Since the internal oblique originates from the lateral half of the inguinal ligament and the transversus abdominis originates from the lateral third of the ligament, the testicle in its descent misses the transversus fibers but comes in contact with the internal oblique fibers, dragging some of the latter downward. These form muscle loops along the spermatic cord which are known as the *cremaster muscle*. The action of this muscle is to draw the testicles upward.

The nerves in this region are found in the interval between the internal oblique and the transversus abdominis muscles and then enter the rectus sheath (Fig 249). The seventh and the eighth thoracic nerves pierce the posterior lamella of the internal oblique aponeurosis at the costal margin and then pass upward and medially. The ninth nerve passes medially and slightly downward.

Blake have emphasized the numerous structural variations present in this region. In twenty cadavers Zieman could find only two in which the conjoined tendon appeared as a definite structure. The author also has

The tenth, the eleventh and the twelfth nerves take a more downward course as they travel medially. The last four nerves pierce the posterior layer of the internal oblique aponeurosis at the lateral edge of the rectus sheath, continue medially behind the rectus muscle and then pierce its substance. All the *e* nerves supply the three lateral muscles as well as the rectus abdominis. They finally pass through the anterior rectus sheath and end by supplying the overlying skin.

The three flat abdominal muscles form an elastic muscular corset which helps to maintain intra-abdominal pressure. This is of importance in retaining the viscera in place. By contracting simultaneously with the diaphragm they aid in inspiration, defecation, vomiting, and parturition. By contracting alternately with the diaphragm (as an antagonist) they aid in exhalation. In the inguinal region the *e* muscles form an arcade traversed by the spermatic cord. Grant has used the phrase "inguinal arcade" to describe this. When the inguinal portions of the internal oblique and transversus muscles contract, their arched fleshy fibers become straighter; this results in the lowering of the roof of the arcade and the constriction of the passage. The contraction of the external oblique approximates the anterior wall to the posterior wall and a sphincterlike action results (Fig. 265).

The *transversalis fascia*, also called the endo-abdominal fascia, is a connective tissue layer which covers the entire internal surface of the abdomen. This fascia covers certain muscles and in each case assumes the name of the muscle which it accompanies, such as the diaphragmatic fascia, the iliac fascia, etc. Its thickness is variable, but that part which is below the inferior margins of the internal oblique and transversus abdominis muscles usually is well developed. It is in this unprotected area that it forms the floor of Hesselbach's triangle and when torn or weakened predisposes to the development of a direct inguinal hernia. The fascia lies between the transversus abdomi-




FIG. 264 The transversus abdominis muscle




FIG 265 The inguinal arcade Grant has used this phrase to describe the muscular arcade traversed by the spermatic cord. Note the lowering of the roof of this arcade when the transversus abdominis and the internal oblique muscles contract.

muscle and the properitoneal fat layer. In certain areas, especially in those people where the fat layer is wanting, a fusion may result between the transversalis fascia and the peritoneum. In a situation such as this the two layers cannot be separated, and the peritoneal cavity must be entered as if through one layer. This fascia is applied to the posterior surface of the rectus sheath and where the latter terminates at the semicircular line it lies in direct contact with the posterior surface of the rectus muscle. Inferiorly it is attached to the outer half of the inguinal ligament and to the iliac crest where it becomes continuous with the iliac fascia. Over the inner half of the inguinal ligament it covers the femoral vessels upon which it passes behind the ligament and downward into the thigh, forming part of the anterior wall of the femoral sheath. Medial to the femoral vessels it is attached to the pectineal line and the pubic crest.

Anson and Daseler have suggested that the abdominal fasciae in the adult be divided into three layers: an internal layer for the gastrointestinal tract with its vessels and nerves, an intermediate layer for the

urogenital system, the adrenals and their associated vessels and nerves, together with the aorta and the vena cava, and an external layer for the parietal musculature (body wall) with its nerves and vessels. The last mentioned outer stratum is what the majority of modern textbooks refer to as the transversalis fascia. Tobin verified this work and states that these strata are clinically important as surgical guides and as barriers to or pathways for the spread of infection or extravasations of blood or urine.

Descent of the Testicle In the early months of intra uterine life the scrotum is undeveloped, and the testis is located in the abdomen (lumbar region) (Figs 266 and 267). The testicle develops between the transversalis fascia and the peritoneum in the stratum of the properitoneal fat. In the third month of intra uterine life it descends from the loin to the iliac fossa and from the fourth to the seventh month it rests at the site of the internal (abdominal) inguinal ring. During the seventh month it passes through the inguinal canal into the scrotum, preceded by a peritoneal diverticulum called the *processus agnalis* its vessels, nerves and duct are dragged after it. The *gubernaculum testis* is a triangular structure the base of which is attached to the testis, and the apex to the bottom of the scrotum. Some authors have suggested the theory that the testicle passes through the inguinal canal as a result of its being pulled into the scrotum by the contraction (or atrophy) of the musculature of the gubernaculum. The remnants of the gubernaculum become the *scrotal ligament*, this is a short band which connects the inferior pole of the testicle to the bottom of the scrotum. Prior to the descent of the testicle the vaginal process of peritoneum extends into the scrotum. This applies itself to the cord and the testicle, it forms an incomplete covering, but at no point does the processus vaginalis completely surround them. That part of the vaginal process which is applied to the testicle is the *tunica agnalis testis* (vaginal portion) it remains patent

That part of the vaginal process which is applied to the spermatic cord, between the tunica vaginalis testis and the abdominal (deep) inguinal ring, becomes the *funicular process*, it loses its patency and becomes a

fascia) The internal spermatic fascia, therefore, is that evaginated portion of the transversalis fascia which supplies a covering for the spermatic cord. At that point where the testicle meets the transversalis




FIG. 266 The descent of the testicle. (A) Early development in the lumbar region. (B) The testicle at a later stage of development in the lumbar region. It lies between the transversalis fascia and the peritoneum. The vaginal process has formed. (C) At the end of the third month of intra uterine life the testicle reaches the pelvic brim. (D) As the testicle descends in the scrotum the vaginal process becomes differentiated into a funicular portion which is applied to the spermatic cord and a vaginal portion which is applied to the testicle. (E) The testicle has reached the base of the scrotum. Normally the funicular portion becomes obliterated, and the vaginal portion remains patent.

fibrous cord known as the vaginal ligament (p. 390). As the testicle descends it contacts the transversalis fascia; it does not force a hole through it but instead pushes or evaginates this fascia. In this way it acquires a tubular covering called the *internal spermatic fascia* (infundibuliform

fascia) and pushes it forward the internal inguinal ring is formed. Hence the internal ring is a thinned out part of transversalis fascia. As the descent of the testicle continues it passes below the curved border of the internal oblique muscle. It does not come in contact with the transversus ab

thard of it it becomes the Colles fascia of the perineum. Camper's fascia (panniculus adiposus) is a fatty layer and since there is no fat in the scrotum, it is replaced by the dartos muscle. At the ninth month the testicle reaches the scrotum.

subcutaneous (superficial) inguinal ring (p. 383). The *anterior wall* of the canal is formed by the aponeurosis of the external abdominal oblique in its entire length and the fleshy fibers of the internal oblique in the lateral half. The *posterior wall* is




FIG. 268 The types of indirect inguinal hernias

The Inguinal Canal. The fully developed inguinal canal (Fig. 258) is not a canal in the true sense of the word but is a cleft which takes an oblique course through the inguino-abdominal region. In the adult its length is about 4 to 5 cm. The entrance to the canal is through the *abdominal (deep) inguinal ring* which is located a little above the center of the inguinal ligament. The exit is through the

formed by the transversalis fascia in the entire length of the canal and the conjoint tendon in the medial half, the latter structure lies in front of the transversalis fascia and behind the cord. The *roof* is formed by the arched lower border of the internal oblique and to a lesser degree by the transversus abdominis. The *floor* is represented by a groove which is formed by a fusion of the upper grooved surface of the in-

guinal ligament, the lacunar ligament and the transversalis fascia. The cord rests upon this groove.

Types of Indirect Inguinal Hernias (Fig 268) Soon after birth, the *processus*

and the opening above is wide enough, bowel or omentum may enter this process and pass into the scrotum. This condition is known as a *vaginal (congenital) indirect inguinal hernia*. When only the proximal or




FIG 269 The interstitial types of hernias. In these hernias, a part of the *processus vaginalis* is found between the layers of the anterior abdominal wall. The three types are presented.

vaginalis, a peritoneal diverticulum, becomes occluded at two points. First at the internal abdominal ring and second directly above the testis. That part of the vaginal process which is situated between these two points the *funicular process* becomes obliterated. If the vaginal process remains patent throughout its entire course

funicular portion of the vaginal process remains open, a *funicular indirect hernia* results. An *encysted hernia* is the same as a vaginal type plus a process of peritoneum which lies in front of the sac and extends up to the external ring. This is due to the catching of a diverticulum of the *processus vaginalis* at the external ring during




FIG 270 Types of hydroceles

development In the *infantile* type the conditions are exactly the same as are found in the funicular type plus a process of peritoneum which is found in front of the hernia as high as the external ring Therefore at operation a peritoneal sac is found in front of the hernial sac this may be very confusing unless properly identified

The *interstitial* types of hernias are due to a diverticulum of the processus vaginalis which becomes caught between the layers of the developing abdominal wall (Fig 269) These types of hernias are rare and usually are found associated with imperfectly descended testicles The sac may be

1 Proparietal (extraparietal), between the superficial fascia and the external oblique muscle

2 Interparietal (intramuscular), between the internal and the external oblique muscles

3 Retroparietal (intraparietal) between the transversalis fascia and the peritoneum

Types of Hydroceles (Fig 270) In the true hydrocele there is a collection of fluid in some part of the processus vaginalis the types may be vaginal congenital infantile and hydroceles of the cord

The *vaginal* type presents a collection of fluid not due to any fault of development in the tunica vaginalis Since it is acquired it becomes important to determine whether

it is the so-called common 'idiopathic' variety or secondary to some disease of the testis or epididymis such as a malignancy or tuberculosis The *congenital* type is also known as an intermittent hydrocele it is due to a tiny communication between the processus vaginalis and the peritoneal cavity which permits the escape of fluid It may be confused with a congenital hernia In the *infantile* type the processus vaginalis is occluded only at the internal abdominal ring In *hydrocele of the cord* the funicular process fails to shrink to a fibrous cord so that a tubular cavity results This is shut off from the peritoneum above and the tunica vaginalis below As it becomes distended with fluid it forms one or more swellings which are separated from the testicle

SURGICAL CONSIDERATIONS

INGUINAL HERNIAS INDIRECT AND DIRECT

Many methods exist for the repair of an *indirect inguinal hernia* An exhaustive and exhausting literature is accessible to any one interested in special studies of this problem Certain points should be stressed however, in considering herniorrhaphies such as the modern concept of the conjoined tendon (doubting the existence of




FIG 271 The repair of an indirect inguinal hernia (A) The incision extends from a point which joins the middle and the outer thirds of an imaginary line between the antero-superior iliac spine and the umbilicus to the pubic tubercle (B) The cremaster fibers are cut, and the lower border of the internal oblique muscle is freed (C) The internal oblique

(Concluded on facing page)

such a structure), the importance of the transversalis fascia and the management of the sac. A method which emphasizes the points will be described (Fig. 271).

The incision is made from a point which joins the middle and the outer thirds of a line between the anterior superior iliac spine and the umbilicus to a point which marks the pubic tubercle. It is difficult actually to feel this tubercle, since the spermatic cord passes over it; hence the pubic bulge which is produced by the spermatic cord is the landmark used. The incision is deepened through Camper's and Scarpa's fasciae until the aponeurosis of the external abdominal oblique is exposed. The external inguinal ring is identified and the continuation of the external abdominal oblique over this ring, namely the external spermatic fascia, is incised. Then the external oblique aponeurosis is incised and its edges are held apart and dissected free from the underlying internal oblique muscle. The iliohypogastric and ilio-inguinal nerves usually can be demonstrated at this point. The lower border of the internal oblique becomes visible and its continuation the cremaster muscle loops should be elevated. These are severed and the internal oblique freed from the underlying transversalis fascia. The transversus abdominis muscle is not seen because it is not situated this low. A small blunt retractor is placed under the dissected free edge of the internal oblique and this muscle is retracted cephalad. The lateral cut edge of the external oblique aponeurosis is retracted outward thus exposing Poupart's ligament. The finger or a blunt instrument is placed on this ligament and passed downward to the pubic spine. This elevates the spermatic cord which then is retracted laterally. Since the hernial sac is found at

the upper inner quadrant of the cord lateral traction on the cord tenses the transversalis fascia which overlies the sac. It is at this quadrant that the transversalis fascia should be opened. Then the preperitoneal fat layer is identified, it serves as an excellent guide since the peritoneum (sac) lies immediately subjacent to this fat. The transversalis fascia, the preperitoneal fat and the peritoneum, however may be fused into one layer especially in thin individuals so that the sac is entered immediately when an attempt is made to dissect the transversalis fascia. The sac is dissected free from the surrounding structures; it is opened and its contents are reduced. Its neck should be freed as high as possible, which anatomically implies on a level with the deep epigastric vessels. In indirect inguinal hernias these vessels lie medial to the neck of the sac. With downward traction on the sac and upward traction on the internal oblique and the transversalis fascia, a high ligation becomes possible. The sac is transfixed and ligated and the redundant tissue distal to the ligation is cut away. The defect in the transversalis fascia which the surgeon has created must be repaired properly to prevent the development of a direct hernia. This closure is accomplished by means of a purse string suture which incorporates the fascia overlying the spermatic cord. The free edge of transversalis fascia then is sutured to Poupart's ligament. No sutures are placed in the internal oblique muscle since this would interfere with its sphincteric or shutterlike action. The cut edges of the aponeurosis of the external abdominal oblique then are sutured thus reconstructing the roof of the inguinal canal. Scarpa's fascia and the skin are closed as separate layers.

muscle is retracted upward and the transversalis fascia is incised at the upper inner quadrant of the cord. (D) The sac is elevated and opened. (E) The sac has been ligated high, the transversalis fascia is repaired by means of a purse string suture which incorporates the fascia overlying the cord. (F) The free edge of transversalis fascia is sutured to Poupart's ligament. (G) No sutures are placed in the internal oblique muscle. (H) The aponeurosis of the external abdominal oblique is sutured.




FIG 272 Embryology of the umbilical region. The cloaca, a part of the hindgut, separates into a dorsal part (rectum) and a ventral part. The ventral part divides into a cranial part (the urachus), a middle part (the bladder) and a caudal part (the urethra).

Since the underlying cause of a *direct inguinal hernia* is a weakness of or defect in the transversalis fascia, the method of repair becomes the most important feature. The operation is essentially the same as that described for an indirect hernia. When the bulge of the direct hernia has been located the thinned transversalis fascia is opened and the underlying properitoneal fat and the hernial sac are freed. The sac usually is not opened but is reduced by means of a pursestring suture. One attempts to repair the defect in the thin transversalis fascia by means of mattress sutures which imbricate it. The resulting free edge of transversalis fascia then is sutured to Poupart's ligament. If the fascia is too thin and will not hold the sutures a flap of the anterior rectus sheath (internal oblique aponeurosis) is freed and sewed to Poupart's ligament. Numerous modifications, including cutis grafts, wire mesh and fascia lata have been used to strengthen this defect.

Jennings, Anson and Wright have described a method for the repair of indirect inguinal hernias; they utilize a midline in-

cision, retract the rectus muscle and grasp the sac abdominally. The sac is freed from the cord and is ligated high, the abdominal incision is closed. The method has found favor with some surgeons.

UMBILICAL REGION

The umbilical region occupies the central part of the anterolateral abdominal wall.

Embryology The cloaca is a part of the hindgut which ultimately separates into a dorsal part (rectum) and a ventral part. The ventral section divides into three components: (1) a cranial component which becomes the *urachus* (*allantois*), (2) a middle part which becomes the bladder and (3) a caudal part which becomes the urethra and, in the female, part of the vagina (Fig 272). The upper part of the allantois is continued into the umbilicus and the umbilical cord; the intraabdominal portion of the allantois is called the urachus. The urachus and the allantois become a solid cord, which may develop cyst-like dilatations. These dilatations are characteristic of this cord and may be found at any period in the development of the embryo. They persist in many adults and account for the small cysts found at operation. If the urachus remains patent at birth, a urinary umbilical fistula results.

If the peritoneal surface of the umbilical region is examined four fibrous cords are seen radiating from it (Fig 273). These are the remains of four tubes which pass through the umbilical cord in fetal life: they are the urachus, the right and the left umbilical arteries and the left umbilical vein. They are situated in the extraperitoneal fatty layer of the anterior abdominal wall and produce peritoneal folds. In the early human embryo the alimentary tract communicates with the yolk sac by means of a *vitello intestinal* (omphalomesenteric) duct. This structure usually disappears when the embryo is between 6 and 12 mm in length; it does not leave a residual peritoneal fold. However its vessels persist long after the duct has disappeared. Al-




FIG 273 The umbilicus (A) In the fetus four structures radiate from the umbilicus the umbilical vein above and the two umbilical arteries and the urachus below (B) The umbilicus seen from within in the adult The obliterated umbilical vein becomes the round ligament of the liver The urachus becomes the median umbilical ligament and the two obliterated umbilical arteries become the lateral umbilical ligaments

though the duct normally disappears a part of it may remain or it may be found patent. If patent an umbilical fecal fistula develops. If only the inner end remains patent a Meckel's diverticulum develops which may or may not be adherent to the umbilicus. Rarely the median portion persists and the duct becomes obliterated at both ends in such cases an intestinal cyst results. At times the omph

alomesenteric vessels persist as fibrous cords which may give rise to intestinal obstruction.

Vessels Originally there were two arteries and two veins. The left vein is the larger and persists, but the smaller right vein disappears before the embryo is 10 mm long. The two umbilical arteries pass from the internal iliac artery to the umbilicus. They run to either side of the

urachus but soon become obliterated and are then known as the obliterated hypogastric (umbilical) arteries. In adults they appear as fibrous cords, but they may remain patent and then constitute the superior vesical branches to the urinary bladder. The *umbilical vein (left)* passes upward and backward from the umbilicus to the liver, occupying the free border of the falciform ligament; in this way the falciform ligament forms a "mesentery" for this vessel. At birth, when the umbilical cord is cut, the left umbilical vein becomes obliterated and thereafter is known as the round ligament or ligamentum teres of the liver. Under normal conditions all the umbilical structures (duct, vessels and urachus) atrophy, and the umbilical ring becomes reduced to a small orifice. It heals rapidly; fibrous changes take place, and a puckered scar called the *umbilicus* (navel) results. The retraction of the umbilical vein usually draws the scar against the uppermost circumference of the umbilical ring; this is the weak spot where umbilical hernias may occur.

The umbilical papilla is usually circular; it may bulge in the newborn but in the adult it becomes retracted. At the umbilical ring, a thin layer of skin becomes fused directly to the ring margin, and there is no fat. Ascites or multiple pregnancies may dilate and enlarge the ring. The *umbilical fascia*, when it exists, is derived from the transversalis fascia.

The *superficial lymphatics* of the umbilical region pass in the subcutaneous fat and drain in four directions. The upper set passes to the axillary lymph glands and the lower ones to the superficial inguinal group. These channels dip a little deeper and may rest upon the muscular aponeurosis. Those from the upper umbilical region pass to either side of the falciform ligament of the liver, pierce the diaphragm and drain into the anterior mediastinal glands. Small lymph channels are found along the course of the round ligament of the liver, along this channel carcinoma of the gastro-

intestinal tract (stomach and gallbladder) reaches the telltale umbilical lymph node. The lateral channels at first pass laterally, then curve downward to reach the deep inguinal glands. Thus, the lymph channels from the lower portion of the umbilicus may pass directly downward to the deep inguinal set. It is possible, therefore, to find carcinomatous metastases at the umbilicus; a primary malignant tumor from the ovaries and the adnexae spreads by means of the lower set, and carcinoma from the gastrointestinal tract from the upper set.

Types of Umbilical Hernias Hernias may occur in this region, and, owing to the persistence of the embryologic communication between the peritoneal cavity and the umbilical cord, a congenital umbilical hernia may develop. Umbilical hernias have been classified as follows: (1) hernia of the umbilical cord; (2) umbilical hernia in adults; and (3) umbilical hernia in children.

Hernias of the umbilical cord may contain a considerable portion of the abdominal viscera. The coverings of such a hernia are amnion, Wharton's jelly and peritoneum. These coverings are so thin that the hernial contents may be seen through these diaphanous coverings. There is no skin over such a protrusion except at its edges. The condition has also been referred to as *exomphalos* and may be subdivided into complete or partial. The umbilical hernia of adults is the acquired umbilical hernia. The umbilical cicatrix becomes greatly stretched, allowing a process of peritoneum with coils of gut or omentum to escape through it. It is usually large and requires surgical repair. It should be recalled that the fibers of the rectus sheath run transversely; hence, Mayo has devised a procedure in which the incision follows the course of these transverse fibers. The congenital hernia of children usually is due to one of two causes, namely the persistence of a small peritoneal process into the umbilical cord or

an imperfect closure in the linea alba immediately above the umbilicus Straining at stool and coughing may be additional predisposing factors

REPAIR OF UMBILICAL HERNIAS

An umbilical hernia rarely protrudes directly through the umbilical ring, but rather

freed and returned to the peritoneal cavity. Some surgeons prefer to close the peritoneum as a separate layer but since this is usually very difficult to define, because of the great amount of scarring, a repair is effected which includes fascia, scar and peritoneum together. The repair is made by imbricating the upper flap over the




FIG. 274 The muscles of the lumbar region. A posterior view showing the musculature divided into three groups—superficial, middle and deep. The serratus posterior inferior has been reflected upward.

appears above or below it. A wide elliptical transverse incision is made including the umbilicus at its central point. The incision is deepened to the rectus sheaths and the neck of the sac is defined and freed from all adjacent tissues. Horizontal incisions are made at each end of the rectus sheaths; these enlarge the neck of the sac and aid in the reduction of its contents. The sac is opened at its neck; the contents are

lower with interrupted mattress sutures. This is followed by interrupted sutures placed between the free margin of the overlapping sheath and the lower flap.

POSTEROLATERAL WALL (LUMBAR OR ILIOCOSTAL REGION)

The lumbar region also has been referred to as the iliocostal and posterolateral region of the abdominal wall. It is a quad-

lateral area situated between the lowest rib, the iliac crest, the vertebral column and a vertical line erected at the anterior superior iliac spine. The superficial fascia is arranged in two layers between which a large amount of fat usually is deposited

superficial, middle and deep (Figs 274 and 275)

The *superficial* musculature consists of

- 1 Latissimus dorsi
- 2 External abdominal oblique

The *middle* layer consists of




FIG 275 The muscles of the lumbar region in cross section at the level of the third lumbar vertebra. The serratus posterior inferior muscle is not shown in this view

To understand the arrangement of the musculature in this region reference should be made to the lumbodorsal (lumbar) fascia (p 401)

MUSCULATURE

(SUPERFICIAL, MIDDLE AND DEEP LAYERS)

The muscles of the lumbar region can be divided conveniently into three groups

- 1 Serratus posterior inferior
- 2 Sacro-spinalis (erector spinae)
- 3 Internal oblique muscle

The *deep* group consists of

- 1 Quadratus lumborum
- 2 Psoas major
- 3 Transversus abdominis

The *Superficial* Muscles The *Latissimus dorsi* arises from the lower six tho-




FIG 276 The sacrospinalis (erector spinae) muscle. This muscle mass is conveniently divided into three muscles (iliocostalis, longissimus and spinalis) from lateral to medial. The insert shows a cross section of this group and also of the muscles which constitute the transversus spinalis group.




FIG 277 The quadratus lumborum muscle. The relations of this muscle to the ilio lumbar ligament the lumbocostal ligament and the kidney are shown

racic vertebrae from all the lumbar and upper sacral spines and from the supra spinous ligament through the posterior layer of the lumbodorsal fascia. It also has an origin by means of fleshy fibers from the outer lip of the iliac crest (posterior part) the last three or four ribs and at times an additional origin from the inferior angle of the scapula. From this very extensive origin the muscle inserts by means of a tendon which is one inch broad into the floor of the intertubercular sulcus of the humerus (p 710). As the muscle passes upward and laterally to its insertion, it twists around the lower border of the teres major in such a way that its surfaces and borders become reversed. The upper border of the muscle passes across the inferior angle of the scapula forming a muscular pocket for this scapular angle, in this way the scapula is held against the chest wall. Paralysis of this muscle is one of the causes of "winging" of the scapula. The muscle takes part in the formation of

the lumbar triangle of Petit, which is bounded in front by the posterior border of the external oblique behind by the anterior border of the latissimus dorsi and below by the iliac crest. The actions of the muscle are adduction of the humerus, extension of the arm at the shoulder and medial rotation. The muscle is supplied by the subscapular artery and the thoraco-dorsal nerve. Its action can be tested by grasping the posterior axillary fold and asking the patient to cough vigorously, as this is done, the muscle will be felt to contract.

The external abdominal oblique (p 380) descends obliquely downward and forward and presents a free posterior border. It arises from the ninth, the tenth and the eleventh ribs. During kidney operations these posterior fibers may be retracted ventrally or they may be incised. Such incisions should be placed parallel with the lower ribs to avoid cutting the nerves. The free posterior border of the external oblique usually is located at the midpoint of the iliac crest.

The Middle Group of Muscles. Phylogenetically, the serratus muscles form a continuous muscular sheet. This becomes divided into superior and inferior parts. The *serratus posterior inferior* appears in this region blends with the lumbar fascia and through it gains attachment to the upper lumbar and lower thoracic spines. It is under the latissimus dorsi and passes upward and transversely to ribs nine, ten, eleven and twelve. (The *serratus posterior superior* is a flat muscle which lies under the rhomboids. It arises from the lower cervical and upper thoracic spines passes downward and laterally and inserts into ribs two, three, four and five.) The muscles are supplied by corresponding intercostal nerves. The serratus posterior superior elevates and the serratus posterior inferior depresses the ribs into which they insert. The serratus posterior inferior is an important surgical landmark in kidney operations, since its lowermost fibers lie super




FIG 278 The psoas muscle and sheath (A) The psoas sheath and the course taken by a psoas abscess (B) Transverse section of the psoas muscle and sheath The layers of the lumbodorsal fascia are shown

ficial to the posterior lumbocostal ligament and mark this ligament (Fig 277) Since the pleura is on a level with the lumbocostal ligament or slightly above it in incisions which encroach upon the muscle and the ligament should be avoided if the pleura is to escape injury

The *sacrospinalis* (*erector spinae*) muscle is really an elongated group of muscles which extends upward from the dorsum of the sacrum and the posterior part of the

iliac crest (Fig 276) It corresponds to a muscle mass approximately as broad as the hand and is situated in the aponeurotic compartment formed by the posterior and the middle layers of the lumbodorsal fascia (Fig 278 B) Laterally it extends from the spines of the vertebrae to the angles of the ribs vertically it passes from the fourth piece of the sacrum to the mastoid process of the occipital bone It is best to consider this group as three subdivisions




FIG 277 The quadratus lumborum muscle. The relations of this muscle to the ilolumbar ligament the lumbocostal ligament and the kidney are shown

racic vertebrae from all the lumbar and upper sacral spines and from the supraspinous ligament through the posterior layer of the lumbodorsal fascia. It also has an origin by means of fleshy fibers from the outer lip of the iliac crest (posterior part) the first three or four ribs, and at times an additional origin from the inferior angle of the scapula. From this very extensive origin the muscle inserts by means of a tendon which is one inch broad into the floor of the intertubercular sulcus of the humerus (p 710). As the muscle passes upward and laterally to its insertion, it twists around the lower border of the teres major in such a way that its surfaces and borders become reversed. The upper border of the muscle passes across the inferior angle of the scapula forming a muscular pocket for this scapular angle in this way the scapula is held against the chest wall. Paralysis of this muscle is one of the causes of "winging" of the scapula. The muscle takes part in the formation of

the *lumbar triangle of Petit* which is bounded in front by the posterior border of the external oblique, behind by the anterior border of the latissimus dorsi and below by the iliac crest. The actions of the muscle are adduction of the humerus, extension of the arm at the shoulder and medial rotation. The muscle is supplied by the subscapular artery and the thoraco-dorsal nerve. Its action can be tested by grasping the posterior axillary fold and asking the patient to cough vigorously, as this is done, the muscle will be felt to contract.

The *external abdominal oblique* (p 380) descends obliquely downward and forward and presents a free posterior border. It arises from the ninth, the tenth and the eleventh ribs. During kidney operations these posterior fibers may be retracted ventrally or they may be incised. Such incisions should be placed parallel with the lower ribs to avoid cutting the nerves. The free posterior border of the external oblique usually is located at the midpoint of the iliac crest.

The Middle Group of Muscles Phylogenetically, the serratus muscles form a continuous muscular sheet. This becomes divided into superior and inferior parts. The *serratus posterior inferior* appears in this region, blends with the lumbar fascia and through it gains attachment to the upper lumbar and lower thoracic spines. It is under the latissimus dorsi and passes upward and transversely to ribs nine, ten, eleven and twelve. (The *serratus posterior superior* is a flat muscle which lies under the rhomboids. It arises from the lower cervical and upper thoracic spines, passes downward and laterally and inserts into ribs two, three, four and five.) The muscles are supplied by corresponding intercostal nerves. The serratus posterior superior elevates and the serratus posterior inferior depresses the ribs into which they insert. The serratus posterior inferior is an important surgical landmark in kidney operations, since its lowermost fibers lie super




FIG 279 Fascial relations of the kidney (A) Cross section through the hilus of the kidney. The renal fascia is derived from the transversalis fascia. At the lateral border of the kidney the transversalis fascia splits into an anterior prerenal and a posterior retrorenal layer. The fat surrounding the kidney is arranged in two layers (1) pararenal (retrorenal) fat and (2) perirenal fat. The latter fills the space of Gerota. The arrow indicates the lumbar approach. (B) Longitudinal section through the kidney. The two layers of renal fascia fuse at the upper pole of the kidney but remain open at the lower pole. This explains the downward path (indicated by the arrow) of a ptotic kidney and also explains why the suprarenal remains in situ during the course of a nephrectomy.

1 The *iliocostalis* consists of lumbar, thoracic and cervical portions and is the most lateral group

2 The *longissimus* is intermediate in position and is the widest and bulkiest of the three subdivisions its uppermost part is the *longissimus capitis*

3 The *spinalis* constitutes the most medial subdivision and is the shortest of the three

In kidney incisions only the lateral bundles (*iliocostalis*) of the *sacrospinalis* muscle are encountered. If they must be cut the incision should be made transversely to the fibers slightly below and parallel with the twelfth rib so that the lateral and the ventral branches of the last thoracic and the first lumbar nerves and the dorsal branches of the tenth and the eleventh thoracic nerves and their accompanying vessels may be avoided.

The *internal oblique* muscle, which arises from the iliac crest and the inferior part of the lumbodorsal fascia extends posteriorly to the external oblique and forms the floor of Petit's triangle (lumbar trigone). If this muscle is traced upward as it extends onto the lumbar fascia, it presents a free superior border.

Another group the *transversus spinalis*, is made up of three muscle masses which lie deep to the *sacrospinalis* (Fig 276) and extend from the fourth piece of sacrum to the skull. They fill the groove which exists between the spines of the vertebrae and their transverse processes. These three muscles lie one on top of each other, from superficial to deep they are the *semi-spinalis*, the *multifidus* and the *rotatores*.

The Deep Group of Muscles The *quadratus lumborum* is a flat muscle which lies lateral to the *psaos* (Fig 277). It arises from the *iliolumbar* ligament (which extends from the fifth lumbar transverse process to the posterior part of the iliac crest), from the adjoining part of the iliac crest and from the tips of the lower lumbar transverse processes. It takes an

upward and medial course and becomes inserted into the lower border of the twelfth rib. It fixes the last rib so that it assists the action of the diaphragm in inspiration and bends the vertebral column to the side. The anterior and the middle layers of lumbar fascia surround this muscle. Its nerve supply is derived from lumbar nerves one, two, three and four. The anterior layer of lumbodorsal fascia separates it from the *transversalis fascia*. Its upper portion is strengthened anteriorly by the lateral *lumbocostal* ligament. Normally the kidney extends about an inch lateral to the lateral margin of this muscle, since the muscle can be drawn medially, only rarely is it necessary to sacrifice its lateral bundles for exposure in kidney operations.

The *psaos major* muscle may be considered as part of the *iliacus* muscle which has migrated above the iliac crest. (The *psaos minor* is present in approximately 30 per cent of individuals.) It occupies the bony trough which is situated between the bodies and the transverse processes of the lumbar vertebrae. It arises from the twelfth thoracic and all of the lumbar vertebrae and passes downward and laterally along the margin of the pelvic brim. It continues beneath the inguinal ligament, enters the thigh and inserts onto a traction epiphysis of the lesser trochanter of the femur. Since this muscle is deeply and medially placed it does not come directly into view in kidney surgery. It is supplied by lumbar nerves two, three and four and is a powerful flexor of the thigh. It also assists in medial rotation of the thigh and flexes the trunk on the lower limb. The sheath of the *psaos* is a stout membranous covering which is situated around the muscle (Fig 278). This sheath is attached medially to the bodies of the lumbar vertebrae and, laterally it blends with the anterior layer of the lumbodorsal fascia. It extends behind the femoral artery into the thigh where it blends with the *psaos tendon*. Above it is kept open by its upper attachment to the body of the second lumbar

cles. Through this layer it gains attachment to the vertebral column.

The two layers of renal fascia fuse at the upper pole of the kidney but remain separated at the lower pole (Fig. 279 B). This structural arrangement explains two facts: (1) it is possible to shell out the kidney within its capsule leaving the suprarenal gland in situ because this fascia forms a separate chamber for the suprarenal gland and (2) diminution of the perirenal fat predisposes to mobility (floating) of the kidney. Since the renal fascia does not fuse at the lower pole the kidney drops caudad but does not carry the suprarenal gland with it. The renal fascial envelope is poorly defined in the cadaver; however, like many other fascial layers it is quite definite in the living. G. A. G. Mitchell is of the opinion that the anterior and posterior layers of renal fascia fuse superiorly and laterally. Contrary to the accepted view he states that they are also united medially and inferiorly.

The fat surrounding the kidney is arranged in two separate fat planes which are: (1) the pararenal fat (retrorenal fat) and (2) the perirenal fat (Fig. 279 A).

The *pararenal fat* is that layer of fat which lies behind the kidney and is located between the aponeurosis of origin of the transversus abdominis muscle and the posterior layer of renal fascia. It varies from a small layer 5 mm. thick to a cushion of enormous size. As soon as the aponeurosis of origin of the transversus muscle is incised the first fat layer is reached.

The *perirenal fat*, the second fat layer, is a specialized layer which lies in the fascial space of Gerota and fills this space. Before this fat can be seen the posterior layer of renal fascia must be incised. It forms the fatty capsule of the kidney and runs completely around it passing medially into the hilum and insinuating itself between the renal vessels. Its consistency is almost semiliquid because of this property it gives the kidney a certain amount of movement transmitted to it by the diaphragm.

The Kidney Proper (Vessels and

Nerves) The kidney has three capsules: (1) the renal fascia (transversalis fascia), (2) the adipose capsule (perirenal fat) and (3) the capsule proper, a fibrous membrane which normally strips easily from the kidney (in inflammatory conditions it strips with difficulty and tears kidney tissue).

The kidney is reddish brown in color and is soft in consistency. It is from four to five inches long, two and one half inches wide and one inch in thickness at its middle. It is usually referred to as "bean shaped," having upper and lower poles, anterior and posterior surfaces, and medial and lateral borders (Fig. 280 A). The hilum is a vertical slit on the medial border which is bounded by thick lips of renal substance. Through it the branches of the renal artery enter the gland, and the veins and the ureter leave. The hilum leads into a wide space inside the kidney called the *sinus of the kidney*. A number of structures lie in the sinus: branches of the renal artery, tributaries of the renal veins, short funnel shaped tubes called calyces which unite to form the ureter, the dilated proximal end of the ureter called the pelvis of the ureter and the lymph vessels, nerves and fat.

The *renal artery* may divide into many branches before entering the gland and it also sends a branch behind the ureter, the retro ureteric branch of the renal artery. Anson, Cauldwell, Pick and Beaton conducted a comprehensive study of the blood vessels in the dorsal portion of the trunk. They state that supernumerary renal arteries are more likely to be present than absent and that the arrangement of these vessels varies greatly. Commonly, the main artery is accompanied by lesser accessory renals which may give off an internal spermatic. When the accessory renals arise from the main renal, phrenic or suprarenal arteries they are small and go to the upper pole of the kidney (Fig. 280 B); if they are large, they usually are arranged in a serial manner and affect both poles as well as the hilum of the kidney (Fig. 280 C). These vessels pass to the kidney either in front of or behind the inferior vena cava.

vertebra medially and the first lumbar transverse process laterally. Pus from a tuberculous thoracic vertebra may enter the sheath and become directed into the thigh where a puffy swelling may appear behind and on each side of the femoral vessels. Such collections may rupture higher up into the anterior compartment of the lumbodorsal fascia or under the iliac fascia.

The *transversus abdominis* muscle also appears in this region. It arises from the fusion of the three aponeurotic layers of lumbodorsal fascia and extends over the anterolateral wall toward the linea alba where it becomes muscular. The upper part of the transversus aponeurosis is strengthened by the posterior lumbocostal ligament. The peritoneum is separated from this muscle by extraperitoneal fat and transversalis fascia.

The nerves which are encountered in this region are the twelfth thoracic and the first lumbar. The *first lumbar nerve* gives rise to the larger iliohypogastric and the smaller ilioinguinal nerves. These travel between the psoas major and quadratus lumborum muscles. The iliohypogastric nerve pierces the transversus abdominis aponeurosis and then continues between it and the internal oblique. The ilioinguinal nerve travels along the inner surface of the transversus aponeurosis until it perforates that muscle near the anterior part of the iliac crest. It then pierces the internal oblique and continues through the inguinal canal (Fig 262).

The vessels found here are the twelfth intercostal artery (subcostal) and the lumbar artery and vein. The twelfth intercostal artery is the last parietal branch of the thoracic aorta. It passes behind the lateral arcuate ligament above the subcostal nerve and accompanies that nerve across the quadratus lumborum and through the transversus muscle. It ends in twigs to the transversus and the internal oblique muscles.

The *subcostal vein* lies above the artery, close to the last rib. Therefore the order of these structures is vein, artery and

nerve. The vein passes behind the lateral arcuate ligament to join the azygos vein or the inferior hemiazygos (Fig 242).

KIDNEYS

Fascial Relations The surgical anatomy of the kidneys is closely related to the lumbodorsal and the renal fascia.

The *lumbodorsal fascia* consists of three layers—anterior, middle and posterior—which fill the gap between the twelfth rib and the iliac crest (Fig 278). The posterior and the middle layers are very dense and are stronger than the anterior. The *posterior layer* arises from the tips of the spines of the lumbar, the sacral and the thoracic vertebrae, the *middle layer* arises from the tips of the transverse processes of the lumbar vertebrae and the *anterior layer* arises from the anterior surfaces of the lumbar transverse processes near their roots. The psoas fascia springs from this layer.

As these three layers pass laterally they fuse near the outer border of the quadratus lumborum muscle; the fusion results in the formation of a dense tendinous structure known as the *aponeurosis of origin of the transversus abdominis muscle*. It is from this structure that the internal oblique muscle partly arises. Between the posterior and the middle layers of lumbodorsal fascia the sacrospinalis muscle group (erector spinae) is found and between the middle and the anterior layer the quadratus lumborum is situated.

The *renal fascia* is derived from the transversalis fascia. At the lateral border of the kidney the transversalis fascia splits into an anterior (prerenal) and a posterior (retrorenal) layer. In this way the perirenal fascial space of Cerota is formed (Fig 279 A). The anterior layer is carried medially in front of the kidney and its vessels the aorta and the vena cava, and becomes continuous with its corresponding layer of the opposite side. The posterior layer extends medially behind the kidney and blends with the fascia of the quadratus lumborum and the psoas major mus-

or may clasp the renal vein. Therefore, our concept of the so-called kidney 'pedicle' may better be looked upon as a ladder of vessels which arise from the aorta over in area which might correspond to the entire height of the kidney. The veins emerge through the walls of the sinus and are quite small; they unite to form larger veins which for the greater part lie in front of the arteries but may come to lie between the arteries and even behind the ureter. Anson et al. state that the pattern of the renal veins does not follow that of the renal arteries in number or in course. They believe that the right renal vein may be single, double or triple; however, duplication of the left renal vein is very rare. Division of a single renal vein en route to the inferior vena cava is common, however, and in such instances the divisions surround the aorta and form a circumaortic venous ring. Accessory renal veins are infrequent but the complexity of the venous pattern is due to the continuity of the renal veins with veins which drain the surrounding structures. The left renal vein appears to be at the center of a huge venous network (Fig. 280 D). This makes nephrectomy hazardous and permits the spread of infectious materials and neoplasms. The left renal vein is longer than the right; it has a greater distance to travel to the inferior vena cava which lies to the right of the midline. The lymph vessels follow the veins and drain into nearby glands in the region of the inferior vena cava and the aorta.

The nerves are derived from the twelfth thoracic (subcostal nerve) and the first lumbar (iliohypogastric and ilioinguinal nerves); they run more or less parallel with the last rib. The subcostal nerve is accompanied by the subcostal vessels. The three nerves lie in the paranephric fat as they run forward; they come to lie between the transversus abdominis and the internal oblique muscles.

Both kidneys lie above the level of the umbilicus; the right kidney reaches the

upper border of the twelfth rib, the left reaches the lower border of the eleventh rib and can be placed approximately opposite the last thoracic and upper two lumbar vertebrae (Fig. 281). The right organ is a rule, lies somewhat lower than the left because of the volume of the right lobe of the liver. Occasionally, the kidneys occupy the same level and in rare instances their relations are reversed. The long axes of the organs are not parallel but are oblique to the spine; therefore, the upper poles are closer to each other than are the lower. The lower poles are about an inch above the highest point of the iliac crest; the outer border of the organ lies about one half inch lateral to the outer border of the sacrospinalis muscle.

The kidneys rest upon four muscles: the diaphragm above, the transversus muscle laterally, the psoas muscle medially and the quadratus lumborum muscle (between the preceding two).

The twelfth rib is an important landmark in kidney anatomy and is separated from the kidney by the pleura and the diaphragm. The twelfth rib takes an oblique course downward while the lower border of the pleura is horizontal; therefore these two lines cross like the letter X. This rib may be very short so that the sacrospinalis muscle covers it completely and in such cases the eleventh rib is often mistaken for the twelfth and an incision is placed too high; in such cases the pleura may be opened inadvertently. The twelfth rib and the outer border of the sacrospinalis muscle form an angle which is known as the kidney angle. Pressure over this angle usually elicits tenderness in kidney lesions. Lumbar incisions for kidney operations commence here.

The relations of the anterior the kidneys differ (Fig. 282) both capped by the suprarenal glands; the right kidney's anterior is related to the liver above, the head of the colon below and the second part of the duodenum near the kidney.




Fig. 290. The kidney and its blood vessels. (A) Anterior view of the right kidney. (B) When the accessory renal arteries arise from the mid-ventral the phloem in the upper renal artery they are small and pass to the upper pole of the kidney. (C) When the accessory renal arteries arise from the mid-ventral they are small and pass to both poles and the hilum of the kidney. (D) The venous drainage of the kidney at the renal level. On the right, the pattern is a simple one, the renal and the upper renal veins empty directly into the inferior vena cava. On the left the pattern is a complicated one in which the left renal vein is the center of an extensive venous network, the inferior phloem and accessory veins enter from above. The posterior (coeliac) lumbar, coeliac and accessory veins enter from below and to the left. Other veins which have communications are the azygos and the lumbar veins (via the lumbar) and the inferior and the external vertebral plexuses (via the inferior vena cava and the lumbar).

lower pole is crossed by the ascending branch of the right colic artery. It is covered with peritoneum except at its extreme upper, inner and lower parts. At times a coil of small intestine may come

spots are left in the diaphragm above the twelfth rib near its free end. The triangle is more marked on the left side because the liver covers it on the right. If such triangles are well developed the lateral




FIG. 281 Posterior relations of the kidneys seen from behind. The deep musculature has been removed on the right side.

into relation with the inferior pole. The left kidney has in front of it the stomach above the spleen laterally the pancreas transversely across it from the hilum to the splenic area and the transverse colon below. The lower pole is in contact anteriorly and medially with coils of jejunum. It is crossed by the ascending branch of the left colic artery. Only gastric, splenic and jejunal surfaces are covered by peritoneum.

The diaphragm separates the upper pole of the kidney from the pleura. Dorsal to the pleura are the twelfth rib and the muscles of the back. In some individuals weak

aspect of the kidney is in close relation with the pleura and the last rib, being separated from them by only a little adipose tissue.

The kidneys are kept in place by attached vessels by the pressure of surrounding organs and by their fat and fascia. The kidneys move downward with respiration for an excursion of about 2 cm.

At times the lower poles of the kidneys are fused across the midline by a thick bridge of kidney tissue which crosses in front of the inferior vena cava and the aorta. This is called a "horseshoe kidney."




FIG 282 Anterior relations of the kidneys





FIG 283 Various approaches to the kidney must be utilized since no single approach admits sufficient exposure for all surgical procedures on this organ. The illustration shows the extraperitoneal and the transperitoneal approaches as well as the approach through the lumbar trigone.

SURGICAL CONSIDERATIONS

NEPHRECTOMY

No single incision accomplishes the desired exposure for all conditions affecting the kidney (Fig 283) Furcolo described a trans

(Figs 284 and 285 A) From this point it curves inward and forward and runs parallel with the iliac crest about two inches from it. The incision is carried through the skin and the subcutaneous tissue until the musculature is exposed. The muscle



*FIG 284 Exposure of the left kidney

fascial approach which gives excellent exposure and produces minimal tissue damage. Another useful incision is the one herein described for nephrectomy.

The incision begins about one inch above the junction of the last rib and the erector spinae muscle group. This passes almost vertically downward with a slight inclination forward to a point about halfway between the twelfth rib and the iliac crest.

layer consists of the latissimus dorsi and the serratus posterior inferior at the posterior end of the wound and the external oblique at the anterior extremity. The muscles (latissimus dorsi, serratus posterior inferior, external oblique, internal oblique and transversus abdominis) are divided until the lumbar fascia is exposed. Deep to this fascia are the twelfth dorsal nerve and vessels which cross from above down.




FIG 285 Nephrectomy through a lumbar approach

ward and forward. If possible they should be spared. Usually a well developed layer of pararenal (retrorenal) fat will be found between the lumbar aponeurosis and the retrorenal leaf of perinephric fascia. The


retrorenal leaf of renal fascia is opened and another fat layer the perirenal layer comes into view. This is the surgeon's cleavage plane, since it is this fat which immediately surrounds the kidney. This fat continues

SURGICAL CONSIDERATIONS

NEPHRECTOMY

No single incision accomplishes the desired exposure for all conditions affecting the kidney (Fig 283) Furcolo described a trans

(Figs 284 and 285 A) From this point it curves inward and forward and runs parallel with the iliac crest about two inches from it. The incision is carried through the skin and the subcutaneous tissue until the musculature is exposed. The muscle



*Fig 284 Exposure of the left kidney

fascial approach which gives excellent exposure and produces minimal tissue damage. Another useful incision is the one herein described for nephrectomy.

The incision begins about one inch above the junction of the last rib and the erector spinae muscle group. This passes almost vertically downward with a slight inclination forward to a point about halfway between the twelfth rib and the iliac crest.

This layer consists of the latissimus dorsi and the serratus posterior inferior at the posterior end of the wound and the external oblique at the anterior extremity. The muscles (latissimus dorsi, serratus posterior inferior, external oblique, internal oblique and transversus abdominis) are divided until the lumbar fascia is exposed. Deep to this fascia are the twelfth dorsal nerve and vessels which cross from above down.

Esophagogastro-intestinal Tract

EMBRYOLOGY

ROTATION AND FIXATION

In the earliest days of its development the gastro-intestinal tract is represented as a straight tube of uniform caliber which is suspended in the midline of the abdominal cavity by a ventral and a dorsal mesentery (Fig. 286). The dorsal mesentery extends along the entire length of this tube; it may be subdivided into mesogastrium, mesoduodenum, mesojejunum, mesoileum and the various mesocola. The ventral mesentery, however, extends only as far as the first inch of the duodenum or, in other words, as far as the umbilicus; it is referred to as the ventral mesogastrium. The straight gastro-intestinal tube lies between two layers of mesentery and therefore has right and left surfaces. The aorta supplies the entire tube by means of three branches: the celiac axis and the superior and the inferior mesenteric arteries. The celiac axis supplies the foregut (stomach and duodenum as far as the entrance of the bile duct). The superior mesenteric artery supplies the midgut (from the entrance of the bile duct to the junction of the middle and the left thirds of the transverse colon). The inferior mesenteric artery supplies the hindgut (from the left third of the transverse colon to the rectum).

Since the adult intestinal tract is well over twenty feet in length and since the abdominal cavity is only two feet long, many changes must take place to accommodate the one to the other.

The initial short segment of the straight

tube is the abdominal esophagus; distal to this the upper part of the foregut bulges out to form the stomach. The lower inch of foregut and the entire midgut lengthen to form the redundant umbilical loop which has a descending proximal limb and an ascending distal limb (Fig. 286). The small intestine eventually develops from the descending limb and part (about one half) of the ascending limb; the remaining half of the ascending limb bulges into a cecal bud. The segment at the terminal portion of the umbilical loop (initial colic segment) is directly continuous with the hindgut (terminal colic segment). Prolongation of the initial colic segment (midgut) forms the ascending colon and the greater part of the transverse colon. The terminal colic segment (hindgut) forms the remainder of the transverse colon, the descending, the sigmoid and the pelvic portions of the colon. The rectum develops from the primitive cloaca.

The upper end of the hindgut is fixed to the posterior abdominal wall by the mesentery of the terminal colic segment. Where the midgut meets the hindgut or, in other words, where the initial colic segment meets the terminal colic segment, an angle is formed known as the 'colic angle'. The extremities of the midgut are anchored by the fixed upper duodenum above and the fixed colic angle below. These two fixed points are quite close together, and the mesentery filled space between them is known as the duodenocolic isthmus.

Part of the umbilical loop (descending limb and first half of ascending limb)

around the pelvis the great vessels and the ureter (Fig 284) The peritoneum is pushed forward as the fat is wiped away both poles are mobilized and the kidney is delivered into the wound Nephrectomy (Fig 285) can be accomplished after exposing and delivering the pedicle with its contained vessels and ureter These are clamped and divided the kidney is removed and the pedicle is ligated

NEPHROPEXY

In nephropexy Zieman has pointed out the importance of anchoring a movable kidney along its anatomic plane In this way nature's own confining fascial covering (transversalis fascia) is utilized

THE SUPRARENAL GLANDS

These are two in number and are situated one on each side in the epigastric region (Fig 280) They are flattened from before backward broad from side to side and set upon the superior extremity of the corresponding kidney They have separate fascial capsules this permits the removal of a kidney without removal of the suprarenal (Fig 279 B) For the same reason a suprarenal does not move with a so called floating kidney However Davies found that in 6 out of 1 500 postmortem examinations the suprarenal and the kidney

were so intimately fused that nephrectomy in these cases would have resulted also in a suprarenalectomy If this thought is kept in mind careful exploration will reveal a small space (cleavage plane) filled with connective tissue between the inferomedial angle of the suprarenal and the kidney, where the two structures may be separated

The right suprarenal is pyramidal in shape and smaller than the left It is situated between the diaphragm and the right lobe of the liver Its anterior surface is related to the inferior vena cava medially and the bare area of the liver laterally The posterior surface is related to the kidney inferiorly and the crus of the diaphragm superiorly The right celiac ganglion lies on the medial side of this gland

The left suprarenal is semilunar in shape and seems to have slipped down on the medial border of the kidney as far as the renal vessels Therefore its lower pole is in contact with the renal vessels and its upper pole is in contact with the spleen Its anterior surface is related to the stomach superiorly and to the pancreas inferiorly The posterior surface is related to the crus of the diaphragm medially and the kidney laterally

The blood supply has been carefully described by Anson et al (Fig 280)

grows so rapidly that the embryonic peritoneal cavity is unable to contain it. As a result of this part of the loop grows into the umbilical cord (extra embryonic celom). This results in an umbilical hernia which is temporary and physiologic.

The superior mesenteric artery supplies the umbilical loop (midgut). It starts as

a branch of the abdominal aorta, passes through the duodenocolic isthmus, sends branches to the umbilical loop and ends as the vitelline artery which supplies the vitellointestinal duct. This duct also called the omphalomesenteric duct is the communication between the midgut and the yolk sac, normally, it disappears. It will




FIG 287 Normal fetal circulation. Red indicates arterial blood, blue indicates venous blood, and purple indicates an admixture of both.




FIG 286 Rotation and fixation of the gastro intestinal tract

tery which passes obliquely from the duodenojejunal flexure to the ileocecal angle.

The descending colon with its mesocolon normally fuses with the left parietal peritoneum. A peculiar characteristic of the mesentery of the sigmoid is that it does not fuse with the left pelvic peritoneum and because of its redundancy it forms an intersigmoid recess or fossa the depth of which is variable (p. 477).

If the surgeon bears in mind the facts just described he will recall that cohesion has taken place between the two surfaces of peritoneum but that the cleavers are not firmly fixed. They may be restored to their embryologic state by opening and separating them. No vessels, nerves or other vital structures pass between them hence the surgeon refers to such spaces as cleavage planes.

Fixation along the entire alimentary tract has taken place by lateral fixation either right or left. Therefore when one wishes to restore a segment of gut to its embryologic state one must incise lateral to the segment enter the cleavage plane and free the gut in a medial direction. In this way the primitive dorsal mesentery is reconstructed.

It is unnecessary to free the transverse colon or the sigmoid because they do not fuse. However fusions and fixations are variable so that at times fusion does not take place and the ascending colon hangs free by its original mesentery. On the other hand the sigmoid which normally does not fuse with the parietal peritoneum may do so either partially or completely and may require separation.

FETAL CIRCULATION

Since the lungs do not function in fetal life the fetus receives oxygenated blood from the placenta by way of the umbilical vein (Fig. 287). This vein passes through the liver and enters the inferior vena cava via the ductus venosus. Some of the blood may circulate through the liver and enter the inferior vena cava through the hepatic veins. As the inferior vena cava enters the

right auricle it contains a mixture of oxygenated blood from the placenta and unoxygenated blood from the fetus. Most of the blood from the inferior vena cava passes through the foramen ovale and into the left auricle where it mixes with the venous blood returning from the lungs. This blood passes from the left auricle to the left ventricle and out through the aorta.

The superior vena cava conveys the blood from the head and the superior extremities to the right auricle. The greater part of this blood is directed to the right ventricle and then out the pulmonary artery.

Most of the blood from the pulmonary artery passes through the ductus arteriosus to the aorta to the trunk and to the inferior extremities. Part of this blood is returned to the right auricle via the inferior vena cava, and part flows through the hypogastric arteries to the umbilical arteries and out to the placenta for removal of waste products and oxygenation. The blood in the pulmonary artery which does not pass through the ductus arteriosus passes through the main branches of the pulmonary artery to the lungs through which it circulates but receives no oxygen. It returns to the left auricle by way of the pulmonary veins.

In the fetus the work of the right ventricle is increased because it not only pumps blood through the ductus arteriosus but also pumps blood against the high pressure of the collapsed lungs. Hence during intra uterine life the right ventricle does more work so that at birth the thickness of both ventricles is approximately the same.

The fetal structures as compared with those in adult life may be outlined in the following manner:

FETUS	ADULT
Umbilical vein	Ligamentum teres of liver
Ductus venosus	Ligamentum venosum
Ductus arteriosus	Ligamentum arteriosum
Hypogastric arteries	Lateral umbilical ligaments

be discussed in detail under the heading of Meckel's diverticulum (p 460) As the artery runs in the mesentery of the umbilical loop it sends branches upward to the descending limb and downward to the ascending limb of the loop Some authors prefer to refer to the limb and the mesentery supplied by the upward running branches as the prearterial limb and the prearterial mesentery the limb and the mesentery supplied by the branches which run downward are referred to as the postarterial limb and the postarterial mesentery (Fig 286 C)

At the beginning of the fifth week rotation takes place It starts while the midgut loop is still in the umbilical cord The growth of the right lobe of the liver starts rotation by pressing on the prearterial segment so that this segment is pushed to the right and downward This in turn forces the postarterial segment up and to the left The growth of the liver has thereby succeeded in rotating or pushing the umbilical loop 90° counter clockwise so that the primitive left surface of the mesentery of the loop now faces upward and the primitive right surface faces downward (Fig 286 D) If rotation is arrested at this stage, the appendix and the cecum are found on the left side of the body

About the beginning of the tenth week the umbilical loop which now lies transversely starts to return from the umbilical cord to the abdominal cavity This return takes place in a definite and orderly manner The proximal part of the prearterial segment returns first At this stage the superior mesenteric artery is fixed firmly from its origin at the aorta to its termination at the umbilicus so that it forms a taut cord The return of the small gut starts to the right of this artery but since the intra abdominal space to the right of the artery is small the coils which have been reduced first are pushed to the left and behind the artery As these coils pass to the left they encounter the dorsal mesentery of the hindgut which occupies the midline This in turn is also pushed to the

left ahead of the small gut so that the descending colon comes to occupy the left flank and what was the "colic angle" is pushed upward and to the left to form the splenic flexure As the last coil of ileum enters the abdominal cavity it carries the superior mesenteric artery with it The cecum and the right half of the colon now follow crossing in front of the origin of the superior mesenteric artery At this stage the following has been accomplished (Fig 286 E)

1 The duodenum lies behind the superior mesenteric artery

2 The transverse colon is in front of the superior mesenteric artery

3 The small gut travels from the left upper to the right lower quadrant of the abdomen

4 The descending colon has been pushed to the left

5 The cecum and the appendix are under the liver

6 There is no ascending colon

As rotation continues descent of the cecum and fixation of the gut to the posterior abdominal wall take place The cecum descends until it reaches the right iliac fossa as a result of this an ascending colon is formed The ascending, the transverse and the descending portions of the colon now have reached their ultimate positions, thus forming an inverted "U" which embraces the jejunum and the ileum The cecum the ascending colon and the ascending mesocolon (postarterial) fuse with the right parietal peritoneum The upper limit of ascending mesocolon overlies a part of the loop of the duodenum and the head of the pancreas which aids in fixing these structures to the posterior abdominal wall

✓ The transverse colon and mesocolon do not fuse with the posterior abdominal wall, hence part of the colon hangs free in the peritoneal cavity by its unfused mesentery The two transverse colic angles' (hepatic and splenic flexures) are fixed The jejunal and ileal loops with their mesentery acquire no posterior fixation so that they hang free by a common jejuno ileal mesen

In the thorax the esophagus does not remain directly in the midline but opposite the fifth sixth seventh and eighth thoracic vertebrae it returns to its midline position. In the lower part of the thorax

of the vertebrae in the upper two thirds of its course but the longus colli, the thoracic duct the azygos and the hemiazygos veins and the right posterior (aortic) intercostal artery intervene. In the lower third




FIG. 289 The esophagus seen from the left side. The distance from the upper incisor teeth to the beginning of the esophagus (cricoid cartilage) is about 6 inches; from the upper incisors to the level of the bronchi 9 inches; to the cardia 16 inches. Therefore the esophagus itself is about 10 inches long.

it again inclines to the left, passes forward from the vertebral column and pierces the muscular part of the diaphragm at the level of the tenth thoracic vertebra. Therefore it passes through the superior and the posterior mediastina. Posteriorly, the esophagus is closely related to the bodies

of the vertebrae in the upper two thirds of its course but the longus colli, the thoracic duct, the azygos and the hemiazygos veins and the right posterior (aortic) intercostal artery intervene. In the lower third




FIG 288 Embryology of the esophagus (A) (B) and (C) represent the medial growth of two lateral septa which divide the early single tubular structure into an anterior (ventral) trachea and a posterior (dorsal) esophagus (D) The trachea and the esophagus as a single structure (E) Later development and separation of the esophagus and the trachea

THE ESOPHAGUS

EMBRYOLOGY

At a very early period in fetal development the stomach is separated from the primitive pharynx by a constriction which is the future esophagus (Fig 288). Owing to the development of the lungs the constriction becomes lengthened but previous to this elongation the trachea and the esophagus form a single tubular structure. The latter becomes divided by the growth of two lateral septa which fuse and form the trachea anteriorly and the esophagus posteriorly. The esophagus becomes converted into a solid cord of cells losing its tubular nature; this cord later becomes canalized to form a tube again. The embryology of the esophagus explains the development of an esophagotracheal fistula

which would be due to a lack of fusion of the two lateral septa. If there is imperfect canalization of the solid cord stage, a congenital stricture may result.

ADULT ESOPHAGUS

The fully developed esophagus is a muscular tube lined with mucous membrane; it is about 10 inches long (Fig 289). It commences at the lower margin of the pharynx which is opposite the sixth cervical vertebra and at the lower border of the cricoid cartilage; its termination is at the cardiac orifice of the stomach opposite the eleventh thoracic vertebra. In its course it passes through the lower part of the neck, the superior mediastinum, the posterior mediastinum and the diaphragm; its terminal inch or inch and a half is within the abdomen. The distance from the front teeth to the junction of the esophagus and the stomach is about 16 inches. Three constant constrictions are found in the esophagus. The first is at its beginning on a level with the cricoid cartilage, the second is behind the bifurcation of the trachea (broncho-aortic constriction) on a level with the fourth thoracic vertebra and the third is at its passage through the esophageal hiatus in the diaphragm. The last is not a narrowing of the tube itself, but is due to the muscular fibers of the diaphragm which surround the esophagus. Its relations in the neck, in the thorax and in the abdomen are surgically important (Fig 151).

In the neck it lies in front of the vertebral column and the longus cervicis (colli) muscle. On each side it is related to the thyroid lobe, and its left border is in close contact with the thoracic duct (Fig 151). Anteriorly it is in direct contact with the trachea and the recurrent laryngeal nerves. To the left side of the esophagus the left inferior thyroid, the left carotid and the left subclavian arteries are found; on its right side the right carotid artery is found. As it descends it inclines to the left side of the midline, hence the surgical approach usually should be from the left.




FIG. 290 The blood vessels of the esophagus (A) The arterial supply is derived from the inferior thyroid artery in its upper part from the aorta the intercostals and the bronchial vessels in its middle part from the left gastric and the inferior phrenic arteries in its lower part (B) The venous return is through the inferior thyroid veins in its upper part through the azygos and the hemiazygos in its middle part and through the short gastric and the coronary veins in its lower part

thoracic vertebra it is crossed by the left bronchus, the bifurcation of the trachea being situated a little to the right of the median plane. Below this level the pericardium separates the esophagus from the left atrium. The right edge of the esophagus is closely related to the mediastinal aspect of the right lung, the left edge being related to the thoracic duct and to the left subclavian artery in the superior mediastinum. On a level with the fourth thoracic vertebra it is crossed by the aortic arch, and below that level is related to the descending thoracic aorta. Still lower it is related to the mediastinal surface of the left lung. Below the roots of the lung, the two vagi emerge from the posterior pulmonary plexus and come in contact with the esophagus. From this point the right vagus descends on the posterior surface of the esophagus and the left descends on its anterior surface. It is because of the close relationship of the pleura to the esophagus that an empyema may be a late finding in esophageal carcinoma.

In the abdomen the esophagus passes through the esophageal opening in the diaphragm, opposite the tenth thoracic vertebra and ends at the cardiac opening of the stomach opposite the eleventh thoracic vertebra. Its entire abdominal part is about an inch long and is covered by peritoneum in front and over its left side. Posteriorly it is in contact with the diaphragm and the left phrenic artery between it and the diaphragm.

VESSELS AND NERVES

The arterial supply (Fig. 290 A) is derived from the esophageal branches of the inferior thyroid artery in its upper part, in the thorax from the esophageal branches of the descending aorta, the right intercostal and bronchial arteries. The diaphragmatic and abdominal portions are supplied by the left gastric and left inferior phrenic arteries.

The venous return of the esophagus (Fig. 290 B) passes through the esophageal

venous plexus which is located in the submucosa and from which branches pass through the musculature to an intercommunicating venous plexus on the external surface. From the upper part of this latter plexus the blood drains to the inferior thyroid veins, then to the innominate veins and finally to the superior vena cava. From the middle portion of the esophagus, the veins drain to the azygos and the hemi-azygos. The lower part of the esophageal plexus drains into the coronary and the short gastric veins. In such conditions as cirrhosis of the liver there is an obstruction to the venous flow in the portal vein, and the blood is shunted to the superior vena cava via the coronary vein, the esophageal plexus and the azygos vein. This leads to the formation of esophageal varices.

The lymphatic drainage of the esophagus also may be subdivided into upper, middle and lower parts (Fig. 291). Lymph from the upper part drains into the para-tracheal and the inferior deep cervical nodes. The middle of the esophagus is drained by lymphatics which pass to bronchial nodes. The lower part is drained by vessels which travel to the posterior mediastinal glands and then to the celiac and the suprapancreatic nodes.

The nerves of the esophagus are derived from both the sympathetic and the parasympathetic systems (Fig. 292). The sympathetic innervation is derived from the cervical and the thoracic chains. In the neck these fibers arise from the superior and the inferior cervical ganglia; there may be a communication between the inferior ganglion and the recurrent laryngeal nerve. The ansa subclavia loops over the front of the subclavian artery and connects the middle and the inferior cervical ganglia. The superior ganglion connects with the ganglia of the vagus. In the thorax, the esophagus receives its sympathetic fibers from the upper thoracic ganglia and the greater and the lesser splanchnic nerves. In the abdomen a few fibers from the celiac plexus supply it.

its position so that in the fully developed stage it becomes almost transversely placed with its greater curvature facing downward and to the left and its lesser curvature facing upward and to the right. This

lesser peritoneal cavity (omental bursa) now forms a retrogastric pouch. The spleen and the splenic artery are on the left and the mesoesophagus has become so shortened that the esophagus lies almost




FIG. 292 The nerve supply of the esophagus, seen from behind. The sympathetic nerves are presented in green and the parasympathetic (vagus) fibers in yellow.

change is brought about by two combined axial rotations: the first takes place about the longitudinal axis of the stomach and the second about the anteroposterior axis. The first rotation (longitudinal axis) swings through an arc of 90° ; as a result of this the primitive left gastric surface is directed forward, the primitive right gastric surface, backward. The greater curvature, with its attached dorsal mesogastrium, to the left and the lesser curvature with its attached ventral mesogastrium to the right. The

against the posterior wall. The second rotation (anteroposterior axis) draws the pyloric end of the stomach to the right and the cardiac end to the left. The opening into the lesser sac is formed and is known as the epiploic foramen (of Winslow).

THE ADULT STOMACH

The stomach is the most dilated part of the digestive tube. It is approximately ten inches long, five inches wide, and has a normal capacity of about two pints. It is

The parasympathetic supply of the esophagus is received via the vagus nerves. The upper part is supplied through the recurrent laryngeal nerve. The midportion of the esophagus receives its vagus fibers from

The stomach is developed from that part of the foregut which is situated between the esophagus and the pharynx in front and the liver bud and the yolk sac behind. During the fourth week, the stomach is




FIG 291 The lymphatics of the esophagus. These may be divided into upper, middle and lower parts. They drain into paratracheal, bronchial and posterior mediastinal lymph nodes respectively.

the pulmonary plexuses which are located on the posterior part of each bronchus. Esophageal nerves also are derived from the vagi which supply the lower part.

STOMACH (VENTRICULUS OR GASTER)

EMBRYOLOGY

To understand thoroughly the surgical anatomy of the stomach and the maneuvers necessary for good surgical exposure, the embryology must be understood (Fig 293).

located in the neck at that time, the heart, the lungs and the stomach all lie near the exit of the vagal fibers from the central nervous system. During the sixth and the seventh weeks, the growth of the lung buds causes an elongation of the esophagus, and a backward migration of the stomach so that it changes from a cervical structure to one which is located in the lower thorax. This organ whose embryologic position has its long axis in the median plane and its greater curvature facing dorsally, changes

capable of great dilatation and may shrink into a more or less tubular form when empty. At its upper part it is approximated to the diaphragm by the esophagus at its lower end it is more or less fixed because

left part of the abdomen. It is largely under shelter of the ribs, from which it is separated by the diaphragm, the lower part of the left pleura and the left lung, overlap it. It lies, therefore, in the epigastric




FIG. 294 The adult stomach

of its connection with the duodenum it should be recalled however that the first inch of duodenum has some degree of mobility. The position and the shape of the stomach are not fixed since they vary considerably and are dependent upon the posture of the body the amount of the gastric contents the stage of gastric digestion the degree of contraction of both abdominal and gastric musculature the pressure of surrounding viscera respiration and gastric tonus. The long axis of the viscus passes downward, forward to the right and finally backward and slightly upward. Its shape has been likened to a "horn of plenty" as it lies in the upper

and the left hypochondriac regions in such a manner that only one sixth of this viscus is to the right of the midline. The stomach has two orifices, two curvatures, two surfaces and two incisurae. It is further subdivided into a fundus, a body and a pyloric portion.

The two incisurae or "notches" are the incisura angularis and the incisura cardiaca (cardiac notch) (Fig. 294). The left border of the esophagus is not continuous with the greater curvature as a straight line but meets it at an acute angle and forms the cardiac notch (incisura cardiaca). The incisura angularis (angular notch) is the deepest part of the concavity formed by the




FIG 293 Embryology of the stomach (A) Early development of the stomach as it is situated between the two leaves of peritoneum which form the dorsal and the ventral meso gastria (B) After the first rotation (longitudinal axis) in which the stomach swings through an arc of 90° The omental bursa is formed (C) After the second rotation (anteroposterior axis) this draws the pyloric end of the stomach to the right and the cardiac end to the left (D) After rotation is completed, and with the distal portion of the stomach removed to show the peritoneal relations

right and the greater on the left. The lesser curvature extends between the cardiac and pyloric orifices. It has vertical and horizontal parts which join at the incisura angularis and form a concave border in the form of a letter J. This curvature is continuous with the right margin of the esophagus and normally is overlapped by the liver. It affords attachment for the lesser omentum (gastrohepatic part) and contains the arterial circle formed by the right and the left gastric arteries. The greater curvature is convex and is four or five times as long as the lesser. Its upper third is directed toward the left, the middle third downward and to the left and the lower third downward and to the right. It starts at the incisura cardiaca, passes upward as high as the sixth left costal cartilage and ends at the pylorus. Along the lower part of the greater curvature the two layers of peritoneum which envelope the stomach pass downward as the greater omentum; on the left they pass backward toward the spleen as the gastro-splenic ligament. Although the lesser curvature is comparatively fixed owing to its attachments, the greater curvature is freely movable and its position alters as the stomach becomes full or empty, contracted or relaxed. When an individual is standing, the greater curvature may descend to the umbilicus or below it, but when lying down it is an inch or more above the umbilicus. In ptosis, the curvatures become more nearly vertical in position, and both curvatures descend, but in gastric dilatation the greater curvature is lower, without altering the position of the somewhat fixed lesser curvature. The right and the left gastroepiploic vessels form an arterial circle as they separate the two layers of peritoneum which are attached here.

The fundus is the rounded uppermost part of the stomach which is situated above the level of the esophageal junction. During life it probably always contains gas. It bulges upward into the left cupola of the diaphragm as high as the level of the fifth costal cartilage and therefore, is re-

lated to the heart, the pericardium and the left lung. This partly explains the increased cardiac activity and the accelerated respirations which are produced by the upward pressure of a full or distended stomach. The top of the fundus is almost on a level with the left male nipple.

The body of the stomach is the main portion which lies between the incisura angularis and the incisura cardiaca (between the fundus and the pylorus). Its general direction is oblique and to the left.

The pylorus is the point of junction between the stomach and the duodenum. The outer surface of the pylorus is marked by a circular constriction (duodenopyloric constriction). It lies in the transpyloric plane, about an inch to the right of the midline behind the quadrate lobe of the liver and in front of the neck of the pancreas. Its position usually is marked by a prepyloric vein (vein of Mayo) which descends over its anterior surface from the right gastric vein to the right gastroepiploic vein. However, this vein may be ill defined. The pyloric portion of the stomach is divided into proximal and distal parts. The proximal part represents a slight dilatation and is known as the pyloric antrum, the distal part is more tubular and is called the pyloric canal. The pylorus usually is considered as that terminal half inch of stomach which is in contact with and covered by the liver. Since the liver hides it from view and since most perforated peptic ulcers occur in this area, it becomes an area of great surgical importance. The pylorus has thicker walls than the rest of the stomach because of an increase in the circular muscle fibers. This thick muscular ring closes and relaxes the pyloric orifice and forms the pyloric sphincter. Normally, the pylorus is in a closed state but when open it is capable of admitting a finger tip. Despite its narrowness many cases are reported in which foreign bodies as large as pencils forks keys etc have been passed through it. Behind it is related to the portal vein, the hepatic artery and the common duct.

lesser curvature, therefore, it is the angle formed by the junction of the vertical and the horizontal parts of the lesser curvature. It is an important landmark in surgery of the stomach. If we locate the cardiac notch and draw a horizontal line across it and then drop an oblique line from the incisura angularis to the greater curvature, we shall have constructed the subdivisions of the stomach namely

- 1 The fundus is above the level of and to the left of the cardiac notch

- 2 The body is that part which lies between the cardiac notch and the incisura angularis

- 3 The pyloric portion, the remainder, is further subdivided into pyloric antrum and pyloric canal

The two orifices are the cardiac and the pyloric. The cardiac orifice (cardia) is the point of junction between the esophagus and the stomach. It marks that point at which the two curvatures begin. The esophageal end which has been referred to as the cardia is fixed to the diaphragm. It is about one inch to the left of the mid line about four inches behind the seventh left costal cartilage and is located at the level of the ninth thoracic spine. It presents the following boundaries: in front the left lobe of the liver; behind the diaphragm; to its right the esophageal branches of the left gastric vessels. The pyloric orifice is the communication between the stomach and the duodenum (duodenopyloric junction). This opening lies one inch to the right of the midline at the level of the first lumbar vertebra.

The two surfaces are anterior and posterior. The anterior surface is more convex than the posterior and is directed upward and forward. It lies below the lesser curvature and is covered by the left and also by a part of the right lobe of the liver; therefore in the epigastrium and below the xiphoid, the stomach is not in immediate contact with the anterior abdominal wall. Downward and to the left however there is a gastric triangle formed where this surface rests against the inner surface

of the abdominal wall. It is bounded on the left by the eighth and the ninth costal cartilages, on the right by the free margin of the liver and below by the transverse colon. It represents the most accessible portion of the stomach through an abdominal incision. In the left hypochondriac region, the stomach is covered not only by the ribs and the intercostal muscles but also by the left lung, the left pleural cavity and by the diaphragm. Thus penetrating wounds in this region may injure the pleura, the lung and the stomach; therefore gastric contents may escape into the pleural cavity. The so called space of Traube is situated in the left hypochondriac region and represents that portion of the stomach which is not covered by the neighboring viscera. It is bounded above, and to the right by the inferior margin of the left lung; below and to the right by the costal margin and posteriorly and to the left by the spleen. When the stomach is empty, the transverse colon is displaced upward and comes to lie in front of the contracted viscus. The posterior surface runs downward and backward and forms a large part of the anterior wall of the lesser peritoneal sac (omental bursa). This sac separates the posterior surface from the so called "stomach bed". The greater curvature is in relation to the transverse colon below and behind; the adjoining part of the posterior surface rests on the transverse mesocolon. Above the transverse mesocolon the stomach is in contact with the anterior surface of the pancreas; above the pancreas the stomach lies to the left of the median plane and rests upon the upper part of the left kidney and the left suprarenal gland. At a still higher level, the stomach (fundus) occupies the concave gastric area of the spleen and comes into relationship with the left half of the diaphragm. The normal stomach is separated anteriorly and posteriorly from the neighboring organs only by capillary spaces; this separation is effected in such a manner that direct contact is made.

The two curvatures are the lesser on the

Two layers of peritoneum envelope the stomach at the lesser curvature these meet and pass upward as the *lesser omentum*, which becomes attached to the liver and the diaphragm. This omentum has two parts the gastrohepatic and the duodenohepatic. The gastrohepatic part is avascular thin transparent and contains no important structures. The duodenohepatic part of the lesser omentum is thick and contains three vital structures the common duct the portal vein and the hepatic artery. The two layers of peritoneum which clothe the stomach meet at the greater curvature and pass downward as one great fold. Different parts of this fold receive different names according to their attachments the gastrophrenic ligament is attached to the diaphragm the gastrosplenic ligament to the spleen and the greater omentum to the transverse colon. That portion of greater omentum which is situated between the stomach and the transverse colon is known as the gastrocolic ligament (See Peritoneum p. 434).

VESSELS AND NERVES

The arterial supply to the stomach (Fig. 295) is derived from the celiac axis (p. 428). The lesser curvature is supplied by the *left gastric (coronary) artery* which reaches the cardiac end of the curvature along the left edge of the gastrohepatic omentum. It passes upward and to the left on the left crus of the diaphragm and then it turns over the upper border of the lesser sac to reach the stomach. It continues downward forward and to the right and passes along the curvature to anastomose with the *right gastric (pyloric) artery*, a branch of the hepatic.

The greater curvature is supplied by the following arteries

The *asa brevia* (short gastric) which are usually four or five in number arise from the splenic artery or from one of its terminal branches. These pass between the layers of the gastrosplenic ligament to the left end of the greater curvature and anas-

tomose with esophageal, gastric branches, and the left gastro-epiploic artery.

The *left gastro-epiploic artery* arises from the splenic near its termination passes in the gastrosplenic ligament to the stomach and then runs from left to right along the greater curvature between the layers of the gastrocolic ligament. It anastomoses with the right gastro-epiploic artery after sending branches to both surfaces of the stomach.

The *gastroduodenal artery* takes origin from the hepatic above the duodenum passes behind it between the neck of the pancreas and the duodenum and ends at the lower border of the first part of the duodenum by dividing into a *superior pancreaticoduodenal* and a *right gastro-epiploic*. The latter artery passes from right to left between the layers of the gastro-epiploic omentum sending gastric branches upward to both walls of the stomach, and ends by anastomosing with the left gastro-epiploic.

The veins of the stomach (Fig. 296) correspond to the arteries they terminate in the portal vein or the two large vessels which form it (superior mesenteric and splenic veins). They form two great loops one along the lesser curvature and one along the greater. Associated with these are some short gastric veins at the fundus. The loop on the lesser curvature is made up of the left gastric (coronary) and the right gastric veins. The *left gastric vein* accompanies the left gastric artery along the lesser curvature and receives tributaries from both surfaces of that organ and also from the esophagus. It continues backward in the left gastropancreatic fold to the posterior wall of the abdomen, then it turns downward and to the right and empties into the portal vein. The *right gastric vein* passes to the right along the lesser curvature of the stomach and at the pylorus turns backward and enters the portal vein. It receives venous blood from both surfaces of the stomach and from a vein which travels upward in front of the py-




FIG 295 The arterial supply of the stomach (A) The lesser omentum has been removed and a wedge of greater omentum has been lifted to show the relations of the vessels (B) The stomach has been elevated so that the posterior gastric surface is viewed

lorus, the prepyloric vein of Mayo. The latter vessel usually connects the right gastric and the gastroepiploic veins. The venous loop along the greater curvature lies between the layers of the greater omentum

tenesis which may be fatal (See I ophagus)

The lymph drainage of the stomach (Fig. 297) follows the three branches of the celiac axis (hepatic, gastric and splenic




FIG. 297 The lymphatics of the stomach (A) The arrows indicate the lymph drainage (B) Diagram of lymph zones and flow

and is made up of the left and the right gastroepiploic veins. The left gastroepiploic vein passes upward and to the left and empties into the splenic vein. The right gastroepiploic vein runs to the right, arches backward at the pylorus and usually enters the superior mesenteric. The left gastric vein (portal system) anastomoses with the lower esophageal vein; the latter in turn anastomoses with the upper esophageal veins which drain through the azygos into the caval venous system. In this way an important communication is formed between the portal and the caval systems (portacaval anastomosis). The veins at the inferior end of the esophagus may become distended and varicose in such conditions as cirrhosis of the liver (portal obstruction); their rupture results in severe hema-

mia. Hence there are three sets of lymph glands and ducts (1) hepatic (2) gastric and (3) pancreaticosplenic. The hepatic glands lie in the lesser omentum along the course of the bile ducts; part of them follow the course of the cystic and the hepatic arteries and are known as the cystic (hepatic) glands. They receive lymph from the liver and the gallbladder. Since this set of glands follows the course of the hepatic artery, or its branches, they give rise to a group of glands (subpyloric) which are located on the head of the pancreas and in the angle between the first and the second parts of the duodenum. They receive lymph from the right two thirds of the greater curvature of the stomach; this lymph travels via the inferior gastric glands. The hepatic group of glands therefore has three




FIG 296 The veins of the stomach (A) The liver has been sectioned to show the venous relations (B) The distal four fifths of the stomach and part of the pancreas have been removed

reaching the stomach. They divided the nerve patterns into four groups. Miller and Davis studied the vagus nerves below the level of the pulmonary plexus in 13 cadavers. They state that in only three instances were the nerve arrangements comparable with those described in the text

books as 'normal'. The remaining 10 cadavers showed marked variations.

The sympathetic nerve supply to the stomach is derived from the celiac (solar) plexus. This consists of a network of intercommunicating nerve fibers and two relatively large flat ganglia, the celiac ganglia




FIG. 298 The nerve supply to the stomach

separate sets associated with it a hepatic proper, following the duct a cystic, following the cystic artery and a subpyloric, following the gastroduodenal artery. The second group of glands is the gastric. It is divided into superior and inferior subgroups. The superior glands follow the course of the left gastric artery along the lesser curvature of the stomach and between the layers of the lesser omentum. The inferior glands follow the right gastroepiploic vessels between the layers of the greater omentum they are found mainly along the pyloric half of the greater curvature. The third group is the pancreaticocolic (splenic set). These follow the course of the splenic artery along the upper border of the pancreas. Some are found in the gastrosplenic ligament in relation to the short gastric branches of the splenic artery.

The efferent lymphatics from all of these glands pass to glands which surround the celiac axis in front of the aorta these are known as the celiac group or *preaortic glands*. The lymph drainage of the stomach can be represented diagrammatically in the following way the stomach is divided by an imaginary line in its long axis, two thirds being to the right of this line and one third to the left. A line is now constructed dividing the left third into two at the junction of its upper third and lower two thirds. In this way three areas of lymph drainage are marked out. Area 1 represents that part of the stomach which drains into the superior gastric glands. Area 2 drains into the inferior gastric and Area 3 drains via the pancreaticocolic glands. The celiac group empties into the receptaculum chyli after receiving lymph from all these areas.

Nerves The stomach is innervated by both the parasympathetic and the sympathetic nervous systems (Fig 298). The *parasympathetic nerve supply* is derived from the *vagus nerves* which originate in the medulla descend in the carotid sheath and into the thorax. On the posterior surface of the root of each lung each vagus

aids in the formation of the so called posterior pulmonary plexus, and from the e branches continue to the esophagus and the stomach. The nerves then pass through the esophageal orifice of the diaphragm and reach the respective surfaces of the stomach, where the right vagus is known as the posterior gastric nerve and the left vagus as the anterior, they pass along the lesser curvature of the stomach. Much recent work has been done on the anatomy and the distribution of the vagi. Probably our most reliable information comes from E. Perman who in 1935, performed a series of painstaking and accurate dissections dealing with this subject. His conclusions are interesting, instructive and apparently accurate. He concludes that both vagi reach the stomach through the lesser omentum and that they divide into branches with out the formation of a plexus of inter twining fibers. He states that anastomoses exist between the various branches, but that they do not lose their individuality as would be the case in a nerve plexus. The *left vagus nerve* sends branches to the liver and to the anterior wall of the stomach. Those branches traveling to the liver turn to the right pass through the lesser omentum and to the porta hepatis. The gastric branches divide into several smaller nerves which spread over the anterior wall and can be followed to the greater curvature. The *right vagus nerve* is arranged in a similar manner one part goes to the celiac plexus and the remainder supplies the posterior wall of the stomach. Perman was unable to follow branches of either the left or the right vagus into the greater omentum.

Recently papers have appeared dealing with the subject of the nerve supply to the stomach but they too are quite contradictory. Bradley, Small, Wilson and Walters examined 111 cadavers they concluded that there was a great variation in nerve pattern from the cardiopulmonary plexus to the stomach but the nerves were very constant in course and distribution after




FIG 299 The attachments of the stomach (omenta) (A) The early development of the greater omentum from the primitive dorsal mesogastrium (B) Later development, showing beginning fusion of dorsal mesogastrium and transverse mesocolon (C) Adult lesser and greater omenta The arrow indicates the foramen of Winslow

elongation of the primitive dorsal mesogastrium which does not cease growing with the completion of gastric rotation but continues until a broad sheet of peritoneum (floor of omental bursa) hangs down from the greater curvature of the stomach ventral to the coils of small intestine (Fig 299 A). After passing downward and being reflected upward it again reaches the dorsal wall of the abdomen at a point slightly above the line of attachment of the trans

verse mesocolon. It is thereby brought into contact with the upper layer of the transverse mesocolon with which it ultimately fuses (Fig 299 B). This brings the floor of the omental bursa into union with the transverse mesocolon. The dorsal mesogastrium and the transverse mesocolon fuse to form a common supporting membrane, the layers composing the dependent part of the bursa fuse with each other to obliterate the distal part of the lumen of the bur a

The plexus lies in front of the upper part of the abdominal portion of the vertebra around the celiac artery. The right and the left celiac ganglia lie on corresponding crura of the diaphragm, the right being situated behind the inferior vena cava. The fibers to the plexus reach it from the greater and the lesser splanchnic nerves. The greater splanchnic nerve on either side arises from the right sympathetic chain between the fifth and the tenth thoracic ganglia. The lesser splanchnic nerve also arises from the sympathetic chain in the region of the ninth and the tenth thoracic ganglia. The greater splanchnic nerve usually terminates in the upper end of the ganglion; the lesser splanchnic reaches the lower end. The celiac plexus supplies nerves which travel along the branches of the celiac artery; these fibers continue along the subdivisions of the three vessels and terminate in the stomach wall. In the gastric wall a plexus is situated between the muscle layers (myenteric plexus) and another in the submucosa (submucous plexus). They contain both sympathetic and parasympathetic fibers and from them terminal nerve fibers are supplied to the musculature and the glands of the stomach.

The stomach has four coats: serous, muscular, submucous, and mucous. The serous coat is an investment of peritoneum which completely covers the anterior and the posterior surfaces of the stomach; the only uncovered parts are the greater and the lesser curvatures and a small area to the left of the cardia which is in direct contact with the diaphragm. The muscular coat consists of three layers of involuntary muscle: an outer longitudinal, a middle circular, and an incomplete inner oblique. The longitudinal muscle is continuous with that of the esophagus; the circular layer becomes thickest in the region of the pylorus and forms the pyloric sphincter. In infants, excessive thickening of this circular layer at the pylorus may give rise to the condition known as congenital pyloric stenosis. The submucosa consists of an abundant, loosely arranged connective tis-

sue layer which contains vessels of considerable size. The toughness of this layer explains its ability to hold sutures. The mucosa is freely movable upon its underlying lax submucosa and, in the undistended state, presents numerous folds giving it a rugose appearance. These folds are arranged chiefly in longitudinal directions.

ATTACHMENTS OF THE STOMACH (OMENTA)

Peritoneal folds attach the stomach to the liver, the transverse colon, the spleen, the biliary ducts, the pancreas and the diaphragm. These folds are indicated by such names as omenta or gastric ligaments (Fig. 299). Omenta are defined as compound peritoneal folds which pass from the stomach to other intra-abdominal organs. These attachments are found only along the curvatures of the stomach. The two gastric surfaces, the anterior belonging to the general peritoneal cavity and the posterior belonging to the lesser cavity (omental bursa) are free and unattached. All omenta and gastric ligaments of the adult stomach originate from the midline mesenteries of embryonic life and the only way to gain a clear picture of these connections is through a visualization of the succeeding steps in gastric development.

The *lesser omentum* is a wide fold of peritoneum which is hidden by the left lobe of the liver. It is attached to the first inch of duodenum, the lesser curvature of the stomach, the diaphragm for half an inch between the esophagus and the upper end of the fissure for the ligamentum venosum, the bottom of that fissure and to the lips and the right end of the porta hepatis. Its right border is a free edge at which the two layers are continuous with each other (Fig. 295A). It forms the anterior boundary of the opening (foramen of Winslow) into the lesser sac which separates it from the inferior vena cava. Between its layers and at its right border are the common duct, the portal vein and the hepatic artery; the right and the left gastric arteries are found along the lesser curvature.

The *greater omentum* is for by the




FIG 299 The attachments of the stomach (omenta) (A) The early development of the greater omentum from the primitive dorsal mesogastrum (B) Later development showing beginning fusion of dorsal mesogastrum and transverse mesocolon (C) Adult lesser and greater omenta The arrow indicates the foramen of Winslow

elongation of the primitive dorsal mesogastrum which does not cease growing with the completion of gastric rotation but continues until a broad sheet of peritoneum (floor of omental bursa) hangs down from the greater curvature of the stomach ventral to the coils of small intestine (Fig 299 A) After passing downward and being reflected upward it again reaches the dorsal wall of the abdomen at a point slightly above the line of attachment of the trans

verse mesocolon It is thereby brought into contact with the upper layer of the transverse mesocolon with which it ultimately fuses (Fig 299 B) This brings the floor of the omental bursa into union with the transverse mesocolon The dorsal mesogastrium and the transverse mesocolon fuse to form a common supporting membrane the layers composing the dependent part of the bursa fuse with each other to obliterate the distal part of the lumen of the bursa

Fat is laid down in this omental apron which provides an insulating layer for the protection of the abdominal viscera.

The reflections of the gastric and the omental surfaces of the peritoneum as encountered by the surgeon can be traced easily both with regard to the greater and the lesser peritoneal cavities (Fig. 299 C). Beginning at the porta hepatis a peritoneal surface extends downward as the anterior leaf of the gastrohepatic (lesser) omentum passes over the ventral surface of the stomach and then downward as the anterior leaf of greater omentum. It then turns back and upward as the posterior leaf of the greater omentum until the transverse colon is reached.

Starting at the porta hepatis again an other peritoneal surface the dorsal leaf of lesser omentum passes downward covers the dorsal gastric wall and continues downward from the greater curvature of the stomach. It turns back and upward to the transverse colon as the innermost leaf of the greater omentum. It then passes over the anterior and upper walls of the transverse colon and backward to the posterior parietes as the uppermost layer of the transverse mesocolon. When illustrations of the ascending double layer are studied in the adult the two layers seem to diverge and enclose the transverse colon and continue as the mesocolon. This however is a wrong impression since the ascending double layer in the fetus passes up in front of the transverse colon to the posterior wall and to the lower border of the pancreas. On gaining the latter the anterior or inner serous layer of ascending omentum passes in front of the pancreas as the posterior wall of the omental bursa and then continues over the under surface of the liver to its starting point. The outer or posterior serous layer of ascending omentum passes behind the pancreas to reach the body wall. It is reflected from this to become continuous with the upper layer of the transverse mesocolon. The original fetal relations become the surgeon's cleav-

age planes which detach the greater omentum from the transverse colon and its mesentery.

These peritoneal reflections are related to the walls of the omental bursa in the following way: the pouch extends behind and below the liver and the stomach, above the transverse mesocolon within the greater omentum (when not fused) and behind the lesser omentum.

SURGICAL CONSIDERATIONS

GASTROJEJUNOSTOMY

Gastrojejunostomy is indicated in the patient who has a pyloric obstruction and low gastric acidity. It is used also as a palliative measure to provide relief for an obstructed pylorus (inoperable carcinoma) or as a preliminary procedure for future surgery. The operation may be done anterior or posterior to the transverse colon.

A posterior gastrojejunostomy (Fig. 300) is accomplished by passing the posterior wall of the stomach through a rent in the transverse mesocolon and performing an anastomosis between the stomach and a proximal loop of jejunum. The gastric site for the stomach should be placed at the most available and dependent part near the greater curvature and in line with the esophagus. The details and the structural orientation may be found in the description of gastric resection which follows. Following the anastomosis the rent in the transverse mesocolon is sutured to the posterior wall of the stomach to prevent internal herniation.

Anterior gastrojejunostomy (Fig. 301) is preferred by many surgeons. It is technically simpler, does not endanger the middle colic artery and does away with many of the hazards if reoperation becomes necessary. The anastomosis is placed on the anterior surface of the stomach and anterior to the transverse colon. Whether an anterior or posterior operation is done it is well to suture the greater curvature of the stomach to the distal end of bowel and the lesser curvature end of the stomach to the proximal end of bowel.




FIG. 300 Posterior gastrojejunostomy. (A) An incision has been made in the transverse mesocolon to the left of the middle colic artery. (B) The posterior wall of the stomach is delivered through the rent in the mesocolon. (C) The lesser curvature is approximated to the proximal jejunum and the greater curvature to the distal end of the jejunal loop. (D) The anastomosis. (E) The stomach is sutured to the mesocolon. (F) The completed anastomosis.




FIG. 301. Anterior gastrojejunostomy with entero anastomosis

GASTRECTOMY

Subtotal gastrectomy is done for carcinoma of the stomach and peptic ulcer. It is difficult to standardize such a procedure since every clinic has a technic of its own; however a standardized subtotal gastrectomy utilizing an end to side ante colic anastomosis will be described here (Figs. 302 and 303). Many men's names and modifications are associated with gastric operations but space does not permit a review of such procedures; these can be found in any standard surgical text.

The incision is usually one of the upper rectus incisions either placed to the right or the left of the midline depending upon the surgeon's preference and the site of the lesion. Operability must be determined first. This can be done by opening the hepatogastric part of the lesser omentum and placing a finger into the lesser peritoneal cavity. The index finger of the left hand serves admirably for this purpose; it makes its exit through an avascular point in the gastrocolic part of the greater omentum. A strip of gauze replaces the finger and is used for traction. This too greatly simplifies exposure of the duodenum and also protects the transverse mesocolon with

its middle colic artery which will lie behind the gauze traction tape. Mobilization of the greater curvature is accomplished next; it extends to the "avascular triangle" (p. 428) on the left and an inch distal to the pylorus on the right. After freeing the greater curvature of its vascular attachments and ligating the left and the right gastroepiploic arteries the lesser curvature is mobilized.

Mobilization of the lesser curvature already has been partially accomplished by the opening made in the hepatogastric part of the lesser omentum; this is continued by cutting and ligating the right gastric artery. After mobilization of the curvatures upward traction is maintained on the gauze tape so that the stomach may be separated from its attachments posteriorly to the pancreas (pancreaticogastric folds). In patients who have an adherent ulcer which is situated in the duodenum it is safer to expose and thus protect the common duct.

Division of the duodenum is accomplished next; the distal end is closed. Ligation of the left gastric artery is simpler and safer after the stomach has been severed from its duodenal attachment. The stomach then can be retracted to the patient's left side; this enables the surgeon to visualize the left gastric artery as it approaches the lesser curvature posteriorly.

Location of the ligament of Treitz is accomplished by making upward traction on the transverse colon thus stretching its mesocolon; the duodenojejunal angle and the ligament of Treitz will be found immediately to the left of the midline. To perform the antecolic operation, a long jejunal loop is required; this usually measures from 10 to 12 inches from Treitz's ligament. The jejunal loop is approximated to the posterior wall of the stomach near the line of resection. An anastomosis is performed which places the greater curvature of the stomach to the distal end of jejunum and the lesser curvature to the proximal end of the jejunal loop.




FIG 302 Subtotal gastrectomy (A) right upper rectus incision (B) the lesser and the greater curvatures have been mobilized and the right gastric, gastroduodenal and left gastro epiploic arteries have been ligated, (C) closure of the duodenal stump, (D) isolation of the left gastric artery




FIG 303 Subtotal gastrectomy (*continued*) (E) locating the ligament of Treitz and the duodenojejunal junction (F) the jejunum has been brought over the front of the transverse colon and approximated to the posterior wall of the stomach (G) the anastomosis, (H) the completed antecolic end to side gastrojejunostomy following resection of the involved stomach

TRANSABDOMINAL VAGUS NERVE SECTION (VAGOTOMY) (Fig. 304)

The abdominal approach to the gastric nerves (vagi) allows exploration of the abdominal contents and the lesion, it also facilitates the performance of a gastroenterotomy if pyloric obstruction is present or is likely to occur.

A long incision is necessary for proper exposure. A left muscle splitting rectus incision which commences in the angle between the xiphoid and the left costal cartilage and extends one or two inches below the umbilicus is utilized. The peritoneal cavity is entered and the left triangular ligament of the liver is exposed. This bloodless fold is severed and it then becomes possible to retract the left lobe of the liver to the right. The peritoneum covering the lower end of the esophagus is incised; the posterior mediastinum is entered and the lower three or four inches of the esophagus are mobilized and exposed. The vagus nerves are identified by palpation; they feel like gut cords which can be differentiated readily from the more yielding muscle of the esophagus. The left (anterior) vagus has a tendency to hug the esophagus but the right (posterior) vagus travels a slight distance away from it. By finger dissection the fibers are assembled into two main trunks comprising the right and the left vagi; these are ligated and divided. The position of the right and the left trunks below the esophageal hiatus is found to be remarkably constant; however, many times these nerves are numerous and communicating and their distribution does not follow a uniform pattern. At the conclusion of the operation the left lobe of the liver is permitted to fall into place; it has been found unnecessary to resuture the severed left triangular ligament.

CARCINOMA OF THE LOWER THIRD OF THE ESOPHAGUS AND THE CARDIAC END OF THE STOMACH (Fig. 305)

Most lesions involving the lower part of the esophagus and the cardiac end of the stomach can be removed through a com-

bined thoracic-abdominal approach. The incision affords an excellent exposure of the upper abdomen and the thoracic cavity, thus enabling more extensive resections. Humphreys, Garlock, Adams and Phemister, Marshall, Churchill and Sweet—all have applied some form of this approach for such lesions.

A left upper rectus incision is made; this extends from or below the umbilicus to the left costal arch. The peritoneal cavity is entered and a thorough exploration is carried out to determine the extent of the growth, fixation to vital structures and the presence or absence of metastases (liver, peripneumonic pelvic and diaphragmatic). Should the tumor prove to be operable, the incision is extended over the costal arch and then upward and outward into the seventh intercostal interspace. The costal arch is divided and the pleural cavity is entered. The intercostal muscles and the pleura are incised well past the inferior angle of the scapula, and the left leaf of the diaphragm is severed. The diaphragm is divided radially from the esophageal hiatus to its peripheral attachment. Large phrenic vessels are encountered; these should be properly isolated, divided and tied. The inferior pulmonary ligament is severed; this exposes an esophageal triangle which is bounded in front by the heart behind by the descending aorta and below by the diaphragm (Fig. 305 B). In this triangle the esophagus can be identified easily. The technic for the resection and anastomosis is essentially the same as that described under lesions of the mid-thoracic esophagus (Fig. 224). The diaphragm is repaired and the now somewhat enlarged esophageal hiatus is sutured to the stomach. The pleura, the intercostal muscles and the overlying soft tissues are approximated and the abdominal incision is closed in layers.

CLOSURE OF A PERFORATED PEPTIC ULCER (Fig. 306)

Most perforations of a peptic ulcer occur at the so-called "dollar area." This circu-

lar area, about the size of a silver dollar, is bisected by the pylorus. Normally, the right lobe of the liver covers this region and attempts to seal the perforation. To locate most perforated peptic ulcers, therefore, the right lobe of the liver should be retracted upward, and the stomach should be pulled gently in a downward direction.




FIG 304 Transabdominal vagus nerve section (vagotomy) (A) The incision commences in the angle between the xiphoid process and the left costal arch and ends an inch below the umbilicus (B) The left triangular ligament is exposed and made taut by gently pulling the left lobe of the liver to the right. It is severed (C) The left lobe of the liver is retracted to the right, and the peritoneum covering the lower end of the esophagus is incised (D) The esophagus is delivered, and the vagi are cut




FIG 305 The surgical treatment for carcinoma of the lower third of the esophagus and the cardiac end of the stomach (A) The incision (B) the esophageal triangle is bounded in front by the heart behind by the descending aorta and below by the diaphragm (C) the lower end of the esophagus and the upper end of the stomach are mobilized and removed, (D) anastomosis and repair of the diaphragm (E) closure

and to the left (Fig 306 B) If the perforation is not found with this maneuver then the lesser and the greater curvatures should be examined still failing to find the ulcer the gastroduodenal ligament must be

the ileum begins The lumen of the small intestine is widest in the duodenum and narrowest near the ileocecal valve for this reason a foreign body tends to become packed in the region of the latter The




FIG 306 Perforated peptic ulcer (A) The 'dollar-area' where most perforated peptic ulcers are found (B) Locating and repairing a perforated peptic ulcer

severed and the posterior wall of the stomach inspected Many methods of repair have been advocated these vary from a simple graft of omentum placed over the perforation to excision and closure

SMALL INTESTINE

The small intestine (duodenum jejunum and ileum) has an average length of 22 feet the extremes being 30 and 15 feet The division into jejunum and ileum is arbitrary, since there is no one point at which it may be said that the jejunum ends and

upper jejunum may be differentiated from the lower ileum by the fact that the number of arterial arcades and the amount of fat in the mesentery increases distally Clear spaces (lunettes) between the vessels approaching the bowel are present in the more proximal part of small bowel but are absent in the distal portion The jejunum fills the space below the transverse colon and the mesocolon, and more or less overlies the ascending and the descending colons it rests upon the iliac fossae and is related to the pelvic viscera The great

omentum hangs down from the transverse colon and depending upon its degree of development separates the intestines from the anterior abdominal wall. No small intestine occupies the fetal pelvis but in the adult pelvis the amount depends upon the state of distention of the bladder and the rectum and upon the position of the pelvic colon.

DUODENUM

Embryology The early development of the duodenum (Figs 307, 308 and 309) has been described on p. 424. The rotation of the intestines to their ultimate abdominal positions is produced by drawing the initial colic segment to the right so that the duodenojejunal junction and small intestines lie toward the left (Fig. 307). This places the duodenojejunal angle against the mesentery of the terminal intestine with which it fuses. The degree of fusion accounts for the fossae and the peritoneal folds which are found in this region. These fossae and folds are of surgical interest since deficient fixation of the angle increases the depth and the capacity of the fossae and loops of intestines may herniate into them and become strangulated. Hyperfixation of the duodenojejunal angle may fix the duodenum so firmly that it becomes kinked and does not empty properly. The descending duodenum and part of the transverse duodenum fuse with the primitive right parietal peritoneum; the remainder of the transverse duodenum and the ascending duodenum fuse with the descending mesocolon and the duodenojejunal angle fuses with the transverse mesocolon. The superior part of the ascending mesocolon forms a fusion fascia with the anterior part of the mesoduodenum (p. 447). Proper cleavage planes can be found easily and surgical mobilization can be accomplished readily if these embryologic details are kept in mind.

Adult Duodenum The duodenum (Fig. 310) receives its name because at first it was thought to be 12 inches long, in re-

ality it is closer to 10 or 11 inches in length. Not only is it the first and shortest part of the small bowel, but also it is the lightest, thickest and most fixed of the three parts. It extends from the pylorus to the duodenojejunal junction making a C-shaped curve; the concavity of the curve is directed upward and to the left and is occupied by the head of the pancreas. The duodenum may be traced upward backward and to the right then downward until it is crossed by the transverse colon. The portion which comprises the entire first and upper half of the second part lies in the supracolic compartment. To visualize further the duodenum it is necessary to turn the greater omentum upward and displace the coils of jejunum and ileum downward and to the left. Then the duodenum can be traced downward and horizontally to the left on the upper part of the posterior wall of the right infracolic compartment. It disappears behind the root of the mesentery; this portion is difficult to demonstrate because it lies behind the peritoneum of the posterior abdominal wall. Anteriorly it is related to coils of the small intestine which separate it from the transverse mesocolon. To its right side the lower pole of the right kidney is found. The rest of the duodenum lies in the left infracolic compartment and to visualize it the coils of jejunum and ileum must be drawn upward and to the right. This portion is identified easily and can be traced upward close to the root of the mesentery and to the duodenojejunal flexure. Here it bends forward and downward and becomes continuous with the jejunum. The flexure usually lies to the left and on a level with the second lumbar vertebra. Therefore the duodenum is found in the supracolic and both infracolic compartments. The 'C' which the duodenum forms is covered anteriorly and on its convexity by peritoneum except where the transverse colon crosses the second part and holds the peritoneum away. The posterior surface and concavity of the 'C' are devoid of peritoneum. Approximately the




FIG 307 Embryology (A) Rotation of the umbilical loop has been completed, and the ascending and the transverse colon segments have been formed. The right portion of the transverse mesocolon is the upper limit of fusion between the ascending mesocolon and the right primitive parietal peritoneum; the left portion of the transverse mesocolon is the upward limit of fusion between the descending mesocolon and the left primitive parietal peritoneum. The duodenojejunal angle is to the left of the midline and rests against the mesentery of the transverse colon. (B) The descending duodenum and part of the transverse duodenum fuse with the right parietal peritoneum; the remainder of the transverse duodenum and the ascending duodenum fuse with the descending mesocolon. (C) Final stage, following posterior peritoneal fixation and fusion.

first inch of the first part is almost entirely covered by peritoneum. In the region where the bile duct enters the second part of the duodenum diverticula devoid of a peritoneal covering may occur. This is of surgical importance since the removal of such a diverticulum is associated with the risk of peritonitis because of infection in the retroperitoneal tissues. Because of the C-shaped curve which it makes its beginning and end are close together. It lies on

the posterior wall of the abdomen above the level of the umbilicus and is almost entirely in the right half of the abdomen.

For convenience of description the duodenum is divided into the following four parts:

- 1 Superior part—about 2 inches long
- 2 Descending part—about 3 inches long
- 3 Horizontal part—about 4 inches long
- 4 Ascending part—about 1 inch long

The first (superior) part begins at the




FIG 308 Embryology (A) Early stage of development before fusion has taken place (B) After fusion of the ascending mesocolon with mesoduodenum posterior fixation of the colon is also shown

pylorus on a level with the body of the first lumbar vertebra and passes backward, upward and to the right. Here it is in close relation with the liver, it ends at the neck of the gallbladder by bending sharply to

the left. The lesser omentum passes from its superior border to the liver, and the greater omentum hangs from its lower border. Posteriorly, it is separated from the neck of




FIG 309 Embryology of the duodenum (A) Cross section through the duodenum and the mesoduodenum before rotation of the gastroduodenal segment. The arrow presents the direction of rotation against the right primitive parietal peritoneum. (B) The same as 'A' after fusion has taken place. The surgical cleavage plane for mobilization of the duodenum and the head of the pancreas is indicated.

become the second part. After death, this area usually is stained green by bile that leaks through the walls of the gallbladder. Since its first inch is clothed on the front and the back with peritoneum, it is con-

the pancreas by the lesser peritoneal sac. anteriorly it is related to the quadrate lobe of the liver. The first inch of part one of the duodenum can be moved with the stomach. The second inch is covered with peri-




FIG 310 The duodenum (A) The relations of parts one and two of the duodenum (B) The four parts of the duodenum are shown and the peritoneal relations of each are presented

toneum only above and in front where it is related to the liver and the neck of the gallbladder posteriorly it is directly related to the gastroduodenal artery, bile ducts portal vein and part of the neck of the pancreas (Fig 312) Inferiorly it is related directly to the head of the pancreas The portal vein and the common duct sepa

rate it posteriorly from the inferior vena cava (Fig 310) Since this part of the duodenum takes a backward rather than a sideward course the structures related to it lie medial rather than behind it The intimate relation between the first part of the duodenum and the gallbladder explains the adhesions which exist between them when

pylorus on a level with the body of the first lumbar vertebra and passes backward, upward and to the right. Here it is in close relation with the liver. It ends at the neck of the gallbladder by bending sharply to

be low. The lesser omentum passes from its superior border to the liver, and the greater omentum hangs from its lower border. Posteriorly, it is separated from the neck of




FIG 309 Embryology of the duodenum (A) Cross section through the duodenum and the mesoduodenum before rotation of the gastroduodenal segment. The arrow presents the direction of rotation against the right primitive parietal peritoneum. (B) The same as 'A' after fusion has taken place. The surgical cleavage plane for mobilization of the duodenum and the head of the pancreas is indicated.

become the second part. After death this area usually is stained green by bile that leaks through the walls of the gallbladder. Since its first inch is clothed on the front and the back with peritoneum, it is con-

the pancreas by the lesser peritoneal sac anteriorly. It is related to the quadrate lobe of the liver. The first inch of part one of the duodenum can be moved with the stomach. The second inch is covered with peri-

border of the duodenum to the root of the transverse mesocolon

The *duodenojejunal flexure*, although usually retroperitoneal, may penetrate into the root of the transverse mesocolon (Fig 311). It usually lies to the left of the midline between the first and the second lumbar vertebrae but may approach the midline or begin at the middle of the second or even the third lumbar vertebra. Its relation to the transverse mesocolon depends on the length of the ligament of Treitz (Fig 311). Posteriorly it is in relation to the lumbar portion of the diaphragm above, it is related to the inferior border of the pancreas and it is embraced by the concavity of the arch formed by the inferior mesenteric vein before it terminates below and behind the pancreas (Figs 310 B, 313 A and B).

The flexure is related to the internal border of the left kidney on its left and anteriorly to the posterior wall of the stomach from which it is separated by the transverse mesocolon. It is overlapped somewhat by the pancreas. The duodenojejunal flexure is fixed by the so called muscle or ligament of Treitz.

The *suspensory ligament (muscle) of Treitz* is a band of fibrous muscular tissue which extends from the duodenojejunal angle and the ascending portion of the duodenum to the right pillar of the diaphragm. It is triangular in shape and originates from a broad base upon the superior border of the duodenojejunal angle. It passes upward behind the pancreas and in front of the aorta. It is better developed in the more muscular individuals and fixes the duodenojejunal angle to the posterior abdominal wall. The length of the ligament of Treitz determines whether the duodenum will be "U" shaped or "C" shaped (Fig 311). If the ligament is long the duodenojejunal flexure lies below the transverse mesocolon and the "C" shaped duodenum results. If the ligament is short the duodenojejunal flexure lies above the transverse mesocolon, and the "U" shaped duodenum is found.

The surgeon should be able to locate this




FIG 311 The ligament of Treitz (A) The short type of ligament which pulls the duodenojejunal flexure above the transverse mesocolon and results in a "U" shaped duodenum (B) The long type of ligament which allows the duodenojejunal flexure to lie below the transverse mesocolon and results in a "C" shaped duodenum

ligament rapidly and in this way orient himself and "run" the intestinal tract (jejunum ileum) in search of pathology, he is also able to select that segment of small bowel which he wishes to utilize in a gastrointestinal anastomosis. The ligament and the angle are found in the following way: the surgeon's left hand grasps the

either is diseased, and also explains the spontaneous passage of gallstones into the duodenum (autocholecystoduodenostomy) The term "duodenal bulb" applies to the first inch of duodenum

The *second (descending) part* passes vertically downward in front of the hilum and the adjoining part of the anterior surface of the right kidney. It descends to the level of the third lumbar vertebra, bends sharply to the left and becomes the third part. Part two of the duodenum is crossed by the transverse colon; the colon at this point may or may not have a mesentery. Only parts of the anterior surface above and below the transverse colon are covered by peritoneum (Fig 310 B). Above the attachment of the transverse colon the descending duodenum lies in the supramesocolic compartment; below this attachment, it lies in the inframesocolic compartment where it is related to the ascending colon. Above the transverse colon it is related to the ascending colon, and anteriorly it is related to the gallbladder and the right lobe of the liver. Below the transverse colon it is related anteriorly to the jejunum; the head of the pancreas lies to its medial side, and the ascending colon, the hepatic flexure and the right lobe of the liver to its lateral side, in that order from below upward. Posteriorly, it rests upon the psaos major muscle being partly separated from it by the renal vessels and the ureter. The bile duct and the pancreatic ducts enter this part on the posteromedial surface a little below its middle (Fig 372). The accessory pancreatic duct opens about three quarters of an inch above (cephalad) the openings of the common bile and the main pancreatic ducts. Because of its peritoneal attachments this part of the duodenum is quite firmly fixed in its position.

The *third (horizontal) part* of the duodenum is about four inches long and passes horizontally and to the left. Since it is crossed by the root of the mesentery it is found in the right and the left infracolic compartments. From right to left it crosses

in front of the right psaos muscle, the ureter, the inferior vena cava and the abdominal aorta, it ends to the left side of the body of the third lumbar vertebra. Its upper border is related to the head of the pancreas and its lower border to the jejunum. Anteriorly it is crossed about its middle by the superior mesenteric vessels as they pass to the root of the mesentery. Therefore, it crosses through a vascular angle which is formed by the superior mesenteric vessels in front and the aorta behind. The superior mesenteric vessels may compress the duodenum so that a dilatation of the stomach or a duodenal ileus may result. The peritoneum covers it anteriorly except where the root of the mesentery crosses it (Fig 310 B). To the right of the mesentery it is covered by loops of jejunum which separate it from the transverse colon. It finally bends upward to become the fourth part.

The *fourth (ascending) part* is a little more than an inch long and represents the shortest part of the duodenum. It turns upward along the left side of the aorta on the left psaos muscle and ends about an inch to the left of the median plane at the level of the second lumbar vertebra. At this point it bends sharply forward to form the duodenojejunal flexure, here it becomes continuous with the jejunum. Anteriorly it is related to the root of the mesentery and the coils of the jejunum, posteriorly to the medial border of the left psaos muscle, the left renal and spermatic (ovarian) vessels, on its right to the vertebral column and on its left side to the proximal coils of jejunum. This part of the duodenum sometimes overlaps the pelvis of the left kidney. Internally it lies along the aorta and is adherent to the pancreas, externally, it is found on the inner side of the left kidney. A vascular arch is found in the space which separates the duodenum from the kidney, it has been called the *vascular arch of Treitz*. This arch is formed by the left colic artery and the inferior mesenteric vein as they ascend together near the left

tro epiploic and the anterior superior pancreaticoduodenal arteries. The gastroduodenal artery gives off a posterior superior pancreaticoduodenal artery as it passes dorsally to the superior margin of the duodenum. The first part of the duodenum receives two smaller branches, namely, the *supraduodenal artery* to the superior wall and the anterior surface, and the *retroduodenal artery* which arises about one half inch above the bifurcation of the gastroduodenal and supplies the lower two-thirds of the posterior wall. It sometimes extends as far as the second part. The remainder of the first part of the duodenum is supplied by branches from the right gastroepiploic and the superior pancreaticoduodenal arteries. The superior anterior and posterior pancreaticoduodenal arteries anastomose with corresponding anterior and posterior inferior pancreaticoduodenal arteries from the superior mesenteric. In this way two arterial arcades are formed one on the posterior surface of the head of the pancreas and the other on the anterior surface. They are called respectively the *posterior* and the *anterior arcades* of the pancreas. The two inferior pancreaticoduodenal arteries arise from a common trunk from the superior mesenteric called the *common inferior pancreaticoduodenal artery*. From the two arterial arcades the duodenum receives anterior and posterior sets of vasa recta (Fig 312 B). Shapiro and Robillard have stressed the possible dangers (blowouts and leakage) which might result from injury and ligation of the vasa recta during a too radical mobilization of the duodenal stump from the pancreas in the course of a gastric resection. They further stress the futility of thorough ligation for the control of hemorrhage from a duodenal ulcer stating that such a procedure is tantamount to complete devascularization of the duodenum and the head of the pancreas.

The *nerves* are derived from the celiac and the superior mesenteric plexuses and follow the course of the arteries.

The *lymphatics* of the duodenum are closely related to those of the pancreas. There are anterior and posterior sets of glands which drain into the superior pancreatic and pancreaticoduodenal lymph glands on the anterior and the posterior aspects of the groove between the duodenum and the pancreas. The efferent vessels from these glands pass in two directions upward to the hepatic lymph glands and downward to the preaortic lymph glands around the superior mesenteric artery. There are also some communications with the lymphatics of the ascending colon and the appendix.

Duodenal Fossae There are *five duodenal fossae* which may be encountered (Fig 313).

- 1 The *paraduodenal fossa* lies to the left of the duodenojejunal flexure and opens to the right and upward. It occurs in about 20 per cent of people and rarely, if ever, exists with any other type of duodenal fossa. It is bounded on the right by the aorta, on the left by the kidney above by the pancreas and the renal vessels and anteriorly by the inferior mesenteric vein which runs in the anterior wall of the fossa. This anterior relationship is of surgical importance since a hernia into this fossa may press upon the inferior mesenteric vein and produce hemorrhoids. In case this fossa is the site of a strangulated hernia its surgical enlargement should be brought about in a downward direction in this way injury to the inferior mesenteric vein is avoided (Fig 313 A).

- 2 The *superior duodenojejunal fossa* faces downward is about one inch in depth and is in front of the second lumbar vertebra.

- 3 The *inferior duodenojejunal fossa* is directed upward and is in front of the third lumbar vertebra. The last two mentioned fossae are formed by two peritoneal folds which pass to the left from the terminal portion of the duodenum. The inferior mesenteric vein passes along their left extremities.




FIG 312 The arterial blood supply of the duodenum (A) The formation of the anterior and the posterior arterial arcades is shown. The arrow and the horizontal line indicate the level at which the cross section shown as 'B' was taken (B) Cross section showing the intimate relation between the duodenum, the pancreas and the common ducts. Anterior and posterior vasa recta are shown.

greater omentum and the transverse colon, and maintaining upward traction on these structures the transverse mesocolon is made taut. The right hand then is placed upon the lower surface of the stretched transverse mesocolon and follows it posteriorly to its attachment in the region of the first lumbar vertebra. The hand is placed to the left and immediately encounters the duodenojejunal angle with the ligament of Treitz immediately above it.

Vessels Nerves and Lymphatics Since the relationship of the duodenum to the head of the pancreas is so intimate their

blood supplies naturally overlap. Many vascular patterns and anomalies have been described nevertheless the most constant vascular patterns and those of greatest surgical significance are described herein. Pier son has made an accurate study of this region, and much of his material is of practical value. The *gastroduodenal artery* is a branch of the hepatic artery and arises dorsal and superior to the pyloroduodenal junction (Fig 312). It courses downward, medial to the common duct and terminates at the lower border of the first part of the duodenum by dividing into the *right gas*

They comprise the second and the third portions of the small intestine, they also make up about two fifths of the total length which is the jejunum, and three fifths the ileum. There is no sharp dividing line

being narrowest at its termination. This is of practical importance since foreign bodies are usually stopped at this narrowest part which consists of the last 6 to 12 inches of ileum. The jejunum-ileum is




FIG 314 The jejunum-ileum (A) The normally placed coils of jejunum-ileum the jejunum is above and to the left, and the ileum is below and to the right (B) The stretched root of mesentery (C) The jejunum-ileum has been removed, and the convolutions of the mesentery are shown

between these two parts of bowel, they differ from the duodenum in that they are not fixed but are suspended from the posterior wall by a fold of peritoneum, the mesentery (Fig 314 B). The caliber of the lumen of the small bowel is not uniform, but diminishes from above downward,

completely covered with peritoneum except along its line of attachment to the anterior border of the posterior mesentery. To accommodate the great length of small intestine the mesentery is thrown into extensive series of convolutions (Fig 314 C). The posterior line of attachment of the mesen-




FIG 313 The five duodenal fossae (A) The paraduodenal fossa. Enlarge-
ment of this fossa must be made in a downward direction to avoid the inferior
mesenteric vein (B) The superior and the inferior duodenojejunal fossae formed
by two peritoneal folds (C) The inferior duodenal fossa extends behind the
third part of the duodenum (D) The mesentericoparietal fossa is located
behind the first part of mesojejunum

4 The *inferior duodenal fossa* is rarely seen. If present, it extends behind the third part of the duodenum.

5 The *mesentericoparietal fossa* (Waldeyer) is located behind the first part of the mesojejunum. It lies immediately behind the superior mesenteric artery and below the duodenum. Its orifice faces to the left. In front, it is bounded by the superior mesenteric artery and behind by the lumbar vertebrae. A swelling produced by a herniation of small bowel into it would occupy the right half of the abdominal

cavity. The orifice of this fossa is so large that small gut may enter or leave it without causing symptoms or strangulation. The bowel can be withdrawn from this fossa without much difficulty. Should enlargement become necessary, the relationship of the superior mesenteric vessels must be kept in mind and the fossa incised only in a downward direction.

THE JEJUNO ILEUM

The jejunum and the ileum together measure about 20 feet in length (Fig 314).

and become closely picked below the duodenal papilla. They are equally close in the upper part of the jejunum but toward its lower end they diminish. In the ileum they become more widely separated and finally in the terminal portion are entirely absent. These plicae increase the area of absorptive surface without increasing the length of the gut. Small collections of lymphoid tissue form tiny elevations in the mucous membrane. They are known as solitary lymphatic nodules; however larger collections of lymphoid tissue constitute the aggregated lymphoid nodules (Peyer's patches) which are most numerous toward the terminal portion of ileum where they form elongated oval areas on the antimesenteric border of the bowel. They are absent in the upper two thirds of the jejunum; they are best marked in younger individuals and tend to disappear as one grows older.

Is it jejunum or ileum? This question may be answered if a few differential anatomic points are observed. The upper part of the small intestine is thicker and its diameter becomes diminished from above downward. The blood vessels of the small bowel are larger proximally; therefore there are only primary vascular loops which are associated with vasa recta (some 3 to 5 cm long (Fig 315)). Distally, secondary vascular loops or arcades are seen; these produce smaller windows (lunettes) and shorter vasa recta; the latter being approximately 1 cm in length. The more distally small bowel is observed, the greater is the amount of fat; proximally it is quite easy to see through the windows formed by the vascular loops, whereas the fat prevents these windows from being transparent in the distal ileum.

A fold of peritoneum which connects the intestines to the posterior abdominal wall and conveys vessels and nerves to and from it is called a mesentery. The *mesentery proper* connects the coils of jejunum and ileum to the posterior abdominal wall below the line of attachment of the trans-




FIG 316 The root of the mesentery. In its oblique course downward the root of the mesentery crosses the third part of the duodenum, the abdominal aorta and the right psoas muscle.

verse mesocolon. Its *root* or *radix* (parietal attachment) extends from the left side of the second lumbar vertebra downward and to the right to the right sacroiliac joint, a distance of about 6 inches. In its oblique course downward and to the right the root of the mesentery crosses in front of the third part of the duodenum, the abdominal aorta and the right psoas muscle (Fig 316). Although the root of the mesentery measures only 6 inches in length, it accommodates 20 feet of small bowel; this is accomplished by its folding and ruffling. The small intestine is so mobile and convoluted that the surgeon may explore many feet without being able to determine whether he is progressing toward the duodenum or toward the ileum. By the simple procedure of placing a hand on each side of the mesentery and drawing the hands forward from the root to the intes-

tery begins around the descending aorta opposite the body of the second lumbar vertebra, deviates obliquely to the right at an angle of about 45° and terminates in the region of the right sacro iliac joint

a point 6 feet from the duodenojejunal flexure and continue to a point 11 feet from that flexure, this is due to the great length of the mesentery to this part of bowel. These are the parts of the small bowel which are




FIG 315 Localization of the jejunum (A) About 3 feet from the duodenojejunal flexure, primary loops with long vasa recta are shown (B) About 7 feet from the duodenojejunal flexure secondary vascular loops are present with "lunette" formation (C) Ten to 12 feet from the duodenojejunal flexure tertiary vascular loops are present and increased mesenteric fat is seen (D) In the terminal ileum the vascular arches and "lunettes" are obscured by fat

Since the coils of the small intestine are movable, their position is variable the jejunum tends to be above and to the left and the ileum below and to the right. The coils are hemmed in on the right above and to the left by the colon and are related posteriorly to the posterior abdominal wall and the retroperitoneal structures also they are in relation anteriorly to the anterior abdominal wall and the greater omentum the latter as a rule being spread over them. The two parts of the small bowel which lie in the pelvis are

- 1 The terminal ileum (except the last two inches) which is fixed in the right iliac fossa

- 2 The 5 feet of small gut which begin at

most likely to be affected in pelvic peritonitis and become adherent to pathologic adnexae they are the most probable sites for small bowel intestinal obstructions

From the pylorus to the ileocecal valve the small intestine has a complete external muscular coat of longitudinal fibers and an internal muscular coat of circular fibers. The mucous membrane, however, differs in different parts of the gut. In the first part of the duodenum the inner lining is smooth, but the branched tubular duodenal glands are numerous especially near the pylorus. The plicae circulares are true infoldings of mucous membrane which are set at right angles to the long axis of the gut they begin in the second part of the duodenum

the mesentery proper. Removal of a cyst or a solid tumor of the mesentery endangers the blood supply to the intestine.

In traversing the infracolonic compartment, the mesentery converts it into two parts: the one to the right is smaller and terminates in the right iliac fossa; the other to the left is larger and passes into the true pelvis.

The arteries which supply the jejunum arise from the left side of the *superior mesenteric artery* (Fig. 317). The latter arises behind the neck of the pancreas and passes in front of the uncinate process; in this way it reaches the third part of the duodenum in front of which it crosses and enters the root of the mesentery. It continues downward into the root of the mesentery and passes in front of the inferior vena cava, the right psoas muscle and the right ureter; it ends by anastomosing with one of its own branches, the *ileocolic artery*.

Close to the origin of the superior mesenteric artery the *inferior pancreaticoduodenal artery* is given off. It divides into anterior and posterior branches which connect with similar branches of the *superior pancreaticoduodenal artery*, thus forming two arches, one in front of and the other behind the head of the pancreas (Fig. 312). Each arch supplies branches to the head of the pancreas and sends a row of straight vessels (*vasa recta*) to the second and the third parts of the duodenum. Between the two rows the common bile duct descends. Therefore these arches constitute the anastomosis which exists between the superior mesenteric artery and the celiac axis.

The *jejunal and ileal arteries* constitute twelve or more branches which spread out from the left side of the superior mesenteric artery and pass between the layers of mesentery to reach the jejunum. They unite and form loops or arches from which the straight terminal branches (*vasa recta*) alternately pass to opposite sides of the jejunum and the ileum. In the intestinal wall the vessels run parallel with the




FIG. 318. Meckel's diverticulum. (A) view of the interior of the diverticulum with possible locations of ectopic gastric or pancreatic tissue. (B) external view.

circular muscle coat, traversing the serous, muscle and submucous layers successively. The *vasa recta* do not anastomose themselves but pass to the submucous plexus where their ramifications anastomose freely. They are believed to be end arteries.

The *superior mesenteric vein* returns blood from the small intestines and the ascending and transverse colon. Behind the neck of the pancreas this vein unites with the splenic vein to form the portal vein (Fig. 342).

The *lymphatics* of the jejunum drain into the superior mesenteric glands within the mesentery; here they are closely related to the arterial arches. The glands may be involved in mesenteric lymphadenitis, tuberculosis and other inflammatory as well as neoplastic conditions.

The *nerve supply* to the small intestine is derived from the celiac plexus of the sympathetic system and from the vagus nerve. In small bowel lesions referred pain




FIG 320 The closed 'aseptic' anastomosis.

tissue appear at two sites namely at the blind end of the diverticulum or at its base where it attaches to the ileum. Therefore it is important that a wide excision of the base or even a resection of the attached ileum be done. When a simple diverticulectomy is performed the enzymes may be activated by the surgery and the sutures (catgut) are digested; this may result in a fatal peritonitis.

SURGICAL CONSIDERATIONS

OPEN AND CLOSED ANASTOMOSES

Open Method of Small Bowel Anastomosis (Fig 319) Removal of part of the small intestine (enterectomy) is done for tumors, trauma and gangrene of the bowel. Clamps are applied in such a way that the tissue to be removed is placed in crushing

clamps, and the tissue which remains for the anastomosis is held by nontraumatizing clamps. Following removal of the mass, the intestinal clamps are placed side by side and a posterior sero-serous suture line either interrupted or continuous is placed (Fig 319 B). A Maunsell mesenteric stitch is placed and a traction suture is utilized on the antimesenteric borders of the bowel. The Maunsell stitch is important since it protects the mesenteric triangle which is deficient of peritoneum and also ligates the vessels along the mesenteric border. A posterior layer of through and through sutures then is placed (Fig 319 C). This is followed by an anterior through and through suture (Fig 319 D). The clamps are removed, and the anterior sero-serous suture completes the anastomosis (Fig 319 E). The rent in the mesentery is closed




FIG 319 Open method of small bowel anastomosis (A) clamps placed and bowel resected (B) posterior serous layer, (C) posterior through and through layer, (D) anterior through and through layer (E) anterior serous layer

is experienced in areas of the ninth tenth and the eleventh thoracic nerves. Pain usually is about the umbilical region and may spread to the lumbar region and the back.

MECKEL'S DIVERTICULUM

This outpouching resembles the finger of a rubber glove extending at right angles from the terminal ileum opposite its mesenteric attachment (Fig 318). Such a diverticulum usually occurs within the terminal *two* feet of ileum. It is usually *two* inches long, is present in *two* per cent of all people and occurs *two* to one in favor of males.

In the human embryo the convexity of the umbilical loop of the primitive gut communicates with the yolk sac by the omphalo (vitello) intestinal duct. This duct

normally becomes occluded and should disappear entirely; however all or part of it may persist. If the duct remains completely patent a congenital fecal fistula results at the umbilicus. The commonest anomaly of this duct is a blind diverticulum which is attached to the ileum. This has been described as a Meckel's diverticulum. As a rule it has the same diameter as the gut from which it arises; its end may be free or attached to the umbilicus by a fibrous cord. The vessel which accompanies such a diverticulum is the terminal part of the superior mesenteric artery, therefore a Meckel's diverticulum has an artery of its own. It is important to remember that such diverticula may have ectopic pancreatic or gastric tissue contained within. These islands of digestive




FIG. 321 Embryology of the large bowel. Sections 1a and 2a are cross sections before posterior fixations have taken place. Sections 1b and 2b are corresponding cross sections after posterior fixations have taken place.

THE LARGE INTESTINE PROPER

The differences between the small and the large intestines may be listed as follows:

1 The large bowel is sacculated, the small bowel is smooth

2 The large bowel has *taeniae coli*; the small bowel has none. One of the *taeniae* lies along the line of the mesenteric attachment and the other two are equidistant from it and from each other. All three

Closed 'Aseptic' Method of Anastomosis Four crushing clamps are placed on the bowel and the diseased mass is resected (Fig 320) A continuous or interrupted suture method may be used the former will be described The suture starts on the side opposite the surgeon and passes at right angles to the clamp, following this the suture passes parallel with the clamps and ends on the opposite side to which it started The handles are reversed and the same type of suture is placed again The forceps are removed, and the sutures are tied The lumen is opened by finger pressure to either side of the invaginated tissue The operation is completed by a layer of interrupted or continuous seroserous sutures and the margins of the mesentery are sutured

ENTEROSTOMY

In this operation an artificial fistulous opening is created between the lumen of the small bowel and the body surface It may be temporary or permanent If jejunum is used the operation is known as a jejunostomy if the ileum is used it is called an ileostomy Many methods and modifications have been described but they all utilize the principles of opening the bowel transfixing the tube and peritonizing with some method of invagination or tunneling

LARGE INTESTINE (COLON)

EMBRYOLOGY

Following the stage of the formation of a distinct intestinal loop a torsion takes place about the superior mesenteric artery (p 413, Fig 286) Following this primary torsion the small intestine begins to lengthen so rapidly that the abdominal cavity can not retain it hence a temporary but normal umbilical hernia results By contrast the large intestine and its associated mesentery grow relatively little at this period In embryos of ten weeks the abdominal cavity has increased sufficiently in

size to permit the intestines to return Probably because of the cecal swelling the large intestine is the last to leave the umbilical cord and re enter the abdominal cavity The cecum, the ascending colon and approximately half of the transverse colon are derived from the midgut, the remainder of the large bowel being derived from the hindgut The cecum becomes fixed on the right side close to the crest of the ileum At this stage however, the colon passes obliquely upward to the left of the stomach where it curves sharply to form the splenic flexure and continues as the future descending colon As the liver decreases in relative size a hepatic flexure appears in the originally oblique proximal colon this flexure demarcates ascending from transverse colon Posterior peritoneal fixations of the colon take place so that the ascending mesocolon and the colon fuse with the right parietal peritoneum and the anterior surface of the descending duodenum and its mesentery the descending colon fuses with the left parietal peritoneum (Figs 321 and 322) The mesentery to the remainder of small bowel remains free and unfused (Fig 314) These various fusions may be complete or incomplete they form surgical cleavage planes which permit proper bloodless mobilization of a given segment of bowel The transverse colon and the mesocolon do not fuse with the posterior parietal peritoneum but hang suspended from the posterior abdominal wall and remain fixed at the two colic angles The redundant sigmoid loop does not fuse with the left pelvic peritoneum The upper boundary of the mesosigmoid is the retrosigmoid or intersigmoid recess (fossa) the depth of which depends upon the inferior limit of fusion of the descending mesocolon Into this recess a loop of small bowel may herniate and strangulate (Fig 334) The rectum is the only part of the entire alimentary tube which maintains its primitive sagittal position it has no mesentery




FIG. 321 Embryology of the large bowel. Sections 1a and 2a are cross sections before posterior fixations have taken place. Sections 1b and 2b are corresponding cross sections after posterior fixations have taken place.

THE LARGE INTESTINE PROPER

The differences between the small and the large intestines may be listed as follows:

1 The large bowel is sacculated; the small bowel is smooth.

2 The large bowel has *taeniae coli*, the small bowel has none. One of the *taeniae* lies along the line of the mesenteric attachment and the other two are equidistant from it and from each other. All three




FIG 322 Embryology of the large bowel (A) before posterior fixation, (B) after posterior fixation

converge upon the cecum to the base of the vermiform appendix. These taeniae are explained by the fact that the outer longitudinal muscle of the large bowel does not form a complete coat as it does in the

small intestine. It is arranged in three narrow longitudinal bands which are shorter than the gut itself, thereby causing a puckering and forming sacculations. If the taeniae are cut the sacculated form is lost.

3 The large bowel has *appendices epiploicae*, the small bowel has none. There are little fatty tags which project from the serous coat of the large intestine. Those in the region of the appendix, the caecum and the rectum generally contain little fat; they may even be absent in these areas. Most of them are attached to the colon between its internal margin and the anterior tremit. In the iliac and the pelvic regions the appendices appear in two rows, one on each side of the anterior tremit.

4 The large intestine has a greater caliber than the small bowel. The size of the colon diminishes from its cecal extremity; the diameter of which is usually 6 cm. at the sigmoid colon its narrowest part the diameter is usually 2½ cm.

5 Internally the large intestine has no aggregated lymph nodules with or circular folds, all of which are present in the small intestine. The mucous membrane of the large bowel is thrown into folds opposite the constrictions between its sacculations. These folds are not permanent as in the small bowel; hence the former can be smoothed when the longitudinal muscle bands are cut.

The large bowel begins in the right iliac fossa as a blind head called the caecum to which the vermiform appendix is attached. The caecum continues upward into the ascending colon which lies on the right half of the posterior wall of the abdomen. At the inferior surface of the liver the ascending colon makes a sharp bend medially to form the right colic (hepatic) flexure, which lies on the anterior surface of the right kidney; it continues as the transverse colon. The latter crosses the abdomen transversely to the lower part of the spleen and on the front of the left kidney; it makes a sharp bend to form the left colic (splenic) flexure which passes into the descending colon. This continues down the left side of the posterior abdominal wall to the iliac crest then downward and medially in the left iliac fossa to end at the medial margin of the psoas major mus-

cle is the pelvic (sigmoid) colon. This part of the colon hangs into the pelvis as a loop and ends at the middle of the middle piece of sacrum; it continues as the rectum. The primitive mesentery possessed by the large bowel in fetal life is retained by only two parts of the large intestine, namely, the transverse and the pelvic colons. The extent to which the ascending and descending colons are surrounded by peritoneum is variable. They usually are surrounded on three sides and remain bare posteriorly. However, it may be completely surrounded by peritoneum but have no mesentery; finally the mesentery may persist wholly or in part. Because of its usual method of fixation, the position of the large bowel is more constant than that of the small bowel. The large bowel is five or six feet long (one quarter that of the small bowel) and forms a three-sided frame around the small gut leaving the most inferior part open to communicate with the pelvis.

Because all parts of the colon are capable of greater distention than the small intestine, the adjective 'large' has been used.

CECUM

The ileocecal region and the attached appendix form an important surgical and structural unit (Fig. 323). During early development the cecal segment forms a tube of uniform dimension. However the lower part of the cecal segment lags in growth while the upper part continues to increase with the rest of the colon. This difference in size becomes greater, and finally the lower tapering extremity becomes the vermiform appendix and the larger part situated directly above it becomes the caecum (Fig. 324). At birth the caecum has a conical smooth external appearance, but by the third year longitudinal bands or taeniae with sacculi between them are present. The sacculus between the anterior and the lateral bands develops more rapidly and

out of proportion to the others. This large sacculus forms the most dependent part (fundus) and constitutes the greater part of the anterior wall of the cecum. The appendix is attached medially and posteriorly. It is not associated with this large

muscle, thereby forming a small cul de sac behind the cecum, this is known as the *retrocecal recess*. When such a recess or fossa is well developed, it frequently contains the vermiform appendix. Posteriorly, the cecum rests upon the iliopsoas muscle,




FIG 323 Cecum. A window has been cut in the anterior cecal wall to show the valve and the opening of the appendix.

cecal sacculus. The cecum or head of the colon, as it has sometimes been referred to, is a blind pouch which normally is found in the right iliac fossa. It is that portion of large intestine which is below the ileocecal valve and is usually $2\frac{1}{2}$ inches long and $2\frac{1}{2}$ inches wide. It has a more or less complete peritoneal investment which accounts for its having a certain degree of mobility, but it is held in place because of its continuity with the ascending colon. From its anterior surface the peritoneum is continuous upward over the ascending colon, but from the upper part of its posterior surface the peritoneum is reflected backward and downward over the iliac

the lateral cutaneous nerve of the thigh (femoral nerve) and very often the external iliac artery. When distended it is in contact with the greater omentum and the anterior abdominal wall, but when collapsed it is covered by a few coils of small intestine. The ileocecal orifice and valve are located internally in its upper half and the opening of the vermiform appendix is in the posteromedial aspect (Fig 323). The ileocecal valve is a shelllike projection of mucous membrane where the wall of the ileum has become invaginated into the lumen of the cecum. The cecum is not only the widest part of the large bowel, but it is also the thinnest. Because of this, almost




FIG 324 Embryology of the cecum


all spontaneous perforations of the large intestine occur in this region. The taeniae coli of the cecum are anterior, posterior and medial. They converge on the base of the vermiform appendix for which they provide a complete longitudinal muscle coat. The position of the cecum may vary. In its low position it may lie in the depth of the pelvis and in its high position due to incomplete development of the colon it may occupy a position below the liver and on the right kidney. In the fetus and the infant it lies high; this should be kept in mind when an incision is being contemplated for an appendectomy in children. It usually elongates and descends with advancing age and may be present in the sac of an inguinal hernia. Occasionally the cecum and the colon retain their posterior fetal peritoneal connections and then are suspended from the posterior abdominal wall by a mesentery which permits a large range of mobility. This makes it possible for the ileocecal segment to become twisted (volvulus) and may also be an etiologic factor in the occurrence of intussusception. Appendices epiploicae frequently are absent over this portion of the large intestine.

Accessory peritoneal bands or membranes which are of surgical importance are found in this region (Fig 325). Two in particular warrant mentioning: Lane's and Jackson's membranes. Lane's ileal membrane is a thickening of parietal peritoneum in the region of the right iliac fossa. It extends from this fossa to the antimesenteric border

of the last two or three inches of ileum. It was thought by Lane that a shortening of this band would produce a kink (Lane's kink) of the small gut; however, it is unusual to find any obstruction caused by it. Therefore, it may pull the ileum to the right and make locating the appendix more difficult. It is an avascular membrane and may be cut with impunity. Jackson's membrane is a fold of peritoneum which is thin and transparent and extends from the posterior abdominal wall to the region of the ascending colon. It then continues downward and inward and attaches to the anterior longitudinal band of the ascending colon or cecum. A characteristic feature of



Lane's ileal membrane



Jackson's membrane

FIG 325 Accessory peritoneal bands

out of proportion to the others. This large sacculus forms the most dependent part (fundus) and constitutes the greater part of the anterior wall of the cecum. The appendix is attached medially and posteriorly; it is not associated with this large

muscle, thereby forming a small cul de sac behind the cecum, this is known as the *retrocecal recess*. When such a recess fossa is well developed, it frequently contains the vermiform appendix. Posteriorly the cecum rests upon the iliopsoas muscle.




FIG 323 Cecum. A window has been cut in the anterior cecal wall to show the valve and the opening of the appendix.

cecal sacculus. The cecum or head of the colon, as it has sometimes been referred to, is a blind pouch which normally is found in the right iliac fossa. It is that portion of large intestine which is below the ileocecal valve and is usually $2\frac{1}{2}$ inches long and $2\frac{1}{2}$ inches wide. It has a more or less complete peritoneal investment, which accounts for its having a certain degree of mobility but it is held in place because of its continuity with the ascending colon. From its anterior surface the peritoneum is continuous upward over the ascending colon, but from the upper part of its posterior surface the peritoneum is reflected backward and downward over the iliac

the lateral cutaneous nerve of the thigh (femoral nerve) and very often the external iliac artery. When distended it is in contact with the greater omentum and the anterior abdominal wall, but when collapsed it is covered by a few coils of small intestine. The ileocecal orifice and valve are located internally in its upper half and the opening of the vermiform appendix is in the posteromedial aspect (Fig 323). The ileocecal valve is a shelflike projection of mucous membrane where the wall of the ileum has become invaginated into the lumen of the cecum. The cecum is not only the widest part of the large bowel but it is also the thinnest. Because of this, almost




FIG 327 The vermiform appendix and the ileocecal region (A) The appendix is shown lying over the pelvic brim this is not its most frequent position (see text) (B) Various positions in which the appendix may be found

has a mesentery (meso appendix) which is derived from the left side of the mesentery proper. The *appendicular artery* is a branch of the ileocolic which reaches the appendix along the mesentery; if the mesentery is incomplete the artery lies on the wall of the appendix proper. It does not pass retroceally but rather retroileally. A large amount of lymphoid tissue is present in the appendix hence its name the abdominal tonsil; this tissue diminishes with age. The appendicular mesentery represents a triangular fold of peritoneum which is continuous with the lower or left layer of small bowel mesentery and reaches the appendix by passing downward behind the termination of the ileum. As a rule the mesentery does not extend to the upper half of the appendix.

When inflamed and in its usual position,

a point of tenderness known as *McBurney's point* is located at the junction of the middle and the outer thirds of a line joining the umbilicus and the anterior superior iliac spine. The site of an appendix determines the site of an abscess which may form as a result of appendicitis. When situated in front of the cecum, the abscess is walled off in front by coils of small intestine and omentum. An abscess behind the cecum may be intraperitoneal or extra-peritoneal. In the latter case it ascends upward to the perinephric or even the subphrenic regions, usually causing some tenderness and edema in the loin. Such abscesses are best approached posteriorly while those which are intraperitoneal should be approached along the outer side of the cecum (Fig 328). When situated on the inner side of the cecum and in front of




FIG 326 The cecal fossae

this membrane is the presence of fine-paral-
lel vessels which are seen through it, they
rarely, if ever, require ligation

The *cecal (pericecal) fossae* are pouches which are formed in the ileocecal region by peritoneal folds. They are of importance to the surgeon because the appendix may occupy any one of them. Herniations into these fossae also have been recorded. The three main cecal fossae are the following (Fig 326) (1) The ileocolic (superior ileocecal), (2) the ileocecal and (3) the subcecal (retrocecal).

The *ileocolic or superior ileocecal fossa* lies above the ileocolic junction and is formed by a peritoneal fold which passes across the ileocolic angle. It is bounded anteriorly by the ileocolic fold which contains the *ileocolic artery and vein* and posteriorly by the ascending colon. It opens toward the left.

The *ileocecal fossa* is formed by the so-called ileocecal or bloodless fold of Treves. This fold extends from the terminal ileum to the cecum and the mesentery of the appendix. The fossa is quite constant and large enough to admit two fingers. Dever has noted that the depth of this fossa varies and at times may extend upward behind the ascending colon as far as the right kidney and the duodenum. If the appendix cannot be found, this fossa should be the first to be investigated. It is bounded anteriorly by the ileocecal fold

superiorly by the posterior surface of the ileum and its mesentery, and posteriorly by the mesentery of the appendix.

The *subcecal (retrocecal) fossa* is situated behind the cecum and at times extends behind the ascending colon. It is bounded anteriorly by the posterior surface of the cecum posteriorly by the iliac fossa which is covered by parietal peritoneum, to the right by the peritoneum of the right colic gutter, and to the left by the mesentery. It has been the experience of the author to find the most common site for the appendix in this fossa.

VERMIFORM APPENDIX

In fetal life the appendix opens into the apex of the cecum, but in the adult the opening is an inch below the ileocolic junction (Fig 327). It may occupy any position depending upon its length and its mesentery. Wakeley in 10 000 cases, found it either to be postcecal or retrocolic in 65.28 per cent of the cases. It has been the impression of the author that the vermiform appendix is found in a retrocecal position in at least 70 per cent of those cases seen at the operating table and in the cadaver. Although the relation of the base of the appendix to the cecum is quite constant, it may occupy one of many positions. The so-called *paracolic position* is one in which the appendix is located on the outer side of the ascending colon. In the *splenic position* the appendix is entirely intraperitoneal but passes up in the direction of the spleen either in front of or behind the terminal ileum. The *promontoric position* is one in which the appendix is directed transversely inward toward the promontory of the sacrum. At times the appendix is *pelvic*; it then hangs over the pelvic brim and is in the true pelvis. It has also been described as assuming a *midinguinal position* when it passes down toward the middle of the inguinal ligament.

The appendix is usually from three to four inches in length but extremes varying from one to nine inches have been recorded. It is entirely covered by peritoneum and




FIG 330 Appendectomy (A) McBurney incision (B) the external oblique, the internal oblique and the transversus abdominis muscles have been incised in line with their fibers (C) the appendix is located by displacing the cecum upward and the ileal fat pad to the left (assistant) (D) the meso appendix is clamped and cut (E) the appendix is amputated between the clamp and the ligature (F) no inversion technic




FIG 328 Extraperitoneal drainage of an appendiceal abscess. The incision is placed laterally, the peritoneum is peeled away from the abdominal wall and the abscess is entered. In this way the peritoneal cavity is not soiled.

the mesentery of the small intestine the abscess may be bounded again in front by the anterior abdominal wall but when situated behind the mesentery, the peritoneal cavity must be traversed before such an abscess can be evacuated. A pelvic abscess is accompanied by rectal or vesical irritation depending upon which of the two structures is involved. Such an abscess may discharge into the bladder, the cecum, the colon or the rectum. Abscesses in the pelvis may be evacuated vaginally or rectally (Fig 329).

APPENDECTOMY

Since the appendix is a mobile part and since it may be found almost anywhere in the abdomen a variety of incisions have been described for its removal. This however still remains a personal problem with the surgeon.

The appendix is located by first making upward traction on the cecum, the ileal fat pad is located and turned to the left (Fig 330). This usually uncovers the appendix which, in most instances, is found retrocecaly. If the appendix is not located after dislocating the cecum and the ileal fat pad, one assumes that it is retroperitoneal and mobilization of the cecum becomes necessary. This is accomplished by incising along the paracecal gutter and dislocating the cecum and the ascending colon to the patient's left. When the appendix is delivered the meso-appendix is clamped and cut, the base of the appendix is ligated with or without clamping. The hemostats on the meso-appendix are replaced by ligatures. If a purse string is used this is placed now. A hemostat is placed above the ligated base and the appendix is removed between this ligature and the clamp. There are many modifications of this procedure.

ASCENDING COLON

This part of the colon lies between the cecum and the right colic (hepatic) flexure. It varies in length, depending upon




FIG 329 Drainage of a pelvic abscess. An aspirating needle is placed through the anterior rectal wall where the abscess points and into the abscess. The bowel floats above the abscess and therefore is protected. An incision is placed where the pus is aspirated and the abscess is drained.




FIG 332 The relations of the ascending the transverse and the descending colons. The numerals indicate the five muscles over which the descending colon passes

passes directly in front of the right kidney, an abscess of this kidney may discharge into this portion of bowel

RIGHT COLIC (ILIAC) ILLAURE

This is an angle or bend which forms at the junction of the ascending and the transverse colons. It lies in front of the right kidney and under the liver and the gallbladder (Fig. 331). It may form an obtuse or an acute angle but is not as sharp as the angle of the splenic flexure. Medial to it is the second part of the duodenum and lateral to it is the edge of the liver or the lateral abdominal wall. Above it touches the liver posteriorly it lies on the right

kidney. It is clothed with peritoneum except on its posterior surface. A peritoneal band from the lesser omentum sometimes passes downward to the flexure, it is called the hepatocolic ligament.

TRANSVERSE COLON

The transverse colon measures from 18 to 20 inches in length and is the longest section of the large intestine. It runs across the abdomen from right to left in front of the duodenum and the pancreas. Above, it is in relation to the stomach; below, to the coils of the small intestine (Figs. 331 and 332). At its beginning where the mesocolon is short or absent, it crosses the second part of the




FIG 331 The mesenteries and their attachments The jejunum ileum ascending, transverse descending and sigmoid colons have been removed

the location of the cecum its average length being between five and eight inches. It is covered anteriorly medially and laterally by peritoneum (Fig 331) in exceptional cases an ascending mesocolon may be present. Posteriorly it is related to the iliacus muscle and its fascia to the fascia covering the quadratus lumborum and to the lower part of the right kidney (Fig 332). Medially it is related to the psoas muscle and the descending duodenum. To the right of the ascending colon is the so called right paracolic gutter. If an ascending colon mesentery exists, it permits the bowel to fall away from the loin thus dragging the cecum and the hepatic

flexure with it. Though no symptoms may result this at times may account for such conditions as duodenal ileus, cecal stasis, volvulus, ileocecal intussusception and movable right kidney. The ascending colon has to support and propel a column of liquid feces against gravity and to do this it should be firmly fixed to the posterior abdominal wall. Anteriorly the ascending colon is either in direct contact with the anterior abdominal wall or separated from it by the greater omentum and part of the small bowel. The ascending colon is very short and it occupies only that space which exists between the iliac crest and the under surface of the liver. Since it




FIG 335 The rectum and its peritoneal relations (A) sagittal section of rectal relations in the male (B) sagittal section of rectal relations in the female

the fallopian tubes thus causing a kink sufficient to produce an obstruction. Abnormally long transverse colons have been found not only in ventral and umbilical hernias but also in inguinal and femoral hernias. As the transverse colon passes from right to left it ascends thus the splenic flexure is placed at a higher level than the hepatic. The transverse colon is covered on its posterior surface with the peri-

toneum of the general peritoneal cavity, but on its anterior surface it has acquired a covering of peritoneum of the omental bursa. Peritoneal bands may produce 'normal' kinking of the transverse colon. Two such bands which are found most commonly associated with this part of the colon are the mesocolicojejunal membrane and the intercolic membrane.

The *mesocolicojejunal* membrane is a




FIG 333 The intercolic membranes

duodenum, but past this point the increased length of its mesentery allows a sagging of the colon over the small bowel. This sagging may be so marked that the transverse colon reaches the symphysis pubis. To the left the mesentery is shortened again and the colon is held close to the pancreatic tail which it follows under the stomach and to the lower pole of the spleen. The right side of the transverse colon is in close contact with the gallbladder and is commonly found to be bile stained after death. In some cases gallstones may ulcerate through the wall of the gallbladder and into the transverse colon (autocholecysto-transversecolostomy). Hepatic abscesses may drain into the transverse colon. Since this part of the colon possesses a mesentery (transverse mesocolon), a wide range of movement is possible. It is related anteriorly to the anterior two layers of the greater omentum and the anterior abdominal wall; posteriorly it lies in contact with the second part of the duodenum and the head of the pancreas. In the rest of its extent it is separated from the posterior abdominal wall by coils of jejunum ileum. The upper border of the transverse colon is separated from the greater curvature of the stomach by the lesser peritoneal sac and the anterior two layers of the greater omentum (Fig 331). The *transverse mesocolon* connects the transverse colon to the posterior abdominal wall. As it suspends the colon, it forms a horizontal partition which separates the cavity of the omental




FIG 334 The pelvic mesocolon. The attachment of this mesocolon is placed obliquely and forms an inverted 'V'. The intersigmoid recess and the path of an intraperitoneal hernia are identified by arrows.

bursa and the supramesocolic structures from the inframesocolic compartment. In this way it acts as a barrier to infection between these areas. The posterior attachment of the transverse mesocolon extends to the anterior surface of the head, the neck and the body of the pancreas but may continue to the right and cross the anterior surface of the second part of the duodenum (Fig 331). The *middle colic artery* passes between the two layers of the transverse mesocolon, although it is called the 'middle colic artery' it should be noted that it passes well to the right (Fig 338). To the left of this vessel is a wide area (avascular area of Riordan) which contains no blood vessels. When incised, it allows the fingers to be introduced into the lesser peritoneal cavity. The great variations in the position of the transverse colon result in the formation of a 'V' shaped or 'U' shaped bend. Within the female pelvis a pendulous transverse colon may acquire adhesions which attach to the uterus, the ovaries and




FIG. 335 The rectum and its peritoneal relations (A) sagittal section of rectal relations in the male, (B) sagittal section of rectal relations in the female

the fallopian tubes thus causing a kink sufficient to produce an obstruction. Abnormally long transverse colons have been found not only in ventral and umbilical hernias, but also in inguinal and femoral hernias. As the transverse colon passes from right to left it ascends, thus the splenic flexure is placed at a higher level than the hepatic. The transverse colon is covered on its posterior surface with the peri-

toneum of the general peritoneal cavity but on its anterior surface it has acquired a covering of peritoneum of the omental bursa. Peritoneal bands may produce normal kinking of the transverse colon. Two such bands which are found most commonly associated with this part of the colon are the mesocolicojejunal membrane and the intercolic membrane.

The *mesocolicojejunal membrane* is a

band which extends from the under surface of the transverse mesocolon to the anti-mesenteric border of the first part of the jejunum. The *intercolic membranes* are peritoneal folds which bind together the ascending colon and the proximal part of the transverse colon and the descending colon and the distal part of the transverse colon (Fig 333). If these intercolic membranes are present they cause the so-called 'double barreled' colon and have been considered a cause of partial large bowel obstruction.

LEFT COLIC (SPLENIC) FLEXURE

This lies at a higher level and on a deeper plane than the right; it also forms a sharper bend (Figs 331 and 332). It is limited above by the tail of the pancreas and the base of the spleen; it rests upon the outer border of the left kidney, the diaphragm and the transversus muscle. The *phrenicocolic ligament* is a fold of peritoneum which connects the splenic flexure to the diaphragm opposite the tenth or the eleventh rib. It is bloodless and may be cut with impunity in mobilizing the splenic flexure or during splenectomy. This peritoneal fold aids in the fixation of the left colic flexure and also forms a floor upon which the spleen rests. The posterior surface of the splenic flexure is bare as a rule but the entire flexure may be enclosed in peritoneum and then is connected with the end of the pancreas by a short fold of transverse mesocolon. Because of the situation and the fixation of this flexure its exposure and mobilization are more difficult than any other part of the large intestine.

DESCENDING COLON

This part of the large bowel (descending colon) includes what was formerly called the iliac colon; however it is not considered as a separate part but rather an integral part of the descending colon. The latter and its associated iliac colon

are 10 or 11 inches long and extend from the left colic flexure above to the pelvic inlet below. (Some authors still prefer to state that the descending colon ends at the iliac crest and that the portion below the iliac crest is known as the iliac colon.) The descending colon is more deeply placed than the ascending colon, it rarely possesses a mesentery. It starts in an angle which is situated between the left kidney and the transversus abdominis muscle; it descends in front of the lateral border of this kidney and curves medially along its lower pole. It then passes vertically downward in front of the quadratus lumborum muscle, crosses the iliac crest and continues downward on the iliacus muscle almost reaching the inguinal ligament. It turns medially across the left psoas muscle and becomes continuous with the pelvic colon in front of the external iliac artery. This colon separates the left infracolic compartment from the left paracolic gutter. The greater omentum and the coils of the jejunum intervene between it and the anterior and lateral abdominal walls. Medially it is related to the left kidney and the psoas major muscle; posteriorly, it crosses five muscles (Fig 332). They are, in succession, the diaphragm, the transversus abdominis, the quadratus lumborum, the iliacus and the psoas major.

A number of vessels and nerves separate the descending colon from some of these muscles. Thus the iliohypogastric and the ilioinguinal nerves separate it from the quadratus lumborum, the lateral cutaneous nerve of the thigh and the iliac branches of the ilio-lumbar vessels separate it from the iliacus; the femoral nerve, from the iliacus and psoas, and the external iliac vessels from the psoas. The testicular (ovarian) vessels and the branches of the genitofemoral nerve are in close relation to the external iliac artery. Although it is stated that the nerves lie between the muscles and the descending colon, this is not correct because the nerves lie beneath the fascia which covers the muscles. There

fore the iliohypogastric and the ilioinguinal nerves are separated from the colon by the fascia covering the quadratus lumborum and the lateral cutaneous nerve of the thigh and the femoral nerve is separated from the bowel by the iliac fascia this fascia must be incised before the nerves can be demonstrated

PELVIC (SIGMOID) COLON

The external iliac artery can be considered as the dividing line between the iliac and the pelvic colons the latter commencing in front of the artery about two inches above the inguinal ligament (Fig. 338). The average length of this part of the colon is between 10 and 15 inches but may vary from 5 to 35 inches. It ends in the midline at the level of the third sacral vertebra where it becomes continuous with the rectum. The differentiation between the sigmoid and the rectum is marked by the facts that the diameter of the rectum is diminished the peritoneum ceases to enclose the rectum, and the rectum has no appendices epiploicae. In the pelvis the colon is related to the urinary bladder anteriorly to the sacrum posteriorly and to the terminal coils of ileum on its right side. It is suspended from the posterior wall of the pelvis by a mesentery which is known as the *pelvic mesocolon*. Although this mesocolon varies with the length of the sigmoid nevertheless, the attachment of its root is quite constant. This obliquely placed mesocolon has an inverted V shaped course (Fig. 334). Its line of attachment reveals the following: a lateral limb which extends along the iliac arteries from the middle of the external iliac artery to the middle of the left common iliac artery; the medial limb extends from the middle of the left common iliac to the middle of the third sacral vertebra. At the apex of this 'V' there is a small peritoneal recess the opening of which looks downward it is known as the intersigmoid recess (fossa intersigmoidea).

It may be deep or merely represented by a dimple, it acts as a guide to the left ureter. If a finger is placed in this fossa, the ureter can be rolled on the underlying common iliac artery, if the peritoneum over it is divided, the left ureter is exposed. Internal herniations with strangulations of small bowel may take place into this fossa. The superior hemorrhoidal artery runs downward and medially to the rectum in the medial limb of the pelvic mesocolon. The length of the mesocolon determines the length, the location and the mobility of the pelvic colon proper; therefore, there is a wide variation. Usually the pelvic colon is situated partly in the abdomen and partly in the pelvis. However if the mesocolon is long, it may cross past the midline and appear in the right lower abdominal quadrant, it may be exposed in the course of an appendectomy. Such a mobile pelvic colon may twist upon itself producing a volvulus. The *mesosigmoid membrane* is a thickening and a shortening of the peritoneum of the left iliac fossa; it binds the junction of the iliac and the pelvic colons to the pelvic brim. This band has been referred to as Lane's first and last link. The reason for this is that Lane thought this band was the first to appear but involved the last part of bowel. If present it must be cut when this portion of the colon is to be mobilized, it is avascular.

RECTUM

The rectum (Figs. 335 and 336) begins at the point where the colon ceases to have a mesentery; this usually occurs in front of the third sacral vertebra. It not only loses its mesentery but also differs from the colon in that it is not sacculated has no taenia coli or appendices epiploicae. Its upper third is covered anteriorly and at the sides by peritoneum, the middle third is covered only anteriorly by peritoneum and the lowest third is entirely devoid of peritoneum (Fig. 335). The rec-




FIG 336 Anterior and posterior relations of the rectum (A) seen from above and in front, (B) seen from behind part of the sacrum and the coccyx have been removed

tum is about five inches long and occupies the posterior part of the pelvis. It follows the curve of the sacrum and the coccyx and ends one inch in front of the tip of the coccyx by bending sharply downward and

backward into the anal canal. It derives its name rectum from the fact that in lower animals this part of the intestinal tract is straight; however, the human rectum is not straight. It has an anteroposte-

rior curve where it follows the concavity of the sacrum and the coccyx, it also has three lateral curves or flexures. The upper and the lower of these are concave toward the left and the middle is concave toward the right. Corresponding to the concavity of these flexures are the *valves of Houston*. These rectal valves appear as crescentic horizontal folds which arise transversely from the lateral aspects of the bowel with the exception of the outer longitudinal muscular coat all the coats of the rectum take part in their formation. Three such valves are usually present: the middle one is on the right side and the superior and the inferior are on the left. Toward the lower portion of the rectum the lumen expands to form the ampulla; the lumen of the rectum therefore is narrower at its upper and lower ends.

The rectum has the following relations (Fig. 336). *Posteriorly* is the superior hemorrhoidal artery which is so intimately associated with it that the artery is removed with the rectum in cases of carcinoma involving this part. The sacrum, the coccyx and the anococcygeal body are also situated here and the piriformis, the coccygeus and the levator ani form a smooth curved bed in which the rectum is situated postero-laterally. The median sacral vessels lie between it and the sacrum and the coccyx. Separating the rectum from its muscular bed are the sympathetic trunk, the lower lateral sacral vessels and nerves and the coccygeal nerve. *Anteriorly* as long as it is covered by peritoneum the rectum is related to the terminal part of the pelvic colon. Below the peritoneal reflection however it is related to the posterior surface of the bladder in the median plane and to the end of the vas deferens and the seminal vesicles on each side of this plane. The anterior wall of the rectal ampulla is related to the posterior surface of the prostate. It is separated from these structures by loose areolar tissue and the rectovesical fascia. In the female the only differences

in the anterior relations are that the upper two thirds are related to intestines which separate the rectum from the uterus and the upper third of the vagina. The lower third of the rectum is directly related to the middle third of the vagina. On each side are the so called *rectal stalks* (lateral or suspensory ligaments). These are situated in the lower two thirds and are condensations of areolar tissue around the middle hemorrhoidal artery and veins (Fig. 338). J. W. Smith is of the opinion that they are situated one inch above the levator and extend from the third piece of the sacrum to the rectal wall. This areolar tissue then has a backward as well as a lateral prolongation and contains the nervi erigentes (sacral second and third), as well as the middle hemorrhoidal vessels.

Five arteries supply the rectum: the superior hemorrhoidal artery, which is a continuation of the inferior mesenteric; the two middle hemorrhoidals derived from the internal iliac; and the two inferior hemorrhoidals which are branches of the internal pudendals. The *superior hemorrhoidal (rectal) artery* is a continuation of the inferior mesenteric and begins at the middle of the left common iliac artery. It enters the root of the medial limb of the pelvic mesocolon and descends in it to the third sacral vertebra. Here it divides into two diverging branches which pass downward first on the back and then on the sides of the rectum. These divide into smaller branches which are disposed around the rectum; they pierce the muscular coat about its middle and descend in the submucosa to the anal canal. The *middle hemorrhoidal (rectal) arteries* are small and inconstant branches of the internal iliac. They pass to the sides of the rectum and are enclosed within the condensations of the visceral pelvic fascia which forms the so called rectal stalks or lateral ligaments of the rectum. The *inferior hemorrhoidal (rectal) artery* arises on each side from the internal pudendal (pudic) artery, which is situated in

Alcock's canal It supplies the anal canal and the lower part of the rectum, chiefly its posterior part. The superior hemorrhoidal artery supplies the entire internal surface and the upper half of the external

situated between the anal canal and the coccyx, and blends above with the median raphe of the levator ani. On each side the puborectal (levator ani) muscles separate the anal canal from the ischiorectal fossa.




FIG 337 The anal canal. The pecten is situated between Hilton's line and the pectinate line. The three parts of the external sphincter ani muscle are identified.

surface of the rectum but the middle and the inferior hemorrhoidal arteries are confined chiefly to the external surface of the lower half. The middle sacral artery also contributes slightly to the blood supply of the posterior rectal wall.

ANAL CANAL

The anal canal represents the terminal portion of the large intestine and is about one and one half inches long. It runs downward and backward at right angles to the rectum through the fascia and between the two levators into the perineum where it opens on the exterior at the anus. Anteriorly in the male the perineal body (central point of the perineum) separates it from the transverse perineal muscles, the membranous urethra and the bulb of the penis; in the female it is separated from the lower third of the vagina. Posteriorly it is related to the anococcygeal body, a collection of dense fibrous tissue which is

A view of the anal canal through the anoscope presents four rather definite landmarks: (1) the anocutaneous line, (2) Hilton's line, (3) the pectinate line and (4) the anorectal line (Fig 337).

The *anocutaneous line* also has been referred to as the anal verge. Normally, it is in a state of apposition, the epithelium surrounding it being thrown into folds by the involuntary action of a muscle which has been called the 'corrugator of the anal skin'.

Hilton's (intersphincteric) white line is really more blue in color than white and is more palpable than visible. It marks the sharp nonmuscular interval which exists between the internal and the external sphincters and feels like a depression. It lies halfway between the anal verge and the more superior pectinate line. Directly above Hilton's line is an area about one eighth to one third of an inch in width. Stroud has called this 'the pecten'. It has been given this name because, arising from




FIG 338 The blood supply of the large bowel. The branching vessels which pass along the inner margin of the colon form the so called marginal 'artery' of Drummond

its upper edge there is a serrated margin that resembles the teeth of a comb. Miles has stressed the importance of this area because of the heavy deposits of fibrous

tissue underlying it. He believes that it is necessary to cut this stenosing fibrous ring to cure anal fissures. It is an important anatomic landmark, since it is the line over

which prolapsing masses of mucosa fall through the sphincteric region

The *pectinate line* also has been referred to as the dentate line. It is the upper border of the area just described as the pecten. It has received its name because of its comblike arrangement brought about by the anal papillae which are continuous above with the columns of Morgagni. The bases of the anal papillae are connected by irregular folds which are known as anal valves. This arrangement forms small pockets between the vertical columns; these are known as the crypts of Morgagni.

The area which has been described as the pecten or that area which exists between Hilton's line below and the pectinate line above, is an important surgical landmark. Pennington has stated that 85 per cent of all proctologic diseases occur in this area. There are structural as well as clinical differences which result at this line.

1 Stratified squamous epithelium is found below this line and above it is columnar epithelium. The line itself is said to be covered by transitional epithelium.

2 At this line the external sphincter replaces the internal.

3 The sympathetic and the cerebrospinal nerves meet here. The skin distal to the line is supplied by the inferior hemorrhoidal nerve which carries pain fibers, but the mucous membrane proximal to the line is supplied by sympathetic fibers which do not contain pain fibers. Therefore any anorectal condition which is associated with pain must be situated below the pecten. For this reason a carcinoma of the rectum is 'silent' but a fissure in ano produces severe pain.

4 Internal hemorrhoids occur above this line and external hemorrhoids occur below it.

5 The line divides the lymphatic drainage. The intestine above the line drains into the pelvic lymphatics (sacral and hypogastric) and the rectum below it drains into the iliac lymphatics.

side of the root of the thigh. This explains the reason that lesions below the pecten may be associated with inguinal lymphadenopathy but lesions above this line do not show such adenopathy.

6 The pecten marks the dividing line between the superior and the inferior hemorrhoidal vessels (p 486). Therefore, the small veins in the submucosa of the pecten communicate the portal with the systemic circulation at this point (portacaval communication).

7 Focal infections take place at this line because this is the location of the crypts of Morgagni; hence, cryptitis, papillitis and fistulae in ano are located here.

8 Developmental defects may be found here. Since the anal canal is formed by fusion of an ingrowth of skin from below known as the proctodeum, and a downward growth of hindgut from above, the anal membrane which forms a partition between these two is located at the pecten. The septum disappears, as a rule, leaving on the dentate line, but should it remain intact the membrane then is visible and separates the hindgut from the proctodeum.

The *anorectal line* should not be confused with the anocutaneous line. The anorectal line lies about $1\frac{1}{2}$ cm above the pectinate line. The anorectal junction is $1\frac{1}{2}$ inches above the anocutaneous line when the canal is empty. It can be identified when the posterior wall appears while withdrawing the proctoscope.

The *anal sphincters* are two in number, namely the external and the internal sphincters and (Fig 337). The *internal sphincter* is the lower, thickened portion of the circular muscle of the bowel; it is about one inch long and can be felt on digital examination. It encloses the upper two thirds of the canal. The external sphincter is a subcutaneous muscle which is placed superficial to the internal sphincter. The fibers of this muscle are arranged in three layers: subcutaneous, superficial and deep. The subcutaneous fibers are without bony attachment, they surround the anal orifice.

and some decussate inferiorly. The superficial fibers arise from the uncoccygeal body, pass around the sides of the anus and are inserted into the perineal body (central point of the perineum). The deep fibers embrace the subcutaneous layer in that they have no direct bony attachment but encircle the lower half of the anal canal and form a true sphincteric muscle. The deep liver is intimately associated with the puborectal portion of the levator ani. The external sphincter is supplied by the perineal branch of the fourth sacral and also by the inferior hemorrhoidal nerves.

VASCULAR SUPPLY OF THE COLON THE RECTUM AND THE ANAL CANAL

The colon receives its blood from the superior and the inferior mesenteric arteries (Fig. 338). The *superior mesenteric artery* supplies that part of the intestinal tract which extends from the second part of the duodenum to the right half of the transverse colon. The vessel crosses in front of the third part of the duodenum and then enters the mesentery proper. It passes between the head and the body of the pancreas and may be followed upward to the aorta whence it arises. Since the body of the pancreas is associated with the transverse mesocolon anteriorly and the splenic vein posteriorly, the superior mesenteric artery has three anterior relations, namely, the transverse mesocolon, the pancreas and the splenic vein, the left renal vein is posterior to it and therefore is clamped between the artery and the aorta. The superior mesenteric artery passes downward and to the right where it ends by forming an arch with one of its own branches (the ileal branch of the ileocolic artery). Throughout its course it is surrounded by the superior mesenteric plexus of sympathetic nerves from the celiac plexus. It is accompanied by its vein which lies to its right side either in front of the right colic and the ileocolic branches or behind them. As it descends in the mesentery, it passes the following

structures from left to right, the third part of the duodenum, the aorta, the inferior vena cava, the right ureter and the testicular (or ovarian) vessels. The branches of the superior mesenteric artery are numerous and are accompanied by veins. The jejuno-ileal branches arise from its convex border and the usual three colic branches arise from its concave right border. The colic branches from above downward are the middle colic, the right colic and the ileocolic. Although the inferior pancreaticoduodenal is not a colic branch nevertheless it arises from the right side of the vessel. Many variations of the above arrangement are possible, these must be kept in mind during surgery of the colon.

The *middle colic artery* arises below the pancreas, enters the transverse mesocolon and passes downward, forward and to the right. It is the first branch of the superior mesenteric artery. It divides into left and right branches. The left branch anastomoses near the splenic end of the transverse colon with the left colic artery, the right branch anastomoses on the inner side of the ascending colon with the right colic artery. Since the middle colic artery lies in the transverse mesocolon it is situated posterior to the stomach, therefore, it is in danger of being caught when the right gastroepiploic vessels are clamped, since only two layers of peritoneum separate the two vessels. The main trunk of the middle colic artery does not lie directly in the midline but rather to the right, hence any surgical opening which is made through the transverse mesocolon should be made to the left of this vessel where the large so-called avascular area of Riordan is found. When the transverse colon and the greater omentum are pulled upward, the artery is seen to curve upward in the right half of the transverse mesocolon.

The *right colic artery* arises a little below the middle colic and passes to the right behind the peritoneum and on the posterior wall of the right infracolic compartment. It crosses in front of the inferior vena cava,




FIG. 339 The arterial blood supply of the sigmoid and the rectum

the right testicular (or ovarian) vessels and the right ureter. On reaching the upper part of the ascending colon it divides into a superior branch which anastomoses with the middle colic artery and an inferior branch which anastomoses with the ileocolic artery. At times it does not arise as an independent branch but springs from the ileocolic or from the middle colic artery. It supplies the ascending colon.

The *ileocolic artery* is the lowest branch which is given off from the concavity of the superior mesenteric artery. It supplies the last six inches of ileum, cecum, appendix and part of the ascending colon. As it descends subperitoneally it crosses the inferior vena cava, the ureter, the genitofemoral

nerve and the testicular (or ovarian) vessels which lie on the psoas major. It terminates by dividing into ascending and descending branches. The descending (ileocecal) branch divides into anterior and posterior cecal, appendicular and ileal branches. The anterior cecal branch runs in the superior ileocecal fold of peritoneum in front of the cecum and supplies this area; the posterior cecal branch supplies the posterior cecal surface. The ileal branch anastomoses in the mesentery with the end of the superior mesenteric artery, thus forming a single or sometimes a double, tier of arches from which *vasa recta* pass to the last six inches of ileum. The *appendicular artery* usually arises from the




FIG 340 The venous drainage of the sigmoid, the rectum and the anus

posterior cecal branch descends behind the ileum and runs in the free border of the mesentery of the appendix (Fig 327). Therefore bleeding from the appendicular artery is retro ileal and not retrocecal. The ascending branch of the ileocolic artery anastomoses with the right colic.

The *inferior mesenteric artery* supplies the descending and the sigmoid colons and the proximal part of the rectum. It does this by means of its left colic, sigmoid and superior hemorrhoidal branches. It arises from the front of the aorta about $1\frac{1}{2}$ inches above its bifurcation. This origin is

located approximately three quarters of an inch above the umbilicus and in front of the third lumbar vertebra. It is smaller than the superior mesenteric artery, has a more limited distribution and is surrounded by the inferior mesenteric plexus of nerves which is derived from the aortic plexus. Its vein lies to its lateral side but is not in close contact with it. (The two mesenteric arteries are situated between the two mesenteric veins.) As it passes downward it inclines somewhat to the left, lying on the aorta and the psoas fascia, then crosses the left common iliac artery and enters the

pelvis as the superior hemorrhoidal (superior rectal) artery. As it descends it gives off the left colic, sigmoid and superior hemorrhoidal branches.

The *left colic artery* (Fig. 339) arises about $1\frac{1}{2}$ inches along the stem of the inferior mesenteric artery below the duodenum passes subperitoneally to the left and crosses the testicular vessels, the ureter and the inferior mesenteric vein. It divides into ascending and descending branches. The *sigmoid artery* also has been referred to as the inferior (lower) left colic artery. The sigmoid branches are usually three or four in number and supply the descending and the pelvic colons. As they pass to the left side they divide and anastomose with each other. The lowest sigmoidal branch is connected to the superior hemorrhoidal vessel by a very small branch.

Because of this weak link, there is a little or no anastomotic connection between the superior hemorrhoidal and the sigmoidal vessels. This weak spot has been called the "critical point of Sudeck."

It was formerly believed that ligation of the superior hemorrhoidal artery below the origin of the lowest sigmoidal artery would produce a necrosis of the rectosigmoid and the upper part of the rectum. The "critical point of Sudeck" was discussed in connection with this. It was thought that the marginal artery which runs parallel with the colon ends abruptly in the region of the lower sigmoid and does not anastomose with the blood supply from below. Dixon is of the opinion that although this might appear to be true, it actually is not; hence, he definitely states that the superior hemorrhoidal artery can be ligated and even some of the marginal artery resected without damaging the blood supply to the remaining portion of the descending colon, the rectosigmoid or the rectum. He further states that all of the colon which lies below the brim of the true pelvis remains viable without the superior hemorrhoidal or marginal arteries. Dixon is of the opinion that the distal part of the bowel is adequately

supplied by the middle and the inferior hemorrhoidal arteries. Based upon this, he has described a radical anterior resection of the lower part of the sigmoid colon and the rectosigmoid in which he re-establishes the continuity of the large bowel. In this way sphincteric action is preserved.

The inferior mesenteric artery continues beyond the origin of the lowest sigmoid artery as the *superior hemorrhoidal artery* (Fig. 339). The latter continues downward into the pelvis behind the rectum, it divides into right and left branches which subsequently anastomose with the middle and the inferior hemorrhoidal vessels in the submucous layer of the anal canal.

The so called *marginal 'artery' of Drummond* is formed from the vessels which supply the large intestines. These are the following: the end of the superior mesenteric and the adjacent branches of the ileocolic, the right colic, the middle colic, the upper left colic and the lower left colic (sigmoid). By anastomosing with each other, these vessels form an "artery" which passes along the margin of the large intestine and is known as the marginal "artery" of Drummond. It extends from the end of the ileum to the end of the pelvic colon. It is situated about a half inch from the margin of the large bowel, is closest to the descending and the pelvic colons and is capable of supplying the gut by means of its anastomoses even though one of the large feeding trunks may be ligated.

The arteries which supply the *rectum and anal canal* are the superior, the middle and the inferior hemorrhoidals and the middle sacral arteries. These vessels form rich anastomoses around the anorectal region. The *superior hemorrhoidal artery* is a direct continuation of the inferior mesenteric and is the largest and most important of the rectal vessels. After leaving the pelvic mesocolon it reaches the posterior wall of the rectum, at the upper part of which it divides into two lateral branches that enter the muscular coat and divide into numerous smaller branches. The latter

anastomose freely with the inferior and the middle hemorrhoidal arteries and supply the entire length of the anal canal and the rectum. The *middle hemorrhoidal arteries* arise one on each side from the anterior division of the internal iliac (hypogastric) artery. They reach the lateral surface of the rectum enclosed within the visceral pelvic fascia thereby forming the lateral ligaments of the rectum (Fig. 339). They are distributed chiefly to the lower and the anterior parts of the rectum and they also supply the base of the bladder and the upper part of the vagina. The *inferior hemorrhoidal arteries* arise one on each side from the internal pudic (pudendal) arteries which travel in Alcock's canal (Fig. 338). They supply the anus and the lower part of the rectum mainly at its posterior aspect. The *middle sacral artery* arises from the abdominal aorta near its termination and continues downward in the median plane on the posterior surface of the rectum which it supplies by means of a few small twigs. The superior hemorrhoidal artery supplies the entire internal surface and the upper half of the external surface of the rectum and the middle and the inferior hemorrhoidal arteries supply the external surface of the lower half.

The *rectal veins* are arranged in a similar manner to the arteries but differ from those of the other divisions of the large bowel in that they form a *hemorrhoidal plexus* within the thickness of the bowel (Fig. 340). This plexus is best developed in the anal region; it begins inferiorly at the internal margin in a number of small veins which increase in size and number as they ascend. In the anal canal the plexus chiefly occupies the columns of Morgagni. In the upper part of the rectum the venous trunks traverse the muscular layer and end exteriorly where they unite to form the *superior hemorrhoidal vein*. This vein drains into the inferior mesenteric vein and finally into the portal vein; hence the greater part of blood from the rectum and the anal canal joins the portal circulation.




FIG. 341 The upper end of the inferior mesenteric vein

The *middle hemorrhoidal vein* chiefly drains the external surface of the rectum in its lower half. It accompanies the artery of the same name and terminates in the internal iliac vein. The *inferior hemorrhoidal vein* drains the lower part of the anal canal and joins the internal pudic (pudendal) vein, which empties into the internal iliac vein.

Certain structural factors are important in the development of varicosities of the veins which are known as hemorrhoids. They are the absence of valves and the oblique passage of the veins through the muscular wall. Since the greater part of the venous blood of the rectum returns to the portal circulation, any portal obstruction alters the return flow.

The *superior mesenteric vein* lies on the right side of its artery (Fig. 338). It begins at the lower end of the root of the mesentery, passes upward and to the left and receives tributaries which correspond to the branches of the superior mesenteric artery. The right gastro-epiploic vein from

pelvis as the superior hemorrhoidal (superior rectal) artery. As it descends it gives off the left colic, sigmoid and superior hemorrhoidal branches.

The *left colic artery* (Fig. 339) arises about 1½ inches along the stem of the inferior mesenteric artery below the duodenum passes subperitoneally to the left and crosses the testicular vessels, the ureter and the inferior mesenteric vein. It divides into ascending and descending branches. The *sigmoid artery* also has been referred to as the inferior (lower) left colic artery. The *sigmoid branches* are usually three or four in number and supply the descending and the pelvic colons. As they pass to the left side they divide and anastomose with each other. The lowest sigmoidal branch is connected to the superior hemorrhoidal vessel by a very small branch.

Because of this weak link there is a little or no anastomotic connection between the superior hemorrhoidal and the sigmoidal vessels. This weak spot has been called the "critical point of Sudeck."

It was formerly believed that ligation of the superior hemorrhoidal artery below the origin of the lowest sigmoidal artery would produce a necrosis of the rectosigmoid and the upper part of the rectum. The "critical point of Sudeck" was discussed in connection with this. It was thought that the marginal artery which runs parallel with the colon ends abruptly in the region of the lower sigmoid and does not anastomose with the blood supply from below. Dixon is of the opinion that although this might appear to be true it actually is not; hence, he definitely states that the superior hemorrhoidal artery can be ligated and even some of the marginal artery resected without damaging the blood supply to the remaining portion of the descending colon, the rectosigmoid or the rectum. He further states that all of the colon which lies below the brim of the true pelvis remains viable without the superior hemorrhoidal or marginal arteries. Dixon is of the opinion that the distal part of the bowel is adequately

supplied by the middle and the inferior hemorrhoidal arteries. Based upon this, he has described a radical anterior resection of the lower part of the sigmoid colon and the rectosigmoid in which he re-establishes the continuity of the large bowel. In this way sphincteric action is preserved.

The inferior mesenteric artery continues beyond the origin of the lowest sigmoid artery as the *superior hemorrhoidal artery* (Fig. 339). The latter continues downward into the pelvis behind the rectum, it divides into right and left branches which subsequently anastomose with the middle and the inferior hemorrhoidal vessels in the submucous layer of the anal canal.

The so called *marginal "artery" of Drummond* is formed from the vessels which supply the large intestines. These are the following: the end of the superior mesenteric and the adjacent branches of the ileocolic, the right colic, the middle colic, the upper left colic and the lower left colic (sigmoid). By anastomosing with each other, these vessels form an "artery" which passes along the margin of the large intestine and is known as the marginal "artery" of Drummond. It extends from the end of the ileum to the end of the pelvic colon. It is situated about a half inch from the margin of the large bowel is closest to the descending and the pelvic colons and is capable of supplying the gut by means of its anastomoses even though one of the large feeding trunks may be ligated.

The *arteries* which supply the *rectum and anal canal* are the superior, the middle and the inferior hemorrhoidals and the middle sacral arteries. These vessels form rich anastomoses around the anorectal region. The *superior hemorrhoidal artery* is a direct continuation of the inferior mesenteric and is the largest and most important of the rectal vessels. After leaving the pelvic mesocolon it reaches the posterior wall of the rectum at the upper part of which it divides into two lateral branches; these enter the muscular coat and divide into numerous smaller branches. The latter

the greater curvature of the stomach also empties into it. It leaves the root of the mesentery, crosses in front of the third part of the duodenum and the uncinate process of the pancreas and terminates behind the neck of the pancreas by joining the splenic vein to form the portal vein.

The *inferior mesenteric vein* is a continuation of the superior rectal (hemorrhoidal) it passes upward on the posterior abdominal wall to the left side of the inferior mesenteric artery. It receives tributaries which correspond to the branches of the artery, then curves to the right above the duodenojejunal flexure, passes behind the body of the pancreas and joins the splenic vein. The branches of the lower and the upper left colic artery cross either in front or behind it (Fig. 341) but the testicular artery and the genitofemoral nerve always cross behind it.

The *portal vein* is formed behind the neck of the pancreas by the union of the superior and the inferior mesenteric veins and the splenic veins (Fig. 342). It passes upward and to the right behind the first part of the duodenum and at the upper border of the duodenum it enters and ascends in the lesser omentum; it then divides into right and left branches. In its course it receives the left and the right gastric veins from the lesser curvature of the stomach as well as the pancreaticoduodenal vein.

Although this pattern of the formation of the portal vein is described frequently, it must be emphasized that many other patterns are possible (Fig. 343). Rousselot has emphasized the importance of such variations in the clinical behavior of patients suffering with congestive splenomegaly (Banti's syndrome).

The portal vein delivers to the liver blood which has circulated through the spleen, the pancreas and through the whole length of the alimentary tract from the lower end of the esophagus to the upper end of the anal canal. The *hepatic veins* carry blood from the liver to the inferior vena cava,




FIG. 343 Variations in the pattern of the portal system. These variations have been taken from some of the standard textbooks in anatomy.

which lies in a groove on the posterior aspect of that organ. When the liver becomes diseased, the portal vein may become obstructed as in cirrhosis of the liver. Communications exist between the portal vein and the inferior vena cava (portacaval communications) (Figs. 342 and 344). These anastomoses exist but do not function unless obstruction to the portal vein, either in its intraperitoneal or intrahepatic




FIG. 344 Sites of anastomoses between the portal and the caval systems (A) at the lower end of the esophagus (B) at the bare area of the liver and the retroperitoneal structures (C) at the lower end of the rectum, (D) at the umbilicus.




FIG 342 The portal system of veins The usual pattern of this system is presented however, many variations are possible

RECTAL SURGERY

HEMORRHOIDECTOMY

Hemorrhoids or piles are varicosities of the hemorrhoidal veins. Internal hemorrhoids or varices of the superior and the middle hemorrhoidal veins, are covered by mucous membrane and are above the pectinate line. External hemorrhoids are dilations of the inferior hemorrhoidal veins, are covered by skin and appear below the pectinate (dentate) line (Fig 345). An external pile is usually associated with each of the three primary internal hemorrhoids (3, 7 and 11 o'clock). Therefore, in doing a hemorrhoidectomy a hemostat is placed on the external hemorrhoid; this is elevated and an incision is made in the skin. This dissection is carried to the mucocutaneous junction and a clamp is placed on the entire internal pile. A suture is passed beneath the tip of the clamp and tied; this ligates the nutrient artery. The pile above the clamp is removed and an over and over suture replaces the hemostat. The suture is made taut and the two ends are tied together.

ISCHIORECTAL ABSCESS AND FISTULAS

Many authorities are of the opinion that an *ischio-rectal abscess* and a *fistula in ano* result from an infected crypt of Morgagni. The infection may burrow above, below or through the sphincter ani muscle (Fig 346). As a result of this burrowing the ischio-rectal fossa is reached and here an ischio-rectal abscess develops. This may open spontaneously or is opened surgically but in either event a fistula in ano with its external opening results. The internal opening corresponds to the infected crypt. Successful treatment of such fistulas depends upon the eradication of the internal opening as a primary focus of infection and removal of the fistulous tract. If the tract is subcutaneous a fistulectomy can be done. However, if the tract lies deeper and has many ramifications a wide excision with




FIG 347 The lymph drainage of the colon. These lymphatics mainly follow the course of the chief blood vessels. Most of the lymph drainage is to the group of glands located around the upper part of the superior mesenteric artery, from here the efferent vessels drain to the main intestinal lymph trunk.

healing by secondary intention becomes the method of choice.

LYMPHATICS OF THE COLON

G. Gordon Taylor has remarked that the surgery of cancer is the surgery of the lymphatic system; therefore, a thorough understanding of the regional lymph drainage aids the surgeon when operative intervention is contemplated. In the case of the colon the involved bowel should be resected well to either side of the malignant growth together with the lymphatic channels which drain the affected parts (Fig 347). Since the removal of the main artery to a segment of bowel may devitalize that portion of the intestine it becomes neces-




FIG 345 Internal and external hemorrhoids




FIG 346 Types of fistulae in ano. The fistula may burrow above, below or through the sphincter ani muscle. Number 4 represents the horseshoe type of fistula.

course is present. Such communications have been referred to as the accessory portal system and are found at the following places:

1 *At the lower end of the esophagus* the esophageal branches of the left gastric veins (portal) anastomose with the esophageal branches of the azygos veins (caval). In portal obstruction these esophageal veins may become varicose and dilated and produce large varices which project into the esophageal mucosa. Since they are unsupported they may rupture when the patient is in apparently good health; this results in an exsanguinating hemorrhage. They have been referred to as 'esophageal piles'.

2 *In the bare area of the liver* small veins, known as the veins of Retzius, unite the diaphragmatic veins (caval) with the hepatic veins (portal). To this group belong the retroperitoneal veins which lie about the abdominal viscera (liver, suprarenals, duodenum, pancreas, ascending and descending colons, etc.). They divert the blood into such caval veins as the lower

intercostals, diaphragmatic, lumbar, epigastric and ilio-lumbar.

3 *At the lower end of the rectum* the superior hemorrhoidal (rectal) vein becomes the inferior mesenteric which drains into the portal vein. The inferior and the middle hemorrhoidal veins empty into the hypogastric (caval) vein. In obstructions of the portal system the veins in the rectum become dilated and the blood passes into the caval channels. These dilated vessels form hemorrhoids (piles).

4 *Around the umbilicus* veins passing along the falciform ligament to the umbilicus connect the veins of the liver (portal) with the epigastric veins around the umbilicus (caval). Enlargement of these veins produces the so-called caput Medusae.

Although connections exist between these two venous systems, they seldom suffice to produce a portal compensation when the portal system is obstructed. In an attempt to communicate the portal and the caval systems, surgical procedures which result in portacaval and splenorenal shunts are now being done. At present the results of these operations are quite encouraging.

sary to resect a considerable length of colon. Therefore typical lesions result in typical resection patterns (Fig. 348).

1 *Cancer of the cecum and the ascending colon* The blood vessel which supplies this part of the colon is the ilioocolic branch of the superior mesenteric artery. It supplies the last six to eight inches of the ileum, the cecum, the ascending colon and the hepatic flexure. In this resection therefore it becomes necessary to remove the terminal six inches of ileum, the cecum, the ascending colon and the hepatic flexure since the associated lymphatics should be included.

2 *Cancer of the hepatic flexure* This flexure is supplied by the right colic and the middle colic arteries. As for cancer of the ascending colon and the cecum the amount to be removed is essentially the same as that previously described since the lymph drainage and the blood supply are the same.

3 *Cancer of the transverse colon* This part of the large intestine is supplied by the middle colic branch of the superior mesenteric artery. It is necessary to remove from three to four inches to either side of the growth thereby removing the lymph draining area.

4 *Cancer of the splenic flexure* The splenic flexure is supplied by the left colic branch of the inferior mesenteric artery. The area supplied by the left colic includes the colon from the junction of the middle and the left thirds of the transverse colon

to the middle of the descending colon; therefore, this area must be removed.


5 *Cancer of the descending colon* This portion of the colon is supplied by the left colic and the upper sigmoid branch of the inferior mesenteric artery. Reaction which is necessary here is the same as for the splenic flexure plus the upper half of the pelvic colon.

6 *Cancer of the iliac colon* The iliac colon is supplied by the upper and the lower sigmoid arteries. Resection involves the removal of the lower half of the descending colon, the iliac colon and the upper half of the pelvic colon.


7 *Cancer of the pelvic colon* This portion of the colon is supplied by the sigmoid and the superior hemorrhoidal branches of the inferior mesenteric artery. In carcinoma of this portion of the bowel it is desirable to resect the middle of the descending colon where the left colic area begins. The lower extent of this resection naturally varies with the situation of the growth. If the growth is situated fairly high in the pelvic colon the resection is accomplished near the pelvicorectal junction with an anastomosis of the divided ends of bowel; however, if the lesion is low in the pelvic colon the rectum also may require excision.

8 *Cancer of the rectum* This part of the large bowel is involved in half of all cases of carcinoma of the colon. W. E. Miles has described three zones of lymphatic spread in carcinoma of the rectum: downward, lateral and upward (Fig. 349).


FIG. 348. Extent of resection necessary in malignant lesions involving portions of the large bowel. (A) Carcinoma of the cecum or the ascending colon requires removal of the terminal 6 or 8 inches of the ileum, the cecum, the ascending colon and the transverse colon up to the middle colic artery. (B) Carcinoma of the transverse colon requires removal of enough bowel to incorporate from 3 to 4 inches of normal tissue to either side of the growth. (C) Carcinoma of the splenic flexure requires removal of the colon from the junction of the middle and the left thirds of the transverse colon to the middle of the descending colon. (D) Carcinoma of the descending colon requires resection similar to that used for splenic flexure carcinoma plus the removal of the upper half of the pelvic colon. (E) Carcinoma of the pelvic colon requires removal of the middle of the descending colon to the region of the pelvicorectal junction. (F) Carcinoma of the rectum requires removal of the bowel distal to the lower part of the sigmoid.




A




B




C



D



E



F

FIG 348 (Legend on facing page)

way of the lesser splanchnic and possibly the lowest splanchnic nerves. From here they proceed to the superior mesenteric plexus by way of communicating nerves. The fibers which supply the cecum the appendix the ascending and the transverse colon originate in the superior mesenteric ganglia from which nerves pass along the superior mesenteric artery to reach the bowel. Some of the other nerve fibers which leave the superior mesenteric ganglion join the intermesenteric nerves anterior to the aorta. The lumbar sympathetic nerves leave the sympathetic chain via the lumbar splanchnic nerves and join the intermesenteric nerves. The fibers to the descending colon the sigmoid colon and the upper rectum originate in the inferior mesenteric plexus and follow the course of the inferior mesenteric artery to the bowel wall. The intermesenteric nerves pass downward anterior to the bifurcation of the aorta as the hypogastric plexus. This plexus divides into right and left pelvic plexuses each lying to one side of the rectum. These fibers supply the bladder the prostate the pelvic organs and also form the so-called rectal plexus.

The *parasympathetic fibers* arise from both the vagus and the pelvic nerves. These are distributed to the large bowel with the sympathetic fibers. The *nervi erigentes* are the sacral autonomic nerves which arise from the second the third and the fourth sacral nerves. They join the pelvic plexuses on each side and are distributed to the bowel with the sympathetic fibers. Some fibers follow the course of the left common iliac artery to the inferior mesenteric artery and are distributed to the descending colon and the sigmoid.

The pudendal nerve originates from the second the third and the fourth sacral nerves. It accompanies the internal pudendal artery. It enters the perineum runs in Alcock's canal and gives off the inferior hemorrhoidal nerve which reaches the external sphincter and the lower cutaneous part of the anal canal.




FIG. 350 Lymph drainage of the anal canal and the lower rectum. The arrows indicate the two main courses of lymph flow. Lymph from the lower part of the anal canal passes across the perineum to the superficial inguinal nodes. Lymph from the upper part of the anal canal passes upward to the inferior mesenteric nodes.

LARGE BOWEL SURGERY

CECOSTOMY

A cecostomy may be performed either as an emergency procedure for large bowel obstruction or as an elective procedure preliminary to operations on the colon. The so-called 'blind' type of cecostomy is a simple and efficient method for decompression. A modified McBurney incision is made close to the anterior superior iliac spine, and the cecum is identified and delivered. Two noncrushing clamps are placed on a longitudinal band, and a piece of gauze is placed between the cecum and the parietal peritoneum. The clamps are taped in place. At least three hours are permitted to elapse for walling off, and then an incision is made between the clamps and into the cecum. A mushroom catheter is sewn into the cecal lumen.

COLOSTOMY

The *Devine colostomy* has been called a 'defunctioning' operation because the con-




FIG 349 The lymphatic drainage of the rectum. The arrows indicate the three zones of lymphatic spread. Zone 1 travels upward, zone 2 laterad, between the pelvic fascia and the levator ani muscle, zone 3 spreads downward.

The *downward spread* involves the perineal skin, the ischiorectal fat and the external sphincter ani muscle. This set of lymph vessels constitutes the lowest of the three sets and is situated between the white line and the anal orifice. The *lateral spread* of lymph vessels constitutes the middle zone which is situated between the levator ani and the pelvic fascia. It includes the levator ani muscle, the sacral and the internal iliac glands, the base of the bladder and the seminal vesicles. In the female the posterior vaginal wall, the cervix and the base of the broad ligaments also are involved. Occasionally, there is a lymph gland which is situated on the uterine artery where it crosses the ureter (Toirier's gland). The *upward flow* of lymphatics involves the pelvic peritoneum, the pelvic mesocolon and the glands at the bifurcation of the left common iliac artery. These vessels follow the course of the superior hemorrhoidal arteries. Although the three sys-

tems drain in different directions, they communicate freely.

Lymph from the anal canal and the adjoining part of the rectum in general follows two courses (Fig 350). The lymph vessels from the lower part of the anal canal pass downward and forward across the perineum and then travel along the vulva or the scrotum to the inner margin of the thigh, and in this way reach the superficial inguinal lymph nodes. Lymph from the upper part of the anal canal and the rectum passes upward to the preaortic nodes, which are associated with the inferior mesenteric group of nodes. If this is kept in mind it can be understood readily that involvement of the superficial inguinal glands could be associated only with a lesion extremely far down in the terminal part of the anal canal.

Gilchrist and David found retrograde metastases to the level of 4 cm below the primary lesion in 2 cases out of 22. In both of these cases however the lymph nodes above the lesion were completely blocked with carcinomatous cells.

If a rectal lesion as well as its associated lymphatics is to be removed, the extent of the operation is great. It would be necessary to remove most of the pelvic colon and the mesocolon, the rectum, the anus, the surrounding skin, the fat of the ischiorectal fossae and the levator ani muscles.

NERVE SUPPLY OF THE COLON

The nerve supply to the large bowel is derived from the autonomic nervous system, except for the lower end of the anal canal, which is supplied by the inferior hemorrhoidal nerve (Figs 351 and 352). The colon, therefore, has both sympathetic and parasympathetic fibers.

The *sympathetic fibers* are derived from the lower thoracic and the upper lumbar segments of the spinal cord. They reach the sympathetic chain via corresponding white rami communicantes. The thoracic fibers then proceed to the celiac plexus by

way of the lesser splanchnic and possibly the lowest splanchnic nerve. Then, therefore, they proceed to the superior mesenteric plexus by way of communicating nerve. The others which supply the cecum, the appendix, the ascending and the transverse colon originate in the superior mesenteric ganglia from which nerves pass along the superior mesenteric artery to reach the bowel. Some of the afferent nerve fibers which leave the superior mesenteric ganglia join the inferior mesenteric nerve anterior to the aorta. The lumbar sympathetic nerves leave the sympathetic chain via the lumbar splanchnic nerves and join the inferior mesenteric nerves. The fibers to the descending colon, the sigmoid colon and the upper rectum originate in the inferior mesenteric plexus and follow the course of the inferior mesenteric artery to the bowel wall. The inferior mesenteric nerve passes downward anterior to the bifurcation of the aorta as the hypogastric plexus. This plexus divides into right and left pelvic plexuses each lying to one side of the rectum. The fibers supply the bladder, the prostate, the pelvic organs and also form the so-called rectal plexus.

The *parasympathetic fibers* arise from both the vagus and the pelvic nerves; these are distributed to the large bowel with the sympathetic fibers. The nervi erigentes are the sacral autonomic nerves which arise from the second, the third and the fourth sacral nerves. They join the pelvic plexuses on each side and are distributed to the bowel with the sympathetic fibers. Some fibers follow the course of the left common iliac artery to the inferior mesenteric artery and are distributed to the descending colon and the sigmoid.

The pudendal nerve originates from the second, the third and the fourth sacral nerves; it accompanies the internal pudendal artery. It enters the perineum, runs in Alcock's canal and gives off the inferior hemorrhoidal nerve which reaches the external sphincter and the lower cutaneous part of the anal canal.




FIG. 350 Lymph drainage of the anal canal and the lower rectum. The arrows indicate the two main courses of lymph flow. Lymph from the lower part of the anal canal passes across the perineum to the superficial inguinal nodes. Lymph from the upper part of the anal canal passes upward to the inferior mesenteric nodes.

LARGE BOWEL SURGERY

CECOSTOMY

A cecostomy may be performed either as an emergency procedure for large bowel obstruction or as an elective procedure preliminary to operations on the colon. The so-called blind type of cecostomy is a simple and efficient method for decompression. A modified McBurney incision is made close to the anterior superior iliac spine and the cecum is identified and delivered. Two noncrushing clamps are placed on a longitudinal band and a piece of gauze is placed between the cecum and the parietal peritoneum. The clamps are taped in place. At least three hours are permitted to elapse for walling off and then an incision is made between the clamps and into the cecum; a mushroom catheter is sewn into the cecal lumen.

COLOSTOMY

The *De me colostomy* has been called a defunctioning operation because the con-




FIG 351 The nerve supply of the large bowel

tents of the proximal colon are prevented from entering the distal colon. Devine has resected successfully segments of the left half of the colon with primary suture of the sigmoid to a short rectal stump.

In performing a *loop colostomy* the portion of bowel selected is brought out through the incision and a small opening is made in its mesentery near the bowel wall. Through this opening a tape or a rubber tube is passed for traction. The peritoneum is closed beneath the loop with two or three sutures; the anterior fascia and the skin also are sutured beneath the loop in the same manner. The closure of the wound is completed with interrupted sutures placed above and below the loop. A glass rod or a rubber tube is placed beneath the loop to prevent retraction.

RESECTION OF THE COLON

In malignant diseases involving the right side of the colon, a segment should

be removed which includes the terminal six or eight inches of the ileum, the cecum, the ascending colon, the hepatic flexure and part of the transverse colon. Lesions which involve the colon in that part of bowel which is situated between the middle colic and superior hemorrhoidal artery can be resected and anastomosed or exteriorized by means of the Mikulicz procedure. Lesions which involve the lower sigmoid, the recto-sigmoid and the rectum usually require an abdominoperineal operation, but some (Dixon and Devine) prefer to remove the malignancy and attempt an anastomosis (Fig 348).

Resection of the right side of the colon is done for lesions which involve the terminal ileum, the cecum, the ascending colon, the hepatic flexure and the proximal third of the transverse colon (Fig 353). A long right rectus incision is made, the ascending colon is pulled toward the midline and the posterior parietal peritoneum is incised along the lateral paracolic gutter; an avascular retrocolic cleavage plane is entered. This mobilizes the right colon so that it hangs by its original mesentery. As the medial dissection is continued, the spermatic (ovarian) vessels first come into view and then the ureter, which usually remains adherent to the peritoneum; the retroperitoneal portion of the duodenum must be separated from the mesentery of the upper part of the ascending colon (Fig 353 B). The mesentery which holds the ileum, the ascending colon and that part of the transverse colon which is to be removed is then clamped, cut and ligated, two clamps are placed on the ileum at the point where it is to be transected and two more clamps are placed upon the transverse colon at the point where it is to be removed. The bowel between these clamps is severed. The anastomosis is accomplished by closure of the blind ends of the ileum and the colon followed by a lateral anastomosis; closure of only the end of the colon with an end-to-side ileotransverse colostomy is preferred by some.

A lower left rectus incision is made. This is carried well above the level of the umbilicus. The posterior parietal peritoneum lateral to the sigmoid is divided and the sigmoid, the mesosigmoid and the descending colon are mobilized. Once this cleavage plane is entered the mesosigmoid is freed almost to the midline and three structures are identified. From left to right they are the left spermatic (ovarian) vessels, the left ureter and the superior hemorrhoidal vessels. At this stage the left ureter is in danger of being ligated when the superior hemorrhoidal vessels are tied. For this reason the ureter should be identified and retracted. The left colic artery, the first

The Miltz is the large, vascular, elongated organ that lies in the upper left quadrant of the abdomen. It is a part of the digestive system and is connected to the stomach by the splenic artery and vein. The spleen is a large, soft, and spongy organ that is about the size of a fist. It is located in the upper left quadrant of the abdomen, just below the stomach. The spleen is a part of the digestive system and is connected to the stomach by the splenic artery and vein. The spleen is a large, soft, and spongy organ that is about the size of a fist. It is located in the upper left quadrant of the abdomen, just below the stomach. The spleen is a part of the digestive system and is connected to the stomach by the splenic artery and vein.

Many operations have been devised for excision of the rectosigmoid and the more distal lesions. A *no-stage laparotomy* or *rectal resection* (Miles) will be described (Figs. 355 and 356).

A lower left rectus incision is made. This is carried well above the level of the umbilicus. The posterior parietal peritoneum lateral to the sigmoid is divided and the sigmoid, the mesosigmoid and the descending colon are mobilized. Once this cleavage plane is entered the mesosigmoid is freed almost to the midline and three structures are identified. From left to right they are the left spermatic (ovarian) vessels, the left ureter and the superior hemorrhoidal vessels. At this stage the left ureter is in danger of being ligated when the superior hemorrhoidal vessels are tied. For this reason the ureter should be identified and retracted. The left colic artery, the first




FIG. 352 Side view of the nerve supply to the lower part of the large bowel and to the anal canal

and the second sigmoidal arteries and the superior hemorrhoidal artery are then isolated. A point of division which ensures viability to the remaining sigmoid is selected. The sigmoid is reflected to the left side and the posterior parietal peritoneum is incised in a fashion similar to that used on the right side until this incision connects with the one made on the left. The right ureter is identified. A usual good guide for the level of ligation of the superior hemorrhoidal artery is the promontory of the sacrum. This permits preservation of the remaining sigmoidal blood supply. When the superior hemorrhoidal vessels have been divided a cleavage plane is easily found between the posterior surface of the bowel and the sacrum. With the hand kept as close to the sacrum as possible a loose areolar space is entered, and the rectum is freed as low as the tip of the




FIG 351 The nerve supply of the large bowel

tents of the proximal colon are prevented from entering the distal colon. Devine has resected successfully segments of the left half of the colon with primary suture of the sigmoid to a short rectal stump.

In performing a *loop colostomy* the portion of bowel selected is brought out through the incision and a small opening is made in its mesentery near the bowel wall. Through this opening a tape or a rubber tube is passed for traction. The peritoneum is closed beneath the loop with two or three sutures; the anterior fascia and the skin also are sutured beneath the loop in the same manner. The closure of the wound is completed with interrupted sutures placed above and below the loop. A glass rod or a rubber tube is placed beneath the loop to prevent retraction.

RESECTION OF THE COLON

In malignant diseases involving the right side of the colon, a segment should

be removed which includes the terminal ileum or eight inches of the ileum, the cecum, the ascending colon, the hepatic flexure and part of the transverse colon. Lesions which involve the colon in that part of bowel which is situated between the middle colic and superior hemorrhoidal artery can be resected and anastomosed or exteriorized by means of the Mikulicz procedure. Lesions which involve the lower sigmoid, the rectum and the rectum usually require an abdominoperineal operation but some (Dixon and Devine) prefer to remove the malignancy and attempt an anastomosis (Fig 348).

Resection of the right side of the colon is done for lesions which involve the terminal ileum, the cecum, the ascending colon, the hepatic flexure and the proximal third of the transverse colon (Fig 353). A low right rectus incision is made; the ascending colon is pulled toward the midline and the posterior parietal peritoneum is incised along the lateral paracolic gutter; an avascular, retrocolic cleavage plane is entered. This mobilizes the right colon so that it hangs by its original mesentery. As the medial dissection is continued the spermatic (ovarian) vessels first come into view and then the ureter which usually remains adherent to the peritoneum. The retroperitoneal portion of the duodenum must be separated from the mesentery of the upper part of the ascending colon (Fig 353 B). The mesentery which holds the ileum, the ascending colon and that part of the transverse colon which is to be removed is then clamped, cut and ligated. Two clamps are placed on the ileum at the point where it is to be transected, and two more clamps are placed upon the transverse colon at the point where it is to be removed. The bowel between these clamps is severed. The anastomosis is accomplished by closure of the blind ends of the ileum and the colon followed by a later anastomosis; closure of only the end of the colon with an end to side ileotransverse colostomy is preferred by some.



1. The rectum is the terminal part of the digestive tract. It is the part of the large intestine that leads to the cloaca. In the male, it is the part of the large intestine that leads to the cloaca. In the female, it is the part of the large intestine that leads to the cloaca.

2. The rectum is the terminal part of the digestive tract. It is the part of the large intestine that leads to the cloaca. In the male, it is the part of the large intestine that leads to the cloaca. In the female, it is the part of the large intestine that leads to the cloaca.




FIG 353 Right hemicolectomy This resection includes the last 6 to 8 inches of ileum and is usually done for malignant neoplasms (A) The amount of tissue to be removed (B) Mobilization of the ascending colon reveals the spermatic (ovarian) vessels the ureter and the duodenum (C) Clamps applied prior to the resection of the bowel The major blood vessels have been divided and tied (D) Lateral anastomosis between the terminal ileum and the transverse colon has been completed




FIG. 354. The Mikulicz (exteriorization) procedure. (A) The involved bowel, sigmoid, with a pur formed by suturing together the bowel that is proximal and distal to the lesion. (B) The involved segment removed. (C) The proximal and distal ends of the bowel being closed. (D) The resulting, male-barreled colo tomy. (E) Closure of the bowel.

cecyx, thus mobilizes the rectum posteriorly. The operation is then directed toward freeing the rectum anteriorly. In the male a cleavage plane is found between the prostate and the bowel, in the female between the uterus and the bowel. This dissection is carried downward until the anal vest

cles are seen in the male or until the tip of the cervix can be felt in the female. With the bowel freed anteriorly and posteriorly, only its lateral attachments remain, namely, the so-called lateral or suspensory ligaments. These contain the middle hemorrhoidal vessels as they pass to the lateral




FIG. 355. Abdominoperineal resection. (A) long, lower left rectus incision, (B) both right and left leaves of peritoneum have been divided and then joined in the midline, (C) isolation of ureters, spermatic vessels and superior hemorrhoidal artery, (D) the superior hemorrhoidal artery has been ligated and divided and the rectum is freed posteriorly to the tip of the coccyx, (E) mobilization of the rectum from its lateral attachments, (F) the sigmoid is divided between clamps, (G) the distal end of the divided sigmoid is placed deep into the pelvis. The sutured peritoneum forms the new pelvic floor.




FIG 356 Abdominoperineal resection (*continued*) (H) circular incision around the anus (I) dissection carried through the sphincter ani muscle, (J) the pelvic fascia is incised immediately below the tip of the coccyx (K) the levator ani muscles on both sides are divided (L) dissection is completed and the involved segment is removed

bowel wall on each side. Some surgeons believe it unnecessary to ligate the vessels; however, it makes for cleaner and safer surgery to clamp, cut, and place a ligature around them. Following these maneuvers, the bowel is detached completely from its anterior, posterior, and lateral attachments. Once the bowel is freed completely, two clamps are placed on the

sigmoid and the bowel is divided between these. The proximal clamp remains on the permanent colostomy. The distal bowel is folded on itself and is turned down into the hollow of the sacrum. The peritoneum is freed from the bladder, and a new pelvic floor is made by suturing this mobilized peritoneum. In the female, instead of dis-




FIG 355 Abdominoperineal resection (A) long, lower left rectus incision (B) both right and left leaves of peritoneum have been divided and then joined in the midline (C) isolation of ureters spermatic vessels and superior hemorrhoidal artery, (D) the superior hemorrhoidal artery has been ligated and divided and the rectum is freed posteriorly to the tip of the coccyx (E) mobilization of the rectum from its lateral attachments (F) the sigmoid is divided between clamps (G) the distal end of the divided sigmoid is placed deep into the pelvis The sutured peritoneum forms the new pelvic floor




FIG 358 Sliding hernia (A) This figure is used for comparison to show the formation of a typical inguinal hernia sac (B) The posterior parietal peritoneum lateral to the sigmoid will pass through the internal inguinal ring this results in an unfolding of the peritoneal leaves which form the mesosigmoid (C) On opening the peritoneum one finds the colon occupying the apex of the sac The continuity of the peritoneum is over the colon and continues along the posterior wall of the sac (D) If a laparotomy is performed and the sigmoid is drawn into the peritoneal cavity, the opening which previously has been made in the sac becomes a defect in the lateral leaf of the mesosigmoid




FIG 357 A sliding hernia seen through a sagittal section on the right side. Both visceral and parietal peritoneum form the sac. The blood vessels are in the properitoneal fat layer.

secting the peritoneum off of the bladder, the uterus and the adnexae may be used as the anterior flap and the peritoneum as a posterior one. The wound is closed around the permanent colostomy. The patient is placed on his left side, back or abdomen for the perineal part of the operation.

An incision is made around the anus so that it passes over the sacrococcygeal joint and meets in the perineum (Fig 356 H). This incision is deepened and the inferior hemorrhoidal vessels are ligated. A transverse incision is made just below the tip of the coccyx and the deep pelvic fascia (fascia propria) is identified and incised. This enters the presacral space which has been dissected previously. A finger is placed laterally so that the upper surface of the levator ani muscle is felt and divided at its posterior two thirds. The same is done on the opposite side. The entire distal bowel segment can then be withdrawn

easily, the transverse perineal muscles are severed, and the anterior portion of the levators is divided. This leaves the bowel attached anteriorly for a short distance either to the muscles over the membranous urethra or the vagina. A cleavage plane is found the bowel is removed and all bleeding points are controlled. The wound may be drained or closed tightly.

SLIDING HERNIA

Sliding hernia has been defined as the extrusion of an organ (ascending, descending or sigmoid colons) in such a way that the visceral peritoneum forms part of the sac (Fig 357). Therefore, attempts to isolate the sac as in indirect inguinal hernias are impossible. R. R. Graham is of the opinion that the formation of such a hernia is the result of a pushing mechanism which shoves the posterior parietal peritoneum lateral to the sigmoid so that it appears at the internal ring. As a result of this, the mesosigmoid unfolds, and the sigmoid comes to lie at the apex of the hernia (Fig 358). The vessels then lie behind the colonic segment and are exposed to injury if they are mistaken for adhesions and if dissection is carried in this plane. If one attempts to separate such "adhesions," encroachment upon the blood supply of the colon may result in devitalization of the bowel. Since complete reduction of the contents, high ligation of the sac and proper repair are impossible in this type of hernia, another method must be sought. Moschowitz suggested that the peritoneal cavity also be opened and the sigmoid be drawn back into it through the abdominal incision. It then is noted that the opening which has been made in the hernial sac through the inguinal incision is truly an incision in the anterior (lateral) layer of mesosigmoid. This defect is closed. Following this no hernial sac is present. The abdominal wound is closed, and the inguinal canal is repaired by one of the routine methods.




FIG 359 The liver (A) seen from in front the right lobe is pulled toward the midline to place the right triangular ligament on a stretch (B) seen from behind, (C) the inferior surface

The Liver (Hepar)

EMBRYOLOGY

The hepatic diverticulum is the primordial outgrowth of cells destined to form the secretory tubules of the liver, its duct system and the gallbladder. It arises ventrally during the fourth week from the entodermal lining of the gut, and when it is first recognizable, it lies just caudad to the heart. A maze of anastomosing and branching cell cords grows ventrad and cephalad. The distal portions of these cords give rise to the secretory tubules of the liver and their proximal portions form the hepatic ducts. The growing hepatic tubules push between the two layers of splanchnic mesoderm which form the ventral mesentery and spread these two layers apart. The investing mesodermal layers form the fibrous connective tissue capsule of the liver and the interstitial connective tissue of the liver lobules.

THE LIVER PROPER

The liver is the largest gland in the body, is extremely vascular and has many functions to perform (Fig. 359). It receives its arterial blood supply from the hepatic artery and the portal vein conveys blood to it from the intestinal tract. The blood of the liver is drained by the hepatic veins which open into the inferior vena cava. This organ resembles the shape of a pyramid, the base being to the right and the apex to the left. The sides of the pyramid are formed by the superior, inferior, anterior and posterior surfaces. In the adult it constitutes approximately one fiftieth of the body weight, it occupies the

uppermost part of the abdomen, chiefly on the right side. The organ is in close relation with the diaphragm and is covered by the ribs which afford it some protection. At birth the liver is relatively larger. This is especially true of the left lobe, the prominent bulging of an infant's abdomen is mainly due to the large size of the gland.

The *falciform ligament* of the liver is a wide fold of peritoneum which lies obliquely between the liver and the anterior abdominal wall. The right surface of this ligament is in close contact with the abdominal wall, and the left surface is in contact with the liver. The ligament has three borders: an upper border which is attached to the diaphragm and to the anterior abdominal wall as far as the umbilicus, the second border is attached to the upper and the anterior surfaces of the liver, dividing it into right and left lobes. The third border is a free edge where the two layers of the ligament become continuous with each other. The round ligament (*ligamentum teres*) passes in this free edge. If the left lobe of the liver is pulled away from the diaphragm a fold of peritoneum, the *left triangular ligament* is placed on the stretch. It connects the left hepatic lobe to the diaphragm and presents three borders. One border is attached to the back of the upper surface of the left lobe, the second is attached to the central tendon of the diaphragm, and the third is a free edge which is directed toward the left where the two layers of the ligament are continuous with each other (Figs. 360 and 361).

If the fingers of the right hand are

passed backward over the top of the right lobe they are topped by a layer of peritoneum which is known as the *upper layer of the triangular (coronary) ligament* (Fig. 360). This is reflected from the back of the right lobe onto the diaphragm. If the fingers of the left hand are passed upward behind the right part of the right lobe and pressed backward they will be stopped by the *lower layer of the triangular (coronary) ligament*. The lower layer is reflected from the inferior surface of the liver onto the right kidney, the adrenal gland and the inferior vena cava; it also is referred to as the *hepatorenal ligament*. Below this ligament is a peritoneal space known as the *hepatorenal pouch* (Morrison). The upper and the lower layers of the coronary ligament approximate each other at the right extremity of the liver and where they fuse they form the *right triangular ligament*. This ligament is not as well marked as the left because its two layers diverge so rapidly.

Between the two layers of the coronary ligament there is a fairly large triangular area of liver which is devoid of peritoneum and is known as the *bare area*; it is attached directly to the diaphragm by areolar tissue. The apex of this bare triangular area corresponds to the meeting point of the two layers of the coronary ligament on the right where they form the right triangular ligament. The base of the triangle is formed by the fossa for the inferior vena cava. The bare area is in contact with the inferior vena cava, the upper part of the right suprarenal gland and the diaphragm. It is connected to the liver by connective tissue in which are found the veins of Retzius which form a portosystemic anastomosis (Fig. 344).

The student's crutch, the time honored letter *H*, is formed by structures which lie on the inferior surface of the liver (Fig. 359C). The left limb of the letter *H* divides this surface into right and left lobes. It contains embryonic structures, namely the fissure for the ligamentum teres (left umbilical vein) in front and the fis-




FIG. 362 Diagrammatic representation of fetal circulation

sure for the ductus venosus behind. Fetal blood is returned from the placenta to the fetus by means of the umbilical vein which enters the abdomen at the umbilicus, passes upward along the free margin of the falciform ligament to the under surface of the liver. At the transverse fissure of liver (porta hepatis) it divides into branches, one of these joins the portal vein and enters the right lobe, the other joins the ductus venosus, thereby short-circuiting the blood to the inferior vena cava (Fig. 362). Therefore since the umbilical vein and ductus venosus were continuous with each other in fetal life it is quite natural that their adult landmarks (ligamentum teres and ligamentum venosum) should also be continuous, thereby forming the left limb of the *H*.

The right limb of the *H* contains visceral structures, the fossa for the gallbladder in front and the inferior vena cava behind. The transverse part of the *H* is formed by the porta hepatis (the transverse fissure) and this contains from before backward the hepatic duct, the hepatic artery and branches of the portal vein. The




FIG 360 The ligaments of the liver. The liver has been displaced to the right and out of the peritoneal cavity so that its ligamentous attachments may be seen. This illustration, therefore, shows the posterior aspect of the liver and the anterior aspect of the posterior abdominal wall to which the liver is normally attached.




FIG 361 The diaphragmatic attachments of the liver, (A) relations of heart and lungs (B) seen from below the diaphragm, with the liver removed.




FIG 363 The portal vein and the portal system

stomach and to the lesser omentum. The gastric impression appears as a wide shallow concave area to the left. The omental part is a bulging prominence to the right and behind; it is called the *tuber omentale*. The quadrate lobe lies between the fissure for the ligamentum teres and the fossa for the gallbladder. This lobe is related to the pyloric part of the stomach and the first

part of the duodenum below, and to the right part of the lesser omentum above. It is the quadrate lobe which attempts to seal over perforated peptic ulcers, the vast majority of which occur in this portion of the stomach or in the duodenum. The gallbladder lies in front of the first and the second parts of the duodenum, but the latter extends beyond it and is in relation to the

porta is deep and wide and is about two inches long a portion of the lesser omentum is attached to it. The nerves of the liver and most of its lymph vessels also are found here. Besides these structures it also contains fatty tissue and some lymph glands which when enlarged may obstruct the flow of bile in the hepatic ducts, thereby causing jaundice. The hepatic duct is formed on the right side of the porta by the union of the right and the left hepatic ducts. The branches of the hepatic artery enter on the left side of the common duct and then pass behind the right and the left ducts. The portal vein lies behind the artery. The porta hepatis is bounded anteriorly by the quadrate lobe and posteriorly by the caudate lobe of the liver.

LOBES AND SURFACES

The liver consists of two lobes a larger right and a smaller left lobe. The proportion between the two is as six is to one. They are divided by the fissure for the ligamentum venosum on the posterior sur-

- the fissure for the ligamentum teres
- the inferior surface and the attachment of the falciform ligament on the superior
- the anterior surfaces. Two circumscribed areas which are found over the medial part of the right lobe are also referred to as 'lobes' they are the quadrate lobe on the inferior surface situated between the gallbladder and the fissure for the ligamentum teres and the caudate lobe on the posterior surface, situated between the inferior vena cava and the fissure for the ligamentum venosum.

The base of the pyramidal shaped liver is the *right lateral surface* it is somewhat quadrilateral and convex. It is related to the diaphragm opposite the seventh to the eleventh ribs in the midaxillary line. The pleura and the right lung are important relations to this surface they are separated by the diaphragm. In the midaxillary line the pleura overlaps the liver as low as the tenth rib and the lung to the eighth. The twelfth rib, as a rule, does not reach suf-

ficiently far forward to come into relation ship to this hepatic surface. Therefore a puncture wound over the lower part of the right side of the thorax may pass through the pleura, the lung, the diaphragm, the peritoneum and the liver (Fig 342).

The anterior surface of the liver is of considerable clinical importance, since it is the surface which is most readily accessible for examination as far as the tenth costal cartilage on the right side. The median portion, which lies against the anterior abdominal wall, is palpated easily and thus yields valuable information. If inspiration is forced almost the entire inferior border of the liver can be felt.

The *superior surface* is related to the diaphragm, which separates it from the two pleural sacs and the pericardium. On the right side it rises into a convexity that reaches almost to the level of the right nipple. On the left, the surface ends as a thin edge which is opposite the fifth rib in a line dropped from the left nipple.

The *posterior surface* cannot be seen until the liver has been removed from the body (Fig 359 B). On the left this surface is covered with peritoneum of the greater sac, and a groove made by the esophagus is formed here. In the median plane is the caudate lobe which is covered with peritoneum of the lesser sac. This lobe lies between the fossa for the vena cava and the fossa for the ductus venosus. To the right of this the bare area is found. The inferior vena cava occupies the leftmost portion of the area, and the kidney and the adrenal gland encroach upon it from below.

The *inferior surface* also has been called the *visceral surface* of the liver (Fig 359 C). It faces downward, to the left and backward. It is covered with the peritoneum of the greater sac and everywhere shows the imprints of viscera with which it is in contact. It is only distinctly separated from the inferior surface, and the 'H' which has been described occupies this surface. The part of this surface which belongs to the left lobe is related to the

The liver is a large, soft, reddish-brown organ, situated in the right upper quadrant of the abdomen, beneath the diaphragm. It is the largest gland in the body and is responsible for the production and secretion of bile. The liver is divided into two main lobes, the right and left lobes, by the falciform ligament. The right lobe is larger and is situated on the right side of the body, while the left lobe is smaller and is situated on the left side. The liver is covered by a thin, fibrous capsule, and its surface is marked by numerous blood vessels and ducts. The liver is connected to the gallbladder by the cystic duct and to the duodenum by the common bile duct. The liver is also connected to the inferior vena cava by the inferior vena cava and to the superior vena cava by the superior vena cava.

The portal system of the liver is a network of blood vessels that carries blood from the digestive organs to the liver. The portal system is formed by the union of the superior mesenteric vein and the splenic vein, which join to form the portal vein. The portal vein enters the liver at the porta hepatis and divides into numerous smaller branches that permeate the liver tissue. The portal system is responsible for the transport of nutrients and toxins from the digestive organs to the liver, where they can be processed and stored. The portal system is also responsible for the transport of bile from the liver to the gallbladder and to the duodenum. The portal system is a critical component of the liver's function and is essential for the health of the entire body.

The nerves of the liver are derived from the left vagus and the sympathetic. They enter at the porta hepatis and accompany the vessels and the ducts to the interlobular spaces.

The lymph vessels of the liver terminate largely in a small group of lymph glands in and around the porta hepatis. The efferent vessels from these glands pass to the celiac lymph glands. Some of the superficial lymph vessels in the anterior surface of the liver pass to the diaphragm in the falciform ligament and finally reach the mediastinal glands. There is another group which accompanies the inferior vena

and is related to the intra-hepatic lymphatics.

STRUCTURE

The liver is determined by its position. Only an approximate size of the gland can be obtained, since the exact location of the limits of the liver is difficult to obtain because the lower edge of the lung overlaps the liver above and the stomach overlaps the liver below. The upper part of the right lobe (highest point of the liver) lies beneath the right dome of the diaphragm; it is on a level with the upper margin of the fifth rib about an inch medial to the mammary line and about 1 cm. below the right nipple. The upper limit of the left lobe corresponds to the upper border of the sixth rib in the mammary line about an inch below the left nipple. At this point the left tip of the liver is separated from the apex of the heart only by the diaphragm. The lower border of the liver can be traced best from right to left. It follows the costal arch as far as the tip of the ninth costal cartilage; however, in the erect position it may descend an additional inch below the ribs. From the ninth costal cartilage it crosses obliquely until it reaches the tip of the eighth costal cartilage on the left side. From this point on it continues laterally until it meets the upper and the lateral limits of the left lobe. In the midline the lower border of the liver lies midway between the xiphoid and the umbilicus.

PRACTICAL AND SURGICAL CONSIDERATIONS

THE SIX SUBPHRENIC SPACES

The one large subphrenic area is divided into six subphrenic spaces (Fig. 364). The 'subphrenic space' is a region situated between the diaphragm above and the transverse colon and its mesocolon below. The

adjoining part of the right lobe. Directly to the right of the duodenal area the right colic flexure leaves its imprint and behind this the under surface of the right lobe is related to the right kidney, which leaves its renal impression.

The liver is completely covered with peritoneum except in three locations namely the bare area, the groove for the inferior vena cava and the gallbladder fossa. The lesser omentum is attached to the margins of the porta hepatis and around its right extremity its two layers are continued from the left extremity of the porta hepatis to the fissure for the ligamentum venosum. At the upper end of this fissure these two layers separate. The ligaments mentioned in connection with the liver should not be regarded as supporting the entire weight of the organ since it like other abdominal and pelvic organs, is kept in place by intra abdominal pressure which is attributed mainly to the tonus of the muscles of the anterior and the lateral abdominal walls. Therefore it is of little or no consequence when one of the so called supporting ligaments of the liver is severed during surgical procedures since the liver will not become ptotic.

VESSELS, NERVES AND LYMPHATICS

The liver has three vessels associated with it the hepatic artery, the portal vein and the hepatic veins. The *hepatic artery* one of the trifurcating branches of the celiac axis supplies arterial blood to the substance of the liver. Daseler Anson, et al reported on investigations made in 500 laboratory specimens. They observed that the *common hepatic artery* arose as a branch of the celiac axis in 416 of the 500 (83.2 per cent). This vessel was absent in 61 cases (12.2 per cent). When the common hepatic artery was absent the right and the left hepatic lobes derived their arterial supply from separate branches. These anatomists found that in 358 of 439 cases studied (81.54 per cent) the common hepatic artery was a rather long trunk which

divided into its hepatic branches within 4 cm of the liver surface, in 81 cases (18.46 per cent) the artery was short and divided into hepatic branches which ascended for a distance of more than 4 cm. A normal *right hepatic artery* (one which supplies the right lobe of the liver after originating from a normal common hepatic artery) was present in 416 of 500 cases (83.2 per cent). Replacing and accessory right hepatic arteries are also encountered. In 15 cases (3 per cent) the accessory right hepatic artery arose from the superior mesenteric artery in 13 cases (2.6 per cent) it arose as a branch of the left hepatic artery in 5 cases (1 per cent) from the gastroduodenal artery in 2 cases (0.4 per cent) from the celiac axis and in only 1 case (0.2 per cent) it arose directly from the aorta. A normal *left hepatic artery* was found in 410 of the 500 specimens (82 per cent). A replacing type of left hepatic artery occurred in 90 of the 500 cases (18 per cent). These replacing vessels may originate from the celiac axis, the left gastric artery, the superior mesenteric artery, the gastroduodenal artery or directly from the aorta. In 175 of the 500 specimens (35 per cent) an accessory left hepatic artery was encountered.

N. A. Michels noted that, in 100 bodies investigated no two patterns of the arterial supply to the liver were the same. The hepatic artery varied in the origin, caliber, number and distribution of its main branches. The typical common hepatic artery divides into a right, a middle (to the quadrate lobe) and a left branch.

To shut off completely the arterial blood supply to the liver would be fatal but a collateral anastomosis exists. In recent years opinions have been divided as to whether or not necrosis will result in man from ligation of a common, a right or a left hepatic artery. Viability of the liver may be explained by the following: (1) If the common hepatic artery is ligated hepatic circulation is maintained in a ratio of one to eight because the right artery may arise from the superior mesenteric artery. (2)

[illegible]

The space between the superior and inferior mesenteric arteries is occupied by the falciform ligament, the superior mesenteric artery, the inferior mesenteric artery, and the inferior vena cava. The falciform ligament is a double layer of peritoneum which separates the superior and inferior mesenteric arteries from the inferior vena cava. It is the only ligament which connects the liver to the anterior abdominal wall. The falciform ligament is a double layer of peritoneum which separates the superior and inferior mesenteric arteries from the inferior vena cava. It is the only ligament which connects the liver to the anterior abdominal wall. The falciform ligament is a double layer of peritoneum which separates the superior and inferior mesenteric arteries from the inferior vena cava. It is the only ligament which connects the liver to the anterior abdominal wall.

liver by the diaphragm below by the superior border of the liver behind by the upper layer of the coronary ligament and medially by the right surface of the falciform ligament. The lower layer of the coronary ligament on the right forms the roof of a space which is limited by the liver in front and the posterior parietal peritoneum behind. This is smaller than the anterior space just described since it still is associated with the superior surface of the liver and since it lies to the right of the falciform ligament but behind the lower layer of the coronary ligament, it is called the *right superior posterior subphrenic space*. To the left of the falciform ligament but still in the suprahepatic area the left triangular (coronary) ligament courses along the posterior border of the left lobe of the liver and separates the superior surface from the inferior surface of the liver. In this respect it differs from the ligament on the right which has two diverging layers thus dividing the superior surface on the right into anterior and pos-

Left supra-hepatic space. Since the layers of the left crus do not diverge and since they run vertically at the junction of the superior and the inferior borders the left supra-hepatic space constitutes only one space and is not divided into two. It is called the *left supra-hepatic space* and is bounded by the diaphragm above the superior surface of the left lobe of the liver below and the left side of the falciform ligament medially.

The infraphrenic area also is divided into three subphrenic spaces. In addition this area is divided into right and left sides by the round ligament and the ligament of the ductus venosus. To the right of these structures is a large space known as the *right inferior subphrenic space*. It is bounded above by the inferior surface of the liver and below by the transverse mesocolon and the colon. Medially it extends to the round ligament. To the left are two spaces separated from each other by the stomach and the lesser omentum. The space anterior to the stomach is known as the *left anterior inferior subphrenic space* and the space posterior to the stomach is known as the *left inferior posterior subphrenic space*. The left anterior inferior space also has been referred to as the perigastric space. In this space a perigastric abscess may form following the perforation of a peptic ulcer. The right inferior space is bounded above by the inferior surface of the liver, below by the transverse colon and the mesocolon and anteriorly by the anterior abdominal wall. The left inferior posterior subphrenic space is better known as the lesser peritoneal cavity. It is bounded above by the inferior surface of the liver, below by the transverse mesocolon, anteriorly, by the stomach and the lesser omentum and, posteriorly, by the posterior parietal peritoneum of the lesser sac. The bare area which is really the space within the confines of the coronary ligament has not been included as one of the six subphrenic spaces, but is considered as an *extraperitoneal* space. The meso for the





FIG 364 The six subphrenic spaces (A) the three suprahepatic spaces, (B) the three infrahepatic spaces

The Spleen

EMBRYOLOGY

To understand the peritoneal attachments of the spleen and their surgical applications the embryologic changes which take place must be understood. The stomach (before rotation) is attached posteriorly by a dorsal mesogastrium and anteriorly by a ventral mesogastrium (Fig 383 A). The spleen originates as a localized cellular collection in the left layer of the dorsal mesogastrium. The cellular collections fuse with one another to form a lobulated spleen, the notch or notches of which are the only surface traces of lobulation in the adult organ. The spleen divides the dorsal mesogastrium into (1) a gastrosplenic part and (2) a spleno-aortic part (lienorenal ligament). As growth takes place the spleen and the stomach shift to the left and the liver shifts to the right. The spleno-aortic ligament is pulled against the posterior abdominal wall and a fusion takes place between the two opposed surfaces (Fig 383 B). The spleno-aortic ligament having been pulled to the left comes in contact with the left kidney and because of its new position it is referred to as the lienorenal (splenorenal) ligament. The splenic artery runs in the lienorenal ligament. To mobilize the spleen it becomes necessary to incise the left leaf of the lienorenal ligament and to enter the fusion (cleavage) plane behind the splenic artery. This converts the lienorenal ligament back to its early form, namely the spleno-aortic ligament. It is a bloodless maneuver and will be discussed under the heading of 'Splenectomy'.

That part of the dorsal mesogastrium

which is located between the greater curvature of the stomach and the spleen is the gastrosplenic omentum; it contains continuations of the splenic artery known as the *visa brevia*. The lienorenal ligament and the gastrosplenic omentum form the *splenic pedicle* which connects the spleen to the kidney and the stomach; this pedicle consists of four layers (Figs 384 B and 385).

ADULT SPLEEN

The spleen is covered completely by peritoneum except at the hilum (Fig 384). It




FIG 383 Embryology of the spleen (A) Before rotation the dorsal mesogastrium is divided by the spleen into gastrosplenic and spleno-aortic ligaments (B) After rotation the spleno-aortic ligament becomes the splenorenal (lienorenal) ligament. Fusion to the posterior abdominal wall has taken place.




FIG 565 Drainage of subphrenic abscesses (A) line of incision over the twelfth rib and deeper transverse incision at the level of the first lumbar spinous process (B) approach to an abscess in the right superior posterior subphrenic space (C) incision for drainage of an abscess in the right superior anterior subphrenic space (D) drainage of a right superior anterior subphrenic space abscess




FIG. 385 The spleen in relation to the tenth rib. The cut splenic pedicle and its contents also are shown.

eleventh ribs (Fig. 384 A). This ligament is usually avascular and forms a floor upon which the spleen rests, thus giving it additional support. It is of surgical importance in the mobilization of the spleen and the splenic flexure.

The adult spleen is placed high in the left posterior corner of the abdomen and lies deep to the ninth, the tenth and the eleventh left ribs. Its long axis corresponds to that of the tenth rib (Fig. 385). The peritoneal cavity, the diaphragm and the pleural cavity separate it from the ribs; the left lung intervenes in its upper third.

If the surgeon stands to the right of the patient and passes his right hand above the phrenicocolic ligament, he will be able to follow the diaphragm posteriorly, and the spleen will fall into his hand. At times, adhesion of variable density attach the spleen to the diaphragm; these must be severed before the organ can be mobilized properly. The exploring hand is stopped by the left layer of the lienorenal ligament.

VESSELS

The splenic artery passes to the left, along the upper border of the body and the tail of the pancreas and across the left kidney to reach the spleen (Fig. 384). The artery does not enter the spleen as a single large vessel but breaks up into from five to eight terminal splenic branches.

The splenic vein is formed at the hilum of the spleen and is joined by the left gastroepiploic and other veins from the greater curvature of the stomach. It passes to the right in the lienorenal ligament behind the pancreas and lies below the splenic artery (Fig. 363). Behind the neck of the pancreas it joins the superior mesenteric vein to form the portal vein; in its course it receives the inferior mesenteric vein.

Accessory splenic tissue has been found in 11 per cent of autopsy material (Adami); the most common sites are near the hilum, the mesentery or the omentum, the tail of the pancreas and the bowel wall (Gray).

SPLENECTOMY

This operation has been performed for injuries to the spleen, hemolytic jaundice, Gaucher's disease, splenic anemia, tumors, cysts, hypersplenism and splenomegaly which produces pressure symptoms.

Many incisions have been described, including a thoracoabdominal approach. The one preferred by Warren Cole is a curved oblique incision which starts high in the epigastrium, about three fourths of an inch to the left of the midline and extends downward for a distance of two inches or more, then curves to the left and runs parallel with the costal margin; it sacrifices only the eleventh nerve. Both the




FIG 384 The spleen (A) The gastro-splenic ligament (part of the greater omentum) has been divided the short gastric and the splenic vessels can be seen (B) Cross section seen from above The splenic pedicle consists of four layers two derived from the spleno-renal ligament and two derived from the gastro-splenic ligament

presents four surfaces (1) a posterior surface which is convex and lies in contact with the diaphragm (2) an anterior surface toward the stomach (3) an inferior surface, which is small and rests on the splenic flexure of the colon and (4) an internal which is in contact with the left kidney. The hilum is on the anterior or gastric

surface, and posterior to it is a depression which lodges the tail of the pancreas. Vessels and nerves enter and leave at the hilum and the lienorenal and the gastro-splenic ligaments attach here.

A phrenicocolic (costocolic) ligament runs from the splenic flexure of the colon to the diaphragm opposite the tenth and the

rectus sheath and the lateral oblique muscles are severed. Another incision frequently used is a straight paramedian one (Fig. 386 A). The right hand of the surgeon should be passed between the diaphragm and the spleen to determine its size and degree of mobility. If it is freely mobile and not anchored to the diaphragm by adhesions, the fingers of the right hand can be swept around its inferior border and the organ brought through the abdominal incision and delivered onto the anterior abdominal wall. However, this usually is not the case and mobilization becomes necessary. The gastrotocolic and the gastrosplenic attachments are clamped and cut so that the anterior attachments of the spleen or the anterior part of the pedicle are severed. The vessels which run in the gastrosplenic ligament (*lig. brevis*) are ligated (Figs. 386 B and 386 F).

Cole is of the opinion that preliminary ligation of the splenic artery makes for better surgery. The posterior parietal peritoneum is incised over the upper border of the pancreas where the splenic artery is found. Since the artery runs a tortuous

course it humps over the upper border of the pancreas and can be seen, felt and ligated here.

The incision into the left leaf of the lienorenal ligament is next accomplished to permit further mobilization of the spleen (Fig. 386 C). This is divided and the cleavage plane which permits delivery of the spleen and the splenic vessels is entered. If it is impossible to see this leaf of peritoneum it can be divided blindly over the upper pole of the kidney.

This step has been considered by many as a key to the operation since this left leaf of lienorenal ligament anchors the spleen. When this ligament is cut the spleen becomes mobile and can be drawn out through the abdominal incision. Following delivery the vessels are ligated individually as they pass under cover of the right leaf of the lienorenal ligament.

The tail of the pancreas and the stomach should be carefully retracted and visualized before the clamps are applied to the remainder of the splenic pedicle so that these structures are not injured.






FIG 386 Splenectomy (A) Long left rectus incision (B) The gastrosplenic ligament has been divided and the vasa brevia have been ligated. An incision is made in the posterior parietal peritoneum and the splenic artery is ligated (C) The left leaf of the lienorenal ligament is cut (D) The spleen is delivered and individual ligation of the splenic vessels is accomplished (E) Mobilization and removal of the spleen by dividing (1) the gastro-splenic ligament, (2) the left leaf of lienorenal ligament and (3) the right leaf of lienorenal ligament



Before rotation



After rotation

FIG 387 Embryology of the pancreas (A) The two primitive pancreatic buds, dorsal and ventral before rotation has taken place. The arrow indicates the path of rotation. (B) After rotation and before fusion of the pancreatic buds. The superior mesenteric vessels (portal vein) are sandwiched in between the primitive buds.

peritoneal cavity. The right end of the transverse colon has no mesocolon; therefore the head of the pancreas is directly attached to it, being separated from it only by a little areolar tissue. The tail of the pancreas continues to the left and upward from the body until it abuts the spleen. Since it travels in the lienorenal ligament, this part of the pancreas loses its retroperitoneal characteristics and is more movable. The transverse mesocolon continues from the body to the tail of the pancreas




FIG 388 The relations and the divisions of the pancreas. The two projections of the pancreas, the uncinate process and the omental tuberosity, are identified.

so that the transverse colon hangs by a mesentery from only two parts of the pancreas, namely the body and the tail. Posteriorly, the head of the pancreas is in contact with the renal vessels and the inferior vena cava. Behind the pancreatic neck lies the portal vein. Behind the body of the pancreas, from right to left, is the aorta (with the origin of the superior mesenteric and the renal arteries), the left suprarenal gland, the left kidney, and the spleen. The uncinate process (uncus hook) is a downward projection from the lower part of the head which hooks behind the superior mesenteric vessels. The omental tuberosity (tuber omentale) is another pancreatic pro-

The Pancreas

EMBRYOLOGY

The single adult pancreas is developed from two primitive pancreatic buds which are called the dorsal (proximal) pancreatic bud and the ventral (distal) pancreatic bud (Fig 387). The dorsal bud springs from the posterior border of the duodenum and grows between the leaves of the dorsal mesoduodenum; its duct system empties directly into the duodenum. The ventral bud arises from the anterior border of the duodenum and invades the ventral mesoduodenum; it originates with the primitive bile duct system; hence its duct system communicates with that of the bile (Fig 387 A). The ventral bud rotates backward behind the duodenum, around its right side and grows back into the dorsal mesoduodenum. The two buds fuse; the ventral bud gives rise to the posterior portion of the lower part of the head and the uncinate process of the pancreas; the dorsal bud becomes the upper and the anterior part of the head, the neck, the body and the tail of the pancreas (Fig 387 B). The right side of the pancreas is directed backward and the left side forward; the right surface is applied to the posterior abdominal wall. The peritoneum which originally covered its right side is absorbed; therefore, in the adult, the pancreas appears to be retroperitoneal, being covered by the parietal peritoneum. At the time of fusion between the ventral and the dorsal buds, a communication is established between their ducts. The duct of the dorsal bud becomes the accessory pancreatic duct of Santorini, and the duct of the ventral bud becomes the main pancreatic duct of Wirsung. In

about 20 per cent of individuals the accessory duct of Santorini becomes occluded and cannot compensate for trauma inflicted upon the duct of Wirsung.

After rotation, the portal vein becomes "sandwiched in" between the dorsal bud which lies ventral to the vein and the ventral bud which now lies dorsal to the vein. The last statement may appear confusing at first but if it is visualized it explains the ultimate positions of the superior mesenteric and the portal veins, between the head and the neck of the pancreas. It also explains how the accessory duct, which was formerly posterior, now enters on the anterior surface of the duodenum and the main duct which was originally anterior, now lies posteromedial.

ADULT PANCREAS

The adult pancreas is pistol shaped (Figs 388 and 389). Its length, which is variable, averages from 4 to 6 inches; it is divided indistinctly into a head, a neck, a body and a tail (Fig 388). The head lies within the concavity of the duodenum and slightly overflows it. The neck is that portion which presents a slight constriction and lies in front of the portal vein. The body of the pancreas continues to the left and upward; it presents a triangular shape on cross section, resulting in anterosuperior and antero-inferior surfaces. The transverse mesocolon attaches along the ridgelike junction of these two surfaces. The anterosuperior surface is covered by peritoneum of the lesser peritoneal cavity, the antero-inferior surface is covered by peritoneum of the greater




FIG. 390 Variations in the termination of the pancreatic duct (A) Both ducts enter the ampulla of Vater independently (B) The ducts enter the bowel independently (C) The ducts join and enter the ampulla by a common channel




FIG. 391 The three approaches to the pancreas (A) through the lesser omentum (B) through the greater omentum, (C) through the transverse mesocolon

pancreas and the duodenum as two parallel vessels not as a single vessel as is usually depicted. The inferior pancreaticoduodenal (superior mesenteric) artery also divides into two parallel vessels which anastomose with the two branches of the superior pancreaticoduodenal artery. In this way two arterial arches are formed, one in front of the head of the pancreas and another behind it. By means of these two arches the medial aspect of the duodenum receives an anterior and posterior set of vasa recta (Fig. 312). The head of the gland is supplied by the superior and the inferior pancreaticoduodenal arteries and the body, and the tail by the splenic artery.

Pancreatic veins issue from the pancreas and end in the *splenic vein*. The latter passes behind the body of the pancreas and below the splenic artery. It ends behind the neck of the pancreas by joining with the superior mesenteric vein to form the portal vein.

The **lymphatics** of the pancreas drain

either directly or indirectly into the celiac glands around the root of the celiac artery.

Ducts

The *pancreatic duct of Wirsung* forms the chief excretory channel of the gland. It begins in the tail and passes through the middle of the gland toward its head; its termination is quite variable (Fig. 390). In most instances, the duct opens independently into the ampulla of Vater, which then presents one opening common to both the pancreatic and the common bile ducts. In other instances the pancreatic duct may join the common bile duct and both enter the ampulla by a common channel. Another variation presents the common bile duct and the pancreatic duct entering the duodenum by entirely separate orifices. The *accessory pancreatic duct of Santorini* represents the original duct of the dorsal bud. In the adult it passes to the right and in front of the common bile duct. It remains patent in most instances and opens into




FIG 389 The pancreas The splenic artery passes to the left along the upper border of the body and the tail of the pancreas and the hepatic artery passes to the right along the upper border of the neck and the head of the gland The splenic vein lies behind the pancreas

jection which projects upward from the body It fits into the lesser curvature of the stomach where it comes in contact with the lesser omentum and separates it from the downward projecting tuber omentale of the liver (left lobe)

VESSELS

The upper border of the pancreas is a good landmark for the *arteries* which supply it and other organs in this region

(Fig 389) The splenic artery passes to the left along the upper border of the body and the tail and the hepatic artery passes to the right along the upper border of the head of the pancreas Opposite the lower border of the duodenum the gastroduodenal artery (hepatic) divides into a superior pancreaticoduodenal and right gastroepiploic arteries (Fig 312) The superior pancreaticoduodenal artery divides and continues downward between the head of the

the duodenum about three fourths of an inch above the ampulla of Vater. In most individuals it anastomoses with the chief pancreatic duct (Wirsung) within the head of the pancreas.

SURGICAL CONSIDERATIONS

The pancreas can be considered no longer as the hermit organ since it now comes within the realm of modern surgery.

The approaches to the pancreas are along three anterior transperitoneal routes namely through the lesser omentum (gastrohepatic portion) the transverse mesocolon and the gastrocolic part of the greater omentum (Fig. 391). The last named approach is preferred since it affords greatest exposure and does not endanger the middle colic artery; however the site and the extent of the pathology determines which route is most applicable. If for example a pancreatic cyst points through the lesser omentum or the transverse mesocolon these paths are taken.

PANCREATODUODENECTOMY

Pancreatoduodenectomy is done for carcinoma of the head of the pancreas carcinoma of the ampulla of Vater and carcinoma of the lower end of the common bile duct (Fig. 392). It may be performed in one or two stages. Whipple has done much of the pioneer work in this field. Many types of operative procedures have been described and a typical one will be discussed here. The scope of this operation calls for a block resection of the head of the pancreas the lower end of the common duct the pylorus of the stomach and the entire duodenum. Hence the gastrointestinal tract the biliary tract and the pancreas are interrupted. The gastrointestinal tract can be restored by an end to side or end to end gastrojejunostomy. The biliary tract can be restored by an anastomosis of the common bile duct or the common hepatic duct to a portion of the gastro-

intestinal tract. In the two stage operation the gallbladder can be used for the anastomosis. Some surgeons advocate closure of the cut end of the pancreas others prefer to anastomose it to the jejunum. Surgery is contraindicated if the portal vein or the superior mesenteric vessels are involved, if there are multiple distant metastases or if there is invasion beyond the limits of resection. Involvement of the portal vein can be discerned by division of the gastroduodenal artery and displacement of the common duct downward. Involvement of the superior mesenteric vessels is determined by division of the gastrocolic omentum and incision of the peritoneum along the inferior border of the pancreas.

If a two stage procedure is utilized a cholecystojejunostomy is done first and at the second stage this is displaced downward. The peritoneum over the right kidney is incised to the right of the duodenum and the duodenum and the head of the pancreas are mobilized to the left. The gastrocolic omentum is divided and the third part of the duodenum, the head of the pancreas and the superior mesenteric vessels are exposed. The gastroduodenal artery is divided and ligated the common duct is divided and the proximal end is invaginated. The stomach the body of the pancreas and the jejunum are divided the ligament of Treitz is freed. The block of tissue is removed and the operation is completed by performing the following anastomoses end to side or end to end gastrojejunostomy, pancreaticojejunostomy and cholecystojejunostomy (previously done in the two stage procedure).

SURGERY FOR PANCREATITIS

Pancreatitis is still a rather obscure lesion, but the surgical procedures which have been utilized if the case is operated upon, are in the form of cholecystostomy and incision of the pancreatic capsule. This capsule is the posterior parietal peritoneum which covers the organ.




FIG 392 Pancreatoduodenectomy (A) A long right rectus incision gives ample exposure (B) Cholecystojejunostomy may be done as a first stage operation or else combined with a radical one stage procedure (C) The duodenum has been mobilized and the gastroduodenal artery and the common duct have been severed and ligated (D) The pylorus has been severed and the pancreas has been incised over the superior mesenteric vessels. The jejunum has been divided immediately distal to the ligament of Treitz (E) Following removal of the duodenum and the head of the pancreas pancreatocojejunostomy and gastrojejunostomy complete the operation. In the one stage procedure it is thought preferable to anastomose the common duct to the jejunum.

branch to the hilum of the spleen by means of five to eight terminal splenic branches. Short gastric arteries (*vasa brevia*), from four to six in number, reach the fundus and the greater curvature of the stomach via the gastroepiploic vessels. The left gastroepiploic artery arises from the front of the splenic artery close to its termination, passes forward between the layers of the gastrosplenic omentum into the greater omentum and then continues from left to right along the greater curvature about one finger's breadth from it. It anastomoses with the right gastroepiploic artery. In its course it supplies branches to both surfaces of the stomach and long slender omental branches.


The *hepatic artery* passes to the right along the upper border of the pancreas, turns upward in the lesser omentum and runs in front of the portal vein and to the left of the common bile duct. Its gastroduodenal branch arises above the upper border of the first part of the duodenum, passes downward behind the duodenum and in its downward course lies between the duodenum and the pancreas. Opposite the lower border of the duodenum the gastroduodenal artery divides into a right gastroepiploic and a superior pancreaticoduodenal artery. The right gastroepiploic artery travels from right to left between the layers of greater omentum supplying the stomach, as does the left gastroepiploic with

which it anastomoses. The superior pancreaticoduodenal artery continues between the duodenum and the head of the pancreas. It forms a double arch by dividing into anterior and posterior branches and anastomoses with similar branches from the inferior pancreaticoduodenal branch of the superior mesenteric artery. The anterior arch runs in front of the head of the pancreas and the posterior arch passes behind it (Fig. 312).

The right gastric artery arises opposite or near (usually distal to) the gastroduodenal artery, makes a sharp turn backward on itself and passes between the layers of the lesser omentum to the pylorus. It then passes along the lesser curvature of the stomach and anastomoses with the left gastric artery. The hepatic artery continues upward to the porta hepatis, where it divides into right and left hepatic arteries which are distributed to corresponding lobes of the liver. The cystic artery is usually a branch of the right hepatic artery.

MESENTERIC VESSELS

The *superior mesenteric artery* constitutes a vascular axis around which early rotation takes place. After rotation those branches which originally arose from the right side of the vessel now arise from the left and vice versa. This vessel originates from the front of the aorta about one half inch below the origin of the celiac artery and



The Blood Supply of the Gut

The primitive gut is divisible into three parts foregut midgut and hindgut. The foregut ends and the midgut begins where the bile duct enters the duodenum. The midgut ends and the hindgut begins at the junction of the right and the middle thirds of the transverse colon. Each of the above three portions has its own blood vessel as follows: (1) the foregut is supplied by the celiac artery, (2) the midgut is supplied by the superior mesenteric artery, (3) the hindgut is supplied by the inferior mesenteric artery.

The celiac artery supplies the stomach and the duodenum to the entrance of the bile duct and its associated glands, the liver, the pancreas and the spleen. The superior mesenteric artery supplies the duodenum distal to the entrance of the bile duct, the jejunum, the ileum and the colon almost as far as the left colic flexure. The inferior mesenteric artery supplies the descending colon, the sigmoid and the rectum.

CELIAC ARTERY (CELIAC AXIS)

The celiac artery (celiac axis) is the first branch of the abdominal aorta. It is short, about one half inch long and thick. The artery originally arose at the level of the seventh cervical vertebra, but during development, the lungs pushed the diaphragm caudally and the diaphragm in turn forced the stomach and the celiac vessel downward. In its final position, therefore, the median arcuate ligament which unites the two crura of the diaphragm lies immediately above the artery, and the crura are on each side of it.

The vessel cannot be seen until the lesser

omentum is incised, and then it is found immediately above the pancreas and behind the posterior parietal peritoneum. It is found at the level between the last thoracic and the first lumbar vertebrae. After passing almost horizontally forward for one half inch it trifurcates into (1) the left gastric artery, (2) the splenic artery and (3) the hepatic artery.

The left gastric artery (coronary artery) is the smallest of the three branches. It runs obliquely upward and to the left until it nearly reaches the esophagus. It then arches sharply forward to reach the lesser curvature of the stomach. In so doing it drags a fold of peritoneum with it; this forms a 'mesentery' for the vessel known as the left gastropancreatic fold. In its course it first lies on the left crus of the diaphragm behind the lesser sac; it then passes into the gastropancreatic fold and finally continues between the layers of the lesser omentum. When it reaches the stomach it supplies esophageal branches which pass upward and anastomose with esophageal branches of the thoracic aorta. Its branches are distributed to both surfaces of the stomach; these anastomose with the short gastric branches of the splenic and the gastroepiploic arteries.

The splenic artery (lienal artery) is the largest branch of the celiac artery and is remarkable for its tortuosity. It travels to the left along the upper border of the pancreas into which it sends branches. It crosses the left crus of the diaphragm, the left adrenal gland and the upper part of the left kidney. It then enters the lienorenal ligament through which it gains en-

The *ileocolic artery* arises from the superior mesenteric artery about half way down its right side. It descends subperitoneally toward the ileocolic region. In its course it crosses the inferior vena cava, the ureter and the testicular vessels (the latter two structures lie on the psoas fascia). It divides into an ascending and descending branches. The ascending branch supplies the proximal part of the ascending colon and anastomoses with the right colic artery. The descending branch may be a very short trunk and is better referred to as the *ileocecocolic artery*. The latter also supplies the ileal branch which anastomoses with the end of the superior mesenteric artery; therefore it anastomoses with it self. The *ileocecocolic artery* also supplies anterior and posterior cecal branches.

The all important and sometimes troublesome appendicular artery is a branch of the posterior cecal branch of the *ileocecocolic artery*. It passes behind the ileum and not behind the cecum. The artery enters the free border of the mesentery of the appendix and sends a few straight branches to the vermiform appendix. It does not anastomose with any other artery; hence if obstructed or kinked early gangrene of the appendix results.

The *right colic artery* arises a little below the duodenum and runs to the right and behind the peritoneum. It crosses the same structures as the *ileocolic artery* and divides into an ascending branch which anastomoses with the middle colic and a descending branch which anastomoses with the *ileocolic*. Not infrequently the right

colic artery fails to arise as a separate branch but springs from either the *ileocolic* or the middle colic artery.

The *middle colic artery* is the first branch of the superior mesenteric artery. The term middle should not be misleading since the vessel actually passes to the right side of the transverse colon. Because of this fact the openings in the transverse mesocolon are best made in its left half. The vessel arises at the lower border of the pancreas and enters the root of the transverse mesocolon. It then passes downward and to the right between the two layers of the transverse mesocolon. It divides into a right branch which supplies the right third of the transverse colon and anastomoses with the ascending branch of the right colic artery and a left branch which supplies the left two-thirds of the transverse colon and anastomoses with the superior left colic artery. Students erroneously picture the vessel as passing upward because of the many illustrations in which the transverse colon has been pulled up. In reality its course is distinctly downward. The middle colic artery may be injured while incising the transverse mesocolon in a posterior gastrojejunostomy or it may be ligated accidentally with the gastrocolic ligament (greater omentum) in performing a gastrectomy. If the vessel has a free anastomosis with the left colic artery necrosis will be avoided but should the anastomosis be imperfect the colon in the region of the splenic flexure becomes gangrenous and resection becomes imperative.

For *inferior mesenteric artery* see p. 483.

opposite the first lumbar vertebra. At its origin it lies behind the pancreas and the splenic vein. Where it passes in front of the duodenum it is crossed anteriorly by the transverse colon, in the lower part of its course it lies behind the coils of the small intestine. Although the superior mesenteric artery and vein lie behind the body of the pancreas, they pass anterior to the uncinate process of the head of the pancreas. The vessel takes a downward and forward course, descending between the layers of the mesentery to the right iliac fossa where, considerably diminished in size, it anastomoses with one of its own branches, the ileocolic artery. As it travels in the root of the mesentery it crosses the third part of the duodenum, the aorta, the inferior vena cava, the right ureter and the psoas major muscle in the order named. Its branches are the inferior pancreaticoduodenal, the intestinal (jejunal and ileal), the ileocolic, the right colic and the middle colic arteries, although mentioned last the middle colic artery is really the first branch.

The *inferior pancreaticoduodenal artery* arises opposite the upper border of the transverse (third) portion of the duodenum. It courses to the right between the head of the pancreas and the duodenum, passing behind the superior mesenteric vein. The vessel divides into anterior and posterior branches which anastomose with corresponding anterior and posterior branches of the superior pancreaticoduodenal artery and in this way forms two vascular arches, one in front of the right margin of the head of the pancreas and the other behind it. These arches supply the head of the pancreas and by means of the straight vasa recta, supply the corresponding part of the duodenum. Of surgical importance is the fact that the pancreatic part of the common duct descends between these arches (Fig 312).

The *jejunal and ileal arteries* from 10 to 15 in number, spring from the left (convex) side of the superior mesenteric artery and pass obliquely forward and downward be-

tween the layers of the mesentery, each divides into two branches which anastomose with adjacent arteries to form a series of arcades, the convexities of which are directed toward the intestines. From these arcades, straight terminal vessels, the vasa recta, pass to the wall of the gut, some going to one side and some to the other. Occasionally, one of these will divide and supply both sides of the gut wall. Distally, from jejunum to ileum the upper jejunal branches form only one or two arches, but the process of division and union is repeated three or four times in the region of the ileal branches, thus four or five tiers of arches are formed in the longer lower part of the mesentery. This latter fact may aid the surgeon in distinguishing between the upper and the lower coils of small intestine. The vasa recta themselves do not anastomose but pass to the submucous plexus where they ramify and then anastomose.

In severing the bowel, it is advisable to remove less of the mesenteric than of the antimesenteric border so that the retained cut margin may have an adequate blood supply.

The *three colic branches* are the ileocolic, the right colic and the middle colic, they arise from the right side of the superior mesenteric artery. They travel behind the peritoneum, bifurcate and anastomose with the artery on each side of it. In this way the loops form a continuous vessel which runs along the mesenteric margin of the large bowel. This same arrangement continues in the branches of the left colic and the sigmoid branches (inferior mesenteric artery). The result is a continuous vessel known as the "marginal artery of Drummond." This 'artery' extends from the ascending colon to the end of the pelvic colon, its distance from the margin of the bowel varies from almost hugging the bowel wall to eight cm away from it. It lies closest to the bowel along the descending and the pelvic colons.

SECTION FIVE

THE PELVIS

Pelvic Bones

The complete bony ring, which forms the pelvis so named because of its resemblance to a basin is composed of two hip bones anteriorly and laterally, and the sacrum and the coccyx posteriorly. The cavity thus created is divided into a smaller inferior portion called the true pelvis and a larger superior one the false pelvis. The line of separation between these two is the iliopectineal line (Fig. 393). The side walls of the true pelvis are formed largely by the pubes and the ischia; the side walls of the false pelvis are formed by the ilia.

Distinct differences exist between the male and the female pelvis. The female pelvis is distinguished from the male pelvis by the following features: Its bones are more delicate. Its depth less. The entire pelvis is less massive. Its muscular impressions are less marked. The anterior iliac spines are more widely separated. The superior aperture of the lesser pelvis is larger and more circular. The obturator foramina are triangular. The coccyx is more movable. The pubic arch is wider and more rounded forming an angle rather than an arch. In brief the female pelvis appears to be wider, more shallow and more graceful.

HIP BONE

Galen wrote that since the hip bone resembles no commonplace object no name had been given to the bone and it therefore became known as the innominate or unnamed bone. It consists of three parts: the ilium, the ischium and the pubis. These meet at the acetabulum. Up to the age of twelve the connecting piece is a triangular segment of cartilage which begins to ossify at about this period. Ossification usually is

complete by the age of sixteen (Figs. 394 and 395).

ILIUM

The ilium (I flank) is the largest of the three bones and forms the larger upper expanded area of the hip bone. It is fan-shaped the handle of the fan being placed downward where the ilium joins the ischium and the pubis. The iliac crest is the arched upper border which is easily felt in the living subject at the lower limit of the waist. Its margins are called the outer and the inner lip and the interval between them is called the intermediate area. The highest point of the crest is at its middle and toward the back, this marks the level of the body of the fourth lumbar vertebra. The iliac crest is crossed by cutaneous nerves, since no muscles cross it the deep fascia attaches here. It terminates anteriorly in a small tubercle called the anterior superior iliac spine which is an important surgical landmark and can be felt easily at the upper end of the fold of the groin. The crest terminates behind in a sharp posterior superior iliac spine which can be felt on a level with the second sacral spine, at the bottom of the small dimple which is visible in the upper and the medial part of the buttock. The tubercle of the crest is a tiny projection on the external lip it is palpable about two inches above and behind the anterior superior spine in the living it forms the highest point when viewed from in front. It is approximately at the level of the body of the fifth lumbar vertebra.

The anterior border of the ilium is concave and extends from the anterior superior




FIG 395 The right hip bone (A) seen from without, (B) seen from within.

on the greater sciatic notch and divide the surface into four areas for the gluteal muscles (Fig. 395 A). The areas for the gluteus medius and minimus muscles are extensive; however, a small and restricted area is present between the gluteus minimus and the acetabular margin for the iliofemoral ligament and the reflected head of the rectus femoris. The *posterior gluteal line* passes upward and slightly forward from the posterior inferior iliac spine to the iliac crest. The *middle (anterior) gluteal line* runs from the middle of the upper border of the greater sciatic notch forward to the iliac crest just in front of its tubercle. The *inferior gluteal line* is quite indistinct and passes from the apex of the greater sciatic notch to the notch which exists between the anterior superior and the anterior inferior iliac spines.

ISCHIUM

The *ischium* (G buttock) consists of three parts: a body which adjoins the ilium, a tuberosity projecting downward from the body, and a ramus (inferior)

which passes from the tuberosity upward below the obturator foramen. The *body* is triangular on cross section and therefore presents three surfaces which are separated by three borders. The borders are parts of the margin of the obturator foramen, the acetabulum, and the greater sciatic notch. The surfaces are pelvic (medial), acetabular (lateral), and gluteal (posterior). The *tuberosity* (tuber ischi) is an oval mass of bone which caps the posterior aspect of the lower part of the body of the bone. The upper part of the medial border is crossed by the tendon of the obturator internus; it is smooth, is covered by a bursa, and it forms part of the lesser sciatic notch. The lower part of the medial border is a rough crest for the attachment of the sacrotuberous ligament. The lateral border gives origin to the quadratus femoris and between this and the acetabulum the groove for the obturator externus is located. Its chief function is to support the body weight when sitting. The *ramus of the ischium* is a flattened bar of bone that projects forward and medially from the tuberosity. It




FIG 393 The bony pelvis, seen from above

spine to the iliopubic eminence which marks the junction between the ilium and the pubis. This border is subdivided into two equal concavities by the anterior inferior iliac spine, the latter being too deeply situated to be palpable through the skin; the iliopsoas leaves the abdomen through the notch between it and the iliopubic eminence. The posterior border extends from the posterior superior iliac spine toward

the ischial spine through a point on the margin of the greater sciatic notch opposite the middle of the acetabulum. It is subdivided into two unequal concavities by the posterior inferior iliac spine, which lies at the posterior limit of the sacro iliac joint about one inch below the posterior superior iliac spine. The upper concavity is slight; the lower concavity forms the upper part of the greater sciatic notch.




FIG 394 The innominate (hip) bone. It consists of three parts (the ilium, the ischium and the pubis), which meet at the acetabulum.

The ilium has two surfaces, an inner and an outer (dorsum ilii). The inner surface is subdivided into the iliac fossa, the tuberosity, the auricular surface, and an area within the true pelvis (Fig 395 B). The iliac fossa is the large, smooth, medial surface which is limited posteriorly by a roughened area through which the hip bone articulates with the sacrum at the sacro iliac joint, and is limited inferiorly by a prominent ridge, the iliopectineal line. The iliac tuberosity is the rough part of the inner surface and the auricular surface articulates with the sacrum. The area within the true pelvis is the lowest part which is smooth and helps to form the side wall of the true pelvis. The outer (gluteal) surface, also known as the dorsum ilii, presents a wavy appearance and is crossed by three rough lines: the inferior, the middle, and the posterior gluteal lines, which converge




FIG 396 The sacrum (A) Seen from in front (B) Posterior view, a probe has been placed through the sacral hiatus and into the sacral canal (C) Seen from above (D) Sagittal section showing a needle placed in the epidural space




FIG 397 The bony structure of the sacrococcygeal region

joins the inferior ramus of the pubis and together these conjoined rami form the sides of the *pubic arch*.

The *greater sciatic notch* is a wide gap which is situated between the posterior inferior iliac spine and the ischial spine. It is bounded by the posterior borders of the ilium and the ischium. The *lesser sciatic notch* is the small gap situated between the ischial spine and the ischial tuberosity. These notches are converted into sciatic foramina (greater and lesser) by the sacrotuberous and the sacrospinous ligaments. The floor of the cartilage-covered surface of the lesser sciatic notch is grooved by the tendon of the obturator internus.

PUBIS

The *pubic bone* (L. pubis adult) has received its name from that region where the hair develops during adulthood. It consists of a body and two rami (superior and inferior). The *body* is the wide flattened medial part of the bone, the pelvic surface of which looks upward and is smooth; it is in relation to the retropubic fat pad and the bladder. The femoral surface is rough and the symphyseal surface is joined to the opposite pubic bone by the fibrocartilage and the ligaments of the symphysis pubis. The lateral border bounds the obturator foramen. The *pubic crest* forms the upper border of the body of the bone and is easily felt at the lower limit of the abdomen and at the side of the midline. The crest terminates laterally in the *pubic tubercle* to which the medial end of the inguinal ligament is attached. If the hip bone is held in the erect position the tubercle and the anterior superior iliac spine are in the same vertical plane.

The *superior ramus* has two ends, three surfaces and three borders. The medial end is expanded and becomes the body and the lateral end expands and fuses with the ilium and the ischium to form part of the acetabulum. The upper border is sharp and is called the *pectineal line*; it extends from the pubic tubercle to the iliopectineal

eminence. The anterior border is a ridge known as the *obturator crest*; it extends from the pubic tubercle to the acetabular notch. The inferior border forms the upper margin of the obturator foramen. The pectineal surface is triangular in shape and is situated between the pubic crest and the iliopectineal eminence; it gives origin to the pectineus muscle. The pelvic surface is smooth and continuous with the body of the bone. The obturator surface is the upper boundary of the obturator foramen.

The *inferior ramus* passes downward and laterally from the body to meet the ramus of the ischium.

ACETABULUM

The *acetabulum* (L. little cup for vinegar) forms the socket for the head of the femur (Fig. 394). The ilium, the pubis and the ischium meet in the center of this cavity and their lines of fusion radiate from the center like the spokes of a wheel. These lines are visible in the child but in the adult they are no longer evident. The acetabulum is directed laterally and downward. It presents a horseshoe-shaped area which is covered with cartilage but leaves a rough acetabular fossa in the floor which adjoins the *acetabular notch* (the gap in the lower part of the cup above the obturator foramen). The transverse ligament completes the rim and converts the notch into a foramen (Fig. 619). The articular branches of the obturator and the medial circumflex arteries enter the joint through this notch.

The *obturator foramen* is below the acetabulum and is closed by the obturator membrane which is attached to its margins except above at the obturator groove. Through this groove the obturator vessels and nerves pass out of the pelvis.

SACRUM AND COCCYX

SACRUM

The *sacrum* is triangular in shape possessing an upper surface which forms its base and a lower end which corresponds to

upper surface of the body of the first sacral vertebra is the promontory. The posterior wall of the sacral canal is formed by the superficial posterior sacrococcygeal ligament where the laminae of the fifth sacral vertebra are absent. The sacral hiatus transmits the fifth sacral nerve, the coccygeal nerves and the filum terminale.

Coccyx

The coccyx is formed from the rudimentary vertebrae which tend to fuse. The bone has a base on apex dorsal and pelvic surfaces and lateral borders. Its apex points downward.

SACROCOCYGEAL REGION

Toward the base of the coccyx where it articulates with the sacrum two lateral bony prominences can be palpated; these are the coccygeal and the sacral cornua which bound the sacral hiatus (Fig. 397). The hiatus is the external opening of the sacrococcygeal canal. The termination of the subarachnoid space can be indicated by a line which joins the posterior superior spines of the first and the second sacral foramina.

The skin over the sacrococcygeal region is resistant and thick; it is loose and movable over the convexity of the sacrum but is bound down in the region of the anal crease. The inferior portion of the dorsal layer of lumbodorsal fascia forms a musculoponeurotic layer over the sacrum. This fuses with the tendinous origin of the spinal muscles.

Sacral anesthesia is an extradural type which reaches the nerves within the sacral canal (Fig. 398). This produces anesthesia in the perineum and external genitalia. In the caudal type of sacral anesthesia the needle is placed through the sacrococcygeal ligament into the sacral hiatus and then upward along the sacral canal for from 3 to 4 cm. Transsacral anesthesia is produced by direct injection of the anesthetic agent into the sacral canal and around the sacral nerves via each of the posterior sacral foramina.




FIG. 400 The ligaments that resist sacral rotation.

SACRO-ILIAC REGION

The sacro iliac joints include the three upper sacral segments and the articular surfaces of the ilia (Fig. 399). The joints act as shock absorbers between the spinal column and the lower extremities. Although the sacro iliac articulation is synovial in type, it permits very little movement. The articular surfaces of the joint are mainly smooth but several projections and depressions help to lock and stabilize it. Union is maintained by anterior interosseous short and long posterior sacro iliac ligaments. The sacrotuberous and the sacrospinous ligaments further stabilize the joint; these arise over the whole area of the posterior sacro iliac ligaments and attach at the ischial tuberosity and the spine. The interosseous sacro iliac ligament, the short and the long posterior sacro iliac ligaments and the iliolumbar ligament resist forward rotation of the upper end of the sacrum. The sacrotuberous and the sacrospinous ligaments resist backward rotation of the lower end of the sacrum (Fig. 400).

Surgical approaches to the sacro iliac joint have been described by Smith, Petersen and Picque.




FIG 398 Sacral anesthesia. A needle has been placed through the sacral hiatus and into the sacral canal. The bony roof of the sacral canal has been removed.

the apex, it has pelvic, dorsal and two lateral surfaces (Fig 396). The bone is formed by five fused vertebrae. The female sacrum is broader than the male sacrum and is more abruptly curved below. It is inserted like a wedge between the two hip bones, its base articulates with the last lumbar vertebra and its apex with the coccyx. The pelvic surface is marked by four transverse ridges at the ends of which are the anterior sacral foramina. There are four foramina on each side, they diminish in size from above downward, and give exit to the anterior divisions of the sacral nerves and entrance to the lateral sacral arteries. Lateral to these foramina are the so called lateral parts of the sacrum. A sagittal section through the center of the bone shows that the bone is united at the circumference but that a centrally placed interval is filled by fibrocartilage. The dorsal surface is convex and reveals the posterior sacral foramina which are smaller in size than the anterior and transmit the posterior divisions of the sacral nerves. The inferior articular processes of the fifth sacral vertebra are prolonged downward as the sacral cornua, which connect with the cornua of the coccyx. The anterior projecting




FIG 399 The sacro iliac region. (A) cross section. (B) seen from behind.

To the ischial spine the gemellus superior and the gemellus inferior muscles the levator ani the coccygeus and the sacrospinous ligament

To the pelvic surface of the ischium and the ilium the obturator internus

To the body of the pubis (pelvic surface) the levator ani the puboprostatic ligament and the adductor longus

From the region of the symphysis and the inferior ramus the gracilis the adductor brevis and the obturator externus. The adductor magnus originates at the lower end of the ischium medial to the gracilis. The crus penis the ischioavernosus the superficial transverse perineal the perineal membrane the sphincter urethrae the deep transverse perineal the filiform process of the sacrotuberous ligament and the in-

ferior pubic ligament are also attached here

To the symphyseal surface the fibrocartilage of the symphysis and the anterior posterior, superior and inferior pubic ligaments

To the crest the aponeurosis of the external abdominal oblique the fascia lata the conjoint tendon, the pyramidalis and the rectus abdominis muscles and the transversalis fascia

To the pectineal line the pectineus muscle the pectineal fascia the reflected part of the inguinal ligament the conjoint tendon the transversalis fascia and the psoas minor

To the antero-inferior iliac spine the iliofemoral ligament

To the obturator crest the pubofemoral ligament.




FIG 401 Muscular attachments to the iliac bone (A) seen from without (B) seen from within

MUSCULAR AND LIGAMENTOUS ATTACHMENTS

The attachments to the hip bone can be outlined in the following way (Fig 401)

Ilium

To the anterosuperior iliac spine the inguinal ligament the sartorius and the tensor fasciae latae muscles

To the outer lip the external abdominal oblique muscle the latissimus dorsi and the fascia lata

To the intermediate area the internal oblique muscle

To the inner lip the transversus abdominis muscle, the quadratus lumborum muscle and the iliolumbar ligament. At the inner lip the transversalis fascia becomes continuous with the iliac fascia

To the posterosuperior iliac spine the long posterior sacro iliac ligament

To the posterosuperior and the postero inferior iliac spines the piriformis muscle

To the antero inferior iliac spine the straight head of the rectus femoris muscle and the iliofemoral ligament

To the gluteal surface the reflected head of the rectus femoris muscle the gluteus minimus the gluteus medius and the gluteus maximus muscles

To the upper part of the iliac fossa the iliacus

To the iliac tuberosity the sacro-pubic muscle and the posterior and the interosseous sacro iliac ligaments

To the auricular surface the anterior sacro iliac ligament

Ischium and Pubis

To the ischial tuberosity the quadratus femoris the sacrotuberous ligament, the semitendinosus, the long head of the biceps and the adductor magnus

the levator ani is more medially placed its fibers pass in an anteroposterior direction and insert into a dense ligament behind the rectum. This ligament is known as the anterior sacrococcygeal ligament and is inserted into the lower two pieces of sacrum and the upper segment of coccyx. The pubococcygeus muscle has been termed the visceral part of the pelvic diaphragm since this muscle fixes the terminal portions of the visceral tubes. There is no hiatus in the levator surrounding the visceral tubes. The implantation of the medial fibers of the pubococcygeus therefore firmly fixes the viscera and constitutes a firm attachment. This intimate relationship between the pubococcygeus and the viscera is of surgical importance in the proper understanding of the mechanics of surgical repair. The *iliococcygeal portion* of the levator ani is more laterally and posteriorly placed than the pubococcygeus and its fibers take a more transverse course. It is inserted into the sides of the sacrum and into the anococcygeal raphe. The iliococcygeus has no relation to the organs as they pass from the pelvis to the exterior even its most anterior fibers do not reach the anal canal. In crossing the midline in front of the coccyx the muscle forms part of the floor and the wall against which the terminal part of the rectum rests. It also offers indirect support to the sigmoid and to the jejunum ileum when the body is in the standing position. It is of obstetric importance as a support but of no great importance in gynecologic repairs.

The coccygeus muscle fills the space between the coccyx and the ischial spine. It is of little importance as a diaphragmatic support but helps to complete or fill in the formation of the pelvic diaphragm. It is of major importance as a support in pregnancy but does not suffer in the course of a normal delivery.

The obturator internus the piriformis and the coccygeus assist the associated ligaments in maintaining fixation of the sacro-




FIG. 402. Muscles of the true pelvis (obturator internus and piriformis). (A) Seen from behind a section of the sacrotuberous ligament has been removed. (B) Posterolateral view.

iliac joint by holding the posterior wall of the pelvis together. Therefore they are of importance in relation to backache and so called sacro-iliac strain.

FASCIA

The pelvic fascia which is distributed in the basin shaped pelvis may be divided into three main divisions: (1) the parietal fascia which covers the muscles of the pelvic cavity; (2) the diaphragmatic fascia which forms a covering for the pelvic diaphragm; and (3) the endopelvic or visceral fascia, which covers the pelvic viscera.

The parietal layer of the pelvic fascia lines the sides, the back, and the front of the pelvic cavity and covers the muscles which form a padding for this cavity (Fig. 403 B). It forms a rather firm layer over

Pelvic Diaphragm

MUSCLES

The muscles within the true pelvis may be considered in two groups (1) two muscles which together form the pelvic diaphragm and are associated with the pelvic viscera (levator ani and coccygeus) and (2) two muscles which are associated with the lower extremity but arise in the pelvis (obturator internus and piriformis)

The walls of the pelvis minor are covered on each side by the obturator internus and posterior to this by the piriformis, these are referred to as the pelvifemoral group of muscles (Fig 402) The walls of the pelvis therefore are padded by muscles of the thigh since both the obturator internus and the piriformis insert into the femur They are covered by fascia which will be discussed subsequently (p 557)

The obturator internus muscle covers the inner aspect of the pelvis It arises from the pelvic surface of the obturator membrane and from the pelvic surface of the hip bone behind the obturator foramen In its posterior part the muscle extends up to the iliopectineal line Its upper border recedes and falls short of the upper margin of the obturator foramen thus the obturator vessels and nerves can leave the pelvis without having to pierce it The muscle bundles converge toward and almost fill the lesser sciatic foramen the converging tendon bends sharply at the margin of the foramen and inserts on the medial surface of the greater trochanter just above the trochanteric fossa It acts as an external rotator of the thigh The nerve supply of the obturator internus muscle has been re-

ferred to as a "special nerve" which arises from L 5 and S 1 and 2

The piriformis muscle (S 1 and 2), like the obturator internus, arises from the os seoligamentous framework of the interior of the pelvis It lies on the posterior wall of the pelvis and arises from the second, the third and the fourth pieces of the sacrum Its fibers travel outward and converge to form a musculo aponeurotic tendon which leaves the pelvis through the greater sciatic foramen It inserts into the top of the greater trochanter and, although it belongs, with the obturator internus, to the pelvifemoral group, it nevertheless serves a diaphragmatic function, since it is continuous in the same plane with the coccygeus (Fig 403 B) In the standing position, the muscle is on the wall rather than the floor of the pelvic cavity It abducts the flexed thigh and laterally rotates the extended thigh

The pelvic diaphragm is composed of two muscles on each side the levator ani and the coccygeus (Figs 403, 404 and 405) The levator ani may be divided into two parts the pubococcygeus and the iliococcygeus The three muscles (pubococcygeus, iliococcygeus and coccygeus) are the original "tail" muscles which take their origin from the pelvic bone and together form the whole of the pelvic diaphragm A distinct space or cleft separates them, but this is only apparent when the fascia is removed The levator ani arises from the inner side of the pubis for a short distance lateral to the symphysis and from the tendinous arch (white line) The pubococcygeal portion of




FIG. 404 The pelvic diaphragm (levatores ani and coccygei) seen from above. The pubococcygeus and the iliococcygeus muscles form the levator ani, the pubococcygeus is the stronger of the two.

turator fascia such a space is known as the *hiatus of Schwalbe*. At times an elongation of pelvic peritoneum may enter the hiatus and into the so called supratrigeminal space (Fig. 405). If this exists a hernia into the ischiorectal fossa may result.

The diaphragmatic pelvic fascia is that fascia which forms a sheath or envelope for the levator ani and the coccygeus muscle. Therefore it has two layers referred to as superior (internal) and inferior (external) layers (Figs. 403 A and 405). The *superior layer* of diaphragmatic fascia is strong and thick, but the inferior layer is much thinner. The superior layer is strong enough to give additional support to the structures which rest upon the diaphragm. The *inferior layer* is known as the anal fascia caudally it becomes continuous with the superior fascia of the urogenital diaphragm and with the fascia of the sphincter ani muscle (Fig. 403 B). The levator ani muscles and their fascial coverings divide the extraperitoneal space on each side of the rectum into an upper pelvirectal and a

lower ischiorectal space both of which are filled with fat and areolar tissue. Along the lateral wall of each ischiorectal space *Ilcock's canal* is found. This canal is formed by a split in the obturator internus fascia, it carries the pudendal vessels and nerves as they course horizontally backward.

The visceral part of the pelvic fascia is that layer of connective tissue which envelops the pelvic viscera (Fig. 406). On each side it is continuous with the fascia on the pelvic surface of the levator ani muscles and so indirectly becomes continuous with the parietal pelvic fascia along the origin of that muscle. It forms three tubes of fascia which encase in succession the urethra and the bladder, the vagina and the lower part of the uterus and the rectum. In each instance the fascial sheath is in intimate contact with the musculature of the corresponding viscus and is believed to receive muscle fibers from it. These fascial tubes are connected by thickened portions of the visceral fascia.




FIG 40. The pelvic diaphragm and its fascia (A) Sagittal section showing the origin of the levator ani from the arcus tendineus the arrows indicate the space which may exist (hiatus of Schwalbe) if the obturator fascia forms a tendinous sling between the pubic bone and the ischial spine A hernia could occur through such a gap (B) Formation of Alcock's canal, the arrow indicates the hiatus of Schwalbe The parietal and the diaphragmatic pelvic fasciae are shown

the muscles but a very thin layer over the periosteum. It is a downward continuation of the transversalis fascia and as it enters the pelvis it attaches on each side to the bone at the linea terminalis (iliopectineal line). It then continues downward over the obturator internus muscle forming a fascial covering for this muscle. It attaches to the bone about the margin of the muscle. That portion of fascia which overlies the obturator internus muscle is known as the *obturator fascia*. Over the upper portion of this fascia a curved line forms as a result of a thickening of the fascia. This thickened portion has been referred to as the *white line* or the *arcus tendineus* (Figs

404 and 405). It is a linear thickening which extends from the symphysis pubis in front to the ischial spine posteriorly. It does not travel as a straight line but has a downward directed curvature. From this line the levator ani muscle and its pelvic fascia covering (diaphragmatic pelvic fascia) take origin (Figs 403, 404 and 405). It is true that in most instances the levator ani arises from the pubic bone anteriorly the ischial spine posteriorly and the obturator fascia between these two points however, at times the fascia forms a tendinous sling which attaches to bone only in front and behind. This results in a space which exists between the sling and the ob

which are called ligaments. On either side of the vagina and the lower uterus the *cardinal ligaments* extend laterally to the parietal pelvic fascia. These are the bases of the broad ligaments and are important in gynecologic surgery; they have also been referred to as Mackenrodt's ligaments. On each side of the rectum its lateral ligaments extend backward to the sacrum; they are known as the *rectal stalks*. The front of the sacrum also is covered by fascia which pierces behind the rectum and forms a fascial enclosed space called the *retrorectal space*. This space is bounded in front by the fascia on the back of the rectum, behind by the presacral fascia, and on each side by the lateral rectal stalks. In the male it forms the important *retovesical fascia* and the sheath of the prostate (p. 576).

The obturator internus and the piriformis muscles are located outside of (beneath) the pelvic fascia since they both ultimately leave the pelvis (Fig. 407). The sacral nerves are also beneath this fascia since




FIG. 407 The arrangement of structures on the side wall of the pelvis. The muscles (obturator internus and piriformis) and the sacral nerves are beneath the parietal layer of pelvic fascia; the internal iliac vessels are above it.

the majority of them leave the pelvis through the sacral foramina. Therefore it is unnecessary for the muscles and nerves to pierce the fascia. On the other hand the blood vessels of the pelvis (branches of the internal iliac vessels) are destined to remain in the pelvis and are located inside of (above) the pelvic fascia, between it and the peritoneum.




FIG 405 The pelvic diaphragm and its fascia, seen in a frontal section




FIG 406 The visceral part of the pelvic fascia. This layer of connective tissue envelops the pelvic viscera

At birth the true pelvis is undeveloped hence little room is available for either intestines or bladder. During infancy the bladder is an abdominal organ whether full or empty and is in contact with the anterior abdominal wall (Fig. 411). The peritoneum is reflected off of the uterus and onto the vesical neck in the male the reflection is even lower off the rectum and onto the prostate. As the pelvis enlarges the bladder gradually sinks into it so that the larger part of the empty bladder is accommodated by the pelvis at the sixth year. Shortly after puberty the bladder becomes a pelvic organ exclusively.

THE ADULT BLADDER

The empty and contracted urinary bladder has four angles four surfaces and four ducts a duct being attached to each angle. The pelling of each duct starts with the letter U one urachus one urethra and two ureters (Fig. 410 A). The urachus attaches to the anterior angle (apex) the right and the left ureters attach to the posterolateral angles and the urethra attaches to the inferior angle. The four surfaces are the superior the two inferolaterals and the posterior. They are somewhat triangular




FIG. 409 Embryology of the urinary bladder (A) The bladder is divided into upper and lower parts (B) The parts meet at the interureteric bar (C) Formation of a bladder diverticulum at the interureteric bar

in shape and are bounded by the three angles which connect around the borders. The superior surface and about a half inch of the posterior surface are the only parts covered with peritoneum. The superior surface is directed upward and is related to the coils of the ileum and the pelvic colon (Fig. 412). In the female, the uterus lies on this surface and tends to indent it. At its anterior end this surface becomes somewhat pointed and forms the apex of the bladder. This is situated immediately behind the upper margin of the pubic sym-




FIG. 410 The urinary bladder (A) Side view showing the surfaces the angles and the 'ducts' (B) Malformations of the urachus

The Pelvic Viscera

THE BLADDER (VESICA URINARIS)

EMBRYOLOGY

The allantois is an evagination from the primitive hindgut (Fig. 408 A). Shortly after this forms the gut caudad to the point of origin of the allantois enlarges to form the cloaca. The cloaca is divided into a ventral and a dorsal part by an ingrowing urorectal fold, the ventral part becomes the urogenital sinus and the dorsal part becomes the rectum (Fig. 408 B). The urorectal fold cuts into the cephalic part of the cloaca where the allantois and the hindgut meet and then grows caudad to the cloacal membrane.

The entire upper part of the bladder (except the base) is derived from the cephalic or upper end of the anterior division of the cloaca and the base and the prostatic urethra are formed from the lower end of the Wolffian duct. These two portions fuse along a line marked by a bar of muscle, the interureteric bar which is situated between the ureters (Fig. 409). Organs which have a double origin may develop congenital abnormalities at the site of fusion of the two parts; hence when congenital diverticula of the bladder occur they are found somewhere along the line of the interureteric bar and are in close proximity to the ureteric orifice. The urachus (the allantois of the embryo) is a fibrous cord which connects the apex of the bladder to the umbilicus. If it remains patent throughout its entire length urine will be discharged at the umbilicus (Fig. 410 B). It is believed that if this condition exists an obstruction to the outflow of urine from the bladder is also present. The urachus may

remain open only in localized areas, forming small lacunae which are known as the lacunae of Luschka. They are usually symptomless and are found at postmortem. If such a lacuna enlarges there results a urachal cyst which is situated below the umbilicus in the midline (Fig. 410 B).




FIG 408 Embryology of the urinary bladder (A) The formation of the allantois, an evagination of the primitive hindgut (B) The arrow indicates the down growth of the urorectal fold which divides the cloaca into a ventral part (the urogenital sinus) and a dorsal part (the rectum)




FIG 413 Midsagittal section through the distended bladder. As the bladder fills, the neck remains fixed; the peritoneum is stripped from the anterior abdominal wall.

ture the bladder neck in the male lies a little below the level of the upper margin of the symphysis and about two and one half inches behind it (Fig. 413). The bladder neck rests upon the base of the prostate and its muscle fibers are uninterruptedly continuous with those of the prostate. The union of the bladder and the prostate is marked on the outside by a groove in which lie the veins of the prostatic and the vesical plexuses. These veins extend above the groove onto the inferolateral surface of the bladder and below it onto the lateral aspect of the prostate gland.

As the bladder fills the neck remains fixed; the upper wall rises and with the other surfaces increases in area and becomes more convex. The inferolateral surfaces approximate themselves to a greater area of the side walls of the pelvis; the greater vessels and nerves and the vasa deferentia. The borders become rounded and obliterated. The bladder continues to rise out of the pelvis, stripping the peritoneum from the anterior abdominal wall so that it is in direct contact with the transversalis fascia for about an inch and one half above the pubic bone. When con-

tracted and emptied the bladder lies in the lower and the anterior part of the pelvis immediately below the peritoneum in the extraperitoneal fatty tissue; the areolar element of which becomes condensed to form a sheath around it. A distended bladder pushes the prostate backward, making it more prominent on rectal exami-




FIG 414 The puboprostatic (pubovesical) ligaments.



FIG 411 The position of the empty bladder (A) In infancy as an abdominal organ (B) In the adult as a pelvic organ

physis and is continuous with a strong fibrous cord (median umbilical ligament) which passes upward in the midline between the transversalis fascia and the peritoneum (p 567). The *inferolateral surfaces* are in contact in front with the retropubic fat pad which fills the space of Retzius. More posteriorly, the surfaces are related to the obturator internus muscle and the lateral umbilical ligament (obliterated umbilical artery) above and to the levator ani muscles below. The numerous veins of the vesical venous plexus pass backward and are in intimate relationship with these sur-

faces. The *posterior surface* of the bladder faces as much downward as backward and has been referred to as the *base* or *fundus* of the urinary bladder. It lies in front of the rectum, and it can be palpated through the rectum. No peritoneum exists between the rectum and the posterior surface of the bladder, except to a very slight degree above, however, they are separated from each other by the vasa deferentia, the seminal vesicles and the rectovesical fascia (Denonvilliers).

The two vasa deferentia lie side by side on the posterior surface of the bladder and intervene between the seminal vesicles. The ureters enter at the superolateral angles.

The *neck* of the bladder is that part which is continuous with the urethra. In the male it is embraced by the prostate and in the female it lies on the upper layer of the urogenital diaphragm (triangular ligament). It is the lowest part of the bladder and is connected with the lower part of the back of the pubis by the pubovesical or puboprostatic ligaments. Because of the obliquity of the pubis in the erect pos-




FIG 412 The urinary bladder seen from above




FIG 416 The arterial supply to the bladder. The relations of the superior and the inferior vesical arteries are shown.

brane that interrupts the fingers when pushed down between the bladder and the pubis when one examines the space of Retzius. A narrow fascial sheath unites each ligament with its fellow of the other side and the two form a roof over the anterior part of the gap between the anterior borders of the levatores ani.

The medial puboprostatic ligaments constitute the strongest, most definite and most important part of the pelvic fascia. They are continuous laterally with the *lateral puboprostatic ligament*, which is that part of pelvic fascia covering the anterior part of the levator ani; it is connected with the fascial sheath of the prostate and the bladder at the side of the bladder neck. The bladder is retained in position anteriorly by the *median umbilical ligament* (urachus), the *lateral umbilical ligaments* (atrophied fetal umbilical arteries) also stabilize the bladder anteriorly. The lateral and the median umbilical ligaments maintain the bladder against the anterior abdominal wall when it fills and rises out of

the pelvis. Posteriorly the bladder is supported by the rectovesical fascia (Denonvilliers) (p. 576).

The structure of the bladder reveals five coats: serous, fascial, muscular, submucous and mucous.

1 The serous coat is peritoneum which is restricted to the upper surface and also to a small part of the base in the male.

2 The fascial coat is extraperitoneal tissue which sheaths the bladder. It is loose except on the upper surface where it becomes an exceedingly thin layer which binds the serous to the muscular coat.

3 The muscular coat is a thick, strong, nonstriated muscle which is arranged in intersecting bundles traveling in different directions. This is difficult to display in the dissecting room but it is arranged in close bundles which pass both obliquely and circularly around the bladder. At the neck of the bladder these bundles become massed together to form a ring called the *sphincter of the bladder*; the sphincter is continuous inferiorly with the muscular

nation hence the true size of the prostate can best be estimated through the rectum only when the bladder is empty

The *prevesical* or *retropubic space* of Retzius is that space which is behind the

bladder infections and urinary extravasation as seen in extraperitoneal rupture of the bladder, an effusion into this space may extend into the extraperitoneal tissue of the abdominal wall or the pelvis. The sur-




FIG 415 The interior of the bladder

pubic bone and in front of the urinary bladder (Fig 415). The space is bounded anteriorly by the posterior sheath of the rectus muscle and the posterior surface of the pubis. It is limited below by the puboprosthetic (pubovesical) ligaments in the fascia covering the levator ani. On each side it extends as far back as the internal iliac artery and its visceral branches. Superiorly, it is continuous with the interval that exists between the peritoneum and the transversalis fascia which extends up to the umbilicus, here it is limited on each side by the lateral umbilical ligaments. The median umbilical ligament (urachus) bisects it. This extraperitoneal space is filled with fatty and areolar tissue which separates the bladder from the ventral pelvic wall. In inflammatory involvement of it may follow

geon may enter the bladder extraperitoneally through the space of Retzius.

The bladder is anchored at its base where it is fixed by continuity with the prostate and the urethra. The latter in turn is fixed to the urogenital diaphragm (triangular ligament). The neck of the bladder is fused by the *puboprosthetic* (pubovesical in the female) *ligaments* (Fig 414). In the female, the visceral attachments of these ligaments are to the neck of the bladder; therefore, they have been called the pubovesical ligaments. Their anatomy, however, is essentially the same. The *medial puboprosthetic* (pubovesical) *ligaments* are thickenings of the pelvic fascia which form a pair of strong thick bands that fix the prostate and the neck of the bladder. They arise from the lower part of the back of the pubis at the sides of the symphysis, pass backward and fuse with the strong fascia that surrounds the base of the prostate and the neck of the bladder. They form the resisting mem-

SURGICAL CONSIDERATIONS

INJURIES TO THE BLADDER

Bladder wounds would occur far more frequently if the organ were not so well protected within the pelvic cavity. These injuries may occur in various ways as a result of laceration by sharp bony fragments in fractures of the pelvis from direct blows over the hypogastrium, especially if the bladder is distended penetrating wounds account for a certain number of bladder injuries, as does violence exerted through the rectum the vagina or the perineum. The injury may be intraperitoneal or extraperitoneal (Fig. 418). Intraperitoneal rupture occurs in the part of the bladder covered by peritoneum; extraperitoneal rupture involves only the mucomuscular coats of the viscus since these are not covered by peritoneum. In the latter case the lesion is subperitoneal and the urine extravasates beneath the peritoneum. The most frequent site for rupture of the bladder is the posterosuperior aspect. Whether the rupture is intraperitoneal or extraperitoneal, immediate surgery must be employed.

APPROACHES TO THE BLADDER

For diagnostic purposes the urethral (cystoscopic) approach is employed. The




FIG. 417 The nerve supply to the bladder (diagrammatic)

The nerve supply accompanies the arteries and involves not only a complex coordination of sympathetic and parasympathetic nerves but also the voluntary control of the sphincter via the pudendal nerve (Fig. 417). The sympathetic nerves (hypogastric plexus) are the filling nerves of the bladder since they inhibit the detrusor muscle which makes up the bladder wall they cause increased tone in the internal sphincter thereby permitting the bladder to retain its contents. The parasympathetic nerves (pelvic splanchnic nerves) on the other hand are the emptying nerves of the bladder because they stimulate the contraction of the detrusor muscle the elevation of the trigone and the relaxation of the internal sphincter. This is accompanied by voluntary relaxation of the external sphincter by means of cerebral control via the pudendal nerve.




FIG. 418 Bladder injuries. A bladder injury may be either intraperitoneal or extraperitoneal.

wall of the urethra in the female and with the muscular substance of the prostate in the male

4 The submucous coat is a layer of areolar tissue which forms a loose connection between the muscular and the mucous coats. The blood vessels and the nerves ramify in this coat before entering the mucosa

5 The mucous coat is of the usual type

THE INTERIOR OF THE BLADDER If the bladder is contracted and empty, the mucosa is thrown into folds and presents a wrinkled or rugose appearance in the distended bladder however the mucosa becomes smooth. The *trigone* (trigonum vesicae) is a triangular area which occupies most of the inner surface of the posterior bladder wall and remains smooth even when the bladder is empty (Fig 415). It is elastic and tightly bound by areolar tissue to the muscular coat therefore it does not alter its appearance as does the rest of the mucous membrane. It is thinner than the rest of the mucosa. When a cystoscopic examination is made in a living subject the trigone appears pink because this thinness permits the vessels to be seen through it. The rest of the mucous membrane of the bladder presents a straw-colored appearance. The apex of the trigone is formed by the internal urethral orifice the base corresponding to a line which passes between the two ureteral orifices, and is known as the *interureteric ridge*. This ridge is mucous membrane which has been raised by an underlying bar of muscle. The sides of the trigone are about an inch wide when the bladder is empty and about an inch and a half wide when it is full.

There are three openings into the bladder two inlets and one outlet these are situated at the angles of the trigone. The two orifices of the ureters constitute the inlets they appear as a pair of semilunar slits which are placed at the extremities of the trigone and are separated by the interureteric ridge. If a probe or catheter is

passed into these openings, it is noted that the ureter takes an oblique course through the bladder wall for about three quarters of an inch. This obliquity forms a valve which allows urine to pass into the bladder but prevents regurgitation as the bladder fills. The *internal urethral orifice* is at the apex of the trigone. It is not completely circular because behind it an elevation known as the *uvula* or vesical crest pushes its posterior margin slightly forward. This uvula presents a bulging which results from the middle lobe of the prostate, if this lobe becomes enlarged, it may partially or completely block the orifice. The *retrotrigonal fossa* is the interior of the fundus of the bladder. When it is deepened by increased intravesical pressure (prostatic hypertrophy) urine may accumulate here and stagnate. Foreign bodies may gravitate into this fossa, and bladder ruptures can occur through it.

VESSELS AND NERVES

The *arterial supply* to the bladder is derived mainly from the internal iliac artery, small branches from the obturator and the internal pudendal arteries are supplied to the anterior part of the bladder (Fig 416). The *superior vesical artery*, which is the unobliterated part of the umbilical artery, supplies the superolateral wall. The *inferior vesical artery* is distributed between the floor of the bladder the prostate and the prostatic urethra. The *middle hemorrhoidal artery* supplies a branch to the posterior surface of the bladder.

The *veins* form perivesical plexuses which are most dense around the neck and the ends of the ureters these drain into the inferior vesical veins. In the male, the larger veins lie in the groove between the bladder and the prostate and form the vesicoprostatic plexus.

The *lymph vessels* of the anterior part of the bladder pass to the external iliac glands. From the posterior part, a few may pass to the external iliac glands, but the major portion of these drain into the internal iliac glands.

SURGICAL CONSIDERATIONS

INJURIES TO THE BLADDER

Bladder wounds would occur far more frequently if the organ were not so well protected within the pelvic cavity. These injuries may occur in various ways as a result of laceration by sharp bony fragments in fractures of the pelvis from direct blows over the hypogastrum especially if the bladder is distended penetrating wounds account for a certain number of bladder injuries as does violence exerted through the rectum the vagina or the perineum. The injury may be intraperitoneal or extraperitoneal (Fig. 418). Intraperitoneal rupture occurs in the part of the bladder covered by peritoneum extraperitoneal rupture involves only the mucomuscular coats of the viscus since these are not covered by peritoneum. In the latter case the lesion is subperitoneal and the urine extravasates beneath the peritoneum. The most frequent site for rupture of the bladder is the posterolateral aspect. Whether the rupture is intraperitoneal or extraperitoneal immediate surgery must be employed.

APPROACHES TO THE BLADDER

For diagnostic purposes the urethral (cystoscopic) approach is employed. The




FIG. 417 The nerve supply to the bladder (diagrammatic)

The nerve supply accompanies the arteries and involves not only a complex co-ordination of sympathetic and parasympathetic nerves, but also the voluntary control of the sphincter via the pudendal nerve (Fig. 417). The sympathetic nerves (hypogastric plexus) are the inhibitory nerves of the bladder since they inhibit the detrusor muscle which makes up the bladder wall. They cause increased tone in the internal sphincter thereby permitting the bladder to retain its contents. The parasympathetic nerves (pelvic splanchnic nerves) on the other hand are the emptying nerves of the bladder because they stimulate the contraction of the detrusor muscle the elevation of the trigone and the relaxation of the internal sphincter. This is accompanied by voluntary relaxation of the external sphincter by means of cerebral control via the pudendal nerve.

EXTRAPERITONEAL RUPTURE



FIG. 418 Bladder injuries. A bladder injury may be either intraperitoneal or extraperitoneal.




FIG 419 Surgical approaches to the bladder

three most common other approaches usually described are the suprapubic (extra peritoneal) the abdominal (transperitoneal) and a transperineal (perineo urethral) (Fig 419)

The *suprapubic approach* affords excellent access to the extraperitoneally placed bladder. It is particularly applicable in prostatectomy and in the removal of calculi and neoplasms.

The *abdominal and transperineal approaches* are more of didactic than practical interest.

SUPRAPUBIC CYSTOSTOMY

This operation is accomplished through a vertical midline incision which is placed in the suprapubic region (Fig 420). It is preferable to have the organ fully distended as a preliminary step. The incision is deepened to an interval between the rectus abdominis and the pyramidalis muscles. Behind these muscles and at the upper border of the symphysis lies the transversalis fascia. The prevesical space is exposed by dividing this fascia. If the bladder is distended it can be felt by inserting a finger into the lower angle of the incision. The peritoneum is reflected upward since the connection between the peritoneum and the bladder is loose, this

maneuver is accomplished readily. The prevesical fat and the visceral layer of pelvic fascia are incised. Vesical veins may be found in this stratum. Now the bladder can be elevated and entered. A Pezzer type of catheter is introduced into the bladder for drainage.

PELVIC VISCERA IN THE MALE

The upper part of the pelvic colon usually can be lifted out of the male pelvis, but the lower part remains attached to the dorsal wall by the medial limb of the pelvic mesocolon (Figs 421 and 422). The rectum occupies the lower portion of the dorsal part of this cavity and follows the concavity of the sacrum and the coccyx. The urinary bladder lies in the lower and anterior part of the cavity behind the pubic bone. Both ureters usually can be seen shining through the peritoneum posteriorly at the side walls of the pelvis. The seminal vesicles lie on the back of the bladder between it and the rectum, and on each side the vas deferens can be seen through the peritoneum as it passes from the deep inguinal ring toward the bladder. Having crossed the pelvic brim, the vas first passes downward and backward and then medially across the ureter to reach the back of the bladder where it descends along the medial side of the seminal vesicle close to the vesicle of the opposite side. The prostate lies below the bladder, directly in front of the lower part of the rectum, and encloses the prostatic urethra. The pelvic peritoneum covers the dorsal wall of the pelvis and is reflected off as the medial limb of the pelvic mesocolon. At the third piece of sacrum, the peritoneum reaches the rectum, to which it gives a partial covering, and then covers the front of the upper third of the rectum and its sides. At the middle third it covers only the anterior surface and the lower end of the middle third as it passes from the rectum to the bladder. It covers the upper surface of the bladder, from which it passes forward onto the anterior abdominal wall and the sides of the pelvic wall. From the sides of the




FIG 420 Suprapubic cystostomy (A) A vertical midline incision is made in the suprapubic region (B) The muscles and the transversalis fascia are incised and retracted. The peritoneum is reflected upward and the bladder is incised (C) The completed cystostomy in sagittal section

upper third of the rectum it extends to the side walls of the pelvis forming the floor of a pair of depressions called the *pararectal fossae*. As it continues forward from the rectum to the bladder it forms the floor of the depression known as the *recto vesical pouch*. When the peritoneum reaches the bladder it is tucked behind it to cover a small portion of its posterior surface in the median plane between the two vasa deferentia.

DEFERENT DUCTS

The *vas (ductus) deferens* has a scrotal, an inguinal and a pelvic course (Fig 421)

It begins at the lower end of the epididymis passes upward over the back of the testis on the medial side of the epididymis and ascends to the superficial inguinal ring. It traverses the inguinal canal as a constituent of the spermatic cord in the posterior part of the cord it is readily palpable because of its firmness. It leaves the other constituents of the spermatic cord at the deep inguinal ring. The intrapelvic portion of each vas extends from the internal inguinal ring to the base of the prostate. It hooks around the origin of the inferior epigastric artery and passes backward with a slight downward bend on the side wall of the pelvis until it reaches the region of the




FIG 421 The pelvic viscera in the male The left wall of the pelvis has been removed and the bladder is partly filled

ischial spines (Fig 423) Here it makes a right angle bend which carries it medially, forward and downward across the terminal part of the ureter and down the posterior surface of the bladder After hooking around the inferior epigastric artery it crosses the external iliac artery and vein the superior ramus of the pubis, and the obturator internus muscle but is separated from the latter by the lateral umbilical ligament (obliterated umbilical artery) and the obturator artery, nerve and vein At the ischial spine where it turns medially, it

crosses the ureter and then passes downward on the posterior aspect of the bladder In this part of its course it lies behind and in front of the rectum with the seminal vesicle on its inferolateral side and the vas of the opposite side in close contact with it Until the vas reaches the posterior surface of the bladder it is in direct contact on its medial side with the peritoneum, but thereafter it lies below the peritoneal floor of the pelvis In its terminal part each vas is enclosed within the thickness of the frontally disposed rectovesical fascia



FIG 422 Pelvic viscera in the male seen from behind




FIG. 423 The intrapelvic portion of the vas deferens (seen from behind). The left seminal vesicle and the ampulla of the vas have been sectioned and part of the prostate has been removed in order to expose the ejaculatory duct.

(Denonvilliers) and becomes widened into an ampulla. The ampullae appear as elongated bags which are reservoirs for the semen; it is in the ampullae that a secretion of the mucous membrane of the vas is added. The vasa deferentia converge and unite with the excretory ducts of the seminal vesicles to form the ejaculatory ducts; these traverse the prostate and open into the prostatic urethra. The artery to the vas deferens arises either from the superior or the inferior vesical artery; runs in close relation with the wall of the vas from the base of the bladder to the epididymis and anastomoses with the testicular artery.

SEMINAL VESICLES

The seminal vesicles are offshoots of the deferent ducts (Fig. 422 and 423). They appear as lobulated sacs about two inches long and one half inch in diameter, and present the same histologic picture as the ampullated end of the vas. The bladder is in front, the rectum behind, the vas is medial and is capped above by peritoneum; laterally it is separated from the levator ani by numerous vesical vessels. Each semi-

nal vesicle lies obliquely so that its lateral surface faces downward as well as side ward and it is related to the fat on the levator ani muscle. If the vesicle is teased apart, it is found to be a sacculated tube about six inches long which is folded and coiled into its baglike form (Fig. 424). The seminal vesicle is not to be considered simply a reservoir for spermatozoa; its function is to produce a secretion which forms a large part of the seminal fluid. The ejaculatory duct is that duct which is common to both the vas and the vesicle. Its diameter is approximately that of a pencil. It is easily torn away from the prostate, the upper half of which it pierces obliquely to open beside the prostatic utricle. The arteries to the seminal vesicle and the ampulla of the vas are tiny branches which are derived from the vesical and the middle hemorrhoidal arteries. The veins correspond to the arteries and the lymph vessels of the vesicle and the ampulla of the vas and end in the internal and the external iliac glands.

PROSTATE GLAND

The prostate gland is a solid organ which surrounds the urethra between the bladder




FIG 421 The pelvic viscera in the male. The left wall of the pelvis has been removed, and the bladder is partly filled

ischial spines (Fig 423). Here it makes a right angle bend which carries it medially, forward and downward across the terminal part of the ureter and down the posterior surface of the bladder. After hooking around the inferior epigastric artery, it crosses the external iliac artery and vein, the superior ramus of the pubis, and the obturator internus muscle but is separated from the latter by the lateral umbilical ligament (obliterated umbilical artery) and the obturator artery nerve and vein. At the ischial spine, where it turns medially, it

crosses the ureter and then passes downward on the posterior aspect of the bladder. In this part of its course it lies behind and in front of the rectum with the seminal vesicle on its inferolateral side and the vas of the opposite side in close contact with it. Until the vas reaches the posterior surface of the bladder it is in direct contact on its medial side with the peritoneum but thereafter it lies below the peritoneal floor of the pelvis. In its terminal part each vas is enclosed within the thickness of the frontally disposed rectovesical fascia




FIG 422 Pelvic viscera in the male, seen from behind




FIG 425 Diagrammatic presentation of relations of the prostate (coronal section)

ward until they occupy almost the entire base (upper portion) of the gland. As they grow anteriorly they almost approximate one another in the anterior region of the urethra. Hypertrophy of these lobes causes urinary obstruction by lateral encroachment upon the prostatic portion of the urethra, and if one lobe greatly exceeds the other in size the urethra may be pushed laterally and be increased in length.

Clinically the median (middle) lobe is the most important. It originates on the posterior surface of the floor of the ejaculatory ducts. It is post-urethral as is the posterior lobe, but unlike the posterior lobe it is pre-permeatic; it is below the neck of the bladder and contains much glandular tissue. In this region the utricular and the subcervical glands (Albarran) are found. These are mucous glands which are entirely separate and distinct from the prostate and are important because of their intimate relationship to the bladder neck. Slight degrees of enlargement of these glands may lead to obstruction of the outflow of urine. The middle lobe normally projects into the urethra, causing a prominence on its floor; this prominence is known as the verumontanum (crista ureth-

ralis, seminal colliculus). This lobe is clinically important because it is the one in which adenomas frequently grow. The line of least resistance is inward into the urethra. As it enlarges it pushes the mucous membrane of the urethra ahead of it, extends into the bladder and may entirely block the internal urinary meatus. The effort of straining to urinate pushes it onto the internal meatus, thus further blocking the outlet.




FIG 426 The five lobes of the prostate (A) a cross section at the neck of the bladder of an embryo (B) sagittal section of the bladder and the prostate




FIG 424 The seminal vesicle The vesicle has been unravelled. It is a tortuous tube with many outpouchings

and the urogenital diaphragm (Fig 413). It consists of fibrous tissue, plain muscle and glandular elements. It is broader than it is long, being about $1\frac{1}{4}$ inches long and $1\frac{1}{2}$ inches broad. Its exact functions are not known. It adds a secretion which is concerned with the vitality of the spermatozoa. It has an apex (lower end), a base (upper surface), an anterior surface and a posterior surface and a pair of lateral surfaces. It is the size and the shape of a chestnut, surrounds the first $1\frac{1}{4}$ inch of the urethra and is traversed by the ejaculatory ducts.

The base or superior surface, although structurally continuous with the superimposed bladder (neither the fibers nor the muscular part show any interruption as they pass from one organ to another), nevertheless shows a circular groove in which fat and veins are lodged. Its apex points downward and rests upon the super-

rior fascia of the urogenital diaphragm (Fig 425). Its anterior border or surface is blunt and rounded and is separated from the retropubic space (Retzius) by the puboprostatic ligaments and from the lower part of the symphysis by fibro-adipose tissue and a plexus of veins. The posterior surface is flattened and rests against the lower inch of rectum. This is the portion of the prostate which is felt by digital examination, only the rectovesical fascia intervening. This surface is pierced on each side of the median plane by the ejaculatory ducts. The two lateral surfaces (inferolateral) are convex and are supported by the anterior fibers of the levator ani; the two anterior borders of the levators clasp the lower part of the prostate between them.

Lobes of the Prostate. In uterine life longitudinal depressions appear on the walls of the urethra immediately inferior to the bladder. These depressions become buds which grow and penetrate the surrounding muscle and the connective tissue to form the ultimate five lobes of the prostate gland: an anterior, a posterior, a medial and two lateral lobes (Fig 426). The anterior lobe buds from the anterior wall of the urethra; its glandular elements gradually disappear so that at birth few or no glandular elements remain. Therefore, adenomas rarely, if ever, occur in this lobe and there is no encroachment upon the lumen of the urethra from this direction.

The posterior lobe arises from the posterior wall of the urethra, inferior to the orifice of the ejaculatory ducts and grows superiorly to occupy a plane behind the ducts. As it grows toward the base of the bladder it becomes both post-urethral and post-spermatic. This lobe lies behind the middle lobe, forms the entire posterior surface of the gland and is the lobe encountered during digital examination. Adenomas rarely, if ever, occur here, but primary carcinoma may. The two lateral lobes arise as tubular outgrowths from the lateral walls of the urethra. They grow laterally, anteriorly, posteriorly and up-




FIG. 429 The prostatic urethra. A frontal section is made so that the posterior aspect of the urethra is seen.

which has been so aptly described as passing 'between wind and water'.

Roux has described a so-called rectourethralis muscle. It consists of two muscle bundles—superior and inferior both of which are derived from the longitudinal muscle coat of the bowel wall. It holds the rectum at an angle forward. These muscle bundles are attached to the upper part of the perineal body and must be divided in perineal prostatectomy if the rectum is to be successfully displaced backward and out of danger.

Vessels. The blood supply of the prostate is derived from the inferior vesical and the middle rectal (hemorrhoidal) arteries. The prostatic plexus of veins is joined in front by the deep dorsal vein of the penis. As these veins pass backward they extend around the junction of the prostate and the bladder and are joined by numerous vesical veins. They continue backward lateral to the seminal vesicles and below the ureter and terminate in the internal iliac vein. The lymph vessels end in the internal iliac and the sacral lymph glands.

Prostatic Urethra. The prostatic part of the urethra is about one inch long and is the widest and the most dilatable part (Figs. 413 and 429). It passes almost perpendicularly from the neck of the bladder slightly forward through the prostate and emerges a little above its apex where it becomes continuous with the second or

membranous part. It is fusiform in shape, but on transverse section appears crescentic owing to the presence of a prominent vertebral ridge on the posterior wall called the *urethral crest*. On each side of this crest a gutter is formed. This is called the *prostatic sinus* and appears as a groove into which numerous small ducts of the prostate open. The highest point or summit of the urethral crest is called the *seminal colliculus* (*verumontanum*) and lies over the middle of the prostatic urethra. This colliculus bifurcates as it fades away. Opening onto the colliculus is a diverticulum called the *prostatic utricle*. Through this a probe may be passed for about one half inch into the substance of the prostate. This tiny structure is the homologue of the uterus and the vagina. It is of practical importance because it may catch the end of a catheter or a small bougie and impede its passage. The *ejaculatory ducts* open into the urethra by minute slitlike orifices at the sides of the mouth of the utricle. There is much clinical interest concerning the prostatic urethra. A seminal vesiculitis (verumontanitis) may cause obliteration or constriction of the ejaculatory ducts. In epididymitis may result. In chronic urethral infections




FIG. 430 The arrows indicate the possible paths of extension and rupture of a prostatic abcess.




FIG 427 The capsules of the prostate, diagrammatic presentation of the true and the false capsules in coronal section

Fascial Relations and Capsules The prostate has two capsules, a true and a false (Fig 427). The true capsule is formed by a condensation of tissue at the periphery of the gland. The false capsule is formed by the visceral layer of the pelvic fascia which provides a sheath common to both the bladder and the prostate but is absent where these two organs are in contact. For this reason, adenomas of the prostate grow upward into the bladder, this being the line of least resistance. A *pudendal (prostatic) plexus of veins* lies between the two capsules; it receives the deep dorsal vein of the penis in front. During suprapubic prostatectomy the surgeon enu-

cleates the prostate from within both of its capsules and in this way leaves the prostatic plexus of veins undisturbed. During this operation the prostatic urethra is removed with the gland, and the ejaculatory ducts are torn. As a result of this, the patient, although not impotent, is sterile.

In the fetus the peritoneum of the pelvic floor extends down as a pouch behind the prostate gland; normally this pouch is shut off from the peritoneal cavity and then exists as two layers with a potential space between them. These two layers are attached above to the peritoneum (cul de sac of Douglas) and below to the urogenital diaphragm and the perineal body. It is a prostaticoperitoneal layer which is known as *Denonvilliers' fascia* (Fig 428). The anterior layer of this fascia is attached firmly to the prostate, but the posterior layer is attached loosely to the pelvic fascia around the rectum. The potential space between these layers is called the *retroprostatic space of Proust*.

This space should not be confused with the misnamed *prerectal space* which is supposed to exist between the rectum and the fascia of Denonvilliers. In the performance of a perineal prostatectomy the surgeon must find the space of Proust, which exists between the two fascial layers, if he wishes to avoid difficulties such as excessive bleeding and entrance into the rectum. It may be difficult at times to find this space.




FIG 428 Denonvilliers' fascia

pubic prostatectomy, transurethral resection, perineal prostatectomy and retropubic prostatectomy.

The *suprapubic prostatectomy* requires exposure through the bladder (Fig. 431). There are many who find fault with this approach because the gland lies entirely outside of the bladder; the bladder is entered, the enucleation is done blindly and hemorrhage may be difficult to control. In addition, it does not permit complete removal of a carcinomatous gland which has invaded the capsule.

The *transurethral resection* operation is well adapted to smaller glands, median bars and serves as a palliative procedure for obstruction due to carcinoma. In the hands of excellent resectionists, however, the scope of the operation is much greater, and the results are good; hence some outstanding urologists remain most enthusiastic about it. The morbidity may be prolonged by the necrosis of tissue electrically treated in a fairly large percentage of resections; the procedure has to be repeated.

Perineal prostatectomy is a surgical operation in which the gland is removed under direct vision; hemorrhage can be controlled more readily (Fig. 432). It is applicable in the removal of a malignant prostate which has invaded the capsule. It requires a thorough knowledge of perineal anatomy and a highly skilled and trained surgical team. In inexperienced hands, a persistent fistula may result, the rectum may be injured or complete incontinence may be an annoying sequela.

Villin, of London, has described a new approach in the operation of *retropubic prostatectomy* (Fig. 433). Although the space of Retzius has been considered the potential danger area, nevertheless this operation takes place directly through this space. The skin incision extends from the symphysis to the umbilicus in the midline and the rectus muscles are separated. The preprostatic fat which occupies the space of Retzius is identified. The bladder is retracted upward, and an incision is made into the prostatic capsule. The gland is




FIG. 432 Perineal prostatectomy. Denonvilliers' fascia has been incised, and the prostate gland is exposed.

the prostatic duct may also be involved and obstructed. If the infection travels by way of the prostatic opening, a prostatic abscess may result. The seminal vesicles are also involved in gonorrheal infections of

several small foci. The path of least resistance is toward the urethra, and many prostatic abscesses may rupture here (Fig 430). The dense pelvic fascia which invests the prostate usually resists the progress of




FIG 431 Suprapubic prostatectomy. One finger is placed into the bladder and another finger is placed into the rectum so that the gland is defined completely and removed through the bladder.

the prostatic urethra via the ejaculatory ducts.

The internal and the external urinary sphincters of the bladder govern the outflow of urine. The *internal (vesical) urinary sphincter* is derived from the outer and the middle muscle layers of the bladder. These are the fibers which are destroyed in the operation of prostatectomy. The *external (urethral) urinary sphincter* is derived from the *sphincter urethrae membranaceae* (p 632); this is the muscle which compensates and controls urinary flow when the internal sphincter is torn during prostatectomy.

SURGICAL CONSIDERATIONS

PROSTATIC ABSCESS

This condition follows a prostatitis and may appear as a single large abscess or as

the abscess upward through the peritoneum and into the pelvic cavity. The strong urogenital diaphragm resists its spread downward to the perineum. However, it can reach the perineum by pointing toward the rectum where it comes into contact with a thin rectovesical fascia. The abscess may follow this fascia through the space between the urogenital diaphragm and the anus into the perineum; the pus also may erode through the rectovesical fascia and rupture into the rectum. A periprostatic infection can lie lateral to the gland, invade the levator ani muscle and reach the ischio-rectal fossa. A rare path of spread is anteriorly through the pubovesical ligaments and into the space of Retzius.

PROSTATECTOMY

Four accepted methods of removal of the prostate gland have been described: supra-

enucleated to the vesicle neck the prostate is peeled off of the bladder and the prostatic arteries are ligated. A catheter is introduced from the meatus and into the bladder. This operation too has its antagonists and protagonists.

No one operative procedure will meet the requirements of every case therefore all the methods must be known and included in the armamentarium of the surgeons who do this type of work.

PELVIC VISCERA IN THE FEMALE

EMBRYOLOGY

Before the sex of the embryo is determined four parallel tubes grow caudally in the subperitoneal tissue of the posterior abdominal wall (11, 434). They are the right and the left müllerian (paramesonephric) ducts and the right and the left wolffian (mesonephric) ducts. They terminate in that anterior part of the cloaca known as the urogenital sinus. The wolffian duct predominates in the male and gives rise to the spermatic duct, the epididymus, the vas deferens and the ejaculatory duct (p. 562). The müllerian duct predominates in the female and becomes the fallopian tubes, the uterus and the vagina. The cephalic ends of müller's (paramesonephric) ducts open into the body cavity but the caudal ends having crossed the wolffian ducts fuse with each other and form a single tube which opens into the urogenital sinus. The cranial ends of these ducts become the fallopian tubes, their intermediate parts fuse to form the uterus and the caudal ends fuse and form the upper part of the vagina. To meet its fellow in the midline the intermediate part of the duct must pull away from the side wall of the pelvis and in so doing pulls a peritoneal fold with it; this fold becomes the broad ligament of the uterus. Therefore the broad ligament is the mesentery of the müllerian duct. In the male müller's duct almost entirely disappears,

with the exception of its cranial extremity which forms the prostatic utricle and the cephalic extremity, which form the appendix testis (sessile hydrotid). The wolffian duct only persists at its extremities in the female. At its cephalic end it forms longitudinal tubules of the paroophoron and the paroophoron. The transverse tubules of these vestigial bodies occupy the broad ligament in the vicinity of the ovaries. The caudal extremity of the wolffian duct may persist as a tubular remnant known as the duct of Gartner, which is embedded in the lateral wall of the cervix and the vagina.

The ovary originally is a retroperitoneal abdominal organ as is the testicle, but in the adult it becomes a pelvic organ. The gubernaculum of the ovary is attached caudally to the skin which later becomes the labium majus. In its course the gubernaculum becomes attached to the side of the uterus. In the male the gubernaculum testis passes through the inguinal canal and into the scrotum pulling with it a processus vaginalis and the testis. In the female the gubernaculum ovarii passes through the inguinal canal into the labium majus followed by a similar processus vaginalis which is called the canal of Nuck. As the ovary descends into the pelvis it draws its nerve and vascular supply across the external iliac vessels. In its fully developed state the gubernaculum in the female becomes the ligament of the ovary and the round ligament of the uterus (Fig. 436 A). These two ligaments are practically continuous at their site of uterine attachment which is just below the uterine tube. The round ligament of the uterus parallels the subperitoneal course taken by the vas deferens in the male; it crosses the side wall of the pelvis and the external iliac vessels then turns around the inferior epigastric artery passes through the inguinal canal and ends in the labium majus which is the homologue of the scrotum. The ovary may descend abnormally in such instances it follows the gubernaculum into the labium majus; this is known as an ectopic ovary.




FIG 433 Retropubic prostatectomy (A) The approach through the space of Retzius is indicated by the arrow (B) Exposure and mobilization of the gland (C) Enucleation and removal of the prostate (D) Appearance after removal of the gland (E) Closure




FIG 435 The six ligamentous supports of the female pelvic viscera (A) The broad, round ovarian infundibulopelvic uterosacral and Mackenrodt's ligaments are shown from behind. On the right the posterior leaf of the broad ligament has been removed to show the structure of the ligaments. (B) Transverse diagrammatic section to show the formation of Mackenrodt's ligament.

each other and form a free upper border which in the normal pelvis is more anterior than superior. The inner four fifths of the free upper border is occupied by the fallopian tube and the shorter lateral one fifth extends beyond the tube from the fimbriated end to the wall of the pelvis as the infundibulopelvic ligament. The two layers pass in opposite directions at their lines of attachment to the lateral pelvic wall and floor to become continuous with the general peritoneal lining of the pelvic cavity. Between the layers of the broad ligament the extraperitoneal connective tissue is located; this is the parametrium. In addition to the uterine tube the round ligament of the uterus, the ovarian ligament, the epoophoron and the uterine and the ovarian vessels also are found between the two layers of the broad ligament. Two secondary ligaments originate from it. Passing posteriorly is a fold the *mesovarium* which contains the ovary and the ovarian liga-

ment. The *mesosalpinx* is that portion of the broad ligament which lies immediately below the uterine tube between it and the ovary.

The *round ligaments* of the uterus are not duplications of peritoneum but are true ligamentous fibromuscular cords. They pass from the superolateral angle of the uterus to the internal inguinal ring representing the lower part of the gubernaculum; they are enclosed between the serous layers of the broad ligaments (Fig 436). Usually they raise a ridge on the anterior aspect of the broad ligament and occasionally may be accompanied by a persistent tubular prolongation of abdominal peritoneum known as the canal of Nuck. They pass horizontally and extend outward to the wall of the lesser pelvis, pass forward under the peritoneum and cross the obliterated hypogastric artery, the external iliac vessels and the psoas major muscle. They then cross the pelvic brim to reach the

THE SIX LIGAMENTOUS SUPPORTS

The six ligamentous supports of the female pelvic viscera are the broad, the round, the uterosacral, Mackenrodt's, the ovarian and the infundibulopelvic ligaments (Figs 435 and 436)

Each broad ligament of the uterus is a thick, mesenterylike fold which passes from the lateral margin of the uterus to the lateral wall of the pelvis. It is a structure of

great importance because of its relation to the uterine tube, the uterine and the ovarian vessels and the ovary. The two layers of the broad ligament are triangular in shape when placed on a stretch. Medially, its two layers separate to envelope the uterus, and inferiorly and laterally they separate to cover the floor and the side wall of the pelvis (Fig 439). Superiorly, these two layers become continuous with




FIG 434 Development of the female pelvic viscera (A) Two wolffian and two mullerian ducts are present (B) The wolffian ducts do not persist in the female (C) The cranial ends of the mullerian ducts become the fallopian tubes, the intermediate parts fuse to form the uterus and the caudal ends fuse and form the upper part of the vagina. In the female the wolffian duct persists only at its extremities, at its cephalic end the epoophoron and the paroophoron are formed, at its caudal end, the duct of Gartner may persist




FIG 437 The uterus as seen from above

responding utero acral ligaments. They are the bases of the broad ligaments. Blood vessels especially vein make up the chief components of this ligament. They are a condensation of parametrial tissue which helps suspend the cervix and the uterus to the pelvic walls (Fig 435 B). When the cardinal ligaments become stretched the uterus drops to a lower level.

The *ovarian ligament* is a rounded fibromuscular cord which is enveloped between the two layers of the broad ligament and may be seen through the peritoneum as it passes along a line separating the mesosalpinx from the mesovarium. It extends from the uterine (lower) pole of the ovary to the lateral aspect of the uterus here it is attached between the fallopian tube and the round ligament of the uterus. The ovarian and the round ligaments of the uterus together represent the gubernaculum of the ovary the entire cord being subdivided into ovarian and uterine parts (Fig 436 A).

UTERUS

The uterus is a pear shaped muscular organ which is intermediate in position between the bladder the rectum and the

broad ligaments (Figs 437 and 438). It is three inches long two inches at its widest part and one inch at its thickest part. It is flattened in front where it is in contact with the bladder but is convex behind. Its lower third is cylindrical but the remaining upper two-thirds widens gradually toward the free end. It is lined with mucous membrane and is invested partially by peritoneum. The uterine (fallopian) tubes enter at its widest part. The broad ligaments are attached to its side margins and the ligament of the ovary and the round ligament of the uterus are attached just below the tubes.

The uterus is divided into three parts a base or fundus a main portion the body or corpus and the larger lower prolongation known as the neck or cervix which projects into the vagina. The cervix is demarcated from the corpus by a slight constriction called the isthmus. The fundus and the body form the upper two inches and the cervix forms the lower inch.

The *fundus* is the dome shaped uppermost end which rises above the tubes. It is broad in its transverse diameter, and the fallopian tubes form a junction with it at its lateral margins. These junctions are




FIG 436 Ligamentous supports of the female pelvic viscera (A) The division of the gubernaculum into the ovarian and the round ligaments (B) The structures seen from above and in front The anterior leaf of the left broad ligament has been reflected forward

internal inguinal ring through which they enter the inguinal canal. Each round ligament leaves the external inguinal ring and terminates in the labium majus where it ends by breaking up into fine fibrous strands. The function of the round ligaments is to draw the uterus forward after it has been displaced backward by a pregnant uterus or a distended bladder. Once returned to its normal forward position the intra-abdominal pressure on the posterior surface of the uterus maintains its position. Should the round ligaments fail to function intra-abdominal pressure presses the fundus of the uterus downward and into the vagina. This in turn puts a greater strain on the other supporting ligamentous structures and results in prolapse of the uterus.

The *infundibulopelvic ligament* (suspensory ligament of the ovary) extends from the tubal end of the ovary to the lateral pelvic wall. It is the lateral one fifth of the broad ligament and is not occupied by the fallopian tube. It passes upward from the ovary, crosses the external iliac vessels and becomes lost in the fascia and

the peritoneum covering the psoas major muscle. The ovarian vessels and nerves travel in this ligament.

The *uterosacral ligaments* are two short, fibromuscular cords which pass backward from the posterior aspect of the upper end of the cervix on each side of the rectum and end in the sacrum. They lie directly in contact with the peritoneum and form ridges called recto-uterine folds in the lateral walls of the recto-uterine pouch. Following inflammatory conditions, these ligaments may shorten and overaccentuate the ante-flexion of the uterus. The function of the uterosacral ligaments is to hold the cervix up and back. If they fail to function (congenital weakness, loss of tone from pregnancies, etc.), the cervix is displaced downward and forward, this permits a backward displacement of the corpus so that the axis of the uterus and the vagina coincide. Intra-abdominal pressure then forces the uterus into the vagina (prolapse).

Mackenrodt's ligaments (cardinal or transverse cervical ligaments) are situated lateral to the cervix and the vagina, and are continuous on each side with the cor




FIG. 439 The attachments of the broad ligament.

The *cervix* is the narrower cylindrical segment of the uterus. It enters the vagina through the anterior vaginal wall and lies at right angles to it. Since it pierces the vagina it is divided into supravaginal and intravaginal (vaginal) portions (Fig. 438). The supravaginal part lies above the ring of vaginal attachment; it is covered with peritoneum posteriorly and is related to the intestines. Anteriorly it is separated from the bladder by fatty tissue and is connected laterally with the broad ligament and the parametrium which contains the blood vessels. The lower intravaginal (vaginal) portion is the free segment which projects through the vault of the vagina; it is covered with mucous membrane which has been reflected onto it from the upper part of the vaginal wall. The cervix opens into the vaginal cavity through the *external os*. The os has anterior and posterior lips which are normally in contact with the posterior vaginal wall; this wall ascends to a higher cervical level than does the anterior wall and thus envelopes the inferior third

of the cervix. In nulliparae, the os is a small transverse slit the lips of which are smooth and rounded; but in multiparae it is wider and the lips are quite irregular.

The *cavity of the uterus* is small when compared with the thickness of its wall. In sagittal section it is an elongated narrow cleft; but when viewed from in front it is triangular in shape with all of its sides being convex inward (Fig. 442). Its normal capacity is about three to eight cc. The base of the triangle is directed upward, and at its two upper corners it is continuous with the fallopian tubes; the apex of the triangle is directed downward where, at the constricted internal os (corresponding to the isthmus externally), it becomes continuous with the cervical canal. The mucous membrane of the cavity of the body of the uterus is smooth and velvety. The *canal of the cervix* is spindle shaped and about one inch long; it opens into the vagina at its lower end through the external os. The mucous membrane in the canal is raised into median longitudinal folds both in front




FIG 438 The uterus as seen in sagittal section. The organ is divided into three parts: a fundus, a corpus and a cervix.

called the cornua or horns. The *corpus* narrows as it approaches the cervix, and when inspected from the front, it appears to be triangular in shape. The anterior surface of the corpus, which has also been referred to as the ventral or inferior surface, is covered by visceral peritoneum, which is reflected to the upper surface of the bladder at the junction of the body and the cervix of the uterus. This reflection of peritoneum forms a potential space known as the utero-vesical pouch. The posterior (dorsal or superior) surface is covered by peritoneum which extends downward beyond the corpus to cover the cervix from which it is reflected to the front of the rectum. The space thus formed is known as the recto-uterine excavation (cul de sac of Douglas or Douglas' pouch). The lateral margins of the uterus extend from the fallopian tubes above to the uterosacral ligaments below,

they are devoid of peritoneum, since these margins give attachments to the diverging layers of the broad ligaments (Fig 439). The round ligament of the uterus is attached in front of the origin of the fallopian tube, and the uterine and the ovarian vessels are situated below and behind it. The ligament of the ovary is attached to the intestinal surface of the uterus, but the round ligament is attached to the vesical surface. These structures lie between the opposed layers of the broad ligaments as the latter pass toward the lateral pelvic walls. A fatty fibrous tissue fills the spaces between the broad ligaments. This tissue is called the *parametrium* and is most abundant near the cervix and the vagina, where it becomes continuous with the extraperitoneal tissue of the pelvic wall and floor.

and behind. Between these, in nulliparae, are secondary branching folds which pass upward and laterally. The treelike appearance has been called the arbor vitae (rugae or plicae palmatae), these folds usually are absent after the first pregnancy.

The body of the uterus is the most movable part, the cervix, although mobile, is held rather firmly at either side by fascial and ligamentous bands known as Mackenrodt's (cardinal) ligaments (p. 584).

In the virgin the uterus lies with its long axis almost parallel with the superior aperture of the true pelvis and almost at right angles to the long axis of the vagina. Therefore the fundus of the uterus is directed forward; this position is described as anteversion. Furthermore, the uterus is bent forward upon itself producing ante flexion. It also is rotated slightly on its own axis. The position varies greatly in different individuals and is subject to change, depending upon posture and the condition of the bladder and the rectum.

The structure of the uterus consists of three layers: an outer serous coat, a middle muscular coat, and an inner lining, the mucous membrane. The outer serous coat (perimetrium) is visceral peritoneum which consists of mesothelial cells; it is attached to the subjacent muscular coat through a thin layer of connective tissue. This attachment is firm over the fundus and the posterior part of the corpus but is much less firm over the posterior part of the cervix. The muscular layer is known as the myometrium and makes up the greater part of the organ. It consists of interlacing bundles of smooth muscle fibers which are united by connective tissue. These fibers increase in size and probably in number during the first half of pregnancy and they never regain their virginal size. The inner lining of mucous membrane is the endometrium; it is smooth and velvety and is about two to five mm in thickness. The epithelium is columnar in type and is firmly attached to the underlying myometrium. The endocervix also is a columnar epi-

thelium richly provided with compound racemose glands which secrete a clear mucous; this may fill the cervical canal and act as a protective plug against uterine infection.

Various developmental malformations of the uterus may take place. The two müllerian ducts normally fuse over those parts which form the uterus and the vagina (Fig. 434). The upper or tubal portions of the ducts retain their independence as the two fallopian tubes. The fused uterus and the vagina are at first partitioned by a median septum which disappears later, and the double uterine and vaginal canals become converted into a single cavity. The disappearance of this median partition occurs from the vulva upward, and the degree of its absorption may vary. Therefore, a partitioned vagina with a partitioned uterus (uterus didelphys), a completely developed single vagina and a partitioned uterus (uterus duplex), or a single vagina and a single uterus (uterus simplex) may result. Occasionally, the ducts remain separated throughout their entire length and then two entirely separate uteri and vaginae are found. The uterus may be divided, producing the bicornate uterus; the cervix may be either single or double. If one müllerian duct fails to keep pace with the other, any variety of asymmetry may result.

VAGINA

The vagina is a flattened but distensible musculomembranous canal which usually measures about three inches in length. It extends from the vulva, through the urogenital diaphragm and to the region of the recto-uterine pouch of Douglas (Figs. 438, 440 and 441). If followed from above downward, it passes forward through the fascia of the pelvis, between the borders of the two levators and, after passing through the urogenital diaphragm, opens onto the surface of the perineum between the labia minora (Fig. 440). Therefore, it lies partly in the pelvis and partly in the perineum. Its anterior wall is 3 inches long.




FIG. 442 The uterus ovaries and fallopian tubes (A) A section of the uterus has been removed so that the interior of the uterine cavity and the cervical canal can be seen (B) Transverse section through the ovary

nal iliac glands while some of those from the lower part drain into the sacral and the common iliac glands. Other glands are associated with lymph vessels from the anal canal and the vulva; they end in the superficial inguinal glands.

The vagina has four coats: (1) an external fascial coat of areolar tissue containing a plexus of veins; (2) a coat of nonstriated muscle; (3) a submucous coat of elastic areolar tissue which contains a dense plexus of veins so thin walled that it resembles erectile tissue; and (4) a mucous coat which is covered with stratified epithelium and is mucous only in name, for the vagina per se does not contain mucous glands. It is kept moist by mucous from the uterus.

UTERINE TUBES (FALLOPIAN TUBES)

The uterine tubes are the paired oviducts which convey the ovum to the uterus. Each is about four inches long a quarter of an inch wide, and is quite tortuous (Figs 442, 437, 439). They are found in the upper border of the broad ligaments which, therefore form a "mesentery" for the tube. Each tube emerges from the uterine wall

at the junction of the corpus and the fundus uteri. Its course is at first horizontally outward and then backward; it curls around the tubal end of the ovary and overlaps its medial surface (Fig. 435). It connects with the uterine cavity through the uterine ostium, and with the abdominal cavity through the abdominal ostium. The caliber of the latter is subject to great variation in different individuals. These four chief subdivisions are recognized (Fig. 442): (1) The interstitial part is a short portion which begins at the upper angle of the uterine cavity with which it connects by a minute ostium. It is that part which passes through the uterine wall (about one half inch thick) and appears externally at the cornu just above the uterine attachment of the round and the ovarian ligaments. (2) The isthmus is that medial inch of tube which is short and cordlike; it appears just outside of the uterus and runs a rather narrow but straight course. The lumen of the isthmus gradually increases and joins the ampulla. (3) The ampulla is that portion which is the widest and the longest subdivision of the tube; it appears to be convoluted. It




FIG 441 The vagina (A) Seen from in front and above. The arrow leads to the lateral fornix (B) The "H" shape of the upper part of the vagina seen in cross section

At a lower level the vagina is clasped by the inner borders of the levator ani muscles which form a "sphincter vagina", at its lowest part it is covered by the vestibular glands and the bulb of the vestibule.

The chief artery on each side is the vaginal artery, this replaces the inferior vesical artery of the male (Fig 448). It arises from the anterior division of the internal iliac artery and passes forward and medially on the levator ani to the vagina.

Further arterial blood is contributed by the uterine and the middle rectal arteries and by the artery of the bulb of the vestibule. The veins form networks in the submucous coat and on the surface. These networks are drained by veins accompanying the arteries. The lymph vessels from the upper part accompany the uterine lymph vessels to the external and the internal iliac glands, those from the middle part pass along the vaginal blood vessels to the inter-

ment, the mesovarium and the infundibulopelvic ligament

The blood supply is derived from the ovarian artery, a direct branch of the aorta, which arises just below the origin of the renal artery (Fig. 451). Unlike the corresponding artery in the male it does not pass through the internal inguinal ring, but turns medially over the pelvic inlet to enter the infundibulopelvic ligament of the ovary. Its branches reach the hilum by way of the mesovarium, but the terminal branches continue medially in the broad ligament to supply the uterine tube and the upper part of the uterus. It anastomoses with branches of the uterine artery. Several veins arise from the hilum of the ovary

but they unite to form a single or double ovarian vein. The right ovarian vein empties into the inferior vena cava, and the left joins the left renal vein. The lymph vessels follow the ovarian veins and end in the aortic lymph glands. The nerve supply is derived from the aortic and the renal plexuses (10 Th).

The structure of the ovary reveals two zones: a central medullary and an outer cortical layer or zone. The medullary zone is characterized by its numerous blood vessels within the connective tissue. The cortical layer besides containing connective tissue contains the essential glandular tissue in the form of graafian follicles in various stages of development.

is thin walled and dilatable and constitutes the most important part of the tube. It leads into the trumpet shaped expansion which is the infundibulum. (4) The infundibulum is funnel shaped, but the surface of the funnel is broken into numerous fingerlike processes called fimbriae, which give the free margin a fringed or ragged appearance.

From its uterine attachment to the fimbriated end the tube is enveloped by a superior fold of broad ligament, the *mesosalpinx*. The isthmus of the tube, which has a relatively short mesosalpinx, moves with the uterus, but the ampulla and the infundibulum with a comparatively long mesosalpinx, are nearly as mobile as the ovary.

In addition to an outer serous coat derived from the broad ligament, the tube is surrounded by a subserous layer and a muscle layer which is continuous with that of the uterus. The mucosa lining the tube is peculiar in that it is arranged in folds which are directed longitudinally. This mucous membrane is covered with a ciliated epithelium; the action of the cilia is supposed to create a stream of lymph from the peritoneal cavity into the mouth of the tube and along it to the uterus.

The arterial blood supply is derived from the tubal branches of the uterine and the ovarian arteries (Fig. 451). The lymph vessels drain to the thoracic glands with the vessels to the ovary and the fundus of the uterus. The nerve supply is derived from the uterine and the ovarian plexuses and ultimately from 11 and 12 Th and 1 L.

OVARIES

The genital gland of the female resembles a large almond in both size and shape. It projects from the posterior layer of the broad ligament which it draws outward to form the mesovarium (Fig. 442). It is covered with cuboidal epithelium not peritoneum. The mesovarium is usually short and attaches only to the anterior border of the ovary. The gland is smooth and pink

in young nulliparae but becomes gray and puckered in elderly women and in multiparae. This is due to the repeated discharge of ova through its surface and the resultant formation of puckering scars; in old women it becomes shrunken, wrinkled and atrophic. The ovary lies in the peritoneal depression on the side wall of the pelvis, the depression is bounded behind by the ureter and in front by the broad ligament. In the floor of this fossa the obturator vessels and nerves are found. At the first pregnancy, the broad ligament enlarges with the uterus and carries the ovary up into the abdomen proper. After childbirth, the organ returns to the pelvis but seldom regains its former position, it may be found in any location in the dorsal part of the pelvis. It also may be prolapsed deep into the cul de sac, where it can be palpated vaginally, lateral to or behind the cervix.

The ovary has two extremities and two surfaces. The tubal extremity, which is referred to as the upper pole, is rounded, faces superiorly and is embraced by the fallopian tube. The infundibulopelvic ligament (suspensory ligament of the ovary) attaches this pole to the peritoneum of the pelvic wall; it is derived from the upper and the lateral aspects of the broad ligament and contains the ovarian vessels. The fimbriae of the fallopian tube also are found at the upper pole of the organ. The lower (uterine) pole connects the ovary with the superolateral angle of the uterus by means of the ovarian ligament; it is about one quarter of an inch above the pelvic floor. The medial surface is directed inward and since it is overlapped to a great extent by the fallopian tube, only a small part of it is exposed to the eye. The lateral surface faces outward and is in direct contact with the parietal peritoneum of the pelvic wall where this layer is depressed to form the ovarian fossa. Although pregnancy may alter the position of the ovary in multiparae, it nevertheless remains anchored at three places: the ovarian liga-

attached to the lateral pelvic wall and the anteromedial aspect of the internal iliac artery. It crosses all the anterior branches of this artery, namely the obturator and the superior vesical arteries (Fig. 443). Medially this portion of the ureter approaches the posterior margin of the ovary which lies immediately anterior to the internal iliac artery; therefore the posterior boundary of the ovarian fossa is formed by the pars posterior of the pelvic portion of the ureter (Fig. 444 A). This part of the ureter is accompanied by the uterine artery which lies along its anterolateral surface (Fig. 441).

The *pars intermedia* of the pelvic portion of the ureter is that part which runs in Mackenrodt's ligament. It extends from its entrance into the ligament as far as the vesico-uterine ligament. In this ligament the ureter comes into close relationship with the cervix for a short distance, being about one and a half cm from it (Fig. 444 C). In the upper portion of its course the ureter is covered by the uterine artery and vein, but in its deepest portion these vessels cross it. In its intermediate portion it is difficult to isolate because it is surrounded on all sides by vessels, mostly veins (Fig. 444 B). Crudely, the deep uterine veins and the vaginal veins are found; medially there is the uterovaginal plexus which passes downward along the edge of the uterus and the vagina; laterally the anastomoses between the superficial and deep uterine veins appear. Although these vessels surround the ureter they do not directly touch it since the ureter travels in a preformed canal to which its adventitia is attached by loose connective tissue. Therefore in order to free this part of the ureter the dissection must be carried along the correct cleavage plane which is between the canal of the ureter and its adventitia. If this plane is found it is possible to dissect it without injury and unnecessary hemorrhage. The distance from the ureter to the cervix is not constant, the average being one half to one inch. It depends upon

the framework of vessels around the ureteral canal. If the anastomoses between the deep and the superficial veins are close to the edge of the uterus, the ureter lies near to the cervix. If the anastomoses are situated nearer to the pelvic wall the ureter is farther away. Lateral displacement of the uterus also alters the ureteral position. If the uterus is displaced to the right, then the right ureter lies nearer to the edge of the cervix and vice versa.

The *pars anterior* of the pelvic portion of the ureter extends from its entrance into the vesico-uterine ligament as far as the ureteral orifice of the bladder. The veins draining the vesical plexus lie lateral to and above the ureters. The vaginal plexus is caudad and forward toward the symphysis and the anterior vaginal wall is adjacent to it. Medially it is bounded by the vesico-vaginal space. As it passes forward in the vesico-uterine ligament it gradually turns upward and medially; it empties into the bladder about one and a half cm below the level of the anterior lip of the cervix (Fig. 444 C). This is a relationship which should be appreciated for at times a calculus in this portion of the ureter may be felt vaginally (Fig. 441 A). As the ureter (*pars intermedia*) travels through a sort of canal in Mackenrodt's ligament, so does the *pars anterior* course through a similar canal in the vesico-uterine ligament. The wall of the canal is attached to the ureter by a similar type of loose connective tissue.

The uterine artery is lateral to part one, runs across part two and is medial to part three of the ureter.

The Pelvic Part of the Ureter in the Male. This part of the ureter crosses the beginning of the external iliac artery, passes backward and downward along the lower border of the internal iliac (hypogastric) artery and reaches the level of the ischial spine (Fig. 446). At this point it curves forward and medial in the fat above the levator ani muscle and reaches the posterosuperior angle of the bladder. It

The Ureters

The ureters are expansile muscular tubes, whitish in appearance, which are approximately ten inches long and about one quarter of an inch in diameter. The iliopectineal line serves as a dividing point between the abdominal and the pelvic portions of the ureters. From above downward the ureter rests upon the genitofemoral (genitocrural) nerve, the common iliac vessels on the left side, and the external iliac vessels on the right side after passing downward on the internal iliac artery, it is related to the ligaments in the pelvis (Fig 443). As the ureter bends into the true pelvis the ovarian (testicular) vessels gradually diverge from it. The end of the abdominal portion of the ureter is separated from the iliopectineal line by the psoas muscle and the iliac vessels. On the right side it crosses the vessels at the point of bifurcation of the common iliac artery, but on the left side it crosses the common iliac about one to one and a half cm above its bifurcation. On the left side it bears a constant relationship to the sigmoid. It appears above the iliopectineal line at the apex of the intersigmoid fossa (Fig 443 B). On the right side the relation of the ureter to the intestine is less constant because of the variable position of the cecum and lower loops of the ileum. The ureters are placed behind the peritoneum to which they are loosely attached.

The *right ureter* is a little lateral to the inferior vena cava. Its pelvis is covered by the second part of the duodenum. Four sets of blood vessels cross in front of it, between it and the peritoneum (Fig 443 A). These are the right colic artery, the tes-

ticular (ovarian) artery, the ileocolic artery and the superior mesenteric artery in the root of the mesentery.

The *left ureter* is a little lateral to the inferior mesenteric vein. Its pelvis is more exposed than the right and, after appearing from behind the renal vessels, is covered only by the peritoneum. It is separated, as on the right side, at intervals from the peritoneum by the upper left colic, the testicular (ovarian) and two or more left colic vessels. Because of the vessels which cross the abdominal part of the ureter, the extra peritoneal lumbo inguinal approach is preferable to the transperitoneal one.

The pelvic part of the ureter is divided into three portions (Figs 444 and 445): (1) a pars posterior (in the uterosacral ligament), (2) a pars intermedia (in Mackenrodt's ligament) and (3) a pars anterior (in the vesico uterine ligament).

The *pars posterior* of the pelvic portion of the ureter begins at the level of the sacro iliac joint. At this point the ureters are separated by a distance of six to seven cm, a distance which corresponds roughly to the width of the middle of the sacrum (Fig 393). In this part of their course they form an arch, the convexity of which is directed laterad. After traveling about an inch they lie from 12 to 13 cm from each other, they reach the upper edge of Mackenrodt's ligament via the uterosacral ligaments (p 534). They next bend medially and, due to the position of the uterosacral ligament on the posterior surface of Mackenrodt's ligament they pass in an antero-inferior and medial direction into this ligament. This portion of the ureter remains




FIG 444 The three parts of the pelvic ureter (A) It is convenient to divide the pelvic portion of the ureter into three parts (1) a posterior part in the uterosacral ligament (2) an intermediate part Mackenrodt's ligament and (3) an anterior part in the vesico-uterine ligament (B) The intermediate part of the ureter is surrounded on all sides by vessels, mostly veins (C) The uterine artery is lateral to the first part, passes across the second part and is medial to the third part of the ureter

downward it lies in the fat above the levator ani muscle and beneath the peritoneum the vas deferens crosses above it between it and the peritoneum near the bladder. Near the bladder it is surrounded by a plexus of veins and is overlapped by the upper end of the seminal vesicle. It receives its blood supply from branches arising from the renal, the testicular, the colic, the vesical and the middle rectal arteries. Because of its great vascularity the ureter may withstand a considerable amount of surgical trauma, and large segments of it may be mobilized without sloughing. It is for

this reason that injury to it heals quickly. Its nerve supply is derived from the renal, the testicular and the hypogastric plexuses. The lymphatics end in glands nearest it in the abdomen and the pelvis.

The ureter is constricted in certain localities. The uppermost of these constrictions is about 55 cm from the kidney pelvis, the next at the brim of the pelvis where the ureter crosses the common iliac artery, and the third or lowermost just outside of the ureteral orifice. A ureteral calculus usually stops at one of these constrictions as it passes down the ureter.




FIG 443 The ureter (A) The ureters are shown in their entire courses and their anatomic relationships. Four vessels cross the right ureter—the right colic, the testicular (ovarian), the ileocolic and the superior mesenteric. (B) The relation of the left ureter to the intersigmoid fossa.

passes through the posterior wall of the bladder at an extreme oblique angle, running medially and downward. It opens into the bladder at the upper angle of an area called the trigone. As the ureter approaches the bladder, it is under cover of the closely adherent peritoneum and at times may be

seen shining through it. In the beginning of its course the internal iliac artery is above and behind it. Lateral to it are the psoas and the obturator internus muscles, the external iliac vein, the obturator nerve, the umbilical artery, and the obturator and the inferior vesical vessels. As the ureter turns




FIG 446 The ureter in the male, seen from the right. The vas deferens crosses above the ureter as it is overlapped by the upper end of the seminal vesicle.




FIG 447 Exposure of the right ureter. The illustration reveals a retroperitoneal approach. The peritoneum is retracted medially, and the relations to the surrounding vessels are demonstrated.

in the lateral decubitus and is well arched over a kidney rest or a sandbag. An adequate lumbo iliac incision is made. The incision begins about the middle of the twelfth rib and extends downward and forward to a midpoint between the center of the iliac crest and the anterior superior iliac spine. It then passes around the anterior iliac spine and continues forward and parallel with the inguinal ligament. The external and the internal oblique muscles and the transversus abdominis muscle are incised in the direction of the skin incision, the trans-

versalis fascia is incised and the extra peritoneal fat is exposed. The peritoneum is mobilized medially, and the ureter and the pelvic vessels are identified. The ureter normally remains adherent to the peritoneum when that structure is reflected toward the midline. Nevertheless, the ureter can be detached easily from the peritoneum to permit any surgical procedure or exploration which might be deemed necessary.




FIG 445 The ureter (A) The blood supply of the ureter is derived from the renal, the testicular, the colic, the vesical and the middle rectal arteries (Fig 445A) (B) The pelvic portion of the ureter showing its entrance into the bladder

SURGICAL CONSIDERATIONS

EXPOSURE OF THE URETER

It may be necessary to expose the ureter for excision, the removal of stones or for repair (Fig 447) A number of incisions have

been described (Fig 462), however, it is agreed that this structure is most readily approached by a retroperitoneal route The incision should be ample and allow for examination of not only the entire ureter but the kidney as well The patient is placed




FIG 448 The right internal iliac artery and its branches The uterus and the rectum have been pulled to the left and forward

skin The *superior gluteal artery* is the largest branch of the posterior division of the internal iliac artery and its course in the pelvis is short It passes downward and backward between the lumbosacral trunk and the first sacral nerve pierces the parietal pelvic fascia and enters the gluteal region via the upper part of the greater sciatic foramen above the piriformis muscle It travels with its vein and the superior gluteal nerve

The *anterior division* of the internal iliac artery gives rise to nine branches All of the posterior branches previously described are parietal but the anterior branches are both visceral and parietal The three parietal branches are the obturator the internal pudendal and the inferior gluteal, the six visceral branches are the umbilical, the superior vesical, the inferior vesical the middle hemorrhoidal the uterine and the vaginal

Neurovascular Structures

VESSELS AND LYMPHATICS

Most of the vessels supplying the structures within the pelvis lie in the extraperitoneal fatty tissue which intervenes between the peritoneum and the fascia. The nerves at first, lie outside of the fascia and are not only retroperitoneal but, like the muscles, are also retrofascial.

ARTERIES

The arteries of the pelvis are the internal iliac (hypogastric), the superior hemorrhoidal (rectal) which is the continuation of the inferior mesenteric, and the median sacral. The ovarian artery is an exception in that it does not arise within the true pelvis but originates from the aorta at the level of the kidneys (Fig. 451).

The *internal iliac artery* (hypogastric) is the largest artery in the true pelvis and gives rise to all the arteries of the pelvis except the superior hemorrhoidal, the median sacral and the ovarian (Figs. 448 and 449). It is a wide vessel smaller than the external iliac and is about $1\frac{1}{2}$ inches long. It arises as a terminal branch of the common iliac on the medial border of the psoas muscle, passes backward and downward across the medial surface of the psoas muscle and enters the pelvis. In its course it passes the sacro iliac joint and ends near the upper border of the greater sciatic notch by breaking up into anterior and posterior divisions which supply the exterior and the interior of the pelvis. Although it is narrower in the adult than the external iliac, it is twice as wide in the fetus because of its umbilical branch which passes to the umbilicus and the placenta. After birth,

the umbilical branch is patent to a point where the superior vesical arteries arise, and beyond this it becomes a fibrous cord called the lateral umbilical ligament. The ureter is in front of it, behind it lies its vein, and as it descends subperitoneally it crosses medial to the external iliac vein and obturator nerve (Fig. 448). At the upper border of the greater foramen, the artery divides into anterior and posterior divisions; the terminal branches from these divisions follow a pattern which is open to considerable variation.

The *posterior division* gives rise to the following three branches, all of which are parietal: the ilio lumbar, the lateral sacral and the superior gluteal (Fig. 448).

The *ilio lumbar artery*, located at the fifth lumbar segment, corresponds to a lumbar artery. It passes upward and laterally, first between the obturator nerve and the lumbo sacral cord and, secondly, between the psoas muscle and the spinal column. Opposite the pelvic brim the artery divides into an iliac and a lumbar branch, the former ramifying the iliac fossa and the latter ascending behind the psoas to send a spinal branch into the vertebral canal via the lumbosacral intervertebral foramen. The ilio lumbar vein does not descend into the pelvis with its artery but ends in back of the common iliac vein. The *lateral sacral artery* passes medially and downward in front of the sacral nerves, and each of them divides into two. Four arteries, therefore, pass through the anterior sacral foramina to nourish the structures in the sacral canal; they emerge through the posterior sacral foramina to supply the muscles on the back of the sacrum and the overlying

The *inferior vesical artery* is small in the male it arises a little below the obturator artery. It passes forward to reach the bladder and supplies the seminal vesicles the prostate and the posterior and inferior parts of the bladder. It gives off a long slender branch called the *artery of the vas deferens* which supplies and accompanies the vas as far as the testis.

The *aginal artery* replaces the inferior vesical artery of the male. It is larger than the latter and arises a little below the obturator artery descends and divides into branches which pass to the vagina other branches pass onward to the posterior and the lower parts of the bladder.

The *middle hemorrhoidal (rectal) artery* travels in a leash of veins that forms the posterior limit of the retroperic space. It usually arises from the internal pudendal artery but may arise with the inferior vesical. It passes medially to the rectum ramifies its walls and sends twigs forward to the vagina or to the seminal vesicles and the prostate gland. With the veins and a condensation of extraperitoneal areolar tissue it constitutes the rectal stalk or the lateral rectal ligament.

The *uterine artery* is a large vessel which arises near the lower end of the anterior division of the internal iliac. It may be divided conveniently into the following three parts: (1) descending (2) horizontal and (3) ascending (Fig. 431). The descending part represents its course on the lateral pelvic wall which corresponds to the posterior edge of the ovarian fossa. Since this part is associated with the parietal wall it is known as the parietal portion and it is here that the artery may best be isolated from its surrounding tissues. The horizontal part is the parametrial portion; it crosses the ureter and is related to Mackenrodt's ligament. This part may be subdivided into ureterolateral and ureteromesial portions, depending upon its relation to the ureter. The ascending part is the para-uterine portion; it extends upward along the edge of the uterus and with the

accompanying veins it forms a definite vascular cord in the parametrium. The first branch of the uterine artery is the ureteral branch which is given off where the artery crosses the ureter; it passes upward along the ureter. At or just after crossing the ureter a second uterine branch, the cervicovaginal artery, is given off. This branch supplies the posterior and the anterior walls of the cervix and the vagina; it lies within the cervical and the vaginal septa of the surrounding connective tissue. The uterine branches proper are given off from part three (ascending part). At the tubo-uterine junction the uterine artery divides into its four terminal branches: (1) The fundic branches which pass medially, penetrate the musculature of the uterus and supply the fundus. (2) The branch to the round ligament is the smallest branch; it passes forward beneath the tube at the cornu and accompanies the round ligament along its course in the inguinal canal. This vessel anastomoses with a branch from the inferior epigastric. (3) The tubal branch extends from the ligament of the ovary into the mesosalpinx and divides into cranial and caudal branches. The cranial branch extends along the underside of the tube within the mesosalpinx and supplies branches to both the tube and the ampulla. The caudal branch lies in the lower portion of the mesosalpinx near the hilus of the ovary and bends around the upper extremity of the ovary to reach the infundibulopelvic ligament where it anastomoses with the ovarian artery. The cranial and the caudal branches anastomose via small vessels which cross between the layers of the broad ligament. (4) The ovarian branch arises beneath the ligament of the ovary; it extends along the ventral side of the ligament, passes to the hilus of the ovary, gives off numerous branches and then joins the ovarian artery. The location of the uterine artery is important because of the great number of surgical procedures performed in this region. It is especially important where it crosses the ureter. This

The *obturator artery* passes forward and downward along the lateral wall of the pelvis and emerges through the obturator foramen above the obturator internus muscle. It is accompanied by its nerve and vein, the order from above downward, is nerve, artery and vein. Converging on the nerve and after passing through the upper part of the obturator foramen, it divides into lateral and medial branches which surround the obturator foramen lying between it and the obturator externus muscle. These branches encircle the outer surface of the obturator membrane, supply the obturator externus muscle and give an acetabular branch to the hip joint. An *abnormal obturator artery* when present is important in the surgery of femoral hernias (p. 814). The obturator and the inferior epigastric arteries each supply pubic branches, which are small and anastomose at the back of the pubis. In 30 to 35 per cent of cases, however the pubic branch of the inferior epigastric artery is large and replaces the obturator branch; it is called the *abnormal obturator artery* (Fig. 450). This apparently is attributable to an obliteration of the usual origin of the obturator artery. From its origin the abnormal artery descends into the true pelvis on the medial side of the external iliac vein and usually lies lateral to the femoral ring. If the artery is on the medial side of the ring and along the edge of the lacunar ligament, it is in a precarious location since cutting this ligament in a strangulated femoral hernia might sever the artery and result in profuse hemorrhage.

The *internal pudendal artery* travels a rather complicated course. It descends over the piriformis muscle and the sacral plexus in the interval between the piriformis and the coccygeus muscles. At this point the artery leaves the pelvis through the greater sciatic foramen and enters the buttock, where it rests upon the spine of the ischium with the pudendal nerve on its medial side and the nerve to the obturator internus on its lateral side, these are covered by the

gluteus maximus muscle. The artery then disappears through the lesser sciatic foramen and reaches Alcock's pudendal canal where it passes downward to gain access to the perineum (Fig. 338). It terminates by piercing the perineal membrane and divides into the deep and the dorsal arteries of the penis or the clitoris. It supplies inferior rectal, scrotal (labial), transverse perineal, bulbar, penile and clitoral branches.

The *inferior gluteal artery* is the terminal and largest branch of the anterior division. It passes downward and backward, pierces the fascia in front of the piriformis muscle and continues between the first and the second, or the second and the third sacral nerves. It leaves the pelvis through the lower part of the greater sciatic foramen and appears in the buttock between the piriformis and the gemellus superior. Its branches in the pelvis are only twigs to the surrounding structures.

The *umbilical artery* passes downward and forward along the side wall of the pelvis in front of the obturator nerve, it is in contact with the bladder when it is full but is some distance from it when it is empty. It proceeds upward from the bladder to the umbilicus, being covered by peritoneum. In the pelvis it is crossed by the ureter and the vas deferens (ligamentum teres in the female). It gives off the superior vesical artery beyond that point its lumen becomes obliterated and then it is known as the lateral umbilical ligament (Fig. 449 B). Under that name it ascends out of the pelvis in the extraperitoneal tissue of the anterior abdominal wall to reach the umbilicus. The umbilical artery has no accompanying vein, the umbilical vein which accompanies the fetal arteries in the umbilical cord leaves them at the umbilicus, continues to the liver and becomes the round ligament of the liver.

The *superior vesical arteries* may arise as two or three branches from the umbilical artery. They supply the superior aspect of the bladder and may give off the artery to the vas deferens.




FIG 451 The uterine artery. This vessel may be divided into three parts (1) descending (2) horizontal and (3) ascending. The tubes and the ovaries have been retracted outward to show the entire course of the uterine and the ovarian arteries.

crossing is near the level of the internal os about one or two cm from the lateral border of the cervix. At this point the ureter may be injured when the artery is ligated.

The *ovarian artery* is homologous to the internal spermatic artery in the male. It arises from the aorta below the origin of the renal artery and passes downward and laterally on the posterior abdominal wall (Fig 451). Unlike the corresponding artery in the male, it does not pass to the deep

inguinal ring but turns medially over the pelvic inlet, coursing over the psoas muscle and crossing the external iliac vessels. It enters the infundibulopelvic ligament and reaches the ovarian hilus by way of the mesovarium. Its terminal branches continue medially in the broad ligament and supply the tube and the upper part of the uterus. It anastomoses freely with branches of the uterine artery. This vessel also crosses the ureter but in a different




FIG 449 The right internal iliac artery (A) Relations of the prostate and bladder (B) The middle hemorrhoidal vessels form the posterior boundary of the prevesical space




FIG 450 The normal and the abnormal obturator arteries (A) normal, (B) abnormal

surrounds the ovarian artery in the pelvis. It accompanies this artery in the abdomen and ends on the left side in the left renal vein; on the right side it passes directly into the inferior vena cava. In the male, the *testicular vein* arises from the pampiniform plexus at or near the deep inguinal ring and accompanies the artery into the abdomen. The left testicular vein ends in the left renal vein and the right ends in the inferior vena cava a little below the level of the renal vein. Many believe that this arrangement of the left testicular vein predisposes this side to the formation of varicoceles.

The *medial sacral vein* is formed from the junction of the vena comitantes which travel with the median sacral artery. This vein usually passes along the right side of the artery and ends in the left common iliac vein.

The *inferior vena cava* is formed by the junction of the two common iliac veins on the right side of the fifth lumbar vertebra (Fig. 453). It ascends along the right side of the abdominal aorta and continues upward in a groove on the posterior surface of the liver. It perforates the diaphragm between the right and the median portions of its central tendon. After inclining forward and medially for about an inch, it pierces the fibrous pericardium, passes behind the serous pericardium and opens into the lower and the back part of the right atrium. The relations of the abdominal portion of the inferior vena cava are as follows. *In front* from below upward it is related to the right common iliac artery, the mesentery, the right internal spermatic artery, the inferior part of the duodenum, the pancreas, the common bile duct, the portal vein and the posterior surface of the liver which partly overlaps and occasionally surrounds it completely. *Behind* it is in relation with the vertebral column, the right psoas major muscle, the right diaphragmatic crus, the right inferior phrenic, suprarenal, renal and lumbar arteries, the right sympathetic trunk and

the right celiac ganglion and the medial part of the right suprarenal gland. Relations on the *right side* are with the right kidney and ureter, on the *left side*, with the aorta, the right diaphragmatic crus and the caudate liver lobe.

THE LYMPHATICS

The *lymph glands* and the *lymph vessels* of the female pelvis occupy rather constant positions (Fig. 454). The afferent lymph vessels from the skin and the subcutaneous tissue of the perineum, with the superficial afferent vessels from the inferior extremity, drain into a small group of lymph glands which are situated on either side of the upper part of the great saphenous vein. This group is known as the *superficial subinguinal glands*. An adjacent group of glands, the *superficial inguinal glands*, about 10 to 20 in number, are situated just below the inguinal ligament and also receive perineal vessels including those from the anus and the vulva. Into this latter group, the afferent lymphatics of the abdominal wall below the level of the umbilicus also pass. The efferent vessels from both groups (superficial inguinal and superficial subinguinal) converge toward the saphenous opening in the deep fascia of the thigh; through this they drain into the *deep subinguinal glands*. This group usually numbers about three or four glands and is situated on the medial side of the femoral vein; they receive afferent vessels from the clitoris and associated structures. The highest gland in this group has been called the gland of Rosenmüller or the *node of Cloquet*. It is located in the femoral ring; should it become inflamed it might be mistaken for a strangulated femoral hernia. The group as a whole is continuous with an extensive chain of parietal pelvic glands which are related to the common iliac artery and its branches. These iliac glands have been subdivided into three groups: the external iliac, the internal iliac (hypogastric) and the common iliac. All

direction than the uterine artery. It crosses at an acute angle at the entrance of the true pelvis where it lies in front of the ureter. distal to this point the ovarian artery and the ureter separate. The vessel proceeds along the lateral border of the ureter until the latter dips into the true pelvis at the terminal line.

VEINS

The chief veins of the pelvis are the two internal iliac veins and their tributaries. Besides these there are the superior hemorrhoidal (rectal) and the median sacral veins, and in the female there is a pair of ovarian pampiniform plexuses (Fig. 452). The veins of the pelvis are thin walled, accompany the arteries and anastomose freely thus forming many venous plexuses on and in the walls of the viscera from which the visceral veins arise. These plexuses are the rectal, the vesical, the prostatic, the uterine and the vaginal. They are not closed systems but since they anastomose freely the plexus of one organ communicates with the plexus of a neighboring viscus. It has been stated that the pelvic viscera lie within a basket woven of large, thin walled venous plexuses among which the arteries thread their way.

The *internal iliac vein* is the widest vein of the pelvis. It is short and is formed by the confluence of the *venae comitantes* of the superior gluteal artery and most of the veins that accompany the other branches of the internal iliac artery. It commences immediately above the greater sciatic foramen, passes forward and slightly upward out of the pelvis and ends on the medial surface of the psoas muscle. It joins the external iliac vein to form the common iliac vein. The internal iliac artery is below and in front of it and the sacroiliac joint and the lumbosacral trunks are above and behind it. Medially it is separated from the intestines by peritoneum and laterally it is related first to the pelvic wall and the obturator nerve and then to the psoas muscle (Fig. 340).

The veins of the uterus constitute one of the most important of the plexuses. The *uterine plexus* completely encircles the ascending portion of the artery and continues downward along the sides of the vagina as far as the external genitalia. The uterovaginal plexus lies enclosed in the compact connective tissue of the cervical and the vaginal septa as it continues upward to the edge of the uterus. These veins like the vaginal, are chiefly on the sides of the organ where they surround the nutrient arteries. They arise in the cavernous venous spaces in the uterine wall and leave the lateral aspect of the organ at about the level of the cervix. Here, they form a plexus which surrounds the ureter. The uterine veins anastomose with those of the vagina to form the uterovaginal plexus. The trunks from this plexus converge into the internal iliac vein or into one of its main tributaries. The vaginal venous plexus is massed at the sides of the vagina and communicates with the vesical, the rectal and the uterine plexuses. A vaginal vein arises on each side and accompanies the vaginal artery to the internal iliac vein.

In the female the *vesical venous plexus* lies on the surface of the bladder. It is densest around the neck and the upper part of the urethra, where it receives the dorsal vein of the clitoris. It drains into the vaginal plexus. In the male, the plexus lies on the surface of the bladder, chiefly below, behind and around the seminal vesicles. It empties into the internal iliac vein by large vesical veins that accompany the inferior vesical artery.

The *prostatic venous plexus* is a dense network that lies on the front and the sides of the prostate between its capsule and its fascial sheath (Fig. 427). Anteriorly, it receives the deep dorsal vein of the penis and superiorly it is continuous with the vesical plexus into which its blood is drained. The rectal venous plexuses have been discussed elsewhere (p. 340).

The *ovarian vein* arises at the pelvic brim from the pampiniform plexus, which




FIG. 454 The lymphatic system of the female pelvis

guinal group. The majority of the lymph vessels from the fundus and the cervix of the uterus pass laterad in the broad ligament and become continuous with the ovarian lymph vessels which ascend with the ovarian blood vessels to the aortic glands. Some of these however may pass to the hypogastric and the other iliac groups. The efferent vessels of the fallopian tubes join those of the uterus and the ovaries. The vessels from the rectum pass upward to glands of the sigmoid mesocolon and then to the aortic group. Those from the anal canal end in the hypogastric glands and those from the anus pass forward with those of the perineum to the inguinal group. Malignant neoplasms of the female genital tract drain into the iliac and the aortic glands and therefore are not palpable superficially. Cancerous processes which affect the vulva, the perineum, the anus and the lowermost portions of the vagina may cause easily felt enlargements

of the superficial inguinal glands. There is, however, a rare exception to this rule, since lymph drainage from the fundus of the uterus may travel along the lymphatics of the round ligament through the inguinal ring and to the superficial inguinal glands. Since the surgery of cancer is the surgery of the lymph drainage, it is important to visualize this system when attempting to do a radical removal of cancer and its extensions.

SURGICAL CONSIDERATIONS

LIGATION OF THE INFERIOR VENA CAVA

The inferior vena cava may be approached and ligated either transperitoneally or extraperitoneally (Fig. 455). The collateral circulation has been discussed in another chapter. The *transperitoneal operation* is accomplished through a lower right rectus incision which extends from the symphysis to well above the umbilicus.




FIG 452 The veins of the pelvis. These veins anastomose freely and form many venous plexuses on and in the walls of the pelvic viscera.




FIG 453 The inferior vena cava.

of these connect by numerous anastomoses. Their efferent vessels pass upward to a group of lumbar glands which, because of their position in relation to the abdominal aorta, are called the pre-aortic, the retro-aortic and the lateral aortic glands. The efferent vessels of these glands end in the cisterna chyli of the thoracic duct opposite the second lumbar vertebra.

The lymph vessels of the pelvic organs end mainly in the hypogastric and the iliac glands, but a small number may travel to the aortic and a few may reach the inguinal glands. Those from the bladder pass to the external iliac, the hypogastric and the common iliac glands, and those from the urethra and the intrapelvic part of the ureter drain directly into the hypogastric group. The efferent lymph vessels from the cervix and the major portion of the vagina drain with those of the urinary bladder into the three groups of pelvic glands. Those from the lowermost part of the vagina, however, descend to join those of the vulva and pass to the superficial in

The collateral circulation is carried out in the following way

1 Communication between the two internal iliac arteries

2 Communications between the internal iliac artery and the inferior mesenteric

vessels also anastomose with the anterior abdominal wall vessels above

This operation may be done either through a transperitoneal or an extraperitoneal route

The *transperitoneal* operation is con




FIG 456 The extraperitoneal approach to the common iliac artery (A) The incision extends from the eleventh rib to an inch above and parallel with the inguinal ligament (B) The peritoneum is pushed forward and medially, and the vessel is isolated

The ureter lies anterior the vein behind and the lumbo-sacral trunk still more posterior

The operation is similar to the one described for ligation of the common iliac artery

Ligation of the External Iliac Artery

The indications for this operation are usually femoral aneurysm and hemorrhage from the femoral artery or its branches

The collateral circulation takes place in the following way

1 Branches of the internal iliac artery above anastomose with branches of the external iliac artery below

2 Arteries of the anterior abdominal wall above anastomose with branches of the inferior epigastric artery below the femoral the superficial epigastric the circumflex iliac and the external pudendal

ducted through a vertical low rectus incision with the patient in high Trendelenburg position The intestines are packed off and the peritoneum overlying the vessel is incised the ligature is passed preferably from within outward so that the ureter which crosses the artery near its origin can be avoided The vein is located to the medial side of the artery On the left side the mesocolon overlies the artery

The *extraperitoneal* operation is done through a similar incision described above for exposure of the common or the internal iliac artery When the peritoneum is reached, it is wiped medially until the artery is exposed The femoral nerve lies lateral, the external spermatic branch of the genitofemoral nerve anterior and the vein posterior to the artery above but medial to it below

LIGATION OF THE ILIAC VESSELS

Ligation of the Common Iliac Artery

The indications for this operation are injury, aneurysms of the external iliac artery or preliminary to amputations about the hip joint

The collateral circulation takes place in the following ways

- 1 The inferior mesenteric artery above anastomoses with the visceral branches of the internal iliac artery below

- 2 The ovarian artery above anastomoses with the uterine and the vesical arteries below

- 3 The middle sacral artery above anastomoses with the lateral sacral branch of the internal iliac artery below

- 4 The internal mammary, lower intercostal and lumbar arteries above anastomose with the inferior epigastric below

The operation may be done either intraperitoneally or extraperitoneally. The *intrapertoneal method* is done with the patient in the *high Trendelenburg position*. A low rectus incision is used. The bowel is packed off and retracted so that the posterior parietal peritoneum is exposed and opened over the artery. The veins lie behind the artery on the right side, but behind and medial on the left. The vessel is doubly ligated, and at times severed. The peritoneum is sutured.

The *extraperitoneal method* usually is done through an incision about an inch above and parallel with the inguinal ligament. It extends upward to the tip of the eleventh rib (Fig 456). The abdominal muscles are divided, the peritoneum is exposed and is pushed forward and medial until the vessel is located. The inner border of the psoas major muscle is used as the chief muscular guide.

Ligation of the Internal Iliac (Hypogastric) Artery This is done for malignant growths in the pelvis which produce hemorrhage for gluteal aneurysm and at times for excision of the rectum.




FIG 455 Ligation of the inferior vena cava

biliacus (Fig 455 A). The peritoneal reflection is incised along the paracolic gutter of the cecum and the ascending colon which are reflected medially to the midline. The right ureter and the right ovarian vessels are identified. It is best to ligate the right ovarian veins and artery. The vena cava is identified easily and is doubly ligated about the level of the fourth lumbar vertebra. The cecum and the ascending colon are replaced into their normal positions, and peritonization is accomplished.

The *extraperitoneal approach* may be accomplished through a lateral incision similar to that used in lumbar sympathectomy. The inferior vena cava is identified easily; great caution should be used when ligating this vessel because of possible injury to lumbar veins. These latter veins are four in number on either side of the vena cava, and may be injured while passing the ligatures under the major venous trunk. Injury to these veins obscures the field and makes structure identification most difficult. This type of hemorrhage is hard to control and may result in annoying hematomas.




FIG 458 The sacral plexus (A) seen from in front (B) seen from behind (C) relations to musculature

muscle to join L 5 thus forming the lumbo-sacral cord or trunk. This nerve is joined by S 1 and the resulting broad nerve cord is further joined by S 2 and part of S 3. It lies in front of the piriformis muscle and behind the parietal pelvic fascia. The piriformis muscle separates the sacral plexus from the lateral part of the sacrum. Anteriorly, it is covered by the parietal pelvic fascia which separates it from the internal iliac (hypogastric) vessels above and

from their lateral sacral, inferior gluteal and internal pudendal branches below. Still more anteriorly the rectum is related to the lower part of the plexus. The branches of the plexus are the following:

- 1 The superior gluteal nerve (L 4, 5 and S 1) passes backward above the piriformis into the gluteal region. It supplies the gluteus medius and minimus and the tensor fasciae latae muscles.

- 2 The inferior gluteal nerve (L 5 and

NERVES

The autonomic nerves below the bifurcation of the aorta where the intermesenteric nerves join to form the *superior hypogastric plexus*, is known to the surgeon as the *presacral nerve* (Fig 457). This plexus or

the vagina, the urethra and the urinary bladder. In the lower lumbar and upper sacral areas, the three hypogastric plexuses are situated deep in the retroperitoneal connective tissue. The autonomic nerve trunk of the superior and the middle hypogastric




FIG 457 The superior hypogastric plexus (presacral nerve)

nerve supplies the bladder, the rectum and the internal genitalia except the ovary and part of the fallopian tube.

As these fibers pass caudally they diverge and form the bilateral inferior hypogastric plexus (hypogastric nerve). Between the superior and the inferior plexuses a rather inconstant middle hypogastric plexus may be present in front of the promontory of the sacrum. The inferior hypogastric plexus fibers pass downward and laterad then forward over the lateral surface of the ampulla of the rectum to join the pelvic plexus (Frankenhauser). The nervi erigentes also add other fibers to the pelvic plexus. The plexus is quite large and supplies the rectum, the anal canal, the uterus

plexuses is located a little to the left of the midline. This is an important relation, helpful in the operation of presacral neurectomy. The autonomic fibers which supply the ovary are not derived from the sacral ganglion nerves but arise from the renal and the aortic plexuses. They accompany the ovarian vessels as they pass in the suspensory ligament of the ovary.

The muscles which form the walls and the floor of the pelvis minor receive their innervation from the ventral divisions of the last lumbar nerve and the sacral nerves.

The *sacral plexus* is formed by L 4 and 5 and S 1, 2, 3 and 4 (Fig 458). The portion of L 4 which does not join the lumbar plexus runs downward medial to the pos-

In 1937 Livingston stated that the variations in this structure are so common that it is ridiculous to state that given ganglia were removed. Atlas stated that the fusion of the lumbar sympathetic tissue is so er

the right side in 9 instances nor on the left side in 6 instances in 4 other instances a ganglion could not be found on either side of the first lumbar vertebra. They further reported that the number of lumbar ganglia




FIG. 460 The lumbar sympathetic nervous system (after Yaeger and Cowley). This has been shown to be one of the most variable portions of the sympathetic nervous system in the human body. (A) Four ganglia rather symmetrically placed on both sides in corresponding positions to the lumbar vertebrae. This is usually described as the typical arrangement but has been found to be the most atypical. (B) No ganglia are noted on either side of L 1 and almost all of L 2. Three ganglia appear on either side. (C) No ganglia appear overlying L 1 on either side or below the level of L 3 on the left. (D) The rami radiate in all directions and there are intercommunications between the right and the left trunks.

ratio that it is impossible to designate lumbar ganglia on a numerical basis. Yaeger and Cowley made a series of 19 anatomic studies. They could not find a sympathetic ganglion on the first lumbar vertebra on

ranged from 2 to 5 the average on each side being 3. The rami to a ganglion varied from 2 to 7 no two chains were similar in their entire series and no pattern of variation could be established. The direc




FIG 459 The pudendal nerve

S 1 2) passes backward below the piriformis and supplies the gluteus maximus muscle

3 The nerve to the quadratus femoris (L 4 5 and S 1) enters the gluteal region below the piriformis

4 The nerve to the obturator internus (L 5 and S 1, 2) travels in company with the internal pudendal vessels and enters the gluteal region below the piriformis muscle

5 The posterior cutaneous nerve of the thigh (S 1 2 3) passes below the piriformis muscle and enters the gluteal region behind the sciatic nerve

6 The sciatic nerve (L 4 5 and S 1 2 3) constitutes the continuation of the nerve cord which has been formed within the pelvis. It leaves the pelvis through the lower part of the greater sciatic foramen

7 The pudendal nerve (S 2 3 4) is accompanied by the internal pudendal vessels and the nerve to the obturator internus (Fig 459). It passes through the

greater sciatic foramen between the piriformis and the coccygeus muscles to gain entrance to the ischiorectal fossa. It divides into three branches: (1) the inferior hemorrhoidal nerve, (2) the perineal nerve and (3) the dorsal nerve of the penis (clitoris).

8 The nerve to the piriformis (S 2, 3) is a branch of the plexus

9 The pelvic splanchnics (S 2, 3, 4) form a group which runs forward on the levator ani muscle and joins the branches of the pelvic plexus on the walls of the pelvic viscera. Small ganglia are situated at the points of this junction; they are distributed to the pelvic viscera and constitute the sacral part of the parasympathetic system

10 The perforating cutaneous nerve (S 2, 3) runs between the adjoining borders of the coccygeus and the levator ani muscles and supplies the skin of the lower and the medial parts of the buttock.

The coccygeal plexus is formed by part of S 4 and the whole of S 5 plus the coccygeal nerve. It lies on the pelvic surface of the coccygeus muscle and supplies muscular branches to the levator ani, the coccygeus and the external sphincter m. After being joined by S 5 the coccygeal nerve pierces the coccygeus muscle and supplies the skin in the neighborhood of the coccyx.

THE LUMBAR SYMPATHETIC CHAIN

After a rather thorough study of the anatomy of the lumbar sympathetics, Yeager and Cowley have come to the conclusion that this chain is the most variable portion of the entire sympathetic system and one of the most variable structures in the human body (Fig 460). With this in mind, one should not look upon the lumbar sympathetic chain as it is usually presented in diagrams, namely as a ganglion resting on the body of each of the first four lumbar vertebrae on the right and the left sides




FIG 463 Lumbar sympathectomy (transperitoneal approach) (A) Exposure through a low rectus incision (B) Incision into the posterior parietal peritoneum lateral to the inferior vena cava for exposure of the right lumbar sympathetic chain (C) Incision into the posterior parietal peritoneum placed lateral to the sigmoid for exposure of the left lumbar sympathetic chain

Oschner and DeBakey have done much to popularize and standardize it. The procedure may be performed either in the lateral decubitus or with the patient in the prone position. Intracutaneous wheals are made approximately two fingersbreadth lateral to the spinous processes of the first, second, third, and fourth lumbar vertebrae

(Fig 461). A needle is inserted vertically through each wheal until it reaches the transverse process of the corresponding vertebra. Then the direction of the needle is changed, either superiorly or inferiorly and toward the midline. The needle can be advanced another two fingersbreadth so that its point comes to lie against the lateral




FIG 461 Lumbar sympathetic block. Diagrammatic presentation of the injection of the lumbar sympathetic chain. The arrow indicates the change in direction of the needle after it comes into contact with the left transverse process.

tion of the rami varied from cephalad to transverse to caudad. Therefore it is to be concluded that the identification of a specific ganglion is unreliable according to the direction of its rami. The most constant and largest of the lumbar ganglia and hence the most easily identified even by palpation was found to be associated with the second lumbar vertebra, usually at its lower end. If a ganglion is present at the first lumbar vertebra, it usually is not seen be-


cause it is covered by the medial lumbo-costal arch. The sympathetic tissue overlying the fourth lumbar vertebra usually is obscured by the common iliac vessels.

SURGICAL CONSIDERATIONS

LUMBAR SYMPATHETIC BLOCK

This procedure has become quite popular in the treatment of thromboembolic phenomena of the inferior extremities.

FIG 462 Lumbar sympathectomy (retroperitoneal approach). (A) The incision extends from the twelfth rib to the brim of the pelvis. (B) The peritoneum has been retracted forward and the lumbar sympathetic chain is found in a gutter formed by the psoas muscle and the lumbar vertebrae.






FIG 465 Subtotal (supravaginal) hysterectomy (A) The lower midline incision extends to the left of the umbilicus if necessary (B) The round ligaments are severed and tied, and a peritoneal (vesical) flap is formed (C) The tubes and the ovarian ligaments are severed and tied (D) Clamps bite into and slide off of the cervix in this way the uterine vessels are secured (E) The uterine vessels are severed, and the cervix is coned and cut across (F) Peritonization




FIG 464 Presacral neurectomy (A) Incision (B) An incision has been placed into the posterior parietal peritoneum at the bifurcation of the aorta. The nerves are severed and dissected downward.

surface of the body of the vertebra in the retroperitoneal space. Usually one per cent procaine solution is injected.

LUMBAR SYMPATHECTOMY

This operation has been recommended for vasospastic conditions of the lower extremities, for megacolon, hyperhidrosis, and chronic ulcers. It may be done either extra-peritoneally or transperitoneally.

The *retroperitoneal approach* can be accomplished through one of many skin incisions. A commonly used incision begins at the lower border of the twelfth rib at the outer edge of the sacrospinalis group of muscles and extends downward parallel with the muscles to the crest of the ilium; it then curves forward along the brim of the pelvis for about five or six inches (Fig 462 A). The lumbodorsal fascia is divided and the oblique and the transverse abdominal muscles are separated from the sacro-

spinalis and the quadratus lumborum muscles. Between the peritoneum and the transversalis fascia, the iliohypogastric and the ilioinguinal nerves usually are identified and protected. The abdominal muscles are cut along the iliac crest. The peritoneum is separated from the quadratus lumborum and the iliopsoas muscles by blunt dissection; the ureter is identified, and the peritoneum and the overlying viscera are retracted toward the midline (Fig 462 B). The removal of the second, the third and the fourth lumbar ganglia with their connecting trunks is similar to that described in the next paragraph.

The *transperitoneal approach* utilizes a lower rectus incision; the patient is placed in the Trendelenburg position, and the intestines are packed into the upper abdomen (Fig 463 A). The lateral peritoneal attachment is incised on the left and the sigmoid with its mesentery, is reflected toward the midline (Fig 463 C). This exposes the left sympathetic chain; the ureter, the aorta and the left common iliac artery are identified and protected. The genitofemoral nerve usually is seen extending obliquely downward over the psoas muscle. The ganglia lie just beneath the edge of the aorta in the gutter between the psoas muscle and the vertebrae. The approach to the right lumbar ganglionated chain is similar to that on the left but the incision is made lateral to the inferior vena cava and continues downward over the right common iliac vein and into the pelvis (Fig 463 B). The small intestines, the cecum, the ascending colon and the ureter are retracted to the right. The nerve trunk on this side bears the same relation to the vena cava and the common iliac vein that it bears to the aorta and the common iliac artery on the left. The vena cava is retracted to the left. Lumbar veins overlying or beneath the sympathetic trunk may be injured during exposure and obscure the field. To dissect the chain it is best first to locate the fourth lumbar ganglion. It lies beneath the margin of the left common iliac artery and near




FIG 465 Subtotal (supravaginal) hysterectomy (A) The lower midline incision extends to the left of the umbilicus if necessary (B) The round ligaments are severed and tied, and a peritoneal (vesical) flap is formed (C) The tubes and the ovarian ligaments are severed and tied (D) Clamps bite into and slide off of the cervix, in this way the uterine vessels are secured (E) The uterine vessels are severed, and the cervix is coned and cut across. (F) Peritonization




FIG 464 Presacral neurectomy (A) Incision (B) An incision has been placed into the posterior parietal peritoneum at the bifurcation of the aorta. The nerves are severed and dissected downward.

surface of the body of the vertebra in the retroperitoneal space. Usually one per cent procaine solution is injected.

LUMBAR SYMPATHECTOMY

This operation has been recommended for vasospastic conditions of the lower extremities, for megacolon, hyperhidrosis, and chronic ulcers; it may be done either extra-peritoneally or transperitoneally.

The *retroperitoneal approach* can be accomplished through one of many skin incisions. A commonly used incision begins at the lower border of the twelfth rib at the outer edge of the sacrospinalis group of muscles and extends downward parallel with the muscles to the crest of the ilium; it then curves forward along the brim of the pelvis for about five or six inches (Fig. 462 A). The lumbodorsal fascia is divided, and the oblique and the transverse abdominal muscles are separated from the sacro-

spinalis and the quadratus lumborum muscles. Between the peritoneum and the transversalis fascia, the iliohypogastric and the ilioinguinal nerves usually are identified and protected. The abdominal muscles are cut along the iliac crest. The peritoneum is separated from the quadratus lumborum and the iliopsoas muscles by blunt dissection; the ureter is identified, and the peritoneum and the overlying viscera are retracted toward the midline (Fig. 462 B). The removal of the second, the third, and the fourth lumbar ganglia with their connecting trunks is similar to that described in the next paragraph.

The *transperitoneal approach* utilizes a lower rectus incision; the patient is placed in the Trendelenburg position and the intestines are packed into the upper abdomen (Fig. 463 A). The lateral peritoneal attachment is incised on the left, and the sigmoid with its mesentery, is reflected toward the midline (Fig. 463 C). This exposes the left sympathetic chain; the ureter, the aorta, and the left common iliac artery are identified and protected. The genitofemoral nerve usually is seen extending obliquely downward over the psoas muscle. The ganglia lie just beneath the edge of the aorta in the gutter between the psoas muscle and the vertebrae. The approach to the right lumbar ganglionated chain is similar to that on the left, but the incision is made lateral to the inferior vena cava and continues downward over the right common iliac vein and into the pelvis (Fig. 463 B). The small intestines, the cecum, the ascending colon, and the ureter are retracted to the right. The nerve trunk on this side bears the same relation to the vena cava and the common iliac vein that it bears to the aorta and the common iliac artery on the left. The vena cava is retracted to the left. Lumbar veins overlying or beneath the sympathetic trunk may be injured during exposure and obscure the field. To dissect the chain it is best first to locate the fourth lumbar ganglion. It lies beneath the margin of the left common iliac artery and near

the aortic bifurcation. It is grasped with a hemostat and freed from the surrounding areolar tissue and sympathetic rami. The trunk is dissected and severed above the second lumbar ganglion. The connecting sympathetic trunk is removed with the ganglia.

PRESACRAL (SUPERIOR HYPOGASTRIC) NEURECTOMY

This operation has been done for intractable pain in the uterus, the bladder of the rectum, and for the relief of spasms of the bladder resulting from spinal cord disease or injury. Removal of the presacral nerves usually causes the loss of power of ejaculation, but the powers of erection and orgasm is not impaired.

The operation is done through a low rectus incision (Fig. 464 A). The intestines are picked upward, and the bifurcation of the aorta is sought. The posterior peritoneum is incised above the aortic bifurcation and the peritoneal margins are carefully dissected laterally and retracted (Fig. 464 B). The superior hemorrhoidal vessels (inferior mesenteric) if visible usually are retracted to the left and the presacral nerves are exposed where they lie in the loose connective tissue in this area. The hollow of the sacrum between the common iliac arteries lodges the continuation of these nerves. At times it may be necessary to ligate the middle sacral artery. The left common iliac vein lies medial to the artery and should be protected during this entire procedure. As a rule the right ureter is exposed. The nerves are picked up as they cross the aortic bifurcation and are freed

downward. The communicating rami are severed and the entire plexus is removed. All primary fibers should be severed. The peritoneal incision is closed, and the operation is concluded.

SURGICAL CONSIDERATIONS OF THE UTERUS AND THE ADNEXAE

HYSTERECTOMY

Subtotal (Supravaginal) Hysterectomy
This operation commonly is performed for benign lesions or extensive inflammatory disease.

A low midline incision is made and the round ligaments are severed on both sides about an inch away from the cornual end of the uterus (Fig. 465). These severed ends are ligated. This step opens the broad ligaments so that an anterior vesical flap of peritoneum can be formed. If the adnexae are to remain an avascular area is found in the broad ligament close to the uterus; this is entered with either a curved hemostat or the finger. Clamps are applied to the tube and the ovarian ligament adjacent to the uterus. These structures are cut between clamps and the clamps are replaced by transfexion sutures. If one desires to remove the tube or the ovary the end of the tube is grasped and reflected medially. Clamps are applied to the infundibulopelvic ligament and an incision is made between these; they also are replaced by transfexion sutures. The uterine vessels are clamped and severed at approximately the corpocervical junction; the cervix is coned. The cervical stump is closed transversely with interrupted sutures. Peritonization is accomplished in the following way:

FIG. 466. Panhysterectomy. (A) The incision is a long midline one which extends to the left and above the umbilicus. (B) The vesico-uterine peritoneum is incised transversely. The round ligaments may or may not be grasped with the fallopian tubes and the utero-ovarian ligaments. The finger has perforated an avascular area in the left broad ligament. (C) The uterine vessels are clamped and cut, this permits downward displacement of the ureter. (D) The bladder is separated from the cervix by blunt dissection. (E) The anterior and the posterior dissections are completed below the cervix. (F) Amputation across the vaginal vault is done as close to the cervix as possible. (G) Closure of the vaginal vault with apposition to it of the round and the utero ovarian ligaments.




FIG 466 (Legend on next page)




FIG 468 Salpingo-oophorectomy




FIG 469 The Baldy Webster operation for retrodisplaced uterus

tube as possible so that the vascular supply of the ovary is not interfered with. The mesosalpinx is cut and the uterine cornu is excised. The latter is closed and the hemostats on the mesosalpinx are ligated. Peritonization is accomplished by suturing the posterior leaf of the broad ligament to the posterior surface of the uterus.

Salpingo Oophorectomy When both the tubes and the ovary are to be removed the clamps are applied to the infundibulopelvic ligament which contains the ovarian vessels (Fig 468). The remainder of the procedure is the same as that described for salpingectomy.

SURGERY FOR

RETRODISPLACEMENT OF THE UTERUS

Many operations have been devised to correct the retrodisplaced uterus. The usual procedures performed are the Gilliam, the Baldy Webster, the Olshausen, and the Coffey.

The Gilliam Operation After opening the abdomen a clamp is used to grasp the round ligaments about one inch from the cornua of the uterus. The clamp is withdrawn through the aponeurosis, the muscle and the peritoneum. The same is done on

the other side. These knuckles of ligaments then are pulled well up through the defects, bringing the uterus into an anterior position. They are anchored to the aponeurosis with a few interrupted sutures. Although this is one of the most popular operations for retrodisplacement, some authorities are of the opinion that the procedure is faulty since it does not retain the cervix in its normal position; furthermore, it is dangerous because of the possibility of strangulation of a loop of intestines in the pocket formed between the round ligament and the anterior abdominal wall.

The Baldy Webster Operation In this procedure an avascular area in the mesosalpinx is sought by stretching the tube and the ovary (Fig 469). The clamp is placed through this area immediately beneath the utero-ovarian ligament and the round ligament is grasped about $1\frac{1}{2}$ inches from the cornua of the uterus. The knuckle of round ligament then is brought posteriorly through this perforation. The same is done on the opposite side. The loops of the two ligaments are approximated on the posterior surface of the uterus and sutured, each suture includes the uterine wall.

The Olshausen Operation The round




FIG 467 Salpingectomy

(Fig 465 F) a stitch is placed in the (1) posterior cervical wall, then grasps (2) the tube or the infundibulopelvic ligament, as the case may be then (3) the round ligament and finally (4) the anterior vesical flap which has been mobilized. When this flap is tied one side of the cervical stump is peritonized and supported. A similar four bite stitch is placed on the opposite side. Peritonization is completed by a few interrupted sutures which grasp the posterior cervical wall and the anterior vesical flap.

Panhysterectomy The steps of this procedure may be similar to those for subtotal hysterectomy until the uterine vessels are ligated (Fig 466). After this step the operator examines the region of the cervix to determine the length of the cervix and the position of the bladder. The latter is pushed downward usually by gauze dissection. This is continued downward and forward until the thumb and the index finger can compress the vaginal wall below

the cervix. The peritoneum on the posterior cervical wall is incised and dissected downward until the cervix can be palpated through the vaginal vault. The vagina is entered, and the vaginal vault is divided as close to the cervix as possible. After freeing the cervix from the vagina the anterior and the posterior vaginal walls are approximated. During the closure the round ligaments, the tubes and the utero-ovarian ligaments are anchored to the angles of the vaginal vault. All raw surfaces are carefully peritonized.

SALPINGECTOMY AND SALPINGO OOPHORECTOMY

Removal of the fallopian tubes and the ovaries usually is done for inflammatory involvement, cysts, neoplasms, ectopic pregnancies, etc.

Salpingectomy After exposing the tube, clamps are applied to the outer margin of the mesosalpinx (Fig 467). It is important that these clamps be placed as close to the

SECTION SIX

MALE PERINEUM AND
EXTERNAL GENITALIA

ligament is picked up by a suture which is carried beneath it about $1\frac{1}{2}$ inches from the cornua of the uterus the same is done on the opposite side. The uterus is brought forward to a point corresponding to its normal anterior position, and the sutures previously introduced are carried through the peritoneum, the recti muscles and the aponeurosis about a half inch to each side of the median incision. The sutures are tied. This operation also has a disadvantage in that it leaves two apertures between the

ligaments and the anterior abdominal wall through these openings loops of intestines or omentum may become strangulated.

The Coffey Operation In this procedure, the folded excess loop of round ligament is sutured to the anterior surface of the uterus. This suture begins about one inch below the uterine end of the round ligament and extends upward toward the cornu of the uterus. At times, the anterior leaf or broad ligament is used to peritonize the sutured area.

Male Perineum

EMBRYOLOGY

In the embryo the endodermal alimentary tract ends as a blind receptacle called the cloaca, this has an anterior diverticulum called the allantois (urachus). The mesonephric duct (adult vas deferens) grows caudally and opens into the anterior part of the cloaca (Fig. 470). The ureter develops as an outpouching of the mesonephric duct the two for a period ending in one terminal duct. This common duct subsequently is absorbed into the wall of the bladder and the prostatic urethra with the result that the ureter and the vas deferens eventually have separate openings. A mesodermal septum (urorectal septum) divides the cloaca into an anterior, urogenital part and a posterior intestinal part. The cloaca has a sphincter which is also divided into an anterior portion which becomes the superficial transversus perineus, the bulbospongiosus, the ischiocavernosus and the urogenital diaphragm; the posterior part of the sphincter becomes the external sphincter ani. One nerve the pudendal supplies the cloacal sphincter as well as the skin of the region around it; its accompanying artery the pudendal, nourishes this region. The bladder and the rectum receive their nerve supply through the pelvic splanchnic nerve and the hypogastric plexus.

The *perineum* is a lozenge shaped space which is bounded by the pubic symphysis, the ramus of the pubis and the ischia, the ischial tuberosities, the great sacrotuberous ligament, the edges of the great gluteal muscles and the coccyx (Fig. 471). If a transverse line is drawn across the space between the anterior extremities of the

ischial tuberosities, directly in front of the anus, it divides the perineum into two parts. The anterior part forms a nearly equilateral triangle which measures approximately $3\frac{1}{4}$ inches on all sides and is known as the anterior or the urogenital triangle. The posterior part is also somewhat triangular, contains the rectum and the ischioanal fossae and is called the anal triangle. The bony framework of the perineum may be felt more or less distinctly, and in thin subjects the sacrotuberous ligament may even be made out beneath the gluteus maximus muscle. The superficial areas of the perineum depend upon the posture of the body. When the thighs are brought together it is very limited and then is represented only by a narrow groove which contains the anus and the roots of the scrotum and the penis. The region is wider in the female because of the greater size of the pelvic outlet. In the midline of the perineum a cutaneous ridge, the median raphe, can be followed from the front of the anus forward over the scrotum and along the lower surface of the penis. This raphe marks that line along which the floor of the urethra was completed and where the two halves of the scrotum fused during their development.

THE UROGENITAL TRIANGLE

This is the anterior triangle of the perineum or the genito-urinary part. It is bounded in front by the pubic symphysis, on the sides by the ramus of the pubis and the ischium and posteriorly by a line drawn between the anterior parts of the ischial tuberosities.

The *superficial fascia* consists of two

and the scrotum and so forms a covering for the testis and the spermatic cord.

The arrangements and the attachments of this fascia are important because they determine the direction in which extravasated urine will spread after rupture of the cavernous portion of the urethra. The fascia has a median septum which attaches to the perineal muscles but this septum is not complete and fluid may pass through it from side to side. Urine under Colles' fascia following rupture of the urethra may extend downward as far as the lower border of the urogenital diaphragm because at this point it fuses with the base of the diaphragm. Laterally, it may extend through the median septum as far as the attachment of the fascia to the conjoined ischiopubic rami upward it may extend over the scrotum and the penis and onto the anterior abdominal wall. Once the fluid has reached the anterior abdominal wall it can extend downward and over the inguinal




FIG 473 The superficial and the deep perineal pouches.




FIG 474 The superficial perineal pouch and its contents. Colles' fascia has been incised and reflected to reveal the contents of this pouch.

layers an outer fatty layer and an inner membranous layer. The *superficial fatty layer* of the superficial fascia is continuous with the superficial fat of the rest of the body and contains small cutaneous vessels and nerves. The farther downward this layer is traced the scarcer becomes the fat so that over the scrotum the fat entirely disappears and gives place to a thin layer of involuntary muscle fibers. These constitute the dartos muscle and are responsible for the rugosity of the scrotal

skin which is caused by their contraction. The *deep layer of superficial fascia* is not fatty but membranous and is continuous with a similar layer of fascia in the lower part of the anterior abdominal wall. In the anterior abdominal wall it is called Scarpa's fascia but changes its name in the perineum to the fascia of Colles, it is found only over the urogenital triangle (Fig 472). Its attachments are to the fascia lata, the pubic arch and the base of the perineal membrane. It is prolonged over the penis




FIG 470 Embryology of the male urogenital system (A) An early stage, a cloaca is present (B) A later stage the cloaca has been divided by the urorectal septum




FIG 471 The male perineum




FIG 472 Colles' fascia. This fascia is the deep layer of superficial fascia, on the anterior abdominal wall it is called Scarpa's fascia. This fascia determines the direction of spread of extravasated urine

2 The *ischio-cavernosus* muscle is applied to the crus and it is close to the superficial transverse perineal muscle. It covers the free surface of the crus into which it is inserted inferiorly. The two ischio-cavernosus muscles compress the crura against the pubic arch and so obstruct the venous return of the corpora cavernosa.

3 The *bulbo-cavernosus* (bulbospongiosus) muscle arises from the perineal body and from a median raphe which separates the two halves of the muscles on the inferior surface of the bulb. It is therefore a bilateral structure. The most posterior fibers of this muscle pass to the perineal membrane, the intermediate fibers of the two sides meet on the dorsum of the corpus spongiosum and the most anterior fibers meet on the dorsum of the penis where they blend with the fibers of the penis. This muscle acts as a sphincter which empties the bulb and part of the spongy urethra and also compresses the bulb against the perineal membrane thereby constricting the corpus spongiosum.

All the superficial perineal muscles are supplied by the perineal branch of the pudendal nerve. The perineum, on each side of the corpus cavernosum, urethra is traversed by nerves and vessels which are small branches of the pudendal trunks. They supply the surrounding structures in the superficial perineal compartment.

THE DEEP PERINEAL POUCH (UROGENITAL DIAPHRAGM)

The *urogenital diaphragm* is a musculo-membranous diaphragm which is tightly stretched across the pubic arch and is attached to the ischiopubic rami (Figs 473, 474 and 475). It separates the perineum from the pelvis and consists of two layers of fascia with two muscles between them. The two fascial layers are the superior (upper) and the inferior (lower) layers; the two muscles are the sphincter urethrae membranaceae and the deep transverse perineal. The space which is created by these two layers of fascia and is filled by the two

muscles is known as the deep perineal pouch or compartment.

The *inferior fascial layer* of the urogenital diaphragm also has been referred to as the superficial layer of the triangular ligament and the perineal membrane. It covers the lower surface of the sphincter urethrae and the deep transverse perineal muscle. Its lower surface is largely covered by the root of the penis and each side is attached to the side of the pubic arch. Its posterior border is fused with the posterior border of the superior fascia of the urogenital diaphragm and the membranous layer of superficial fascia. In the midline the fused borders are continuous with a fatty fibromuscular nodule called the *perineal body*. Anteriorly this fascia presents a thickened free margin known as the transverse perineal ligament. Between this ligament and the inferior ligament of the pubis there is an oval interval through which the deep dorsal vein of the penis passes into the pelvis to enter the venous network around the prostate (Fig. 425). The membrane is pierced by several structures which enter the superficial perineal pouch: (1) the urethra pierces it in the midline about one inch below the symphysis pubis; it is accompanied on either side by the small ducts of the bulbo-urethral glands opening into the spongy portion; (2) the artery to the bulb of the penis pierces the membrane a little to either side of the urethra; (3) the internal pudendal artery; (4) the dorsal nerve to the penis pierces the membrane close to its lateral attachment and under cover of the anterior part of the crus.

The *superior or upper layer of perineal fascia* is derived from the parietal pelvic fascia. It is a loose layer of fibrous tissue which covers the pelvic surface of the sphincter urethrae and the deep transverse perineal muscles. On each side it is attached to the obturator fascia. The apex of the prostate rests upon it and it is continuous with the fascial sheath of that viscus. The urethra emerging from the prostate, pierces it in the midline.

ligament until it is held up by the attachment of Scarpa's fascia to the fascia lata approximately one inch below and parallel with the inguinal ligament

THE SUPERFICIAL PERINEAL POUCH

The *superficial perineal pouch* is a compartment in the urogenital part of the peri-

portions of the corpora cavernosa of the penis and the urethra their overlying ischio-cavernosus and bulbocavernosus muscles, the superficial transverse perineal muscle and those branches of the internal pudendal vessels and nerves which pierce the inferior fascia of the urogenital diaphragm to reach this space




FIG 475 The deep perineal pouch (urogenital diaphragm) (A) Seen from below The inferior layer of fascia has been retracted, and the muscle has been left intact on the opposite side the deep transverse perineal muscle has also been reflected, exposing the superior layer of fascia (B) Frontal section

neum which is bounded inferiorly (a floor) by Colles' fascia and superiorly (a roof) by the urogenital diaphragm (perineal membrane) (Fig 473) The pouch is closed behind by the fusion of its roof and floor and on each side by the attachments of the walls to the margins of the pubic arch. Above however it remains open and communicates with the cellular interval which is situated between Scarpa's fascia and the anterior rectus sheath. Should the urethra rupture into this space, it would fill the posterior part of the pouch and then spread into the scrotum and the penis and, if allowed to continue, would ascend in front of the symphysis pubis and so reach the anterior abdominal wall.

The contents of the superficial perineal compartment consist of the roots or fixed

The two roots of the corpora cavernosa of the penis arise from the midportion of the ischiopubic rami, run obliquely upward and forward and adhere to the periosteum of the descending rami of the pubes and to the inferior surface of the urogenital diaphragm (p 635). Each cavernous body is covered by the ischio-cavernosus muscle.

On each side, the following *three superficial perineal muscles* lie in the superficial perineal pouch (Fig 474):

1 The *superficial transverse perineal muscle* lies at the base of the pouch and extends from the ischial tuberosity to the central point of the perineum. The two transverse muscles act together to steady the perineal body during defecation and to fix it during contractions of the external sphincter and the bulbospongiosus.




FIG 477 The internal pudendal artery This artery gives rise to the dorsal artery of the penis, the deep artery of the penis and the artery to the bulb The dorsal nerve of the penis accompanies the internal pudendal artery

phragm Their ducts which are about one inch long pass through the urethral openings in the perineal membrane and open into the floor of the spongy portion of the urethra Each gland receives a branch of the bulbo urethral artery They are involved in gonorrheal inflammation of the cavernous urethra and may give rise to abscesses which can be felt through the rectum Such suppurations may evacuate into the urethra the perineum or the rectum

The *internal pudendal artery* is a branch of the internal iliac artery and passes forward from the pudendal canal deep to the inferior layer of the urogenital diaphragm (Fig 477) It lies under cover of the pubic arch and has the dorsal nerve of the penis to its lateral side In its course it passes through the pelvis the gluteal region and the perineum, and is accompanied throughout by its two veins Under cover of the anterior part of the crus penis it pierces the inferior layer of the urogenital dia




FIG 476 The bulbo urethral gland (Cowper). The gland is situated between the layers of the urogenital diaphragm. If the gland suppurates, it may evacuate into the urethra, the perineum or the rectum.

The *deep perineal muscles* are one sheet of muscle which is divided into two parts, namely a deep transverse perineal and a sphincter urethrae (Fig. 483). The *sphincter urethrae (membranaceae) muscle* arises from the pubic arch on a level with the urethra. As the fibers approach the median plane some of them pass behind the membranous part of the urethra and some in front of it; they blend with the corresponding fibers of the opposite side. The *deep transverse perineal muscle* is the posterior part of the muscle just described. It is small and passes below and behind the membranous part of the urethra.

Both muscles are supplied by two delicate twigs from the perineal nerve. When the sphincter vesicae (internal sphincter) is destroyed after prostatectomy, the sphincter urethrae is the only muscle left but is perfectly competent to control urination.

The *deep perineal pouch* is that space which is enclosed by the superior and the inferior fasciae of the urogenital diaphragm. It is separated from the superficial perineal pouch by the perineal membrane and from the anterior part of the pelvis by the fi-

brous tissue which forms the sheath of the prostate and contributes to the formation of the perineal body. This pouch contains the (1) two muscles just described (sphincter urethrae and the deep transverse perineal), (2) the membranous part of the urethra, (3) the bulbo urethral gland, (4) the internal pudendal artery and the artery to the bulb of the penis and (5) the dorsal nerve of the penis.

The membranous portion is the shortest part of the urethra, being about one half inch long, and lies about one inch below the pubic symphysis (Fig. 482). It is continuous above with the prostatic and below with the spongy urethra. The prostatic and the membranous portions of the urethra are directed downward and forward, but the spongy part curves upward and forward in the bulb of the penis before it turns down in the corpus spongiosum. The membranous urethra is the least dilatable and the narrowest part with the exception of the external orifice. If this part of the urethra ruptures proximal to a stricture in the cavernous portion, extravasation of urine results into the deep perineal compartment from which an exit can be found only through one or the other of the fascial sheaths of the urogenital diaphragm. If urine breaks through the inferior fascia, it passes into the superficial perineal pouch and forward onto the abdomen in front of the pubis. If the extension is through the superior fascia, however, or if there is an extraperitoneal rupture of the bladder, the extravasated urine enters the interval above the median puboprostatic ligaments and extends forward into the retropubic space of Retzius. From there it ascends in the anterior abdominal wall between the transversalis fascia and the parietal peritoneum.

The *bulbo urethral glands (Cowper)* are two small pea-sized bodies which lie posterolateral to the membranous urethra and under cover of its sphincter muscle (Figs. 476 and 481). They are located between the layers of the urogenital dia-

External Genitalia

PLNIS

The *penis* has a posterior fixed part or root and an anterior mobile portion called the body. It is composed of three fibro-elastic cylinders which are filled with spongy or erectile tissue. These cylinder-like masses are the right and the left *corpora cavernosa* and the *corpus spongiosum* (urethrae) (Fig 477). The two roots of the *corpora cavernosa* of the penis arise from the midportion of the ischiopubic rami, pass obliquely upward and forward, hugging the periosteum of the descending rami of the pubes and the inferior surface of the urogenital diaphragm. Each is covered by the ischio-cavernosus muscle. The *corpora* are united side by side in the body of the penis but at its root they are separate and assume the name of crura, each of which tapers to a point posteriorly. The *corpus spongiosum* which is much more slender lies along the lower surface of the united *corpora cavernosa* and is traversed lengthwise by the longest of the three divisions of the urethra. Anteriorly at the end of the penis it enlarges to form the *glans* of the penis in which the anterior ends of the *corpora cavernosa* are embedded.

The *body* of the penis is formed by the union of all the cavernous masses. It begins at the apex of the urogenital diaphragm and is attached to it by connective tissue bands. The *corpora cavernosa* lie side by side on the dorsum and the *corpus spongiosum* lies ventrally. The *corpus spongiosum* terminates posteriorly in a large, free bulbous sac known as the *bulb of the urethra* (Fig 483). This latter structure overlaps the junction of the membranous and the cavernous divisions of the urethra posteriorly.

THE SUPERFICIAL STRUCTURES

The skin of the penis is continued forward as the *prepuce* (*foreskin*) (Fig 478). The skin is devoid of hair and the fascia is devoid of fat. The prepuce is a fairly dense portion of skin which forms a cuff or hood covering the glans. Within the cavity of the prepuce the modified skin contains sebaceous glands which secrete smegma. On the under aspect of the glans a well defined fold of skin called the *frenulum* passes forward and is attached to the prepuce. The subcutaneous tissue of the penis is a continuation of Colles' fascia is very loose in texture and is traversed by the superficial dorsal vein. The looseness of these tissues gives mobility to the penis and explains the ease with which blood or urine may extravasate, producing tremendous swellings of the organ. The superficial lymphatics accompany the superficial dorsal vein and enter the subinguinal lymph nodes. These become involved in infections about the prepuce and the glans.

Beneath the subcutaneous layer the penis is invested by a thin fibrous membrane known as the *fascia of the penis* (*Buck's fascia*). This fascia envelops the body of the penis and the corona of the glans to the root of the penis. It is adherent on each side in the groove between the *corpora cavernosa* and the *corpus spongiosum*. The *suspensory ligament of the penis* is a thickened triangular fibro-elastic band. It is fixed above to the lower part of the linea alba and the upper part of the symphysis pubis, below it splits to form a sling for the penis at the junction of its fixed and mobile parts where it blends with the fascia of the penis.

phragm enters the superficial pouch and divides into the dorsal artery of the penis and the deep artery of the penis. The deep artery of the penis pierces the medial side of the crus penis and runs forward in the substance of the corpus cavernosum which it supplies. The dorsal artery of the penis runs upward between the bone and the commencement of the crus to gain the dorsum of the penis. The internal pudendal artery gives rise to the *artery to the bulb*, this vessel runs medially on the surface of the deep transverse perineal muscle, pierces the perineal membrane and ends in the bulb. It supplies a small twig to the bulbourethral gland. It pierces the perineal membrane, enters the bulb of the penis and runs onward through the whole length of the corpus spongiosum supplying its substance.

The *dorsal nerve of the penis* arises from the pudendal nerve in the pudendal canal (Fig. 477). It accompanies the internal pudendal and the dorsal arteries, which lie

to its medial side, and supplies the corpus cavernosum penis, the glans and the skin of the penis.

The *anterior prolongation of the ischio-rectal fossa* is the deepest space in the anterior perineum. It runs forward toward the pubes, between the superior fascia of the urogenital diaphragm, the anterior portion of the levator ani, and the mesial surface of the obturator internus muscle (p. 556).

The *central point of the perineum* is marked by a fibromuscular node lying between the anorectal junction and the apex of the sphincters, and the bulbocavernosus muscle (Fig. 474). It is also a point of insertion for the rectourethral and the superficial transverse perineal muscles and for the levator fibers which are associated with the support of the prostate (Fig. 474). This point is an excellent guide, since it unites the urogenital diaphragm and the anus with their substratum of levators. It affords the proper perineal approach to the deeper pelvic structures.

URETHRA

The *urethra* is a fibro-chlastic structure which measures about eight inches in length and is divided by the superior and the inferior fasciae of the urogenital diaphragm into three parts: prostatic, membranous and spongy (Fig. 481). The part above the superior fascia travels through the prostate, the part between the two urogenital diaphragm fasciae constitutes part two, and the part beyond the inferior fascia (perineal membrane) traverses the corpus spongiosum.

The *prostatic urethra* is the widest and most dilatable portion of the urethra and travels almost perpendicularly; it is about an inch in length. On transverse section it appears crescentic because of the presence of a prominent vertical ridge on its posterior wall, the *urethral crest* (Fig. 482). The gutter to each side of this crest is known as the prostatic sinus. The urethral crest rises to a summit, the *colliculus*, and bifurcates below as it dis-




FIG. 479 The venous drainage of the penis (A) Lateral view of the relations between the superficial and the deep dorsal veins (B) Cross section showing relations of vessels to the fasciae




FIG. 480 The tunica albuginea and Buck's fascia (A) cross section, (B) relations to the urogenital diaphragm, (C) sagittal view

The deep dorsal nerve, arteries, veins and lymph vessels run beneath Buck's fascia and along the dorsum of the penis. Encircling branches of the veins drain the corpora cavernosa and the corpus spongiosum and encircling arteries send twigs to

after passing below the inferior pubic ligament. It ends by joining the venous plexus which surrounds the prostate.

The dorsal arteries of the penis are the terminal branches of the internal pudendal. They pass forward in the interval between




FIG 478 The superficial structures of the penis. The penis has three superficial encircling coats: the skin, the loose areolar subcutaneous tissue and the fascia of the penis (Buck's). These have been reflected in the drawing.

the same structures. The deep vein passes between the intrapubic ligament and the urogenital diaphragm to the prostatic venous plexus. On the dorsum of the penis a pair of dorsal nerves pass lengthwise beneath the deep fascia; between these there is a pair of dorsal arteries, and between these the deep dorsal vein lies in the median plane (Figs 477 and 478). The superficial dorsal vein, also median, lies in the superficial fascia and is the one which is seen through the skin. It should be noted that the veins are not left and right as are the arteries and the nerves but are median, either superficial or deep. The superficial dorsal vein receives tributaries from the skin and the prepuce, and terminates posteriorly by dividing into right and left branches which drain into the external pudendal veins in the thigh (Fig 479). The deep dorsal vein begins by the union of several twigs from the glans and the prepuce. It runs backward in the median line, passes between the two layers of the suspensory ligament and enters the pelvis

the corpora cavernosa and reach the dorsum of the penis. Here the two arteries lie one on each side of the deep dorsal vein (Fig 477). The dorsal nerve lies lateral to the artery; both vessels and nerves are enclosed between the two layers of the suspensory ligament of the penis. These vessels supply the body of the penis and terminate in the glans. The deep artery of the penis pierces the medial aspect of the anterior part of the crus and runs forward in the corpus cavernosum penis.

Each dorsal nerve of the penis is a terminal branch of the pudendal nerve. It supplies branches to the corpus cavernosum, the glans and the skin of the penis.

Each erectile body is surrounded by a distensible elastic fibrous tissue called the tunica albuginea; the trabeculae of which surround blood spaces (Fig 480). Where the corpora are applied against each other, the albuginea forms a median partition called the septum of the penis. It is difficult at times to differentiate or separate Buck's fascia from the tunica albuginea.

URETHRA

The *urethra* is a fibro elastic structure which measures about eight inches in length and is divided by the superior and the inferior fasciae of the urogenital diaphragm into three parts: prostatic, membranous and spongy (Fig. 481). The part above the superior fascia travels through the prostate, the part between the two urogenital diaphragm fasciae constitutes part two and the part beyond the inferior fascia (perineal membrane) traverses the corpus spongiosum.

The *prostatic urethra* is the widest and most dilatable portion of the urethra and travels almost perpendicularly, it is about an inch in length. On transverse section it appears crescentic because of the presence of a prominent vertical ridge on its posterior wall the *urethral crest* (Fig. 482). The gutter to each side of this crest is known as the *prostatic sinus*. The urethral crest rises to a summit, the *colliculus*, and bifurcates below as it dis-




FIG. 479 The venous drainage of the penis (A) Lateral view of the relations between the superficial and the deep dorsal veins (B) Cross section showing relations of vessels to the fasciae




FIG. 480 The tunica albuginea and Buck's fascia (A) cross section, (B) relations to the urogenital diaphragm, (C) sagittal view




FIG 481 The male urethra The urethra is divided into prostatic, membranous and penile parts The relations of each part are shown in sagittal section

appears Opening onto the colliculus is a diverticulum called the *prostatic utricle*, through which a probe can be passed for about half an inch into the substance of the prostate On its lips open the much finer orifices of the *ejaculatory ducts* Onto the floor of each prostatic sinus the prostatic ducts appear as several dozen small openings

The *membranous urethra* passes through the urogenital diaphragm and its two fasciae It is approximately one half inch long and has no surrounding tissue proper Behind it on each side lie the *bulbo urethral glands of Cowper* The circular fibers of the diaphragm called the *sphincter urethrae (compressor urethrae)*, have been referred to as the 'cut off' or 'shut off' muscle it has a sphincterlike action and is a voluntary muscle supplied by the perineal branch of the internal pudendal nerve Like the sphincter ani, also supplied by the pudendal nerve, it is in constant contraction

The *spongy, penile or cavernous urethra* traverses the bulb, the body and the glans of the corpus spongiosum penis It is the longest portion of the urethra and extends from the inferior layer of fascia of the urogenital diaphragm to the external meatus After piercing the urogenital diaphragm it enters the bulb about one cm in front of its rounded posterior extremity (Fig 483) In its passage it lies nearer the dorsal aspect Its lumen is dilated both in the bulb and in the glans, the latter dilatation being known as the *terminal (navicular) fossa* The bulbous portion of the urethra forms the most dependent part of the perineal curve The bulbo urethral glands of Cowper open into this portion of the urethra at its lower or posterior wall The external orifice is the narrowest part and at times requires incision to permit the passage of instruments which may pass easily through the remainder of the urethra The passage of a sound is a simple procedure in a normal urethra, if the beak is

kept in contact with the urethral roof after the navicular fossa has been passed. Once the level of the membranous portion has been reached little difficulty is encountered in entering the bladder except in pathologic conditions which involve either the urethra or the prostate gland.

SCROTUM

The scrotum is a pendulous purse-like bag of skin and fascia in which the testes are found (Fig. 484). It has a bilateral origin, being derived from right and left labio-scrotal folds. In the female, the folds remain separated as the labia majora, but in the male they fuse behind the penis to form the scrotum. A vestige of the fusion of the two sides of the scrotum remains as the median raphe which is continued into the perineal skin behind the scrotum and along the lower aspect of the penis anteriorly.

The skin of the scrotum forms a single pouch. It is delicate in texture, darker in color than the surrounding region and quite distensible. Its rugosity, which varies with temperature, is produced by the *dartos muscle* which lies immediately subjacent. The *superficial fascia* in the scrotum is entirely devoid of fat and is largely replaced by the thin sheet of muscle just mentioned, the *dartos*. This muscle sends a median partition across the scrotum which separates the testes from each other.




FIG. 482 The posterior wall of the male urethra





FIG. 483 The penile portion of the urethra after it pierces the urogenital diaphragm



✓ FIG 484 The scrotum and its six associated layers
(A) side view, (B) schematic cross section

the septum, however is incomplete superiorly. It is a laminated thin sheet of involuntary muscle which is platysmalike since it is intimately adherent to the skin, causing it to wrinkle. It contracts with cold and relaxes with heat; its tonicity decreasing with age. Sympathetic nerve fibers supply it.

In the wall of each scrotal chamber there are, besides skin and dartos, three complete layers which are derived from the anterior abdominal wall. They are named from without inward: the external spermatic fascia, the cremaster muscle, and the internal spermatic fascia. These provide additional coverings or coats for each testis. The *external spermatic fascia*, which is derived from the external oblique aponeurosis, appears as a small layer of areolar tissue situated directly under the dartos. Though the skin and the superficial fascia are common to both halves of the scrotum,

the three additional layers are confined to each corresponding side because of the septum produced by the dartos muscle. The *cremaster muscle* is derived from the internal oblique. Its muscle loops reach the testicle as thin strands. By their contraction the testis is drawn toward the subcutaneous inguinal ring and produces the cremasteric reflex. The *internal spermatic fascia* is derived from the transversalis fascia. It is composed of loose connective tissue and closely invests the elements of the cord and the testicle. The *tunica vaginalis testis* is developmentally a portion of the peritoneum. It is a serous membrane and like all other serous membranes, has parietal and visceral layers. These are separated by a capillary interval which contains a film of fluid which keeps the surfaces moist. The parietal layer lines the wall of the scrotum and is closely adherent to the internal spermatic fascia. At the back of




FIG. 485 The testis (A) A section of the gland has been removed to show its relations to the epididymis and the tunica albuginea (B) and (C) Coverings of the spermatic cord and the testis

the scrotum it is reflected forward and becomes continuous with the visceral layer. The latter covers the epididymis and then the testis itself. In inguinal herniae of long standing, the coats of the testis and the spermatic cord become thickened and may be separated and displayed, but in normal individuals although the dartos and the tunica vaginalis are easily identified one finds that the external spermatic fascia, the cremaster and the internal spermatic fascia have a tendency to become fused and are less easily defined.

TESTIS

This gland appears as an oval body with flattened sides; it lies in the scrotum with its long axis oblique; its upper pole tilted forward. It varies in size but its average dimensions are one and one half inches in length, one inch in anteroposterior diameter, and a little less than that from side to side. The vas deferens and the epididymis are applied to its posterior border (Fig. 485). On each side and anteriorly, it is enveloped

by the tunica vaginalis which under normal conditions, forms a completely closed sac. The visceral layer of this tunic is closely adherent to the testis and becomes continuous with the parietal layer at the upper and the lower poles and along the posterior part of both sides of the gland. On the lateral aspect it is reflected onto the medial side of the epididymis thus forming the underlying sinus of the epididymis, which partially separates the body of the epididymis from the testis (Fig. 486).

The *tunica albuginea* is a pearly white coat which forms a complete fibrous covering deep to the tunica vaginalis. At the posterior border of the gland it becomes thicker, forming the *mediastinum testis*. From this mediastinum incomplete fibrous septa pass inward to subdivide the gland into lobes. Convoluted seminiferous tubules lie in the lobes and pass backward into the mediastinum testis where they unite and form a network called the *rete testis*. From this network about 20 efferent ductules (*vasa efferentia*) arise, they emerge




FIG 486 The internal structure of the testis (A) Transverse section of the right testis (B) Teased sagittal section

from the upper pole of the testis and enter the head of the epididymis

The *epididymis* is applied to the upper pole and the posterior border of the testis. It tapers from above downward and is subdivided into a head, a body, and a tail. The head of the epididymis is enlarged and fits like a cap on the upper pole of the testis to which it is attached by the efferent ductules. The body is separated from the testis by the sinus of the epididymis and the tail or lower end is attached only by areolar tissue near its lower end. Within the head, the efferent ductules unite to form the canal of the epididymis which is coiled up within the body and the tail. When unraveled it measures almost 20 feet in length. This duct emerges from the tail as the vas (ductus) deferens which ascends medial to the epididymis and enters the spermatic cord. The body and the tail of the epididymis can be separated easily from the testicle, but the head must be severed at its efferent ductules.

SPERMATIC CORD

This appears as a long rounded bundle which extends from the deep inguinal ring to the posterosuperior border of the testicle (Figs 485, 486 and 487). Within the abdomen, its constituent parts are widely separated but from the deep inguinal ring to the testis they are wrapped together by the coverings of the cord. It is encased in three fibrous coats derived from the abdominal wall during the descent of the testis, namely a continuation of the external abdominal oblique (the external spermatic fascia), a continuation of the internal abdominal oblique (the cremaster muscle), and a continuation of the transversalis fascia (the internal spermatic fascia). Plus this, the two inner layers of the abdominal wall, namely, peritoneum and properitoneal fat are also present. In the fatty layer run the duct, the vessels and the nerves of the testis and the vessels and the nerves of the epididymis. These constituents of the cord assemble at

the internal inguinal ring, lateral to the inferior epigastric artery, pass through the inguinal canal and descend in the scrotum to the testis. The cord lies behind the internal oblique laterally and in front of it medially. As it emerges from the superficial inguinal ring, it passes over the pubic tubercle and covers it; hence when one attempts to feel the tubercle, it is first necessary to displace the cord.

The constituents of the spermatic cord are

1. Continuations of the two inner layers of the abdominal wall (processus vaginalis, peritoneum and the preperitoneal fatty areolar tissue).

2. Structures associated with the testicle (vas deferens and artery, veins, lymphatics and nerves).

3. Vessels and nerves associated with the vas deferens and the epididymis.

The *processus vaginalis peritonei* (funicular process of peritoneum, tunica vaginalis testis) is a tubelike process of peritoneum, the upper part of which lies in front of the vas; it is obliterated before birth or within a month thereafter to become a fibrouslike thread (Fig. 266). Its lower part remains patent and is invaginated from behind by the testis, changing its name to the tunica vaginalis testis.

The *preperitoneal fatty areolar tissue* is an extension of the extraperitoneal abdominal fat which surrounds the processus vaginalis and forms a covering for the structures which pass to and from the testis. This layer is the surgeon's landmark to the underlying sac in inguinal hernia operations. The adipose tissue in this layer diminishes as one proceeds down the cord; thus no fat is found in the scrotum.

The *vas deferens* (*ductus deferens*) is the structure which conveys spermatozoa from the testis to the urethra. It is as long as an adult femur. It starts in the tail of the epididymis, of which it is the prolongation. The pathologic changes of one affects

the other. It is the only hard structure in the spermatic cord; hence it can be identified easily; the firmness is due to a thick muscular coat. It has a tiny lumen and is dilated at its two extremities, which are the only thin-walled portions of the vas. It first ascends behind the testis along the medial border of the epididymis, continues through the scrotum and the inguinal canal as the posterior constituent of the spermatic cord, then winds around the lateral side of the inferior epigastric artery and descends to the posterolateral angle of the bladder and thence to the urethra (Fig. 487). The vas is subperitoneal throughout its entire course. Normally, it is bluish white in color, resembling cartilage. Because of its posterior relationship, the sac of an indirect inguinal hernia usually lies anterior to it.

VESSELS AND NERVES

There are two arteries in the spermatic cord, namely the testicular and the deferential arteries (Fig. 487). The *testicular (internal spermatic) artery* is the larger and supplies the testis. It arises from the abdominal aorta in the lumboiliac region and joins the cord at the abdominal inguinal ring. In the cord it is surrounded and hidden by the spermatic group of veins. It lies in front of the vas. The *artery of the vas deferens* is a slender branch of the inferior vesical artery which passes along the vas to supply it and the epididymis.

The *pampiniform plexus* represents the veins of the testis and the epididymis; they number about a dozen. This anastomosing plexus receives its name from its resemblance to a vine. The veins ascend in three longitudinal groups. The anterior group surrounds the testicular artery and the middle surrounds the vas; the posterior group runs alone. As the veins ascend they decrease in number but increase in size and finally end at or near the deep inguinal ring as the *testicular vein*, which continues up




FIG 486 The internal structure of the testis (A) Transverse section of the right testis (B) Teased sagittal section

from the upper pole of the testis and enter the head of the epididymis

The *epididymis* is applied to the upper pole and the posterior border of the testis. It tapers from above downward and is subdivided into a head, a body and a tail. The head of the epididymis is enlarged and fits like a cap on the upper pole of the testis to which it is attached by the efferent ductules. The body is separated from the testis by the sinus of the epididymis and the tail or lower end is attached only by areolar tissue near its lower end. Within the head the efferent ductules unite to form the canal of the epididymis which is coiled up within the body and the tail. When unraveled, it measures almost 20 feet in length. This duct emerges from the tail as the vas (ductus) deferens which ascends medial to the epididymis and enters the spermatic cord. The body and the tail of the epididymis can be separated easily from the testicle but the head must be severed at its efferent ductules.

SPERMATIC CORD

This appears as a long, rounded bundle which extends from the deep inguinal ring to the posterosuperior border of the testicle (Figs 485, 486 and 487). Within the abdomen its constituent parts are widely separated but from the deep inguinal ring to the testis they are wrapped together by the coverings of the cord. It is encased in three fibrous coats derived from the abdominal wall during the descent of the testis, namely, a continuation of the external abdominal oblique (the external spermatic fascia), a continuation of the internal abdominal oblique (the cremaster muscle), and a continuation of the transversalis fascia (the internal spermatic fascia). Plus this the two inner layers of the abdominal wall namely, peritoneum and properitoneal fat, are also present. In the fatty layer run the duct, the vessels and the nerves of the testis and the vessels and the nerves of the epididymis. These constituents of the cord assemble at

SURGICAL CONSIDERATIONS

VARICOCELECTOMY

A varicocele is a dilatation and varicose condition of the spermatic veins (primarily pampiniform plexus). It is more common on the

The ends of the severed veins are brought together, thus supporting the testicle. At least one large vein or group of veins remains so that some return venous flow is preserved.




FIG 488 Varicocelectomy

left than on the right side (p 644). The veins usually involved are the anterior group which surround the testicular artery. To perform the operation an incision is made low in the inguinal region (Fig 488). The spermatic cord is located at the external inguinal ring and drawn into the wound. The coverings of the cord are incised and the veins are exposed. Two thirds of the veins involved are doubly ligated, and the intervening segment is removed.

HYDROCELECTOMY

This operation is done for a collection of fluid which is found between the layers of the tunica vaginalis (vaginal hydrocele). Other types of hydrocele have been described (p 391). The usual operation performed is the so called 'bottle operation' (Fig 489). The incision is made through the skin, the dartos and the superficial fascia; it is placed directly in the scrotum and over the hydrocele. The testicle with

ward over the posterior wall of the abdomen. The right vein ends in the inferior vena cava; the left joins the left renal vein. In the lower part of the abdomen they are frequently double. On the right the vein empties into the inferior vena cava near

aorta and the inferior vena cava. In addition to the structures just discussed, a *cremasteric artery* exists; it arises from the inferior epigastric artery close to the deep inguinal ring and supplies the coverings of the cord.




FIG. 487 The blood supply of the testis and the constituents of the spermatic cord

the renal pedicle; on the left it enters the renal vein almost at a right angle. This fact explains the increased incidence of varicoceles on the left side as compared with the right.

The lymphatics of the cord and the testicle follow the spermatic vessels throughout their course and end in the external iliac glands or the lumbar nodes about the

The genital branch of the *genitofemoral nerve* (L 1 and 2) supplies the cremaster muscle and a sensory branch to the tunica vaginalis. *Sympathetic fibers* from the renal and the aortic plexuses carried by the testicular artery and from the pelvic plexus carried by the artery to the vas supply branches to the testis (T 10) and to the epididymis (T 11, 12 and L 1).

SECTION SEVEN

FEMALE PERINEUM AND
EXTERNAL GENITALIA




FIG 489 Hydrocelectomy




FIG 490 Circumcision

its tunica vaginalis are exposed, the fluid is aspirated and the tunica is opened. The parietal layer of the tunica vaginalis is excised partially but enough is permitted to remain so that it may be everted and sutured behind the testicle and the spermatic cord. In this way the secreting surface faces outward.

CIRCUMCISION

Before the operation is attempted, the

prepuce should be freed from the glans, since adhesions might be present and result in an unsatisfactory operation or injury to the glans. The redundant prepuce is placed on tension and amputated parallel with the corona. The redundant inner layer is mucous membrane and should be excised. The remaining tissue is folded back and sutured to the skin of the shaft of the penis. An alternate method of dorsal slit may be utilized (Fig 490).

Female Perineum

The *perineum* is a region at the inferior end of the trunk which is situated between the thighs and the lower part of the buttocks. It is a diamond shaped space at the angles of which are found the inferior pubic (treuate) ligament above, the tip of the coccyx below and the ischial tuberosities at each side. The pubic arch and the sacrotuberous ligaments form its sides, but the latter are hidden by the gluteus maximus muscles. If a line is drawn from the anterior part of one ischial tuberosity in front of the anus to the anterior part of the other tuberosity this diamond shaped area becomes conveniently divided into an anterior urogenital triangle and a posterior anal triangle (Fig. 491). The anal triangles are about the same in both sexes but the urogenital triangles differ. On the surface the urogenital triangle is bounded by the mons veneris in front, by the gluteal region (buttocks) behind and by the femoral region (thigh) at each side.

THE UROGENITAL REGION

EXTERNAL GENITALIA

The *mons veneris* is a cushionlike eminence on the front of the pubes. It is produced by a collection of fatty tissue under the skin (Figs. 491 and 492). It is covered with hair which ceases abruptly as the mons merges with the anterior abdominal wall.

The term *pudendum* (*vulva*) is a collective term which includes the labia majora, the labia minora, the body and the glans of the clitoris and the vaginal orifice. It extends from the pubes above to a point in front of the anus below.

The *labia majora* are homologous to the halves of the scrotum in the male. The line of the intervening vestibular or pudendal cleft between the two labia corresponds to the scrotal raphe. In nulliparae these labia are in contact with each other, and are therefore the only visible part of the external genitalia. Each labium is a broad rounded cutaneous fold which lies lateral to the labium minus and covers a long fingerlike process of fat. The two large labia are united below the mons veneris (mons pubis) and form the *anterior commissure*; they are connected posteriorly and form a narrower and less distinct *posterior commissure*. The outer convex surface is covered by ordinary skin and hair and is provided with numerous sebaceous glands, but the inner surface which lies against the opposite labium, possesses a more delicate skin with large sebaceous follicles. The elevation of the labium is produced by the presence of a diverticulum of fat which is a continuation of the superficial fat of the inguinal region. This fatty finger shaped process is demarcated from the surrounding fat in which it is embedded. It rests against the deep layer of superficial fascia.

The *labia minora* (*nymphae*) are cutaneous folds which lie medial to the labia majora (Fig. 492). The minor lips enclose the vestibule and in the young they are commonly concealed by the approximated majora. In older women and multiparae they are not infrequently pendulous and externally visible. They are shorter and thinner than the labia majora and become highest near their anterior end. The ante-




FIG. 493 The superficial anatomy of the urogenital region. On the right side (reader's left) the superficial layer of superficial fascia has been incised longitudinally to expose the continuation of the superficial inguinal fascia which appears as a fatty diverticular process; this process accounts for the labial elevation. On the left side (reader's right) the two layers of superficial fascia and the superficial musculature are demonstrated.

part of the body and the glans are visible when the labia minora are retracted since the labia and the mons hide the greater part of this structure.

The *estibule* of the vagina is the cleft which exists between the labia minora. It is a fissure which is placed anteroposteriorly and into which the urethral orifice opens above and the vaginal orifice below. On each side the entrance of the two minute ducts of the corresponding Bartholin glands are found.

The *urethral orifice* also has been referred to as the external urinary meatus; it appears as a vertical slitlike or ovoid opening about four or five mm in diameter. It is about one inch below the clitoris and the mucous membrane around its margin is somewhat prominent and puckered. A group of minute glands appear at each side of the lower part of the urethra and represent the homologue of the prostate gland in the male. On each side they group themselves to employ a common para urethral duct (Skene's) which passes downward in the submucous coat and opens at the sides of the orifice. They are of clinical impor-

tance because they may harbor infections.

The *aginal orifice* is nearer the posterior end of the vestibule and in the virgin is partially closed by the *hymen*. The latter is a duplication of mucous membrane which after rupture is represented by irregular projections into the vaginal orifice known as the hymenal caruncles (*carunculae myrtiformes*). The hymen is usually a thin vascular fold of mucous membrane which varies in shape and thickness and presents a central opening which can be stretched sufficiently to admit one examining finger without tearing. Whether the hymen is intact or torn it nevertheless persists anteriorly as a membranous band as it approaches and joins the tissues forming the urethral floor at the meatus. These bands become stretched and pull on the floor of the meatus when the vaginal introitus is dilated by digital examination or coitus. This is a feature of diagnostic importance especially in dyspareunia.

The *superficial perineal fascia* divides into two definite layers in the urogenital diaphragm: a superficial fatty layer and a deeper membranous one (Fig. 493). This

rior extremities each split into two layers, the upper of which meet above the clitoris to form its *prepuce* the lower layers become attached to the inferior aspect of the glans of the clitoris and form its *frenulum*. The labia minora diminish in size as they pass posteriorly and blend with the labia majora. In front of the posterior commissure they are connected by a transverse

fold of skin, the frenulum of the labia (fourchet). Immediately anterior to and above this fold, between it and the posterior limit of the vaginal orifice, a shallow depression is formed which is known as the *fossa navicularis*. The clitoris is hair free and resembles mucous membrane.

The *clitoris* is the female penis and lies at the apex of the vestibule. Only a small




FIG 491 The female perineum




FIG 492 The female external genitalia




FIG. 495 The three layers of the perineal musculature. (A) The first layer with its three superficial muscles. (B) The urogenital diaphragm. This diaphragm consists of an inferior layer of fascia, a deep transverse perineus muscle and a superior layer of fascia. The inferior fascial layer has been incised to show the relations. The deep transverse perineus muscle continues upward as the sphincter urethrae muscle. (C) The third layer consists of the puborectal portion of the levator ani muscle. It is necessary to cut through the urogenital diaphragm to visualize this structure.

ment and in vertical directions in the median plane pass the terminal portions of the urinary and the genital tracts.

The only portion of the clitoris which is visible when the labia are retracted is the small end known as the glans and a small part of its body. The other constituents of this erectile tissue with the investing musculature are in the superficial perineal compartment and are brought into view only when the deep layer of the superficial perineal fascia and the inferior perineal fascia are incised. The crus of the clitoris corresponds to the crus penis although much diminished in size. Like the male structure it is covered by the ischio-cavernosus muscle. The crura are continuous with the

corpora cavernosa at the lower part of the pubic symphysis. The crura are large in comparison with the corpora. On the symphysis each crus passes backward and laterally to taper at a point near the lower end of the ischium. It lies on the lower surface of the perineal membrane along the side of the pubic arch whose perineal surface is grooved to accommodate it. It is adherent to both the bone and the membrane and is hidden by the overlying ischio-cavernosus muscle. The laterally placed corpora cavernosa fuse anteriorly to form the small unpaired body of the clitoris. This is bent upon itself and tapers distally where it is covered by the glans. The clitoris is supplied with a suspensory liga-




FIG 494 Deeper dissection of the urogenital region. The contents of the superficial perineal pouch are shown. On the reader's right the inferior fascia of the urogenital diaphragm has been incised to show the relation of the deep transverse perineus muscle.

arrangement is a continuation of the two layers of superficial fascia of the anterior abdominal wall namely the superficial fatty layer of Camper and the deeper membranous layer of Scarpa.

The superficial layer of the superficial fascia is part of the general adipose panniculus which covers the entire body. Posteriorly it is continuous with the adipose tissue which fills the ischio-rectal fossa and anteriorly it is carried upward in front of the pubis as Camper's fascia. Where it covers the labia the fat is replaced by a very thin layer of involuntary muscle fibers which is the homologue of the dartos muscle in the male scrotum. Laterally it leaves the perineum and becomes continuous with the fatty tissue of the thigh. The deep layer of superficial perineal fascia is membranous and is a continuation of Scarpa's fascia of the abdomen but changes its name in this region to Colles' fascia. It is found only in the anterior half of the perineum and ends behind at a transverse line which joins the ischial tuberosities. At the side of the anterior urogenital triangle it ends by becoming firmly attached to the

ischio-pubic ramus and the ischial tuberosities. On the same plane, but laterally placed is the fascia lata of the thigh. The deep layer of superficial fascia joins the fascia of the urogenital diaphragm behind.

The superficial perineal pouch is a space or compartment which exists between the perineal membrane (p. 630) and the deep layer of the superficial perineal fascia. This space is bounded inferiorly by the membranous layer of fascia which forms its floor. It is bounded superiorly by the perineal membrane which forms its roof, and laterally by the side of the pubic arch between the attachments of these two membranes. It is closed posteriorly by their fusion. Anteriorly however, the pouch remains open and is continuous with that interval which exists between the superficial fascia of the anterior abdominal wall and the aponeurosis of the external oblique muscle, the interval being filled with areolar tissue. Each half of the pouch contains a crus of the clitoris, the bulb of the vestibule, the greater vestibular gland and the superficial perineal muscles, nerves, and vessels (Fig. 494). Through the compart




FIG 497 The pudendal nerve and its branches

The normal Bartholin glands are not palpable since they are covered by the bulb of the vestibule. When diseased, however, they are enlarged and become palpable at the junction of the posterior and the middle thirds of the vagina.

MUSCULATURE OF THE PERINEUM AND THE PELVIS

It is helpful to consider the perineal muscles as being arranged in three separate strata or layers (Fig 495). There is a superficial layer which consists of three muscles: the superficial transverse perineal, the bulbocavernosus and the ischio-cavernosus. The middle layer (urogenital diaphragm) consists of the sphincter of the urethra and the deep transverse perineal plus its fascia. The deep layer is the levator ani and the coccygeus which have been discussed elsewhere (p 556).

The *superficial transverse perineal muscle* lies along the base of the urogenital diaphragm; it is at times difficult to define and even may be absent. It is a slender

fasciculus which originates from the ramus of the ischium close to the tuberosity, passes medially and inserts into the perineal body at which point it fuses with its fellow of the opposite side (Fig 495). Posteriorly it lies against the external sphincter of the anus; anteriorly, it almost reaches the posterior wall of the vagina. If visible it is a good surgical landmark, since the pudendal nerve and artery wind around its posterior border to turn upward and reach the urogenital region. At this point the nerve may be blocked for surgical and obstetric procedures as well as for the relief of pruritus vulvae.

The *ischio-cavernosus muscle* arises from the medial aspect of the ischium close to its tuberosity, extends forward over the crus and becomes aponeurotic. As these fibers pass upward they ensheath and insert into the medial and the inferior surfaces of the crus and extend as far forward as the body of the clitoris. These two muscles compress the crura, thereby retarding the flow of blood and assisting in the maintenance of an erection of the clitoris.




FIG 496 The internal pudendal artery and its branches

ment which passes upward to the symphysis and onto the anterior abdominal wall. The glans like the homologous male organ has a frenum and a prepuce.

The *bulb of the vestibule* corresponds to the bulb of the penis but because of the presence of the vagina it has become a bilateral structure (Fig 494). These appear as two oblong masses of erectile tissue which lie on the inferior aspect of the perineal membrane and in contact with the lateral walls of the vagina. They are covered by the bulbocavernosus muscles and where they are in close contact with the Bartholin glands they are rounded. In front where they pass to the sides of the urethra and unite near the body of the clitoris they are pointed. The two halves are united in front of the urethra by a venous plexus called the *pars intermedia*.

The muscles which cover the bulb and the superficial and deep transverse perineal muscles plus the external sphincter of the

anus converge to a central point. This is a musculotendinous point which is located in the midline of the perineum anterior to the anus at the posterior limit of the superficial perineal compartment. The fibers of this musculotendinous portion plus the tissue between the anal and the vaginal canals, constitute the *perineal body*.

The *greater vestibular glands* (Bartholin's) correspond to the bulbo urethral (Cowper's) glands of the male but differ in position and in the termination of their ducts. They are about one cm in length and lie on the side of the lowest part of the vagina under cover of the posterior part of the bulb. The long axis of the gland is transverse. The duct follows an oblique course passing anteromedially and opening into the vestibule, one on each side of the fossa navicularis. Their orifices are macroscopically visible just external to the hymen near the middle of the vaginal orifice (Figs 492 and 494).




FIG 497 The pudendal nerve and its branches

The normal Bartholin glands are not palpable since they are covered by the bulb of the vestibule. When diseased, however, they are enlarged and become palpable at the junction of the posterior and the middle thirds of the vagina.

MUSCULATURE OF THE PERINEUM AND THE PELVIS

It is helpful to consider the perineal muscles as being arranged in three separate strata or layers (Fig 495). There is a superficial layer which consists of three muscles: the superficial transverse perineal, the bulbocavernosus and the ischio cavernosus. The middle layer (urogenital diaphragm) consists of the sphincter of the urethra and the deep transverse perineal plus its fascia. The deep layer is the levator ani and the coccygeus which have been discussed elsewhere (p 556).

The *superficial transverse perineal muscle* lies along the base of the urogenital diaphragm; it is at times difficult to define and even may be absent. It is a slender

fasciculus which originates from the ramus of the ischium close to the tuberosity, passes medially and inserts into the perineal body at which point it fuses with its fellow of the opposite side (Fig 495). Posteriorly, it lies against the external sphincter of the anus; anteriorly, it almost reaches the posterior wall of the vagina. If visible it is a good surgical landmark, since the pudendal nerve and artery wind around its posterior border to turn upward and reach the urogenital region. At this point the nerve may be blocked for surgical and obstetric procedures as well as for the relief of pruritus vulvae.

The *ischioanal muscle* arises from the medial aspect of the ischium close to its tuberosity; it extends forward over the crus and becomes aponeurotic. As these fibers pass upward they ensheath and insert into the medial and the inferior surfaces of the crus and extend as far forward as the body of the clitoris. These two muscles compress the crura, thereby retarding the flow of blood and assisting in the maintenance of an erection of the clitoris.

are smaller than the corresponding muscles of the male

The *bulbocavernosus muscle* has also been referred to as the *bulbospongiosus* and the *sphincter vaginae*. In the male, the *bulbocavernosus* is a single structure, but in the female it is halved symmetrically by the vestibule and each side becomes closely related to the lateral surface of the vestibular bulbs. The fibers originate from the central tendinous point, separate pass forward on the walls of the vestibule and converge toward the midline in front, where they are attached to the body of the clitoris. They cover the bulbs of the vestibule and act as constrictor muscles of the erectile tissue as does the *ischiocavernosus*.

The three superficial perineal muscles are supplied by the perineal branch of the pudendal nerve.

THE UROGENITAL DIAPHRAGM

The urogenital diaphragm (triangular ligament) consists of two layers of fascia with two intervening muscles. The lower layer of fascia is the inferior layer and the upper layer constitutes the superior fascia. The interposed muscles are the deep transverse perineal and the sphincter urethrae membranaceae. The space between the two layers of fascia not only contains the deep transverse perineal muscles but also encloses the space which is called the second or the deep compartment of the perineum (Figs 494, 495, 496 and 497).

The *inferior layer (perineal membrane)* of the urogenital diaphragm is the more superficial of the two fascial layers and forms the roof of the superficial and the floor of the deep perineal compartments laterally, it attaches to the ischiopubic rami. Medially it is attached to the sides of the vagina. Posteriorly, the two halves of the membrane join behind the vagina. Their posterior borders fuse with the posterior borders of the fascia above the deep transversus and the membranous layer of the superficial fascia. This fusion closes the deep perineal pouch posteriorly. Anteriorly,

the halves meet in front of the vagina and the urethra, and their borders fuse with the anterior borders of the fascia above the sphincter urethrae. The fused anterior borders are thickened to form a band called the transverse ligament of the perineum, this is separated from the inferior ligament of the pubis by an oval interval which transmits the dorsal vein of the clitoris. The inferior layer of fascia is pierced in the midline by the urethra, the vagina, to either side by the internal pudendal vessels and the pudendal nerves, and by branches of these to the erectile tissue of the bulb, the crus and the glans.

The *superior layer* of the urogenital diaphragm (upper lamina) also has been referred to as the deep layer of the triangular ligament (Fig 481). It forms the roof of the deep perineal compartment and the floor of the anterior extension of the ischio-rectal fossa on either side of the midline. It is derived from the parietal layer of the pelvic fascia. Anteriorly conjoined with the inferior layer, it forms the transverse ligament of the pelvis, behind, it again becomes continuous with the inferior layer around the deep transverse perineal muscles and by means of this fusion attaches to the deep layer (Colles') of superficial fascia. At the sides it meets the obturator fascia. Medially and above, it joins the fascial coverings on the under surface of the levator ani muscle.

The *deep perineal compartment* is the pouch which exists between the two layers of deep fascia of the urogenital diaphragm of the perineum. It contains the deep transverse perineal muscle, the sphincter muscle surrounding the membranous portion of the urethra and the pudendal vessels and nerves (Fig 496).

The *sphincter muscle of the membranous urethra (sphincter urethrae membranaceae)* is not named entirely correctly since it would indicate that it is related only to the urethra, but in reality it sends fibers to the vaginal and the anal canals as well. The muscles arise on each side from the

ischio pubic rami and as they approach the midline an anterior group passes to the urethra almost reaching the inferior margin of the symphysis pubis. More posteriorly a group becomes implanted into the urethra similarly a group of fibers is related to the vagina the postvaginal group crosses transversely behind the vaginal canal between it and the anus.

The *deep transverse perineal muscle* is the backward continuation of the sphincter urethrae (Figs 494 and 495). It appears as a triangular prolongation which passes backward deep to the coccygeal extension of the external anal sphincter and surrounds the anal canal. The fibers of the two sides which originate at the junction of the ischial and the pubic rami are inserted into the tip of the coccyx. While both of these muscles may have some sphincteric function the main function of the urogenital musculature is to support the pelvic organs. They are supplied by the perineal nerve.

Between the two layers of fascia the following structures are found: the membranous urethra, the sphincter urethrae, the vagina, the internal pudendal arteries, arteries to the bulb and the dorsal nerve to the clitoris. In the female the greater vestibular glands (Bartholin) do not lie between the two layers of fascia but beneath the inferior layer so that the ducts (bulbo urethral glands) do not have to pierce this fascia as they do in the male.

In the urogenital half of the perineum and above the superior layer of urogenital fascia a fat filled *ischio rectal fossa* (*anterior recess*) extends forward for two inches on either side. This space resembles a triangular prism. The lateral boundary is formed by the parietal fascia which covers the obturator internus muscle; the superior boundary is the inferior fascia of the pelvic diaphragm which covers the under surface of the levator ani muscle and the inferior boundary is the superior fascia of the urogenital diaphragm.

THE PELVIC DIAPHRAGM

This diaphragm consists of the levator ani and the coccygeus muscles plus the fascia which invests their perineal and pelvic surfaces. From the pelvic wall on either side these muscles pass downward toward the midline where they fuse or surround the terminal portions of the anus, the vagina and the urethra (Fig. 403). The inferior layer of fascia which covers this muscular diaphragm also is referred to as the anal or the ischio rectal fascia; the superior layer is called the visceral layer of diaphragmatic fascia (p. 557).

The *internal pudendal artery* leaves the lesser pelvis to enter the gluteal region by passing through the lower part of the greater sciatic foramen between the piriformis and the coccygeus muscles (Fig. 496). After turning around the spine of the ischium it reaches the anal part of the perineum by passing through the lesser sciatic foramen, then it passes along the lateral wall of the ischio rectal fossa where it is accompanied by its venae comites and the pudendal nerve. In this location the artery lies in an aponeurotic canal known as Alcock's canal (Fig. 496 B). In the fossa the artery at each side gives off the inferior hemorrhoidal artery which passes medially through the fatty tissue of the fossa to supply the anus and the anal canal. It also supplies the superficial fascia, the skin of the perineum and the skin and the musculature of the gluteal region.

The main stem of the vessel continues upward, leaves the anal triangle and enters the urogenital triangle. It supplies the following branches (Fig. 496): small posterior labial branches which are distributed to the skin and the fatty tissue of the labia; the perineal artery arises within the ischio rectal fossa, passes forward and medialward to enter the superficial perineal pouch by passing either over or under the perineal muscle (within this compartment it supplies the three muscles of the superficial pouch, namely the ischiocavernosus, the bulbocavernosus and the superficial trans-

verse perineal) the clitoridal branch of the perineal artery enters the deep perineal compartment by piercing the base of the urogenital diaphragm continues forward in the substance of the urethral sphincter muscle which it supplies and ends in terminal branches known as the deep and the dorsal arteries of the clitoris. These branches also supply the erectile tissue of the superficial perineal compartment.

The dorsal vein of the clitoris occupies a groove in the medial line with the dorsal artery and nerve lying on each side of it. It corresponds to the deep dorsal vein of the penis. It takes origin in the glans, passes backward and at the root of the clitoris passes between the transverse ligament of the perineum and the inferior pubic ligament. It continues upward into the pelvis to join the plexus of veins on the wall of the vagina in the region of the neck of the bladder. Communication is also made with the internal pudendal vein.

The *pudendal nerve* is the chief source of innervation to the muscles and the skin of the perineum (Fig. 497). The nerve on each side represents a smaller part of the pudendal plexus (the larger part constituting the sciatic nerve). It is derived from the anterior rami of S 2, 3 and 4 and accompanies the internal pudendal artery and vein leaving the pelvis through the greater sciatic foramen and entering the ischiorectal fossa through the lesser sciatic foramen. As the nerve enters the ischiorectal fossa it gives off the *inferior hemorrhoidal nerves*, which accompany the vessels of the same name medialward to supply the external sphincter ani muscle and the skin around the anus. Near the posterior margin of the urogenital diaphragm the pudendal nerve divides into its two terminal branches, namely the perineal nerve and the dorsal nerve of the clitoris. The *perineal nerve* sends superficial branches forward; they enter the superficial perineal compartment as the *posterior labial nerves*. These are accompanied by the arteries of the same name to the skin of the labia and the anterior

part of the perineum. The deep division of the nerve is muscular and supplies the muscles in the anal and the urogenital portions of the perineum. In the anal triangle, fibers are sent to the levator ani and the external anal sphincter; the nerve then pierces the base of the urogenital diaphragm, enters the deep perineal compartment and supplies the deep transverse perineal muscle and the urethral sphincter. Other fibers supply the superficial transverse perineal, the ischiocavernosus and the bulbocavernosus. The *dorsal nerve of the clitoris* enters the deep compartment at the anterior end of Alcock's canal. It is accompanied by the dorsal artery; it traverses this space and pierces the inferior fascia of the urogenital diaphragm to travel forward on the dorsum of the clitoris to the glans. It supplies the erectile tissue. The integument of the perineum has an additional nerve supply which will be discussed with the individual nerves appearing in this region.

THE ANAL TRIANGLE

This triangle is bounded behind by the coccyx on each side by the ischial tuberosities and the sacrotuberous ligament which are overlapped by the lower borders of the gluteus maximus muscles (Fig. 491). In the midline, it contains the lower part of the anal canal and the external sphincter ani muscle; on each side it includes the ischiorectal fossae.

Each *ischiorectal fossa* is prismatic in shape and lies below the lateral part of the pelvic diaphragm (Fig. 405). Its roof is formed by the levator ani, the origin of that muscle from the fascia covering the parietal pelvic muscles separates the fossa from the pelvic cavity. Its lateral wall is formed by the lower part of the obturator internus muscle and its fascia. In the posterior part of this wall the fascia interrupts communications with the gluteal region through the lesser sciatic foramen. Posteriorly the fossa is limited by the sacrotuberous ligament; anteriorly, the base of the perineal ligament intervenes between

the fossa and the urogenital triangle. The medial wall is formed by the anal canal and the levator ani muscle. Anteriorly, the fossa does not end at the base of the urogenital diaphragm but continues forward laterally between the urogenital and the pelvic diaphragms into the urogenital part of the perineum. The cavity is about two inches long, two inches deep and one inch wide. Under the skin is a large fat pad which fills the fossa. This fat fulfills an important supporting function since it assists in holding the rectum in place. Should it disappear, as occurs in wasting diseases, the rectum may prolapse and protrude through the anus.

The deep fascia is not directly under the skin in this region because of the intervening fat. This fascia was studied in detail by Elliott Smith who gave it the name of 'fascia lunata' (Fig. 496 B). Medially, it covers the levator fascia (anal fascia) and ends at the lower end of the levator. Laterally, it covers the obturator fascia and is attached to the ischium. The internal pudendal vessels and nerves are between these two layers. It has been argued therefore, that Alcock's canal is not formed by a division of the obturator fascia but is really that space which exists between the obturator fascia and the fascia lunata. Anteriorly, the fascia fuses with the urogenital diaphragm. Superiorly, it arches upward, at which point it is called the tegmentum (Fig. 403). The space which exists between this tegmen and the apex of the fossa is called the supratsegmental space; it is devoid of fat.

The levator ani arises from the pubic bone anteriorly, the ischial spine posteriorly, and the obturator fascia between these two points. At times, however, it arises from the tendinous ring which is attached only to the bone in front and behind and not to the fascia between. This results in a space between its two points of origin. This gaping space is known as the *hiatus of Schaalbe* (Fig. 405). The practical importance of the hiatus is that a process of




FIG. 498 Descent of the uterus, cystocele and rectocele. (A) Normal uterine supports. (B) Failure of the normal uterine supports.

pelvic peritoneum may be pushed through it into the supratsegmental space, resulting in a hernia into the ischio-rectal fossa. The coverings of the hernia would be the tegmentum of the fascia lunata, the ischio-rectal fat pad and the skin.

The external sphincter ani muscle surrounds the margin of the anal canal and consists of three parts: subcutaneous, superficial, and deep. The subcutaneous portion of the external sphincter is the only muscle which surrounds the anal orifice proper. The superficial and deep portions of the muscle surround the anal canal.




FIG 499 Vaginal hysterectomy

The adjacent fibers of the deep external sphincter intermingle with those of the puborectal portion of the levator ani. Partial division of the muscle usually leaves a competent sphincter but a complete

SURGICAL CONSIDERATIONS

VAGINAL HYSTERECTOMY

This operation is usually done for pro-
cedentia and for prolapse of moderate de-




FIG 500 Repair of a cystocele (A) Sagittal view of the cystocele (B through F) The repair

perineal tear results in a sphincteric incontinence. The muscle has been described in detail elsewhere (p. 482).

The *anococcygeal body* consists of the posterior fibers of the external sphincter and a backward extension of the deep perineal muscles and the median strip of the pubococcygeal part of the levator ani (Fig. 474). It is an important unit in the perineum and injury to it may result in the loss of the essential elements of visceral suspension and support.

gree associated with cystocele and rectocele (Fig. 498). Prolapse of the uterus results from a failure of the supporting structures to hold the uterus in place. These supporting structures are the round ligaments, the uterosacral ligaments, the bases of the broad ligaments (Mackenrodt), the pelvic floor and the fascia surrounding the vagina. Vaginal hysterectomy is performed in the following way: the lips of the cervix are sewn together or grasped with a tenaculum for the purpose of trac-




FIG 501 Repair of a rectocele (A) Sagittal view of the rectocele (B through E) The repair




FIG 502 Posterior colpotomy (A) The cervix is drawn upward and an incision is placed in the vaginal mucosa (B) A sagittal section showing the location of pus or blood in the recto-uterine cul de sac (Douglas)

tion (Fig 499) A circular incision is made around the cervix in such a way that the bladder is not injured. The anterior vaginal wall is freed and the bladder is dissected off of the anterior surface of the cervix until the vesico-uterine peritoneum is identified. With the bladder retracted upward the vesico-uterine peritoneum is opened, and the index and the middle fingers of the left hand are introduced into the peritoneal cavity (Fig 499 C). The fingers depress the fundus and the peritoneal opening is extended laterally on each side as far as the broad ligament. The fundus is delivered as the fingers in the peritoneal cavity push the peritoneum forward over the pouch of Douglas. An incision is made over this finger and the peritoneal cavity is entered posterior to the cervix. The peritoneum is incised as far as the uterosacral ligaments on each




FIG 503 Repair of a vesicovaginal fistula

side. These ligaments are clamped, divided, and ligated. Hemostats then are placed at the top of the broad ligament in the region of the cornu of the uterus and they grasp the round ligament and the adnexal attachments. Similar clamps are placed at the base of the broad ligament; these secure the uterine vessels. The tissue between these clamps is divided. It is best to carry this out on the left side first and replace the clamps by transfixion sutures (Fig 499 F). The uterus then can be rotated outward so that it remains attached only on the right side and a similar procedure is carried out here. The peritoneum of the

pouch of Douglas and the bladder are approximated by interrupted sutures, the stump of the adnexae remain extraperitoneal. The vaginal flaps are closed by interrupted sutures and a slight opening is permitted to remain for drainage, if desired.

REPAIR OF CYSTOCELE (ANTERIOR COLPORRHAPHY)

The limits of the bladder should be identified by a sound or a catheter placed in the urethra and carried down toward the cervix. Also the presence or absence of a urethrocele should be noted. Through a short transverse incision a cleavage plane is




FIG 504 Repair of a rectovaginal fistula

found between the vaginal wall and the bladder (Fig 500). The vaginal wall is dissected laterad on each side and separated from the underlying musculofascial tissue; this tissue is chiefly the urogenital diaphragm (Fig 500 C). The bladder is separated from the cervix and the pillars on each side are cut; this permits upward displacement of the bladder (Fig 500 D). Mattress type sutures are placed from side to side in the tissue of the urogenital diaphragm but are placed lateral to the urethra. With the bladder held in an upward direction sutures are placed through the lateral musculofascial tissue and through the uterus. In this way the herniation of the bladder is corrected. The redundant vaginal flaps are trimmed and approximated with interrupted sutures.

REPAIR OF RECTOCELE (PERINEORRHAPHY)

Clamps are applied slightly within the mucocutaneous junction on each side at the carunculae myrtiformes (Fig 501). Outward traction is made on the clamps, and the skin and the mucous membrane are divided along this line. The posterior vaginal wall is separated from the rectal wall. This

dissection is carried in an upward direction and extends above the upper margin of the rectocele. The puborectal portions of the levator ani muscles are identified and sutured, thus, a musculofascial bridge which keeps the herniated rectum in place is formed. The uppermost suture grasps the under surface of the vaginal wall. If the torn fascia of the urogenital diaphragm is visible, this too is sutured as a separate layer over the levator. Skin sutures are placed.

POSTERIOR COLPOTOMY

This is usually used in the treatment of pelvic abscess or as a diagnostic method in ruptured ectopic pregnancy. Tenacula are applied to the cervix to pull it upward and forward, and an incision about an inch and a half in length is made in the mucous membrane at the junction of the posterior vaginal wall and the cervix (Fig 502). The underlying tissue is divided with scissors; the points of which are directed toward the cervix. When the abscess cavity has been entered a finger is inserted to explore, and the opening is enlarged sufficiently so that drainage may be instituted.

VESICOVAGINAL FISTULAE

Birth injuries, surgery, radium burns, and carcinoma are the chief causes of such fistulae. Reich and Wilkey have described a combined gynecologic and urologic technique to treat this condition. The cystoscopist passes a ureteral catheter into the bladder via the urethra and then through the fistula into the vagina (Fig 503). An incision is made in the vaginal wall, and the bladder is freed. A purse string suture is placed and tightened simultaneously with upward withdrawal of the catheter. Reinforcing sutures and repair complete the procedure.

RECTOVAGINAL FISTULAE

These fistulae may result from carcinoma of the cervix or the rectum; the repair of

a complete perineal laceration, and operations for abscesses and fistulae in ano. Smaller fistulae above the level of the sphincter ani may be closed according to

the technic of V C David. A circular incision is made around the fistula, and the fistulous tract is inverted into the rectum (Fig. 504).

SECTION EIGHT

THE SUPERIOR EXTREMITY

Shoulder

The shoulder is topographically divided into the axillary the pectoral the deltoid and the scapular regions

The cutaneous nerve supply of this region is derived from the supraclavicular the axillary the medial antibrachial cutaneous, the medial brachial cutaneous and the intercostobrachial nerves (Fig. 505)

AXILLARY AND PECTORAL REGIONS

The *axilla* is an anatomic pyramid situated between the medial side of the upper arm and the upper lateral side of the chest wall. Since it is pyramidal in shape, it consists of four walls, an apex and a base.

The *four walls* are the anterior the posterior the medial and the lateral (Fig. 506). The *anterior (pectoral) wall* is composed of a superficial layer (pectoralis major muscle with its enveloping fascia) and an inner or deeper layer (pectoralis minor and subclavius muscles with their enveloping clavipectoral fascia). The *posterior (scapular) wall* is formed by the scapula which is covered by the subscapularis the latissimus dorsi and the teres major muscles. The *medial (costal) wall* consists of the upper ribs (second to sixth) and the serratus anterior muscle. The *lateral (humeral) wall* is formed by the humerus (bicipital groove). This groove lodges the long head of the biceps tendon and its lips give attachment to the muscles of the anterior and the posterior axillary walls. The long head of the biceps tendon is covered by the short head of the biceps and the coracobrachialis.

The *axillary apex* is blunted and triangu-

lar and is bounded by three bones anteriorly by the *clavicle*, posteriorly by the upper border of the *scapula* and medially by the *first rib*. The base of the axilla made up of skin subcutaneous tissue and *axillary fascia* the latter extending from the lower border of the pectoralis major muscle to the latissimus dorsi (Fig. 507). Occasionally a small strip of muscle extends from the latissimus dorsi to the structures deep to the pectoralis major, it forms the anomalous axillary arch.

There are two *fasciae* in the pectoral region namely, the pectoral fascia proper and the clavipectoral fascia (Fig. 508).

The *pectoral fascia proper* (Fig. 508) is attached above to the anterior superior aspect of the clavicle. It passes down and ensheathes the pectoralis major muscle and then blends with the axillary fascia in the floor of the axilla. Medially it is attached to the sternum and is continuous below and medially with the serratus anterior and the external oblique muscles. Laterally it blends with the fascia of the arm. The *clavipectoral fascia* lies deep to the pectoral fascia proper (Fig. 508). Vertically it extends from the clavicle above to the dome of the axillary fascia below, thereby acting as a *suspensory ligament* for the axillary fascia. It is interrupted in its vertical path by the subclavius and the pectoralis minor muscles, both of which it separates and encloses. That portion of the clavipectoral fascia which lies between the subclavius and the pectoralis minor muscles is called the *costocoracoid ligament (membrane)*. It is attached laterally to the coracoid process and medially to the first and the second

Shoulder

The shoulder is topographically divided into the axillary, the pectoral, the deltoid and the scapular regions.

The cutaneous nerve supply of this region is derived from the supraclavicular, the axillary, the medial antibrachial cutaneous, the medial brachial cutaneous and the intercostobrachial nerves (Fig. 505).

AXILLARY AND PECTORAL REGIONS

The *axilla* is an anatomic pyramid situated between the medial side of the upper arm and the upper lateral side of the chest wall. Since it is pyramidal in shape, it consists of four walls, an apex and a base.

The *four walls* are the anterior, the posterior, the medial and the lateral (Fig. 506). The *anterior (pectoral) wall* is composed of a superficial layer (pectoralis major muscle with its enveloping fascia) and an inner or deeper layer (pectoralis minor and subclavius muscles with their enveloping clavipectoral fascia). The *posterior (scapular) wall* is formed by the scapula, which is covered by the subscapularis, the latissimus dorsi and the teres major muscles. The *medial (costal) wall* consists of the upper ribs (second to sixth) and the serratus anterior muscle. The *lateral (humeral) wall* is formed by the humerus (bicipital groove). This groove lodges the long head of the biceps tendon, and its lips give attachment to the muscles of the anterior and the posterior axillary walls. The long head of the biceps tendon is covered by the short head of the biceps and the coracobrachialis.

The *axillary apex* is blunted and triangu-

lar and is bounded by three bones: anteriorly by the *clavicle*, posteriorly by the upper border of the *scapula* and medially by the *first rib*. The base of the axilla is made up of skin, subcutaneous tissue and *axillary fascia*, the latter extending from the lower border of the pectoralis major muscle to the latissimus dorsi (Fig. 507). Occasionally a small strip of muscle extends from the latissimus dorsi to the structures deep to the pectoralis major, this forms the anomalous axillary arch.

There are two *fasciae* in the pectoral region, namely, the pectoral fascia proper and the clavipectoral fascia (Fig. 508).

The *pectoral fascia proper* (Fig. 508 B) is attached above to the anterior superior aspect of the clavicle; it passes down to ensheath the pectoralis major muscle and then blends with the axillary fascia in the floor of the axilla. Medially it is attached to the sternum and is continuous below and medially with the serratus anterior and the external oblique muscles. Laterally, it blends with the fascia of the arm. The *clavipectoral fascia* lies deep to the pectoral fascia proper (Fig. 508). Vertically it extends from the clavicle above to the dome of the axillary fascia below, thereby acting as a *suspensory ligament* for the axillary fascia. It is interrupted in its vertical path by the subclavius and the pectoralis minor muscles, both of which it separates and encloses. That portion of the clavipectoral fascia which lies between the subclavius and the pectoralis minor muscles is called the *costocoracoid ligament (membrane)*; it is attached laterally to the coracoid process and medially to the first and the second

costal cartilages. The suspensory ligament is that part of the clavipectoral fascia which lies between the pectoralis minor and the axillary fascia. The costocoracoid ligament is pierced by the cephalic vein, which drains into the axillary vein, the

of the coracoid process of the scapula. The coracoid lies one inch below the clavicle, barely covered by the anterior border of the deltoid muscle. The pectoralis minor is covered by the pectoralis major, which lies on the same plane as the deltoid muscle




FIG 505 The cutaneous nerve supply of the shoulder
(A) anterior view, (B) posterior view

thoracoacromial artery, a branch of the axillary artery; the anterior thoracic nerves to the pectoral muscles; and lymph vessels from the upper outer quadrant of the breast.

The *pectoralis minor muscle* is the key structure to the axillary and the pectoral regions; its position and relations to the brachial plexus and the axillary vessels are important surgically (Fig 509). The pectoralis minor is a triangular muscle which has its origin from the third, the fourth and the fifth ribs near their costochondral junctions, and its insertion on the medial border

of the *deltoid process* of the scapula. The coracoid lies one inch below the clavicle, barely covered by the anterior border of the deltoid muscle. The pectoralis minor is covered by the pectoralis major, which lies on the same plane as the deltoid muscle. The *deltopectoral groove* is situated between the deltoid and the pectoralis major muscles. The *cephalic vein* runs in this groove, crosses the anterior surface of the pectoralis minor muscle and pierces the costocoracoid membrane before emptying into the axillary vein. The cephalic vein is an important surgical guide to the axillary vein and the axillary artery, and it acts as a compensatory vein when the axillary vein has no longer function.

If the pectoralis minor muscle is severed and reflected downward with its clavipectoral fascia, the axillary vessels and the




FIG. 506 The four walls of the axilla

The axilla is pyramidal in its shape hence it has an anterior (pectoral) wall a posterior (scapular) wall a medial (costal) wall and a lateral (humeral) wall. The various walls and views are depicted.

brachial plexus do not immediately come into view because they are covered by a connective tissue layer known as the *axillary sheath*. This is a lateral prolongation of the prevertebral layer of fascia that travels down the arm as far as the elbow (Fig. 510). The fascia passes over the scapular muscles; the brachial plexus and the sub



FIG. 507 The axillary fascia

costal cartilages. The suspensory ligament is that part of the clavipectoral fascia which lies between the pectoralis minor and the axillary fascia. The costocoracoid ligament is pierced by the cephalic vein, which drains into the axillary vein; the

of the coracoid process of the scapula. The coracoid lies one inch below the clavicle, barely covered by the anterior border of the deltoid muscle. The pectoralis minor is covered by the pectoralis major, which lies on the same plane as the deltoid muscle.




FIG. 505 The cutaneous nerve supply of the shoulder (A) anterior view, (B) posterior view

thoracoacromial artery, a branch of the axillary artery; the anterior thoracic nerves to the pectoral muscles; and lymph vessels from the upper outer quadrant of the breast.

The *pectoralis minor* muscle is the key structure to the axillary and the pectoral regions, its position and relations to the brachial plexus and the axillary vessels are important surgically (Fig. 509). The *pectoralis minor* is a triangular muscle which has its origin from the third, the fourth and the fifth ribs near their costochondral junctions, and its insertion on the medial border

of the *deltopectoral groove* is situated between the deltoid and the *pectoralis major* muscles. The *cephalic vein* runs in this groove, crosses the anterior surface of the *pectoralis minor* muscle and pierces the *costocoracoid* membrane before emptying into the axillary vein. The *cephalic vein* is an important surgical guide to the axillary vein and the axillary artery, and it acts as a compensatory vein when the axillary can no longer function.

If the *pectoralis minor* muscle is severed and reflected downward with its clavipectoral fascia, the axillary vessels and the




FIG. 506 The four walls of the axilla. The axilla is pyramidal in its shape hence it has an anterior (pectoral) wall a posterior (scapular) wall a medial (costal) wall and a lateral (humeral) wall. The various walls and views are depicted.

brachial plexus do not immediately come into view because they are covered by a connective tissue layer known as the *axillary sheath*; this is a lateral prolongation of the prevertebral layer of fascia traveling down the arm as far as the elbow (Fig. 510). The fascia passes over the scalenus muscles, the brachial plexus and the sub-




FIG. 507 The axillary region.




FIG 508 The clavipectoral fascia (A) Seen from in front after reflecting the pectoralis major muscle (B) Sagittal section the pectoral fascia is also shown


clavian artery. On leaving the neck on their way to the axilla these vessels and nerves pierce this fascia and carry a tubular sheath of it along with them.

AXILLARY VESSELS

The *axillary vein* is the first structure to appear following incision into the axillary sheath (Fig 509). It is formed by the junction of three veins of the superior extremity: the two venae comites of the brachial artery (the *brachial veins*) and the basilic vein, which pierces the deep fascia in the middle of the arm. The axillary vein

begins at the lower border of the teres major muscle and continues to the outer border of the first rib where it becomes the subclavian vein. The latter joins the internal jugular to form the innominate vein. Sometimes the union of the basilic and the brachial veins does not take place until the clavicle is reached; in such instances a single trunk axillary vein may not exist or may be very short.

When the arm is abducted, the vein covers the axillary artery and conceals it. This intimate relationship between the artery and the vein explains the not too-



infrequent appearance of arteriovenous aneurysms in this region. The tributaries of the axillary vein correspond to the branches of the axillary artery.

The *axillary artery* is a continuation of the subclavian and is about six inches in length (Fig. 509). It starts at the outer border of the first rib and ends at the lower border of the *teres major* muscle, where it becomes the *brachial artery*. The *pectoralis minor* muscle divides the axillary artery into three parts (Fig. 511). The first part lies proximal to the *pectoralis minor* muscle under the *costocoracoid* membrane and has one branch, the highest or superior thoracic artery. The second part lies behind the *pectoralis minor* muscle; is the shortest part and has two branches, the *thoraco-acromial* and *lateral thoracic* arteries. The third part lies distal to the *pectoralis minor* muscle; is the longest part

FIG. 509 The *pectoralis minor* muscle and its relations. The *pectoralis major* muscle has been reflected and the *clavipectoral* fascia has been removed. The axillary vein lies medial to the axillary artery and the *brachial plexus* appears to be wrapped around the artery.




FIG. 510 The axillary sheath. The prevertebral layer of deep cervical fascia gives off a fascial process which is continuous down the arm as the axillary sheath.




Fig 511 The three parts of the axillary artery. The pectoralis minor muscle divides the axillary artery into three parts.

and has three branches: the subscapular, the anterior humeral circumflex, and the posterior humeral circumflex arteries. It is well to remember that part one has one branch, part two has two branches, and part three has three branches.

The superior thoracic artery is the first branch of the axillary artery and the only branch of part one. It is usually small, runs medially, and supplies the muscles of the first two intercostal spaces. The thoracoacromial artery arises from the second part as a very short trunk but is of considerable size. Winding around the upper border of the pectoralis minor muscle, it pierces the costocoracoid membrane and divides into four branches: the pectoral, the acromial, the deltoid, and the clavicular. The deltoid branch accompanies the ce-

phalic vein in the deltopectoral groove. The lateral thoracic artery also arises from the second part of the axillary artery but it follows the lower border of the pectoralis minor muscle to the chest wall. It does not accompany the long thoracic nerve as is commonly thought. The latter is found with the terminal part of the subclavian artery. The subscapular artery is the largest branch of the axillary artery. It arises near the lower border of the subscapularis muscle, along which it descends, accompanied by its venae comites (Fig 509). The subscapular artery supplies the posterior axillary wall (subscapularis, teres major, and latissimus dorsi muscles). Although it is the vessel of the posterior wall, it terminates on the medial wall (serratus anterior muscle). Branches of this artery




FIG 512 The brachial plexus The formula for the plexus may be presented as follows
 5 roots (roots) = 3 trunks = 6 divisions = 3 cords = the nerve supply (branches) to the superior extremity

accompany the nerve supply to the subscapularis the teres major and the latissimus dorsi muscles. The nerve to the latissimus dorsi muscle is the thoracodorsal hence that part of the subscapular artery which runs with it is called the *thoracodorsal artery*. The terminal branches of the subscapular artery send twigs to the serratus anterior muscle and here the artery is accompanied by the nerve supply to that muscle (the long thoracic nerve). The subscapular artery also gives rise to the circumflex scapular artery which passes through the triangular space on its way to the dorsum of the scapula. *Anterior and posterior circumflex humeral arteries* form an arterial ring around the surgical neck of the humerus. The anterior lies behind

the biceps and the coracobrachialis muscles and the posterior accompanies the axillary nerve through the quadrilateral space to reach the deep aspect of the deltoid muscle (Fig 537). The three branches of the third part of the axillary artery may arise from a common trunk.

BRACHIAL PLEXUS

To visualize the brachial plexus as a whole it must be followed from its origin in the neck, through the axilla and into the superior extremity (Figs 512 and 513).

The following facts should be kept in mind to understand the brachial plexus:
 (1) It is made up of the anterior rami of the fifth sixth seventh and eighth cervical nerves and the first thoracic nerve with




FIG 513 Diagram showing the construction of the brachial plexus

communications from the fourth cervical and the second thoracic (2) The plexus is arranged so that five rami (roots) = three trunks = six divisions = three cords = nerve supply (branches) to the upper extremity (3) The roots and the trunks lie in the neck the divisions are behind the clavicle and the cords and the branches are in the axilla (4) The roots and the trunks are in relation to the subclavian artery the cords are in relation to the first and the second parts of the axillary artery (5) The cords become branches at the lower border of the pectoralis minor muscle (third part of the axillary artery)

The fifth and the sixth cervical roots join to form the upper trunk the seventh cervical forms the middle trunk and the eighth cervical and the first thoracic form the lower trunk Each trunk divides into an anterior and a posterior division The three posterior divisions join to form the posterior cord the anterior divisions of the upper and the middle trunk unite to

form the lateral cord and the anterior division of the lower trunk continues alone as the medial cord Branches arise from the roots the trunks and the cords, no branches have their origin from the divisions

The branches (Fig 513) arising from the roots are dorsal scapular (to the rhomboids) C 5 long thoracic (to the serratus anterior), C 5, 6 and 7 muscular branches (to the three scaleni and longus colli muscles) The branches arising from the trunks are suprascapular (to the supraspinatus and the infraspinatus), C 5 and 6 subclavius (to the subclavius) C 5 and 6 The branches arising from cords are as follows from the lateral cord, the lateral anterior thoracic (to the pectoral muscles), C 5, 6 and 7 the musculocutaneous (to the biceps, the coracobrachialis and the greater part of the brachialis) C 5, 6 and 7 the lateral head of the median, C 5 6 and 7 From the medial cord arise the medial anterior thoracic (to the pectoral muscles), C 8 and




FIG 514 The relations of the brachial plexus. The pectoralis minor muscle and the axillary vein have been removed; the lateral and the medial cords of the brachial plexus are retracted upward.

T 1 the medial head of the median C 8 and T 1 the ulnar C 8 and T 1 medial cutaneous nerve of the forearm C 8 and T 1 medial cutaneous nerve of the arm T 1 From the posterior cord arise the radial C 5 6 7 and 8 and T 1 axillary (to the deltoid and the teres minor) C 5 and 6 thoracodorsal (to the latissimus dorsi) C 6 7 and 8 upper subscapular (to the subscapular) C 5 and 6 and lower subscapular (to the teres major) C 5 and 6

Relation of Brachial Plexus to Axillary Artery The brachial plexus arises in the neck and takes a downward course; the axillary artery travels upward from the chest (figs 509 and 514). Therefore the plexus lies lateral to the subclavian artery. The three cords of the plexus are placed around the second part of the axillary artery and in this way receive their

names. Thus the lateral cord lies lateral to the artery, the medial lies medial to the artery, and the posterior behind it. Since all the nerves lie lateral to the artery in the neck, it must follow that the medial cord crosses the artery to assume its medial position. This it does by running behind part one of the axillary artery. Most of the branches of the plexus are grouped around the third part of the artery. The musculocutaneous nerve lies lateral to the median nerve, and both of these lie lateral to the artery. In the groove between the axillary artery and vein two nerves are found: the medial cutaneous nerve of the forearm and the deeper lying ulnar nerve. Because of this arrangement these nerves usually are confused with each other. The medial cutaneous nerve of the arm passes along the medial border of the vein. The axillary and

Upper radicular syndrome
(Erb Duchenne) 5C & 6C

Middle radicular
syndrome 7C

Lower radicular
syndrome
(Klumpke) 8C & 1T




FIG 515 Three types of brachial plexus palsy




FIG 516 Ligation of the first part of the axillary artery

the radial nerves separate the axillary artery from the subscapular muscle and the radial nerve alone separates the artery from the latissimus dorsi and the teres major muscles

SURGICAL CONSIDERATIONS

BRACHIAL PLEXUS PALSY

Brachial plexus lesions are divided into those lesions which involve the entire plexus or only the upper, the middle or the lower portions (Fig 515). When the *entire plexus* is involved either from injury or pressure the following features are noted: complete anesthesia of the lower part of the arm, the forearm and the hand and flaccid paralysis of the superior extremities, with eventual wasting of the muscles.

Erb Duchenne (upper arm) paralysis is the most common type of nerve injury occurring at birth. It involves the fifth and the sixth cervical nerves. It may occur during the course of a complicated delivery with marked downward traction on the head resulting in a widening of the angle between the head and the shoulder. The injury usually is located where the fifth and the sixth cervical nerves join to form the upper trunk of the plexus, this is known as Erb's

point and is the spot where six nerves meet, namely, the fifth cervical root, the sixth cervical root, the anterior division of the upper trunk, the posterior division of the upper trunk, the suprascapular nerve and the nerve to the subclavius muscle. The hand hangs at the side in internal rotation with the forearm pronated and the fingers and the wrist flexed. This is referred to by some as the "headwaiter's tip hand." External rotation and abduction are lost at the shoulder, as are flexion and supination of the forearm. The clinical appearance is produced by a paralysis of the abductors and the lateral rotators of the shoulder (deltoid, supraspinatus and infraspinatus) plus a paralysis of the flexors of the elbow (biceps brachialis and brachioradialis), a weakness of the adductors and the medial rotators of the shoulders (pectoralis major, teres major, latissimus dorsi, subscapularis) also results. The pronator teres, the supinator, the flexors of the wrist and the thenar muscles may be slightly involved.

The *middle arm type lesion (middle radicular syndrome)* involves the seventh cervical nerve and produces a paralysis of the entire radial nerve except its branch

to the brachioradialis, there is also a paralysis of the coracobrachialis.

Atrophy (lower arm) paralysis is usually the result of upward traction on the shoulder. It also may result from injuries or during breech presentations when the arms are placed over the head. The lesion involves the eighth cervical and the first thoracic nerves. It results in a paralysis of the intrinsic muscles of the hand and a paralysis of the flexors of the digits. A "claw hand" results. There is also diminished sensation over the medial side of the arm, the forearm and the hand.

LOCATION OF THE AXILLARY ARTERY

If the axillary artery is ligated above the origin of the thoricoacromial, the collateral circulation is the same as that of the third part of the subclavian artery. When ligated at its lower limit the following arteries are involved in the collateral supply: the subscapular, the transverse scapular, the transverse cervical, the internal mammary, the intercostal, the thoricoacromial, the lateral thoracic and the anterior and the posterior humeral circumflex.

The axillary artery may be ligated in its first part (above the pectoralis minor muscle) or in its third part (below the pectoralis minor muscle). Ligation of the first part can be accomplished by an incision extending just below the clavicle from the coracoid process to the sternoclavicular joint (Fig. 516). The clavicular portion of the pectoralis major muscle is incised through its whole thickness and the pectoralis minor is retracted downward. The costocoracoid membrane is divided along the upper border of the pectoralis minor care being taken not to injure the axillary vein. The axillary artery is now exposed with the vein on its inner side and the cords of the brachial plexus outside and behind it. To accomplish the ligation it may be necessary to lower the arm since the vein overlies and conceals the artery when the arm is abducted.

The third part of the axillary artery is

superficial and is easier to approach. The incision is in upward prolongation of an incision placed over the brachial artery. The coracobrachialis muscle is exposed and drawn outward with the musculocutaneous nerve. The basilic vein which joins the brachial vein comes to form the axillary vein. It is found on the inner side of the artery. The cords of the brachial plexus are disposed around all sides of the artery and must be identified and retracted out of the way.

DELTOID AND SCAPULAR REGIONS

It is well to study the scapula in the discussion of the deltoid and the scapular regions since this bone presents many bony surgical landmarks and gives attachment to the muscles in this region.

SCAPULA (SHOULDER BLADE)

The *scapula (shoulder blade)* is a flat triangular bone which lies on the posterolateral aspect of the thorax opposite the second to the seventh ribs. It has three borders, three angles, two surfaces and two processes (Figs. 517 and 518).

The three borders are the superior, the medial and the lateral. The superior border is the shortest; it inclines laterally and downward from the superior angle where the levator scapulae is inserted. The suprascapular notch is located at its lateral part and is converted by the suprascapular ligament into a foramen which transmits the nerve of the same name. Since this border gives attachment only to the small omohyoid muscle, it remains thin and sharp. The medial (vertebral) border is the longest and is quite thick; it gives insertion to the second layer of back muscles (rhomboid minor, rhomboid major and levator scapulae). The lateral (axillary) border is the thickest of the three. It extends from the inferior angle upward, laterally and forward to the glenoid cavity, at its upper end is the triangular impression known as the infraglenoid tubercle for the attachment of the long head of the triceps.




FIG 517 The muscle attachments to the scapula and the humerus (anterior view) Origins are represented in red and insertions in blue

The *three angles* are the superior, the inferior and the lateral. The obtuse *superior angle* is situated between the superior and the medial borders. It is covered by the trapezius and, therefore is difficult to feel. The acute *inferior angle* is located between the medial and the lateral borders and is an important anatomic and surgical

landmark. Fortunately, it is felt easily at the level of the seventh intercostal space when the extremity hangs at the side. The *lateral angle*, located between the superior and the lateral borders, forms the shallow glenoid cavity which articulates with the head of the humerus and displays above its apex a slightly roughened area (the




FIG. 518 The muscle attachments to the scapula and the humerus (posterior view). Origins are represented in red and insertions in blue.

supraglenoid tubercle) for the origin of the long head of the biceps.

The *two surfaces* are the dorsal and the costal (ventral). The *dorsal surface* is unequally subdivided by the spine of the scapula into the smaller supraspinous and the larger infraspinous fossae. Transverse grooves for the circumflex scapular artery are noted over this surface. The *costal*

surface is hollow and forms the floor of the subscapular fossa which is deepest opposite the spine. This area is covered by the serratus anterior and the subscapularis muscles.

The *two processes* are the coracoid and the acromion. The *coracoid process* projects from the lateral part of the superior border of the bone and sharply bends for

ward and laterally at a right angle. The lateral border of this process gives attachment to the coraco acromial ligament, which helps the acromion form an arch above the head of the humerus. The tip

from the skin into the fibrous investments of the deltoid muscle. This area is supplied above by the supraclavicular nerves and below by the cutaneous branches of the axillary nerve and the intercostal nerves.




FIG. 519 The cutaneous nerve supply of the deltoid region

of the coracoid gives origin to the coraco brachialis and the short head of the biceps muscles. Although this tip is covered by the anterior fibers of the deltoid it can be felt on deep pressure through the lateral boundary of the *infraclavicular fossa* about one inch below the clavicle. The spine of the scapula terminates laterally as the *acromion process* which projects laterally at first and then bends sharply forward to form the acromial angle. The entire upper surface and borders of the acromion are palpable subcutaneously. Immediately in front of the shoulder joint it gives attachment to the lateral end of the coraco-acromial ligament.

MUSCULAR ATTACHMENTS VESSELS, NERVES AND BURSÆ

Deltoid Region. The skin over the deltoid region is thick. Fibrous septa extend

(Fig. 519) The deep fascia covering the deltoid invests the muscle and sends many septa between its fasciculi. In front it is continuous with the fascia covering the pectoralis major muscle and it becomes thick posteriorly where it is continuous with the fascia covering the infraspinatus muscle. It is continuous below with the deep fascia of the arm and is attached above to the clavicle, the acromion process and the spine of the scapula.

The *deltoid muscle* is large, thick and triangular and covers the shoulder joint in front, behind and laterally (Fig. 520). It has a wide V-shaped origin from the lateral third of the clavicle (anterior border), the acromion (tip and lateral border) and the crest of the spine of the scapula (lower border). The fibers converge and are inserted into a roughened area called the *deltoid tuberosity*, which is located about

halfway down the lateral aspect of the humerus. It is the great abductor of the arm. Most authorities agree that the first 15° of abduction of the arm are effected by the supraspinatus muscle but the del-

the humerus. The two subdivisions usually communicate but occasionally are separated by a thin partition. The bursa does not normally communicate with the shoulder joint but may do so when the




FIG 520 The deltoid muscle (A) Origin and insertion of the muscle (B) The supraspinatus muscle initiates abduction of the arm and this is continued by the deltoid muscle (C) With a torn supraspinatus muscle abduction cannot be started by the deltoid unless at first the arm is pushed away from the body

toid continues and maintains it (Fig 520 B and C). The clavicular fibers aid in flexion and internal rotation and the posterior fibers aid in extension and external rotation. The muscle is supplied by the axillary (circumflex) nerve from C 5 and 6.

The *subdeltoid (subacromial) bursa* is one large bursa with subacromial and subdeltoid subdivisions (Fig 521). The subacromial division lies between the deep surface of the acromion above and the tendon of the supraspinatus muscle below. The subdeltoid division lies between the deltoid muscle and the upper and lateral aspect of

bursal floor (supraspinatus tendon) is torn.

The *long head of the biceps muscle* arises by a round tendon from the supraglenoid tubercle on the scapula and passes through the shoulder joint (Fig 522). Although it is intra-capsular, it remains extrasynovial since it receives a tubular sheath from the synovial membrane. The tendon and its acquired synovial sheath pass through the intertubercular sulcus (bicipital groove) and are held in this groove by a thickened part of the capsule which is called the transverse humeral ligament and is attached to both tubercles. Should this liga-

ment be torn the tendon of the biceps becomes displaced to the medial side of the lesser tubercle. The tendon strengthens the upper part of the joint and keeps the head of the humerus against the glenoid cavity.

muscle, below by the long head of the triceps brachii, behind by the tendons of the infraspinatus and the teres minor, and in front by the tendon of the subscapularis.

The *supraspinatus* muscle arises from the medial two thirds of the floor of the




FIG. 521 The subdeltoid bursa (A) The bursa has two parts a subacromial part and a subdeltoid part (B) Surface projection of the subdeltoid part of the bursa

The short head of the biceps and the coracobrachialis muscles arise together from the coracoid process of the scapula. The coracobrachialis is slender and descends along the medial margin of the biceps and is inserted into the medial part of the humerus. The short head of the biceps muscle is the medial and is discussed elsewhere (p. 696).

Scapular Region Three muscles, the supraspinatus, the infraspinatus and the teres minor, are attached to the greater tuberosity (Fig. 522). The shoulder joint is bounded above by the supraspinatus

supraspinous fossa. The fibers pass laterally under the acromion and end in a short, stout tendon inserted into the top of the greater tuberosity of the humerus. The supraspinatus is covered by the trapezius, the coracoacromial arch and the deltoid. Its tendon is closely adherent to the capsule of the shoulder joint. This muscle initiates the action of abduction which is then continued by the deltoid (Fig. 520). In cases of injury to the suprascapular nerve, the supra and the infraspinatus muscles are paralyzed, in such cases the patient cannot initiate abduction but can

carry out this action if he starts it with the hand of the other arm or swings the arm away from the side of the body by a quick movement.

The *infraspinatus muscle* arises from the whole of the floor of the infraspinous fossa

It arises from an elongated flat impression on the dorsum of the scapula and is inserted into the back of the greater tuberosity of the humerus slightly behind the *infraspinatus*. As it approaches its insertion it is separated from the *teres major* by the




FIG. 522. The muscles of the scapular region. (A) The relations of the long head of the biceps and the long head of the triceps brachii muscles. (B) The supraspinatus, the infraspinatus and the teres minor muscles insert on the greater tuberosity.

and is inserted into the greater tuberosity a little behind the supraspinatus. Its tendon is closely adherent to the capsule of the shoulder joint and its lateral part is covered by the deltoid. At times a small bursa is found between its tendon and the capsule of the shoulder joint; if present, it may communicate with the joint. This muscle is a lateral rotator of the arm.

The *teres minor muscle* is small and lies along the lower border of the infraspinatus

long head of the triceps brachii (Fig. 522 B). It is adherent to the capsule of the shoulder joint and acts as an abductor and a lateral rotator of the arm.

The greater tuberosity of the humerus is reserved for the insertion of the three SIT muscles: the Supraspinatus on the anterior impression, the Infraspinatus on the middle impression and the Teres minor on the posterior impression. These muscles aid in lateral rotation of the arm.

ment be torn the tendon of the biceps becomes displaced to the medial side of the lesser tubercle. The tendon strengthens the upper part of the joint and keeps the head of the humerus against the glenoid cavity.

muscle, below by the long head of the triceps brachii, behind by the tendons of the infraspinatus and the teres minor, and in front by the tendon of the subscapularis.

The *supraspinatus* muscle arises from the medial two thirds of the floor of the




FIG 521 The subdeltoid bursa (A) The bursa has two parts, a subacromial part and a subdeltoid part (B) Surface projection of the subdeltoid part of the bursa

The *short head of the biceps* and the *coracobrachialis* muscles arise together from the coracoid process of the scapula. The coracobrachialis is slender, descends along the medial margin of the biceps, and is inserted into the medial part of the humerus. The short head of the biceps muscle is the medial and is discussed elsewhere (p 696).

Scapular Region Three muscles, the supraspinatus, the infraspinatus, and the teres minor, are attached to the greater tuberosity (Fig 522). The shoulder joint is bounded above by the supraspinatus

muscle. The fibers pass laterally under the acromion and end in a short, stout tendon inserted into the top of the greater tuberosity of the humerus. The supraspinatus is covered by the trapezius, the coracoacromial arch, and the deltoid. Its tendon is closely adherent to the capsule of the shoulder joint. This muscle initiates the action of abduction, which is then continued by the deltoid (Fig 520). In cases of injury to the suprascapular nerve, the supra and the infraspinatus muscles are paralyzed; in such cases the patient cannot initiate abduction but can

carry out this action if he starts it with the hand of the other arm or swings the arm away from the side of the body by a quick movement.

The *infraspinatus muscle* arises from the whole of the floor of the infraspinous fossa

It arises from an elongated flat impression on the dorsum of the scapula and is inserted into the back of the greater tuberosity of the humerus slightly behind the *infraspinatus*. As it approaches its insertion it is separated from the *teres major* by the




FIG. 522 The muscles of the scapular region. (A) The relations of the long head of the biceps and the long head of the triceps brachii muscles. (B) The supraspinatus, the infraspinatus and the teres minor muscles insert on the greater tuberosity.

and is inserted into the greater tuberosity a little behind the supraspinatus. Its tendon is closely adherent to the capsule of the shoulder joint and its lateral part is covered by the deltoid. At times a small bursa is found between its tendon and the capsule of the shoulder joint; if present, it may communicate with the joint. This muscle is a lateral rotator of the arm.

The *teres minor muscle* is small and lies along the lower border of the infraspinatus

long head of the triceps brachii (Fig. 522 B). It is adherent to the capsule of the shoulder joint and acts as an abductor and a lateral rotator of the arm.

The greater tuberosity of the humerus is reserved for the insertion of the three 'SIT' muscles: the Supraspinatus on the anterior impression, the Infraspinatus on the middle impression and the Teres minor on the posterior impression. These muscles aid in lateral rotation of the arm.




FIG 523 The subscapularis muscle

The *subscapularis muscle* is thick and wide and arises from the ventral surface of the scapula (Fig 523). It does not reach the vertebral border of the scapula because this is reserved for insertion of the serratus

magnus muscle. Its fleshy fibers converge upon a stout tendon which is closely adherent to the capsule of the shoulder joint and is inserted into the lesser tuberosity of the humerus, this tendon is seen when the joint is opened posteriorly. As the muscle proceeds to its insertion, it passes under an arch formed by the coracoid process and the conjoint origin of the short head of the biceps and the coracobrachialis muscles. The subscapularis is an adductor and internal rotator of the arm. If it is cut vertically, it will be noted that the muscle does not arise from the part of the subscapular fossa which is near the joint, the muscle only passes over this part and is separated from it by a loose tissue which contains the subscapularis bursa. At this site the bursal wall and the joint capsule are in contact. The bursa facilitates the movement of the subscapularis on the front




FIG 524 Five ligaments surround the shoulder joint proper (A) seen from in front (B) lateral view with the humerus removed

of the head and the neck of the humerus. An opening between the bursa and the joint tends to weaken the capsule and at this point the head of the humerus may burst through in dislocations.

The tendons of the supraspinatus, the infraspinatus, the teres minor and the subscapularis converge and fuse with the capsule of the shoulder joint to form a common tendon capsule cuff (Figs 524 and 525). The *subdeltoid (subacromial) bursa* lies upon this 'cuff' and the greater tuberosity, it is covered by the deltoid muscle, the acromion process and the coracoacromial ligament.

THE SHOULDER JOINT

The *shoulder joint* is a ball and socket joint (enarthrodial) (Figs 524 and 525). The ball is the head of the humerus and the socket is the glenoid cavity of the scapula. In no other joint are the movements so free and varied. The ligaments do not maintain the joint surfaces in apposition when only the ligaments remain the humerus can be separated from the glenoid cavity for almost an inch. The joint is protected above by an arch formed by the coracoid process, the acromion and the coracoacromial ligament; this prevents upward displacement of the joint. The ligaments of the shoulder joint proper are five in number: (1) the articular (capsular), (2) the coracohumeral, (3) the glenohumeral (superior, middle and inferior), (4) the transverse humeral and (5) the glenoidal labrum (Fig 524).

The *articular capsule (capsular ligament)* completely encircles the shoulder joint and is attached above to the circumference of the glenoid cavity beyond the glenoid labrum; below it is attached to the anatomic neck of the humerus. This capsule or ligament is so remarkably loose and lax that it has no action in keeping the bones in contact. It is strengthened above by the supraspinatus tendon, below by the long head of the triceps brachii, behind by the tendons of the infraspinatus and the teres

minor, and in front by the tendon of the subscapularis. The weakest part of the capsule is its lower portion, this being partially due to the lax folds which are visible when the arm is adducted. Because of this weakness, dislocations of the head of the humerus take place through this inferior part of the capsule downward and into the axilla. When such a dislocation occurs, the circumflex vessels and the nerves may be injured. There are usually three openings in the capsule: the *first* is anterior and below the coracoid process and establishes a communication between the joint and the bursa beneath the tendon of the subscapularis (Fig 525). When this aperture (subscapular bursa) is large a dislocation may take place through it rather than the inferior aspect of the shoulder joint. The *second* aperture is not constant; if present, it is situated at the posterolateral part of the capsule and permits protrusion of the synovial membrane to form a bursa under cover of the infraspinatus muscle. The *third* aperture is in the groove between the tubercles of the humerus; this permits passage of the long tendon of the biceps brachii. The tendon is enclosed in a tubular prolongation of synovial membrane which surrounds it and lines the bicipital groove (Fig 525 B). The articular capsule cannot extend onto the lesser and the greater tuberosities because the subscapularis, the supraspinatus, the infraspinatus and the teres minor muscles insert here; however it does extend inferiorly down to the surgical neck.

The *coracohumeral ligament* is a broad band which strengthens the upper part of the articular capsule. It passes from the lateral border of the coracoid process to the front of the greater tubercle of the humerus where it blends with the tendon of the supraspinatus. The ligament is connected intimately to the capsule by its hind and lower borders, its anterior and upper borders present a free edge which overlaps the capsule.

The *glenohumeral ligament* consists of




FIG 525 The relations around the shoulder joint (A) seen from the left side with the humerus removed, (B) the synovial sheath

three parts (Fig 524 B). They constitute three bands which are thickenings of the anterior part of the capsular ligament and have been referred to as the superior, the middle, and the inferior glenohumeral ligaments. They may be thick enough to bulge into the joint and raise ridges upon the synovial membrane.

The *transverse humeral ligament* is a broad band which passes from the lesser to the greater tubercle of the humerus. It is limited to that portion of the bone which lies above the epiphyseal line and converts the intertubercular groove into an intertubercular canal in which the long head of the biceps brachii is located.

The *glenoid labrum* is a dense fibrocartilaginous lip attached to the rim of the glenoid cavity. It aids in deepening the socket. It is somewhat triangular in shape

and becomes continuous above with the tendon of the long head of the biceps brachii.

The *synovial membrane* lines the capsular ligament and is prolonged onto the glenoid labrum and over the neck of the humerus to the articular margin. It supplies the long tendon of the biceps with a sheath which is prolonged into the bicipital groove. It becomes reflected upward and is continuous with the joint lining beneath the ligament to form bursae which have been described previously (p. 683).

The *relations* around the shoulder joint are as follows (Fig 525): *anteriorly* the subscapularis muscle and its bursa separate the axillary vessels and nerves from the joint. *above* the supraspinatus and the coracoacromial ligament form an overhanging arch. The subacromial bursa is be-




FIG 526 The scapular anastomoses

neath this arch and the deltoid muscle *posteriorly* the infraspinatus and the teres minor muscles *inferiorly* the long head of the triceps the posterior circumflex vessels and the circumflex nerve which lie in the quadrilateral space and that part of the subscapularis which arises along side of the lateral margin of the scapula. The circumflex (axillary) nerve and the posterior circumflex vessels separate the teres major and the latissimus dorsi from the inferior portion of the subscapularis muscle. Passing through the joint and over the head of the humerus is the long tendon of the biceps which is excluded from the joint cavity proper by its synovial sheath. The deltoid overlaps the joint anteriorly posteriorly laterally and above but does not come into contact with the capsule because it is separated by the coracoid process the coracoacromial ligament the subacromial

bursa and the muscles which attach to the tuberosities.

Scapular Anastomoses Around large joints throughout the body there occur free arterial anastomoses these are situated close to the bones which take part in the articulation. The shoulder joint is no exception to this rule (Fig 526). The anterior and the posterior *circumflex humeral arteries* form an anastomosing circle around the upper end of the humerus and a free anastomosis on both the costal and dorsal surfaces of the scapula. The scapular anastomosis takes place in the following way: the *suprascapular artery* (transverse scapular) is distributed to both supra- and infraspinous fossae and the deep branch of the *transverse cervical artery* passes downward along the medial border of the scapula. These two arteries are branches of the subclavian via the *thyrocervical trunk*. Both

the *subscapular artery*, which passes downward along the lateral border of the scapula and the *circumflex scapular artery* which arises from the subscapular, are distributed to the infraspinous fossa both

produced by the pectoralis major, the coracobrachialis, the anterior part of the deltoid and the biceps. Extension (backward movement) is produced by the latissimus dorsi, the teres major and minor,




FIG 527 The anterior approach to the shoulder joint

are derived from the third part of the axillary. Since the suprascapular and the transverse cervical arteries are derived from the first part of the subclavian and since the subscapular and the circumflex scapular are derived from the third part of the axillary the scapular anastomosis connects these two widely separated vessels. On the thoracic wall the intercostal arteries anastomose with the transverse cervical the highest thoracic the lateral thoracic and the scapular arteries.

Nerves and Movements The *nerve supply* to the shoulder joint is derived from the suprascapular the upper subscapular and the circumflex (axillary) nerves.

Since the shoulder is a ball and socket joint, movements in every direction are permitted. Flexion (forward movement) is

the posterior part of the deltoid, the infraspinatus and the long head of the triceps. Abduction is brought about by the deltoid and the supraspinatus. Adduction by the subscapularis the pectoralis major the teres major and minor, the latissimus dorsi, the coracobrachialis and the long head of the triceps. The force of gravity aids this latter movement. Circumduction (a combination of movements) is accomplished by combining the four preceding movements. Medial rotation which is much stronger than lateral rotation because of the number of muscles brought into play is produced by the pectoralis major the anterior part of the deltoid the subscapularis, the latissimus dorsi and the teres major. The lateral rotators are the infraspinatus, the teres minor and the posterior part of the deltoid.

SURGICAL CONSIDERATIONS

SURGICAL APPROACH
TO THE SHOULDER JOINT

Many approaches to the shoulder joint have been described but the three used

muscles (Supraspinatus, Infraspinatus and Teres minor) to the greater tuberosity. The capsule can be exposed by detaching the muscles from their respective tuberosities or by detaching the tuberosities themselves. Through this approach the vessels and the




FIG. 528 The posterior approach to the shoulder joint (A) Incision (B) Exposure

most frequently will be discussed here. The *anterior* approach is the method described by Ollier and is the most popular of the three (Fig. 527). It gives access to the subdeltoid bursa and the upper part of the humerus as well as the joint. The incision is made in the deltopectoral groove, beginning at the coracoid process and extending about five inches down the arm. The cephalic vein is exposed and retracted in a downward direction, and the deltoid muscle is retracted laterally. The joint capsule is hidden by the muscles which attach to the tuberosities, the subscapularis to the lesser tuberosity, and the "SIT"

nerves are avoided. The *posterior approach* has been described by Kocher (Fig. 528). Although it is more difficult than the anterior, some authorities state that it gives better exposure of the joint. The incision is curved and commences over the acromioclavicular joint; it extends backward along the inner border of the acromion then over the junction of the acromion with the spine of the scapula and ends about 2 in. above the posterior axillary fold.

A finger is inserted beneath the deltoid muscle separating it from the deeper muscles. The deltoid is cut away from the spine of the scapula to the acromioclavicular

lar joint, leaving about a quarter of an inch of muscle attached to the scapular spine. The cut deltoid is retracted laterally, and by gentle traction the circumflex vessels and the nerve can be exposed without

over the top of the shoulder and continues through the superficial soft structures. The acromion and its attached deltoid are then retracted laterally and the superior aspect of the shoulder joint comes to view. The




FIG 529 Aspiration of the shoulder joint. A frontal section showing two routes of approach (anterior and lateral)

injury. The infraspinatus, the teres minor, the teres major and the long and the lateral heads of the triceps are now visible as is the upper posterior aspect of the humeral shaft. If further exposure of the posterior aspect of the shoulder capsule is desired the supraspinatus the infraspinatus and the teres minor are divided near their insertions and retracted medially. The *superior approach* is used rarely being reserved for cases where bony union of the humerus with the scapula is desired. Through this method the action of the deltoid muscle usually is sacrificed.

RUPTURE OF THE SUPRASPINATUS TENDON

This usually takes place close to the greater tuberosity, and most authorities are of the opinion that it is the most common cause of traumatic subdeltoid bursitis. Codman has devised a saber cut incision which affords the necessary exposure. It passes posteriorly from the acromioclavicular joint,

tendons overlying the humeral head and the capsule can be inspected and the extent of supraspinatus tendon injury determined. The arm is placed in abduction and a groove is cut in the anatomic neck of the humerus in which the edge of the tendon will be placed. Drill holes are made through the lateral edge of this groove, and fascia lata or a similar type of suture laces the tendon in place.

ASPIRATION OF THE SHOULDER JOINT

It may become necessary to withdraw fluid from this joint for diagnostic or therapeutic purposes. There are two methods for aspirating this joint: anterior and lateral (Fig 529). The *anterior method* is accomplished by placing the needle just lateral to the tip of the coracoid process and passing it in a backward and outward direction. The *lateral method* is accomplished by placing the needle just lateral to the angle formed by the junction of the




FIG 530 Dislocations of the shoulder. Primarily, a shoulder dislocation assumes a subglenoid position, but then it may pass anteriorly (subcoracoid or subclavicular) or posteriorly (subacromial or subspinous)




FIG 531 Fracture of the clavicle (A) The usual displacement (B) Reduction in the recumbent position

spine of the scapula with the acromion. The needle is then passed inward until the joint cavity is reached. Fluid in the shoulder joint can follow the long head of the biceps and present a swelling on the anterior surface of the arm, or it can communicate with the subacromial bursa. It may escape through the weak areas of the capsule. At times effusions in this joint pass under the deltoid muscle and appear at either the anterior or the posterior border of the muscle.

DISLOCATIONS OF THE SHOULDER

This is the most frequent of all dislocations because of the shallowness of the glenoid fossa and the disproportion between the head of the humerus and the glenoid cavity. The capsule is protected by muscles in front and in back and above by the coracoacromial arch. Below the capsule remains unprotected. The latter is the weakest part, and here the head of the humerus leaves the joint (Fig 530). A primary subglenoid position results as the head tears through this weak point. The

humeral head enters the axilla in front of the triceps. From this position it may pass either anterior or posterior and assume one of the following positions. If anterior a *subcoracoid* dislocation results and the humeral head lies below the coracoid process and the pectoralis minor muscle, three fourths of all shoulder dislocations are of this type. In *subclavicular* (anterior) dislocations, the head lies under the clavicle and the pectoralis major muscle, a rare occurrence. The posterior positions are *subacromial*, where the head rests upon the posterior angle of the acromion, the supraspinatus is stretched or torn and the infraspinatus is relaxed, *subspinous*, in which the head travels from the subglenoid position in a posterior direction and comes to rest upon the posterior aspect of the neck of the scapula, the subscapularis muscle usually being torn. *Luxatio erecta* is a rare form of dislocation in which the head of the humerus remains below the glenoid cavity with the arm pointing in an upward direction along the side of the head. As the head continues to pass downward, it comes to lie on the serratus anterior muscle.

Many methods and modifications for the treatment of dislocations of the shoulder have been described. One of the oldest and most widely used is Kocher's method. It is accomplished by three movements: the wrist is moved outward until the arm assumes a position of external rotation, external rotation and flexion at the elbow are maintained by moving the elbow forward and inward until the arm is nearly horizontal, the arm is rotated inward, and the hand is brought to the opposite shoulder. By external rotation, the first movement tension is relieved on the posterior scapular muscles and the rent in the capsule is widened. In the second movement relaxation of the tense but untorn portion of the capsule is obtained, and the head of the humerus is permitted to enter the socket. In the third movement, the head of the humerus is brought into contact with the glenoid fossa.

Recurrent (Habitual) Dislocation of the Shoulder Joint Following a traumatic dislocation a weak point is left this might result in recurrent dislocation from trivial trauma. Other authorities are of the opinion that structural weaknesses besides those in the inferior aspect of the capsule are the cause and that all shoulder dislocations therefore do not start originally as a sub glenoid variety.

NICOLA OPERATION

An incision is made from the clavicle, above the coracoid through the anterior border of the deltoid. The long head of the biceps is freed by dividing the transverse humeral ligament below which the biceps is divided the upper end is brought through a hole in the head of the humerus. This is united with the lower end. The capsule and other structures are repaired.

FRACTURED CLAVICLE

The clavicle is fractured more frequently than any other bone in the body. The usual location of such a fracture is at the junction of the middle and outer thirds of the bone (Fig. 531). The medial fragment is tilted upward by the contractions of the sternocleidomastoid and the trapezius muscles and the lateral fragment is displaced downward by the contractions of the pectoralis the teres major and the weight of the arm.

Treatment of a fractured clavicle may be bothersome because direct splinting of the bone is difficult. All methods of closed reduction aim at pushing the shoulder backward until the two fragments are placed in apposition (Fig. 531 B). The recumbent position aids such reduction because the muscles are relaxed and the displacement due to the weight of the arm is relieved.

Arm (Brachial Region)

SURFACE ANATOMY

The arm in the adult appears to be flattened from side to side because of grouping of the anterior and the posterior arm muscles (Fig 532). The fullness anteriorly is produced by the fleshy belly of the biceps brachii; this is lost under the deltoid muscle. Over the posterior aspect of the arm the fullness is produced by the triceps brachii muscle; this fades into a flattened distal appearance produced by the triceps tendon.

The medial bicipital sulcus (groove) commences in front of the posterior axillary fold and descends along the inner aspect of the arm to its lower third, where it bends obliquely forward to the center of the elbow. It separates the biceps and the coracobrachialis muscles in front from the triceps behind. The groove indicates the course of the brachial vessels, the median nerve and the basilic vein.

The lateral bicipital sulcus (groove) does not stand out as well as the medial. It commences at the middle of the arm near the insertion of the deltoid muscle and ends at the bend of the elbow. In its lower part it separates the biceps muscle from the brachioradialis and the radial extensor muscles; the cephalic vein ascends in this sulcus.

The cutaneous nerve supply is depicted in Fig 533.

FASCIA

The arm or brachium is completely invested by a deep fascia called the *brachial aponeurosis*. This is a sleeve of tough fascia which is continuous with that of the fore arm (Fig 534). It is fixed at each side of

the arm by the intermuscular septa which are attached along the outer and the inner margins of the humerus. The lateral intermuscular septum extends from the lateral epicondyle to the deltoid tubercle, the medial extends from the medial epicondyle to the insertion of the coracobrachialis muscle (in the middle of the shaft of the humerus). This fascial arrangement divides the arm into anterior and posterior compartments, which also serve to limit inflammatory exudates and hemorrhagic effusions. It is possible, however, for such fluids to pass from one compartment into another by following those structures which pierce the intermuscular septa.

MUSCLES

In the *anterior (flexor) compartment* three muscles are found: the biceps, the coracobrachialis and the brachialis (Fig 535).

The *biceps muscle (biceps brachii)* arises by two tendinous heads: the long and the short. The *long head* is lateral and arises from the supraglenoid tubercle on the scapula. Its tendon passes through the cavity of the shoulder joint ensheathed by synovial membrane; it emerges from under the transverse ligament and occupies the bicipital groove. In the middle of the arm the long head joins the belly of the *short head*, which arises from the tip of the coracoid process. This head shares its origin on the coracoid process with the coracobrachialis muscle. The tendon of the biceps is inserted into the posterior part of the radial tuberosity. The *bicipital aponeurosis (lacertus fibrosis)* has been discussed elsewhere (p 718). Since this two-headed

muscle that "puts a corkscrew in and pulls the cork out"

The *coracobrachialis* muscle runs parallel and medial to the short head of the biceps. As its name suggests, it originates

the humerus, proximal to the radial groove, and from the lateral intermuscular septum. This head is covered at its upper end by the posterior fibers of the deltoid muscle, but the remainder is superficial. This head




FIG 533 The surface anatomy and cutaneous nerve supply of the arm (A) the anterior aspect (B) the posterior aspect

from the coracoid process and inserts at about the middle of the medial side of the humerus. It aids in flexion and adduction of the arm.

The *brachialis* muscle has its origin by means of two limbs which pass to either side of the deltoid tuberosity. The posterior limb passes up into the spiral groove; the anterior extends upward between the insertions of the deltoid and the *coracobrachialis*. The muscle crosses in front of the elbow joint and inserts into the anterior aspect of the coronoid process of the ulna. It is the most powerful flexor of the elbow joint.

The *triceps* muscle fills the posterior (extensor) compartment of the arm. As its name implies, it has three heads: lateral, medial and long (Fig 536). The lateral head arises from the posterior surface of

converts the spiral groove into a tunnel. The medial head arises from the posterior surface of the shaft of the humerus, distal to the radial groove, and from the median intermuscular septum. It is covered by the other two heads except for its lower fibers which become superficial. The long head is tendinous and arises from a tubercle situated below the glenoid cavity (infra glenoid tubercle). This head is superficial throughout and passes between the teres major and the teres minor muscles to form the triangular and the quadrangular spaces. The fibers of the triceps muscle are inserted by a common tendon into the proximal surface of the olecranon. It is separated from the posterior ligament of the elbow joint by a small bursa. This muscle is the powerful extensor of the forearm.

Quadrangular Space This space does

not actually exist but its boundaries must be artificially separated before it can be visualized. As seen from behind it is bounded by the teres minor muscle above, the teres major below, the long head of the

mark for the circumflex scapular vessels which pass through it.

NIRVIS

The *circumflex (axillary) nerve* & sup




FIG. 554 The deep fascia of the arm. The musculature has been removed. This fascia is known as the brachial aponeurosis, it divides the arm into the anterior (flexor) and the posterior (extensor) compartments.

triceps medially and the surgical neck of the humerus laterally (Fig. 537). The boundaries of the space as seen from in front are the same with the exception of the teres minor which is replaced by the subscapularis as the upper boundary. The circumflex (axillary) nerve and the posterior circumflex humeral vessels pass backward through the space immediately below the capsule.

Triangular Space. This space is formed by the teres minor above and the teres major below, the long head of the triceps forms its base (Fig. 537). Although of little importance, the space acts as a land

mark for the circumflex scapular vessels which pass through it. It divides into anterior and posterior branches. The articular twig originates from the trunk of the nerve in the quad




FIG 535 The muscles of the flexor compartment of the arm (A) seen from in front with the intact deltoid (B) the deltoid has been removed (C) the deep musculature

angular space and enters the joint from below. The posterior branch supplies the nerve to the *teres minor*, curves around the posterior border of the deltoid and supplies this muscle. It continues as the *lateral cutaneous nerve* of the arm. The anterior branch of the nerve continues around the humerus with the *posterior circumflex artery* and ends near the anterior border of the deltoid, supplying this muscle (Fig 537). It also distributes a few fine twigs to the skin.

The *radial (musculospiral) nerve* travels through the posterior compartment of the arm, the "tunnel" and the anterior compartment (Figs 532 and 538). The course of the nerve is more vertical than spiral, being spiral in only a small portion of its mid

dle third. In its upper and lower thirds it is almost perpendicular. In the *posterior compartment* of the arm the nerve appears as a continuation of the posterior cord of the brachial plexus. It lies on the long head of the triceps and appears below the lower border of the *teres major* muscle with the *profunda brachii artery* which accompanies it. It then enters the fascial plane between the long and the lateral heads of the triceps. The so called "tunnel" is the *musculospiral groove*; its roof is the lateral head of the triceps, and its floor is the humerus proper. The radial nerve in this part of its course is in contact with the humerus. In its almost vertical descent through the "tunnel", it separates the lateral from the medial head of the




FIG 536 The triceps muscle (A) superficial view (B) deep view

triceps and supplies both. The nerve gains access to the *anterior compartment* by piercing the lateral intermuscular septum at the junction of the lower and the middle thirds of the humerus. It then passes vertically between the supinator longus (brachioradialis) and the brachialis where it descends vertically (Fig 538). In the region of the lateral epicondyle it divides into its two terminal branches: the posterior interosseous and the radial nerves.

SURGICAL CONSIDERATIONS OF THE RADIAL NERVE

For exposure of the nerve in the *posterior compartment* an incision is made 3 cm below the acromion and is continued for 5 cm past the middle of the humerus; this is in a line with the olecranon. The

incision is carried through the deep fascia. At its upper end three muscular structures may be identified: the posterior border of the deltoid muscle and the long and the lateral heads of the triceps. The deltoid muscle is retracted laterally and the two heads of the triceps are separated in their fascial planes. It may be necessary to incise a small part of the deltoid for more adequate exposure. After separating the two heads of the triceps a glistening aponeurosis (the teres major muscle) is exposed. Distal to this an incision is made in a loose areolar sheath which reveals the nerve and its accompanying vessels.

For exposure of the nerve in its course through the "tunnel" an incision is made extending from a point 3 cm above the level of the insertion of the deltoid directly

Anastomosis between suprascapular
(trans scap) & circumflex scapular aa




FIG 537 The quadrangular and the triangular spaces

downward for 12 cm. This incision is carried through the triceps separating the fibers longitudinally until the aponeurosis on its deep surface is seen. This aponeurosis is incised and the nerve is exposed beneath it.

The exposure of the radial nerve in the anterior compartment will be discussed elsewhere (p 705).

ARTERIES AND VEINS

The *posterior circumflex humeral artery* arises from the axillary artery a short distance below the subscapular, passing backward through the quadrangular space with the circumflex nerve (Fig 537). Winding around the surgical neck of the humerus, it is distributed to the deep surface of the

deltoid muscle. Some of its terminal branches are distributed to the surrounding muscles, the shoulder joint and the skin.

The *anterior circumflex humeral artery*

is smaller than the posterior circumflex humeral artery. It passes anteriorly around the surgical neck of the humerus and makes an arterial circle by joining the posterior humeral circumflex artery.

The *brachial artery* is a direct continuation of the axillary artery. It commences




FIG 538 The radial nerve




FIG. 539 The brachial artery lies successively on three muscles, gives three main branches, is in contact with three important nerves and is associated with three veins.

at the lower border of the *teres major* muscle and terminates about one inch below the transverse skin crease of the elbow, where it divides into its two branches, a large ulnar and a smaller radial. The pulsations of the artery can be felt along the medial bicipital groove throughout the length of the arm until the vessel disappears behind the *lactus fibrosus*.

The brachial artery lies successively on *three muscles*, gives *three main branches*, is in contact with *three important nerves* and is associated with *three veins* (Fig. 539).

The *three muscles* which constitute the floor upon which the brachial artery runs are (from above downward) the long head of the triceps, the coracobrachialis and the brachialis. To cross the muscles in the above order the vessel must pass downward and laterally; thus it does its course corresponding to the inner border of the biceps muscle.

The *three main branches* of the brachial artery are the profunda brachii, the superior ulnar collateral and the inferior ulnar collateral. The *profunda brachii* is a large vessel arising from the upper part of the brachial artery, sometimes as high as the *teres major* muscle. It passes downward, backward and outward between the long and the medial heads of the triceps muscle; it is the companion vessel of the radial nerve (Fig. 538). An important ascending branch arises from the upper part of the vessel and anastomoses with the posterior humeral circumflex artery, thus connecting the axillary and the brachial vessels. Having traversed the musculospiral groove the profunda brachii reaches the lateral intermuscular septum and divides into anterior and posterior branches. The anterior branch follows the radial nerve through the intermuscular septum, passes in front of the lateral epicondyles and anastomoses with the radial recurrent artery. The posterior branch continues downward behind the intermuscular septum, in back of the lateral epicondyle and anastomoses with the posterior interosseous recurrent artery. In this

way a complete arterial circle is formed around the lateral epicondyle (Fig. 550). The *superior ulnar collateral artery* has also been called the inferior profunda artery. It arises near the middle of the arm and is the companion vessel of the ulnar nerve (Fig. 539). It pierces the medial intermuscular septum, enters the posterior compartment and passes behind the medial epicondyle. It anastomoses with the posterior ulnar recurrent artery. The *inferior ulnar collateral artery* has been called the *anastomotica magna*. It arises about two inches above the termination of the brachial artery and passes inward behind the median nerve. It passes in front of the medial epicondyle, anastomoses with the anterior ulnar recurrent artery and forms an arterial circle around the medial epicondyle. These two arterial circles of the epicondyles in turn are connected by a branch of the inferior ulnar collateral artery which passes transversely across the back of the humerus, hence its name "*anastomotica magna*." In this way the rich anastomoses are formed around the elbow joint (Fig. 550).

The *three important nerves* which are associated with the brachial artery are the radial, the ulnar and the median (Fig. 539). The medial cutaneous nerve of the forearm lies to the medial side of the artery and although not as important as the other three it still may cause annoying cutaneous manifestations if involved or injured. The *radial nerve* is associated with the artery only in its upper part immediately below the lower border of the *teres major* muscle. Here it lies behind the artery, separating it from the long head of the triceps muscle. The *median nerve* is related closely to the brachial artery throughout its entire course. In the upper arm it lies lateral to the vessel but as it descends, it crosses in front of the artery in the region of the midarm. At times the nerve crosses behind the vessel. As it continues downward it comes to lie on the medial side of the artery in the lower arm and

elbow region. The *ulnar nerve* passes downward on the medial side of the brachial artery, lying between it and the basilic vein. In the middle of the arm the nerve pierces the medial intermuscular septum.

Both the medial cutaneous nerve of the forearm and the ulnar nerve lie to its medial side and separate it from the basilic vein. Posterior to the artery is the radial nerve, which separates the vessel from the




FIG. 540 Medial approach to the brachial artery

and leaves the vessel. It should be noted that the median and the ulnar nerves make a "nonstop trip" through the arm, giving off no branches.

The *three veins* which are associated with the brachial artery are its *two venae comites* (brachial veins) and the *basilic*. The basilic vein ascends in the groove on the medial side of the biceps muscle superficial to the deep fascia and medial to the artery. Halfway up the arm the basilic vein pierces the deep fascia and becomes more intimately related to the brachial artery. At a variable point it joins the two brachial veins to form the axillary. The brachial veins pass one on each side of the brachial artery and make many venous contacts around the artery as they ascend.

Relationships Around the Brachial Artery These relationships are best described in thirds (Fig. 532). In the *proximal third* the brachial artery lies medial to the humerus and can be compressed laterally against this bone. It is overlapped laterally by the coracobrachialis muscle from which it is separated by the median

long head of the triceps muscle. The *middle third* of the artery may be compressed backward and laterally against the bone. The vessel is overlapped by the medial border of the biceps muscle and is crossed from lateral to medial by the median nerve. The ulnar nerve is medial, but about the middle of the arm it passes posteriorly to reach the posterior compartment of the arm. Posteriorly the artery lies on the brachialis and the insertion of the coracobrachialis muscles. The basilic vein and the medial cutaneous nerve of the forearm are separated from the vessel by the deep fascia. In the *distal third* the brachial artery lies in front of the humerus and can be compressed backward against it. The biceps tendon overlaps it. The median nerve is medial to it; the ulnar nerve has passed into the posterior compartment.

SURGICAL CONSIDERATIONS OF THE BRACHIAL ARTERY

The bifurcation of the brachial artery is not constant and may take place at a high




FIG 541 The right humerus (A) Seen from in front The different shapes of the humerus are depicted in cross section taken at the various identified levels (B) The posterior view

level in the arm. Such a bifurcation may be troublesome as well as embarrassing when attempting to ligate the vessel for hemorrhage distal to the bifurcation.

The usual indications for ligation of the brachial artery are wounds, secondary hemorrhage and hemorrhage from the deep palmar arch. Ligation may be done either at the middle of the arm or at the bend of the elbow. Ligation at the middle of the arm is accomplished in the following way (Fig 540). The arm is placed in abduction,

and the hand in supination. If the arm is allowed to lie on a flat surface the triceps muscle may be pushed upward and be mistaken for the biceps. Dissection through this distorted area exposes the superior ulnar collateral artery and the ulnar nerve instead of the brachial artery and the median nerve. The incision is made in the line of the artery along the medial edge of the biceps muscle. The basilic vein and the medial cutaneous nerve of the forearm may be identified superficial to the deep

fascia at this level. If seen, they are drawn to one side. The deep fascia is incised, and the inner fibers of the biceps muscle are identified and retracted upward. The artery is found lying on the triceps muscle, with the median nerve in front of it. The nerve is isolated and protected. The brachial artery with its two venae comites are exposed; the artery is isolated from its companion veins and ligated.

The *collateral circulation* differs when the brachial artery is ligated above or below the profunda brachii (Fig. 538). If ligated *above* the profunda brachii, the circumflex humeral vessels above anastomose with the profunda brachii below. If ligated *below* the profunda brachii, the profunda brachii above anastomoses with the vessels around the elbow joint below.

HUMERUS

The humerus is a long cylindrical bone which articulates with the scapula above and with the radius and the ulna below (Fig. 541). The *head* of the humerus forms a third of a sphere. It is covered with cartilage which is thickest in its central part and thins toward the circumference. The head is directed medially, upward and a little backward. The *anatomic neck* is a constriction which surrounds the articular cartilage and gives attachment to the capsular ligament. Projecting forward and laterally from the humeral head is a mass of bone which is divided into two unequal parts called the lesser and the greater tuberosities. The groove dividing this bony mass is the bicipital (intertubercular) sulcus; it lodges the long tendon of the biceps. To these two tuberosities attach the tendons of the muscles which hold the head of the humerus in its socket. The *greater tuberosity* is the more lateral of the two and has been called the 'point of the shoulder.' Although it is covered by the deltoid, it can be felt on deep pressure. It has depressions for insertion of the three "SIT" muscles (Supraspinatus, Infraspinatus and Teres minor) (p. 685). The

tuberosity gradually fades and becomes continuous with the shaft of the humerus. The *lesser tuberosity* is located on the front of the shaft and immediately below the anatomic neck. It is also covered by the deltoid and can be felt on deep pressure especially during rotation of the bone. It provides attachment for the subscapularis muscle. The *surgical neck* of the humerus is a fingerbreadth below the tuberosities. A region of surgical importance; it is a narrow zone encircled by the circumflex vessels and partially encircled by the circumflex (axillary) nerve. This neurovascular bundle hugs the bone and does not pierce the four muscles inserted into the greater and the lesser tuberosities or the three muscles (pectoralis major, teres major and latissimus dorsi) which insert into the medial and the lateral lips of the bicipital groove. These lips descend from the tuberosities and deepen the bicipital sulcus.

The surgical and the anatomic necks meet medially in the region of the quadrangular space (p. 702). Slightly above the level of the surgical neck is the *epiphyseal line*, which coincides with the lower margin of the humeral head on the medial side, but passes through the lowest part of the greater tuberosity on the lateral side. The *deltoid tuberosity* is a roughened inverted "delta" with its apex downward. It is located about halfway down the shaft of the bone over its lateral aspect. The shallow spiral (radial) groove lies immediately behind this tuberosity and contains the radial nerve and the profunda artery.

The *body* or shaft of the humerus is almost cylindrical in its upper half and prismatic and flattened in its lower half. The humeral body has three borders: anterior, lateral and medial. The *anterior border* extends from the front of the greater tuberosity to the coronoid fossa, its proximal part forming the lateral lip of the bicipital groove and its middle part the anterior margin of the deltoid tuberosity. The *lateral border* extends from the back of the greater tuberosity to the lateral

epicondyle. It is indistinct proximally where the lateral head of the triceps arises and it is interrupted in its midportion by the oblique groove for the radial nerve. Its distal part is the prominent lateral supracondylar ridge. The medial border extends from the lesser tuberosity to the medial epicondyle and forms the medial lip of the bicipital groove. It is roughened in the middle for the insertion of the coracobrachialis and its distal part becomes the medial supracondylar ridge.

The body of the humerus has three surfaces: anterolateral, anteromedial and posterior. The *anteromedial surface* is situated between the anterior and the medial margins; the bicipital groove forms its proximal part. The *anterolateral surface* is located between the anterior and the lateral margins with the deltoid tuberosity slightly above its midportion. The *posterior surface* situated between the medial and the lateral margins is occupied by the origin of the medial head of the triceps. The spiral groove begins on the posterior surface running obliquely downward between the origins of the medial and the lateral heads of the triceps and ending below the deltoid tuberosity. The radial nerve and its accompanying profunda vessels lie in this groove. A nutrient foramen is situated near the middle of the medial border and another is found frequently in the spiral groove.

The *lower end of the humerus* is divided into two areas: the *capitellum* which receives the head of the radius, and the *trochlea* for the trochlear (semilunar) notch of the ulna. The capitellum is sphere shaped and the trochlea is spool shaped. The *radial fossa* is located immediately above the capitellum and receives the head of the radius during full flexion. The *coronoid fossa* situated immediately above the trochlea receives the coronoid process of the ulna during flexion. The *olecranon fossa* the largest of the three fossae is also situated above the trochlea, posteriorly, it receives the olecranon during extension.




FIG. 542 Capsular reflections, epiphyses and metaphyses of the upper and the lower ends of the humerus.

The *lateral epicondyle* is placed immediately above and lateral to the capitellum; its posterior aspect is broad, smooth and easily felt subcutaneously. The *medial condyle* is large and is felt easily medial to and above the trochlea; its posterior aspect presents a groove in which the ulnar nerve can be felt and rolled about.

The *metaphysis* represents the line of junction between the epiphysis and the diaphysis of a long bone; frequently it is the site of bone disease in the young. If part of the metaphysis is inside of the joint capsule, the disease is likely to involve the joint; conversely, joint disease may involve the shaft of the bone if the metaphysis is partly within the affected joint. Therefore, the relationship between epiphyseal lines and capsular reflections becomes clinically important. At the upper end of the humerus, the epiphyseal line passes around the bone at the level of the lowest part of the articular surface of the head (Fig. 542). The capsule is attached to the anatomic neck above but below it is attached to the shaft about one inch lower than the lowest part of the articular surface of the head. This arrangement places the metaphysis partly intracapsular. At the lower end of the bone, the epiphyseal line is represented by a horizontal line at the level of the lateral epicondyle, the medial epicondyle having a separate epiphysis. The capsule follows the coronoid and the radial fossae anteriorly, and the distal half of the olecranon fossa posteriorly. Medially and

fascia at this level. If seen, they are drawn to one side. The deep fascia is incised, and the inner fibers of the biceps muscle are identified and retracted upward. The artery is found lying on the triceps muscle, with the median nerve in front of it. The nerve is isolated and protected. The brachial artery with its two venae comites are exposed; the artery is isolated from its companion veins and ligated.

The *collateral circulation* differs when the brachial artery is ligated above or below the profunda brachii (Fig. 538). If ligated *above* the profunda brachii, the circumflex humeral vessels above anastomose with the profunda brachii below. If ligated *below* the profunda brachii, the profunda brachii above anastomoses with the vessels around the elbow joint below.

HUMERUS

The humerus is a long cylindrical bone which articulates with the scapula above and with the radius and the ulna below (Fig. 541). The *head* of the humerus forms a third of a sphere. It is covered with cartilage which is thickest in its central part and thins toward the circumference. The head is directed medially upward and a little backward. The *anatomic neck* is a constriction which surrounds the articular cartilage and gives attachment to the capsular ligament. Projecting forward and laterally from the humeral head is a mass of bone which is divided into two unequal parts called the lesser and the greater tuberosities. The groove dividing this bony mass is the bicipital (intertubercular) sulcus; it lodges the long tendon of the biceps. To these two tuberosities attach the tendons of the muscles which hold the head of the humerus in its socket. The *greater tuberosity* is the more lateral of the two and has been called the "point of the shoulder." Although it is covered by the deltoid, it can be felt on deep pressure. It has depressions for insertion of the three "SIT" muscles (Supraspinatus, Infraspinatus and Teres minor) (p. 685). The

tuberosity gradually fades and becomes continuous with the shaft of the humerus. The *lesser tuberosity* is located on the front of the shaft and immediately below the anatomic neck. It is also covered by the deltoid and can be felt on deep pressure, especially during rotation of the bone. It provides attachment for the subscapularis muscle. The *surgical neck* of the humerus is a fingerbreadth below the tuberosities. A region of surgical importance, it is a narrow zone encircled by the circumflex vessels and partially encircled by the circumflex (axillary) nerve. This neurovascular bundle hugs the bone and does not pierce the four muscles inserted into the greater and the lesser tuberosities or the three muscles (pectoralis major, teres major and latissimus dorsi) which insert into the medial and the lateral lips of the bicipital groove. These lips descend from the tuberosities and deepen the bicipital sulcus.

The surgical and the anatomic necks meet medially in the region of the quadrangular space (p. 702). Slightly above the level of the surgical neck is the *epiphyseal line*, which coincides with the lower margin of the humeral head on the medial side, but passes through the lowest part of the greater tuberosity on the lateral side. The *deltoid tuberosity* is a roughened inverted "delta" with its apex downward. It is located about halfway down the shaft of the bone over its lateral aspect. The shallow spiral (radial) groove lies immediately behind this tuberosity and contains the radial nerve and the profunda artery.

The *body* or shaft of the humerus is almost cylindrical in its upper half and prismatic and flattened in its lower half. The humeral body has three borders: anterior, lateral and medial. The *anterior border* extends from the front of the greater tuberosity to the coronoid fossa, its proximal part forming the lateral lip of the bicipital groove and its middle part the anterior margin of the deltoid tuberosity. The *lateral border* extends from the back of the greater tuberosity to the lateral

Fracture of the anatomic neck is intra capsular rare and occurs mainly in older people. At times the shaft may be driven into the head of the bone producing marked impaction. It may become necessary to treat the condition surgically so that function is improved or it may be necessary to remove a loose fragment.

Fractures of the surgical neck are extra capsular and usually result from direct violence. They occur mainly in young or middle aged adults (Fig. 543). The deformity, although it may vary depending upon the relationship of the site of fracture to the insertion of muscles, remains fairly constant. The upper end of the lower fragment is carried upward toward the axilla by the pull of the deltoid, the biceps, the coracobrachialis, and the triceps muscles. It is drawn medially by the pectoralis major, the teres major and the latissimus dorsi. The upper fragment is abducted by the supraspinatus. In reducing the fracture, abduction of the arm should not be performed too forcefully or too rapidly because the pectoralis major acts as a fulcrum and the upper end of the sharp lower fragment may injure the brachial plexus. Therefore bringing the arm forward and making traction outward and forward will release the tension of the pectoralis major and allow the lower fragment to be brought into apposition. After complete reduction the position should be maintained in abduction usually by means of axial traction.

Fracture of the greater tubercle can result from either direct violence or muscle pull from the attached supraspinatus, the infraspinatus and the teres minor. This type of fracture may accompany a fractured neck of the humerus or an anterior dislocation. The supraspinatus usually pulls the tuberosity upward and backward. The arm should be fixed in abduction and external rotation if this fails, surgical correction becomes necessary.

Separation of the upper humeral epiphysis occurs up to the twentieth year and




FIG 543. Fractures of the shaft of the humerus (A) above the insertion of the deltoid muscle (B) below the insertion of the deltoid muscle.

usually is the result of the same type of injury as causes fractures of the surgical neck. Due to action of the supraspinatus, the infraspinatus and the teres minor the upper fragment usually is abducted. Since the upper end of the diaphysis is conical the epiphysis fits into this by a corresponding concavity (Fig. 544). This results in a cup and cone arrangement which makes reduction difficult but immobilization easy. As the child grows older the concavity of the epiphysis gradually becomes flattened so that this is altered. Reduction and immobilization in abduction are required.

Fractures of the lesser tubercle are rare




FIG 543 Fracture of the surgical neck of the humerus. The arrows indicate the pull of the muscles which produces the deformity.




FIG 544 Separation of the upper humeral epiphysis

laterally, it attaches about a quarter of an inch from the articular margins. Therefore, the metaphysis is partly intracapsular.

Attachments to the Humerus The following are the attachments to the humerus (Figs 517 and 518)

To the greater tuberosity—the “SIT” muscles (Supraspinatus, Infraspinatus and Teres Minor)

To the lesser tuberosity—the teres major and the subscapularis, both extending to the surgical neck.

To the anatomic neck—above and about half an inch from it below and medially the capsular ligament of the shoulder the coracohumeral ligament extends onto the anterior part of the greater tuberosity.

To the bicipital groove—the transverse ligament, attached to both tuberosities, bridges across its proximal part the pectoralis major to its lateral lip the teres major to its medial lip and the latissimus dorsi to the floor.

To the lateral epicondyle—the common extensor tendon, the lateral ligament of the elbow, the supinator and the anconeus

To the medial epicondyle—the medial ligament, the common flexor tendon and the pronator teres.

To the medial margin of the shaft—the coracobrachialis.

To the lateral margin of the shaft—the lateral head of the triceps.

To the medial supracondylar ridge—the medial intermuscular septum and the pronator teres.

To the lateral supracondylar ridge—the lateral intermuscular septum the brachioradialis and the extensor carpi radialis longus.

To the deltoid tuberosity—the deltoid muscle.

From the anteromedial and the anterolateral surfaces—the brachialis.

From the posterior surface—the medial head of the triceps.

To the radial and the coronoid fossae—the anterior ligament of the elbow the posterior ligament attaches to the margins of the olecranon fossa on either side and to the back of the epicondyles.

SURGICAL CONSIDERATIONS

FRACTURES

Fractures of the humerus may occur at the upper end, at the shaft and at the lower end.




FIG 546 Supracondylar fracture of the humerus. The close relations of the median nerve and the brachial artery to the sharp fractured fragments are shown.

The deformity is produced by the subscapularis, which pulls the fragments medially.

Shaft fractures may occur in the upper third of the humerus above the deltoid attachment or, more commonly, in the middle of the shaft below the deltoid attachment; hence, the displacement and the deformity vary with the site of the fracture (Fig 545). If the fracture is situated above the insertion of the deltoid the upper fragment is drawn medially by the muscles attached to the bicipital groove (pectoralis major, teres major and latissimus dorsi) and the lower fragment is drawn upward and laterally by the deltoid (Fig 545 A). If the fracture is below the insertion of the deltoid the upper fragment is pulled laterally by the deltoid and the supraspinatus and the lower fragment is displaced medially and upward (Fig 545 B). The relationship of the radial nerve to this fracture is important. At about the middle of the humerus and below the attachment of the deltoid muscle this nerve lies in direct contact with the bone and a sharp bony fragment may injure it. The sensory branches of the radial nerve leave at a higher level than this site of injury; therefore, the nerve symptoms are entirely motor and will be manifested by a wrist drop. For proper reduction normal relations between the external epicondyle and

the greater tubercle should be maintained.

Supracondylar (lower end) fractures occur frequently in children and at that point where the bone is thin (the anteroposterior diameter immediately above the condyle). The lower fragment is displaced upward and backward and may simulate a dislocation (Fig 546). However, the internal condyle, the olecranon and the external condyle remain in normal relations, which would not be true in posterior dislocation of the elbow. The median nerve and vessels in the cubital fossa may be injured, and the possibility of Volkmann's ischemic contracture must be kept in mind. The importance of incising the brachial fascia, following reduction and immobilization, has been stressed (p 534).

Intercondylar fractures are supracondylar and extend into the joint between the condyles, forming a T or Y shaped fracture. They are difficult to reduce and maintain in position. *Fractures of the epicondyle* may be caused by powerful abduction and extension of the elbow or by muscular action. Involvement of the ulnar nerve must be kept in mind when the medial epicondyle is fractured. The lateral epicondyle usually is fractured by a fall on the hand; this may involve the capitulum and the trochlear surface. *Lower epiphyseal separation* is usually seen in children between the ages of five to ten years. The displacement is lateral and backward.

OPERATIONS ON THE SHAFT OF THE HUMERUS

Exposure of the humeral shaft is difficult because this bone is not subcutaneous anywhere and important vessels and nerves are closely related to it. The best approach is a lateral one (Fig 547). The lower two thirds of the shaft of the humerus is exposed through a skin incision which extends downward from the medial border of the deltoid, along the lateral border of the biceps almost to the lateral condyle of the humerus. The cephalic vein may be encountered. The deltoid is retracted laterally




FIG 547 Exposure of the shaft of the humerus (A) incision and position of the arm (B) the relations of the exposed bone to the surrounding musculature




FIG 548 Exposure of the neurovascular structures of the arm

and the biceps medially thus exposing the brachialis muscle. Flexion of the elbow will relax the brachialis tendon. The brachialis muscle is incised longitudinally to the bone and the cut surfaces of the muscle are retracted laterally and medially. The radial nerve can be protected if it is retracted with the posterior part of the brachialis muscle. Thus the lower two thirds of the shaft of the humerus is exposed safely.

The *neurovascular structures* in the arm are approached through a medial incision which is placed in the medial bicipital groove (p. 696). The basilic vein is encountered and is retracted posteriorly (Fig. 548). The medial border of the biceps muscle is elevated and retracted antero-laterally thus the median and the ulnar nerves and the brachial artery, with its *venae comites*, are exposed.

Elbow

ELBOW JOINT

The elbow joint is the articulation of the humerus with the radius and the ulna, since it permits only flexion and extension, it belongs to the hinge or ginglymus variety. The trochlea and the capitellum of the humerus articulate respectively with the trochlear notch of the ulna and the head of the radius. The trochlea of the humerus is grasped by the trochlear (semilunar) notch of the ulna and the capitellum of the humerus rests upon the upper surface of the head of the radius. Some anatomists prefer to consider the elbow joint as the result of three separate joints having one synovial cavity namely, the humero-ulnar, the humeroradial and the superior radio-ulnar joints. Here the elbow joint will be considered as having humero-ulnar and humeroradial parts, and the superior radio ulnar joint will be discussed as a separate joint communicating with the other two.

Ligaments The joint is surrounded by a *capsular ligament*, thickened and reinforced at the sides to form medial and lateral ligaments the intervening portions are known as the anterior and the posterior ligaments of the elbow (Fig 549). The broad, thin *anterior ligament* is attached superiorly to the radial and the coronoid fossae and the epicondyles inferiorly, it is attached to the anterior margin of the coronoid process and the annular ligament of the radius. The *posterior ligament* is placed medially and is thin and weak. Superiorly, it is attached to the floor and the medial and the lateral margins of the olecranon fossa and the epicondyles in

feriorly, it is attached to the anterior and the lateral margins of the olecranon. The *medial ligament* (ulnar collateral) consists of three bands which pass between the internal epicondyle, the coronoid process and the olecranon. The anterior band is strong and taut in extension. The posterior part is a weak, fan shaped portion which becomes taut in flexion, its oblique fibers, which also have been referred to as the ligament of Cooper, deepen the socket for the trochlea of the humerus. The ulnar nerve lies on the posterior and the middle parts of this ligament as it descends from the back of the medial epicondyle into the forearm. The *lateral ligament* (radial collateral) is fan shaped and extends from the lateral epicondyle to the side of the annular ligament. It is a strong short band, the superficial fibers of which may be continued onto the radius as the supinator. It is attached below to the annular ligament and not to the bone.

The epiphyseal line of the humerus and the radius is almost entirely intracapsular, that of the ulna is extracapsular.

The *synovial membrane* lines the deep surface of the capsular ligament but does not reach as high in the radial the coronoid and the olecranon fossae as does the fibrous capsule. On the lateral side it is continuous with the synovial membrane of the superior radio-ulnar joint. The pads of fat which fill the coronoid, the radial and the olecranon fossae are intracapsular but extrasynovial. The anterior fat pad projects into the coronoid fossa during extension of the joint, and the posterior projects into the olecranon fossa during flexion. The synovial




FIG 549 The ligaments of the elbow joint (A) the lateral aspect, (B) the medial aspect

capsule bulges about a quarter of an inch below the lower margin of the annular ligament and surrounds the neck of the radius (Fig. 551)

Blood and Nerve Supply The blood supply around the elbow joint is derived from anastomoses which constitute free communications between the brachial artery and the upper end of the radial and the ulnar arteries (Fig. 550). This like all other periarticular anastomoses lies close to the bone. Branches of nine arteries take part in its formation; they are (1) the anterior branch of the profunda brachii; this anastomoses with (2) the radial recurrent on the front of the lateral epicondyle; (3) the posterior branch of the profunda brachii anastomoses with (4) the interosseous recurrent on the back of the lateral epicondyle; (5) The anterior branch of the supratrochlear anastomoses with (6) the anterior ulnar recurrent on the front of the medial epicondyle; (7) its posterior branch and (8) the ulnar collateral anastomose with (9) the posterior ulnar recurrent on the back of the medial epicondyle.

The nerve supply of the joint is derived

from the median the ulnar, the radial the musculocutaneous and the posterior interosseous nerves.

Relations *Anteriorly* the brachialis muscle nearly covers the entire anterior ligament (Fig. 551). It separates the joint proper from the brachial artery, its companion veins, the biceps tendon and the median nerve. Medial to the brachialis the anterior recurrent ulnar artery is found related to the anterior ligament. Under cover of the muscles is the radial nerve, with its posterior interosseous branch accompanied by the radial recurrent artery. *Laterally* the common tendon of the extensors overlies the lateral ligament of the elbow, and the extensor carpi radialis brevis and the supinator arise from it. *Medially*, the common tendon of the flexors overlies the anterior band of the medial ligament of the elbow; the flexor sublimis arises from it. The flexor carpi ulnaris overlies the posterior band, and the ulnar nerve and the posterior ulnar recurrent artery lie directly on it. *Posteriorly*, the triceps and its bursa lie above the olecranon. The anconeus and the interosseous




FIG 550 The anastomoses around the elbow joint

recurrent artery are at the lateral side of the olecranon. That part of the flexor carpi ulnaris which originates from the olecranon is found to its medial side. A fracture across the olecranon brings the bursa into direct communication with the joint.

Movements The movements at the elbow joint should not be confused with those that take place at the superior radio ulnar joint. At the elbow joint there are two movements namely flexion and extension. The muscles which are chiefly concerned in flexing the forearm are the biceps, the brachialis, the brachioradialis and the pronator teres. Those which extend the forearm are the triceps and the anconeus; these are aided somewhat by the muscles arising from the lateral epicondyle. In extension the forearm bones make an angle with the humerus; this is known as the "carrying angle" and is produced by the inner condyle of the humerus which is set obliquely so that the axis of the elbow joint is transverse between the radius and the

humerus but oblique between the ulna and the humerus. This angle disappears on full flexion, but in extension it is about 10 to 15°. The angle may be disturbed by fractures of the lower end of the humerus or by rupture of the collateral ligaments. If it is increased, the condition of cubitus valgus results; if it is obliterated, the condition of cubitus varus ensues.

ELBOW REGION

The cubital (antecubital) fossa is a triangular depression lying anterior to the elbow joint. The base of this triangle is formed by an imaginary line drawn between the humeral condyle, its converging borders are the pronator teres medially and the brachioradialis laterally. At the apex the brachioradialis overlaps the pronator teres, the floor is formed by the brachialis muscle, and the deep fascia forms its roof (Fig 552).

FASCIA, VESSELS AND NERVES

The superficial veins of the cubital fossa lie in the superficial fascia. Although variable in their course and arrangement, a general plan usually can be adhered to. In this area five superficial veins are found: the cephalic, the basilic, the median cephalic, the median basilic and the median (Fig 552).

The median basilic vein lies, as its name implies, medial to the basilic; the median cephalic lies medial to the cephalic and the cephalic lies lateral to the basilic. The cephalic vein arises on the radial side of the hand, from the dorsal venous arch, passes upward and receives the median cephalic vein at the lateral epicondyle. It ascends over the lateral aspect of the biceps brachii and continues in the deltopectoral groove. It then pierces the costo-coracoid membrane and terminates either in the axillary or the subclavian vein (Fig 508).

The basilic vein arises on the ulnar side of the hand from the dorsal venous arch, passes upward and receives the median




FIG 551 The relations around the elbow joint (A) seen from behind, (B) cross-section




FIG 552 The cubital fossa and its contents

basilic vein in front of the medial epicondyle. It ascends in the medial bicipital groove and pierces the deep fascia in the region of the middle of the arm. It continues as the axillary vein in conjunction with the two brachial veins.

The bicipital fascia, or, as it is more commonly called the *lacertus fibrosus*, lies deep to the superficial veins of the elbow region. It is an excellent surgical landmark (Fig 552).

The biceps brachii is inserted into the




FIG 552 The cubital fossa and its contents after cutting the lacertus fibrosus.

The *median vein* commences in the palmar venous plexus, ascends on the front of the forearm and divides at the apex of the cubital fossa into the median cephalic and the median basilic veins. This division takes place soon after the entrance of its chief tributary, the profunda vein which drains the deeper structures of the forearm.

The *profunda vein* drains into the median. It enters the median vein at the distal edge of the lacertus fibrosus and in this location may be compressed as a result of trauma or tight bandaging. The vessel thus can become obliterated and the return venous flow from the deeper structures of the forearm impaired. Thus it is thought is one of the contributing causes of Volkmann's contracture. For this reason one of the treatments suggested for the condition is incision of the deep fascia to release pressure.

tuberosity of the radius by means of a flat tendon. However, some of the fibers of this muscle do not pass into the formation of this tendon but continue on as a flat tendinous expansion which passes medially and distally to fuse with and become lost in the fascia of the forearm. This flat tendinous expansion is called the *lacertus fibrosus*; it also has been referred to as the bicipital aponeurosis. It occupies the middle of the front of the elbow region and is about three-quarters of an inch wide.

The lacertus is the key structure of this region. The pulsations of the brachial artery can be felt immediately beneath its free medial margin. Full extension of the forearm facilitates the palpation of the artery by relaxing the bicipital fascia; the median nerve lies just medial to the brachial artery.

The lateral antibrachial cutaneous nerve

is the continuation of the musculocutaneous nerve. It pierces the *lactus fibrosus*, runs under the median cephalic vein, becomes superficial and divides into anterior and posterior branches which supply the skin over the anterolateral and the postero

When the *lactus fibrosus* is cut and reflected the underlying brachial artery and median nerve are exposed (Fig. 553). The brachial artery and its venae comites are just medial to the biceps tendon, and the median nerve in turn is medial to the




FIG. 554 The posterior or olecranon region. (A) bony and muscular landmarks, (B) the varying bony relationships in flexion and extension.

lateral aspects of the forearm (Fig. 559). The *medial antibrachial cutaneous nerve* is a branch of the medial cord of the brachial plexus, divides at the middle of the arm into a volar and an ulnar branch. The volar branch passes under the median basilic vein and supplies the skin of the ulnar half of the forearm as far as the wrist.

Four structures are found on the *lactus fibrosus*: the median cephalic vein, the median basilic vein, the lateral antibrachial cutaneous nerve and the medial antibrachial cutaneous nerve (or the branches of these nerves).

The radial nerve can be found lateral to the biceps tendon in a compartment between the brachioradialis and the brachialis muscles. The groove between these muscles may be difficult to determine owing to the absence of a well marked septum. The usual error is to open the interval immediately between the brachialis and the biceps muscles thereby exposing the musculocutaneous nerve instead of the radial. It is advisable, therefore, to hug the lateral border of the biceps tendon and seek the interval between the brachioradialis muscle and the biceps tendon. Lateral retraction of the brachioradialis will

basilic vein in front of the medial epicondyle. It ascends in the medial bicipital groove and pierces the deep fascia in the region of the middle of the arm. It continues as the axillary vein in conjunction with the two brachial veins.

The bicipital fascia, or, as it is more commonly called, the *lacertus fibrosus*, lies deep to the superficial veins of the elbow region. It is an excellent surgical landmark (Fig. 552).

The biceps brachii is inserted into the




FIG. 553 The cubital fossa and its contents after cutting the lacertus fibrosus

The *median cut* commences in the palmar venous plexus, ascends on the front of the forearm and divides at the apex of the cubital fossa into the median cephalic and the median basilic veins. This division takes place soon after the entrance of its chief tributary, the profunda vein, which drains the deeper structures of the forearm.

The *profunda cut* drains into the median. It enters the median vein at the distal edge of the lacertus fibrosus and, in this location, may be compressed as a result of trauma or tight bandaging. The vessel thus can become obliterated and the return venous flow from the deeper structures of the forearm impaired. This, it is thought, is one of the contributing causes of Volkmann's contracture. For this reason, one of the treatments suggested for the condition is incision of the deep fascia to release pressure.

The tuberosity of the radius by means of a flat tendon. However, some of the fibers of this muscle do not pass into the formation of this tendon but continue on as a flat tendinous expansion which passes medially and distally to fuse with and become lost in the fascia of the forearm. This flat tendinous expansion is called the *lacertus fibrosus*; it also has been referred to as the bicipital aponeurosis. It occupies the middle of the front of the elbow region and is about three quarters of an inch wide.

The lacertus is the key structure of this region. The pulsations of the brachial artery can be felt immediately beneath its free medial margin. Full extension of the forearm facilitates the palpation of the artery by relaxing the bicipital fascia; the median nerve lies just medial to the brachial artery.

The lateral antibrachial cutaneous nerve

is the continuation of the musculocutaneous nerve it pierces the lacertus fibrosus runs under the median cephalic vein, becomes superficial and divides into anterior and posterior branches which supply the skin over the anterolateral and the postero

When the lacertus fibrosus is cut and reflected, the underlying brachial artery and median nerve are exposed (Fig 553) The brachial artery and its venae comites are just medial to the biceps tendon and the median nerve in turn is medial to the




FIG. 554 The posterior or olecranon region (A) bony and muscular landmarks (B) the varying bony relationships in flexion and extension

lateral aspects of the forearm (Fig 559) The medial antibrachial cutaneous nerve, a branch of the medial cord of the brachial plexus divides at the middle of the arm into a volar and an ulnar branch. The volar branch passes under the median basilic vein and supplies the skin of the ulnar half of the forearm as far as the wrist.

Our structures are found on the lacertus fibrosus the median cephalic vein, the median basilic vein the lateral antibrachial cutaneous nerve and the medial antibrachial cutaneous nerve (or the branches of these nerves)

The radial nerve can be found lateral to the biceps tendon in a compartment between the brachioradialis and the brachialis muscles. The groove between these muscles may be difficult to determine owing to the absence of a well marked septum. The usual error is to open the interval immediately between the brachialis and the biceps muscles, thereby exposing the musculocutaneous nerve instead of the radial. It is advisable therefore, to hug the lateral border of the biceps tendon and seek the interval between the brachioradialis muscle and the biceps tendon. Lateral retraction of the brachioradialis will




FIG 555 The posterior "U" approach to the elbow joint (A) incision, (B) the resulting wide exposure of the joint following division of the olecranon

expose the radial nerve where it divides into superficial and deep branches

The *brachial artery* can be felt along the medial bicipital groove throughout the length of the arm until it disappears behind the *lacertus fibrosus*. It passes through the cubital fossa under the *lacertus fibrosus* and divides into a larger ulnar and a smaller radial artery. This division takes place at the level of the coronoid process of the ulna and the neck of the radius. These structures are located about one inch below the distal elbow crease.

The *ulnar* and the *median nerves* give off no branches in the arm; they make a "nonstop trip" through it. The *ulnar nerve* lies medial to the *brachial artery* until it reaches the middle of the arm, where it pierces the medial intermuscular septum to reach the posterior compartment. The superior ulnar collateral artery accompanies it at this point. The nerve passes to the back of the medial epicondyle and then on into the forearm. The *median nerve* lies lateral to the *brachial artery* at its beginning but crosses it obliquely and then lies medial to it in the cubital fossa. This

crossing usually takes place in front of the artery.

POSTERIOR OR OLECRANON REGION

The olecranon region includes the posterior soft parts of the elbow; the joint coverings are thin, and the articular extremities of the bones are felt easily (Fig 554).

A knowledge of the surface landmarks in this region is essential. Both of the humeral epicondyles are subcutaneous and readily palpable, but the medial epicondyle is the more prominent. A rather deep but narrow medial para olecranon groove separates the medial epicondyle from the olecranon. The ulnar nerve can be felt passing through the posterior aspect of this groove. The lateral epicondyle is palpated most easily with the arm semiflexed; but when the arm is in full extension, this condyle is hidden in a small depression bounded by the anconeus muscle medially and the extensor carpi radialis muscle laterally. In the region of the para olecranon groove the joint capsule and the synovia are nearest to the surface. When the forearm is extended the intercondylar line is horizontal and passes through the proximal border of the olecranon (Fig 554 B). When the forearm is flexed, however, the olecranon becomes prominent and appears below the horizontal level of the intercondylar line. When the forearm is flexed to a right angle, the olecranon lies on the same plane as the posterior surface of the shaft of the humerus. In this last mentioned position it forms the apex of an inverted triangle, the base of which is located at a line drawn between the epicondyles of the humerus. In full flexion of the forearm the olecranon is carried downward and lies anterior to the articular end of the humerus. Distal to the lateral epicondyle and in a depression which marks the site of the humeroradial joint the projecting head of the radius can be felt, especially on rotary movements produced through supination and pronation. With the forearm flexed, the head of the

radius lies about one inch anterior to the lateral epicondyle the interval separating them being occupied by the capitellum of the humerus. With the forearm in complete extension a distinct depression appears immediately proximal to the head of the radius this corresponds to the lateral and the posterior parts of the radioulnar joint. An effusion in this joint obliterates this depression.

The skin over the back of the elbow is thicker than that over the front it moves with great freedom over the underlying parts.

The *olecranon bursa* is situated between the dorsal surface of the olecranon process the tendinous expansion of the triceps muscle and the skin (Fig 354). Enlargements or involvements of this bursa result in the condition known as *miner's elbow* which is associated with constant bruising as is produced when working in small and confined places.

The *tendon of the triceps brachii* is situated proximal to the joint line where it inserts into the olecranon. The *anconeus muscle* is the only muscle which legitimately belongs to this posterior elbow region throughout its extent it is palpable in the lateral olecranon groove. The *flexor carpi ulnaris muscle* arises from the medial epicondyle and the medial surface of the olecranon.

The *ulnar nerve* reaches the elbow behind the medial intermuscular septum and can be palpated in the medial olecranon groove. It lies in contact with the periosteum under an expansion of the triceps tendon. The nerve leaves the para-olecranon region between the heads of origin of the flexor carpi ulnaris muscle. It may be drawn from its bed and brought around the medial epicondyle to a more protected position during surgery.

The *arteries* of the back of the elbow are part of a network made up of the collateral branches of the brachial the radial and the ulnar trunks which serve as a collateral anastomosis when the main brachial trunk is in occluded. (p 715)



FIG 356 Posterior dislocation of both bones of the forearm

SURGICAL CONSIDERATIONS

SURGICAL APPROACH TO THE ELBOW JOINT

There are many approaches to the elbow joint each having its advantages and disadvantages. Some authorities believe that the lateral approach is the safest. The medial approach is hazardous. A posterolateral approach has also been used. Herein described is a posterior approach using a U-shaped incision (MacAusland). It begins at the external epicondyle of the humerus extends downward and medially crosses the ulna two inches distal to the tip of the olecranon and continues up to the medial epicondyle (Fig 355). The resulting flap is directed upward and the olecranon with the attached triceps tendon is exposed. The ulnar nerve is isolated and retracted medially and the lateral expansions of the triceps tendon are divided transversely. The olecranon is divided with an osteotome and is retracted upward with its muscle attachment. The lateral and the medial muscles in this region are stripped subperiosteally and retracted. A wide exposure results.

DISLOCATION OF THE ELBOW

Dislocation of the elbow involves one or both bones of the forearm and may be backward forward lateral or medial. With these injuries the ulnar and the radial collateral ligaments and the articular capsule




FIG 553 The posterior "U" approach to the elbow joint (A) incision (B) the resulting wide exposure of the joint following division of the olecranon

expose the radial nerve where it divides into superficial and deep branches.

The *brachial artery* can be felt along the medial bicipital groove throughout the length of the arm until it disappears behind the *lacertus fibrosus*. It passes through the cubital fossa under the *lacertus fibrosus* and divides into a larger ulnar and a smaller radial artery. This division takes place at the level of the coronoid process of the ulna and the neck of the radius. These structures are located about one inch below the distal elbow crease.

The *ulnar* and the *median nerves* give off no branches in the arm; they make a nonstop trip through it. The *ulnar nerve* lies medial to the brachial artery until it reaches the middle of the arm, where it pierces the medial intermuscular septum to reach the posterior compartment. The superior ulnar collateral artery accompanies it at this point. The nerve passes to the back of the medial epicondyle and then on into the forearm. The *median nerve* lies lateral to the brachial artery at its beginning but crosses it obliquely and then lies medial to it in the cubital fossa. This

crossing usually takes place in front of the artery.

POSTERIOR OR OLECRANON REGION

The olecranon region includes the posterior soft parts of the elbow; the joint coverings are thin and the articular extremities of the bones are felt easily (Fig 554).

A knowledge of the surface landmarks in this region is essential. Both of the humeral epicondyles are subcutaneous and readily palpable, but the medial epicondyle is the more prominent. A rather deep but narrow medial para olecranon groove separates the medial epicondyle from the olecranon. The ulnar nerve can be felt passing through the posterior aspect of this groove. The lateral epicondyle is palpated most easily with the arm semiflexed, but when the arm is in full extension this condyle is hidden in a small depression bounded by the anconeus muscle medially and the extensor carpi radialis muscle laterally. In the region of the para olecranon groove the joint capsule and the synovia are nearest to the surface. When the forearm is extended the intercondylar line is horizontal and passes through the proximal border of the olecranon (Fig 554 B). When the forearm is flexed however the olecranon becomes prominent and appears below the horizontal level of the intercondylar line. When the forearm is flexed to a right angle, the olecranon lies on the same plane as the posterior surface of the shaft of the humerus. In this last mentioned position it forms the apex of an inverted triangle, the base of which is located at a line drawn between the epicondyles of the humerus. In full flexion of the forearm the olecranon is carried downward and lies anterior to the articular end of the humerus. Distal to the lateral epicondyle and in a depression which marks the site of the humeroradial joint the projecting head of the radius can be felt especially on rotary movements produced through supination and pronation. With the forearm flexed the head of the

radius lies about one inch anterior to the lateral epicondyle the interval separating them being occupied by the capitellum of the humerus. With the forearm in complete extension a distinct depression appears immediately proximal to the head of the radius this corresponds to the lateral and the posterior parts of the radiohumeral joint. An effusion in this joint obliterates this depression.

The skin over the back of the elbow is thicker than that over the front it moves with great freedom over the underlying parts.

The *olecranon bursa* is situated between the dorsal surface of the olecranon process the tendinous expansion of the triceps muscle and the skin (Fig. 554). Infractments or involvements of this bursa result in the condition known as miner's elbow which is associated with constant bruising as is produced when working in small and confined places.

The *tendon of the triceps brachii* is situated proximal to the joint line where it inserts into the olecranon. The *anconeus muscle* is the only muscle which legitimately belongs to this posterior elbow region throughout its extent it is palpable in the lateral olecranon groove. The *flexor carpi ulnaris* muscle arises from the medial epicondyle and the medial surface of the olecranon.

The *ulnar nerve* reaches the elbow behind the medial intermuscular septum and can be palpated in the medial olecranon groove. It lies in contact with the periosteum under an expansion of the triceps tendon. The nerve leaves the para olecranon region between the heads of origin of the flexor carpi ulnaris muscle. It may be drawn from its bed and brought around the medial epicondyle to a more protected position during surgery.

The arteries of the back of the elbow are part of a network made up of the collateral branches of the brachial the radial and the ulnar trunks which serve as a collateral anastomosis when the main brachial trunk is involved (p. 715).




FIG. 556. Posterior dislocation of both bones of the forearm.

SURGICAL CONSIDERATIONS

SURGICAL APPROACH TO THE ELBOW JOINT

There are many approaches to the elbow joint each having its advantages and disadvantages. Some authorities believe that the lateral approach is the safest. The medial approach is hazardous a posterolateral approach has also been used. Herein described is a posterior approach using a U-shaped incision (MacAusland). It begins at the external epicondyle of the humerus extends downward and medially crosses the ulna two inches distal to the tip of the olecranon and continues up to the medial epicondyle (Fig. 555). The resulting flap is dissected upward and the olecranon, with the attached triceps tendon, is exposed. The ulnar nerve is isolated and retracted medially, and the lateral expansions of the triceps tendon are divided transversely. The olecranon is divided with an osteotome and is retracted upward with its muscle attachment. The lateral and the medial muscles in this region are stripped subperiosteally and retracted. A wide exposure results.

DISLOCATION OF THE ELBOW

Dislocation of the elbow involves one or both bones of the forearm and may be backward, forward lateral or medial. With these injuries, the ulnar and the radial collateral ligaments and the articular capsule




FIG 557 Aspiration of the elbow joint

usually are torn and either condyle may be fractured. *Posterior* dislocation of both bones is the most common type; it usually results from a fall upon the outstretched hand (Fig 556). The fibers of the brachialis muscle attaching to the coronoid process usually are torn. If the dislocation is complete the head of the radius lies behind the lateral epicondyle and the distal end of the humerus falls into the cubital fossa. As a result of this the arm and the forearm are semiflexed and at an angle of about 120° . The olecranon projects posteriorly as a hump; the normal relations between the humeral condyle and the olecranon are changed and the olecranon is found above and behind its normal line. *Interior* dislocation of both bones is rare. It results from trauma to the olecranon when the elbow is flexed. The olecranon then lies anterior to the trochlea. *Lateral* and *medial* dislocations are also quite rare and occur from falls on the pronated and outstretched hand.

ARTHROPLASTY OF THE ELBOW

This operation forms an artificial joint and is indicated when ankylosis is present in a poor position (complete extension). Two longitudinal posterior incisions are made passing on each side of the olecranon. A single posterior incision also has been used. The two incisions are deepened down to the bony structure; the musculo-

spiral nerve is located through the radial incision. The ulnar nerve is found behind the internal condyle of the humerus and is protected. The soft parts are retracted and the ankylosed joint is exposed. The lower end of the humerus is removed in such a way that a convex rounded end results. The ulnar end is removed but its end remains concave. It may or may not be necessary to include the radial head in the arthroplasty. Fascia and fat flaps are formed from the radial and the ulnar aspects of the arm and the forearm and are placed over the ends of the bones; these flaps are sutured to the capsule and the periosteum. If no capsule remains or if it is destroyed the flaps are sutured to the surrounding soft tissues. The wounds are closed, and the elbow is immobilized at a right angle. Fascia lata transplants also have been used and sutured to the capsule.

ASPIRATION OF THE ELBOW JOINT

The part of the joint which is closest to the surface lies posteriorly between the head of the radius and the lateral condyle of the humerus (Fig 557). The joint should be flexed to a right angle and the forearm placed in a position of semipronation. The head of the radius is palpated and the needle is inserted just proximal to it in a forward and anterior direction. If the joint is distended with fluid or pus, the capsule bulges to either side of the triceps and can be drained easily.

FRACTURE OF THE OLECRANON PROCESS

This injury results from direct or muscular violence and is characterized by a transverse type of fracture. The deformity is brought about by the triceps muscle which pulls the olecranon upward. Flexion of the elbow further separates the fragments. The treatment of a fractured olecranon process may be nonoperative, with the arm in complete extension or surgical, with the fragments held together by wire placed posterior to the long axis of the ulna.

40

Forearm

The forearm (Fig. 555) is that part of the upper extremity which is between the elbow and the wrist. The anterior (volar) region contains those structures which are anterior to the plane of the radius and the ulna; these include the internal and the external muscle groups which arise from the medial and the lateral epicondyles respectively. The posterior (dorsal) region contains the extensor muscle group which comprises the bulk of this region. When the forearm is in full supination it appears as a cone which is flattened anteroposteriorly. Muscles which arise from the humeral epicondyle increase its transverse diameter near the elbow. Distally the forearm loses its bulk because of the transition of the fleshy muscles into their respective tendons. The shafts of the radius and the ulna can be felt superficially in the distal part of the forearm.

The *cutaneous nerve supply* to the forearm is derived from the lateral and the medial cutaneous nerves ventrally and the lateral, the medial and the posterior nerves dorsally (Fig. 559).

The *deep fascia* of the forearm is a continuation of the deep fascia of the arm. It is strengthened around the olecranon by expansions from the triceps brachii and reinforced anteriorly by the lacertus fibrosus. At the wrist the deep fascia is continuous with the transverse and the dorsal carpal (annular) ligaments. From its deep surface arise intermuscular septa which extend to the radius and the ulna and also form compartments for the various muscle groups which are to be described (Fig. 560).

ANTERIOR (VOLAR) REGION

***Muscles** The muscles of the volar aspect of the forearm occupy three planes or floors which from above downward are as follows (Fig. 561).

The *first floor* (superficial) consists of four muscles which have a common origin from the medial epicondyle of the humerus. They pass obliquely down the forearm with the exception of the flexor carpi ulnaris and are supplied by the median nerve. The *pronator teres* although a powerful pronator of the forearm is also a flexor. It is the most lateral and most obliquely placed muscle of the group. In addition to its origin from the medial epicondyle it has a small deep head of origin from the coronoid process of the ulna. This deep head separates the median nerve from the ulnar artery; the nerve lies between the superficial and the deep head and the artery lies behind both heads (Fig. 562). It inserts on the lateral surface of the middle of the radius. The *flexor carpi radialis* muscle becomes tendinous about the middle of the forearm; it is inserted into the bases of the second and the third metacarpal and produces flexion and radial deviation of the hand. The *palmaris longus* muscle becomes tendinous at about the middle of the forearm but its tendon is longer and narrower than the tendon of the flexor carpi radialis. It passes anterior to the transverse carpal (anterior annular) ligament and inserts into the palmar fascia. Its contraction tenses the palmar fascia and flexes the hand. The *flexor carpi ulnaris* is most medially placed; the digitorum sublimis




FIG. 559 The cutaneous nerve supply of the dorsal and the volar aspects of the forearm

a fibrous band through which the median nerve and the ulnar artery pass to enter the space between the second floor and the third floor musculature. The individual tendons of this muscle start in the lower third of the forearm; they do not lie side by side but pass two above and two below

verse carpal ligament to insert into the bases of the distal phalanges. The *pronator quadratus* lies at the distal end of the forearm but is behind the flexor tendons and sheaths the median nerve and the radial vessels. It originates from the distal fourth of the anterior surface of the ulna, and in




FIG. 560 The deep fascia of the right forearm. The section is taken at the middle of the forearm and shows the fascial spaces and compartments formed for the muscles, the vessels and the nerves.

The two above travel to the third and the fourth fingers and the two below pass to the second and the fifth fingers. The entire muscle is supplied by the median nerve. The splitting of these tendons and their insertions into the borders of the middle phalanges is discussed elsewhere (p. 766).

The *third floor* (deep) consists of three muscles: the flexor pollicis longus, the flexor digitorum profundus and the pronator quadratus. They form a covering for the radius and the ulna and it is upon this that the nerves and the arteries of the front of the flexor region of the forearm travel. The *flexor pollicis longus* muscle arises from the anterior surface of the radius between the oblique line above and the pronator below. It inserts at the base of the terminal phalanx of the thumb. The *flexor digitorum profundus* muscle arises from the volar and the medial surfaces of the ulna between the pronator quadratus and the brachialis muscles. Unlike the sublimis, the tendons of the profundus lie along side of the tendon of the flexor pollicis longus as they pass beneath the trans-

verse carpal ligament to insert into the bases of the distal phalanges. The *pronator quadratus* lies at the distal end of the forearm but is behind the flexor tendons and sheaths the median nerve and the radial vessels. It originates from the distal fourth of the anterior surface of the ulna, and in-

serts into the distal fourth of the anterior surface of the radius and a triangular area on the medial side of the radius in front of the interosseous membrane. It pronates the forearm. All of the muscles previously discussed are supplied by the median nerve with the exception of the flexor carpi ulnaris and the ulnar half of the flexor digitorum profundus (fourth and fifth fingers) as the word *ulnaris* suggests, these muscles are supplied by the ulnar nerve.

Nerves. The *ulnar nerve* enters the forearm by passing between the two heads of the flexor carpi ulnaris and continues downward upon the flexor digitorum profundus (Figs. 562 and 563). In the wrist it is overlapped by the tendon of the flexor carpi ulnaris. It supplies the ulnar half of the flexor digitorum profundus and the flexor carpi ulnaris. It descends vertically near the medial border of the flexor digitorum sublimis and can be exposed by splitting the septum between the sublimis and the flexor carpi ulnaris.

The *median nerve* enters the forearm be-




FIG. 561 The muscles of the volar aspect of the forearm. These muscles occupy three layers or floors, which can be divided into superficial, middle and deep groups.




FIG 562 The blood vessels and the nerves of the right forearm as related to the flexor digitorum sublimis

tween the superficial and the deep heads of the pronator teres passes through the sublimis arch and continues downward on the flexor digitorum profundus. It clings to the deep surface of the flexor digitorum sublimis and in the wrist is overlapped by

the tendon of the palmaris longus. It supplies all the forearm flexors except those already mentioned. That branch of the median nerve which supplies the deep flexors is called the anterior interosseous nerve. As the nerve descends, it clings to




Fig. 563 The blood vessels and the nerves as related to the deep flexors of the right forearm

the undersurface of the *flexor digitorum sublimis* and appears at its lateral border.

The *radial nerve* divides in the region of the lateral epicondyle into superficial and deep branches. The superficial (sensory) branch descends beneath the *brachioradialis* muscle; it approaches the radial artery in the middle of the forearm and

then leaves it to pierce the deep fascia and supply the skin of the dorsum of the hand and the wrist. The deep (dorsal interosseous) branch is mainly motor and reaches the back of the forearm by winding around the neck of the radius through the *supinator* muscle, which makes a tunnel for it (Fig. 563). At the lateral side of the shaft




FIG 562 The blood vessels and the nerves of the right forearm as related to the flexor digitorum sublimis

tween the superficial and the deep heads of the pronator teres passes through the sublimis arch and continues downward on the flexor digitorum profundus. It clings to the deep surface of the flexor digitorum sublimis and in the wrist is overlapped by

the tendon of the palmaris longus. It supplies all the forearm flexors except those already mentioned. That branch of the median nerve which supplies the deep flexors is called the anterior interosseous nerve. As the nerve descends it clings to




FIG. 563 The blood vessels and the nerves as related to the deep flexors of the right forearm

the undersurface of the flexor digitorum sublimis and appears at its lateral border.

The *radial nerve* divides in the region of the lateral epicondyle into superficial and deep branches. The superficial (sensory) branch descends beneath the brachioradialis muscle, it approaches the radial artery in the middle of the forearm and

then leaves it to pierce the deep fascia and supply the skin of the dorsum of the hand and the wrist. The deep (dorsal interosseous) branch is mainly motor and reaches the back of the forearm by winding around the neck of the radius through the supinator muscle, which makes a tunnel for it (Fig. 565). At the lateral side of the shaft

of the radius the nerve passes between the superficial and the deep muscles of the back of the forearm and innervates them

Blood Supply In the upper forearm, the *ulnar artery* is separated from the median nerve by the deep (ulnar) head of the pronator teres in the mid forearm, it descends obliquely behind the flexor digitorum sublimis and on the flexor digitorum

profundus (Figs 562 and 563) At the wrist it is closely related to the ulnar nerve, which lies medial to it Both the artery and the nerve are overlapped by the flexor carpi ulnaris Its branches are the anterior and the posterior ulnar recurrent arteries and, more distally, the common interosseous, which immediately divides into volar (anterior) and dorsal (posterior) branches




FIG 564 The muscles of the back of the right forearm (A) The superficial group consists of six muscles (B) The deep group consists of five muscles

The *radial artery* is unique in that no muscle crosses it; therefore it lies quite superficial and can be ligated almost anywhere in the forearm. It is true, however, that in the upper forearm it is overlapped by the brachioradialis but, as it continues distally, it lies upon the supinator, the pronator teres, the flexor digitorum sublimis, the flexor pollicis longus, and the pronator quadratus in the order named. No motor nerve crosses it.

SURGICAL CONSIDERATIONS

EXPOSURE OF THE RADIAL NERVE

This nerve is injured easily because of its close relation to the humerus. A posterior approach usually is utilized. The incision begins about the middle of the posterior border of the deltoid muscle and extends almost to the olecranon. The deep fascia is incised and the space between the long and the lateral heads of the triceps is identified. The nerve is separated and through this space the nerve with its accompanying profunda artery emerges from the axilla; it passes in the musculospiral (radial) groove. The lateral head of the triceps can be covered and the nerve can be followed in its groove to the lateral region of the arm.

LOCATION OF THE ULNAR ARTERY

Location of the ulnar artery per se is rarely done. It may be ligated at any site along its course, but usually this is done in its lower two thirds. The course of the artery in its lower two thirds can be visualized along a line which corresponds to the lower two thirds of a line drawn from the medial epicondyle to the pisiform bone. The skin incision is placed along this imaginary line. The superficial veins are ligated and the deep fascia is incised. The artery will be found under the flexor carpi ulnaris tendon which can be drawn medially. The vessel is surrounded by its venae comites; the ulnar nerve is medial. This

neurovascular bundle is covered by a layer of fascia which not only binds it down to the surface of the flexor digitorum profundus but also binds the structures to each other. Therefore it is dangerous to place a hematoma without first identifying and dissecting the nerve. In the upper half of the forearm the vessel lies more deeply, being placed beneath the muscle mass which consists of the flexor carpi ulnaris and the flexor digitorum sublimis. The intermuscular cleavage plane existing between the muscles should be opened. The vessel will be found here and can be followed proximally.

LOCATION OF THE RADIAL ARTERY

Location of the radial artery may be done anywhere along its course which corresponds to a line drawn from the middle of the elbow fold (cubital fossa) to the inner side of the front of the styloid process of the radius. The lower two thirds of the radial artery may be exposed through a skin incision which is placed in the line of the artery and is of sufficient length for adequate exposure. The superficial veins are ligated and the deep fascia is divided along the edge of the brachioradialis muscle. In the upper part of the forearm the muscle is retracted laterally so that the artery is exposed with its venae comites as they pass over the pronator teres. The radial nerve approaches the vessels and lies close to them for a short distance in the middle of the forearm but proximal to this there is a slight interval which separates them. The nerve should be guarded. In the lower part of the forearm the vessels are exposed immediately under the deep fascia.

POSTERIOR REGION

The subcutaneous border of the ulna which can be palpated from the olecranon to the wrist separates the extensor muscles of the forearm from the flexors. Such a palpable bony ridge may be utilized as an excellent surgical landmark and guide.

MUSCLES, NERVES AND VESSELS

The muscles of the back of the forearm are divided into superficial and deep groups.

FIG. 594. The superficial group has six muscles and the deep group has five. The two muscles which belong to the superficial group which do not originate from the lateral epicondyle are the brachioradialis and the extensor carpi radialis longus; those which do originate from the lateral epicondyle are the extensor carpi radialis brevis, the extensor digitorum communis, the extensor digiti quinti proprius and the extensor carpi ulnaris. These latter four superficial muscles have a common origin by means of a tendon which is attached to the lateral epicondyle. The deep group of muscles consists of the supinator, the abductor pollicis longus, the extensor pollicis brevis, the extensor pollicis longus and the extensor indicis.

The *brachioradialis muscle* (radial nerve) lies more toward the front of the forearm than on the back. It originates from the upper two-thirds of the lateral supracondylar ridge and about halfway down the forearm is converted into a flat tendon which inserts into the lateral surface of the distal end of the radius. Its fleshy part overlaps the brachialis and descends in front of the lateral epicondyle. It forms the lateral boundary of the cubital fossa. The principal action of the brachioradialis is to flex the forearm; it helps to initiate supination when the forearm is prone and helps to initiate pronation when the forearm is supine.

The *extensor carpi radialis longus muscle* (radial nerve) is closely associated with the brachioradialis. It arises from the distal third of the lateral supracondylar ridge and as it descends it passes over the lateral epicondyle deep to the brachioradialis. At first it is lateral to the radius but it gains the dorsal surface about halfway down the forearm. It has a long tendon which is continued downward toward the wrist where it passes under cover of the extensor retinaculum and inserts into the

base of the second metacarpal bone (Fig. 595). It aids in extension and abduction of the hand at the wrist and is a slight flexor of the forearm.

The *extensor carpi radialis brevis muscle* (posterior interosseous nerve) arises from the common extensor origin on the lateral epicondyle and passes downward at first it is overlapped by the extensor carpi radialis longus but more distally is medial to it. Its tendon begins at the middle of the forearm and passes under cover of the extensor retinaculum through a compartment which it shares with the longus (Fig. 603). It is inserted into the base of the third metacarpal bone. Both radial extensors act as their names indicate: extension and abduction of the wrist.

The *extensor digitorum communis muscle* (posterior interosseous nerve) arises from the common extensor origin at the lateral epicondyle; it passes downward medial to the extensor carpi radialis brevis. In the distal part of the forearm its fleshy belly ends in a tendon which passes under cover of the extensor retinaculum and then divides into four tendons for the fingers. Over the dorsum of the hand the individual tendons diverge and proceed onward to the fingers where they are inserted into the middle and the distal phalanges. These tendons are connected to each other by oblique bands. As a result of this complete extension of an individual finger at the metacarpophalangeal joint is impossible so long as the other fingers are kept flexed. The manner of insertion of these tendons is discussed elsewhere.

The *extensor digiti minimi (quintus proprius) muscle* (posterior interosseous nerve) is a slender muscle which arises in common with the extensor digitorum and at first seems to be part of it. It lies along the medial side of the extensor digitorum but its tendon passes through a special compartment in the extensor retinaculum. The tendon splits into two parts, the lateral being joined by the tendon of the little finger from the extensor digitorum. It forms

the dorsal extensor expansion for the little finger and is an extensor of all the joints of the little finger.

The *extensor carpi ulnaris* muscle (posterior interosseous nerve) arises by means of the common extensor origin from the lateral epicondyle and remains fleshy until it reaches the wrist joint where it becomes tendinous. It occupies the groove on the back of the distal end of the ulna, passes through the most medial compartment of the extensor retinaculum and inserts into the base of the fifth metacarpal. It is an extensor of the wrist and aids the flexor carpi ulnaris in adducting the hand.

The *anconeus* muscle (radial nerve) does not really belong to the superficial group of extensor muscles, but it is convenient to consider it with this group. It originates from the posterior aspect of the lateral epicondyle and is narrow and tendinous; its fibers soon diverge and become inserted into the lateral aspect of the olecranon and the adjoining part of the posterior surface of the ulna. It covers the posterior aspect of the annular ligament of the radius, thus helping to separate the head of the bone from the surface. Its action assists the triceps in extension of the forearm.

If the extensor digitorum communis and the extensor digiti minimi are divided transversely about their middle, the following structures are exposed: the posterior interosseous vessels, the posterior interosseous nerve and the deep muscles of the back of the forearm (Fig. 565 A).

At a variable point in the region of the lateral epicondyle the radial nerve divides into two branches: sensory (superficial) and motor nerves. The motor nerve is the *posterior interosseous (deep radial) nerve*. The level at which branches of nerves originate may be variable, but the side from which nerves originate is quite constant. A motor nerve leaves from that side of the nerve which is nearest the muscle to which it is distributed; hence we may speak of 'sides of safety' and 'sides of danger'. Since the radial nerve supplies the extensor

muscles, its branches arise laterally and therefore it is safe to dissect on the medial side of this nerve. The reverse is true of the median nerve. The posterior interosseous nerve winds around the radius in the substance of the supinator muscle, which creates a muscular tunnel for the nerve. The nerve emerges from the posterior surface of the supinator a little above its lower border and in this way gains access to the fascial plane between the superficial and the deep groups of extensor muscles of the forearm. In its course the nerve is accompanied by the posterior interosseous vessels; they pass across the dorsal surface of the abductor pollicis longus muscle and under cover of the extensor digitorum. At about the middle of the forearm the nerve reaches the extensor pollicis longus and at this point leaves the posterior interosseous vessels and descends over the back of the interosseous membrane. It is accompanied by the anterior interosseous vessels and passes under the extensor pollicis longus and the extensor indicis. The posterior interosseous nerve supplies all the muscles in this region with the exception of the brachioradialis, the extensor carpi radialis longus and the anconeus. The latter are innervated by the radial nerve itself. The nerve terminates on the back of the wrist joint in a slight elevation which sends branches to this joint and to the intercarpal joints.

The *posterior interosseous artery* arises from the common interosseous artery near the upper border of the interosseous membrane. It passes backward between the radius and the ulna above the upper border of the membrane and appears on the back of the forearm between the supinator and the abductor pollicis longus (Fig. 565 A). It travels in the fascial plane between the superficial and the deep group of extensor muscles with the posterior interosseous nerve and reaches the back of the wrist; its lower part is so slender that it seldom can be traced below the middle of the forearm. It ends by taking part in the




FIG 365 The dorsal aspect of the right forearm (A) The extensor digitorum communis muscle has been retracted to expose the posterior interosseous nerve and artery. The anatomic 'snuff box' is shown (B) A cross section of the extensor retinaculum and the six compartments which it forms

anastomosis about the wrist joint. A recurrent branch (the interosseous recurrent artery) passes upward to take part in an anastomosis about the elbow joint.

The *supinator muscle* (posterior interosseous nerve) should not be confused with the supinator longus muscle (Fig. 564 and 565A). The term "supinator muscle" means the supinator brevis; the term "supinator longus" has been used for the brachioradialis. The supinator (brevis) arises from the lateral epicondyle of the humerus and the supinator fossa of the ulna. Its fibers pass backward and laterally around the posterior and the lateral aspects of the upper part of the radius and are inserted into the anterior, the lateral and the posterior aspects of that bone. This muscle inserts as far down as the insertion of the pronator teres. The more the radius is pronated, the tighter and more twisted becomes the supinator. Its action therefore is to untwist itself, and thus it does by supination.

The *abductor pollicis longus muscle* (posterior interosseous nerve) arises from the posterior surfaces of both bones of the forearm and from the interosseous membrane. This origin approximately covers the second quarter of the ulna and the middle third of the radius. At the junction of the middle and the lower thirds of the forearm, its tendon emerges between the extensor digitorum and the extensor carpi radialis brevis. Having come to the surface it crosses the two radial extensors (extensor carpi radialis brevis and radialis longus) and is accompanied closely by the extensor pollicis brevis. It passes under the extensor retinaculum and is inserted into the radial side of the base of the metacarpal bone of the thumb. As its name suggests, it is an abductor of the thumb and also slightly assists in abduction of the hand.

The *extensor pollicis brevis muscle* (posterior interosseous nerve) is placed along the distal border of the preceding muscle. It arises from a small area on the posterior surface of the radius and from the interos-

seous membrane. Its tendon is associated closely with that of the abductor pollicis longus and accompanies it under the extensor retinaculum. It is inserted by a delicate tendon to the dorsum of the base of the proximal phalanx of the thumb. It extends the proximal phalanx of the thumb; in a small number of cases it is absent.

The *extensor pollicis longus muscle* (posterior interosseous nerve) arises from the ulna and the interosseous membrane below the origin of the abductor pollicis longus and takes an oblique course across the carpus. It is inserted into the base of the distal phalanx of the thumb. It is an extensor of all the joints of the thumb and plays a part in initiating supination of the forearm.

The *extensor indicis (proprius) muscle* (posterior interosseous nerve) is a special extensor for the index finger, arising from the ulna and the interosseous membrane immediately below the preceding muscles. It passes downward and laterally to the extensor retinaculum under which it travels in company with the tendons of the extensor digitorum. It terminates by joining the dorsal expansion of the index tendon of that muscle and it lies on the medial side of the most lateral tendon of the common extensor. Its action is to extend all the joints of the index finger.

EXTENSOR RETINACULUM LIGAMENT

The *extensor retinaculum (dorsal carpal or posterior annular)* ligament is a specialized part of the deep fascia of the forearm which passes obliquely across the back of the limb (Fig. 565). It is about an inch wide, has four borders and two surfaces and is longer than the flexor retinaculum but not as strong. The extensors are not able to spring away from the wrist as are the flexors. The ligament acts as a strap which binds the extensor tendons down and holds them in place and being obliquely placed does not interfere with pronation or supination at the wrist. Its

inferior border is continuous with the deep fascia of the hand the *superior* is continuous with the deep fascia of the forearm the medial border is attached to the triquetrum (cuneiform) and pisiform and the lateral is attached to the lower inch of the anterior border of the radius. In this way it forms an annular ligament for the head of the ulna. The retinaculum is not attached to the lower end of the ulna by its medial border hence there is no interference with the movements of the radius around the ulna. The dorsal or *superficial surface* of the extensor retinaculum is crossed by veins draining the dorsal carpal arch this arch usually lies across the lower part of the back of the hand but is inconstant in position and shape. The arch gives origin to the basilic and the cephalic veins and receives tributaries from three dorsal metacarpal veins. Four cutaneous nerves cross superficial to the extensor retinaculum the dorsal branch of the ulnar nerve the superficial branch of the radial and terminations of the posterior branches of the medial and the lateral cutaneous nerves of the forearm. *The septa* springing from the deep surface of the extensor retinaculum are attached to the head of the ulna and to the ridges on the back of the lower end of the radius thus forming six compartments for the extensor tendons (Fig 565 B). In this respect it is unlike the flexor retinaculum which forms only one large compartment for the flexor tendons. Each compartment transmits one or two tendons and is lined with a synovial sheath which envelopes the tendon or tendons. Attached to the deep surface of the extensor retinaculum are the *six compartments* with their enclosed structures. The first compartment is located on the lateral side of the distal end of the radius it contains the tendons of the abductor pollicis longus and the extensor pollicis brevis. The second compartment contains the extensors carpi radialis longus and brevis. The third compartment contains the extensor pollicis longus. The fourth compartment lies over a rather wide but shallow groove at the

medial part of the back of the distal end of the radius and contains the tendons of the extensor digitorum as well as the extensor indicis. Deep to these enclosed tendons this compartment also contains the terminal parts of the posterior interosseous nerve and the anterior interosseous artery. The fifth compartment is situated in the interval that exists between the distal ends of the radius and the ulna and it contains the tendon of the extensor digiti minimi. The sixth is the most medial compartment and is marked by a groove over the dorsum of the distal end of the ulna it encloses the tendon of the extensor carpi ulnaris. *Eight synovial sheaths* surround nine tendons since each tendon has a synovial sheath of its own with the exception of the extensor digitorum and the extensor indicis which have a common sheath. The proximal ends of the sheaths are deep to the extensor retinaculum or slightly proximal to it. The sheaths of the abductor pollicis longus and the three extensors of the carpus extend to the insertions of these muscles. The sheaths of the extensors of the digits usually end about midlength down the hand. At times the abductor pollicis and the extensor pollicis brevis may have a common sheath. Three oblique bands unite the four tendons proximal to the knuckles hence, the independent action of the fingers is restricted. No one finger can be held in flexion while the others pass into extension.

EXTENSOR (DORSAL) REGION OF THE FOREARM AND THE HAND (DORSUM)

This entire area (muscular) is innervated by the *radial nerve*, no motor nerves are found on the dorsum of the hand. No muscles originate from the dorsum of the hand, and no tendons insert into the dorsum of the carpal bones (Fig 565).

Skin and Fascia Over the lateral posterior aspect of the forearm the skin is supplied by the lateral cutaneous nerve of the forearm this is the terminal branch of the musculocutaneous nerve, which becomes cutaneous at the lateral border of

the biceps about an inch above the elbow (Fig. 552). It divides into anterior and posterior branches which pass in front of the elbow; they then descend on the front and the back of the radial side of the forearm; the anterior reaching the thenar eminence and the posterior ending at the wrist joint. The medial cutaneous nerve of the forearm is a direct branch of the medial cord of the brachial plexus (Fig. 559). Like the lateral it too divides into anterior and posterior branches which descend in front of the elbow and then on the front and the back of the ulnar side of the forearm to the wrist. The large strip of skin which passes down the middle of the back of the forearm is supplied by the posterior cutaneous nerve of the forearm; a branch of the radial; it becomes cutaneous about two inches above the lateral epicondyle; supplies the back of the forearm as far as the wrist and in most instances reaches the dorsum of the hand.

The skin of the dorsum of the hand is supplied by the radial nerve and the dorsal branch of the ulnar nerve. The radial nerve winds around the radius deep to the brachioradialis tendon about three inches above the wrist and continues downward superficial to the extensor retinaculum; it supplies the skin over the lateral two thirds of the dorsum and sends digital branches to the thumb, the index finger and the radial side of the middle finger. The dorsal branch of the ulnar nerve winds around the ulna about three inches above the wrist, descends superficial to the extensor retinaculum and supplies the rest of the skin, namely that over the dorsum of the hand, the little and the ring fingers and the ulnar side of the middle finger.

The cutaneous patterns of distribution are variable. The dorsal digital nerves usually do not extend beyond the proximal interphalangeal joints; hence, the rest of the dorsum of each finger receives its nerve supply from the palmar digital nerves.

The *superficial fascia* contains an irregular dorsal venous arch which receives digital veins. From its ulnar and radial ex-

trimities respectively, the basilic and the cephalic veins arise and continue upward in the superficial fascia. The *deep fascia* is part of a strong layer which forms a tubular investment around the muscles of the forearm. At the olecranon at the posterior margin of the ulna and at the lateral distal end of the radius it is connected to the periosteum. It separates the extensors from the flexor muscles by a septum which passes along the posterior margin of the ulna. However on the radial side the separation between extensors and flexors is not developed as definitely. Furthermore it ends partitions between the individual muscles. At the dorsal aspect of the wrist the fascia is strengthened greatly by transverse fibers; this forms the *dorsal carpal ligament* (*posterior annular or extensor retinaculum*) which can be likened to a postage stamp having four borders and two surfaces (Fig. 603). The fascia over the dorsum of the hand reveals the *superficial lamina*, a thin layer under the superficial fascia and above the tendons of the extensor muscles; on both sides of the hand it blends with the fascia of the volar aspect. The *intertendinous lamina* is a connective membrane which lies between the tendons of the extensor digitorum. It is very thin in the white race but thick in the Negro; it is a rudimentary tendon plate. The *dorsal interosseous lamina* lies above the dorsal interosseous muscles and dips down to fuse with the periosteum of each metacarpal bone.

Anatomic Snuff Box (La Tabatiere Anatomique of Cloquet). On the dorsum of the hand the hollow at the base of the thumb is called the "anatomic snuff box" (Fig. 565). It is bounded anteriorly by the abductor pollicis longus and the extensor pollicis brevis, posteriorly, by the extensor pollicis longus. Its floor is formed by the navicular (scaphoid), the trapezium and the articulation between the latter and the first metacarpal bones. The radial artery lies in this box on its way to the first interosseous space. A vein lies superficial to the artery and is called the cephalic vein of Treves.

inferior border is continuous with the deep fascia of the hand the *superior* is continuous with the deep fascia of the forearm the medial border is attached to the triquetrum (cuneiform) and pisiform and the lateral is attached to the lower inch of the anterior border of the radius. In this way it forms an annular ligament for the head of the ulna. The retinaculum is not attached to the lower end of the ulna by its medial border hence there is no interference with the movements of the radius around the ulna. The dorsal or *superficial surface* of the extensor retinaculum is crossed by veins draining the dorsal carpal arch this arch usually lies across the lower part of the back of the hand but is inconstant in position and shape. The arch gives origin to the basilic and the cephalic veins and receives tributaries from three dorsal metacarpal veins. Four cutaneous nerves cross superficial to the extensor retinaculum the dorsal branch of the ulnar nerve the superficial branch of the radial and terminations of the posterior branches of the medial and the lateral cutaneous nerves of the forearm. *Five septa* springing from the deep surface of the extensor retinaculum are attached to the head of the ulna and to the ridges on the back of the lower end of the radius thus forming six compartments for the extensor tendons (Fig. 565 B). In this respect it is unlike the flexor retinaculum which forms only one large compartment for the flexor tendons. Each compartment transmits one or two tendons and is lined with a synovial sheath which envelopes the tendon or tendons. Attached to the deep surface of the extensor retinaculum are the six compartments with their enclosed structures. The first compartment is located on the lateral side of the distal end of the radius it contains the tendons of the abductor pollicis longus and the extensor pollicis brevis. The second compartment contains the extensors carpi radialis longus and brevis. The third compartment contains the extensor pollicis longus. The fourth compartment lies over a rather wide but shallow groove at the

medial part of the back of the distal end of the radius and contains the tendons of the extensor digitorum as well as the extensor indicis. Deep to these enclosed tendons this compartment also contains the terminal parts of the posterior interosseous nerve and the anterior interosseous artery. The fifth compartment is situated in the interval that exists between the distal ends of the radius and the ulna and it contains the tendon of the extensor digiti minimi. The sixth is the most medial compartment and is marked by a groove over the dorsum of the distal end of the ulna it encloses the tendon of the extensor carpi ulnaris. *Eight synovial sheaths* surround nine tendons since each tendon has a synovial sheath of its own with the exception of the extensor digitorum and the extensor indicis which have a common sheath. The proximal ends of the sheaths are deep to the extensor retinaculum or slightly proximal to it. The sheaths of the abductor pollicis longus and the three extensors of the carpus extend to the insertions of these muscles. The sheaths of the extensors of the digits usually end about midlength down the hand. At times the abductor pollicis and the extensor pollicis brevis may have a common sheath. Three oblique bands unite the four tendons proximal to the knuckles hence, the independent action of the fingers is restricted. No one finger can be held in flexion while the others pass into extension.

EXTENSOR (DORSAL) REGION OF THE FOREARM AND THE HAND (DORSUM)

This entire area (muscular) is innervated by the *radial nerve* no motor nerves are found on the dorsum of the hand. No muscles originate from the dorsum of the hand and no tendons insert into the dorsum of the carpal bones (Fig. 565).

Skin and Fascia. Over the lateral posterior aspect of the forearm the skin is supplied by the lateral cutaneous nerve of the forearm this is the terminal branch of the musculocutaneous nerve which becomes cutaneous at the lateral border of

RADIUS AND ULNA

The radius and the ulna form the bony framework of the forearm the radius lying to the lateral and the ulna to the medial side of the upper extremity. The two bones articulate above with the humerus and below with the carpal bones of the wrist (Fig. 567). They also articulate with each other at their upper and lower extremities and are firmly united by the ligaments of the radio-ulnar joints and the interosseous membrane. They are so arranged that the radius supports the entire hand and can revolve on a longitudinal axis around the ulna. This action takes place at the radio-ulnar joints and provides the movements of pronation and supination. The ulna which does not enter into the wrist joint is the more important bone at the elbow joint; the radius has only a secondary role in the latter location.

RADIUS

The proximal end of the radius has a head, a neck and a radial tuberosity.

The *head* of the bone is a cup-shaped disk the upper surface of which is concave and articulates with the capitellum humeri. It is covered by hyaline cartilage and its circumference articulates with the radial notch of the ulna. Although it is embraced by the annular ligament the ligament is not attached to it. This disklike head can be felt easily from the posterior aspect of the limb. If the limb is passively extended a depression becomes visible over the posterior aspect of the elbow on its lateral side. The radial head can be felt in the lower part of it and can be made to rotate within the annular ligament when the hand is alternatively pronated and supinated. In the upper part of this depression the back of the lateral epicondyle of the humerus is palpable and between these two bony projections the line of the radiohumeral joint is located. The *neck* is that constricted portion of the radius which supports the head; it marks the point at




FIG. 567 The radius and the ulna (A) in supination (B) in pronation

which the brachial artery divides into radial and ulnar arteries. The *tuberosity* is placed on the medial side below the neck. anteriorly, it is smooth, and a bursa is located here. It is rough posteriorly for the insertion of the biceps tendon. The *shaft* of the radius reveals a roughened area over its lateral aspect for the insertion of the pronator teres. The interosseous membrane is attached to the interosseous border of the shaft but does not extend as high as the radial tuberosity. The *metaphysis* of the upper end of the radius has the following relationships: since the epiphysis is formed by the head of the bone and the capsule is attached to the neck, the metaphysis or the joint may extend to one or the other very readily.

The distal end of the radius, the widest and bulkiest part of the bone, presents five notches, a styloid process, a dorsal tubercle and an ulnar notch. The *styloid process* is present over the lateral aspect as a downward prolongation which is partially ob-

nne branches of the radial nerve are also found here. The vein is closer to the skin, the artery lies deeper and on the lateral ligament of the bones which form the floor. When ligating the radial artery it is best

pierced the dorsal aponeurosis or may follow an osteomyelitis of the metacarpal or carpal bones. Infections can reach this space from other spaces via the lumbrical sheath. The dorsum almost always becomes edema.




FIG. 566 The subcutaneous and the subaponeurotic spaces of the dorsum of the hand. The drainage of these spaces is indicated.

to avoid opening the sheath of the tendons to the thumb or the scaphoid trapezoid joint.

SURGICAL CONSIDERATIONS

Infections of the dorsum of the hand may involve either the subcutaneous or the subaponeurotic spaces (Fig. 566). The dorsal subcutaneous space may become involved in boils or carbuncles; these infections are superficial to the extensor tendons and the aponeurosis. The dorsal subaponeurotic space infection is uncommon. It may result from perforating dorsal wounds which have

tous in palmar infections because of the loose connective tissue on the back of the hand which is rich in lymphatics. Actual suppuration and primary involvement of this space is rare. When pus collects here, it is limited proximally by fibrous partitions at the base of the metacarpals and distally by similar partitions at the metacarpophalangeal joints. Treatment consists of establishing drainage of the abscess through one or more incisions running parallel to the extensor tendons on the dorsum. The hemostat which opens the space should be placed between the tendons.

the diaphysis are related to the capsular line. At the lower end, the epiphysis is represented by a horizontal line at the level of the upper extremity of the articular surface for the radius; the capsule is attached to the margins of the articular surface except laterally where it is a little proximal to the radial articular surface. Therefore the metaphysis in this location is partly intracapsular and diseases of the bone or the joint may spread in either direction.

RADIO ULNAR JOINTS

The radius and the ulna are united at proximal and distal radio ulnar joint. There is an intermediate joint where the bodies of the two bones are united by the oblique cord, the interosseous membrane and the posterior layer of the fascia which covers the pronator quadratus (Fig. 568).

The *interosseous membrane* of the forearm is a fibrous sheath which stretches across the interval between the two bones of the forearm and is attached to the interosseous border of each. It begins about one inch below the radial tuberosity and extends to and blends with the capsule of the inferior radio ulnar joint. Its fibers pass downward and medial from the radius to the ulna so that shocks transmitted to the radius from the hand are passed on to the ulna and then to the humerus. Over the anterior surface of this membrane and from its upper three quarters the flexor pollicis longus and the digitorum profundus arise; the interior interosseous vessels lie between them and perforate the membrane near its lower end. The pronator quadratus lies on the lower one fourth. The posterior surface gives origin to the abductor pollicis longus, the extensors pollicis brevis and longus and the extensor indicis. The supinator lies on its anterior part, the anterior interosseous vessels and the posterior interosseous nerve on its lower part. The oblique cord is a slender band arising from the tuberosity of the ulna and extending downward and laterally; it attaches to the radius immediately below its tuberosity.




FIG. 568 The superior and the inferior radio-ulnar joints

This cord crosses the open space between the bones of the forearm above the upper border of the interosseous membrane. The posterior interosseous vessels pass backward through the gap which exists between this cord and the interosseous membrane.

Superior (Proximal) Radio Ulnar Joint. This joint is considered with the elbow joint because they have a common synovial cavity, and the lateral ligament of the elbow joint is connected to the annular ligament of the superior radio ulnar joint (Fig. 568). At this joint the medial part of the head of the radius fits into the radial notch of the ulna. The *annular ligament* forms a collar for the head of the radius; this collar returns the radial head

scured in life by the tendons of the abductor pollicis longus and the extensor pollicis brevis. These tendons should be kept relaxed when the bone is being examined. The styloid processes are of great importance in the diagnosis of fractures of the radius; the radial styloid normally projects about a quarter of an inch distal to the ulnar styloid. The *dorsal radial tubercle* of Lister is the most prominent of the ridges over this area and usually can be felt since it is grooved obliquely by the tendon of the extensor pollicis longus. The *medial surface* is concave and smooth and articulates with the head of the ulna. The lateral surface is about half an inch wide and extends onto the ulna and to the styloid process. The *posterior surface* is convex and reaches farther down than the anterior; the dorsal tubercle is located about its center. Shallow grooves lateral to the tubercle lodge the tendons of the extensor carpi radialis longus and brevis, and a narrow oblique groove at the medial side of the tubercle marks the tendon of the extensor pollicis longus. A wide shallow groove medial to this lodges the tendons of the extensor digitorum and the extensor indicis. The *anterior surface* is smooth and slightly concave, being limited distally by a thick ridge which can be felt above the wrist and laterally by a sharp edge which separates it from the lateral surface. The *distal or carpal surface* is concave, smooth and divided into a lateral and a medial area. The lateral area is triangular and articulates with the scaphoid bone and the medial area is square and articulates with the lunate bone. The lower *epiphyseal line* passes around the bone on a level with the upper margin of the ulnar notch; it does not join the shaft until the twentieth year. The *metaphysis* in this region has the following relationships: the epiphysis is represented by a horizontal line at the level of the upper part of the ulnar notch, and the capsule is attached very close to the articular margin all the way around. The metaphysis, therefore is

entirely extracapsular. Both bone and joint diseases are more limited than they would be if the upper metaphysis were involved.

ULNA

The ulna is the medial and longer bone of the forearm. Its proximal end presents an olecranon, a coronoid process and radial and trochlear notches. The *olecranon* is easily palpable posteriorly, and, in extension the upper edge of this process is on the same level as the epicondyle of the humerus. It gives insertion to the tendon of the triceps. The *coronoid process* projects forward and ossifies with the shaft; its anterior aspect is covered by and gives insertion to the brachialis muscle. The *radial notch* is located over the lateral surface, is concave and articulates with the head of the radius. Its inferior and posterior borders give attachment to the annular ligament. The *trochlear notch* (incisura semilunaris) is a wide concavity bounded by the olecranon and the coronoid; it articulates with the trochlea. The *shaft* of the ulna tapers as it passes distally; the posterior border of the shaft is subcutaneous in its whole length from the posterior aspect of the olecranon to its styloid process.

The distal end of the ulna presents a head and a styloid process. The *head* is small and rounded and its distal surface articulates with the triangular articular disk. The head of the ulna can be grasped between the fingers and the thumb when the flexors and the extensors are relaxed, and in some individuals it presents a conspicuous prominence in full pronation. The *styloid process* projects downward from the posteromedial aspect of the head and is felt best when the hand is in full supination.

The *upper and lower metaphyses* have the following relations: at the upper end the epiphysis may be variable but it usually is represented as a flake of bone on the upper surface over its whole extent. This epiphysis, therefore is entirely extracapsular, so that the metaphysis and part of




FIG. 569 Exposure of the shaft of the radius. (A) incision. (B) relations of the deep branch of the radial nerve (dorsal interosseous), (C) the exposed shaft of the radius.

in the radial notch of the ulna. This ligament forms four fifths of a circle which is attached to the anterior and the posterior margins of the notch. It is narrower below than above; hence the head of the radius cannot be pulled downward and out. The lower border of the ligament is free; this allows the head of the radius to rotate during pronation and supination. The *synovial membrane* of the joint lines the deep surface of the annular ligament and is continuous with that of the elbow joint, so that the joint cavities communicate freely. It lines the deep surface of the annular ligament and bulges slightly below it, producing a saciform recess which encircles the neck of the radius.

Inferior (Distal) Radio Ulnar Joint
This is a synovial joint formed by the head of the ulna where it articulates with the ulnar notch of the radius laterally and the articular disk inferiorly (Fig 568). Union is maintained by the articular disk and is aided by a weak capsular ligament passing between the margins of the articular surfaces. The *articular disk* is a thick triangular fibrocartilaginous plate. Its apex is related to the depression at the base of the ulnar styloid process and its base to the lower border of the ulnar notch of the radius. Its anterior and posterior margins blend with the corresponding ligament of the radiocarpal joint. Although it usually is a complete plate, it may be perforated. When this occurs, the joint cavities and the synovial membranes of the inferior radio ulnar and the radiocarpal (wrist) joints become continuous. The *capsular ligament* is weak, possessing feeble anterior and posterior ligaments which invest the anterior, the posterior and the superior aspects of the joint. It is continuous with the capsular ligament of the wrist joint. The *synovial membrane* lines the capsular ligament and the upper surface of the articular disk. It projects upward to form a small cul de sac (*recessus sacciformis*) in front of the lower end of the interosseous membrane. The joint is supplied by the

anterior and the posterior interosseous nerves and vessels.

Movements of the Radio Ulnar Joints
The *rotary* movements of these joints take place around a vertical axis which passes through the center of the head of the radius above and the ulnar attachment of the triangular articular disk below. *Supination*, the position in which the bones of the forearm are parallel and the thumb points laterally, is produced mainly by the supinator, the biceps and the brachioradialis. In *pronation* the radius crosses in front of the ulna, the upper end remaining lateral and the thumb pointing medially. Supination is the strongest movement due to the strength of the biceps. Starting from the supine position, the upper limb can be rotated so that the palm originally directed forward, can be directed successively medially, backward and laterally, moving through an arc of 270° . The greater part of that movement, however, is not pronation but medial rotation at the shoulder joint. Pronation alone can move through an arc of about 130° .

SURGICAL CONSIDERATIONS

EXPOSURE OF THE SHAFT OF THE RADIUS

Exposure of the shaft of the radius is accomplished through an incision over the dorsal aspect of the forearm (Fig 569). The deep fascia is divided, and the extensor digitorum communis is retracted. This exposes the supinator muscle and the deep branch of the radial nerve (dorsal interosseous) piercing it. The supinator is divided longitudinally to the bone and retracted with the muscles of the thumb. The extensor carpi radialis brevis is retracted in the opposite direction, and the shaft of the radius is exposed.

EXPOSURE OF THE DISTAL FOURTH OF THE RADIUS

Exposure of the distal fourth of the radius is accomplished through an incision about three or four inches long, extending upward and medially along the dorsal as




FIG. 569. Exposure of the shaft of the radius. (A) incision. (B) relations of the deep branch of the radial nerve (dorsal interosseous). (C) the exposed shaft of the radius.

in the radial notch of the ulna. This ligament forms four fifths of a circle which is attached to the anterior and the posterior margins of the notch. It is narrower below than above, hence the head of the radius cannot be pulled downward and out. The lower border of the ligament is free; this allows the head of the radius to rotate during pronation and supination. The *synovial membrane* of the joint lines the deep surface of the annular ligament and is continuous with that of the elbow joint so that the joint cavities communicate freely. It lines the deep surface of the annular ligament and bulges slightly below it producing a saciform recess which encircles the neck of the radius.

Inferior (Distal) Radio Ulnar Joint

This is a synovial joint formed by the head of the ulna where it articulates with the ulnar notch of the radius laterally and the articular disk inferiorly (Fig. 568). Union is maintained by the articular disk and is aided by a weak capsular ligament passing between the margins of the articular surfaces. The *articular disk* is a thick triangular fibrocartilaginous plate. Its apex is related to the depression at the base of the ulnar styloid process and its base to the lower border of the ulnar notch of the radius. Its anterior and posterior margins blend with the corresponding ligaments of the radiocarpal joint. Although it usually is a complete plate it may be perforated. When this occurs the joint cavities and the synovial membranes of the inferior radio ulnar and the radiocarpal (wrist) joints become continuous. The *capsular ligament* is weak, possessing feeble anterior and posterior ligaments which invest the anterior, the posterior and the superior aspects of the joint. It is continuous with the capsular ligament of the wrist joint. The *synovial membrane* lines the capsular ligament and the upper surface of the articular disk. It projects upward to form a small cul de sac (*recessus sacciformis*) in front of the lower end of the interosseous membrane. The joint is supplied by the

anterior and the posterior interosseous nerves and vessels.

Movements of the Radio Ulnar Joints
The *rotary* movements of these joints take place around a vertical axis which passes through the center of the head of the radius above and the ulnar attachment of the triangular articular disk below. *Supination*, the position in which the bones of the forearm are parallel and the thumb points laterally is produced mainly by the supinator, the biceps and the brachioradialis. In *pronation* the radius crosses in front of the ulna, the upper end remaining lateral and the thumb pointing medially. Supination is the strongest movement due to the strength of the biceps. Starting from the supine position the upper limb can be rotated so that the palm originally directed forward, can be directed successively medially backward and laterally, moving through an arc of 270° . The greater part of that movement however, is not pronation but medial rotation at the shoulder joint. Pronation alone can move through an arc of about 130° .

SURGICAL CONSIDERATIONS

EXPOSURE OF THE SHAFT OF THE RADIUS

Exposure of the shaft of the radius is accomplished through an incision over the dorsal aspect of the forearm (Fig. 569). The deep fascia is divided and the extensor digitorum communis is retracted. This exposes the supinator muscle and the deep branch of the radial nerve (dorsal interosseous) piercing it. The supinator is divided longitudinally to the bone and retracted with the muscles of the thumb. The extensor carpi radialis brevis is retracted in the opposite direction, and the shaft of the radius is exposed.

EXPOSURE OF THE DISTAL FOURTH OF THE RADIUS

Exposure of the distal fourth of the radius is accomplished through an incision, about three or four inches long, extending upward and medially along the dorsal as

EXPOSURE OF THE SHAFT OF THE ULNA

In the exposure of the shaft of the ulna the location of the incision depends upon the part of the bone requiring exposure (Fig. 561). The incision is located above or below a line drawn between the olecranon and the ulnar styloid. The flexor carpi ulnaris is retracted medially and the extensor carpi ulnaris and the anconeus are retracted laterally. The incision must be deep enough of the bone with an incision. The shaft of the ulna then can be exposed in its entire length.

FRACTURES OF THE FOREARM

Fractures of the forearm present many peculiar complications because of the complicated system of muscles which control movements of the hand and the fingers. For practical purposes, there are attempts to classify the ulna as being at the wrist and the radius as being at the elbow and the radius as being at the wrist. The two forearm bones are joined by the interosseous membrane the fibers of which run from the ulna to the radius in an upward direction. If both bones of the forearm are fractured the membrane has a tendency to pull the ulna toward the radius. In the important motions of pronation and supination the ulna remains fixed and the radius rotates around it so that when the hand is in full pronation the radius comes to lie immediately over the ulna crossing it a little above its middle. The distance between the bones is greatest in semipronation. The pronator teres muscle is the important landmark in fractures of the forearm. It is located a little above the middle of the radius and it must be




FIG. 572. Fractures of the radius in relation to the pronator teres muscle. (A) fracture above the insertion of the pronator teres. (B) fracture below the insertion of the pronator teres.

determined whether the fracture is above or below its insertion (Fig. 572). In a fracture of the radius above the insertion of the pronator teres the upper fragment of the radius is pulled into supination by the supinator brevis and the biceps; the lower fragment is fully pronated. In such a fracture the biceps also will accomplish some flexion of the proximal fragment. In fractures below the attachment of the pronator teres the supinator brevis and the pronator teres will equalize each other between pronation and supination in the upper fragment and the lower fragment will be in full pronation.

The correct position for a radius fractured above the insertion of the pronator teres is with the elbow flexed and the hand

pect of the bone (Fig 570) The deep fascia and the dorsal carpal ligament are incised exposing the extensor digitorum communis muscle the extensor pollicis longus tendon the extensor pollicis brevis muscle the abductor pollicis longus muscle and the tendon of the extensor carpi radialis brevis a small part of the radius

also is visible The abductor pollicis longus, the extensor pollicis brevis and the tendon of the extensor carpi radialis brevis are retracted laterally, and the extensor digitorum communis and the tendon of the extensor pollicis longus are retracted medially This will expose the distal fourth of the radial shaft




FIG 570 Exposure of the distal fourth of the radius




FIG 571 Exposure of the shaft of the ulna

If a patient is found to have been severely injured the radial nerve can be seen and even in the presence of swelling. Normal relationship of the nerve between the styl of process and the olecranon should still be present along the forearm though the wrist and to the elbow.

A reverse Colles' fracture is called a *distal* fracture. This usually is produced by a fall on the back of the hand with the wrist flexed.

Epiphyseal separation may be confused with a Colles' fracture. It is common in children and may occur at any time up to the age thirty or the twentieth year. Here the radius takes the front of the injury in falling on the outstretched hand separation of the distal end of physes is rare.

Amputations

The site of election for forearm amputation is at the junction of the lower and the middle third. However, any site above this junction to within three or four inches

of the elbow will produce a good stump (Fig. 374). A distal forearm stump is difficult to fit because the biceps muscle pulls the limb outward when the elbow is flexed.

In amputations of the forearm anterior and posterior flap pedicles are made through the skin and the superficial flexor then cutting the flaps. The vertical incision is carried through the muscles to the bone. The muscles on the anterior and the posterior aspects of the forearm are divided to the bone and the posterior is flexed and retracted upward. The interosseous membrane is cut transversely at approximately the middle. The soft parts are retracted and the bones are sawed. Attempt is made to divide separately the radial, the ulnar, and the anterior and the posterior interosseous arteries. The median, the ulnar and the radial nerves are cut short. The muscles and the deep fascia are closed over the bone ends and the skin is closed with interrupted sutures.




FIG 575 Site of election in forearm amputations

supinated. In fractures below the pronator teres the thumb up (midprone) position is used with flexion at the elbow. In this position the palm of the hand faces the chest. The important rule in all fractures of the radius above the position of a Colles' fracture is to keep the elbow flexed, otherwise it will be impossible to maintain the forearm in any given position of rotation.

Where both the radius and the ulna are fractured, the broken ends of bone are usually drawn together by the supinators and the pronators, and the interosseous space is narrowed. The lower fragments may be displaced laterally or anteroposteriorly with overriding. Shortening of the forearm results.

The upper part of the *shaft of the ulna*

may be fractured, this usually is associated with anterior dislocation of the head of the radius due to the fact that the annular (orbicular) ligament also may be torn. This is so common an occurrence that in all fractures of the upper part of the ulna, radial dislocation should be ruled out. Fractures along other parts of the ulnar shaft are usually transverse and occur in the distal third of the bone, where muscle masses are replaced by tendons. Marked displacement usually is absent because of the splinting effect of the intact radius. There is however a tendency toward a narrowing of the interosseous space; this is brought about by a pull from the pronator quadratus muscle upon the lower fragment.

FRacture OF THE HEAD AND THE NECK OF THE RADIUS

Fracture of the head and the neck of the radius usually occurs in adults from indirect violence such as a fall upon the palm. Such a fracture produces interference with flexion and rotation of the forearm; these movements may produce crepitus. Reduction is brought about by pressure and flexion and fixation is maintained in supination and flexion. Excision may be necessary. Fracture of the neck of the radius usually results from indirect violence, the fracture occurring between the head and the bicipital tuberosity. The treatment may be open or closed reduction.

COLLES' FRACTURE

Colles' fracture involves the lower end of the radius; it is nearly transverse and within one inch of the articular surface of the bone. It produces a deformity due to dorsal displacement of the distal fragment and volar displacement of the proximal. Usually it is due to a fall upon the extended hand and the typical sign is the 'silver fork' deformity, in which there is a prominence upon the back of the wrist and a lateral displacement of the hand toward the radial side. This is not present if the fracture is impacted or incomplete.

If proper reduction has been accomplished the suture material can be made cut even in the presence of swelling. Normal relation is still existent between the styloid process and the ulna and a line should be present along the forearm although the wrist and to the hand.

A reverse Colles' fracture is called Smith's fracture. This usually is produced by a fall on the back of the hand with the wrist flexed.

Ulnar head separation may be confused with a Colles' fracture. It is common in children and may occur at any time up to the fifteenth or the twentieth year. Since the radius takes the thrust of the injury it falls on the distended hand separation of the distal ulnar epiphysis is rare.

AMPUTATION

The site of election in forearm amputation is at the junction of the lower and the middle thirds. However, any site above this junction to within three or four inches

of the elbow will produce a good stump (Fig. 524). A short forearm stump is difficult to fit because the biceps muscle pulls the elbow socket when the elbow is flexed.

In a patency of the forearm anterior and posterior U-shaped incisions are made through the skin and the superficial fascia thus outlining the flaps. The vertical incisions are cut through the muscles to the bone. The incises on the anterior and the posterior aspects of the forearm are divided to the bone and the periosteum is freed and retracted upward. The interosseous membrane is cut transversely at approximately the saw line, the soft parts are retracted, and the bones are sawed. Attempt is made to ligate separately the posterior ulnar and the anterior and the posterior interosseous arteries. The median, the ulnar and the radial nerves are cut short. The muscles and the deep fascia are closed over the bone ends and the skin is closed with interrupted sutures.

Wrist

The wrist is the link between the forearm and the hand. It contains the soft parts, the bones and the joints in that area which includes the carpus, the distal extremities of the radius and the ulna and the bases of the metacarpals. The radio carpal, the midcarpal and the carpometacarpal joints are located in the wrist and it is in this region that the tendons of the forearm cross on their way to insert onto the carpus. The tendons are held close to the wrist bones by thickenings of the deep fascia which form ligaments.

CARPAL BONES

There are eight small carpal bones which are arranged in two rows, proximal and distal. Each row consists of four bones which have received their names according to their general appearance. The proximal row, named from lateral to medial, consists of the navicular (scaphoid), the lunate (semilunar), the triquetrum (cuneiform) and the pisiform. The distal row, named from lateral to medial, presents the greater multangular (trapezium), the lesser multangular (trapezoid), the capitate (os magnum) and the hamate (unciform) (Fig. 574). These eight bones are more or less cubical in shape and therefore have six surfaces: proximal, lateral, distal, medial, palmar and dorsal. Of these, only two surfaces, the anterior and the posterior, are roughened by the attachments of the ligaments; the remaining four surfaces, which articulate with adjacent bones, remain smooth and are entirely or partly covered with cartilage. The lateral surfaces of the lateral bones and the medial surfaces of the medial bones also receive ligamentous bands and are also roughened.

The *navicular* (boat shaped) bone does not withstand an indirect blow well. Such a blow may be received by falling upon the palm of the hand in radial deviation; the bone is not adapted to receive such trauma because of its curved shape and obliquely curved axis. If the fall occurs, however, with the hand in ulnar deviation, only the proximal part of the bone is exposed to trauma. The navicular is the most commonly fractured of all the carpals. The *tubercle* of the scaphoid can be felt through the skin at the base of the thenar eminence and in line with the radial side of the middle finger. At times it forms a visible protrusion, but it usually is concealed by the tendon of the flexor carpi radialis, which inserts on it and can be felt when that muscle is relaxed. The distal transverse crease at the front of the wrist crosses this tubercle and the pisiform bone.

The *lunate* (moon shaped) is the middle bone of the proximal row. Its distal articular surface, with a part of the distal scaphoid articular surface, lodges the head of the capitate bone. It is the carpal bone which is dislocated most frequently.

The *triquetrum* (triangular shaped) articulates with the articular disk and by means of a specialized surface, it also articulates with the ulnar collateral ligament. This arrangement permits the triquetrum, with the pisiform on its volar aspect, to glide toward the ulna in ulnar flexion. The remainder of the proximal surface of the bone is nonarticular. The scaphoid, the lunate and the triquetral bones form the carpal articular surface in the radiocarpal joint.

The *pisiform* (pea shaped) bone is located at the base of the hypothenar

Wrist

The wrist is the link between the forearm and the hand. It contains the soft parts—the bones and the joints in that area—which includes the carpus, the distal extremities of the radius and the ulna and the bases of the metacarpals. The radiocarpal, the midcarpal and the carpometacarpal joints are located in the wrist, and it is in this region that the tendons of the forearm cross on their way to insert onto the carpus. The tendons are held close to the wrist bones by thickenings of the deep fascia which form ligaments.

CARPAL BONES

There are eight small carpal bones which are arranged in two rows: proximal and distal. Each row consists of four bones which have received their names according to their general appearance. The proximal row, named from lateral to medial, consists of the navicular (scaphoid), the lunate (semilunar), the triquetrum (cuneiform) and the pisiform. The distal row, named from lateral to medial, presents the greater multangular (trapezium), the lesser multangular (trapezoid), the capitate (os magnum) and the hamate (unciform) (Fig. 574). These eight bones are more or less cubical in shape and therefore have six surfaces: proximal, lateral, distal, medial, palmar and dorsal. Of these only two surfaces—the anterior and the posterior—are roughened by the attachments of the ligaments; the remaining four surfaces which articulate with adjacent bones remain smooth and are entirely or partly covered with cartilage. The lateral surfaces of the lateral bones and the medial surfaces of the medial bones also receive ligamentous bands and are also roughened.

The *navicular* (boat shaped) bone does not withstand an indirect blow well. Such a blow may be received by falling upon the palm of the hand in radial deviation; the bone is not adapted to receive such trauma because of its curved shape and obliquely curved axis. If the fall occurs, however, with the hand in ulnar deviation, only the proximal part of the bone is exposed to trauma. The navicular is the most commonly fractured of all the carpals. The *tubercle* of the scaphoid can be felt through the skin at the base of the thenar eminence and in line with the radial side of the middle finger. At times it forms a visible protrusion, but it usually is concealed by the tendon of the flexor carpi radialis, which inserts on it and can be felt when that muscle is relaxed. The distal transverse crease at the front of the wrist crosses this tubercle and the pisiform bone.

The *lunate* (moon shaped) is the middle bone of the proximal row. Its distal articular surface, with a part of the distal scaphoid articular surface, lodges the head of the capitate bone. It is the carpal bone which is dislocated most frequently.

The *triquetrum* (triangular shaped) articulates with the articular disk and by means of a specialized surface, it also articulates with the ulnar collateral ligament. This arrangement permits the triquetrum with the pisiform on its volar aspect to glide toward the ulna in ulnar flexion. The remainder of the proximal surface of the bone is nonarticular. The scaphoid, the lunate and the triquetral bones form the carpal articular surface in the radiocarpal joint.

The *pisiform* (pea shaped) bone is located at the base of the hypothenar

be remembered more easily if they are discussed and visualized in layers or planes (11, 576)

The first layer of structures consists of from lateral to medial the radial artery

bercle of the scaphoid bone and may be used as a guide to this latter structure. The *palmaris longus* tendon is not always present but if it is it crosses at a point which is in the middle of the wrist and therefore




FIG. 576 The structures which are located proximal to the distal skin crease of the wrist. These structures are considered as lying in three layers.

the flexor carpi radialis tendon the palmaris longus tendon the median nerve the flexor carpi ulnaris and the ulnar artery and nerve. The *radial artery*, after crossing, the pronator quadratus comes in contact with the lower end of the radius. It then lies on the skeletal plane and in this region it is covered only by skin superficial and deep fascia. This therefore is the correct site to feel the pulse. The artery is no longer in relation to the major portion of the radial nerve since the latter leaves it by winding around the radial border of the forearm deep to the brachioradialis tendon. The artery disappears deep to the abductor pollicis longus tendon. The *flexor carpi radialis tendon* lies between the radial artery and the median nerve. As it passes distally it pierces the deep fascia (flexor retinaculum) making a private tunnel for itself. In its course it travels over the tu-

bisects the distal skin crease. It crosses in front of the flexor retinaculum and continues into the palm as the palmar aponeurosis. It lies immediately above the median nerve. If absent the nerve is more exposed to injury hence this tendon might be considered as the 'roof' or protector of the median nerve. The *median nerve* is behind the flexor digitorum sublimis in the forearm, but in the region of the wrist it appears at the lateral border of and somewhat above this muscle. It is differentiated from the surrounding tendons by the fact that numerous small vessels (vasa nervorum) are noted distinctly on its surface. At the wrist it lies directly behind the palmaris longus tendon the deep fascia intervening between the palmaris longus and the nerve the latter usually clings to this deep fascia. At times a small 'median artery' accompanies it. The *flexor carpi*

year with the exception of the pisiform, which undergoes ossification about the twelfth year all the carpal bones are in the process of ossification by the eighth year. As a whole, the bones of the carpus

THE DISTAL SKIN CREASE

The distal skin crease of the wrist is always visible and is an excellent landmark (Fig 575). It crosses the tip of the styloid




FIG 575 The distal skin crease of the wrist

are fitted closely together but permit a certain amount of movement, thereby giving a degree of flexibility to the wrist. The proximal surface of the carpus reveals that the pisiform has been placed in front of the triquetrum leaving only three bones of the proximal row in the articulation with the wrist joint above and the distal row of carpal bones below. The widened distal end of the scaphoid supports two bones, the trapezium and the trapezoid. The distal surface of the carpus on the other hand is quite irregular since five metacarpal bones must articulate with four distal carpal bones. The fourth and the fifth metacarpals articulate with the hamate. The carpus as a whole forms a surface which is concave from side to side on its palmar aspect and convex over its dorsum. The extremities of this concavity give attachment to the flexor retinaculum (transverse carpal ligament) (p 752). This ligament, plus its bony attachment forms the osteofascial tunnel for the flexor tendons of the fingers.

process of the radius and the lower part of the lunate bone. It has the following features: it marks the proximal border of the transverse carpal ligament and the proximal row of the carpal bones. It is bisected by the tendon of the palmaris longus (the clenched fist renders this tendon prominent). The median nerve lies immediately beneath the tendon of the palmaris longus; therefore we may say that the median nerve bisects the crease. The flexor carpi radialis tendon crosses its lateral third and the flexor carpi ulnaris is at the extreme medial end of the crease.

It is interesting to flex the index finger and observe the wrist. Although the index is radially placed, the tendon produces movements on the ulnar side of the wrist. This illustrates the point that all the tendons of the flexor digitorum sublimis and the profundus lie on the ulnar side of the wrist; these tendons therefore lie between the ulnar and the median nerves.

Structures Which are Proximal to the Distal Skin Crease. These structures will

bones and the transverse carpal ligament form an osseofibrous tunnel called the *carpal tunnel*. Proximally, the ligament is continuous with the deep fascia of the forearm; distally, it merges with the palmar fascia. The structures *superficial* to the transverse carpal ligament are the palmaris longus tendon, the ulnar nerve and artery, the superficial branch of the radial artery and the cutaneous nerves and veins. The structures passing *deep* to the transverse carpal ligament are the median nerve, the flexor digitorum sublimis, the flexor digitorum profundus and the flexor pollicis longus.

Unnecessary confusion seems to exist between the volar carpal ligament and the transverse carpal ligament. The *volar carpal ligament* is a fascial process which passes from the pisiform bone and the flexor carpi ulnaris medially to the palmar surface of the transverse carpal ligament laterally. In this way it forms the roof of a tunnel for the ulnar artery and nerve; the floor of the tunnel being formed by the medial border of the transverse carpal ligament. The median nerve, the flexor digitorum sublimis, the flexor digitorum profundus and the flexor pollicis longus cross under the ligament. The flexor carpi radialis goes through the ligament, creating in this way a fibrous tunnel for itself.

JOINTS

RADIOCARPAL (WRIST) JOINT

This is the joint which exists between the forearm and the hand, the other joints in this region being known as the intercarpal joints (Fig. 579). The proximal surface of the radiocarpal joint is formed by the concave lower articular surface of the radius and the articular disk; the distal surface is formed by the convex scaphoid, the lunate and the triquetrum bones. Union is maintained by a capsular ligament which is strengthened by the anterior and the posterior radiocarpal, and the lateral and the medial ligaments of the wrist.

The *capsular ligament* is of moderate

strength and is attached close to the margins of the articular surfaces. The *anterior* and the *posterior* ligaments only moderately strengthen their respective aspects of the capsule. The fibers of these ligaments




FIG. 578 The flexor retinaculum (transverse carpal ligament). Its attachments to the four end bones of the carpus are shown.

pass obliquely downward and medially from the front and the back of the proximal row of carpal bones and to the capitate. During pronation and supination of the forearm, therefore, the radius draws the carpal bones after it. The *lateral (radial collateral) ligament* passes from the radial styloid process to the tuberosity of the navicular and the greater multangular. The radial artery crosses it. The *medial (ulnar collateral) ligament* extends from the styloid process of the ulna to the pisiform and the triquetrum.

The *synovial membrane* lines the interior of the capsular ligament, the inferior surface of the articular disk and the two interosseous ligaments which complete the carpal surface. It does not communicate with the intercarpal joints. The blood supply is derived from the carpal branches of the radial, the ulnar and the interosseous arteries and the recurrent branches of the deep palmar arch. The nerve supply of the radiocarpal joint is derived from the anterior and the posterior interosseous nerves and the dorsal and the deep branches of the ulnar nerve.

The *active movements* at the wrist joint are flexion, extension, abduction (radial

ulnaris tendon lies at the medial extremity of the distal skin crease. It forms a "roof" and protection for the ulnar nerve and artery and acts as a guide to the pisiform bone. The muscle does not become entirely

maunder of the muscle about halfway down the forearm and represents a large structure. These four tendons do not lie two upon two, as do the tendons of the *flexor digitorum sublimis*, but they all lie in the




FIG 577 Deep dissection in the wrist showing the arrangement of the tendons

tendinous, but as far as the wrist distinct muscular fibers of the *flexor carpi ulnaris* accompany the tendon, so that it is really half tendon and half muscle. The *ulnar artery* and *nerve* are both protected by the overlying *flexor carpi ulnaris* tendon. They are bound together closely by connective tissue and it is extremely difficult to ligate the artery in this region without incorporating the nerve.

The second layer consists of the *flexor digitorum sublimis*. This group of four tendons lies between the median and the ulnar nerves and, as they pass forward into the palm, the tendons of the middle and the ring fingers are placed somewhat in front of those for the index and the little fingers (Fig 577).

The third layer consists of the *flexor digitorum profundus* and the *flexor pollicis longus*. The four tendons of the *flexor digitorum profundus* enter the hand by passing behind the *sublimis*. The tendon for the index finger separates from the re-

main plane (Fig 577). The *flexor pollicis longus* tendon lies in the same plane as the *flexor digitorum profundus* but is easily separated from it since it travels in its own synovial sheath. It is found immediately beneath and lateral to the median nerve. At the extreme lateral (radial) margin of the wrist the tendons of the *abductor pollicis longus* and the *extensor pollicis brevis* are found. They form the 'anterior margin of the anatomic snuff box' (p 737).

Structures Which Are Distal to the Distal Skin Crease The *transverse carpal ligament* has been referred to as the anterior annular ligament and the *flexor retinaculum*. It is a specialized portion of the deep fascia of the forearm which assumes the form of a tough fibrous band stretching across the arch formed by the carpal bones. It attaches to the four end bones of the carpus namely the navicular (scaphoid) and the greater multangular (trapezium) laterally, and the pisiform and the hamate medially (Fig 578). The arched carpal

bones but also between the scaphoid and the lunate between the lunate and the triquetrum and downward between the bones of the distal row. Generally the cavity communicates with the joint cavities of the four medial carpometacarpal and the intermetacarpal joints. The opposed surfaces of the carpal bones which are nonarticular are connected to each other by interosseous ligaments.

The intercarpal joints derive their nerve supply from the anterior and the posterior interosseous nerves and the dorsal and the deep branches of the ulnar nerve. The movements at these joints supplement those at the radiocarpal joints and increase the range of movements of the hand. Between the individual bones of each row the movements are of a gliding character and are quite limited.

CARPOMETACARPAL AND INTERMETACARPAL JOINTS

The metacarpal bone of the *thumb* articulates with the os trapezium by a joint which is entirely separated from the other carpometacarpal joints (Fig. 580). It is a synovial joint of the saddle variety and because of its shape permits a wide range of movements. The articular capsule which surrounds it is sufficiently lax to permit these movements. The *medial four metacarpal bones* are connected to the carpus by the palmar and the dorsal ligaments and by one interosseous ligament. A medial ligament is present also; this closes the medial side of the joint of the fifth metacarpal bone. The interosseous ligament arises from the continuous distal margins of the capitate and the hamate bones and runs to the medial side of the base of the third metacarpal bone. The metacarpal bones of the fingers are united by strong ligaments and articulate with each other at their bases. The ligaments which bind the medial four metacarpals together are (1) a series of palmar and dorsal metacarpal ligaments which pass transversely between the palmar and the dorsal surfaces

of the bases (2) three interosseous ligaments which pass between the nonarticular parts of the sides of continuous bases (3) the deep transverse ligament of the palm which indirectly connects the heads of the bones. Though the intercarpal, the carpometacarpal and the intermetacarpal joints are spoken of individually as having separate ligaments, they constitute one single ligament which surrounds a continuous joint cavity. (The pisiform joint and the carpometacarpal joint of the thumb possess separate capsules.) The synovial membrane lines all the ligaments and is prolonged over all the intra-articular parts of the bone that do not contain articular cartilage.

METACARPOPHALANGEAL AND INTERPHALANGEAL JOINTS

The *metacarpophalangeal joints* are synovial joints which form where the head of the metacarpal articulates distally with the base of the proximal phalanx and anteriorly with the palmar ligament. Union is maintained by a capsular ligament which is greatly strengthened in front by the palmar ligament and at the sides by collateral ligaments. The *capsular ligament* is attached near the margin of the articular surfaces but posteriorly it is defective and its place is taken by the expanded extensor tendon. The *collateral ligaments* are strong oblique bands which pass downward and forward from the sides of the head of the proximal bone of the joint to the sides of the base of the distal bone. The *palmar ligament* is a dense fibrous plate which is the thickened palmar part of the capsular ligament. At the sides it fuses with the collateral ligaments and is connected with the deep transverse ligaments of the palm. Distally it is attached to the base of the phalanx; proximally it is loosely connected with the palmar surface of the metacarpal immediately above the head. It forms part of the socket and articulates with the front of the head. Its palmar surface is smooth and is covered by the flexor tendons and their synovial sheaths. In a metacarpophalangeal

deviation) adduction (ulnar deviation) and circumduction, the last being produced by a combination of the preceding movements. Rotation of the carpus and the hand around a vertical axis cannot be performed actively. Movements are checked in some

The *pisiform joint* is a small synovial joint which possesses a cap ular ligament and a synovial membrane. Its cavity is shut off from the other joint cavities of the carpus.

The *transverse carpal joint* is a synovial




FIG 579 The radiocarpal (wrist) joint, seen in frontal section




FIG 580 The radiocarpal, the intercarpal and the carpometacarpal joints. Frontal section through the joints of the carpus

cases by ligaments and tendons. When the fingers are flexed, the stretched extensor tendons do not allow full flexion of the wrist. Abduction is less free than adduction because the styloid of the radius meets the carpus.

INTERCARPAL JOINTS

In the carpus there are two joint cavities, the pisiform and the transverse carpal (Fig 580).

joint which is common to the other intercarpal joints, it also has been referred to as the intercarpal or midcarpal joint. It is located between the bones of the proximal and distal rows of the wrist. These bones are connected to one another by palmar and dorsal ligaments and at the radial and the ulnar extremities of the joint by the lateral and the medial ligaments. The synovial membrane which lines this joint cavity is thin, not only between the two rows of

process is altered. Dislocation usually involves the radiocarpal articulation frequently it is compound and the articular edge of the radius may be fractured. True dislocation may occur from great violence and the inferior end of the radius and the

ulna in a faulty position, wrist drop or arthritis (Fig. 582). The position of choice (optimum position) for ankylosis should be sought, this is a 30° extension with some degree of ulnar deviation. In this position the flexors and the extensor




FIG. 582. Arthrodesis of the wrist joint. (A) skin incision and division of the dorsal carpal ligament. (B) retraction of the extensor tendons and incision into the capsule. (C) the joint cavity is exposed and the radius is curetted.

ulna then protrude either to the dorsal or the volar surface of the wrist. In dorsal dislocation of the carpus the deformity may resemble a Colles' fracture but it is closer to the hand. Dislocation of the inferior radio-ulnar joint is an extremely rare wrist dislocation but it may complicate a fracture. Reduction should be accomplished by pressure upon the displaced bone with supination.

ARTHRODESIS OF THE WRIST JOINT

A surgical bony ankylosis of the wrist joint usually is created for flail wrist,

are in proper balance. With the hand in pronation a dorsal incision is begun opposite the center of the second metacarpal. It is continued obliquely upward bisecting a line drawn between the styloid processes and ending about two inches above the radial styloid. The dorsal carpal ligament is exposed and divided, and the extensor tendons are retracted. The capsule is opened so that the proximal row of carpal bones is exposed. A small wedge may be removed from the radius, the navicular and the lunate bones, or the bony surfaces may be curetted.

joint of a finger the margins of the palmar ligament give attachment to the deep transverse ligament of the palm and partial attachment to the processes of the palmar aponeurosis

The *interphalangeal joints* are similar in structure to the metacarpophalangeal




FIG 581 The mechanism of injury to the navicular or lunate bone. The arrows indicate the direction of force following a fall on the outstretched hand

joints. They are of the synovial variety and have capsular collateral and palmar ligaments. The interphalangeal joints have ligaments corresponding to those of the metacarpophalangeal joints but since they do not have rounded heads they do not permit adduction or abduction.

SURGICAL CONSIDERATIONS

Injuries to the carpal bones result from falls upon the outstretched palm; the force being directed from the third metacarpal to the capitate and then to the navicular

and the lunate (Fig 581). Any type of injury may result; the most common is fracture of the navicular, and the next most frequent is dislocation of the lunate.

FRACTURE OF THE NAVICULAR (SCAPHOID) BONE

Fracture of the navicular (scaphoid) bone is more frequent than had been suspected previously. As a result of a fall upon the outstretched hand, the navicular is brought directly under the radius and is pinched between it and the capitate bone. Treatment is by reduction and immobilization. Excision of the navicular, either total or partial, should be avoided if possible, since this leaves a permanent disability.

DISLOCATION OF THE LUNATE (SEMILUNAR) BONE

Dislocation of the lunate (semilunar) bone is caused by a fall on the outstretched hand which results in a momentary backward dislocation of the wrist. Since the lunate is attached more firmly to the radius and the ulna than are the other carpal bones, it does not take place in the backward dislocation; its ligamentous connection with the other carpals is torn. The backward wrist dislocation spontaneously reduces itself and on returning knocks the lunate forward. The proximity of the median nerve must be kept in mind, since an anteriorly dislocated lunate may produce signs of median nerve involvement. The dorsal ligament, which contains the important nutrient vessel to the bone, may be injured and this may result in a progressive degeneration called Kienboch's disease.

DISLOCATIONS OF THE WRIST

Dislocations of the wrist are rare; they may be forward or backward and their importance is mainly in their recognition since they may resemble a Colles' or Smith's fracture. In dislocations the relationship between the styloid processes is preserved but the relation of the carpal bones to these

Hand

The hand is an organ which is directed by the will and is capable of a great variety of complicated movements. These movements are possible because of the highly co-ordinated actions of its intrinsic and extrinsic muscles and its numerous joints. The thumb is all important to the hand since the property of apposition depends upon it; without this the functional capacity of the hand is reduced greatly.

The hand can be divided conveniently into the palmar region, the dorsal region and the phalanges.

PALMAR REGION

This region is quadrilateral in shape and contains the soft parts in front of the metacarpal bones. The hollow of the hand is the triangular central part which is bounded on the radial side by the thenar eminence and on the ulnar side by the hypothenar eminence. These eminences approximate each other as they approach the wrist. It is helpful to consider the central part of the palmar region and then to discuss the thenar and the hypothenar eminences. The central part of the palm consists of the following nine layers, from superficial to deep (Fig. 583).

- 1 The skin
- 2 The subcutaneous tissue
- 3 The palmar aponeurosis
- 4 The superficial volar arch and the median nerve
- 5 The flexor tendons, their sheaths and the lumbrical muscles
- 6 The deep palmar spaces
- 7 The deep volar arch and the ulnar nerve

8 The adductor pollicis and the interosseous muscles

9 The metacarpal bones

The Skin The skin of the palm is thicker, coarser and more vascular than that of the dorsum of the hand. It is thinner over the thenar eminence and especially thick over the heads of the metacarpals. It is free from hairs and sebaceous glands but is well supplied with sweat glands. Two transverse skin creases (proximal and distal) are present in the palm (Fig. 584). The proximal crease accommodates movements of the index finger and approximately marks the convexity of the superficial volar arterial arch. The distal crease accommodates movements of the medial three digits and marks the heads of the third, the fourth and the fifth metacarpals. A vertical palmar crease which limits the thenar eminence also is present.

A series of longitudinal grooves extend from the roots of the fingers toward the palm; between these grooves are raised intervals of fatty tissue. The grooves correspond to the digital slips of palmar fascia, and the raised intervals mark the lumbrical spaces which contain the digital vessels, the nerves and the lumbrical muscles.

The palmar region of the hand receives its cutaneous nerve supply from the following nerve branches (Figs. 584 and 586): the *palmar cutaneous branch of the median nerve* arises about one inch above the wrist, passes obliquely downward behind the flexor carpi radialis tendon and pierces the deep fascia between that tendon and the tendon of the palmaris longus. It then descends, branching as it goes, to supply the

AMPUTATIONS AND DISARTICULATIONS

Amputations and disarticulations at the wrist joint prevent the proper fitting of artificial hands; if possible they should be avoided. There are times, however, when carpometacarpal disarticulation is indicated; if possible the thumb and a finger or other parts of the hand should be saved. A U-shaped incision is begun on the palmar side about half an inch below the styloid process of the radius passing down to the middle of the second metacarpal where it arches across the middle of the remaining metacarpals and ends about one inch be-

low the styloid of the ulna. The dorsal incision is placed transversely across the carpal bones and connects with the palmar incision. The palmar flap is deepened to the flexor tendons and is reflected to the joint. The extensor tendons and ligaments are divided, the joint is traversed and the flexor tendons and the remaining tissues are severed in similar fashion. Tendons and nerves are cut short. Some authorities advocate suturing the tendons together, but others permit them to retract. After careful hemostasis, the wound is closed in layers.




FIG 554 The skin creases and the cutaneous nerve supply of the palmar region




FIG 555 The palmar aponeurosis. The triangular intermediate part is thick and strong but the medial and the lateral parts are thin and weak.

skin of the hollow of the palm. The *palmar cutaneous branch of the ulnar nerve* is very slender and at times is difficult to find. It arises at a variable point below the middle of the forearm and passes downward over the ulnar artery. It pierces the deep fascia near the wrist and supplies the skin over the medial third of the palm. The *terminal part of the radial nerve* pierces the deep fascia about two inches above the styloid process of the radius at the lateral border of the front of the forearm. It descends crossing the tendons that overlie the lateral surface of the distal end of the radius and supplies the skin over the thenar eminence. The *palmar digital nerves* are seven in number: two arise from the ulnar nerve and are distributed to the little finger and the medial half of the

ring finger. The others arise from the median nerve and are distributed to the outer three and a half digits. These nerves are accompanied by the palmar digital vessels, which are in front of them in the palm but behind them at the sides of the fingers. They supply the joints of the digits and the soft parts on the sides and the front of the fingers. Each nerve terminates at the end of the digit by dividing into two branches, one of which enters the pulp of the digit and the other the bed of the nail.

The Subcutaneous Tissue. The skin is bound to the palmar aponeurosis by fibrous septa between which quantities of granular fat are present. This fat constitutes the *subcutaneous tissue*. Over the ball of the thumb (thenar eminence) and the ball




FIG. 583 Cross section through the right hand showing the nine layers in the center of the palmar region of the hand

noticed that the elevations are bounded by four vertical depressions which mark the fusion of the digital processes of the palmar fascia with the fibrous sheath containing the flexor tendons. These elevations

fuse with the theca (fibrous tendon sheath). Their contents are fatty tissue, lumbrical muscle and the digital vessels and nerves.

The Superficial Volar Arch and the Median Nerve. The *superficial volar (pal-*




FIG. 586. The volar arches and the median and the ulnar nerves. The superficial volar arch is formed mainly by the ulnar artery and a small branch of the radial artery; the deep volar arch is formed mainly by the radial artery and a small branch of the ulnar artery.

mark three intervals of surgical importance which have been referred to by such names as commissural spaces, lumbrical canals or web spaces. They are important because infections extending from the subcutaneous tissue of the finger to the subaponeurotic spaces of the palm must pass by way of these spaces. The space is bounded anteriorly by the superficial transverse palmar ligament, posteriorly by the deep transverse metacarpal ligament and laterally by the digital processes of the palmar fascia which

mar) arch lies immediately beneath the palmar aponeurosis and upon the branches of the median nerve (Fig. 586). It is formed by a continuation of the ulnar artery and one of the three branches of the radial artery (superficial palmar, princeps pollicis or radial indicis). The anastomosis between the ulnar artery and the radial branch is so complete that both ends require ligation when the arch is cut. The arch lies superficial to the flexor tendons, the lumbrical muscles and the digital branches of the

of the fifth finger (hypothenar eminence) this fat is not so plentiful or granular. Where skin creases are found subcutaneous fat is present in small amounts or is absent entirely hence perforating injuries are serious in these locations.

The *palmaris brevis* muscle (Fig 585) is a superficial sheet of muscle which arises from the flexor retinaculum and the ulnar margin of the palmar aponeurosis. It passes medially, superficial to the ulnar vessels and nerve and inserts into the skin of the ulnar border of the hand. The superficial branch of the ulnar nerve supplies it. This muscle raises the skin and the fascia over the hypothenar eminence when the fingers bend; this enables the hand to grasp more firmly.

The webs of the fingers are present over the palm of the hand but are absent on the dorsum. In these webs transverse fibers (superficial transverse ligaments) are found. These should not be confused with the superficial transverse metacarpal ligaments which are incomplete and pass across the webs just anterior to the digital vessels and nerves.

The *palmaris brevis* muscle (ulnar nerve) is thin and subcutaneous and lies across the uppermost inch of the hypothenar eminence, hiding the termination of the ulnar artery and nerve. It arises from the flexor retinaculum and the palmar aponeurosis and is inserted into the skin of the ulnar border of the hand. If the palm of the hand is placed in the position of scooping up water the skin over the hypothenar eminence is thrown into wrinkles caused by the action of the *palmaris brevis*. This muscle must be severed and reflected before the hypothenar fascia and muscles become visible.

The Palmar Aponeurosis. The *palmar aponeurosis* is the deep palmar fascia; it is divided into medial, lateral and intermediate parts (Fig 585). The medial and the lateral portions are thin and weak and they extend over the hypothenar and thenar eminences respectively. The intermediate

part is thick and strong and is the palmar aponeurosis proper. It is triangular in shape with its apex placed proximally, where it becomes continuous with the palmaris longus tendon and the flexor retinaculum. Opposite the distal transverse palmar crease it divides into four slips, one going to each finger. Between these slips the digital vessels and nerves and the lumbrical muscles are located. Each slip divides into two processes between which the flexor tendons pass. These processes diverge and attach along the inner and outer aspects of the proximal phalanges and to the proximal part of the second phalanges. They are continuous with the fibrous flexor sheath and assist in flexion; they also bind the flexor tendons to the front of the fingers. A spontaneous contracture of the palmar fascia results in a flexion of the fingers which is known as Dupuytren's contracture. At the base of the palmar fascia the diverging slips are connected to one another by transverse fibers called the superficial transverse metacarpal ligament. In order to avoid confusion concerning these ligaments it is wise to recapitulate: (1) The *superficial transverse (palmar) ligament* appears in the webs of the fingers as a thin band of transverse fibers. It stretches across the roots of the four fingers; however at times it is incomplete. (2) The *superficial transverse metacarpal ligament* is a part of the palmar aponeurosis which connects the diverging slips of fascia. (3) The *deep transverse metacarpal ligament* holds the heads of the metacarpal bones together on their palmar surfaces. (4) The *dorsal transverse metacarpal ligament* holds the heads of the metacarpal bones together on their dorsal aspect. Between the four digital processes of the central portion of the palmar fascia are three intervals. These are occupied by fat in which is imbedded the digital arteries, the nerves and the lumbrical muscles. Corresponding to these intervals in the distal part of the palm are three slight elevations. If the palm is inspected, it is




FIG 588 The arrangement of a tendon sheath

strong. These structures (flexor retinaculum, palmar aponeurosis and fibrous flexor sheath) constitute a single continuous fibrous plate the main function of which is to hold the tendons in position and to increase their efficiency. The arrangement of the fibrous flexor sheaths converts part of the tendon sheaths into cul-de-sacs. Directly beneath these resting on the palm, the pace is restricted greatly so there is little or no room for pus. On the other hand, toward the inner end in front of the second joint and also in front of the metatarsophalangeal joint dilatations in which pus may collect exist. In contrast to the arrangement in the foot the palmar aponeurosis gives no fibrous extension to the thumb. The wide range of motion of the thumb is due to this fact and is characteristic of the human hand.

The *synovial* or mucous sheath is a lubricating device in tubular form which encloses a tendon. These are necessary for the flexor tendons since they rub on the back of the flexor retinaculum during flexion of the wrist and during extension they rub against the carpal bones and the anterior margin of the lower end of the radius. These tendon sheaths therefore act as bursae. The sheath forms a sac which is closed at both ends and is made up of glistening endothelial lined membranes (Fig 588). Each tendon within its sheath has or did have a mesotendon which is a double layer of synovial membrane attaching the tendon to the wall of the sheath and carrying vessels to it. It is attached to the side of the tendon which has least friction. The flexor tendons (sublimis pro-

fundus and pollicis) must have these sheaths first where they pass through the osseofibrous carpal tunnel and then where they pass through the osseofibrous digital tunnel. Therefore there are carpal synovial and digital sheaths. In the thumb however the sheath is always in continuity but that of the fifth finger may fail to unite in about 10 per cent of the cases and thus be identical with that of the other fingers. The sheaths of the index, the middle and the ring fingers remain separate (Fig. 589 and 590). The carpal sheaths of the four sublimis and the profundus tendons become one and are then known as the *common flexor (carpal) sheath*; this has a laterally placed mesotendon.

The digital synovial sheaths of fingers two, three and four extend from the neck of the metacarpal bone to the base of the third phalanx where the profundus tendon ends. Over the middle third of these metacarpal bones the corresponding tendons have no sheaths. The *common flexor synovial sheath* extends for about one-half to one inch above and below the flexor retinaculum. The sheaths investing the tendons to the fifth finger as a rule continue proximally without interruption to join the common flexor sheath at the wrist. This




FIG 589 The synovial sheaths

median nerve in the hand. These digital vessels and nerves cross each other in their trip through the palm; hence in the fingers the nerve lies superficial to the vessels. The medial three and one half fingers are

to the second lumbrical is derived. The motor part of the median nerve, therefore, supplies five muscles: the three thenar muscles (abductor pollicis brevis, opponens pollicis and flexor pollicis brevis) and the two




FIG 587 Distribution of the median nerve. The median nerve has both sensory and motor fibers. Its motor fibers supply five muscles of the hand; namely, the three thenar thumb muscles and the first two lumbricals.

supplied by the arch through four digital vessels. The branch to the fifth finger does not bifurcate but travels along the ulnar border of this finger. The other three digital branches bifurcate in the second, the third and the fourth finger webs, each being distributed to its respective finger borders. The proximal transverse palmar skin crease marks the convexity of the arch.

The median nerve enters the palm behind the transverse carpal ligament and at the distal border of the ligament it breaks up into lateral and medial divisions (Fig 586 and 587). The lateral division supplies the thenar muscles (recurrent branch) both sides of the thumb and the radial side of the index finger. The digital branch to the index finger supplies a branch which innervates the first lumbrical muscle. There are two medial divisions, both bifurcate to supply the adjacent sides of the index, the middle and the ring fingers. From the first of these divisions the nerve supply

lateral lumbricals (lumbricals 1 and 2). The sensory fibers of the median nerve supply the lateral three and one half fingers and the corresponding part of the palm.

The Flexor Tendons, Their Sheaths and the Lumbrical Muscles. As the flexor tendons (*sublimis profundus* and *pollicis*) pass under the transverse carpal ligament and into the palm, they are provided with two sheaths: a fibrous and a synovial.

The fibrous sheaths of the thumb and the little finger are similar in construction to those of the middle three fingers. With the underlying bone they form strong osteo-fascial tunnels which retain the tendons in place. A pair of tendons (*sublimis* and *profundus*) pass under each fibrous flexor sheath. The sheaths attach to the lateral and the medial borders of the phalanges. In front of the joints they are pliable and thin, but in front of the bodies of the proximal and the middle phalanges the fibers are curved transversely and are



FIG 591 The insertion of the flexor tendons. The ulnaris separates, and the profundus perforates

the radial side of the tendinous expansions of the extensor digitorum communis of the medial four fingers (Fig 592). They are peculiar in that they arise from flexor tendons and insert into extensors. Each lumbrical muscle passes to the radial side of the corresponding finger and is accompanied by the digital vessels and nerves. They lie behind the vessels and the nerves and on the deep transverse metacarpal ligament the interossei lie behind this ligament. The lateral two lumbricals arise by single heads from the radial sides and volar surfaces of the deep tendons of the index and the middle fingers. The medial two each arise by two heads from adjacent sides of the tendons of the middle, the ring, and the little fingers. These slender muscles end in delicate tendons which pass backward across the lateral surface of the metacarpophalangeal joint and connect with the expansion of the extensor tendon. It is inserted with the tendon of an interosseus muscle into the base of a terminal phalanx. They flex the finger at the metacarpophalangeal joints but extend them at the two interphalangeal joints through the medium of the extensor expansions. The action of the muscle is interesting since in suppurative tenosynovitis of the flexor tendons and their sheaths complete loss of function may result yet often the patient can flex the metacarpophalangeal joint by means of the lumbrical muscles. The lateral two lumbricals are supplied on their superficial surface by the median nerve. The medial two are supplied on their deep surface by the deep branch of the ulnar nerve. The lateral two arise by single heads and the medial lumbricals arise by

double heads. This fact is important because it explains the formation of a fibrous septum which divides the palm into mid palmar and thenar spaces. Any fibrous septum (partition) which extends from the palmar aponeurosis is deep into the palm is interrupted by the double headed lumbricals which are associated with the fourth and the fifth fingers. Such a lamina however can be carried back on the lateral side of the belly of the second lumbrical throughout its entire extent and insert onto the third metacarpal bone. In this way a fibrous partition is formed which passes from the under surface of the palmar aponeurosis to the third metacarpal bone. This fibrous septum is the fascial investment of the second lumbrical muscle (Fig 593). Such a partition also could be associated with the first lumbrical muscle, but because of the greater mobility of the second digit, the fibrous tissue associated with its lumbrical is lax and thin and forms no barrier across the palm. In this way two spaces are formed: a middle palmar and a thenar.

The Deep Palmar Spaces. The deep palmar spaces exist between the deep flexor tendons and the lumbrical muscles on the palmar side, and also between the interosseous fascia covering the metacarpal bones




FIG 592 The four lumbrical muscles




FIG 590 The arrangement of the flexor tendon sheaths in the fingers, the hand and the wrist. The ulnar bursa has been divided into its three component parts

common flexor sheath with its extension along the little finger is called the *ulnar bursa*. The tendon of the thumb has a sheath which extends from the base of the last phalanx to one inch beyond the proximal border of the wrist joint: this is called the *radial bursa*. These two bursae have been discussed elsewhere (p 781): they may be separate or they may communicate with each other. Should they communicate an infection can spread easily from one sheath to the other. Thus in a tenosynovitis of the thumb the infection may extend along the sheath and infect the sheath of the little finger via such a communication. The radial and the ulnar bursae lie upon the front of the carpus and are separated from the wrist and intercarpal joints only by ligaments. Therefore these joints

may become infected from such suppurative processes.

Certain portions of the original mesotendons of the flexors may remain as triangular folds *vincula* which pass between the tendons and the phalanx. The blood vessels run in the vincula to the tendons as they would in any mesentery.

Opposite the base of the proximal phalanx the sublimis tendon divides so that the profundus tendon can pass to its insertion into the volar aspect of the base of the distal phalanx. The slips of the sublimis tendon insert into the volar surface of the base and the sides of the middle phalanx (Fig 591).

The *lumbrical muscles* are four fleshy muscles which arise from the tendons of the flexor digitorum profundus and insert into

The roof is made up of the flexor tendons and lumbricals of the medial three digits. The floor consists of the dense fascia covering the medial two and a half metacarpal bones and their corresponding interossei.

The Deep Volar Arch and the Ulnar Nerve Two arteries take part in the formation of the *deep volar arch*, the radial and the deep branch of the ulnar (Fig. 586). The radial plays the chief part in




FIG. 595 The retroflexor space of Parona

muscles The lateral wall is made up of the fibrous septum described above and separates it from the thenar space. The medial wall is made up of the hypothenar muscles which are separated from the midpalmar space by the attachment of the palmar aponeurosis which passes to the fifth metacarpal bone. Distally the space extends almost to the level of the distal palmar crease; proximally it reaches the level of the distal margin of the transverse carpal ligament (Fig. 610). The midpalmar space is connected potentially with the so-called Parona's retroflexor space (Figs. 590 and 595). It has been referred to as the forearm space and has the following boundaries: anteriorly the flexor digitorum profundus (ulnar bursa) and the flexor pollicis longus in its synovial sheath (radial bursa), posteriorly the pronator quadratus and the interosseous membrane; proximally it is continuous with the intermuscular spaces of the forearm; distally, it reaches the level of the wrist; and laterally the space extends to the outer and the inner borders of the forearm. It is along these lateral borders that the space is drained by incisions

its formation. On leaving the forearm, the radial artery winds around the radial side of the wrist and crosses the dorsal surface of the navicular and the trapezium (greater multangular). It then passes through the anatomic snuff box (abductor pollicis longus, extensor pollicis brevis and extensor pollicis longus) to gain entrance to the proximal end of the first interosseous space. It continues medially and, in the palm, appears between the oblique and the transverse heads of the adductor pollicis. It turns medially and joins the deep branch of the ulnar artery at the base of the fifth metacarpal bone. The arch thus formed passes across the metacarpal bones immediately distal to their bases. The deep arch is about a fingerbreadth nearer the wrist than is the superficial; its convexity is directed toward the fingers. The deep branch of the ulnar nerve lies in its concavity. This arch lies deep to the flexor tendons and upon the volar interosseous muscles. Three arteries usually arise from the radial: the superficial palmar, which supplies the thenar eminence; the princeps pollicis to the thumb; and the radial in

and the interosseus muscles dorsally (Fig 594 A) Localization of pus in this space and the spread of dyes when injected under pressure indicates that it is divided into two compartments The work of Kanavel

a distal diverticulum of the space (Fig 609)

The *midpalmar space* lies in the inner half of the hollow of the hand, it has a roof, a floor and lateral and medial walls




FIG 593 The fascia of the lumbrical muscles The fascia of the second lumbrical forms the fibrous septum which separates the thenar from the midpalmar space

and Spaulding has shown that the lumbrical fascia of the second lumbrical passes to the lateral side of the muscle thereby producing one complete anteroposterior septum which passes from the palmar aponeurosis to the third metacarpal bone (Fig 593) This septum divides the deep palmar space into two a thenar space laterally and a midpalmar space medially

The *thenar space* lies under the outer half of the hollow of the palm it has a roof, a floor and lateral and medial walls The roof is made up of the flexor tendons the lumbricals of the second digit, and the thenar muscles The floor is formed by the two heads of the adductor pollicis particularly its transverse head (Fig 594 B) The medial wall is made up of the fibrous septum (fascia of the second lumbrical muscle), and the lateral wall is formed by the flexor pollicis longus tendon and its synovial sheath This space may be mapped out on the hand proximally from the distal border of the anterior annular ligament to the transverse palmar crease distally The first lumbrical sheath extends as




FIG 594 The two palmar spaces (A) The thenar space is laterally placed and the midpalmar space is medial (B) The posterior boundaries of the two spaces

The roof is made up of the flexor tendons and lumbricals of the medial three digits. The floor consists of the dense fascia covering the medial two and a half metacarpal bones and their corresponding interosseus

The Deep Volar Arch and the Ulnar Nerve Two arteries take part in the formation of the *deep volar arch*, the radial and the deep branch of the ulnar (Fig. 580). The radial plays the chief part in




FIG. 595. The retroflexor space of Parona

muscles. The lateral wall is made up of the fibrous septum described above and separates it from the thenar space. The medial wall is made up of the hypothenar muscles which are separated from the midpalmar space by the attachment of the palmar aponeurosis, which passes to the fifth metacarpal bone. Distally the space extends almost to the level of the distal palmar crease; proximally, it reaches the level of the distal margin of the transverse carpal ligament (Fig. 610). The midpalmar space is connected potentially with the so-called Parona's retroflexor space (Figs. 590 and 595). It has been referred to as the forearm space and has the following boundaries: anteriorly the flexor digitorum profundus (ulnar bursa) and the flexor pollicis longus in its synovial sheath (radial bursa), posteriorly the pronator quadratus and the interosseous membrane; proximally, it is continuous with the intermuscular spaces of the forearm; distally, it reaches the level of the wrist, and laterally, the space extends to the outer and the inner borders of the forearm. It is along these lateral borders that the space is drained by incisions

its formation. On leaving the forearm, the radial artery winds around the radial side of the wrist and crosses the dorsal surface of the navicular and the trapezium (greater multangular). It then passes through the anatomic snuff box (abductor pollicis longus, extensor pollicis brevis and extensor pollicis longus) to gain entrance to the proximal end of the first interosseous space. It continues medially and, in the palm, appears between the oblique and the transverse heads of the adductor pollicis. It turns medially and joins the deep branch of the ulnar artery at the base of the fifth metacarpal bone. The arch thus formed passes across the metacarpal bones immediately distal to their bases. The deep arch is about a fingerbreadth nearer the wrist than is the superficial; its convexity is directed toward the fingers. The deep branch of the ulnar nerve lies in its concavity. This arch lies deep to the flexor tendons and upon the volar interosseous muscles. Three arteries usually arise from the radial: the superficial palmar, which supplies the thenar eminence, the princeps pollicis to the thumb, and the radial in

and the interosseus muscles dorsally (Fig 594 A) Localization of pus in this space and the spread of dyes when injected under pressure indicates that it is divided into two compartments The work of Kanavel

a distal diverticulum of the space (Fig 609)

The midpalmar space lies in the inner half of the hollow of the hand it has a roof a floor and lateral and medial walls




FIG 593 The fascia of the lumbrical muscles The fascia of the second lumbrical forms the fibrous septum which separates the thenar from the midpalmar space

and Spaulding has shown that the lumbrical fascia of the second lumbrical passes to the lateral side of the muscle thereby producing one complete anteroposterior septum which passes from the palmar aponeurosis to the third metacarpal bone (Fig 593) This septum divides the deep palmar space into two a thenar space laterally and a midpalmar space medially

The thenar space lies under the outer half of the hollow of the palm it has a roof, a floor and lateral and medial walls The roof is made up of the flexor tendons the lumbricals of the second digit and the thenar muscles The floor is formed by the two heads of the adductor pollicis particularly its transverse head (Fig 594 B) The medial wall is made up of the fibrous septum (fascia of the second lumbrical muscle), and the lateral wall is formed by the flexor pollicis longus tendon and its synovial sheath This space may be mapped out on the hand proximally from the distal border of the anterior annular ligament to the transverse palmar crease distally The first lumbrical sheath extends as




FIG 594 The two palmar spaces (A) The thenar space is laterally placed, and the midpalmar space is medial (B) The posterior boundaries of the two spaces




FIG. 597 The interossei (A) the three palmar interossei (B) the four dorsal interossei

and so it is that these give rise to the single heads of the three palmar interossei. The interossei insert into the bases of the proximal phalangeal and the extensor expansions. Since their tendons pass backward and across the metacarpal joints to reach their insertions they aid in flexing these joints. They are inserted by means of the extensor expansions into the bases of the terminal phalanges and aid in extending the interphalangeal joints. Their main action however is abduction and adduction. The dorsal interossei are abductors, and the palmar interossei are adductors. An injury to their nerve supply the deep branch of the ulnar nerve, produces a characteristic deformity of the hand. When the interossei are paralyzed they no longer can act as flexors of the metacarpophalangeal joints. The extensors then are unopposed and bend the fingers backward at these joints; neither can the interossei act as extensors of the interphalangeal joints. The flexors therefore bend the fingers forward at these interphalangeal joints. The result is a typical *main en griffe* or 'claw hand'. The interossei pass dorsal to the deep transverse metacarpal ligament, this ligament separates them from the lumbricals. The dorsal metacarpal ligament joins

the heads of the metacarpal bones of the fingers together posteriorly. With the deep transverse ligament it forms three osseofibrous tunnels between the four fingers in which the palmar and the dorsal interosseus muscles lie.

The Metacarpal Bones The five metacarpal bones form the skeleton of the palm, articulate with the distal row of the carpus and diverge slightly as they extend distally to articulate with the phalanges; each has a base, a shaft and a head. The proximal ends (*bases*) are somewhat expanded and present articular surfaces, proximally, these articulate with the carpal bone and at the sides there are one or more articular surfaces for articulation with each other (Fig. 598). There are distinguishing features on the bases: the second is notched for the trapezoid, the medial margin of the notch articulates with the capitate, and the lateral boundary articulates with the trapezium. The base of the third metacarpal articulates with the capitate, it has a short styloid process extending upward from its dorsolateral part. The fourth base is cuboidal and articulates with the hamate and slightly with the capitate bones. The fifth has a tubercle on its medial side and a metacarpal facet on its lateral side. The

dicis, which passes along the lateral aspect of the index finger. The deep arch usually supplies the three palmar metacarpal arteries which pass between the fingers and unite with the digital branches of the superficial arch.

it has been called the "musician's nerve."

The Adductor Pollicis and the Interosseus Muscles The triangular *adductor pollicis* muscle lies in the depth of the palm and arises from the palmar border of the third metacarpal and its corresponding car




FIG 596 The adductor pollicis muscle. The radial artery divides its origin into two heads: a transverse and an oblique.

The *ulnar nerve* enters the palm between the volar carpal and the transverse carpal ligaments (Fig 586). It divides into superficial and deep branches in the region of the hamate bone. The superficial branch supplies sensory fibers to the little finger and the ulnar side of the ring finger. The deep branch is motor; it supplies all the muscles of the palm of the hand with the exception of the five supplied by the median nerve (p 764). The deep branch of the ulnar nerve, therefore, supplies the three hypothenar muscles, the seven interosseus muscles, the medial two lumbricals (three and four) and the adductor pollicis. This branch passes to the medial side of the hook of the hamate bone and dips into the palm through the cleft between the abductor and the flexor of the little finger. It runs transversely across the palm and is accompanied by the deep volar arch. As it crosses, it lies behind the flexor tendons and on the interossei and it terminates in the adductor pollicis. Since it supplies most of the muscles of the hand which are responsible for the fine movements of the hand,

pal bone, the capitate (Fig 596). The radial artery divides the origin of the muscle into two heads: a transverse (distal) and an oblique (proximal) head. It inserts into the base of the first phalanx of the thumb. Although the muscle lies deep in the palm, its distal edge is subcutaneous and can be exposed by removing the skin and the fascia of the first interdigital web. It forms the floor of the thenar space. Its contraction draws the thumb across the palm and thus keeps the thumb and the palm approximated to each other. This action should not be confused with the action of the opponens, which approximates the tip of the thumb to the tip of the fifth finger.

The *interossei* muscles are seven in number: four dorsal and three palmar. They are supplied by the deep branch of the ulnar nerve (Fig 597). The four *dorsal* interossei arise by double heads from the adjacent sides of the five metacarpals. On the palmar surface, the adductor pollicis arises from the third metacarpal and inserts into the thumb. This leaves only the second, the fourth and the fifth metacarpals free




FIG 599 The three thenar (thumb) muscles. These are the abductor pollicis brevis, the flexor pollicis brevis, and the opponens pollicis. The last lies in a deeper plane than the other two. The recurrent branch of the median nerve supplies this entire group.

shafts of the bones are three sided each presenting a flat surface toward the dorsum and a smooth ridge toward the palm of the hand. Each shaft is curved longitudinally with a palmar concavity and is prismatic on transverse section revealing dorsal lateral and medial surfaces. The anterior border of the third metacarpal body is almost monopolized by the transverse head of the adductor pollicis. The second, the fourth, and the fifth bodies present the attachments of the three palmar interossei. The anteromedial and the anterolateral surfaces of the five digits give origin to the two heads of the four dorsal interossei. The *heads* of the medial four metacarpal bones are convex and smooth distally and they articulate with the phalanges and the palmar ligaments which are attached to the shafts immediately above the heads. At these metacarpophalangeal joints the prominences of the knuckles are formed by the distal aspects of the heads of the metacarpal bones.




FIG 600 The three hypothenar muscles. These are the abductor, the flexor, and the opponens digiti quinti. They are supplied by the deep branch of the ulnar nerves.

The *first metacarpal bone (thumb)* is usually discussed alone because it is the shortest and most movable of all. Its dorsal surface is the same breadth throughout and shows no sign of the flattened triangular areas which differentiate the dorsal aspect of the shaft of the other metacarpal bones. The base of this bone is saddle shaped and articulates with the trapezium.

The *Thenar* and the *Hypothenar Eminences*. The *three thenar (thumb) muscles* are the abductor pollicis brevis and the flexor pollicis brevis, which are superficial, and the opponens pollicis, which lies deeper. They all are supplied by the recurrent





FIG 598 The metacarpal bones The origins of the muscles are shown in red, the insertions, in blue

nence correspond to those of the thenar group and are the abductor digiti quinti, the flexor digiti quinti and the opponens digiti quinti (Fig. 600). They are supplied by the deep branch of the ulnar nerve. These three muscles originate from the transverse carpal ligament and from the medial two carpal bones (pisiform and lunate). The *abductor digiti quinti* muscle inserts into the medial side of the base of the proximal phalanx of the little finger. By its action it abducts the little finger from the axial line of the middle finger. The *flexor digiti quinti* muscle is inserted with the abductor. It is partly fused with the abductor and sometimes it is partly incorporated in the opponens. By its action it flexes the metacarpophalangeal joint of the little finger. The *opponens digiti quinti*




FIG. 602 The dorsal subcutaneous and the subaponeurotic spaces

muscle lies on a deeper plane and is inserted into the whole length of the medial part of the front of the fifth metacarpal bone. The deep branch of the ulnar nerve enters from the lateral side of the hypothenar eminence, hence, incisions into this




FIG. 603 The tendons of the dorsum of the wrist and the hand

branch of the median nerve (Fig 599) These muscles lie to the radial side of the flexor pollicis longus tendon and make up the thenar eminence They are supplied by the recurrent branch of the median

the other two have been divided Its fibers spread out and insert into the lateral half of the palmar surface of the first metacarpal bone At times it is separable into superficial and deep laminae Its action




FIG 601 The cutaneous nerve supply of the dorsum of the hand

nerve which turns back after appearing from under the distal margin of the transverse carpal ligament Since the deep fascia is very thin over this area this important nerve is almost subcutaneous and is unprotected A guide to it is the superficial palmar branch of the radial artery, which lies medial to it The three thumb muscles arise together from the transverse carpal ligament and the lateral carpal bones (navicular and greater multangular) The *abductor pollicis brevis* muscle forms the upper or lateral part of the ball of the thumb It is inserted into the lateral side of the base of the proximal phalanx of the thumb Its action pulls the thumb directly forward so that it comes to lie at right angles to the plane of the palm The *flexor pollicis brevis* muscle is medial to the abductor and inserts with it Its action produces flexion at the metacarpophalangeal joint of the thumb The *opponens pollicis* muscle is visible only after

brings the metacarpal bone of the thumb across the palm of the hand and also rotates it medially so that the pad of the tip of the thumb faces and comes into contact with the pads of the tips of the other fingers This action should not be confused with adduction (p 770) The nerve to these muscles is seen after the superficial muscles are reflected It is a short branch which having given off superficial twigs to the flexor brevis and the abductor, passes between these two to enter the opponens The three muscles are segregated from the central space of the palm by a fascial sheet which passes dorsally (under the muscles) from the radial edge of the palmar aponeurosis and attaches to the first metacarpal bone Therefore, pus formed among these muscles shows no tendency to spread to the palm Incisions into this space should be placed laterally to avoid the median nerve

The three muscles of the hypothenar emi-

nerve correspond to those of the thenar group and are the abductor digiti quinti, the flexor digiti quinti and the opponens digiti quinti (Fig. 600). They are supplied by the deep branch of the ulnar nerve. The three muscles originate from the transverse carpal ligament and from the medial two carpal bones (pisiform and lunate). The *abductor digiti quinti* muscle inserts into the medial side of the base of the proximal phalanx of the little finger. By its action it abducts the little finger from the axial line of the middle finger. The *flexor digiti quinti* muscle is inserted with the abductor. It is partly fused with the abductor and sometimes it is partly incorporated in the opponens. By its action it flexes the metacarpophalangeal joint of the little finger. The *opponens digiti quinti*




FIG. 602 The dorsal subcutaneous and the subaponeurotic spaces

muscle lies on a deeper plane and is inserted into the whole length of the medial part of the front of the fifth metacarpal bone. The deep branch of the ulnar nerve enters from the lateral side of the hypothenar eminence, hence incisions into this




FIG. 603 The tendons of the dorsum of the wrist and the hand




FIG 604 Diagrammatic presentation of the anatomy of a finger (A) cross sectional study (B) the superficial and the deep flexor tendons

space are made along the medial side. The space is separated from the central space of the palm by a septum similar to that described under the thenar eminence. This septum attaches to the fifth metacarpal bone.

THE DORSAL REGION OF THE HAND

The surface anatomy of this region reveals the extensor tendons as being both visible and palpable over the dorsum of the hand. The metacarpal bones can be felt easily. In contrast with the palmar surface of the hand, the dorsal surface is covered with skin of finer texture which has numerous sebaceous glands and short hairs. The cutaneous nerve supply is derived from the dorsal rami of the ulnar, the radial and the dorsal antibrachial cutaneous nerves (Fig 601).

The *dorsal subcutaneous space* is a rather extensive area of loose areolar tissue within definite boundaries (Fig 602). If infected pus can spread quite readily over the entire dorsum of the hand.

The *dorsal subaponeurotic space* (Fig

602) should not be confused with the dorsal subcutaneous space. Over the dorsum of the hand the extensor tendons are united by oblique bands, thus forming an *aponeurotic sheet*, this is attached on each side to the second and the fifth metacarpal bones. The dorsal subaponeurotic space lies between this sheet and the interosseous muscles. It is filled with loose connective tissue. Pus in this space is limited distally at the metacarpophalangeal joints and proximally at the bases of the metacarpal bones.

The *extensor digitorum communis* is enclosed with the extensor indicis in a synovial sheath which is in a compartment of the extensor retinaculum. It divides into tendons which diverge to the fingers (Fig 603). On the dorsal surface of the proximal phalanx each tendon expands to form the dorsal extensor expansion, which is inserted into the bases of the middle and the distal phalanges (Fig 604). It is supplied by the posterior interosseous nerve and as its name suggests it extends the phalanges and the hand.

The *extensor carpi radialis longus* tendon is crossed by the extensors of the thumb, it is enclosed in a synovial sheath, with the *extensor carpi radialis brevis*, under the extensor retinaculum.

The *extensor digiti minimi* tendon is ensheathed in the compartment of the extensor retinaculum that lies between the radius and the ulna. It is inserted with the tendon from the extensor digitorum to the little finger. The *extensor carpi ulnaris* tendon also is enclosed in a synovial sheath and is inserted into the base of the fifth metacarpal bone.

PHALANGES (FINGERS)

The hand has a thumb and four fingers. Some authorities prefer to refer to the thumb as the first of five digits but this is a matter of convenience rather than one of argument. The construction of all five fingers is essentially the same, except that the thumb has two phalanges and the




FIG. 605 The terminal phalanx and the distal closed space (A) cross section (B) longitudinal section

other fingers have three. The thumb also has a short thick metacarpal associated with it which adds to its strength and mobility.

The skin of the flexor surface of the digits is thick, contains some subcutaneous fat, is only slightly mobile, and is devoid of hair follicles. That over the dorsum is thinner, more mobile, and has very little subcutaneous fat. The transverse flexor creases do not indicate the exact positions of the underlying joints. The proximal digital crease is distal to the metacarpophalangeal joint. The middle crease is a good guide to the joint, since it lies directly opposite it. The distal crease is somewhat proximal to the distal interphalangeal joint. Therefore the only digital transverse crease that can be used as an exact landmark of the joint is the middle one. These creases are bound closely to the underlying flexor

tendon sheaths by fibrous tissue strands. The amount of fat is minimal or even entirely absent beneath them; hence a penetrating wound at the crease is likely to penetrate the underlying synovial sheath.

The subcutaneous tissue over the flexor surface is made up of fibrous tissue enclosing small amounts of fat. These septa connect the skin to the fibrous layers of the tendon sheath below and to the periosteum in the terminal phalanges. The last named relationship is important in the treatment of a felon (p. 784). The digital vessels and nerves run in this subcutaneous tissue layer.

The important distal closed space can be understood if the arrangement of the subcutaneous tissue is visualized properly (Fig. 605). In the distal phalanx the subcutaneous tissue is arranged in such a way that it consists of a number of strong

fibrous septa which radiate from the periosteum to the skin. In the compartments thus formed between these septa, fatty tissue is found. The distal four fifths of the phalanx is converted therefore, into a

and the diaphysis, necrosis usually is limited to the diaphyseal region alone and new bone may grow from the epiphyseal end.

The phalanges are the bones of the




FIG 606 Suppurating callosity and web space infections (A) path of extension of a suppurating callosity to a web (lumbrical) space, (B) incision into the abscess

closed space and together with the diaphysis receives its blood supply from the two palmar digital arteries which are found anterolateral to the bone. If a transverse section of the distal closed space is studied, it will be seen that dense connective tissue separates the subungual space or nail bed from the anterior closed space. The epiphysis receives its blood supply from the digital arteries before those vessels enter the closed space (Fig 605B). If inflammatory exudates and edema occur within this space the tension rises, shuts off the blood supply and a necrosis of the diaphysis occurs. Even after the age of twenty and after union of the epiphysis

fingers. There are 14 in all, three (proximal, middle and distal) for each finger and two for the thumb. They are built upon the same general plan as the metacarpals but are shorter, the distal phalanx being the shortest of all and having a rough distal end which underlies the tips of the fingers. The distal ends of the terminal phalanges are neither weight bearing nor force transmitting. The surface under the fingernail is smooth; the surface under the finger pad is rough owing to the attachment of the fibrous bands which bind the skin to it. The dorsal aspect of the proximal and the middle phalanges is smooth, rounded and covered by the extensor expansions. The

palmar surfaces take part in the floor of the osseous tunnel in which the flexor tendons run. The borders of the middle phalanx are more prominent because they receive the attachment of the slips for the

their dorsal surfaces (Fig. 556). The proximal part of the dorsum of the fingers receives its arterial supply via the *dorsal digital arteries*, which arise from the dorsal metacarpal arteries from the dorsal carpal




FIG. 607 Infection of the ulnar bursa. (A) This bursa is usually infected as a result of extension from an infected tendon sheath of the fifth finger. The arrows indicate the possible paths of extension from the infected ulnar bursa to surrounding structures. (B) Combined digital and palmar incision. Accessory incisions are shown to drain Parona's retroflexor space.

insertion of the flexor digitorum sublimis tendon. The bases of the proximal phalanges articulate with the rounded knuckles and therefore are concave.

The common *olar digital arteries* arise from the convexity of the superficial volar arch and give off digital branches which supply contiguous sides of the thumb and the fingers as well as the distal part of

arch. On the fingers, the digital arteries and nerves run side by side in contact with the fibrous flexor sheath not with the phalanges. Each of these vessels gives off a branch to the epiphysis of the terminal phalanx before entering the anterior clove space. The branches ramify across the anterior aspect of the phalanx sending nutrient vessels to the bone. The *digital*

nerve lies anterior or anteromedial to its fellow artery. The distribution of these nerves has been discussed elsewhere.

SURGICAL CONSIDERATIONS

WEB SPACE INFECTIONS AND SUPPURATING CALLOSITY

Web space infections may start as a suppurating callosity which spreads down toward the commissural or web space (Fig 606). The pus tends to spread backward or laterally. It can spread from one web to another and thus may involve three web

spaces without going deeply. Since there are deficiencies in the palmar aponeurosis between its digital prolongations, the infection can burrow backward so that a "collar button" abscess is formed. Adequate drainage can be instituted by making an incision through the web between the fingers and continuing into the palmar aspect of the hand.

TENOSYNOVITIS

Tenosynovitis, or infection in the tendon sheath of the little finger and the thumb is discussed under ulnar and radial bursae infections. Tenosynovitis of the middle, the




FIG 608 Infection of the radial bursa. (A) This bursa is usually infected as a result of extension from an infected tendon sheath of the thumb. The arrows indicate the possible paths of spread from the infected radial bursa to surrounding structures. (B) The incisions used in the treatment of an infected radial bursa and flexor pollicis longus tendon.

ring and the index fingers has a tendency to remain localized since the sheath ends in the region of the heads of the metacarpal bones. The incision which drains a digital tenosynovitis should be made at the side of the sheath and at the site of the known infection. The incision is carried along the shaft of the proximal and the middle phalanx but usually leaves that part which is over the joint untouched to prevent herniation of the tendon.

✓ INFECTION OF THE ULNAR BURSA

Infection of the ulnar bursa usually results from an extension of an infection in the flexor tendon sheath of the little finger (Fig. 607). Perforating wounds in infected midpalmar space and infections of the tendon sheath of the middle or the ring fingers may also spread to this bursa. In the latter case the pus breaks through the proximal end of the synovial sheath passes along the lumbrical muscle into the midpalmar space and from there secondarily involves the ulnar bursa. An infection of the ulnar bursa may spread to the underlying bone or joint to the lumbrical canal to the middle palmar space to the radial bursa or into the wrist.

Since this condition usually results from extension of a tenosynovitis of the little finger the treatment of the latter should be carried out first as described on p. 780. The incision is placed either on the lateral or the medial side of the finger and is carried down into the palm and into the hypothenar eminence (Fig. 607 B). The tendon sheath may be absent between the little finger tendon sheath and the ulnar bursa. This should be kept in mind in order to avoid contaminating a healthy bursa. The combined palmar and digital incision makes it possible to drain both the tendon sheath of the fifth finger and the ulnar bursa at the same time. It extends to the flexor retinaculum. If the infection has extended into the forearm an incision is placed along the ulna. Accessory incisions on the radial side may be necessary

sometimes for through and through drainage of Pirois's retroflexor space.

✓ INFECTIONS OF THE RADIAL BURSA

Infections of the radial bursa usually arise from an infected tendon sheath of the flexor pollicis longus, an infected ulnar bursa or an infected thenar space (Fig. 608). The infection may spread from the flexor pollicis longus to the interphalangeal joint, the bone, the ulnar bursa, the thenar space or under the anterior annular ligament and into the wrist. The incision for an infected radial bursa and flexor pollicis longus tendon starts as an anteromedial incision at the distal volar skin crease and extends through the thenar eminence down to within an inch and a half of the anterior annular ligament, but no farther (Fig. 608 B). This precaution is taken because the motor branch of the median nerve to the thenar muscles is in this region (the danger area) (p. 773). The bursa itself should be drained in the forearm via the approach described under ulnar bursitis; this permits drainage of both bursae and unlike the approach from the radial side, involves no risk to the radial artery.

✓ INFECTIONS OF THE THENAR SPACE

Infections of the thenar space occur as a result of a perforating wound directly into the space or following a tenosynovitis of the index or the middle finger. Abrasions of the thumb, radial bursitis and midpalmar space abscesses (Fig. 609). Abscesses of this space occasionally have been reported following osteomyelitis of the first, the second or even the third metacarpal bones. When it follows a tenosynovitis of the index finger, as it usually does, the cellulitis of the tendon sheath extends downward and bursts through the proximal end of the sheath; it then comes to lie in the loose areolar tissue around the lumbrical muscle which guides it into the thenar space. The pus lies anterior to the adductor muscle of the thumb and ballooning of the web between the thumb and the index finger becomes visible. The treatment is imme-




FIG 609 The infected thenar space (A) The arrows indicate the possible paths of extension into the thenar space (B) Drainage of the infected thenar space

diate incision and drainage the incision being placed along the anterior border of the lateral side of the second metacarpal bone or along the web between the thumb and the index finger (Fig 609 B). A hemostat is placed into the space between the flexor tendons and the adductor pollicis. Pus may accumulate behind the adductor

muscle, and an incision placed as described above can drain both anterior and posterior adductor partitions of the thenar space. The hemostat which is placed into the thenar space should not be thrust past the middle metacarpal bone because the fascial septum may be perforated and the midpalmar space contaminated.




FIG 610 The infected midpalmar space (A) The arrows indicate the possible paths of extension into the midpalmar space (B) Drainage of the infected midpalmar space

INFECTIONS IN THE MIDPALMAR SPACE

Infections in the midpalmar space occur from a tenosynovitis involving one or any of the three medial digits from an infected ulnar bursa or from osteomyelitis of the underlying metacarpals. The condition also may be caused by extension from an in-

fect ed thenar space direct penetrating wounds or from infections of one of the medial three web spaces traveling along a lumbrical muscle (Fig 610). When the midpalmar space is involved, the concavity of the palm is lost. Since direct attack upon the space would endanger too many struc-




FIG 611 Felon (A) and (B) "Fish mouth" type of incision (C) Closed space arrangement of the distal phalanx (D) and (E) "Hockey stick" type of incision

tures, effective drainage can be obtained via a lumbrical space by opening a web between the ring and the middle finger or the ring and the little finger (Fig. 610 B). In this way a hemostat can be placed beneath the flexor tendons and into the midpalmar space. It should not be thrust past the middle metacarpal bone since this in turn may involve the thenar space.

~ FELON (WHITLOW)

Felon whitlow is an infection of the anterior closed space of the finger. It is extremely painful, common and dangerous. The connective tissue arrangement (Fig. 611 C) accounts for the fact that if pus develops here, it has no means of escape and produces marked pressure. This shuts off the blood supply and causes early

necrosis. Since the epiphysis (base of the bone) receives its blood supply from vessels which do not pass through this space, it does not become necrotic, as does the rest of the bone, and new bone can grow from it, especially in the young. A "hockey stick" incision or "fish mouth" type of incision may be used to establish adequate drainage and open these spaces (Fig. 611). Incisions of this type place the scar away from the very sensitive tactile surface of the finger. A midline incision is an error, since the drainage produced would be inadequate, the tactile sense interfered with and the flexor tendon sheath possibly could be involved.

PARONYCHIA

Paronychia is an acute infection involving the subepithelial tissue at the side of the nail. If incised and drained early, no ill effects result but if neglected, the infection may spread along the side and the base of the nail forming a so called "run around." The pus may lodge beneath the overlying epithelium (eponychium) and then travel under the nail itself, forming a subungual abscess. In the treatment of paronychia, a lateral incision should be made over the point of maximum tenderness. *bilateral incisions should be used if the infection has run around the nail* (Fig. 612). If a subungual abscess results, an eponychial flap is raised and the nail bed is removed, for the nail acts as a foreign body in the subungual abscess cavity. The distal portion of the nail is not removed, as it protects the underlying sensitive tissue.

FRACTURES OF THE METACARPAL BONES

The metacarpal bones frequently are fractured when the fist is clenched and a blow is struck. McNealy and Lichtenstein have emphasized the important points regarding the mechanism and the treatment of hand fractures.

In *metacarpal bone fractures exclusive of the thumb* a typical deformity results,

which is characterized by shortening of the bone due to bowing of the fragments. This results in a dorsal projection at the fracture site and volar displacement of the metacarpal head because of the action of the interosseus muscle which flexes the proximal phalanx. The distal fragment of the metacarpal bone is attached to the proximal phalanx through the metacarpophalangeal joint and is drawn into a flexed position. An inverted V deformity is typical for fractures of the metacarpal bones and requires immobilization on a straight dorsal splint. This removes the deformity and restores the normal horizontal contour to the dorsum of the hand. The third and the fourth metacarpal bones are splinted laterally by their adjacent metacarpals but the second and the fifth lacking such support require lateral splinting in addition to the dorsal.

The usual deformity in fractures of the first metacarpal (thumb) is adduction of the distal fragment and abduction of the proximal. The treatment for such fractures is abduction which overcomes the contraction of the adductor muscles and maintains the web of the thumb. In a *Bennett's fracture* (fracture of the base of the first metacarpal) abduction may fail to restore the alignment of the bones and in addition to abduction traction may be necessary.

DISLOCATION OF THE METACARPOPHALANGEAL JOINTS

Dislocation of the metacarpophalangeal joints occurs frequently because of their ball and socket arrangement. *Dislocation of the thumb* occurs usually after a fall which produces forceful dorsiflexion upon the hyperextended hand. This results in a tear in the glenoid (volar accessory) ligament and permits the phalanx to pass backward. The resultant deformity is typical as the proximal phalanx comes to rest upon the dorsal aspect of the thumb metacarpal. The head of the metacarpal is caught between the tendons of the flexor




FIG. 612 The treatment of uncomplicated and complicated paronychia

pollicis brevis and the flexor pollicis longus. Because of this reduction cannot be accomplished with traction alone but the joint must be hyperextended almost to a right angle followed by pressure at the proximal end of the phalanx to force it over the head of the metacarpal. Should this fail it becomes necessary to make an incision and enlarge the opening in the capsule so that reduction may be accomplished. *Dislocations of the middle and the distal phalanges* occur quite frequently and usually are produced by a blow struck at the tip of the finger. They may be accompanied by a fracture and since the extensor tendon usually is ruptured at its insertion into the base of the terminal phalanx a *dropped finger* or *“loose ball finger”* results. The extensor tendon does not retract because of its attachment along its lateral expansion.

FRACTURES OF THE PHALANXES

In fractures of the distal phalanx the distal part of the bone is not subject to pull of either intrinsic or extrinsic muscles therefore, displacement is minimal, even




FIG 611 Felon (A) and (B) 'Fish mouth' type of incision (C) Closed space arrangement of the distal phalanx (D) and (E) "Hockey stick" type of incision

tures, effective drainage can be obtained via a lumbrical space by opening a web between the ring and the middle finger or the ring and the little finger (Fig 610 B). In this way a hemostat can be placed beneath the flexor tendons and into the midpalmar space. It should not be thrust past the middle metacarpal bone since this in turn may involve the thenar space.

FELON (WHITLOW)

Felon, whitlow is an infection of the anterior closed space of the finger. It is extremely painful, common and dangerous. The connective tissue arrangement (Fig 611 C) accounts for the fact that if pus develops here, it has no means of escape and produces marked pressure. This shuts off the blood supply and causes early

necrosis. Since the epiphysis (base of the bone) receives its blood supply from vessels which do not pass through this space, it does not become necrotic, as does the rest of the bone, and new bone can grow from it, especially in the young. A "hockey stick" incision or "fish mouth" type of incision may be used to establish adequate drainage and open these spaces (Fig 611). Incisions of this type place the scar away from the very sensitive tactile surface of the finger. A midline incision is an error, since the drainage produced would be inadequate, the tactile sense interfered with and the flexor tendon sheath possibly could be involved.

PARONYCHIA

Paronychia is an acute infection involving the subepithelial tissue at the side of the nail. If incised and drained early, no ill effects result, but, if neglected, the infection may spread along the side and the base of the nail, forming a so-called "run around." The pus may lodge beneath the overlying epithelium (eponychium) and then travel under the nail itself, forming a subungual abscess. In the treatment of paronychia, a lateral incision should be made over the point of maximum tenderness. Bilateral incisions should be used if the infection has run around the nail (Fig 612). If a subungual abscess results, an eponychial flap is raised and the nail bed is removed, for the nail acts as a foreign body in the subungual abscess cavity. The distal portion of the nail is not removed, as it protects the underlying sensitive tissue.

FRACTURES OF THE METACARPAL BONES

The metacarpal bones frequently are fractured when the fist is clenched and a blow is struck. McNealy and Lichtenstein have emphasized the important points regarding the mechanism and the treatment of hand fractures.

In *metacarpal bone fractures exclusive of the thumb*, a typical deformity results,

SECTION NINE

THE INFERIOR EXTREMITY

if crushing is marked. The fingernail may be used as a suitable splint, and the fragments can be molded into place. Fractures involving the *proximal* portion of the terminal phalanx are affected by the pull of

fragment, with the proximal fragment in an extended position, results (Fig 613 B). Therefore a fracture distal to the tendon insertion produces a V shaped deformity, but a fracture proximal to the tendon in




FIG 613 Fractures of the proximal and the middle phalanges

the flexor digitorum profundus and the extensor digitorum communis. This is the same injury described under 'dropped finger'. Hyperextension usually aligns the fragments and can be maintained by some such splint as described by Lewin.

The deformity and the treatment of fractures of the middle phalanx depend upon whether the fracture is proximal or distal to the insertion of the flexor digitorum sublimis. If it is distal then flexion of the proximal fragment and dorsal displacement of the distal fragment result (Fig 613 C). When the fracture is proximal to the tendon insertion flexion of the distal

section produces an inverted V shaped deformity. A straight splint will correct the deformity in a fracture proximal to the tendon insertion and a curved volar splint will correct the deformity found in a fracture distal to the tendon insertion.

In fractures of the proximal phalanx, flexion of the proximal fragment is produced by the pull of the interosseus and the lumbrical muscles, and dorsal displacement is brought about by the action of the lumbrical muscles (Fig 613 A). This results in a V shaped deformity which can be corrected by a curved splint which approximates the broken ends of the bone.

The Hip

The pelvis femoral region is that area in which the lower extremity is firmly bound to the pelvis by powerful muscles and ligaments. For study it can be divided conveniently in the gluteal (hip) region and the hip joint.

GLUTEAL REGION

BOUNDARIES AND SUPERFICIAL STRUCTURES

The gluteal region is roughly quadrilateral in shape and is bounded above by the iliac crest below by the gluteus maximus medially by the lateral margin of the sacrum and the coccyx and laterally by the tensor fasciae latae muscle (Fig. 614). The *iliac crest* is palpable because of its subcutaneous position. If the anterosuperior iliac spine is located and the fingers then run backward over the iliac crest they reach a definitely palpable *posterosuperior iliac spine* at which point the iliac crest ends. Below this the posterior border of the innominate bone is continued vertically for about one inch to the postero-inferior iliac spine at which point it turns abruptly forward to form the great sciatic notch (Fig. 395). This notch continues to the ischial spine where a shallow indentation is formed known as the small (lesser) sciatic notch. Therefore the ischial spine separates the greater and the lesser sciatic notches. Below the latter the bone ends in a stout projection known as the ischial tuberosity. The sacrospinous and the sacrotuberous ligaments convert the greater and the lesser sciatic notches into foramina.

The *buttock* (natis) forms a smooth rounded elevation which is separated from its fellow by a deep fissure called the natal

clift. It is limited inferiorly by another groove called the fold of the buttock. The bulging of the buttock is caused by a thick layer of fat and the lower part of the large gluteus maximus muscle.

The *superficial fascia* has the same general characters as it has in other parts of the body but is peculiar in this region in that it is loaded with fat, and the numerous small cutaneous nerves may be difficult to locate. This fat is particularly present in the female. The fascia thickens over the upper and the lower margins of the gluteus maximus and is tough and stringy over the ischial tuberosity where it forms a most efficient cushion upon which the body weight presses while in a sitting posture.

The *cutaneous nerves* are numerous and difficult to find but the small arteries which accompany them may act as guides (Fig. 614). These nerves are derived partly from the posterior primary rami and partly from the anterior primary rami of the spinal nerves. Three twigs arise from the first three lumbar nerves and three from the first three sacral nerves. From the anterior primary rami of the spinal nerves are derived the lateral cutaneous branch of the iliohypogastric the lateral cutaneous branch of the last thoracic twigs from the posterior branch of the lateral cutaneous nerve of the thigh which terminates over the greater trochanter, branches from the posterior cutaneous nerve of the thigh and finally twigs from the perforating cutaneous branch of the fourth sacral.

The *superficial lymph vessels* of the gluteal region join the lateral lymph glands of the superficial inguinal group.

tuberosity and the skin when one is sitting. The upper border of the muscle may be indicated by a line which runs parallel with the lower border and extends outward from the posterosuperior iliac spine to a point two inches above the greater trochanter. This muscle is the great extensor of the thigh bringing the bent thigh into line with the body. Therefore it is important in walking, going up an incline or rising from the sitting posture which it does by pulling the pelvis backward. The blood supply is derived from the inferior gluteal artery. Many important structures lie beneath the deep surface of the gluteus maximus muscle and to understand them the piriformis muscle may be used as a guide (Fig. 616). The lower border of this muscle can be indicated on the skin by a line joining the midpoint between the posterosuperior iliac spine and the tip of the coccyx to the top of the greater trochanter. If an incision is made through the gluteus maximus along this piriformis line and if the incision is carried to the greater trochanter until its bony resistance is felt, the proper cleavage plane will be found. It is wise to relax the gluteus by extending and rotating the thigh laterally, so that a finger may be inserted through the incision and moved about.

Three subgluteal synovial bursae are usually found beneath the muscle in the following locations: (1) between the muscle and the ischial tuberosity (2) between the muscle and the greater trochanter and (3) between the gluteus and the upper part of the vastus lateralis. The bursa between the maximus and the ischial tuberosity may enlarge in those who follow sedentary occupations such a bursa has been referred to as "weaver's bottom." This bursa is usually small and may be absent. However, the bursa which exists between the muscle and the greater trochanter is normally quite large.

For orientation in the region which lies subgluteally (gluteus maximus) it is important to utilize two units as key struc-




FIG. 615 The gluteus maximus muscle (A) the origin and the insertion of the muscle, (B) the muscle outlined on the pelvis-femoral bony framework.

tures, namely the piriformis muscle and the greater sciatic foramen, which has been called the door to the gluteal region. The piriformis muscle itself enters the region via this door; some vessels and nerves enter the region *above* the piriformis (suprapiriformic), while others pass *below* the muscle (infrapiriformic), but all enter through the greater sciatic foramen. Some structures which enter this great door may disappear at once through the lesser sciatic foramen. The obturator internus is the only structure which enters the gluteal region by way of the lesser sciatic foramen.

The piriformis muscle arises within the pelvis by three digitations from the anterior surface of the second, the third and the fourth segments of the sacrum; these fibers arising between the anterior sacral foramina. *Outside* of the pelvis this muscle arises from the upper part of the greater sciatic notch and from the sacrotuberous ligament. The fibers pass through the greater sciatic foramen, continue laterally forward and insert into the highest point of the greater trochanter. The muscle is chiefly an extensor and lateral rotator of the ischium. It receives its nerve supply from the sacral plexus (S 1).

DEEP FASCIA

The *deep fascia* is strongly attached to the iliac crest. Where it overlies the gluteus medius muscle it appears as a dense opaque pearly white sheet. When it reaches

dorsal aspect of the sacrum and the coccyx, and the posterior surface of the sacrotuberous ligament. From this extensive origin the bundles proceed obliquely downward and forward toward the upper




FIG 614 The gluteal region and its cutaneous nerve supply

the upper border of the gluteus maximus; however, it splits into two layers which enclose the muscle. Its appearance over the maximus is not thick and opaque, as over the medius, but in marked contrast appears thin and transparent. It sends septa into the muscle and thus divides it into coarse bundles.

MUSCLES

The Gluteus Maximus. This muscle is rhomboidal in shape and is the most massive in the body. It is also the coarsest, heaviest and strongest muscle (Fig 615). Being associated with the upright posture of the biped, it is especially well developed in man. It arises from the posterior part of the gluteal surface of the ilium, the

part of the shaft of the femur, but only a part of the muscle is inserted into the bone. Three quarters of it is inserted into the iliotibial tract; the lower deep fibers attach to the gluteal tuberosity. It should be noted that the lower border of the muscle does not run parallel with the fold of the buttock but crosses it obliquely, being above its medial part and below its lateral part. The lower border extends from the tip of the coccyx and across the ischial tuberosity to the shaft of the femur (Fig 615 B). The tuberosity is covered by the muscle when one stands erect but it is uncovered when one sits down. It was not the plan of the body to have fleshy muscle support weight; therefore there is a thick mass of stringy fibrous tissue between the

muscle. Arising from the sacral plexus, it enters the gluteal region through the lower part of the greater sciatic foramen and enters the deep surface of the muscle.

The *posterior cutaneous nerve* to the thigh (S 1, 2, 3) passes deep to the gluteus maximus and medial to the sciatic nerve (Fig. 616). It is purely sensory and has been referred to as the "small sciatic" nerve. Its gluteal branch turns around the lower border of the gluteus maximus and its perineal branch passes lateral to the ischial tuberosity to supply the scrotum or the labium majus. The main nerve continues downward to the middle of the thigh, subfascially, and ends on the calf.

The *inferior gluteal artery* divides into numerous terminal branches as soon as it appears beneath the lower border of the piriformis (Fig. 616). These branches are distributed to the neighboring musculature, and a small branch accompanies the sciatic nerve. It anastomoses with branches which join the trochanteric and the crucial anastomoses. The *crucial anastomosis* establishes a connection between the internal iliac and the femoral arteries. The cross is




FIG. 617 The piriformis muscle

formed by horizontal arms from the transverse branches of the circumflex femoral artery, the upper limb from the descending branches of the inferior gluteal artery, and the lower limb from the ascending branch of the first perforating artery.

The *nerve to the obturator internus*, the *internal pudendal artery*, and the *pudendal nerve* run only a small part of their course




FIG. 618 The hip joint seen in frontal section




FIG 616 The structures lying deep to the gluteus maximus muscle. The muscle has been severed and reflected medially to expose its deep surface. Its nerve and blood supplies are also shown. The structures associated with the supra and the infrapiriformic spaces are shown.

THE NERVES AND THE VESSELS OF THE INFRAPIRIFORMIC AND THE SUPRAPIRIFORMIC SPACE

Infrapiriformic Space The structures which enter at the lower border of the piriformis are from lateral to medial the sciatic nerve (which hides the nerve to the quadratus femoris), the nerve to the gluteus maximus (inferior gluteal nerve), the posterior cutaneous nerve of the thigh, the inferior gluteal artery, the nerve to the obturator internus, the internal pudendal vessels and the internal pudendal nerve (Fig 616).

The Sciatic Nerve The sciatic nerve (L 4, 5, S 1, 2, 3) is the largest nerve in the body. It is broad and flat (Fig 649). As it appears from under cover of the piriformis it runs downward to the thigh.

At first it lies on the ischium and then crosses successively the gemelli and the obturator internus, the quadratus femoris and the adductor magnus. The posterior cutaneous nerve of the thigh passes on the superficial aspect of the sciatic. The sciatic continues downward deep to the long head of the biceps. In its course it passes midway between the ischial tuberosity and the greater trochanter. It is the most lateral structure in the infrapiriformic region, having a 'side of danger' and a 'side of safety.' Its lateral side is the 'side of safety' along which dissection may take place without harm. Its medial side, however, is its 'side of danger' from which branches spring to the hamstring muscles.

The *inferior gluteal nerve* (L 5, S 1, 2) is the nerve supply to the gluteus maximus.




FIG 619 The hip joint Five different views showing the relations between the acetabulum the ligaments, the head of the femur and the synovial membranes

insertion with the adductor magnus. By some it is considered as an upper extension of this latter muscle, the division between the two not always being clearly evident. It arises from the lateral border of the ischial tuberosity, passes laterally and becomes inserted into a rounded prominence

on the trochanteric crest of the femur. Its upper border lies edge to edge with the inferior gemellus. The two gemelli, the obturator internus and the quadratus femoris, are closely related to the capsular ligament of the hip joint and act as lateral rotators of the thigh. When the thigh is

in the gluteal region the artery lies between the two nerves. They emerge from the pelvis through the greater sciatic foramen, cross the spine of the ischium and the sacrospinous ligament and enter the lesser sciatic foramen to disappear from view. The nerve to the obturator internus is placed most laterally and supplies a twig to the gemellus superior. The internal pudendal artery with a companion vein on each side crosses the tip of the spine.

Suprapiriformic Space The structures which enter along the upper border of the piriformis muscle are the superior gluteal vessels and the superior gluteal nerves (Fig. 616). The *superior gluteal nerve* (L 4, 5, S 1) passes in the interval between the gluteus medius and the minimus. It supplies both of these muscles and ends in the tensor fasciae latae. Therefore, it supplies the three abductors and the medial rotators of the hip joint, namely the gluteus medius, the gluteus minimus and the tensor fasciae latae. The *superior gluteal artery* is a branch of the posterior division of the internal iliac (hypogastric) artery. As soon as it passes above the upper border of the piriformis muscle it supplies a superficial branch which is distributed to the gluteus maximus. The remaining deep branch breaks up into upper and lower branches which follow the middle and the inferior gluteal lines in the interval between the gluteus medius and the minimus.

The Glutei Medius and Minimus Muscles These are really two parts of a single muscle since they are common in shape, direction of fiber action, nerve and blood supply (Fig. 616). Therefore, it is unusual to find a fascial plane between them although at times such an ill defined plane may be present. The *gluteus medius* arises from the area between the middle gluteal line and the iliac crest. Its fibers converge to form a flattened band, partly fleshy and partly tendinous, which inserts into the greater trochanter of the femur. A small bursa separates this tendon from the anterior part of the trochanter. The

gluteus minimus is covered by the preceding muscle. It arises from the gluteal surface of the ilium between the middle and the inferior gluteal lines, its fibers converge and become inserted into the anterior surface of the greater trochanter. It is intimately connected near its insertion with the capsule of the hip joint and is separated from the trochanter major by a small bursa. These muscles are supplied by the superior gluteal nerve and arteries.

The tensor fasciae latae muscle (N superior gluteal L 4, 5 S 1) arises from the forepart of the lateral lip of the iliac crest and the subjacent bony surface, and is invested by fascia lata. It lies over the anterior borders of the gluteus medius and minimus. Its fibers pass downward and backward to become inserted into the fascia lata a little below the greater trochanter. This part of the fascia lata is known as the iliotibial band (tract) (Fig. 664). It is an extensor of the knee acting through the iliotibial band and a medial rotator of the thigh.

The Two Gemelli and the Obturator Internus Muscles These muscles constitute a three headed muscle plate which occupies the interval between the quadratus femoris and the piriformis (Figs. 616 and 617). The obturator internus arises from almost the entire pelvic surface of the hip bone below the level of the obturator nerve (Fig. 622). It makes a right angle turn as it passes through the lesser sciatic foramen and is separated from the margin of the foramen by a bursa. Its tendon passes across the posterior surface of the ischium and the capsule of the hip joint to reach the anterior facet on the upper border of the greater trochanter. The superior gemellus arises from the ischial spine and the inferior gemellus from the ischial tuberosity. They are associated with the upper and the lower borders of the obturator internus tendon, and the three together have been referred to as the *tricipital tendon*.

The *quadratus femoris* is an oblong muscle which is continuous at its origin and

THE HIP JOINT

The hip joint is an excellent example of the ball and socket variety of joints (Figs 618 and 619). Although it does not allow as free a range of movement as that which takes place in the shoulder joint, the loss in this respect is counterbalanced by a gain in stability and strength. The head of the femur forms the ball, the acetabulum which is deepened by the transverse acetabular ligament and the acetabular labrum forms the socket.

THE ACETABULUM
AND HEAD OF THE FEMUR

The ball (femoral head) forms two-thirds of a sphere. However, this sphere is not perfect since it is flattened above where the acetabulum rests most heavily upon it. It is covered by cartilage over its globoid surface as far as its junction with the femoral neck. A small depression called the *fossa capitis* is located a little behind the summit of the head; it lodges the femoral attachments of the ligamentum




FIG. 622 Transverse section through the right hip joint




FIG 620 The synovial membrane and zona orbicularis of the hip joint seen from behind

flexed, however, the position of the greater trochanter is altered so that the piriformis and the obturator internus and the gemelli become abductors. The nerve supply of the obturator internus and the superior gemellus comes from the nerve to the obturator internus, but the inferior gemellus and the quadratus femoris are supplied by the nerves to the quadratus.

The *obturator externus* muscle is visible in this region but it is better to study its origin when the medial side of the thigh is discussed (Fig 402). It winds backward below the hip joint, its tendon passing obliquely upward and laterally on the back of the neck of the femur to become inserted into the trochanteric fossa.




FIG 621 Relations around the right hip joint. The femur has been removed, and the acetabulum is viewed from the right side.

of the rectus femoris. As it passes downward it divides into two bands which are separated by a narrow interval. The upper band extends to the upper part of the intertrochanteric line and the lower to the lower part of the same line. It is thicker at its sides than in the middle which accounts for its Y appearance. The thinner central portion is perforated by an artery for two-thirds from the ascending branch of the lateral femoral artery. This ligament is approximately a quarter of an inch thick and is one of the strongest ligaments in the body, its only rival being the intersacrosacral ligament. Bigelow has stated that a strain varying from 250 to 750 pounds is required for its rupture. It is rarely torn in hip dislocations. The *pubofemoral ligament* arises from the pubic bone and the obturator membrane and is inserted with the lower limb of the iliofemoral ligament. Above between these two ligaments there is usually a gap through which the sub-psoas burr communicates with the joint. The *ischiofemoral ligament* is a weak band which arises from the ischium below the acetabulum and passes upward and laterally to blend with the posterior part of the capsule.

When one stands erect with the toes turned out the articular cartilage on the head of the femur is directed forward. Its lateral part is protected by the iliofemoral ligament and its medial part by the pubofemoral ligament; however the intermediate part has no covering ligament; hence it is the weak point which is commonly perforated (Fig. 619 A). Passing over this weak point however is the tendon of the psoas muscle which provides some protection. Muscle fibers do not withstand pressure by underlying bone; therefore in such locations they give place to tendons. This is true of the psoas tendon. Furthermore tendons which pass over bony prominences require bursae to diminish friction and to facilitate a free movement. The psoas bursa which commonly communicates with the joint between the iliofemoral and the pubo-

femoral ligaments is no exception to this rule. In front of this tendon lies the femoral artery. The femoral nerve, which is lateral, lies in front of the iliacus muscle. The femoral vein which is medial lies in front of the pectineus muscle (Fig. 622).

The *synovial membrane* lines all parts of the interior of the hip joint except where articular cartilage or fibrocartilage is found (Figs. 619, 619 B and 620). This last statement is true of all synovial joints. The membrane lines the neck of the femur completely in front and as far as the obturator externus tendon behind. It stretches across the acetabular fossa. In front of the femoral neck and below it the membrane is thrown into several loose folds which are called *retinacula* and in which arteries run onto the neck of the femur. As the membrane protrudes posteriorly between the free lower border of the fibrous capsule and the neck it forms a bursa for the tendon of the obturator externus. Therefore an incision made above this tendon usually will enter the joint but one made below usually will miss it.

The *ligamentum teres* or ligament of the head of the femur consists mainly of synovial membrane. It has the form of a flattened triangular band. It is attached above to the fovea on the head of the femur and below it blends with the transverse ligament. Most anatomists believe that it does not play a major part in holding the femur in the acetabulum. The Weber brothers showed the importance of the part played by atmospheric pressure rather than the ligamentum teres. They suspended a cadaver and divided all the muscles and ligaments around the joint and the head of the femur did not pull free. If an opening was made into the acetabulum to allow the entry of air the lower limb immediately fell off. On closing the opening with the finger the limb could again be kept in position. The ligament is tense when the *semiflexed limb* is adducted or rotated outward. It acts as a 'mesentery' since it carries an artery to the femoral head.

teres through which the head receives a small arterial supply. At birth the proximal end of the femur is entirely cartilaginous. The neck is ossified by an extension from the diaphysis as it forms it divides the cartilage into two parts. The more proximal of these parts forms the head. A center of ossification appears in the head early in the first year and unites with the neck during the twentieth year. The more distal part forms the greater trochanter, which begins to ossify in the third year and joins the shaft about the nineteenth year.

In order to increase the power and the mobility of the inferior extremity the neck of the femur is inclined to the shaft at an angle which is about 125° in the adult, and 160° in the child. This has been known as the angle of inclination.

The *acetabulum* (acetum L. = vinegar cup) lies at the point of union of the ilium, the ischium and the pubis. This cup shaped cavity is deficient below where it forms a gap called the *acetabular notch*, which is bridged over by the *transverse acetabular ligament* and the glenoid lip, thus being converted into a *foramen* for the entrance of vessels and nerves. The remainder of the peripheral part of this cup is horse shoe shaped since it articulates with the femur it is covered with cartilage. The floor of the acetabulum which is called the acetabular fossa is covered by a small fat pad (haversian) which in turn is covered by synovial membrane.

The *acetabular lip* (labrum acetabulare glenoid labrum) is a firm fibrocartilaginous ring which is fixed to the rim of the acetabulum. It deepens the cavity of the acetabulum and narrows its mouth. It fits closely upon the head of the femur and has a suckerlike action which exerts an important influence in retaining it in place. Therefore, although the hip joint has been opened it is not easy to pull the head of the femur out of the acetabulum. Both surfaces of the lip are covered with synovial membrane, its free margin is thin but at its

attachment at the acetabular ring it becomes much thicker. Inferiorly, where it bridges the acetabular notch, it is called the transverse acetabular ligament. The *epiphysis* of the head of the femur encircles the articular margin and lies entirely within the synovial capsule. The ilium, the ischium and the pubis contribute to the articular part of the acetabulum. This synostosis is completed about the sixteenth year.

LIGAMENTS

The *capsular ligament* is exceedingly strong and surrounds the joint on all sides. It is attached proximally around the acetabulum and grasps the neck of the femur distally. The anterior part of the distal attachment occupies the whole length of the trochanteric line and the roof of the greater trochanter. It is very firm and strong. Posteriorly, it falls short of the trochanteric crest by about one half an inch therefore its attachment to the neck of the femur is weak. The fibers of this ligament run in two different directions the majority passing obliquely from the hip bone to the femur. However, other fibers lie at right angles to the oblique ones and these constitute the *zona orbicularis* (Figs 619 and 620). They are circular fibers and are more distinct in the posterior part of the capsule. They encircle the neck of the femur posteriorly and below, but are lost toward the upper and the anterior part of the capsule.

Since the ilium, the pubis and the ischium take part in the formation of the acetabulum capsular fibers proceed from each of these bones to the femur. They are known as the iliofemoral, the pubofemoral and the ischiofemoral ligaments (Fig 619). These are thickened portions of the capsule which have been given special names. The *iliofemoral* or inverted Y shaped ligament of Bigelow, is placed over the front of the joint and is the thickest and most powerful part of the capsule. It is attached above to the antero inferior iliac spine immediately below the origin of the straight head

the femoral artery the iliacus, the femoral nerve, the pectineus and the femoral vein (2) *Laterally*, the rectus femoris in front of the iliofemoral ligament and the gluteus minimus (3) *Inferiorly* the obturator externus crosses below the head and runs behind the neck of the femur (4) *Posteriorly* the piriformis the obturator internus the gemelli the upper border of the quadratus femoris and the sciatic nerve

SURGICAL CONSIDERATIONS

TRAUMATIC DISLOCATIONS OF THE HIP

Since the hip is firmly stabilized by the powerful muscles and the strong capsule which are associated with it traumatic dislocations are rather infrequent. The weak point of the joint is at its lower part where a portion of the acetabular rim is deficient. When dislocations do occur however they may be posterior anterior or central (Fig 623)

In a *posterior dislocation* the head of the femur is forcefully pushed against the posterior part of the capsule which it tears; it then passes upward and backward and may occupy an iliac or sciatic position. Hence two types of posterior dislocations have been described namely the iliac variety and the sciatic variety. In the latter the head of the femur lies below the tendon of the obturator internus muscle; in the iliac variety the femoral head lies on the dorsum of the ilium and can be felt in the buttock. The iliofemoral ("Y") ligament usually is not torn since it is the strongest part of the capsule but the posterior portion of the capsule usually is torn. The sciatic nerve may be damaged and the short rotator muscles of the femur particularly the obturator internus also may be injured.

In the *anterior dislocation* the head of the femur is forced through the inferomedial aspect of the joint and passes medially and forward; it may come to rest upon the obturator foramen (obturator variety) or may continue still more anteriorly to reach a position beneath the pubis




FIG 624 The anterior approach to the hip joint

(pubic variety). In the obturator variety the femoral head rests upon the obturator externus muscle. In the pubic variety the femoral head is found in front of the horizontal ramus of the pubis opposite the iliopectineal eminence. The iliopectineal muscles as well as the obturator and the femoral nerves may be injured.

A *central dislocation* of the head of the femur penetrates through the acetabulum and has been referred to as the intrapelvic variety. Usually a radiating type of fracture of the acetabulum results with a depression of the socket.

SURGICAL APPROACHES TO THE HIP JOINT

Numerous approaches have been described for exposure of the hip joint. However only four of these will be discussed in this section, namely the anterior, the anterior iliofemoral, the lateral and the posterior.

The *anterior approach* to the hip joint commences with a five inch or six inch skin incision which extends from the anterior superior iliac spine downward along the sartorius muscle (Fig 624). The super-




FIG 623 Traumatic dislocation of the hip joint

VESSELS AND NERVES

The *arteries* that supply the hip joint are derived from the gluteal the circumflex and the obturator arteries. Wolcott is of the opinion that the anastomosis between the ligamentum teres vessel, the capsular artery and the nutrient artery of the shaft does not take place until the ossification of the head of the femur is practically if not entirely completed. At this time the vessels of the three systems unite by penetrating the thinned out cartilage area at the fovea, thus establishing the anastomosis. The ligamentum teres circulation, he believes is a closed one in so far as the femoral head is concerned, until such an anastomosis takes place. The *nerves* are derived from the nerves to the quadratus femoris the femoral via the nerve to the rectus femoris the anterior division of the obturator nerve and occasionally the accessory obturator nerve.

MOVEMENTS

The depth with which the femoral head enters its socket would have made only flexion and extension possible, but, owing to the length of the femoral neck, greater freedom of movement is permitted. *Flexion* is much greater in the flexed than in the extended position because in this position the capsule is looser. In full extension the head of the femur tends to leave the acetabulum, and the articular surfaces may be separated by one or two centimeters. Flexion is limited by the sides coming in contact with the anterior abdominal wall. The muscles which produce flexion are the psoas, the rectus femoris the sartorius, the pectineus, the anterior part of the gluteus medius and the minimus. In *extension* the articular surfaces are held in close contact. *rotation* and *abduction* are not as free as in flexion. Extension is limited by the iliofemoral (Bigelow) ligament. The muscles which produce extension are the gluteus maximus the hamstrings and the posterior part of the adductor magnus. *Abduction* is very slight in extension, being checked by the "Y" and the pubocapsular ligaments. It is produced by the gluteus medius, the minimus, the upper part of the maximus, the tensor fasciae latae and the sartorius. *Adduction* is produced by the adductors, the gracilis and the pectineus. It is checked by the other limb, but, if in flexion, by the "Y" ligament. The extent of *rotation* is about 90°. *Internal rotation* is produced by the anterior part of the gluteus medius and minimus the tensor fasciae latae and the iliopsoas and is limited by the ischio capsular ligament. *External rotation* is produced by the obturator externus, the obturator internus, the gemelli the piriformis, the quadratus femoris, the posterior parts of the glutei, the adductors and the sartorius and in the flexed condition by the iliopsoas.

RELATIONS

The *relations* are the following (Figs 621 and 622) (1) *Anteriorly* the psoas and

riorly by separating fibers of the gluteus maximus muscle so that adequate exposure is attained. The exposed capsule is incised longitudinally along the superior surface of the femoral neck.

The posterior approach to the hip joint may be accomplished by means of a posterior curved incision described by Kocher. This incision begins at the posterosuperior iliac spine, extends outward and downward one inch distal to the greater trochanter (Fig. 627). The superficial and the deep fasciae are incised and the gluteus maximus muscle is divided about one inch distal to the posterior iliac spine. The aponeurotic insertion of the gluteus maximus is separated from the trochanter. The muscle is then retracted proximally and distally, thus exposing the sciatic nerve and the external rotator muscles of the hip joint. The hip is rotated outward; the tendons of the superior gemellus, the obturator internus and the inferior gemellus muscles are divided about one half inch from their insertion. After retracting the latter muscles medially and the piriformis muscle proximally, the posterior articular capsule




FIG. 627 The posterior approach to the hip joint

will be exposed. The capsule is incised longitudinally and transversely, thereby exposing the posterior aspect of the head and the neck of the femur.




FIG 625 The anterior iliofemoral approach to the hip joint (Smith Peterson)

ficial and the deep fasciae are incised and the upper third of the sartorius and the rectus femoris muscles are exposed. In this region the superficial circumflex iliac vessels are seen and may require ligating. The sartorius and the iliopsoas muscles are retracted medially, and the femoris muscles laterally. This exposes the anterior capsule of the hip joint. The femoral nerve lies on the medial aspect of this capsule and should be retracted medially. The capsule is opened in a longitudinal direction; if greater exposure of the joint is needed, a transverse incision into the capsule is added at the end of the longitudinal one.

The *anterior iliofemoral approach* to the hip joint has been described by Smith Petersen (Fig 625). This exposes the anterior and the lateral aspects of the hip joint. The incision commences at about the middle of the iliac crest, curves forward to the anterior superior iliac spine and then continues distally and somewhat laterally for about five inches. The superficial and the deep fasciae are incised and the gluteus medius and the tensor fasciae latae muscles are severed about one quarter of an inch from the iliac crest. These muscles are




FIG 626 The lateral approach to the hip joint

stripped subperiosteally downward and backward. At times the lateral cutaneous nerve is seen and retracted medially. The capsule is now exposed and is incised transversely, care being taken to avoid injuring the iliofemoral ligament which is on the anterior aspect of the capsule. If greater exposure of the hip joint is needed, the ligamentum teres can be cut, and the femur rotated externally so that the head of the femur is dislocated. Rapid closure may be accomplished by replacing the periosteum against the ilium and suturing the severed muscles to the crest of the ilium.

The *lateral approach* to the hip joint can be accomplished through a "U" shaped incision as described by Olier (Fig 626) (Watson Jones described a lateral approach through a curved incision). The "U" shaped incision commences at the antero superior iliac spine, continues distally below the greater trochanter across the femur, then posteriorly and upward and ends midway between the greater trochanter and the posterosuperior iliac spine. The gluteus medius muscle is separated posteriorly, and the tensor fasciae latae muscle anteriorly down to the greater trochanter. The greater trochanter is removed with an osteotome and, with its attached muscles, is displaced proximally. The incision is extended poste-



FIG 628 The thigh

layer and the deep fascia of the abdominal wall. Upon reaching the abdominal wall they cannot descend the front of the thigh because of the connection of the membranous layer and the fascia lata (deep fascia).

In the superficial fascia the subcutaneous

vessels, the nerves and the lymph glands are found. Of practical importance is the *internal saphenous vein* (saphena magna, great or long saphenous vein) (Fig 630). In the thigh it usually is concealed by the surrounding fat, but it is seen easily in the

The Thigh

The thigh extends from the hip to the knee (Fig 628) The spine of the pubis and the anterosuperior iliac spine, with the inguinal ligament stretched between these two points is the dividing line between the thigh and the abdomen The upper boundary of the thigh posteriorly is the transverse gluteal fold the lower thigh boundary has been set at a level three fingerbreadths above the base of the patella

The contour is conical and oblique in a downward and inward direction this obliquity is more marked in the female The muscles stand out boldly in the well developed male but in the female the thigh is rounded more uniformly due to the greater amount of subcutaneous fat

THE FRONT OF THE THIGH

NERVES FASCIA VESSELS AND LYMPH GLANDS

The skin of the thigh is thicker over the lateral aspect The *cutaneous nerves* of the front of the thigh are (Fig 629)

1 The *ilio inguinal nerve* (L 1) which is located close to the pubic spine and to the outer side of the spermatic cord It supplies the skin of the scrotum and the root of the penis in the male, as well as that part of the thigh in contact with the genitals It supplies the labium majus in the female

2 The *lumbo inguinal nerve* (femoral branch of the genitofemoral L 1, 2) is small and supplies a limited area below the middle of the inguinal ligament It is a slender nerve and not easily found It pierces the deep fascia a little lateral to the saphenous opening

3 The *lateral cutaneous nerve* of the thigh (L 2, 3) appears behind the lateral end of the inguinal ligament It divides into anterior and posterior branches which supply the skin of the lateral aspect of the thighs as far down as the knee it helps in the formation of the patellar plexus The posterior branch supplies the anterior part of the buttocks

4 The *intermediate cutaneous nerve* of the thigh (L 2, 3) supplies the skin over the anterior aspect of the thigh by means of lateral and medial branches, which end in the patellar plexus

5 The *medial cutaneous nerve* of the thigh (L 2 3) supplies the medial aspect of the thigh and ends in the patellar plexus

The *superficial fascia* of the lower limb is the same as that of the body generally Therefore, it has two layers, a fatty superficial layer of superficial fascia, which is a continuation of Camper's fascia of the abdomen and a deep membranous layer of superficial fascia, which is a continuation of Scarpa's fascia of the abdomen The latter is attached to the deep fascia of the thigh about a finger's breadth below the inguinal (Poupart's) ligament, more medially, it attaches along a line which runs parallel with and lateral to the spermatic cord This line runs from the pubic tubercle to the pubic arch

If urine or other fluids pass into the anterior part of the perineum they cannot encroach upon the medial side of the thigh because of the attachment of the membranous layer of superficial fascia from the pubic tubercle to the pubic arch However, they can ascend between the membranous

The most proximal gland of this group (gland of Cloquet) lies in the femoral canal (p. 812). The efferents from the popliteal glands end in these glands and they in turn drain into the external iliac lymph glands.

DEEP FASCIA (FASCIA LATA)

The structures discussed to this point lie in the superficial fascia. Beneath this is the deep fascia (fascia lata). This fascia attaches above and below to all the bony and the ligamentous structures available. *So* it is attached completely around the limb to the anterior superior iliac spine, the inguinal ligament, the pubic bone (body), the pubic arch, the ischial tuberosity and the sacrotuberous ligament. Posteriorly the fascia lata becomes the gluteal fascia and is attached to the sacral spines and the iliac crest and ends as the fascia lata at the anterior superior iliac spine. *Below* the fascia lata attaches to the periosteum of the patella, the medial and the lateral condyles of the tibia and the head of the fibula. Thus it completely surrounds the thigh as a tight fitting sleeve. Posteriorly it continues as the popliteal fascia. The fascia lata is much stronger laterally than medially because of the iliotibial tract which fuses and runs with it. This tract is a conjoined tendon for the insertion of the gluteus maximus and the tensor fasciae latae into the deep fascia of the thigh. The fascia lata provides septa which separate the various groups of muscles of the thigh. Each septum inserts at the linea aspera (Figs. 628 and 631). Thus each group is enclosed in a separate fascial compartment. Since there are three main groups of muscles (extensors, flexors and adductors) there are three main septa.

1 The *lateral intermuscular septum* separates the extensors from the flexors and extends from the deep surface of the fascia lata to the femur along the linea aspera as far as the lateral epicondyle.

2 The *medial intermuscular septum* separates the extensors from the adductors




FIG. 630 (A) The internal saphenous vein (B) The inguinal lymph glands




FIG 629 The cutaneous nerve supply of the anterior region of the thigh

leg hence its name (saphes = easily seen). This vein originates at the inner side of the *dorsal venous arch* of the foot and passes upward in front of the internal malleolus. It continues to ascend behind the inner border of the tibia as far as the posterior surface of the internal condyle of the femur. From here it takes a straight upward course along the medial aspect of the thigh to the fossa ovalis where it empties into the femoral vein (sapheno-femoral junction). Entering the long saphenous vein are two veins which run almost parallel with it. One enters from the antero-external aspect of the thigh and is called the anterior (lateral superficial) saphenous; the other from the postero-internal aspect of the thigh is called the posterior (medial superficial) saphenous. Three additional veins enter the long saphenous: they are the superficial external pudic, the superficial epigastric and the superficial circum-

flex iliac. Each of these is accompanied by its corresponding artery; the arteries are branches of the femoral artery. Some of the superficial tributaries may empty directly into the femoral instead of the internal saphenous vein; therefore, they do not serve as absolute guides; hence, the femoral vein may be ligated by mistake.

The *superficial external pudic* (pudendal) vessels pass medially over the spermatic cord in the male and the round ligament of the uterus in the female. The deep external pudic vessels run under the spermatic cord or the round ligament; the internal pudic vessels reach the external genitals within the pelvis.

The *superficial epigastric vessels* arise about 1 cm below the inguinal ligament. The vein usually enters the saphenous opening, but the artery pierces the deep fascia lateral to the opening.

In this region a number of *lymph glands* will be encountered (Fig 630 B). They are subdivided as follows:

Superficial Group

1 An upper (horizontal) group lies parallel to the inguinal ligament below the attachment of Scarpa's fascia to the fascia lata. They drain the regions supplied by the three superficial inguinal blood vessels (anterior abdominal wall below the navel, the penis, the scrotum, the vulva, the vagina, the anus, the perineum and the buttock).

2 A lower (perpendicular) group is placed on both sides of the upper end of the long saphenous vein. This group receives the superficial lymph vessels of the lower limb except those from the lateral side of the foot and the posterolateral area of the leg which enter the popliteal glands. Lymphangitis from septic conditions of the toes produces enlargement of this set of glands.

Deep Group The deep inguinal lymph glands receive the deep lymph vessels of the lower limb. They are four or five in number and lie beneath the deep fascia close to the upper part of the femoral vein.




FIG. 633 The femoral triangle of Scarpa and its contents. The roof (fascia lata) of the triangle has been removed and the relations of the femoral nerve and vessels to the iliac fascia are shown.

angle is removed the contents, namely the femoral nerve, the artery and the vein, become visible.

Femoral Sheath: Artery, Vein, and Nerve. The *femoral sheath* can be understood by studying the fascial relations in the false pelvis and following them into the thigh (Fig. 634). The fascia which covers the iliopsoas muscle is the iliopsoas fascia. It extends from the iliac crest laterally to the pelvic brim medially. The femoral nerve lies behind it, but the femoral vein and artery lie upon it. The iliopsoas muscle and its fascia pass behind the inguinal ligament on their way to the thigh. The iliac part of the fascia comes in direct contact with the inguinal ligament since

no structures intervene; however, that part of the fascia which covers the psoas muscle cannot touch the inguinal ligament because the femoral artery and vein lie upon the fascia separating it from the ligament. The femoral vessels thus leave the pelvis and enter the thigh, and the psoas fascia continues behind the vessels to become continuous with the pectineus fascia. It has been stated that the fascia lata "takes its origin" from the inguinal ligament; hence the iliac part of the iliopsoas fascia fuses with the fascia lata, but it is impossible for the psoas part of the fascia to touch the fascia lata because of the interposed femoral artery and vein. Therefore, the fascia lata lies in front of




FIG 631 The septa of the thigh. The three main intermuscular septa of the thigh (lateral, medial and posterior) form fascial compartments for the three main groups of muscles (extensors, flexors and adductors)

This septum is much thinner than the lateral. It forms the floor of Hunter's canal (p 822).

3. The *posterior intermuscular septum* separates the adductors from the flexors. This septum, which originates from the deep surface of the fascia lata, is associated with the connective tissue surrounding the sciatic nerve. There are also separate fascial compartments for the individual muscles as well as the larger compartments for the muscle groups.

The fascia lata has numerous small openings for the passage of the vessels and the nerves and one large opening, the *fossa ovalis*, for the internal saphenous vein (Fig 632). This opening is not quite as well marked as the average textbook picture would lead us to believe. Although present and demonstrable, it may be quite indistinct. It is a little more than one inch long, a little less than an inch wide and appears about one inch below the medial end of the inguinal ligament. When well developed, its upper lateral and lower boundaries are well defined and together form a sharply curved edge, the falciform margin. Its medial border is poorly denned




FIG 632 The fossa ovalis

and blends with the pectineus fascia. The falciform margin has an upward and medial prolongation, the superior cornu, and a downward and medial prolongation, the inferior cornu. The superior cornu passes in front of the femoral vessels and attaches to the pubic spine. The inferior cornu passes behind the saphenous vein and blends with the pectineus fascia. The fossa ovalis is covered by a loose areolar and fatty tissue, the fascia cribriform, which fills the fossa.

INGUINO-FEMORAL (SUBINGUINAL) REGION

This region extends from the inguinal ligament above to the level of the apex of the femoral (Scarpa's) triangle below. It also includes the area from the tensor fasciae latae muscle laterally to the pectineus muscle medially.

Femoral Triangle. The femoral triangle of Scarpa (femoral trigone) lies directly below the inguinal ligament which forms its base (Fig 633). Laterally, it is bounded by the medial border of the sartorius muscle, and medially by the medial border of the adductor longus muscle. The floor of the triangle is formed laterally to medial, by the iliacus, the pectineus and the adductor longus muscles. The adductor longus forms part of the floor as well as the medial boundary. The roof is formed by the fascia lata. When the roof of the tri-

of these muscles in the following way (1) from the pons by its sheath and by the nerve to the pectineus (2) from the pectineus by a fat pad which contains the profunda vessels, and (3) from the adductor longus by the femoral vein.

The *profunda femoris artery* is a large vessel which usually arises from the posterolateral aspect of the femoral artery. It may arise as high as the level of the inguinal ligament in which case two main arteries appear to enter the limb. The profunda femoris artery is almost as large as the femoral artery proper. The profunda leaves the triangle by passing behind the adductor longus which separates it from the femoral vessels proper. It then lies on the adductor magnus where it ends as the fourth perforating artery. The lateral and the medial circumflex arteries spring from the profunda near its origin. The *lateral artery* passes laterally among the branches of the femoral nerve sometimes separating this nerve into superficial and deep sets of branches. It leaves the triangle by passing, under cover of the sartorius muscle. It divides into three branches (1) an ascending branch which ends with the nerve to the tensor fasciae latae (2) a transverse branch which anastomoses with the medial circumflex artery, and (3) a descending branch which is associated with the nerve to the vastus externus (vastus lateralis). The *medial circumflex artery* passes through the floor of the triangle between the pectineus and the iliopsoas muscles and terminates in the buttocks at the lower border of the quadratus femoris. The femoral artery leaves the apex of Scarpa's triangle to enter the subsartorial (adductor) canal of Hunter (p 822).

The *femoral vein* is a large vessel and is a direct continuation of the popliteal vein. It begins at an opening in the adductor magnus ascends through the subsartorial canal of Hunter and the femoral triangle and ends behind the inguinal ligament, where it becomes the external iliac vein.

Below it lies posterolateral to the artery, but in the greater part of its course it lies posteriorly except in the upper part of the thigh, where it lies to the medial side of the femoral artery. It receives the long saphenous vein as its main tributary and other smaller tributaries some of which correspond to the artery. At the apex of Scarpa's triangle a definite order of structures exists (Fig 636) from before backward the femoral artery, the femoral vein, the adductor longus muscle, the profunda vein and the profunda artery. Hence, a stab or a bullet wound at the apex of Scarpa's triangle could penetrate all four of these vessels in succession.

The *femoral nerve* is the nerve of the anterior compartment of the thigh. It arises within the abdomen from the lumbar plexus, and forms a thick nerve (Fig 637). In the false pelvis it lies deep in the groove between the psoas and the iliacus and enters the femoral triangle by passing behind the inguinal ligament. In the thigh it is lateral to the femoral artery from which it is separated by a small part of the psoas muscle and the femoral sheath. About one inch below the inguinal ligament it breaks up into a "cauda equina"—like a leash of muscular and cutaneous nerves. The muscular branches pass to the pectineus, the sartorius and the quadriceps femoris. The cutaneous branches constitute the medial cutaneous and the intermediate cutaneous nerves of the thigh and the saphenous nerve. Two of these branches closely follow the artery on its lateral side and into the subsartorial canal the saphenous nerve which is sensory and the nerve to the vastus medialis which is motor. The nerve supply to the quadriceps femoris is through four separate nerves one to each head: the rectus femoris and the three vasti. Articular nerves arise from these four muscular branches. The nerve to the rectus femoris sends a slender branch to the hip joint, and the nerves to the vasti send filaments through the muscles to the knee joint.

the vessels and the continuation of the ilio psoas fascia (pectineus fascia) lies behind them. The femoral vessels (not the nerve) are thus wrapped in a downward prolongation of the extraperitoneal fatty areolar tissue which becomes the femoral sheath.

the femoral triangle (Fig 635). To locate the nerve to the pectineus muscle (femoral nerve) one must retract the femoral artery medially and the femoral nerve laterally. It is of fair size and descends downward and inward to disappear deep




FIG 634 The femoral sheath

The anterior wall of this sheath is formed by a continuation of transversalis fascia; this lines the deep surface of the anterior abdominal wall. The posterior wall of the sheath is formed by that part of the ilio psoas fascia which lies behind the femoral vessels. The sheath ends about an inch and a half below the inguinal ligament by blending with the adventitial coats of the femoral vessels. Two anteroposterior septa divide the sheath into three compartments. Separate longitudinal incisions may be made over each compartment to identify the contents. The femoral artery occupies the lateral compartment, the femoral vein occupies the middle compartment, and in the medial compartment also called the *femoral canal* (p 812) are found the main lymph vessels of the lower limb.

The femoral artery, a continuation of the external iliac artery, bisects the inguinal ligament (midinguinal point) and is therefore the ventral structure running through

to the femoral artery or between it and the deep femoral artery. This is the only motor nerve that crosses the femoral artery in Scarpa's triangle, and since it does so posteriorly it is in a protected position.

Several superficial branches arise from the femoral artery. The superficial circumflex iliac and the superficial epigastric arteries have been described (Fig 635). The superficial external pudendal passes medially in front of the femoral vein and then crosses to the spermatic cord. The deep external pudendal artery arises a little over an inch below the inguinal ligament, runs medially but behind the femoral vein and in front of the pectineus and the adductor longus muscles. It pierces the fascia lata and is distributed to the scrotum or the labium majora.

As the femoral artery travels through Scarpa's triangle it crosses its transmuscular floor. However, it is separated from each




FIG 636 The relations of the femoral artery and vein in the femoral triangle




FIG 637 The femoral nerve




FIG 655 The femoral artery

SURGICAL CONSIDERATIONS

THE SURGICAL ANATOMY AND REPAIR OF A FEMORAL HERNIA

In a femoral hernia the abdominal contents enter the femoral ring, pass through the femoral canal and leave through the fossa ovalis (Fig 638) In so doing, the

abdominal contents push the parietal peritoneum, the extraperitoneal fat and the femoral septum on ahead The femoral canal is only about one half inch in length therefore it is more of an anatomic landmark than a true canal or surgical structure The femoral ring has the following boundaries

The *subinguinal approach* usually is performed through a vertical incision placed directly over the protruding mass (Fig 639). The incision is deepened until a fatty mass is seen below the fatty areolar layer. If the falciform margin is well developed it can be severed; otherwise one proceeds directly to the femoral ring, where the neck of the sac is freed. The extraperitoneal fat is incised and the sac (peritoneum) is located and opened. If the femoral ring is so small and tight that strangulation is produced and the contents cannot be reduced, more room can be gained by cutting the lacunar ligament. If visible the contents are reduced and the sac is ligated and excised. The usual method of repair is one in which the inguinal ligament is sutured to the fascia of the pectineus muscle. The femoral vein must not be encroached upon.

The *inguinal approach* opens the inguinal canal as in the repair of an inguinal hernia. The transversalis fascia is incised, and the neck of the femoral hernia sac is located in the extraperitoneal fatty layer just proximal to the femoral ring. The sac is drawn into the inguinal canal; it is handled in the routine manner. Both the femoral ring and the inguinal canal are closed by placing sutures which approximate the conjoined tendon and the inguinal ligament to Cooper's ligament.

LIGATION OF THE FEMORAL ARTERY IN THE FEMORAL TRIANGLE

The femoral artery is situated in a superficial position in the femoral triangle of Scarpa (Fig 640). The femoral vein lies in close proximity to the artery. The artery is easily ligated in this location because of its superficial position and because of the ease with which it can be separated from the femoral vein, since each vessel is situated in its own compartment within the femoral sheath. Collateral circulation is maintained through anastomoses between




Fig 640 Exposure and ligation of the femoral artery in the femoral triangle

the superior and the inferior gluteal vessels and the first perforating branch of the deep (profunda) femoral artery.

Ligation of the artery at the apex of the femoral trigone can be accomplished through an incision placed directly over the vessel. The sartorius muscle is identified and retracted laterally; the vessel is isolated just before it enters the subsartorial (adductor) canal of Hunter. Collateral circulation is maintained by anastomoses around the knee joint where the branches of the profunda femoris artery anastomose with the branches of the popliteal artery.

MUSCULATURE OF THE THIGH

Since the thigh is capable of performing four principal types of movements it is well to consider the musculature in four parts (Fig 621).

- 1 Adductors (obturator nerve)
- 2 Abductors (superior gluteal nerves) (see p 792)
- 3 Extensors, anterior femoral muscles, (femoral nerve)
- 4 Flexors posterior femoral muscles, (sciatic nerve)




FIG 638 Femoral hernia

Anterior the inguinal ligament
Posterior the pectineus fascia and muscle

Lateral the femoral vein

Medial the lateral sharp edge of the lacunar (Gimbernati's) ligament

With these boundaries kept in mind one readily comprehends the danger of cutting lateral to a femoral hernia (femoral vein)

Surgical Repair The surgical repair of a femoral hernia may be accomplished through a subinguinal approach or an inguinal approach




FIG 639 The anatomy involved in the repair of a femoral hernia




FIG 642 The obturator nerve

turator nerve (The posterior division of the nerve lies behind the adductor brevis) The anterior division of the nerve supplies the adductor longus and the brevis the gracilis and the hip joint Also running in this fat is the deep branch of the femoral artery (profunda femoris) with its accompanying veins The adductor brevis arises from the body of the pubis below the adductor longus and runs downward backward and laterally It inserts into the linea aspera above and behind the adductor longus reaching almost as high as the lesser trochanter Its upper border lies against the obturator externus If the adductor brevis is cut near its origin and turned downward the adductor magnus is seen

The *adductor magnus muscle* is the largest and the most posterior of the three adductors It arises from the pubic arch and the outer part of the inferior surface of the ischial tuberosity It inserts on the

linea aspera extending upward along the linea aspera's lateral continuation the gluteal tuberosity and downward on its medial continuation the medial epicondylar line The fibers which arise from the ischial tuberosity pass almost vertically downward to insert by means of a short tendon into the adductor tubercle which is located on the medial condyle of the femur

At the insertion of the muscle a series of osseous aponeurotic openings are formed by tendinous arches which attach to the bone (Fig 643) The upper openings, usually four in number, are small and give passage to the perforating branches of the profunda femoris artery The lowest opening is the largest and is called the *adductor hiatus* Through it the femoral vessels enter the popliteal fossa The upper border of the adductor magnus lies close to the lower border of the obturator externus, the pos




FIG 641 The adductor group of muscles. Six muscles constitute this group: the three adductors (longus, brevis and magnus), the pectineus, the gracilis and the obturator externus.

THE ADDUCTOR (OBTURATOR) GROUP

The *adductor region* has been referred to as the *obturator region* since it is supplied by the obturator nerve. In this region, which is situated on the medial aspect of the thigh, are found six muscles: three adductors (longus, brevis and magnus) plus three other muscles, the pectineus, the gracilis and the obturator externus (Fig 641).

These muscles constitute a group which is interposed between the *extensor group* in front and the *flexor group* behind. The adductor muscles arise from the bones around the obturator foramen and the

obturator membrane; they insert from the trochanteric fossa of the femur above to the medial surface of the tibia below (Fig 652).

The *pectineus muscle* can be exposed after having identified the femoral triangle; it makes up part of the floor of this triangle. It arises from the superior ramus of the pubis, runs downward and backward to become inserted into the posterior aspect of the proximal part of the femoral shaft just below the lesser trochanter. This muscle is peculiar in that it has a double nerve supply (Fig 642). The medial part is supplied by the obturator nerve; the lateral half, by the femoral nerve. Because of this, some anatomists believe that the muscle has a double origin and should be divided into medial and lateral parts. Although the greater part of the muscle is supplied by the nerve to the pectineus (Fig 642) (femoral nerve), it is still considered one of the adductors in the obturator group.

The *adductor longus muscle* lies on the same plane as the pectineus; therefore it also makes up part of the floor of Scarpa's triangle. It arises by a flattened tendon from the body of the pubis in the angle between the crest of the ilium and the symphysis pubis. If the thigh is abducted, its tendon becomes prominent and palpable and acts as a guide to the pubic tubercle. Extending downward and laterally, its fibers spread out into a rather broad thin aponeurosis which inserts into the medial lip of the linea aspera. It lies between the pectineus and the gracilis (The adductor brevis may be seen behind and between the pectineus and the adductor longus muscles.) It is the most anterior of the three adductor muscles. If it is divided near its origin and turned down, its nerve and blood supply are seen entering its deep surface. The muscle which is exposed by reflecting the adductor longus is the adductor brevis.

The *adductor brevis* is a large muscle, is covered with fat on its anterior surface. In this fat lies the anterior division of the ob-




FIG 645 The subsartorial (adductor) canal of Hunter

THE LATENSOR (ANTERIOR) GROUP

The *extensor group* of muscles is the *femoral nerve group*. This group has been referred to as the flexors of the hip, but usually they are called the extensors of the knee. The group consists of the sartorius, the quadriceps femoris, the iliopsoas and the pectineus (Fig 644).

The *sartorius muscle* is the longest muscle in the body; its fleshy part usually measuring over 18 inches in length. It arises mainly from the anterosuperior iliac spine, then crosses the upper third of the thigh obliquely and descends almost vertically to the posterior part of the medial side of the knee. It passes forward and ends in a thin tendon which is inserted into the upper part of the medial surface of the tibia. It is superficial to the tendons




FIG 646 The quadriceps femoris muscle




FIG 647 The cutaneous nerve supply of the posterior aspect of the thigh




FIG 643 The adductor magnus muscle and its four osseo aponeurotic openings

terior border of the adductor magnus is in relation to the hamstring muscles and the sciatic nerve (Fig 648)

The *obturator externus muscle* arises from the medial margin of the obturator foramen and from the lateral surface of the obturator membrane (Figs 402 and 641). The fibers converge and pass behind the neck of the femur. The obturator vessels lie between the muscle and the obturator membrane. The anterior branch of the obturator nerve reaches the thigh by passing in front of the muscle, the posterior branch by piercing it. It is the powerful lateral rotator of the thigh and is seen best after division of the pectineus muscle.




FIG 644 The extensor group of muscles. To identify immediately the entire musculature of the front of the thigh, the letter "N" can be constructed, using the tensor fasciae latae, the sartorius and the gracilis. Three muscles lie above the sartorius (iliopectineus, pectineus and adductor longus) and three muscles lie below the sartorius (vastus lateralis, rectus femoris and vastus medialis).

The *gracilis muscle* is the most superficial muscle on the medial side of the thigh. It is thin and straplike and arises from the margin of the upper part of the pubic arch and the adjoining part of the body of the pubis. It passes behind the medial epicondyle of the femur and inserts into the upper part of the medial surface of the tibia. When the hamstring muscles are paralyzed, flexion of the leg is accomplished by the gracilis and the sartorius muscles.




FIG 649 The deeper structures of the posterior aspect of the thigh




FIG 648 The hamstring muscles

the thigh and is inserted into the common extensor tendon. If the *gluteus medius* and *minimus* are displaced backward and the *rectus femoris* forward the hip joint is exposed. By this approach no motor nerves are encountered. After being crossed by the *sartorius* the *rectus femoris* becomes superficial and forms a well rounded elevation in front of the thigh which is seen best when the knee is extended. It is safe to dissect along the lateral side of the *rectus femoris* since its nerve from the femoral plexus enters its medial side.

The *vastus lateralis* arises from the lateral part of the *linea aspera* and from its upward lateral continuation (the *gluteal tuberosity*) as well as its downward lateral continuation (the lateral epicondylar line). This muscle is best seen after the *rectus femoris* has been severed about its middle and dissected upward and downward. It forms the greater part of the fleshy muscle mass on the lateral side of the thigh and is recognized since its superficial stratum is a thin aponeurosis. It overlaps the *vastus intermedius* and is partly blended with that muscle. It gains attachment to the patella by means of the common tendon of insertion. The descending branch of the lateral femoral circumflex artery is accompanied by the nerve to the *vastus lateralis*. This then is the best guide to the anterior border of the muscle.

The *vastus medialis* is intimately connected with the *vastus intermedius* and difficulty may be found in separating the two. It originates from the medial lip of the *linea aspera* and from its medial upward continuation (the spiral line) and its medial downward continuation (the medial epicondylar line). Its lowermost fibers arise from the tendon of the *adductor magnus* muscle. The muscle covers the medial surface of the femur. Its lowest fibers which run almost horizontally form the fleshy mass which can be seen medial to the upper part of the patella in the living. It is inserted into the common tendon and into the medial border of the




FIG 650 The methods of measuring the length of the femur

patella and like the *vastus lateralis* gives off a fibrous expansion to the capsule of the knee joint.

The *vastus intermedius* arises from and covers the anterior and the lateral surfaces of the shaft of the femur. Although the *vastus medialis* covers the medial aspect of the femur, no muscle originates from this surface hence the bone is almost bare. It is a large fleshy muscle covered laterally and medially by the *vastus lateralis* and the *medialis* and is covered above by the *rectus femoris*. It is inserted into the deep aspect of the common tendon.

of the gracilis and the semitendinosus and inserts in front of them (Fig 664 B) It flexes abducts and laterally rotates the hip while flexing and medially rotating the knee joint In this way it brings about the position which the tailor assumes at work It forms the lateral boundary of the femoral triangle and the roof of the subsartorial (adductor) canal of Hunter

The *subsartorial (adductor) canal of Hunter* is an intermuscular canal which is situated on the medial aspect of the middle third of the thigh It extends from the apex of Scarpa's triangle to the opening in the adductor magnus muscle which has been referred to as the adductor hiatus (hiatus tendineus) (Fig 645) It is called Hunter's canal because it was here that John Hunter ligated the femoral artery for popliteal aneurysm The canal is bounded laterally by the vastus medialis, posteriorly, a floor is formed by the adductor longus proximally and the adductor magnus distally The roof of the canal is formed by the sartorius muscle with a strong layer of deep fascia, which lies under the sartorius This fascia has been called the subsartorial fascia (fascia vasto adductoria) It stretches from the fascial covering of the adductors to the fascial coverings of the vastus medialis Since the anterior surface of the adductor longus and the magnus are covered by the medial intermuscular septum this septum forms the floor of the canal The femoral vessels and the saphenous nerve traverse the canal Before incising the subsartorial fascia in order to expose the femoral artery one should endeavor to expose a fine subsartorial nerve plexus This lies immediately beneath the sartorius and is formed by branches of the obturator, the long saphenous and the internal cutaneous nerves Once the subsartorial fascia is incised, the most superficial structures in the canal will be found namely the long saphenous nerve which crosses the artery from without inward and gives off a small twig to the subsartorial plexus To the outer side of the long saphenous nerve

another nerve is found, the nerve to the vastus medialis muscle The femoral artery is situated directly beneath the long saphenous nerve The artery is separated from the floor of Hunter's canal by the femoral vein The vein is posterior to the artery in the upper part of the canal but posterolateral to it in the lower part The adductor longus muscle separates the femoral vessels from the profunda vessels (Fig 636) The femur and the vastus medialis are anterolateral to the femoral artery, and the sartorius is interomedial Near the lower end of the canal the femoral artery gives off the descending genicular artery (superior geniculate anastomotic magna) This vessel supplies a superficial branch which accompanies the saphenous nerve, an articular branch which takes part in the anastomosis around the knee joint and muscular branches

The *quadriceps femoris muscle* is composed of four parts the rectus femoris and the three vasti (medialis, lateralis and intermedius) (Figs 644 and 646) The rectus femoris arises from the ilium, and the three vasti arise from the shaft of the femur The rectus femoris is placed over the anterior aspect of the thigh and is quite distinct from the others, except at its insertion The vasti clothe the front and the sides of the shaft of the femur and are more or less blended with each other therefore, they are difficult to separate

The *rectus femoris* is the most superficial of the four and lies between the two vasti it covers the vastus intermedius Since it is the only portion of the quadriceps which arises from the innominate bone it acts as a flexor of the hip joint as well as an extensor of the knee The rectus arises by two heads a straight head from the anterior inferior iliac spine and a reflected head which arises from the impression on the ilium immediately above the acetabulum The latter is under cover of the gluteus minimus The two heads unite in front of the hip joint and the muscular belly which results passes down in front of

Where the common tendon plays across the front of the lower end of the femur a sesamoid bone (the patella) develops. The portion of the tendon distal to the patella is called the patellar ligament. The patella does not lie in front of the knee joint but

rather in front of the end of the femur (p 839)

It is well to keep the following picture in mind, so that the anterior thigh musculature may be quickly visualized.




FIG 652 The femur seen from behind. Muscle origins are shown in red, insertions in blue.

The quadriceps as a whole acts as a powerful extensor of the knee joint, but in addition to this the rectus femoris part of the quadriceps acts as a flexor of the hip joint

The *articularis genu* consists of a few of the deepest bundles of the vastus inter medius. It arises from the front of the femur and is inserted into the synovial membrane of the knee

Greater trochanter

- 1 Piriformis
- 2 Obturator int
- 3 Gemelli

Lat surface great trochanter

- 1 Gluteus minimus

Trochanteric line

- 1 Iliofemoral lig
- 2 Vastus lat
- 3 Vastus med

Lesser trochanter

- 1 Iliopsoas

Shaft

- 1 Vastus inter medius
- 2 Articularis genu

Adductor tubercle

- 1 Adductor magnus




FIG 651 The femur seen from in front. Muscle origins are shown in red insertions, in blue

of the biceps muscle crosses behind it from medial to lateral. It sends branches to the crista tendinis, the semimembranosus, the long head of the biceps and the adductor magnus via the medial popliteal nerve. The short head of the biceps muscle is supplied by the lateral popliteal nerve (Fig 649).

Perforating branches of the profunda femoris artery enter the posterior aspect of the thigh through openings found in the adductor magnus muscle. These vessels continue posteriorly to supply the vastus lateralis muscle and the hamstrings. The first perforating artery enters into the 'crucial anastomosis' and the third and the fourth perforating vessels anastomose with muscular ramus from the popliteal artery.

THE FEMUR

The femur or the thigh bone is the longest, the largest and the heaviest bone in the body, being about a quarter of the entire height of the individual. The femur is more liable to inequality than is the tibia or the fibula, hence the relative length of the lower limb is equal in only 10 per cent of individuals. The measurements of the length of the femur are taken from the anterosuperior iliac spine to either the adductor tubercle or the lower limits of the medial condyle (joint line) (Fig 650). The upper border of the patella also has been used as a distal point in measuring this length, but since it is movable it is not as accurate as the other two. The bone consists of proximal and distal ends and a shaft (Figs 651 and 652). The distal end is larger and close to its fellow femur, but the proximal ends are separated by the width of the pelvis. The shaft is thinnest in the middle and enlarges toward the ends, especially distally.

THE PROXIMAL END

The proximal end consists of a head, a neck, the greater and the lesser trochanters, the trochanteric fossa, the trochanteric line, the trochanteric crest and the quadrate tubercle.

The rounded head forms two thirds of a sphere, which is directed medially, upward and forward and is gripped firmly by the labrum acetabulare beyond its maximum diameter. Therefore, it is much more secure in its socket than is the head of the humerus which forms only one third of a sphere. In the erect posture the upper aspect of the head is pressed against the iliac part of the acetabular articular surface. The head is covered with hyaline cartilage and presents a depression or pit which gives attachment of the ligament of the head (ligamentum teres). This depression is located a little below and behind the central point.

The neck of the femur, about one and one half inches long, is triangular in shape; its apex supports the head of the femur and its base becomes continuous with the shaft. It is placed obliquely and unites the head to the shaft and the trochanters. It thickens toward each end, especially the shaft end, which it joins at an angle of about 125° in the adult, but is more obtuse in the child. This angle is known as the 'vertical neck shaft angle'. Since the neck of the femur is directed upward, inward and forward, another angulation results which is forward and is known as the 'declination angle'. It is normally of about 12° . Any alteration of these angles results in deformity and disability. In reality, the neck of the femur is the medially curved upper extremity of the shaft, but the presence of the greater trochanter hides this. It is separated from the shaft by the trochanteric line in front and the trochanteric crest behind. The trochanteric line presents a roughened edge produced by the attachment of the powerful iliofemoral ligament. Its upper end is at the front of the greater trochanter and its lower end is continuous with a faint ridge called the spiral line, which winds around the lesser trochanter to the back of the shaft. The trochanteric crest crosses the posterior aspect of the bone and continues into the lesser trochanter below. A small rounded

1 The "N" arrangement in which the sartorius makes up the oblique line with three muscles placed above it (iliopsoas, pectineus and adductor longus) and three muscles below it (vastus lateralis, rectus femoris and vastus medialis) (Fig. 644)

2 The adductor brevis is located in the interval between the pectineus and the adductor longus the adductor magnus is located in the interval between the longus and the gracilis the gracilis lies immediately behind and inserts deep to the sartorius (Fig. 635)

III. LEG (POSTERIOR) GROUP

The posterior aspect of the thigh derives its cutaneous nerve supply in the following way: medially it is supplied by the anterior cutaneous ramus of the femoral nerve, posteriorly, by the posterior femoral cutaneous nerve and, laterally, by the lateral femoral cutaneous nerve (Fig. 647)

The posterior thigh compartment contains the three hamstring muscles, namely the semimembranosus, the semitendinosus and the biceps femoris (Figs. 648 and 649). The compartment also contains the sciatic nerve and its two terminal branches, the tibial and the common peroneal. A hamstring muscle is one that arises from the ischial tuberosity and inserts into one of two bones of the leg; it is supplied by the tibial division of the sciatic nerve. Although it covers the femur, it has no attachments to it. The long head of the biceps femoris meets these prerequisites, but the short head does not; hence, this is an exception to the rule. It is interesting also to note that the adductor magnus muscle arises from the ischial tuberosity, inserts onto the tibia and is supplied by the tibial division of the sciatic nerve; therefore, it meets the three prerequisites of a hamstring and should be considered as such. For convenience sake, however, it should be discussed with the adductor group.

Since the *short head of the biceps femoris* does not meet these three prerequisites, it is not really a hamstring, but belongs to

the muscle plate of the gluteus maximus. It is supplied by the peroneal division of the sciatic nerve (Fig. 649).

The *long head of the biceps femoris* arises from the lower and the inner impression of the back part of the tuberosity of the ischium by means of a tendon common to it and the semitendinosus; it also arises from the lower part of the sacrotuberous ligament. Its two heads unite just above the knee joint to form a common tendon. As the muscle bundles pass downward and medially, they lie on the surface of the semimembranosus. The common tendon inserts into the lateral side of the head of the fibula and forms the upper and the lateral boundaries of the popliteal fossa. The common peroneal nerve descends along its medial border. In addition to its action as a flexor of the knee joint and extensor of the hip, it is a lateral rotator.

The *semitendinosus*, so named for the great length of its tendon of insertion, arises from the lower and the medial impression of the ischial tuberosity by a tendon common to it and the long head of the biceps femoris. It inserts into the upper part of the medial surface of the tibia just below the gracilis. It is a medial rotator of the tibia on the femur.

The *semimembranosus*, so named for its membranous tendon of origin, arises by this thick tendon from the upper and the outer impression on the ischial tuberosity above and lateral to that of the biceps femoris and the semitendinosus. It passes downward and medially, it first deep to the conjoined tendon of the biceps and the semitendinosus, and then is overlapped subsequently by the laterally placed muscles. It inserts on the medial condyle of the tibia.

Nerves and Vessels The sciatic nerve leaves the pelvis through the greater sciatic foramen, passes through the gluteal region and the upper part of the thigh. It ends at about the middle of the thigh by dividing into lateral and medial popliteal nerves. In the thigh the adductor magnus muscle is anterior to the nerve, and the long head

of the biceps muscle crosses behind it from medial to lateral. It sends branches to the semitendinosus, the semimembranosus, the long head of the biceps and the adductor magnus via the medial popliteal nerve. The short head of the biceps muscle is supplied by the lateral popliteal nerve (Fig. 649).

Perforating branches of the profunda femori artery enter the posterior aspect of the thigh through openings found in the adductor magnus muscle. These vessels continue posteriorly to supply the vastus lateralis muscle and the hamstring. The first perforating artery enters into the crucial anastomosis and the third and the fourth perforating vessels anastomose with muscular ramus from the popliteal artery.

THE FEMUR

The *femur* or the thigh bone is the longest, the largest and the heaviest bone in the body, being about a quarter of the entire height of the individual. The femur is more liable to inequality than is the tibia or the fibula; hence the relative length of the lower limb is equal in only 10 per cent of individuals. The measurements of the length of the femur are taken from the anterosuperior iliac spine to either the adductor tubercle or the lower limits of the medial condyle (joint line) (Fig. 650). The upper border of the patella also has been used as a distal point in measuring this length, but since it is movable it is not as accurate as the other two. The bone consists of proximal and distal ends and a shaft (Figs. 651 and 652). The distal end is larger and close to its fellow femur, but the proximal ends are separated by the width of the pelvis. The shaft is thinnest in the middle and enlarges toward the ends, especially distally.

THE PROXIMAL END

The *proximal end* consists of a head, a neck, the greater and the lesser trochanters, the trochanteric fossa, the trochanteric line, the trochanteric crest and the quadrate tubercle.

The rounded *head* forms two thirds of a sphere which is directed medially upward and forward and is gripped firmly by the labrum acetabulare beyond its maximum diameter. Therefore, it is much more secure in its socket than is the head of the humerus which forms only one third of a sphere. In the erect posture the upper aspect of the head is pressed against the iliac part of the acetabular articular surface. The head is covered with hyaline cartilage and presents a depression or pit which gives attachment of the ligament of the head (ligamentum teres); this depression is located a little below and behind the central point.

The *neck* of the femur, about one and one half inches long, is triangular in shape; its apex supports the head of the femur and its base becomes continuous with the shaft. It is placed obliquely and unites the head to the shaft and the trochanters. It thickens toward each end, especially the shaft end which it joins at an angle of about 125° in the adult but is more obtuse in the child. This angle is known as the 'vertical neck shaft angle'. Since the neck of the femur is directed upward inward and forward, another angulation results which is forward and is known as the 'declination angle'. It is normally of about 12° . Any alteration of these angles results in deformity and disability. In reality the neck of the femur is the medially curved upper extremity of the shaft but the presence of the greater trochanter hides this. It is separated from the shaft by the trochanteric line in front and the trochanteric crest behind. The *trochanteric line* presents a roughened edge produced by the attachment of the powerful iliofemoral ligament. Its upper end is at the front of the greater trochanter and its lower end is continuous with a faint ridge called the *spiral line* which winds around the lesser trochanter to the back of the shaft. The *trochanteric crest* crosses the posterior aspect of the bone and continues into the lesser trochanter below. A small rounded

tubercle (quadrate) about its middle gives insertion to the quadratus femoris muscle. The *trochanteric fossa* is small and is located at the junction of the posterior part of the neck and the medial side of the great trochanter. The obturator externus muscle inserts here.

the site of fusion of the trochanter and the shaft. If a chisel is driven along the upper border of the femoral neck it would remove the greater trochanter approximately at this rough fusion line.

The *lesser trochanter* is a blunt shaped pyramidal process which is directed back.




FIG. 653 The femoral epiphyseal lines

The *greater trochanter* is a fixed process which lies in line with the lateral aspect of the shaft and can be felt through the skin about one hand's breadth below the iliac crest. The muscles attached to it produce the rotatory movements of the thigh. It should be looked upon as the traction epiphysis of the gluteus medius and minimus as well as the piriformis, the obturator internus and externus, and the gemelli. When the gluteus medius contracts it draws this trochanter upward, medially and backward. Its upper and posterior borders are free and its highest point is located at its posterosuperior angle. The anterior and the lateral aspects of this trochanter would be continuous with the corresponding aspects of the shaft, except for the presence of a rough line which marks

ward and medially from the junction of the lower and the posterior part of the neck of the femur with the shaft, it is not palpable. It gives attachment to the tendon of the iliopsoas and has been considered the traction epiphysis for that structure. The *quadrate tubercle* is an ill defined protrusion which is situated about the center of the trochanteric crest, it gives insertion to the quadratus femoris muscle.

The *epiphyseal line* of the femoral head corresponds to its articular margin (Fig. 653). Anteriorly the capsule is attached to the spiral line; therefore, the whole neck is intracapsular. Posteriorly, the capsule is attached about a finger's breadth medial to the intertrochanteric crest, the neck being partly intracapsular and partly extracapsular. The metaphysis is entirely intra

capsular. Since the site of election for the occurrence of bone disease especially in the young is in the metaphysis, if the metaphysis is inside the joint capsule the disease is likely to invade the joint. On

medial. The lateral epicondyle is the eminence which is situated on the posterior part of the lateral surface of the lateral condyle. A *pit* for the origin of the popliteus muscle is below this epicondyle. The




FIG. 634. Ligation of the superficial femoral vein. (A) incision and exposure. (B) removal of thrombus by suction, (C) ligation and division.

the other hand if the disease is primarily in the joint it may affect the shaft of a bone if the metaphysis is partly within the affected joint.

THE DISTAL END

The *distal end* of the femur reveals lateral and medial condyles and epicondyles. A patellar surface, the intercondylar notch and line, the adductor tubercle and the pit and the groove for the popliteus muscle.

The *condyles* make up nearly the entire distal end and give it an irregular cuboidal shape. They coalesce in front but are separated behind by the deep intercondylar notch. The top of the tibia and the semilunar cartilages of the knee joint articulate with the posterior surfaces of the condyles when the knee is bent but with their inferior surfaces when the knee is straight.

The *lateral condyle* is broader than the

groove for the tendon of the popliteus muscle passes upward and backward from this pit close to the articular margin.

The *medial condyle* is farther from the side of the shaft than is the lateral. It is narrower and more curved. When the shaft is held vertically it projects to a lower level than the lateral but in the natural oblique position of the bone the lower surfaces of both condyles are in the same plane. Immediately behind and above its center its rough medial surface presents the *medial epicondyle* to which the medial ligament of the knee is attached. Immediately above this is the *adductor tubercle* for the insertion of the strong tendon of the adductor magnus.

The *intercondylar notch* is bounded by the opposed surfaces of the condyles and separates them behind and below. This notch is occupied by the cruciate ligament.




FIG 655 Approach to the lesser trochanter of the femur

Its floor slopes upward and backward to a horizontal ridge called the *intercondylar line* which separates it from the popliteal surface of the shaft.

The *patellar (trochlear) surface* is convex from above downward and concave from side to side. It is situated on the anterior aspect of the lower extremity and extends farther upward on the lateral condyle than on the medial. It is separated from the articular surfaces of the tibia by grooves on either side in which the semilunar cartilages of the knee rest when the joint is fully extended. The patella articulates with it when the knee is straight but is drawn off when the knee is bent. In the latter position its margin can be felt through the tendon of the quadriceps.

The sides of the condyles and the adductor tubercles are quite easily felt in the living person.

The *epiphysis at the lower end of the femur* is represented by an irregular horizontal line at the level of the upper limit of the articular surface in front and behind, which crosses the middle of the ad-

ductor tubercle (Fig 653). The capsule may be outlined posteriorly to the articular margin, and laterally and medially about two inches proximal to the articular margin. Therefore, the metaphysis is intra capsular only in front.

THE SHAFT

The *shaft* or body of the femur is bowed slightly forward. Its middle two thirds are circular on cross section, but its upper and lower extremities are oblong, the lower border being the larger. In the erect posture the shaft is oblique, since the distal ends of the femora are in contact with each other, but the proximal ends are separated by the pelvis and by the necks of the femora. Each shaft in its middle third reveals anterior, medial and lateral surfaces which are separated by rather ill defined lateral and medial borders, a well marked posterior border known as the *linea aspera* is easily discernible.

The *linea aspera* is a broad rough line which stands out boldly from the back of the middle two thirds of the femoral shaft. It bifurcates both above and below into divergent lines. The upper lines are the *spiral line* and the *gluteal tuberosity*; the lower ones are the *medial* and the *lateral epicondylar lines*. The *spiral line* passes upward and medially and becomes continuous with the *trochanteric line*; the *gluteal tuberosity* ascends to the side of the greater trochanter where it becomes continuous with the *epiphyseal line*. The lesser trochanter projects from a triangle bounded by these two lines. The *medial* and the *lateral epicondylar lines* descend from the *linea aspera* to the epicondyle and give rise to the boundary of a flat triangular area which is limited below by the *intercondylar line*. This area is known as the *popliteal surface*. The *medial epicondylar line* abruptly turns so that the adductor tubercle which is placed about one half inch above the medial epicondyle, is easily palpable. The *medial aspect of the shaft* is devoid of muscular attachments.




FIG 656 The anterior approach to the shaft of the femur

The Attachments to the Femur (Figs 651 and 652)

To the head the ligamentum teres

To the neck the capsule of the hip joint

To the trochanteric line the iliofemoral ligament the vastus lateralis and the medialis

To the trochanteric fossa the obturator externus

To the greater trochanter to the medial surface the obturator internus the gemelli and the piriformis to the upper border the piriformis to the anterior surface the gluteus medius

To the quadrate tubercle the quadratus femoris

To the lesser trochanter the iliopectus

To the gluteal tuberosity the gluteus maximus and the vastus lateralis

To the spiral line the vastus medialis




FIG 657 The posterior approach to the shaft of the femur

To the area between the gluteal tuberosity and the spiral line from lateral to medial the adductor magnus the adductor brevis the pectineus and the iliopectus

To the linea aspera, lateral to medial the vastus lateralis and the intermedius from the lateral lip the lateral intermuscular septum and the short head of the biceps. From the medial lip, the adductor magnus the brevis and the longus the medial intermuscular septum and the vastus medialis

From the lateral supracondylar line the vastus intermedius the lateral septum the short head of the biceps the plantaris and the lateral head of the gastrocnemius

From the medial supracondylar line the adductor magnus, the medial septum the vastus medialis and the medial head of the gastrocnemius

From the shaft (anterior and lateral surfaces) the vastus intermedius and the articularis genu




FIG 655 Approach to the lesser trochanter of the femur

Its floor slopes upward and backward to a horizontal ridge called the *intercondylar line* which separates it from the popliteal surface of the shaft

The *patellar (trochlear) surface* is convex from above downward and concave from side to side it is situated on the anterior aspect of the lower extremity and extends farther upward on the lateral condyle than on the medial It is separated from the articular surfaces of the tibia by grooves on either side in which the semilunar cartilages of the knee rest when the joint is fully extended The patella articulates with it when the knee is straight but is drawn off when the knee is bent in the latter position its margin can be felt through the tendon of the quadriceps

The sides of the condyles and the adductor tubercles are quite easily felt in the living person

The *epiphysis at the lower end of the femur* is represented by an irregular horizontal line at the level of the upper limit of the articular surface in front and behind, which crosses the middle of the ad-

ductor tubercle (Fig 653) The capsule may be outlined posteriorly to the articular margin, and laterally and medially about two inches proximal to the articular margin Therefore, the metaphysis is intracapsular only in front

THE SHAFT

The *shaft* or body of the femur is bowed slightly forward its middle two thirds are circular on cross section, but its upper and lower extremities are oblong, the lower border being the larger In the erect posture the shaft is oblique, since the distal ends of the femora are in contact with each other but the proximal ends are separated by the pelvis and by the necks of the femora Each shaft in its middle third reveals anterior, medial and lateral surfaces which are separated by rather ill defined lateral and medial borders, a well marked posterior border known as the *linea aspera* is easily discernible

The *linea aspera* is a broad rough line which stands out boldly from the back of the middle two thirds of the femoral shaft It bifurcates both above and below into divergent lines The upper lines are the *spiral line* and the *gluteal tuberosity* the lower ones are the *medial* and the *lateral epicondylar lines* The *spiral line* passes upward and medially and becomes continuous with the *trochanteric line* the *gluteal tuberosity* ascends to the side of the greater trochanter where it becomes continuous with the *epiphyseal line* The lesser trochanter projects from a triangle bounded by these two lines The *medial* and the *lateral epicondylar lines* descend from the *linea aspera* to the epicondyle and give rise to the boundary of a flat triangular area which is limited below by the *intercondylar line* This area is known as the *popliteal surface* The *medial epicondylar line* abruptly turns so that the adductor tubercle, which is placed about one half inch above the medial epicondyle, is easily palpable The medial aspect of the shaft is devoid of muscular attachments

and this will result in an excellent view of the latter

APPROACHES TO THE SHAFT OF THE FEMUR

The shaft of the femur may be surgically approached anteriorly, posteriorly, laterally or medially

incision which is placed over the posterior aspect of the thigh in the line of the shaft of the femur (Fig 657) The posterior femoral cutaneous nerve should be avoided The long head of the biceps femoris muscle with the posterior femoral cutaneous nerve is retracted laterally the semimembranosus and the semitendinosus muscles




FIG 660 The medial approach to the lower end of the shaft of the femur

The anterior approach to the shaft of the femur is accomplished through an incision which is made over the greater extent of the femoral shaft in a line situated between the anterosuperior iliac spine and the middle of the patella (Fig 656) The rectus femoris and the vastus lateralis are separated along the intermuscular septum The vastus intermedius is incised in the line of its fibers until the femur is reached Subperiosteal dissection exposes the anterior and the lateral aspects of the femur

The posterior approach to the shaft of the femur is accomplished through a long

are retracted medially The sciatic nerve and the popliteal artery and vein are now identified The sciatic nerve is retracted laterally and the popliteal vessels medially so that the adductor magnus muscle and the short head of the biceps femoris muscle can be stripped subperiosteally from the femur it is necessary to ligate the perforating arteries to accomplish this The posterior two thirds of the lower aspect of the femoral shaft is thereby exposed

The lateral approach to the shaft of the femur commences with a longitudinal skin




FIG 638 The lateral approach to the shaft of the femur

From the lateral condyle the anterior cruciate ligament of the knee the popliteus, and the lateral ligaments of the knee

From the medial condyle the posterior cruciate ligament and the medial ligament of the knee

The fascia lata attaches to both condyles

SURGICAL CONSIDERATIONS

FEMORAL VEIN LIGATION AND THROMBECTOMY (Fig 634)

Recently Allen Linton and others have advocated interruption of the superficial femoral vein and removal of thrombus. This is done as a prevention for pulmonary embolism. A skin incision is made along the course of the pulsating femoral artery on




FIG 639 Cross sections of the lateral and the medial approaches to the shaft of the femur (A) in the upper third, (B) in the lower third

the involved side (Fig 634 A). The artery overlies the vein in this region, and when the former is retracted laterally the superficial femoral vein is exposed. After identifying the deep femoral vein the superficial femoral vein is incised and the thrombus is removed. It is then ligated and divided (Figs 634 B and 634 C).

APPROACH TO THE LESSER TROCHANTER OF THE FEMUR (Fig 635)

Exposure of the lesser trochanter of the femur is accomplished through an incision which extends from the upper end of the trochanter midway between it and the mid sacral line downward for about two or three inches (Fig 635). This incision is deepened through the thickened fatty layer until the deep fascia is exposed. The gluteus maximus is incised in its thickened portion. The sciatic nerve is retracted medially and the quadratus femoris muscle is either divided or retracted upward. The iliopsoas tendon can be stripped off of the lesser trochanter,

The Knee

The region which constitutes the knee is bounded above by an imaginary line drawn around the thigh at a level of approximately three inches above the base of the patella. Its inferior extent is at the tibial tuberosity.

THE POPLITEAL (POSTERIOR) REGION

This region corresponds to the posterior aspect of the knee (Fig. 661). The popliteal fossa or space is lozenge shaped and has a floor, a roof and lateral boundaries. It consists of an upper (femoral) and a lower (tibial) triangle.

The roof of the space is formed by the deep fascia which is composed of circularly arranged fibers acting as a restraining or retinacular ligament for the hamstrings. It is pierced near its center by the small saphenous vein which passes between the two heads of the gastrocnemius muscle. Deep to it is the cutaneous branch of the medial popliteal nerve (tibial). A transverse incision made through this deep fascia will require little or no suturing, since it approximates itself; however, a longitudinal incision will gape.

The floor of the fossa is formed by the lower end of the femur, the posterior part of the capsule of the knee joint and the popliteus muscle with its strong fascia. The *popliteus fascia* is an expansion from the tendon of the semimembranosus muscle which passes downward and outward and covers the *popliteus muscle* (Figs. 661C and 664B, 664C). It attaches to the popliteal line of the tibia. The popliteal vessels lie on it and end at its lower border. The popliteus muscle arises within the capsule

of the knee joint from the lateral aspect of the lateral condyle of the femur and is inserted into the posterior aspect of the tibia above the popliteal (soleal) line. Its tendon of origin passes downward and backward, separating the lateral semilunar cartilage from the lateral ligament of the joint. It emerges through the inferolateral aspect of the posterior part of the capsular ligament. It is a flexor of the leg and also acts as a medial rotator of the tibia when the knee is flexed. The medial (tibial) popliteal nerve supplies it.

The *femoral (upper) triangle* has the semimembranosus overlaid by the semitendinosus on its medial side and the biceps femoris muscle on its lateral side (Fig. 661A). The *tibial (lower) triangle* is smaller and its sides are formed by the two heads of the gastrocnemius muscle together with the very variable plantaris muscle which lies laterally.

NERVES AND VESSELS

The contents of the popliteal fossa are arranged mainly as a nerve, vein and artery.

- 1 The lateral and the medial popliteal nerves and their branches
- 2 The popliteal vein and its tributaries
- 3 The popliteal artery and its branches
- 4 The posterior cutaneous nerve
- 5 Fat and lymph glands

The Popliteal Nerves. The tibial and the common peroneal nerves are the terminal branches of the sciatic nerve.

The *tibial (internal or medial popliteal) nerve* enters the fossa at the upper angle lateral to the popliteal vessels, runs a straight course to the lower angle of the space and is superficial to the vessels. It

incision which is placed along a line extending from the greater trochanter to the external femoral condyle (Figs 658 and 659). The iliotibial tract, the vastus lateralis and the vastus intermedius muscles are divided in the direction of their fibers. The exposed periosteum is incised longitudinally, freed anteriorly and posteriorly thereby exposing the lateral aspect of the shaft of the femur.

The *medial approach* for exposure of the lower half of the femoral shaft begins with a skin incision which is placed along the adductor tendon and extends well above

and below the adductor tubercle (Fig 660). The deep fascia is freed, and one attempts to avoid entering the synovial membrane of the knee joint. The sartorius muscle is retracted posteriorly and the tendon of the adductor magnus muscle is identified. The saphenous nerve is protected as it courses along the undersurface of the sartorius muscle. The large neurovascular bundle is retracted posteriorly. The adductor magnus tendon and the vastus medialis muscle are retracted anteriorly. At this point the posterior surface of the femur, as it lies in the popliteal space, is exposed.

the back of the leg and in the lower third is joined by the sural communicating branch from the lateral (common peroneal) popliteal nerve (Fig. 661A). The sural nerve travels in company with the short saphenous vein. Three small articular branches usually are present; they supply the knee joint. The close relationship between the tibial nerve and the popliteal vessels explains nerve involvement and pain in popliteal aneurysm.

The *common peroneal (lateral or external popliteal) nerve* generally separates from the sciatic at about the middle of the thigh, enters the popliteal fossa from the lateral side and passes downward and laterally, closely associated with and appearing from behind the biceps femoris. It follows the biceps tendon to its insertion and leaves the popliteal fossa between that tendon and the lateral head of the gastrocnemius. This relationship is important and must be kept in mind when a biceps tenotomy is contemplated. The nerve continues downward behind the head of the fibula and winds around the lateral aspect of the fibular neck to pierce the origin of the peroneus longus muscle. It ends by dividing into the superficial (musculocutaneous) and the deep (anterior tibial) peroneal nerves. The common peroneal nerve gives off no muscular branches but does give a lateral cutaneous nerve of the calf (lateral sural), a sural communicating nerve (anastomotic peroneal) and usually three genicular branches which accompany the genicular vessels and supply the ligaments and the synovial membranes of the knee joint.

The Popliteal Vessels The *popliteal vein* is formed by the junction of the anterior and the posterior tibial veins at the lower border of the popliteus muscle (Fig. 664A). It ascends through the popliteal space to the aperture in the adductor magnus muscle, where it becomes the femoral vein. In its trip through this space it lies superficial to the artery, but crosses it from medial to lateral. The popliteal vein and

artery are bound together by a fascial tube similar to the arrangement in the region of the femoral artery and vein; hence, neither can be displaced without interfering with the other.

The *small saphenous vein (par a)* passes over the calf of the leg, superficial to the enveloping fascia but pierces the deep fascia in the lower part of the popliteal space. It divides into two branches: one enters the popliteal vein, and the other communicates with the great saphenous vein.

The *popliteal artery* is the continuation of the femoral artery; it commences at the opening in the adductor magnus. It passes downward between the condyles of the femur and leaves the fossa at its distal angle to end at the distal border of the popliteus muscle where it divides into the anterior and the posterior tibial arteries (Fig. 662). It appears to run laterally as well as downward because of the inclination of the long axis of the femur. In addition to its terminal branches, the artery gives three paired branches which arise at different levels. They are:

- 1 The *superior genicular arteries* (lateral and medial), which originate at the level of the femoral condyle and wind around the femur proximal to these condyles. They are in close contact with the bone and anastomose anteriorly (Fig. 662).

- 2 The *middle genicular arteries* enter the knee joint through the posterior ligament and are chiefly muscular and articular, being distributed to the gastrocnemius and the intracapsular structures.

- 3 The *inferior genicular arteries* (lateral and medial) wind around the front of the knee and pass under cover of the tibial and the fibular collateral ligaments. They anastomose with each other deep to the patellar ligament; they take place also in the anastomosis around the knee joint. Since no branches are given off in the upper part of the popliteal artery, this portion is most accessible for ligation.

The *anterior (deep) relations* of the artery are, the popliteal surface of the femur,




FIG 661 The popliteal fossa (A) the upper and the lower triangles, (B) the contents (C) the deeper structures

lies immediately beneath the deep fascia. In its course through the space it crosses superficial to the vessels from lateral to medial. It supplies the muscles of the space, namely, the lateral and the medial heads of the gastrocnemius, the soleus, the plantaris and the popliteus. Only one of these, the medial head of the gastrocnemius, lies

medial to the nerve. Because of this anatomic fact it is safer to dissect on the medial side where the nerve has only one branch. The sural nerve is a cutaneous branch which arises from the tibial nerve and descends on the surface of the gastrocnemius muscle. It supplies small branches to the integument of the calf and




FIG. 663 The knee joint (A) the knee joint opened and seen from in front (B) seen from the medial side (C) the arrow shows the relations between the septum and the perforation

the lateral condylar articulations and the patellar articulation. The condylar articulations are subdivided further into upper and lower parts by the medial and the lateral menisci (semilunar fibrocartilages).

In all positions of this joint the patella is in contact with the femur, and the femur with the tibia. These bones do not interlock and their areas of contact are large, the ligaments and the surrounding muscles are strong. Therefore, dislocation of this joint is uncommon.

THE PATELLA

The *patella* is a small sesamoid bone in the tendon of the quadriceps femoris. It is roughly triangular in shape, the inferior angle represents the apex, and the upper border represents the base. The lateral and

the medial borders are rounded. Its anterior surface is easily felt through the skin from which it is partly separated by the subcutaneous prepatellar bursa. The femoral articular surface is divided by a vertical ridge into a larger lateral and a smaller medial area. Below the articular surface the bone is roughened and is nonarticular, and the lower half of this area covers the posterior aspect of the apex. This bone usually begins to ossify between the third and the fifth years, and the process is usually completed by puberty.

If one stands erect with the feet together and the toes pointed forward (the anatomic position) it will be noted that the ball of the big toes, the medial malleoli and the knees of the two sides touch each other; the tibiae are parallel but the femora are

the oblique posterior ligament of the knee joint and the popliteus muscle covered by its fascia. A rather thick fat pad separates the artery from the femur but the vessel lies in direct contact with the oblique pos

take part in this anastomosis are the two lateral and the medial genicular branches of the popliteal, the descending branch of the lateral femoral circumflex artery and the anterior recurrent tibial artery. Super




FIG. 662 The anastomosis around the knee joint

terior ligament of the knee joint. Posteriorly the artery is separated from the fascial roof of the popliteal space by its accompanying veins and the medial popliteal nerve.

The lymph glands of the popliteal space lie under the deep fascia. They receive the lymph from the skin of the outer side of the leg and the foot and from the deep structures of the foot via the lymph vessels which accompany the anterior and the posterior tibial vessels. They also receive lymph from the knee joint. All the efferent vessels from the glands pass with the popliteal vein and then with the femoral vein to the deep inguinal lymph glands. It should be noted that the corresponding glands in the upper limb, namely the supra-trochlear, lie superficial to the deep fascia.

A rich vascular anastomosis exists around and above the patella and on the ends of the femur and the tibia in the region of the knee joint (Fig. 662). The arteries which

facially these vessels are distributed between the fascia and the skin; the deeper vessels lie on the lower end of the femur and the upper end of the tibia, supplying the soft tissues around these structures and sending branches into the interior of the knee joint.

THE KNEE JOINTS

The knee joints constitute a synovial joint of the hinged variety. It is the largest and the most complicated joint in the body (Figs. 663, 664 and 665). Three bones take part in it: the femur, the tibia and the patella. In the human the fibula is entirely excluded from it. Originally in primitive life there were three joint cavities in this location, which now have merged into one. One is situated between the medial condyle of the femur and the tibia, one between the lateral condyle of the femur and the tibia, and one between the patella and the femur. These may be referred to as the medial and

vasti lateralis and the medialis, the tendon of the vastus intermedius, and the synovial joint capsule. If the quadriceps is relaxed, as when the heel is placed on a chair, the patella may be moved medially and laterally, and the posterior articular surface may be palpated. As the position is changed from extension to one of flexion, one can feel the patella glide laterally onto the under aspect of the lateral condyle of the femur, thus leaving the trochlea and the entire under aspect of the medial femoral condyle exposed, except for a tiny strip which bounds the medial border of the intercondylar notch. This tiny strip articulates with a vertical facet on the medial part of the posterior surface of the patella.

LIGAMENTS AND CARTILAGES

Like other movable joints, the knee has a fibular as well as a synovial capsule. The capsular ligament is thin wide and membranous at the back but thicker and shorter at the sides. It is absent in front where it is replaced by the patella the ligamentum patellae below the patella and the tendon of the quadriceps above it. The femoral attachments of the capsular ligament are to the sides of the condyles about a quarter of an inch from the articular margin, to the back of the femur along the intercondylar line and immediately above the articular margin of the condyles. Its tibial attachments are to the posterior surfaces and the sides of the condyles about a quarter of an inch below the articular margin also to the anterior surfaces of the condyles along the oblique lines that begin near the articular margins of the sides and pass to the sides of the tubercle of the tibia. The capsule is strengthened by expansions from surrounding muscles which for the most part are closely attached to it. On the antero-lateral aspect however there is a definite interval which is occupied by fat, vessels and nerves. The heads of the gastrocnemius and the plantaris overlie the posterior part of the capsule opposite the femoral con-

dyles. The medial head is separated from it by a bursa, the lateral head and the plantaris are partly attached to it, the popliteus, after it emerges through the capsule, derives some fleshy fibers of origin from it. At the back of the medial femoral condyle there is usually a hole in the ligament through which the synovial membrane becomes continuous with the bursa under the medial head of the gastrocnemius (Fig 663C). The tendon of the popliteus perforates the capsular ligament opposite the lateral condyle of the tibia. The ligament is also perforated by articular vessels and nerves. The capsule is overlaid by and incorporated with the tendinous expansions of the lateral and the medial vasti (Fig 664).

The *patellar ligament* (*ligamentum patellae*) is a strong fixed band about three inches long and one inch wide. It is attached above to the lower border of the patella and below to the tubercle of the tibia; this attachment extends about one half inch farther down on the inner side (Fig 666A). The ligament constitutes the insertion of the quadriceps extensor into the tibia. It is separated from the skin by a bursa. Its superficial fibers are directly continuous over the patellar surface with the central part of the common tendon of the quadriceps femoris; the deep surface is separated from the synovial membrane by loose fatty tissue called the *infrapatellar pad of fat* (Fig 663). A bursa also separates it from the upper part of the tibia. This bursa is crescentic and when enlarged or inflamed has extensions which pass upward along the sides of the ligament.

The *lateral ligament of the knee* (*fibular collateral ligament*) is a rounded cordlike band which is approximately two inches long. It extends from the lateral epicondyle of the femur above to the head of the fibula below (Figs 664 and 665). Although its upper part is fused with the underlying part of the capsule, most of it is separated from the capsule by fatty tissue in which the inferior lateral geniculate vessels and nerves run. As the ligament crosses the lat-




FIG 664 The right knee joint showing the ligaments the capsule the synovial membrane and the relations. The capsule is colored green the synovial membrane, blue

not. The latter are set obliquely although in contact at the knee joint they are separated above by the width of the pelvis. The rectus femoris and the vastus intermedius are attached to the upper border (base) of the patella, when they contract they pull obliquely upward. The vastus medialis and the vastus lateralis are continuous with each other at their patellar attachments and occupy the space between the rectus femoris and the vastus intermedius. The vastus

medialis is attached to the upper two thirds of the medial border of the patella and only slightly to its upper border. The vastus lateralis is attached to the whole length of the upper border and only slightly to the lateral border. The vastus medialis draws the patella medially and the vastus lateralis pulls it upward but not laterally. A transverse incision above the patella will incise successively the skin, the fat, the fascia lata, the rectus tendon, the tendons of the

vastus lateralis and the medialis the tendon of the vastus intermedius and the synovial joint capsule. If the quadriceps is relaxed as when the heel is placed on a chair the patella may be moved medially and laterally, and the posterior articular surface may be palpated. As the position is changed from extension to one of flexion one can feel the patella glide laterally onto the under aspect of the lateral condyle of the femur thus leaving the trochlea and the entire under aspect of the medial femoral condyle exposed except for a tiny strip which bounds the medial border of the intercondylar notch. This tiny strip articulates with a vertical facet on the medial part of the posterior surface of the patella.

LIGAMENTS AND CARTILAGES

Like other movable joints the knee has a fibrous as well as a synovial capsule. The *capsular ligament* is thin wide and membranous at the back but thicker and shorter at the sides. It is absent in front where it is replaced by the patella the ligamentum patellae below the patella and the tendon of the quadriceps above it. The femoral attachments of the capsular ligament are to the sides of the condyles about a quarter of an inch from the articular margin to the back of the femur along the intercondylar line and immediately above the articular margin of the condyles. Its tibial attachments are to the posterior surfaces and the sides of the condyles about a quarter of an inch below the articular margin also to the anterior surfaces of the condyles along the oblique lines that begin near the articular margins of the sides and pass to the sides of the tubercle of the tibia. The capsule is strengthened by expansions from surrounding muscles, which for the most part are closely attached to it. On the antero-lateral aspect however there is a definite interval which is occupied by fat, vessels and nerves. The heads of the gastrocnemius and the plantaris overlie the posterior part of the capsule opposite the femoral con-

dyles. The medial head is separated from it by a bursa the lateral head and the plantaris are partly attached to it the popliteus after it emerges through the capsule, derives some fleshy fibers of origin from it. At the back of the medial femoral condyle there is usually a hole in the ligament through which the synovial membrane becomes continuous with the bursa under the medial head of the gastrocnemius (Fig 663C). The tendon of the popliteus perforates the capsular ligament opposite the lateral condyle of the tibia. The ligament is also perforated by articular vessels and nerves. The capsule is overlaid by and incorporated with the tendinous expansions of the lateral and the medial vasti (Fig 664).

The *patellar ligament* (*ligamentum patellae*) is a strong fixed band about three inches long and one inch wide. It is attached above to the lower border of the patella and below to the tubercle of the tibia this attachment extends about one half inch farther down on the inner side (Fig 666A). The ligament constitutes the insertion of the quadriceps extensor into the tibia. It is separated from the skin by a bursa. Its superficial fibers are directly continuous over the patellar surface with the central part of the common tendon of the quadriceps femoris, the deep surface is separated from the synovial membrane by loose fatty tissue called the *infrapatellar pad of fat* (Fig 663). A bursa also separates it from the upper part of the tibia. This bursa is crescentic and when enlarged or inflamed has extensions which pass upward along the sides of the ligament.

The *lateral ligament of the knee* (*fibular collateral ligament*) is a rounded cordlike band which is approximately two inches long. It extends from the lateral epicondyle of the femur above to the head of the fibula below (Figs 664 and 665). Although its upper part is fused with the underlying part of the capsule, most of it is separated from the capsule by fatty tissue in which the inferior lateral geniculate vessels and nerves run. As the ligament crosses the lat-




FIG 664 The right knee joint showing the ligaments, the capsule the synovial membrane and the relations. The capsule is colored green, the synovial membrane, blue

not. The latter are set obliquely, although in contact at the knee joint they are separated above by the width of the pelvis. The rectus femoris and the vastus intermedius are attached to the upper border (base) of the patella. When they contract they pull obliquely upward. The vastus medialis and the vastus lateralis are continuous with each other at their patellar attachments, and occupy the space between the rectus femoris and the vastus intermedius. The vastus

medialis is attached to the upper two thirds of the medial border of the patella and only slightly to its upper border. The vastus lateralis is attached to the whole length of the upper border and only slightly to the lateral border. The vastus medialis draws the patella medially, and the vastus lateralis pulls it upward but not laterally. A transverse incision above the patella will incise successively the skin, the fat, the fascia lata, the rectus tendon, the tendons of the

tends forward and under the ligament to gain its insertion into the medial condyle of the tibia.

The two collateral ligaments are strong structures and prevent lateral movements at the knee joint. If they are stretched or torn the integrity of the joint usually is lost.

The three ligamentous extensions of the semimembranosus are the oblique popliteal ligament, the popliteus fascia and the deep fascia of the inner side of the leg. The oblique popliteal ligament (oblique posterior ligament) strengthens the capsule posteriorly (Fig. 664D). It passes upward and outward from the semimembranosus tendon and blends with the capsule. The popliteal vessels lie upon it; it is perforated by the artery, geniculate artery. The popliteus fascia is the second expansion from this tendon and passes downward and outward to cover the popliteus muscle. It gains attachment to the popliteal line of the tibia. The popliteal vessels lie upon it and end at its lower border. The third expansion continues as the deep fascia of the inner side of the leg.

The cruciate ligaments of the knee are two powerful cordlike structures which are so named because they cross each other like the limbs of the letter 'X' (Figs. 663, 664 and 665). The crucial arrangement is seen whether viewed from the front, the sides or the back. These ligaments have been designed to prevent forward and backward displacements of the tibia on the femur. It requires great violence to tear one of them but when torn great disability is caused by the forward and backward gliding of the tibia upon the femur. These ligaments are covered in front and at the sides by synovial membrane and are related posteriorly to the capsular ligament from which they are separated by fat. The anterior cruciate ligament extends upward, backward and laterally from the anterior part of the intercondylar area of the tibia to the posterior part of the medial surface of the lateral condyle of the femur. It is tense in extension and prevents

backward sliding of the femur and forward displacement of the tibia. When the knee is flexed its two points of attachment are approximated and the ligament is relaxed. It prevents hyperextension of the knee joint. The posterior cruciate ligament is tense in flexion; it passes upward, forward and medially from the posterior part of the intercondylar area to the anterior part of the lateral surface of the medial condyle of the femur. It prevents forward gliding of the femur and backward displacement of the tibia during flexion. The anterior ligament passes backward and outward but the posterior passes inward and forward. When the knee joint is opened from the inner side, the posterior cruciate ligament is seen first.

The semilunar cartilages (menisci) are two crescentic plates of fibrocartilage which lie on the circumferential portion of the articular surfaces of the tibia (Figs. 663, 664 and 665). They deepen these areas for the reception of the condyles of the femur since they are elastic, they act as buffers which diminish shocks passing up the limbs. Their distal surfaces are flat, but the proximal are concave for reception of the femoral condyles. In the fetus, both surfaces of the menisci are covered with synovial membrane which helps to attach their peripheral margins to the tibia, but as the result of continued pressure they are devoid of this synovial covering in the adult. Each cartilage has two fibrous extremities which are called horns; these are attached to the intercondylar area on the proximal surface of the tibia. The cartilages are thick toward the circumference of the joint; the lateral cartilage is a little thicker than the medial. Both thin out toward the center where they end as a fine, free, concave edge. They do not cover the entire extent of the condylar surfaces of the tibia.

The lateral semilunar cartilage is nearly circular in outline, and its horns are fixed to the tibia close together. The anterior horn attaches to the front of the intercondylar eminence behind the anterior cruciate ligament with which it blends. The posterior




FIG 665 The ligaments and the cartilages of the right knee joint

eral aspect of the knee joint the tendon of the popliteus muscle intervenes between it and the lateral semilunar cartilage (meniscus). The biceps tendon which is superficial to the lower part of the ligament is split in two by it.

The medial ligament of the knee (*tibial collateral ligament*) is broad and straplike and, unlike the lateral is closely applied to the bone. It extends from the medial epi-

condyle of the femur above to the upper fourth of the shaft of the tibia below. Opposite the interval between the femur and the tibia it is closely fused with the capsular ligament (Fig 664A). It is attached to the medial meniscus. Three tendons cross it: those of the sartorius, the gracilis and the semitendinosus (Fig 664B). A bursa separates these from the ligament. The tendon of the semimembranosus ex-

ter is forward and under the ligament to gain its insertion into the medial condyle of the tibia.

The two collateral ligaments are strong structures and prevent lateral movements at the knee joint. If they are stretched or torn the integrity of the joint usually is lost.

The *three ligamentous extensions of the crumembrianus* are the oblique popliteal ligament, the popliteus fascia and the deep fascia of the inner side of the leg. The *oblique popliteal ligament* (oblique posterior ligament) strengthens the capsule posteriorly (Fig. 661D). It passes upward and outward from the crumembrianus tendon and blends with the capsule. The popliteal vessels lie upon it; it is perforated by the *vngos geniculate artery*. The popliteus fascia is the second expansion from this tendon and passes downward and outward to cover the popliteus muscle. It gains attachment to the popliteal line of the tibia. The popliteal vessels lie upon it and end at its lower border. The third expansion continues as the deep fascia of the inner side of the leg.

The *cruciate ligaments of the knee* are two powerful cordlike structures which are so named because they cross each other like the limbs of the letter X (Figs. 663, 664 and 665). The crucial arrangement is seen whether viewed from the front, the sides or the back. These ligaments have been designed to prevent forward and backward displacements of the tibia on the femur. It requires great violence to tear one of them but when torn great disability is caused by the forward and backward gliding of the tibia upon the femur. The *cruciate ligaments* are covered in front and at the sides by synovial membrane and are related posteriorly to the capsular ligament from which they are separated by fat. The *anterior cruciate ligament* extends upward, backward and laterally from the anterior part of the intercondylar area of the tibia to the posterior part of the medial surface of the lateral condyle of the femur. It is tense in extension and prevents

backward sliding of the femur and forward displacement of the tibia. When the knee is flexed its two points of attachment are approximated and the ligament is relaxed. It prevents hyperextension of the knee joint.

The *posterior cruciate ligament* is tense in flexion; it passes upward, forward and medially from the posterior part of the intercondylar area to the anterior part of the lateral surface of the medial condyle of the femur. It prevents forward gliding of the femur and backward displacement of the tibia during flexion. The anterior ligament passes backward and outward but the posterior passes inward and forward. When the knee joint is opened from the inner side the posterior cruciate ligament is seen first.

The *semilunar cartilages (menisci)* are two crescentic plates of fibrocartilage which lie on the circumferential portion of the articular surfaces of the tibia (Figs. 663, 664 and 665). They deepen these areas for the reception of the condyles of the femur since they are elastic they act as buffers which diminish shocks passing up the limbs. Their distal surfaces are flat but the proximal are concave for reception of the femoral condyles. In the fetus both surfaces of the menisci are covered with synovial membrane which helps to attach their peripheral margins to the tibia but as the result of continued pressure they are devoid of this synovial covering in the adult. Each cartilage has two fibrous extremities which are called horns; these are attached to the intercondylar area on the proximal surface of the tibia. The cartilages are thick toward the circumference of the joint; the lateral cartilage is a little thicker than the medial. Both thin out toward the center where they end as a fine, free, concave edge. They do not cover the entire extent of the condylar surfaces of the tibia.

The *lateral semilunar cartilage* is nearly circular in outline, and its horns are fixed to the tibia close together. The anterior horn attaches to the front of the intercondylar eminence behind the anterior cruciate ligament with which it blends. The posterior




FIG 665 The ligaments and the cartilages of the right knee joint

eral aspect of the knee joint the tendon of the popliteus muscle intervenes between it and the lateral semilunar cartilage (meniscus). The biceps tendon which is superficial to the lower part of the ligament is split in two by it.

The medial ligament of the knee (*tibial collateral ligament*) is broad and straplike and, unlike the lateral is closely applied to the bone. It extends from the medial epi-

condyle of the femur above to the upper fourth of the shaft of the tibia below. Opposite the interval between the femur and the tibia it is closely fused with the capsular ligament (Fig 664A). It is attached to the medial meniscus. Three tendons cross it: those of the sartorius, the gracilis and the semitendinosus (Fig 664B). A bursa separates these from the ligament. The tendon of the semimembranosus ex-




FIG 666 The twelve bursae around the knee joint (A) lateral view of the right knee joint, (B) posterior view

semilunar cartilages to the tibia and the femur respectively. Those fibers which extend to the tibia are shorter since the cartilages follow the movements of this bone more closely than those of the femur.

INTERIOR OF THE KNEE JOINT AND THE SYNOVIAL MEMBRANE

When the knee joint is laid open the semilunar cartilages, the cruciate ligaments and the synovial membrane including its infra

patellar fold become visible (Figs 663, 664 and 665). The *infrapatellar synovial fold* (*ligamentum mucosum*) is the first structure to be seen. This is a triangular fold of synovial membrane which is pinched upward. Its apex is attached to the most anterior part of the intercondylar notch of the femur, and the base extends from below the articular surface of the patella to the anterior intercondylar area on the tibia (Fig 663A). Its sides are pro-

horn attaches to the back of the intercondylar eminence and in front of the posterior end of the medial cartilage. The peripheral margin is adherent to the capsular ligament but to a lesser extent than the medial cartilage, this is due to the fact that the popliteus tendon and its bursal sheath separate part of the margin from the capsule. As a result of the presence of this popliteus tendon the lateral semilunar cartilage is less fixed in position, therefore, it is able to adapt itself more easily to sudden twisting movements of the knee joint. The firmer fixation of the medial semilunar cartilage renders it much more liable to injury. A fibrous band leaves the posterior horn and passes upward along the posterior cruciate ligament to become attached to the medial condyle of the femur. This band has been called the ligament of Wrisberg (Fig. 665C). It is well to remember that in flexion and extension the tibia and the cartilages move on the femur but in rotatory movements the femur and the cartilages move on the tibia.

The *medial semilunar cartilage* is "C" shaped and adapts the upper surface of the medial condyle of the tibia to the curvature of the medial condyle of the femur. It is wider behind than in front while its peripheral borders are thick, its central border thins out into a fine edge. Its anterior horn attaches to the anterior part of the intercondylar area in front of the anterior cruciate ligament; its posterior horn becomes attached to the posterior part of the intercondylar area in front of the posterior cruciate ligament. Its periphery is adherent to the capsule and therefore to the medial ligament of the knee.

The *transverse ligament of the knee* is a fibrous band which stretches across the anterior part of one semilunar cartilage to the corresponding part of the other. By means of this connection the movements of one cartilage are partly controlled and partly accompanied by the other. Some authorities believe that the transverse liga-

ment may be considered the continuation of the peripheral fibers of each meniscus, the more central fibers attach to the tibia. Therefore, if any force acts on the periphery of the meniscus while the central part is fixed, it will tear longitudinally along the line between these inner and outer sets of fibers. This will result in the condition known as a "bucket handle" tear of the cartilage. The medial cartilage is the one usually affected.

The relationship of the medial ligament of the knee (*tibial collateral ligament*) to the medial meniscus is clinically important. It is responsible for the fact that injuries to the medial meniscus are more frequent than to the lateral. The lateral is free to move slightly, but even this slight degree of mobility is sufficient to provide for its safety. The medial, on the other hand, is fixed at one point by the tibial collateral ligament because of this firm fixation, it is prone to injury. The medial ligament of the knee consists of long and short fibers; the short ones are on the deep surface of the ligament at its posterior part and are attached to the margin of the medial meniscus thereby binding the meniscus to the tibia. Passing between these two sets of fibers of this ligament is the tendon of the semimembranosus muscle. By this arrangement the back part of the medial meniscus is firmly fixed. Excessive rotation of the femur on the tibia, therefore tears the movable front part away from the back which is firmly anchored.

On the nonarticular area of the upper surface of the tibia, the structures from before backward are the transverse ligament, the anterior horn of the medial semilunar cartilage, the anterior cruciate ligament, the anterior horn of the lateral semilunar cartilage, the intercondylar tubercle, the posterior limb of the lateral semilunar cartilage, the posterior horn of the medial semilunar cartilage, and the posterior cruciate ligament (Fig. 664A).

The *coronary ligaments* are the deeper portions of the capsule which unite the

times a bursa may exist under the lateral head of the gastrocnemius muscle. An incision may be extended upward on the tibia to within a quarter of an inch of its articular margin and still not open the synovial cavity except posteriorly where the popliteal bursa lies.

The relationship between the synovial membrane and the cruciate ligaments is as if the two ligaments have pushed into the joint from behind carrying the synovial membrane before them. Therefore the posterior cruciate ligament has no covering on its posterior aspect but the anterior cruciate ligament is covered anteriorly. A small diverticulum of synovial membrane is situated between the two and acts as a bursa during movements of the knee joint. Although the synovial membrane lines the portions of the capsular ligament which lie behind the condyles it does not come into relation with the middle part of the deep surface of the posterior ligament since it is held away from it by the cruciate ligaments. The posterior cruciate ligament may be exposed from behind without opening into the synovial cavity; the infrapatellar fold also may be exposed from in front without entering the cavity.

The *infrapatellar fat pad* fills the interval between the patella, the femur and the tibia. It adapts itself to the various forms which that recess assumes during movements of the joint. It is extra-articular and extra-synovial and is of a semifluid nature. A parapatellar incision close to the patella encounters this pad in its thickest portion; if the incision is placed more laterally, easier access is gained since only the thin alar folds are encountered.

Three bursae which communicate with the knee joint already have been discussed. All told, however, twelve bursae are situated around this joint. Four of these are anterior, two posterior, three medial and three lateral (Fig. 666).

The four anterior bursae are

1. The suprapatellar bursa, this has been

thoroughly discussed with the three bursae which communicate with the joint.

2. The prepatellar bursa, this is the bursa which is associated with the condition known as *housemaid's knee*. It is subcutaneous and lies in front of the lower half of the patella and the upper half of the patellar ligament. The term 'housemaid' is used because in scrubbing the floor the hands rest upon the floor bringing the bursae into contact with the ground. This constant rubbing causes an inflammation known as *bursitis*. The bursa then becomes large and because of its weight drops below its normal position.

3. The subcutaneous infrapatellar bursa is situated between the skin and the lower end of the ligamentum patellae (front of the tibial tuberosity).

4. The deep infrapatellar bursa is situated between the deep aspect of the lower end of the ligamentum patellae and the tibia.

The two posterior bursae are located between each head of origin of the gastrocnemius and the capsule of the joint. They often communicate with the joint. The bursa which is present between the medial head of the gastrocnemius and the capsule sends a prolongation between the gastrocnemius and the semimembranosus muscles. If it is enlarged it forms a swelling at the inner side of the popliteal space, which is referred to as an enlarged semimembranous bursa.

The three medial bursae are: One which separates the sartorius, the gracilis and the semitendinosus from the tibial collateral ligament. The two others separate the tendon of the semimembranosus from the tibial collateral ligament medially and the head of the tibia laterally. The semimembranosus tendon is placed between the ligament medially and the condyle of the tibia laterally.

The three lateral bursae are

1. Between the biceps femoris tendon and the fibular collateral ligament.

longed in a fringelike arrangement which forms the alar folds into which fat extends. Knee joint injuries may result in bruising of these fringes. Its base is related to the infrapatellar fat pad which covers the deep surface of the ligamentum patellae; its borders the alar folds remain free.

The *synovial membrane* lines the capsular ligament but leaves the capsule posteriorly to pass forward around the cruciate ligament (Fig. 664A). The complexity of the synovial membrane may be simplified if we recall that developmentally the joint possessed three synovial cavities, a patellar and two condylar. The partition which separated the condylar from the patellar cavity disappeared leaving only its vestigial alar folds. In prenatal life a partition called the intercondylar septum exists which separates the condylar cavities from each other. The lower border of this septum is attached to the intercondylar area on the upper aspect of the tibia. The posterior half of its upper border is attached to the intercondylar notch of the femur, and the anterior half of its upper border is free and extends from the intercondylar notch of the femur to the patella just below its articular surface. During development a perforation appears in this septum which extends backward to the anterior cruciate ligament (Fig. 663C). In this way the intercondylar septum is divided into an anterior part the infrapatellar fold, and the posterior part which is associated with the anterior and the posterior cruciate ligaments. The infrapatellar fold has been described previously. After these developmental changes have taken place fluid may pass from one condylar cavity to the other, either by way of the patellar cavity that is over the infrapatellar folds or via the hole in the intercondylar septum between the infrapatellar folds and the anterior cruciate ligament. It will be remembered that each condylar cavity is divided into upper and lower compartments by the semilunar cartilages. These two parts communicate around the free concave borders of the cartilages.

BURSAE

Since there were three primitive cavities in the knee joint, three bursae remain in the adult which communicate these cavities with the joint. They are the bursae which lie deep to the tendons of the quadriceps femoris, the popliteus, and the medial head of the gastrocnemius (Fig. 666).

The bursa which lies deep to the quadriceps femoris tendon is known as the *suprapatellar bursa*. This bursa lies between the anterior surface of the lower part of the femur and the deep surface of the quadriceps femoris muscle. It extends about three fingerbreaths above the upper border of the patella when the limb is in extension. It almost always communicates with the knee joint, and for this reason it is removed in excision of the joint for tuberculosis, however, it may become shut off from the rest of the joint by adhesions. It rests on a layer of fat which allows it to glide freely when the knee joint is in motion. Through apertures in the back of the capsule it often communicates with bursae under the head of the gastrocnemius and the bursa of the semimembranosus.

The *popliteus bursa* is situated between the popliteus tendon and the lateral condyle of the femur. It separates the popliteus tendon from the lateral semilunar cartilage, the lateral tibial condyle and the superior tibiofibular joint. This bursa is a tube of synovial membrane, which is situated around the popliteus tendon similar to the one around the long head of the biceps at the shoulder joint. It communicates with the knee joint both above and below the semilunar cartilage; in some instances it communicates with the superior tibiofibular joint.

The *gastrocnemius bursa* is situated deep to the medial head of the gastrocnemius muscle. Although this bursa does not always communicate with the medial condylar cavity it communicates with a bursa deep to the semimembranosus. In this way it may bring the semimembranosus bursa and the knee joint into communication. At




FIG 668 Supracondylar amputation (A) A circular incision is placed at the level of the upper border of the patella (B) The four medial muscular structures have been severed and the femoral vessels are identified (C) The periosteum is incised and dissected 2 inches cephalad to the skin incision (D) The fascia lata is approximated




FIG 667 The superior and the inferior tibiofibular joints

2 Between the popliteus tendon and the lateral condyle of the femur

3 Between the fibular collateral ligament and the popliteus tendon

Nerve Supply The *nerve supply* is rich around the knee joint. It is supplied by three branches each from the femoral, the lateral and the medial popliteal nerves, and an additional twig from the obturator nerve.

Movements Flexion, extension and rotation constitute the active movements at the knee joint. Flexion is accompanied by some degree of flexion of the hip joint. The movements of the tibia and the femur on one another combine sliding, rolling, and rotating actions. When one is in a resting upright position the knee joints are not fully extended, and the attitude is maintained by the balanced tone of the flexor and the extensor muscles. The movement of extension is completed by a movement of lateral rotation of the tibia on the femur; the latter

action locks the joint and renders all ligaments tense, with the exception of the anterior fibers of the posterior cruciate ligament. This locking mechanism enables the fully extended knee to become subjected to severe strains without becoming injured. Rotation is impossible when the knee is fully extended and any attempt to produce pure rotation in this position results in injury. Flexion is accompanied in its initial stages by medial rotation of the tibia on the femur. When the knee is flexed to a right angle a considerable range of rotation is allowed, but when it is slightly flexed only a small amount of abduction and adduction can be produced, provided that the foot is placed upon the ground.

THE TIBIOFIBULAR JOINTS

The fibula articulates with the tibia at both of its ends. Therefore, superior and inferior tibiofibular joints are formed (Fig. 667). The superior forms a small synovial joint, but the inferior is a syndesmosis.

The *superior tibiofibular joint* is formed where the head of the fibula articulates with the postero-inferior surface of the lateral condyle of the tibia. These bones are united by a capsular ligament. The tendon of the popliteus and its synovial pouch cross the upper and back part of the joint. The pouch sometimes is continuous with the synovial membrane of the joint through a hole in the capsule and in this way the joint indirectly communicates with the knee joint. The lateral ligament of the knee and the tendon of the biceps cross the upper surface of the joint.

Some fibers of the biceps tendon extend to the tibial condyle and thus form an additional ligament for the joint. Since the uppermost fibers of the extensor digitorum longus and the peroneus longus arise from the lateral condyle of the tibia, they cross in front of the joint. It is supplied by twigs from the nerve to the popliteus and from the recurrent branch of the lateral popliteal (common peroneal) nerve. It permits glid-

tends distally and medially curving around the patella to the tibial tuberosity. The dissection is carried between the quadriceps tendon and the vastus medialis muscle. The capsule and the synovial membrane are divided about one half inch from the inner

border of the patella and the patellar ligament. The patella is turned to the outer side of the lateral condyle of the femur. This exposes the lower end of the femur, the cruciate ligaments, the semilunar cartilages and the articular surface of the patella.




FIG 669 Exposure of the knee joint

ing movements which take place during the separation and the approximation of the lower ends of the tibia and the fibula in dorso and plantar flexion of the ankle joint

The bones of the *inferior tibiofibular joint* are held together by ligaments which do not enclose a cavity. The joint is formed between a convex fibular surface and a corresponding concave tibial one. However, the bones are not in contact with each other because the interosseous ligament not only binds them but separates them. At times this ligament does not quite reach the lateral border of the distal end of the tibia and in such cases there is a narrow strip above the lateral border which is covered with cartilage for articulation with the uppermost part of the facet of the lateral malleolus. This joint is constructed firmly; the strength of the ankle joint largely depends upon its integrity. The antero inferior and the postero inferior tibiofibular ligaments (anterior and posterior ligaments of the lateral malleolus) hide the interosseous ligament. They are strong, flat bands that pass upward and medially from the front and the back of the uppermost part of the lateral malleolus to the distal end of the tibia. The posterior ligament is continuous inferiorly with the transverse ligament. The transverse tibiofibular ligament is attached

along the whole length of the posterior border of the tarsal surface of the tibia and to the malleolar fossa of the fibula. Superiorly it is continuous with the postero inferior ligament, and its deep surface is in contact with a facet on the talus. The joint derives its nerve supply from the anterior tibial nerve and a long filament from the nerve to the popliteus that descends through the interosseous membrane.

SURGICAL CONSIDERATIONS

SUPRACONDYLAR AMPUTATION

The author described a supracondylar amputation in 1942. The procedure is accomplished through a simple circular incision placed on a level of the upper border of the patella (Fig 668). The internal saphenous vein is isolated and severed. This acts as a guide to the sartorius muscle. Four structures are identified and divided over the medial aspect of the lower end of the thigh. They are the sartorius muscle, the gracilis tendon, the semimembranosus muscle and the semitendinosus tendon. Laterally the tensor fasciae latae and the biceps femoris tendon are divided. The femoral vessels and the sciatic nerve are isolated, ligated and divided at the lower aspect of the thigh. The attachment of the quadriceps femoris muscle to the linea aspera is severed. The bone is sawed from two to three inches above the level of the skin incision. The fascia and the skin are approximated.

EXPOSURE OF THE KNEE JOINT

Numerous approaches have been described for exposure of the knee joint; only one approach will be discussed here since the others can be found in any standard text on orthopedic surgery. The procedure herein described is the *anteromedial approach*. This is accomplished through a long incision which begins at the medial border of the quadriceps tendon about three inches above the patella (Fig 669). It ex-




FIG. 670 Cross sections of the right leg at its upper, middle and lower thirds

The Leg

The two bones which are found in the leg are the tibia and the fibula (Figs 677 and 678) These bones furnish attachments for the thigh muscles and the leg muscles (Fig 670)

The *cutaneous nerve supply* of the anterior aspect of the leg is derived from the cutaneous rami of the medial crural branch of the saphenous nerve and from the cutaneous branches of the lateral popliteal nerve (Fig 671) The lower lateral aspect of the leg is supplied by the superficial peroneal nerve The cutaneous nerve supply of the posterior aspect of the leg is supplied by the end of the posterior cutaneous nerve of the thigh the posterior branch of the medial cutaneous nerve of the thigh, the cutaneous branch of the lateral popliteal (common peroneal) nerve branches of the saphenous nerve and the cutaneous branch of the medial popliteal (tibial) nerve, which is derived from the sural nerve

DEEP FASCIA

This fascia does not form a complete investment for the leg it is absent over the subcutaneous part of the medial surface of the tibia (Fig 672) It is attached to the anterior border of the tibia then sweeps laterally and around the front to the back of the leg to reach the tibia again at its posteromedial border where it attaches Its strength and density vary in different parts of the leg By sending inward two partitions which attach to the fibula it divides the leg into lateral anterior and posterior compartments The anterior intermuscular septum attaches to the anterior border of the fibula and separates the extensor muscles of the anterior compartment of the

leg from the peroneal muscles The posterior intermuscular septum is interposed between the peroneal muscles and the muscles on the back of the leg, it is attached to the posterior border of the fibula A deep layer of fascia (lamina profunda) arises from the posterior intermuscular septum and attaches to the medial border of the tibia This layer divides the posterior compartment into a superficial and a deep compartment In this way the three muscular compartments are formed, the anterior compartment contains the extensor muscles and the anterior tibial artery and nerve, the lateral compartment contains the peroneal muscles and the superficial peroneal nerve and the posterior compartment contains the flexor muscles and the posterior tibial vessels and nerve The deep fascia becomes thinner as it passes toward the distal part of the leg In the region of the ankle it again becomes thickened to form fascial bands These bands are called *retinacula* their function is to retain the tendons in position when the muscles which move the joint are in action (Fig 684) The *superior extensor retinaculum (transverse ligament)* is a band of fascia about one and one half inches wide which stretches across the front of the leg from the tibia to the fibula At its medial end the ligament splits to enclose the tendon of the tibialis anterior muscle In this way a special compartment is made which is invested with a synovial sheath for the tendon of this muscle To its lateral side the tendons of the extensor hallucis longus the extensor digitorum longus and the peroneus tertius muscles pass behind the retinaculum in a common compartment This is not

extensor digitorum longus as it passes behind the upper extensor retinaculum, in the lower retinaculum it is lined with an independent synovial sheath. As it passes over the ankle joint it crosses the anterior tibial vessels and nerves so that its tendon comes to lie medial to the dorsalis pedis artery (Fig. 691). It is the only muscle which crosses the phalanx of the great toe on its dorsal aspect. Its action is indicated by its name: extension of the great toe; it aids also in dorsiflexion (extension) of the foot.

The *extensor digitorum longus* muscle arises as a long, thin sheath of muscle from the upper three-fourths of the anterior surface of the fibula and the interosseous membrane. Its tendon passes behind the superior retinaculum and in front of the ankle joint. It passes under the inferior retinaculum and divides into four slips which diverge from each other to reach the lateral four toes. Each tendon inserts into the middle and distal phalanges of the lateral four toes. Each tendon also receives a tendon of the extensor brevis digitorum which passes onto the dorsum of each toe and broadens into a dorsal expansion (p. 882). This is inserted in a fashion similar to the dorsal expansion of the fingers. The muscle is an extensor of the toes and a dorsiflexor of the foot.

The *peroneus tertius* is not a peroneal muscle, but rather is a part of the extensor digitorum longus. It is small and is not always present. Some anatomists consider it the lowest quarter of the extensor digitorum longus. It ends in a slender tendon which fails to reach the toe but gains attachment somewhere along the dorsum of the fifth metatarsal. The action of this muscle is to dorsiflex the foot and to aid the true peroneal muscle in eversion.

Nerves and Vessels. The *anterior tibial (deep peroneal) nerve* is one of the two terminal branches of the lateral popliteal nerve (common peroneal) (Fig. 673). It arises on the lateral side of the neck of the fibula under cover of the peroneus muscle, pierces the anterior intermuscular septum and then usually passes between the ex-

tensor digitorum longus and the fibula to enter the anterior compartment of the leg. In the upper two-thirds of the anterior compartment, it lies very deep between the muscles having the extensor longus muscle to its lateral side and the tibialis anterior to its medial side. In the distal third where fleshy muscle bellies give place to tendons, it comes closer to the surface. At first, the nerve is in front of the interosseous membrane, with the anterior tibial vessels to its medial side. As it descends it passes onto the front of the artery. In the distal third of the leg the nerve lies on the tibia with the vessels usually to its medial side again. The extensor hallucis longus, at first on the lateral side of the nerve, crosses in front of it and the vessels just above the ankle; it lies medial to them at the ankle, thus separating them from the tibialis anterior muscle. The nerve leaves the anterior compartment by passing downward deep to the anterior annular ligament where it continues with the dorsalis pedis artery. It supplies the four muscles of the anterior compartment.

The *anterior tibial artery* begins on the posterior surface of the leg where it arises from the popliteal artery at the lower border of the popliteus muscle (Fig. 673). It is accompanied by two *venae comitantes* which run with the artery and send interlacing veins around it. The artery enters the anterior compartment of the leg by piercing the upper part of the interosseous membrane. In the upper half of its course the vessel is situated deeply with the nerve lying on the interosseous membrane between the tibialis anterior and the extensor digitorum longus. In the lower part of its course the artery lies on the shaft of the tibia and is overlapped by the extensor hallucis longus. After passing behind the superior extensor retinaculum it becomes superficial in the interval between the tendons of the extensor hallucis longus and the extensor digitorum longus. In front of the ankle joint the artery continues as the dorsalis pedis artery (Fig. 691). Branches of this vessel take part in the anastomoses




FIG 671 The interior and posterior cutaneous nerve supply of the leg

provided with a synovial sheath. The anterior tibial vessels and nerve lie posterior to the extensor hallucis longus as they pass behind the retinaculum. The inferior extensor retinaculum (cruciate ligament) lies distal to the ankle joint. It is a Y-shaped ligament which extends from the lateral part of the calcaneum medially and splits, thus giving it the semblance of the letter 'Y' (Fig. 683C). The upper limb of the Y passes to the medial malleolus and the lower limb passes to the deep fascia on the medial side of the foot. The tibialis anterior has a separate synovial sheath under this retinaculum as has the extensor hallucis. The extensor digitorum and the peroneus tertius have a common sheath under the lower retinaculum.

MUSCLES

The muscles of the leg consist of three groups: (1) the interior (extensor) group, all of which are supplied by the interior

tibial (deep peroneal) nerve, (2) the posterior (flexor) group, all of which are supplied by the posterior tibial nerve, (3) the lateral peroneal (evertor) group, which is supplied by the superficial peroneal (musculo-cutaneous) nerve. Since the fibula is on a plane posterior to that of the tibia, the interior compartment faces laterally as well as anteriorly (Fig. 673).

ANTERIOR (EXTENSOR) GROUP (ANTERIOR COMPARTMENT)

If one thinks of the tibia, the large toe and the four remaining toes, it would naturally follow that four muscles constitute this group. They are the tibialis anterior, the extensor hallucis longus, the extensor digitorum longus and the extensor tertius (Fig. 673A and B).

The *tibialis anterior* (*tibialis anticus*) arises from the upper half of the lateral surface of the tibia and from the interosseous membrane. Its tendon begins at about the middle of the leg and follows the anterior border of the tibia, crossing the bone directly in front of the medial malleolus. It passes through the medial compartments of the extensor retinaculum, crosses the ankle joint, the talus and the navicular, and finally is inserted into the medial aspect of the cuneiform bone and the adjoining part of the base of the first metatarsal. Its action is dorsiflexion (extension) and inversion of the foot. It is separated above from the extensor digitorum longus and below from the extensor hallucis longus by a septum of deep fascia which leads to the cellular interspace. This space contains the neurovascular structures.

The *extensor hallucis longus* is the long extensor of the big toe. It is a thin muscle which is placed between the tibialis anterior and the extensor digitorum longus. Its upper portion is hidden by the two last named muscles, but as it passes downward, it reaches the surface between them. It arises from the middle two fourths of the anterior surface of the fibula and from the interosseous membrane. It is accompanied by the




FIG 67s The muscles of the anterior and the lateral groups of the leg (A) the anterior group, (B) deeper dissection showing vessels and nerves (C) the lateral group, (D) deeper dissection showing vessels and nerves




FIG 672 The deep fascia of the leg, cross section showing the three compartments

around the knee and the ankle joints. A straight line drawn from the medial side of the neck of the fibula to a point midway between the two malleoli marks the course of the anterior tibial artery.

LATERAL (PERONEAL) GROUP (LATERAL COMPARTMENT)

This group is made up of two muscles on the lateral aspect of the leg, the peroneus longus and the brevis, they are evertors

(Fig 673). The peronei fill the lateral crural compartment and are separated from the extensor flexor compartment by the anterior and the posterior intermuscular septa, respectively.

The *peroneus longus* arises from the upper two thirds of this compartment, and the *peroneus brevis* from the lower two thirds, thus overlapping each other in the middle third. Both muscles pass downward the brevis being covered by the longus, until





FIG 673 The muscles of the anterior and the lateral groups of the leg (A) the anterior group (B) deeper dissection showing vessels and nerves (C) the lateral group (D) deeper dissection showing, vessels and nerves

they reach the posterior aspect of the lateral malleolus, where the tendon of the brevis is in direct contact with the bone. Here, the tendons are held down by a thickening of the deep fascia, the superior peroneal retinaculum. They are provided with a common synovial sheath. They continue to pass below the malleolus and lie on the lateral aspect of the calcaneum, becoming separated from each other by the peroneal tubercle. At this point, they are held in place by the inferior peroneal retinaculum, and here each possesses a synovial sheath of its own. The tendon of the peroneus brevis passes above the tubercle to be inserted into the dorsal aspect of the tubercle on the base of the fifth metatarsal bone. The tendon of the peroneus longus passes below the peroneal tubercle, medial and forward across the sole of the foot to become inserted into the lateral aspect of the medial cuneiform and the adjoining part of the base of the first metatarsal bone.

Both of these muscles are supplied by the musculocutaneous (superficial peroneal) nerve.

Actions When the foot is off the ground the peroneal muscles produce eversion. A most important function of the peroneus longus is to maintain the transverse arch of the foot. By their ability to draw the foot to the lateral side the peroneal muscles balance the medial pull exerted by the tibialis posterior and the long flexors of the toes.

The *musculocutaneous (superficial peroneal) nerve* arises from the lateral popliteal nerve on the lateral side of the fibular neck (Fig 673). It proceeds downward and forward in the substance of the peroneus longus muscle and then between the peroneus brevis and the anterior intermuscular septum. At the junction of the middle and lower thirds of the leg it passes through the deep fascia to become cutaneous. Plus its muscular and cutaneous branches it gives off a communicating branch on the dorsum of the foot to the sural nerve. The anterior border of the peroneus brevis acts

as a guide to this nerve, since it travels with it to the surface, a variable distance above the subcutaneous area of the fibula.

POSTERIOR (FLEXOR) GROUP (POSTERIOR COMPARTMENT)

This group of muscles is supplied by the posterior tibial nerve, which also has been referred to as the tibial nerve and as the medial popliteal nerve. The muscles are divided into superficial and deep groups (Fig 674).

The superficial muscles are the *gastrocnemius*, the *plantaris* and the *soleus*, they join to form the stout *tendo calcaneus*, which is inserted into the back of the calcaneus (Figs 674 and 675).

The *gastrocnemius* arises from the femur by two heads (Fig 674A). The medial head arises from the back of the femur above the medial condyle; the lateral head arises from the lateral aspect of the lateral condyle. There is an asymmetry between the origins of these two heads. This muscle accounts for the fullness of the calf, since the two muscle bellies broaden as they descend. The muscle bellies do not blend with each other but are separated by a groove in which the sural nerve and the short saphenous vein are found. The lateral head often contains a small sesamoid bone called the *fabella* which usually is noted on the x-ray film opposite the lateral condyle. The common tendon of the two heads joins the tendon of the *soleus* to form the *tendo calcaneus*, this takes place a short distance below the middle of the leg. The muscle acts as a plantar flexor of the foot and as a flexor of the knee.

The *soleus* has a rather extensive horse shoe shaped origin from the upper third of the posterior aspect of the fibula and from the soleal line on the back of the tibia (Fig 674B). In its upper half, this muscle is covered by the bellies of the *gastrocnemius*, but where the common tendon of the latter begins the belly of the *soleus* projects beyond its margins, becoming superficial. The tendon of this muscle develops

on its superficial aspect and joins the deep surface of the *tendo calcaneus*. It is a plantar flexor of the foot.

The *plantaris* is a small muscle about 3 or 4 inches long, with a very long tendon which it times may be over a foot long; it may be bent. Because of this long, narrow tendon, it has been referred to as the "freshman's nerve". It arises from the lateral supracondylar line of the femur and passes downward between the gastrocnemius and the underlying soleus. It reaches the inner side of the *tendo achillis*, with which it blends. It may have a separate insertion into the os calcis, its action is to aid the gastrocnemius.

The *tendo calcaneus* is the most powerful tendon in the body. It narrows as it descends, but near the heel it expands again and inserts into the middle portion of the posterior surface of the calcaneum. The fleshy fibers of the soleus are continued downward on its deep surface almost to the heel. A small bursa separates the tendon from the calcaneum.

The deep group of muscles consists of the popliteus, the flexor hallucis longus, the flexor digitorum longus and the tibialis posterior.

The *popliteus* arises from the lateral aspect of the lateral condyle of the femur, within the capsule of the knee joint. The tendon pierces the posterior part of the capsule of the joint and its fibers fan out to obtain insertion into the posterior aspect of the tibia above the soleal line (Figs 675 and 676). It is mainly a flexor of the knee joint. A strong fascia covers the posterior surface of the popliteus muscle; this tendon can be traced upward and medially to the medial side of the knee where it becomes continuous with the tendon of the semi-membranosus.

The *flexor hallucis longus* is the long flexor of the big toe. It arises chiefly from the posterior surface of the fibula, below the origin of the soleus. The muscle belly is bulky and overlaps and largely conceals the fleshy part of the tibialis posterior.

At the ankle joint, it passes through a separate space in the laciniate ligament being separated from the flexor digitorum longus by the tibial nerve and the posterior tibial vessels (Fig 675B). It inserts into the terminal phalanx of the great toe and is a powerful inverter as well as a flexor of the big toe.

The *flexor digitorum longus* arises from the posterior surface of the tibia, below the popliteus muscle and medial to the vertical ridge. After passing through the split tendon of the flexor brevis muscle it inserts into the terminal phalanges of the four outer toes. It flexes the toes, draws the pillars of the arches of the foot together and also supports the arch.

The *tibialis posterior muscle* originates from the interosseous membrane and the adjoining parts of the posterior surfaces of the tibia and the fibula (Fig 675). This attachment to the interosseous membrane does not reach as high as the attachments to the bone. The upper end of the muscle is bifid; the anterior tibial vessels pierce the membrane between the two parts. As it passes distally, it inclines medially under cover of the flexor digitorum longus and becomes a strong flattened tendon which grooves the back of the medial malleolus under cover of the flexor retinaculum. Its tendon enters the sole and is inserted chiefly into the tuberosity of the navicular bone and the cuneiform bone. Some slips of the tendon also are inserted into other bones of the foot. The muscle is a plantar flexor and inverter of the foot.

Vessels and Nerves. This region contains two main arteries and one main nerve (Fig 676). The arteries are the posterior tibial and its largest branch, the peroneal; the nerve is the posterior tibial. The posterior tibial nerve lies between the two arteries being closely applied to the lateral side of the posterior tibial artery. All three travel distally behind the fascia covering the posterior tibial muscle, and when this muscle passes to a medial position, they continue their course on the skeletal plane.




FIG 674 The superficial posterior group of calf muscles (A) The relations of the plantaris the gastrocnemius and the soleus are shown (B) The two heads of the gastrocnemius have been cut to show the plantaris tendon and the soleus muscle

The nerve takes a straight course and crosses the posterior tibial artery to gain its lateral side. It supplies the three deep muscles and the deep part of the soleus muscle, and then ends deep to the flexor retinaculum (laciniate ligament) by dividing into medial and lateral plantar nerves.

The *posterior tibial artery* is the larger of the two terminal branches of the popliteal artery. It begins at the upper border of the soleus and ends deep to the flexor retinaculum by dividing into the medial and lateral plantar arteries. The flexor hallucis longus muscle lies laterally and the flexor digi-




FIG. 675 The superficial and the deep groups of the calf muscles (A) the superficial group consists of three muscles (B) the deep group consists of four muscles

torum longus lies medially the fascia covering the posterior tibial muscle the shaft of the lower end of the tibia and the capsule of the ankle joint all lie anteriorly. When the fascia is relaxed by inverting the foot the pulsations of the artery can be felt about a finger's breadth from the medial malleolus. The *peroneal artery* arises from the posterior tibial artery before the latter is crossed by the tibial nerve. It descends first behind the fascia covering the tibialis posterior muscle deep to the flexor hallucis

longus then it continues downward behind the fibula and the ankle joint to end on the lateral surface of the calcaneus as the lateral calcanean artery.

TIBIA AND FIBULA

The *tibia* or shin bone, is the medial and the larger of the two bones of the leg (Figs 677 and 678). It presents a proximal end, a shaft and a distal end.

The *proximal end* is the larger of the two, its transverse diameter is wider and

it is bent slightly backward. It consists of a tubercle lateral and medial condyles, an intercondylar area and eminence, fibular facets and a groove for the semimembranosus. This massive prismatic upper end is broader from side to side than from before backward and it is curved so that it overhangs the posterior surface of the shaft. Being so greatly expanded, it provides a good weight bearing surface for the lower end of the femur. The *tubercle* (tuberosity) is seen in front of and below the condyles about an inch from the top. Its lower half is rough for the attachment of the ligamentum patellae; above, it is a smooth area separated by a bursa from this ligament. This prominence is felt easily subcutaneously. In the kneeling position the body rests upon the lower part of this tubercle. The front of the condyles, the ligamentum patellae and the lower part of the patella. The two condyles are felt readily at the sides of the bone and make up most of the proximal end of the tibia. Anteriorly they are united above the tubercle but posteriorly they are separated by a wide and shallow notch. Over their superior surfaces they are covered with cartilage; they articulate centrally with the condyle of the femur and peripherally with a corresponding semilunar cartilage. Between these articular surfaces is the intercondylar area which rises in its center to form the intercondylar eminence. The *medial condyle* is larger than the lateral and its articular surface is more concave. Over its postero-medial aspect the groove for the insertion of the semimembranosus is found. The *lateral condyle* extends farther out from the shaft and presents the facet for the head of the fibula over the postero-inferior surface. On the back and above and medial to this facet is the shallow groove for the popliteus tendon. On the front of the condyle is a raised impression for the attachment to the posterior part of the iliotibial tract. Over the lateral surface is a curved ridge which gives attachment to the strong deep fascia of the leg.

The *shaft* is thick and strong above, but gradually tapers as it is traced downward to the junction of its middle and lower thirds, where it again becomes slightly expanded. It is distinctly prismatic in shape, because of this, it has anterior, lateral and medial borders and posterior, medial and lateral surfaces (Fig. 679). The *anterior border*, which may be felt as the shin, extends from the tubercle above, to the front of the medial malleolus below; it is somewhat indistinct in its lower third. The *lateral (interosseous) border* is sharply defined in its middle third and extends from the fibular facet above to the fibular notch below; the interosseous membrane is attached to it. The *medial border* is rounded and less distinct than the lateral; it can be traced from the lower part of the medial condyle to the back of the medial malleolus. The *lateral surface* is located between the anterior and the interosseous borders and is slightly concave in its upper two thirds to accommodate the origin of the anterior tibialis muscle. The lower third is in relation to the tendons of the extensor muscles; it is convex. The *medial surface* is wide and smooth, it is subcutaneous except at its upper end where tendons are inserted. The *posterior surface* is located between the medial and the interosseous borders and encroaches upon the lateral aspect near its upper end. The *soleal (popliteal) line* appears as a rough ridge which crosses this border obliquely from the fibular facet to the medial margin. Extending downward from this line is the *vertical line*, to the lateral side of which is found a large foramen for the nutrient artery.

The *distal end* of the tibia presents five surfaces: a medial malleolus and a fibular notch. The *medial surface* is subcutaneous and continues below as the medial malleolus. The *anterior surface* is rounded and covered with extensor tendons. The *posterior surface* also is rounded and is grooved on the malleolus for the tibialis posterior. The *inferior (tarsal) surface* is quadrilateral and wider in front than behind; it is

slightly concave from behind forward and convex from side to side. It articulates with the upper surface of the talus. The *lateral surface* is occupied by a triangular depression known as the *fibular notch*. The *medial malleolus* can be palpated without difficulty. It lies a little anterior to the lateral malleolus and does not extend as far downward. Its apex gives attachment to the deltoid ligament of the ankle joint, and its posterior aspect is grooved by the tendon of the *tibialis posterior*. Its lateral surface articulates with the talus.

The epiphysis of the lower end is represented by a horizontal line about a quarter of an inch above the broad lower end of the bone. The metaphysis is separated by the whole thickness of the epiphysis. Diseases of the tibia either in the upper or lower end are unlikely to affect the joint because of the epiphyseal and the capsular relationships.

Attachments to the Tibia (Figs 677 and 678)

To the intercondylar area the anterior horn of the medial semilunar cartilage and the anterior cruciate ligament.

To the intercondylar eminence the anterior horn of the lateral semilunar cartilage to the front and the posterior horn to the back.

To the intercondylar area the posterior horn of the medial cartilage and the posterior cruciate ligament.

To the medial condyle the semimembranosus.

To the tibial tubercle the ligamentum patellae.

To the shaft the *tibialis anterior* from the lateral condyle and two thirds of the lateral sulcus. From the upper part of the medial surface, the *sartorius*, the *gracilis*, the *semitendinosus* and the medial ligament of the knee.

To the soleal line the *popliteus* and the *tibialis posterior* from the upper two thirds of the lateral area of the posterior surface.

From the vertical line the fascia covering the *tibialis posterior* and the *flexor*

digitorum longus from the upper two-thirds of the area medial to the vertical line.

To the anterior and the medial borders the fascia of the leg and the superior extensor retinaculum to the lower part of the anterior border.

To the interosseous border the interosseous membrane.

To the fibular notch. The interosseous tibiofibular ligament and the inferior tibiofibular ligaments to the lower parts of its anterior and posterior margins. The anterior ligament of the ankle to the anterior border of the tarsal tibial surface and the posterior ligament of the ankle and the transverse tibiofibular ligament to the posterior border.

To the medial malleolus the deltoid ligament, the flexor retinaculum and the inferior extensor retinaculum.

The *fibula* is the lateral of the two bones of the leg. It is slender and is attached above and below to the lateral aspect of the tibia. It can be divided conveniently into proximal and distal ends and a shaft.

The *proximal end* consists of a head, a neck and a styloid process. The *head* appears as an irregular cuboidal area which has on its upper surface a triangular facet which articulates with the lateral condyle of the tibia. Projecting upward from its posterolateral aspect is the blunt shaped *styloid process (apex)* to the top of which the short lateral ligament of the knee joint is attached. The tubular head can be felt through the skin on the posterolateral aspect of the knee below the level of the joint. The lateral popliteal (common peroneal) nerve can be felt and rolled by the fingers on the back of this head although it is separated from it by the uppermost fibers of the soleus muscle. The *neck* is that constricted portion just below the head where the lateral popliteal nerve divides over its lateral side.

The *shaft* reveals three borders, three surfaces and a crest (Fig 679). The *interosseous border* is ill defined on the medial side of the anterior border, it extends from




FIG 676 The posterior tibial nerve and the posterior tibial and peroneal arteries




FIG 677 The tibia and the fibula seen from in front. The muscular origins are presented in red the insertions in blue

the neck to the apex of a rough triangle on the medial side of the distal end. It provides attachment for the interosseous membrane. The *anterior border* is sharp and distinct in its lower half but it may be masked and joined with the interosseous border in its upper fourth. The *posterior border* is blunt but well defined and extends from the neck to the medial margin of the back of the lateral malleolus.

The *lateral (peroneal) surface* is situated between the anterior and the posterior borders: it faces laterally above but becomes twisted so that below it faces directly backwards. The *anterior (extensor) surface* is that strip which is situated between the

anterior and the interosseous borders. It is very narrow proximally but is wider distally. The *posterior surface* is situated between the posterior and the interosseous borders and is subdivided into two parts by the medial crest. The *medial crest* is at times the most prominent ridge on the bone. It begins at the neck and ends inferiorly by continuing into the interosseous border a few inches above the distal end. This crest is closely related to the peroneal artery.

The *distal end* of the bone may be considered the *lateral malleolus*. It is pyramidal in shape and compressed from side to side. It presents four surfaces of which




FIG 678 The tibia and the fibula seen from behind. The origins are presented in red, the insertions in blue.

the medial reveals a triangular facet for articulation with the lateral surface of the talus. The *lateral surface* is smooth and convex and palpable subcutaneously. It forms the lateral prominence of the ankle and extends to a slightly lower level than the medial malleolus. The *anterior surface* is narrow and not sharply defined from the lateral. The *posterior surface* presents a longitudinal groove for the tendons of the peroneus longus and the brevis. The *medial surface* reveals a large articular area for the talus.

Attachments to the Fibula (Figs 677 and 678)

To the head, the capsule of the superior tibiofibular joint. The arcuate ligament of the knee to the styloid process, the lateral ligament of the knee and the biceps in front




FIG 679 Diagram of a cross section of the tibia and the fibula, showing the bony borders and surfaces.

of that process, the muscles and their fasciae which arise from the upper part of the shaft and also arise from the adjoining part of the head and the fascia lata.

From the shaft from the anterior surface the extensor digitorum longus, the peroneus tertius and the extensor hallucis longus; from the posterior surface the soleus and the flexor hallucis longus. From the lateral surface the peroneus longus and the brevis. From the anterior border the anterior intermuscular septum and the superior extensor retinaculum.

To the lateral malleolus, the anterior inferior tibiofibular ligament, the anterior talofibular ligament and the calcaneofibular ligament. The posterior inferior tibiofibular ligament, the superior peroneal retinaculum, the posterior talofibular ligament and the transverse tibiofibular ligament to the malleolar fossa.

The *epiphyses* of the fibula appear as bulbous ends at both extremities. The capsules are attached to the articular margins, and the metaphyses are entirely extra capsular. The epiphyseal line at the lower end is at the level of the ankle joint. This anatomic point is important since a disease of the ankle joint may spread to the shaft of the fibula and vice versa.

SURGICAL CONSIDERATIONS

APPROACHES

TO THE TIBIA AND THE FIBULA

The tibia can be approached along its exposed medial surface (Fig 680). The




FIG 680 The surgical approach to the tibia

saphenous nerve and the great saphenous vein should be avoided

The fibula is exposed in such a way that the superficial (musculocutaneous) peroneal nerve is avoided (Fig 681). The proximal and the middle thirds can be approached through an incision along the line of the posterior intermuscular septum; the upper third of the shaft can be approached through an incision between the adjoining borders of the soleus and the peroneus longus muscles. The common peroneal (external popliteal) nerve must be protected where it winds around the neck of the fibula. In the middle third a lateral incision is made through the interval between the peroneus longus and the flexor hallucis longus muscles; the distal third of the




FIG 681 The surgical approach to the fibula

shaft is exposed just behind the anterior intermuscular septum, between the peroneus brevis and the tertius muscles.

LEG AMPUTATION

The technic for leg amputation in the middle third utilizes a long anterior flap and a short posterior flap (Fig 682). The deep fascia is included in these flaps, and in those patients whose circulation seems to be adequate, an additional 2 or 3 inches of deep fascia is cut downward from the posterior incision so that a fascial flap remains attached. The anterior flap of skin and fascia is separated at a little higher level than that point at which the bones are to be saved. All soft tissues are severed to the bone about 2 inches distal to the point of bone section. The tissues are separated from the bone and retracted high enough




FIG 682 Leg amputation In C it should be noted that the fibula is cut at a higher level than the tibia, the tibia is beveled

to promote free use of the saw. The periosteum is elevated upward. The fibula should be made about an inch shorter than the tibia because if it is left as long as the tibia it becomes prominent and tender, producing a stump which will be difficult to fit. The nerves are drawn down as far as possible ligated and divided. The vascular stumps are secured and the muscles are approximated with fascial sutures. The fascia of the posterior flap is sutured over the end of the stump so that the muscle surface is carefully covered. The anterior skin fascia flap is pulled downward and sutured to the posterior fascial layer.

FRACTURES OF THE SHAFT OF THE TIBIA AND THE FIBULA

The shafts of both bones of the leg are

fractured more commonly in young adults and children. If the injury is caused by indirect violence the tibia usually breaks at its weakest point, which is the junction of the middle and the lower thirds; the fibula usually fractures at a higher level. If the cause is direct violence, the bones are broken at the same level, the fractures being transverse and at the site of injury. The lower fragment is pulled upward by the action of the calf muscles, the weight of the foot produces outward rotation.

In the treatment of these fractures, reduction may be difficult. The knee always should be flexed to relax the calf muscles. To check on proper alignment, the inner margin of the great toe, the internal malleolus and the inner margin of the patella should all be in the same line.

The Ankle

The ankle consists of the ankle joint (the tibia and the fibula proximally and the talus distally) and those structures which surround it (Fig. 683). The two malleoli can be felt distinctly, the lateral being less prominent, descending lower and lying farther back than the medial. The tip of the lateral malleolus is about one half inch below and behind the tip of its corresponding bony prominence. Anterior to the lateral malleolus and lateral to the tendon of the peroneus tertius is a shallow depression which indicates the level of the ankle joint. A similar depression lies between the medial malleolus and the tibia's anterior tendon. At these two points the ankle joint is very superficial and when fluid is present these areas become filled and form soft projections. If the foot is forcibly plantar flexed the talus (astragalus) slides forward out of its socket and produces a prominence which is most apparent in front of the lateral malleolus. The medial or internal malleolus is large, flat and prominent. The ankle joint lies approximately one half inch above the tip of the internal malleolus.

The *tendo calcaneus* (*achillis*) stands out prominently at the back of the ankle between it and the malleoli are two hollowed grooves. Over the front of the ankle the tendons of the extensor muscles stand out in bold relief especially when the joint is flexed. From within outward they are (Figs. 683 and 684) the tendon of the anterior tibial muscle, the extensor hallucis longus, the extensor digitorum longus and the peroneus tertius. Above and behind the medial malleolus the tendons of the poste-

rior tibial and the flexor digitorum muscles are noted, the former lies closer to the bone. Behind the lateral malleolus, the long and the short peroneal tendons can be felt lying close to the edge of the fibula, the tendon of the smaller muscle being the closer to it. The interval between the medial malleolus and the calcaneus is crossed by the lacinate (internal annular) ligament, which also forms an osteoaponeurotic canal in which are found the tendons of the flexor digitorum longus, the flexor hallucis longus and the posterior tibial muscles (Fig. 683C). The tendon of the *tibialis posterior* muscle lies immediately behind the back of the medial malleolus and is succeeded by the tendons of the flexor digitorum longus and the flexor hallucis longus. The posterior tibial vessels and nerves lie between the last two named tendons. The tendons lie in close relation to the ankle joint but the calcaneal tendon is separated from it by a considerable interval. A fairly wide space which is filled with fatty areolar tissue also exists between the flexor hallucis longus tendon and the posterior tibial vessels so that there is little chance of damage when operating upon this tendon.

The skin about the ankle is thin and loosely attached to the subjacent parts. Owing to its proximity to the underlying malleoli it may be damaged by the pressure of a cast or a bed rest. The subcutaneous tissue varies both in quantity and character. Over the front of the ankle it is lax and free from fat; therefore, if edema is present, the skin will pit on pressure.




FIG 683 The structures surrounding the right ankle (A) seen from behind, (B) the lateral structures, (C) the medial structures

DFEP FASCIA

The *deep fascia* is strong and is directly continuous with the fascia which invests the leg and the foot. It forms five definite bands (in front of and at each side of the ankle) which maintain the tendons in contact with the bones and it exists in form of osteo-aponeurotic tunnels through which

the tendons and their synovial sheaths pass. The *five binding bands* are (Fig 683) the two anterior bands the transverse crural and the cruciate ligaments, one medial band the lacinate ligament, two lateral bands the peroneal retinacula.

The anterior thickening of the deep fascia has two divisions, an upper and a




FIG 684 The relations around the right ankle joint The deep fascia and the ligaments are shown in blue

lower The upper division or the *transverse crural ligament* stretches between the anterior borders of the tibia and the fibula immediately above the ankle joint. Beneath this ligament are the structures which pass from the front of the leg to the dorsum of the foot. With the exception of the tibialis anterior which lies separately they lie in one compartment. The structures from medial to lateral are the anterior tibial muscle, the extensor hallucis longus, the anterior tibial vessels, the deep peroneal nerve, the extensor digitorum longus, and the peroneus tertius (Figs 684 and 685B). The structures which pass over the superficial surface of this ligament are the long saphenous vein, the saphenous nerve and the superficial peroneal nerve.

The *cruciate ligament* is the lower division of the anterior thickening of deep fascia; it has been referred to as the inferior extensor retinaculum. It is the more

important of the two. Its shape resembles the letter 'Y', the stem of the letter being the lateral part of the ligament (Figs 683, 684 and 685B). The Y is placed on its side and lies across the dorsum of the foot close to the ankle joint. It is firmly attached to the anterior part of the upper surface of the calcaneum. The upper limb of the Y attaches to the medial malleolus; the lower part fuses with the deep fascia along the medial margin of the foot, and with the plantar fascia. The structures which pass beneath this ligament are identical with those passing under the transverse ligament. It splits to form two compartments. The medial of these is occupied by the tendon of the extensor hallucis longus, the lateral compartment by the peroneus tertius and the extensor digitorum longus. Each compartment is lined with a synovial sheath. The vessels and the nerves pass deeply to the ligament. The ligament usually does not




FIG. 685 The five binding bands around the ankle

form a compartment for the tibialis anterior tendon because the tendon runs either above or below the ligament.

The lacinate ligament (internal lateral) bridges the hollow between the medial malleolus and the calcaneus to both of which it is attached (Fig 685A). It has four borders and two surfaces. Of its borders the upper is continuous with two layers of fascia, the deep fascia of the leg, and the strong fascia which extends between the superficial and the deep muscles of the

calf. The lower border is continuous with the medial part of the plantar aponeurosis, the lateral border is attached to the tuberosity of the calcaneus and the medial is attached to the medial malleolus. Of its surfaces the superficial is related to the medial calcaneal vessels and nerves, which first pierce it and then cross it; the deep surface is related to the tendons, the vessels and the nerves passing in back of the leg to the sole of the foot. The e lie in a compartment, in the following order from

before backward (Fig. 654) the posterior tibial tendon the flexor digitorum longus the posterior tibial artery with its companion veins the posterior tibial nerve and the flexor hallucis longus. Each tendon is supplied with a synovial sheath of its own. Under the lower part of this ligament the artery and the nerve both divide into medial and lateral plantar branches.

The *peroneal retinacula* are two lateral thickened parts of the deep fascia they also have been referred to as the external annular ligaments. They bridge the groove between the lateral malleolus and the calcaneus (Fig. 655C). The *superior peroneal retinaculum* extends from the calcaneus to the lateral malleolus and binds the two peronei the longus and the brevis to the back of the lateral malleolus. The brevis lies closer to the bone. The *inferior peroneal retinaculum* is attached to the outer surfaces of the calcaneus. It is divided into two compartments by a septum which is attached to the peroneal tubercle. The superior retinaculum forms a common compartment for the peronei unlike the inferior retinaculum which forms two compartments.

TENDON SHEATHS

The *tendon sheaths* around the ankle joint are mucous sheaths which are placed anteriorly medially laterally and posteriorly. The *anterior sheaths* appear as three separate structures (Fig. 686). They are the sheath of the tibialis anterior which extends from the upper border of the transverse ligament to just below the ankle joint the sheaths of the extensor hallucis longus and of the extensor digitorum longus which extend from the malleoli to the base of the metatarsal bones. The *medial mucous sheaths* are also three in number (Fig. 683C) the sheath of the tibialis posterior which extends from about 2 inches above the medial malleolus to the insertion of the tendon at the navicular tuberosity the sheaths of the flexor hallucis longus and the flexor digitorum longus,




FIG. 686 The three tendon sheaths of the anterior aspect of the ankle

which extend from the medial malleolus to the middle of the sole of the foot. Near the head of the metatarsal bones these tendons acquire new sheaths resembling the arrangements seen in the fingers. Laterally the peroneus longus and brevis are enclosed in a sheath which extends 2 inches above the tip of the malleolus and 2 inches below it (Fig. 683B). Above the malleolus the tendons lie together in a single sheath but where they diverge the sheath provides each with a separate investment. Posteriorly the tendo achillis has a sheath which extends about 3 inches upward from the insertion of the tendon to the calcaneus.

VESSELS

The arteries around the ankle are mainly three in number (Fig. 687) the anterior

tibial the posterior tibial and the peroneal. The *anterior tibial artery* is continued beyond the line of the ankle joint as the *dorsalis pedis* (Fig 691). Proximal to the joint line the vessel is crossed by the tendon of the *extensor hallucis longus*. At a lower level it lies between the tendon of this muscle and the *extensor digitorum longus*. In the region of the ankle, it provides malleolar branches. The *posterior tibial artery* corresponds to the center of a line which connects the internal malleolus and the most prominent part of the heel. The artery terminates opposite the lower margin of the *lacinate ligament* where it divides into medial and lateral plantar ar-

teries. The calcaneal branches supply the tissues at the medial side of the heel. The anterior branch of the *peroneal artery* crosses the ankle joint in front of the *interosseous ligament* between the lower ends of the tibia and the fibula. The anterior and the posterior tibial arteries and the peroneal artery form an anastomotic network about the ankle and the heel regions.

THE ANKLE JOINT (TAILOCRURAL)

The *ankle joint* is a synovial joint of the hinge variety which unites the foot to the leg. Its great strength and stability are ensured by surrounding powerful ligaments and tendons as well as by a close inter-




FIG. 687 The arteries around the ankle, as seen from behind




FIG 688 The ligaments around the ankle joint

locking of its articulating surfaces. Because of its hinge action, the to and fro movements of walking are possible. When one walks the triceps surae (both heads of the gastrocnemius and the soleus) raises the heel from the ground and produces plantar flexion of the ankle joint. The four anterior crural muscles cause the foot to clear the ground and thus produce dorsiflexion of this joint. The malleoli grasp the sides of the talus, the latter transmitting the weight of the body to the tibia. The sharp tip of the lateral (fibular) malleolus can be felt a little less than an inch below the level of the blunt ending medial (tibial) malleolus. Since there are no muscles at the sides of the ankle, the malleoli are subcutaneous and may be palpated readily. With the exception of the tendo calcaneus, all tendons which cross the ankle joint (four in front and five behind) pass forward and become inserted into the foot anterior to the midtarsal joint.

BONES


The bones which enter into the formation of the ankle joint are the talus and the distal ends of the tibia and the fibula. The talus articulates with the bones of the leg by three of its surfaces: the upper, the medial and the lateral. The bones form a deep socket which receives the upper part of the talus. The roof of the joint is formed entirely by the tibia. As the two malleoli project downward, they grasp the talus firmly at each side, thus permitting only a slight degree of lateral or medial movement. The bones just mentioned are so intimately related with the tarsal bones and joints in

the mechanics and the alignment of the ankle joint that it is impossible to isolate the ankle joint from the rest of the foot in either clinical or anatomic discussions (see Joints of the Foot, p. 892).

LIGAMENTS

The bones which form the ankle joint are held together by a *capsular ligament* which is subdivided into anterior, posterior, lateral and medial ligaments (Fig. 688). (See also diagram at bottom of page.)

The capsule is loose in front and behind and tight at the sides. Proximally, it is attached to the margins of the articular surfaces of the tibial and the fibular epiphyses and distally to the margins of the superior articular surface of the talus except at the anterior aspect of the joint, where it extends forward to the neck of the bone. The *medial part* of this capsule is greatly thickened and is named the *deltoid ligament*. It is triangular in shape, with its apex attached above to the tip of the medial malleolus. Its base has a more extensive attachment, extending from the tubercle of the navicular to the plantar calcaneonavicular (spring) ligament, the neck of the talus and the sustentaculum tali to the body of the talus. Its medial surface is crossed by the tendons of the tibialis posterior and the flexor digitorum longus (Fig. 688B). If the foot is everted to an extreme degree, the deltoid ligament usually tears away from the medial malleolus rather than rupturing itself. It braces the spring ligament and helps to support the head of the talus and to preserve the arch of the foot.



The *lateral ligament* is weaker and less complete. Most authors divide it into three parts.

1. The *calcaneohubular ligament* extends parts (Figs 688 B and D).

downward and backward from in front of the apex of the lateral malleolus to the lateral surface of the calcaneus. The fibers are separated from the other fibers of the lateral ligament by some fatty and areolar tissues. The ligament is crossed by the peronei.

2. The *anterior talofibular ligament* passes horizontally forward and inward from the anterior aspect of the lateral malleolus to the lateral side of the neck of the talus.

3. The *posterior talofibular ligament* extends inward behind the joint from the inner surface of the lateral malleolus to the posterior process of the talus. It is the strongest of the three bands and binds the tubula to the talus in a rigid manner.

The *anterior ligament* of the ankle joint is a thin wide membrane which is composed chiefly of transverse fibers. It extends from the anterior margin of the distal surface of the tibia to the dorsal surface of the neck of the talus (Fig. 689 A). A cut across the foot immediately in front of the tibia will open the ankle joint at this point.

The *posterior ligament* is the weakest of all the ankle ligaments. It is thin, sometimes defective and difficult to define. It extends from the posterior border of the distal end of the tibia to the posterior surface of the talus. The tendon of the flexor hallucis longus acts as a strong posterior support for the joint.

SYNOVIAL MEMBRANE

The *synovial membrane* lines the capsular ligament and covers the intracapsular portion of the neck of the talus (Fig. 684). It passes up between the tibia and the fibula for about one-quarter of an inch and extends well forward onto the neck of the talus. A puncture wound or superficial incision made in front of the joint may enter

the joint cavity. The membrane is lax in front and behind where it is covered by the anterior and the posterior ligaments at which points the capsular ligament is thin and loose. It is continuous with the synovial membrane of the distal tibiofibular joint. A joint effusion bulges the synovial membrane and the weak capsule anteriorly and posteriorly.

VESSELS AND NERVES

The *nerves* to the ankle joint are derived from the anterior and the posterior tibial nerves.

Arteries (Figs 684 and 689)

Anterior From the medial to the lateral side lie the tibialis anterior, the extensor hallucis longus, the anterior tibial vessels, the anterior tibial nerves, the extensor digitorum longus and the peroneus tertius. The perforating branch of the peroneal vessels is found on the lateral malleolus. The inferior extensor retinaculum obliquely crosses the joint. The superficial structures which are found in this region are the branches of the musculocutaneous nerve, the superficial vessels, the long saphenous vein and the saphenous nerve on the medial malleolus.

Posterior The tendo calcaneus is separated from the posterior ligament by an interval of fatty areolar tissue which contains small vessels. Between the joint and the tendon are found the flexor hallucis longus, the posterior tibial nerves and vessels and the flexor digitorum longus, the latter structures being named in a lateromedial order. The vessels and the nerves are more superficial than the two flexors and overlap them. All of these structures are maintained in position by the flexor retinaculum.

Medial The tibialis posterior lies on the deltoid ligament above the sustentaculum tali and the flexor digitorum longus lies on the attachment of that ligament to the sustentaculum. The flexor retinaculum overlies the tendon.




FIG 689 Cross sections through the ankle and the foot (A) section taken through the malleoli (B) section taken through the calcaneus and the talus

Lateral The peroneus brevis lies on the posterior talofibular ligament and separates the peroneus longus from it. Its tendons are held down by a retinaculum of deep fascia; they have a common synovial sheath. The termination of the peroneal artery anastomoses with its perforating branch on this side of the joint. More superficially are the short saphenous vein and the sural nerve.

MOVEMENTS

The movements of the ankle joint involve

the joints of the foot as well. Inversion and eversion of the foot are effected by plantar flexion (true flexion) and dorsiflexion (extension). Plantar flexion and dorsiflexion are effected mainly at the ankle joint between the talus, the tibia and the fibula. Dorsiflexion is limited by the lengthening of the calf muscles; if the knee is flexed the range of movement is greater. Plantar flexion is produced by the gastrocnemius, the soleus and the flexor hallucis longus; it also is produced to a minor de-

gree by the *tibialis posterior*, the *peroneus longus* and the *plantaris* muscles. When the foot is moved so that the sole faces medially the movement is described as inversion; the contrary movement is eversion.

to their articular surfaces. The terminal branches of the *peroneal* vessels and the *posterior tibial* should be preserved. The anterior tendons are united to the *calcaneus* tendon or to the *periosteum* of the *tibia*. This




FIG. 690. Amputation through the ankle joint (Syme)

Inversion of the foot is brought about by the action of the *tibialis anterior* and the *tibialis posterior*; eversion is accomplished by the *peronei longus*, the *brevis* and the *tertius*. A greater range of inversion may be produced when the ankle joint is plantar flexed; this is due apparently to an increased range of metatarsal movement. The five tendons which pass behind the ankle are situated too close to the axis of the joint to act upon it; therefore if the *tendo calcaneus* is cut the power to plantar flex is lost.

SURGICAL CONSIDERATIONS

SYME'S AMPUTATION THROUGH THE ANKLE JOINT

This is a disarticulation with removal of both malleoli and the articular surface of the *tibia*. The incision passes under the heel from the tip of the lateral malleolus to a corresponding point on the medial malleolus (Fig. 690). The distal ends of the *tibia* and the *fibula* are exposed and these bones are sectioned about 1 cm. proximal

to their articular surfaces. The terminal branches of the *peroneal* vessels and the *posterior tibial* should be preserved. The anterior tendons are united to the *calcaneus* tendon or to the *periosteum* of the *tibia*. This

amputation provides a good end bearing stump but it is difficult to fit with a prosthesis without producing a wide and ugly looking ankle. In the *Pirogov* amputation the posterior portion of the *calcaneus* is sawed off and approximated to the sawed end of the *tibia* and the *fibula*. It is therefore a modified Syme's amputation; the only difference being that part of the *calcaneus* is retained and brought into contact with the divided lower ends of the *tibia* and the *fibula*.

DISLOCATIONS OF THE ANKLE JOINT

Dislocations of the ankle joint (between the *talus* and the *tibia* and the *fibula*) are classified depending upon the direction in which the foot passes, namely backward, forward, medial, lateral or upward. Lateral and medial displacements occur in association with Pott's fracture or fractures of the malleoli. In forward (anterior) dislocation, the ligaments or malleoli are torn, the heel is shortened and the distance from the malleoli to the heel is diminished; the distance




FIG 689 Cross sections through the ankle and the foot (A) section taken through the malleoli (B) section taken through the calcaneus and the talus

Lateral The peroneus brevis lies on the posterior talofibular ligament and separates the peroneus longus from it. Its tendons are held down by a retinaculum of deep fascia, they have a common synovial sheath. The termination of the peroneal artery anastomoses with its perforating branch on this side of the joint. More superficially are the short saphenous vein and the sural nerve.

MOVEMENTS

The movements of the ankle joint involve

the joints of the foot as well. Inversion and eversion of the foot are effected by plantar flexion (true flexion) and dorsiflexion (extension). Plantar flexion and dorsiflexion are effected mainly at the ankle joint between the talus, the tibia and the fibula. Dorsiflexion is limited by the lengthening of the calf muscles; if the knee is flexed the range of movement is greater. Plantar flexion is produced by the gastrocnemius, the soleus and the flexor hallucis longus, it also is produced to a minor de-

give by the *tibialis posterior* or the *peroneus* *lateralis* and the *plantaris* muscles. When the foot is moved so that the sole faces medially, the movement is described as inversion; the contrary movement is eversion.

to their articular surfaces. The terminal branches of the peroneal vessels and the posterior tibial should be preserved. The anterior tendons are united to the calcaneus tendon or to the periosteum of the tibia. This




FIG. 690 Amputation through the ankle joint (Syme)

Inversion of the foot is brought about by the action of the *tibialis anterior* and the *tibialis posterior*; eversion is accomplished by the *peronei longus*, the *brevis* and the *tertius*. A greater range of inversion may be produced when the ankle joint is plantar flexed; this is due apparently to an increased range of metatarsal movement. The five tendons which pass behind the ankle are situated too close to the axis of the joint to act upon it; therefore if the tendo calcaneus is cut, the power to plantar flex is lost.

SURGICAL CONSIDERATIONS

SYME'S AMPUTATION THROUGH THE ANKLE JOINT

This is a disarticulation with removal of both malleoli and the articular surface of the tibia. The incision passes under the heel, from the tip of the lateral malleolus to a corresponding point on the medial malleolus (Fig. 690). The distal ends of the tibia and the fibula are exposed, and these bones are sectioned about 1 cm. proximal

to their articular surfaces. The terminal branches of the peroneal vessels and the posterior tibial should be preserved. The anterior tendons are united to the calcaneus tendon or to the periosteum of the tibia. This

amputation provides a good end-bearing stump but it is difficult to fit with a prosthesis without producing a wide and ugly looking ankle.

In the *Pirogoff* amputation the posterior portion of the calcaneus is sawed off and approximated to the sawed end of the tibia and the fibula. It is, therefore, a modified Syme's amputation, the only difference being that part of the calcaneus is retained and brought into contact with the divided lower ends of the tibia and the fibula.

DISLOCATIONS OF THE ANKLE JOINT

Dislocations of the ankle joint (between the talus and the tibia and the fibula) are classified depending upon the direction in which the foot passes, namely backward, forward, medial lateral or upward. Lateral and medial displacements occur in association with Pott's fracture or fractures of the malleoli. In forward (anterior) dislocation the ligaments or malleoli are torn, the heel is shortened and the distance from the malleoli to the heel is diminished, the distance

from the malleoli to the toes, however, is increased. The foot appears to be lengthened, the normal hollows at the sides of the tendo achillis are obliterated, and the talus may be felt in front of the tibia. The malleoli appear to lie nearer the sole.

Backward dislocation is the most frequent type, this may be associated with a Pott's fracture. It results from extreme plantar flexion of the foot which tears the ligaments. Involvement of the malleoli and

the posterior articular edge of the tibia is usually present. The foot appears shortened, and the heel is prominent. The malleoli appear somewhat anteriorly. The distance from the malleoli to the heel is increased, while that from the malleoli to the toe is diminished.

Reduction is easy if the knee is bent to relax the tendo achillis and if proper traction and counter traction are applied.

The foot

The foot which is triangular in outline extends from the point of the heel to the tip of the toes (Fig. 691). It is divided into the *truncus* (posterior half) and the *metatarsus* (anterior half). The landmarks which are visible on the lateral aspect are in contrast with the more bulky medial markings.

LATERAL, MEDIAL AND DORSAL ASPECTS

The *lateral margin* of the foot rests in contact with the ground over its entire extent. Near the middle of this border the tuberosity of the base of the fifth metatarsal bone affords a landmark for the tarsometatarsal joint (Lisfranc). If a line is constructed between the tuberosity of the base of the fifth metatarsal and the tip of the lateral malleolus, and a point just anterior to the middle of this line is marked, the cuboid metatarsal joint (Chopart) is located.

The *medial aspect* of the foot is arched in contrast with the flat appearance of the lateral border. The medial border rests upon the ground only at the heel and the ball of the great toe. The sustentaculum tali is located about one inch below the medial malleolus. A definite prominence produced by the tuberosity of the navicular bone is felt by pressing one inch in front of and slightly below the level of the medial malleolus. This latter tuberosity is a useful surgical guide—it is the principal point of insertion of the tibialis posterior tendon. The depression which is below and behind it is a guide to the talonavicular joint.

The *dorsum* of the foot reveals a very

thin skin which is much less sensitive than that on the plantar surface. The subcutaneous tissue over the dorsum is very loose so that edema becomes quite prominent in this region. The veins are arranged in an arch the outline of which is apparent when one is in the erect posture. The large and the small saphenous veins arise from the marginal veins of this arch. The tendons in front of the ankle can be traced over this surface to their insertion. The tendon of the extensor hallucis longus passes forward to the great toe and the tendons of the extensor digitorum longus pass to the four lateral toes. A fibular muscular mass, the extensor digitorum brevis muscle, can be felt on the posterolateral aspect of the dorsum. The tendon of the peroneus brevis muscle passes forward under the lateral malleolus to its insertion into the tuberosity of the fifth metatarsal. The dorsalis pedis artery, a continuation of the anterior tibial artery, may be indicated on the surface by a line drawn midway between the two malleoli to the posterior extremity of the first interosseous space. To the lateral side of this vessel is the anterior tibial nerve.

THE SOLE OF THE FOOT (PLANTAR SURFACE)

The skin is thicker on the sole of the foot than it is over the dorsum. It is particularly thick over those points which bear weight (heel, ball of the big toe and lateral margins of the sole). Like the palm of the hand it is highly sensitive and contains numerous sweat glands. The *cutaneous nerves* are arranged in the following way (Fig. 692): the *medial plantar nerve* sup-



FIG 691 The foot seen in cross sectional views




FIG 692 The cutaneous nerve supply of the foot (A) the dorsum of the foot, (B) the plantar surface of the foot

plies the three and one half digits on the big toe side of the foot as the median nerve supplies the three and one half digits on the thumb of the hand the *lateral plantar nerve* which corresponds to the ulnar nerve of the hand supplies the remaining one and one half digits. The medial calcaneal branches of the posterior tibial nerve supply the skin under the heel.

The *superficial fascia* becomes thick and tough along the lateral border on the ball of the foot and at the heel. Traversing it are small but tough fibrous bands which subdivide the fatty tissue into small lobules. These bands also connect the skin with the deep fascia.

DEEP PLANTAR APONEUROSIS (DEEP FASCIA)

The deep (plantar) fascia arrangement resembles that of the hand (Fig 693). It lies superficial to the vessels, the nerves, the muscles and the tendons and consists of three portions: relatively thin medial and lateral parts and a very dense and strong intermediate part. This thickened strong central part is known as the *plantar aponeurosis*. It forms a dense fibrous sheet which is attached posteriorly to the cal




FIG 693 The plantar fascia




FIG 694 The four layers of muscles and tendons of the sole of the foot

circus and widens anteriorly to divide into five slips one for each toe (The palmar aponeurosis of the hand divides into four slips one for each finger but none for the thumb) The great toe, therefore has a different relationship to this fascia than that of the thumb to the deep fascia of the palm hence its mobility is diminished as compared with that of the thumb The slips to the toes are connected to the fibrous flexor sheaths and to the sides of the metatarsophalangeal joints On each toe the deep fascia is thickened to form curved plates called the *fibrous flexor sheaths* these hold the flexor tendons against the phalanges They are strong and dense opposite the phalanges but are thin and weak opposite the joints so that movements are not hindered The sheaths are attached to the margins of the phalanges and to the plantar ligaments and form with them a tunnel which is occupied by the long and the short flexor tendons This tunnel is lined with the synovial sheath that envelops the tendons

The medial division of the deep fascia covers the abductor hallucis muscle the lateral part of the fascia extends between the calcaneus and the tuberosity of the fifth metatarsal

MUSCLES AND TENDONS

The *muscles* and the *tendons* of the sole of the foot are arranged in four layers which are separated by fascial partitions in these the plantar nerves and vessels run (Fig 694) Only the muscles of layer number one cover the whole extent of the sole The muscles of the second layer are all connected to the flexor digitorum longus tendon and form an X shaped figure so that on each border of the foot the first and the third layers come into contact with each other

The *first layer* consists of the abductor hallucis the flexor digitorum brevis and the abductor digiti quinti (Fig 694A) The flexor digitorum brevis divides into four tendons which pass to the four lateral toes

and become inserted into the middle phalanges The *abductor hallucis* is inserted into the medial side of the base of the proximal phalanx of the great toe, and the *abductor digiti minimi* is inserted into the lateral side of the base of the proximal phalanx of the little toe (Fig 696) The names of these muscles indicate their actions The lateral plantar nerve supplies the abductor digiti minimi, and the other two muscles are supplied by the medial plantar nerve

The *second layer* of muscles consists of the flexor digitorum longus the flexor accessorius (quadratus plantae) the lumbricals and the flexor hallucis longus (Fig 694B)

The tendon of the *flexor digitorum longus* passes forward and laterally from the right flexor retinaculum At first it lies on the medial side of the sustentaculum tali and then it crosses superficial to the flexor hallucis longus tendon, which separates it from the plantar calcaneonavicular ligament This tendon constitutes the central structure in this layer of muscles It should be recalled that this tendon has crossed superficially to the tendon of the tibialis posterior at the back of the medial malleolus (Fig 685A) it now appears from under cover of the abductor hallucis and crosses superficially to the tendon of the flexor hallucis longus Therefore it appears superficial at two points, once where it crosses the tibialis posterior and again where it crosses the flexor hallucis longus As it receives the insertion of the flexor digitorum accessorius it divides into four tendons for the lateral four toes These tendons resemble those of the flexor digitorum profundus in the hand since they pass through rings made by the splitting of the fibers of the short flexor tendon and then pass on to become inserted into the distal phalanges (Fig 694B)

The *flexor digitorum accessorius (quadratus plantae) muscle* arises by two heads, one from each side of the calcaneus The medial head, which is wide and fleshy,

arises from the medial surface of the calcaneus, the lateral head which is narrow and tendinous, arises from the lateral margin of the plantar surface of the bone. It inserts into the tendon of the flexor digitorum longus, in the region of the middle of the sole and acts as a flexor of the toes (Fig 694B). It is supplied by the lateral plantar nerve.

The *lumbricales* are four in number and are more slender than those of the hand. They arise from the tendons of the flexor digitorum longus and proceed to the four lateral toes, where each is inserted into the tibial side of the dorsal expansion of the corresponding extensor tendons. The lumbricalis to the second toe arises from only one tendon—the tendon of the second toe, but the other three lumbricales arise in a bipennate manner from the adjacent sides of the tendons to the second and the third, the third and the fourth, and the fourth and the fifth toes. The first or most medial, lumbricalis is supplied by the medial plantar nerve; the other three are supplied by the lateral plantar nerve. These muscles flex the toes at the metatarsophalangeal joints and extend them at the interphalangeal joints.

The *flexor hallucis longus tendon* after supplying a slip to the tendon of the flexor digitorum longus passes forward to the big toe, where it inserts into the base of the terminal phalanx. It crosses deeply to the tendon of the flexor digitorum longus and lies below the lateral part of the plantar calcaneonavicular ligament. Its name indicates its action; it receives its nerve supply on the back of the leg from the posterior tibial nerve.

The *third layer of muscles* consists of the flexor hallucis brevis, the adductor hallucis (oblique and transverse heads) and the flexor digiti quinti brevis (Fig 694C). The muscles of this layer are limited to the anterior part of the foot. A plan of origin of these muscles may be remembered if it is recalled that the base of each of the five metatarsal bones gives origin to a muscle,

therefore, the first gives rise to the flexor hallucis brevis, the second, third and fourth to the adductor hallucis (oblique head) and the fifth to the flexor digiti quinti.

The *flexor hallucis brevis* covers the plantar aspect of the first metatarsal, its belly divides into two heads. The medial head is inserted, in common with the adductor hallucis, into the medial side of the base of the proximal phalanx of the hallux, and the lateral head is inserted into the lateral side of the same bone in common with the adductor (Fig 696). A sesamoid bone usually is developed in each tendon of insertion, it flexes the first metatarsophalangeal joint. The nerve supply to this muscle is derived from the medial plantar nerve.

The *adductor hallucis muscle* resembles the adductor pollicis in that it has oblique and transverse heads. It arises from the second, the third and the fourth metatarsal bones and is inserted in common with the lateral head of the flexor hallucis brevis. The transverse head is a small muscle bundle which is located under the heads of the metatarsal bones. It arises from the plantar ligaments of the third, the fourth and the fifth metatarsophalangeal joints and is inserted in common with the preceding muscle. The nerve supply is derived from the lateral plantar nerve.

The *flexor digiti quinti brevis* is the short flexor of the little toe. It is a single fleshy muscle slip which arises from the base of the fifth metatarsal bone and the peroneus longus tendon. It inserts into the lateral side of the base of the proximal phalanx of the little toe and flexes the little toe at the metatarsophalangeal joint. It is supplied by the lateral plantar nerve.

The *fourth layer of muscles* consists of the interossei (plantar and dorsal), the tendon of the peroneus longus and the tendon of the tibialis posterior (Fig 694D).

The *interossei* are seven interosseous muscles—three plantar and four dorsal. As in the hand the dorsal are abductors and the plantar are adductors, but the line of action passes through the second digit and not




FIG. 695 The vessels and the nerves of the sole of the foot
(A) superficial dissection (B) deep dissection

the third as in the hand. They lie between the metatarsal bones and arise from them. They abduct and adduct the lateral four toes to and from the middle line of the second toe and also aid in flexion of the metatarsophalangeal joints. The three *plantar interossei* arise from the plantar and the medial surfaces of the lateral three metatarsal bones and each is inserted onto the medial side of the corresponding toe. They are so placed that they adduct the lateral three toes toward the second toe. The

four *dorsal interossei* arise by two heads from the dorsal parts of the sides of the metatarsal bones between which they lie. They are inserted in the following manner (Fig. 696) the first on the medial side of the second toe, the second on the lateral side of the same toe, the third on the lateral side of the third toe and the fourth on the lateral side of the fourth toe. By this arrangement they abduct the second, the third and the fourth toes from the middle line of the second toe.

The *peroneus longus tendon* runs obliquely and medially across the sole of the foot, in the groove on the plantar surface of the cuboid bone, to become inserted into the base of the first metatarsal bone and the adjoining part of the medial cuneiform. It is held in place by a strong fibrous sheath which is derived from the long plantar ligament. This tendon is situated below the transverse arch of the foot and, by taking the strain off the interosseous ligaments, it aids in maintaining the arch. Together with the tendon of the *tibialis anterior*, it forms a *tendon sling* for the anterior part of the tarsus. The common synovial sheath which envelopes the *peronei longus* and *brevis* behind the malleolus, commonly is continued with the synovial sheath of the *longus* into the sole of the foot. Therefore, any injury to either tendon in the region of the ankle may find a pathway into the sole by means of the sheath. The *peroneus longus* is an evolver of the foot. It is supplied by the superficial peroneal (musculo-cutaneous) nerve.

After the *tibialis posterior tendon* enters the sole it divides into two parts. The medial is the larger part and inserts into the tuberosity of the navicular bone; the lateral part divides into slips which spread out from it to every bone of the tarsus except the talus and also to the bases of the second, the third and the fourth metatarsal bones (Fig 696). The tendon lies on the plantar surface of the so-called spring ligament (calcaneonavicular) (Fig 688C). This muscle is an inverter and flexor of the foot. Because of its close association with the spring ligament it is of some importance in supporting the arch. It is supplied by the posterior tibial nerve.

VESSELS AND NERVES

The posterior tibial artery divides into the lateral and the medial plantar arteries at the distal border of the lacinate ligament (Fig 695).

The *lateral plantar artery* is larger than the medial and is considered the continua-

tion of the posterior tibial. It appears from under cover of the abductor hallucis muscle and, with its companion nerve, runs forward and laterally between the first and the second layers of muscles (*flexor digitorum brevis* and *flexor accessorius*) (Fig 695A). It then dips deeper as it continues medially between the third and the fourth layers (*adductor hallucis obliquus* and the *interossei*) (Fig 695B). At the back end of the first intermetatarsal space it anastomoses with the profunda branch of the *dorsalis pedis* artery (anterior tibial), thus forming a deep plantar arterial arch. In the first part of its course the artery gives off calcaneal branches to the skin of the heel and muscular and cutaneous branches to the skin of the sole of the foot. The *plantar arch* gives off perforating branches, which pass upward through the lateral three intermetatarsal spaces, and plantar digital arteries to the lateral three clefts and the lateral side of the little toe. The *arteria magna hallucis* supplies the cleft between the great toe and the second toe, and sends a branch to the medial side of the former; it is derived from the *dorsalis pedis* at its point of union with the plantar arch.

The *medial plantar artery* varies in size but usually is small. It is accompanied by its *venae comitantes* and passes along the medial side of the medial plantar nerve. It ends by joining the digital branch which the first metatarsal artery sends to the medial side of the big toe.

Nerves The *medial plantar nerve* arises from the posterior tibial nerve; it corresponds to the median nerve of the hand (Fig 695). It passes forward into the sole of the foot under cover of the abductor hallucis muscle, accompanied by the medial plantar vessels, which are on its medial side. Reaching the lateral border of the abductor hallucis muscle the nerve runs forward in the interval between that muscle and the *flexor digitorum brevis*. It supplies sensory branches to the inner side of the sole of the foot to the plantar aspect of

BONES

The *tarsus* consists of seven tarsal bones which may be divided conveniently into a posterior row (talus and calcaneus), a middle row (navicular) and an anterior row (three cuneiform bones and the cuboid) (Figs 696 and 697)

hidden below by the tibia and is grasped between the malleoli at each side. The posterior surface of the body has two tubercles a medial and a posterior separated by a groove for the flexor hallucis longus tendon.

The *calcaneus* (as *calcis*) is the heel




FIG 697 Side views of the bones of the right foot
(A) lateral view (B) medial view

The *talus* (astragalus ankle bone) is discussed also in the region of the ankle joint (p 876). It rests upon the anterior two thirds of the calcaneus and has a body, a neck, and a head. It lies below the tibia, sits on the upper surface of the calcaneus and is gripped by the two malleoli. The head of the bone is anterior and articulates with the navicular; below it rests upon the plantar calcaneonavicular (spring) ligament and the calcaneus. If the foot is inverted (so that the sole faces medially) the head of the talus is felt as a rounded prominence about one inch in front of the lateral malleolus. The neck is the constricted portion of the bone which is roughened by the attachment of ligaments. The body is

bone. It has a long arched anterior two thirds which supports the talus; the posterior one third forms the prominence of the heel which rests upon the ground. The anterior surface articulates with the cuboid, and the posterior third of the upper surface is saddle shaped. The lateral surface is almost entirely subcutaneous; it is felt easily below the lateral malleolus as a wide surface that extends forward about two inches from the back of the heel. On the medial side the sustentaculum tali is palpable. It is a horizontal projecting shelf which provides the bony resistance felt about a thumb's breadth below the medial malleolus.

The *navicular* bone (*scaphoid*) is on the

medial side of the foot. It articulates with the head of the talus posteriorly and with the three cuneiforms anteriorly. On its medial side is its tuberosity, which is useful as a landmark. This tuberosity forms a prominence which is felt easily about an inch below and in front of the medial malleolus midway between the back of the heel and the root of the big toe.

The three cuneiform bones are termed the first (medial), the second (intermediate) and the third (lateral). They articulate with the navicular posteriorly and with the first three metatarsals anteriorly. They are wedge shaped, are placed side by side and articulate with each other. The lateral cuneiform articulates with the cuboid and the fourth metatarsal while the intermediate and the medial cuneiforms grip the base of the second metatarsal between them. Since the second cuneiform is shorter than the other two, the base of the second metatarsal articulates on its medial and lateral sides with the first and the third cuneiforms respectively.

The *cuboid* lies on the lateral side of the foot and articulates posteriorly with the calcaneus and anteriorly with the fourth and the fifth metatarsal. Its medial surface articulates with the third cuneiform and the navicular and its plantar surface presents an oblique groove which lodges the tendon of the peroneus longus.

The *metatarsus* is composed of five metatarsal bones which are numbered one to five from medial to lateral. Each bone has a head or distal end, a body or midportion and a base or proximal end. The bases of the first, the second and the third metatarsals articulate with the three cuneiforms and the bases of the fourth and the fifth with the cuboid. These bases also articulate with each other, the heads articulate with the proximal phalanges. The bodies present a triangular shape on section and are concave in their long axes on the plantar surfaces. The first metatarsal is the shortest and the stoutest and in the majority of people its head extends as far forward as




FIG. 695 The accessory bones of the foot

that of the second metatarsal. The metatarsal bones can be felt individually through the anterior part of the tarsus under the extensor tendons. The base of the fifth metatarsal lies proximal to the main metatarsal joint line and forms a prominent landmark on the outer margin of the foot.

The *toes* are numbered from medial to lateral but the first toe is called the hallux, and the little toe the digitus minimus. The bones of the toes are the *phalanges*. The big toe has two phalanges but all of the others have three: a proximal, a middle and a distal phalanx. Each proximal phalanx articulates with the head of a metatarsal bone to form the *metatarsophalangeal joint*. The middle phalanx articulates with the other two to form the *interphalangeal joints*. The proximal end of each phalanx is called its base and its distal end is its head.

The *accessory bones* of the foot are of practical importance, since they may be mistaken on x-ray films for fractures. Although similar bones occur in the hand,

BONES

The *tarsus* consists of seven tarsal bones which may be divided conveniently into a posterior row (talus and calcaneus), a middle row (navicular) and an anterior row (three cuneiform bones and the cuboid) (Figs 696 and 697)

hidden below by the tibia and is grasped between the malleoli at each side. The posterior surface of the body has two tubercles, a medial and a posterior, separated by a groove for the flexor hallucis longus tendon.

The *calcaneus* (*os calcis*) is the heel




FIG. 697. Side views of the bones of the right foot.
(A) lateral view (B) medial view

The *talus* (astragalus, ankle bone) is discussed also in the region of the ankle joint (p. 876). It rests upon the anterior two thirds of the calcaneus and has a body, a neck, and a head. It lies below the tibia, sits on the upper surface of the calcaneus and is gripped by the two malleoli. The head of the bone is anterior and articulates with the navicular. Below it rests upon the plantar calcaneonavicular (spring) ligament and the calcaneus. If the foot is inverted (so that the sole faces medially) the head of the talus is felt as a rounded prominence about one inch in front of the lateral malleolus. The neck is the constricted portion of the bone which is roughened by the attachment of ligaments. The body is

hidden below by the tibia and is grasped between the malleoli at each side. The posterior surface of the body has two tubercles, a medial and a posterior, separated by a groove for the flexor hallucis longus tendon. The *calcaneus* (*os calcis*) is the heel bone. It has a long arched anterior two thirds which supports the talus; the posterior one third forms the prominence of the heel which rests upon the ground. The anterior surface articulates with the cuboid, and the posterior third of the upper surface is saddle-shaped. The lateral surface is almost entirely subcutaneous; it is felt easily below the lateral malleolus as a wide surface that extends forward about two inches from the back of the heel. On the medial side the sustentaculum tali is palpable. It is a horizontal projecting shelf which provides the bony resistance felt about a thumb's breadth below the medial malleolus.

The *navicular* bone (*scaphoid*) is on the

the talus articulates with the anterior and the posterior facets of the calcaneus. The anterior talocalcaneal joint is continuous with the talonavicular joint. The two parts of the joint are separated by the strong interosseous talocalcaneal ligament

bridge over the groove in which the peroneus longus tendon lies. The *short plantar ligament* is attached to a groove at the under surface of the calcaneus and to the ridge forming the posterior boundary of the groove on the cuboid.




FIG. 699 The six tarsal joints. Some of the associated ligaments also are shown.

3 The *calcaneocuboid joint* is a distinct joint formed by the anterior surface of the calcaneus which articulates with the posterior surface of the cuboid. Its cavity does not communicate with the cavities of neighboring joints. It has a capsular ligament which is strengthened inferiorly by the long and the short plantar ligaments. The long plantar ligament which lies superficial to the short, is attached posteriorly to the plantar surface of the calcaneus as far forward as its anterior tubercle (Fig. 700). In front it attaches to the ridge on the cuboid but some fibers are continued onward to the bases of the third, the fourth and the fifth metatarsal bones and thus

The talocalcaneonavicular and the calcaneocuboid joints together form the *transverse tarsal joint*. This articulation plus the talocalcaneal joint are involved in the movements of inversion and eversion. The two joints which form the transverse tarsal joint do not communicate with each other; they lie in almost the same coronal plane. This plane is indicated by a line drawn from a point immediately behind the tuberosity of the navicular to a point half an inch behind the base of the fifth metatarsal.

4 The *cuneonavicular joint* is formed by the navicular bone behind and the three cuneiforms in front. Its cavity is continuous with the joint cavity of the metatarsal

they are so seldom seen on the x ray film that they cannot compare in importance with those of the foot. Accessory bones have been divided into two classes (1) the sesamoids which are regular constituents of the skeleton, and (2) the true accessory bones which are small occasional ossicles that occur in definite sites. In the vast majority of cases they are bilateral, hence the importance of examining both feet by x ray. They occur in about 25 per cent of human feet (Pfitzner). McGregor lists the following twenty accessory bones of the feet (Fig 698)

- 1 Os tibiale externum
- 2 Os trigonum (accessory astragalus)
- 3 Os vesalianum tarsi
- 4 Secondary os calcis
- 5 Secondary cuboid
- 6 Astragaloscapoid bone of Pirie
- 7 Intermetatarsium
- 8 Os intercuneiforme
- 9 Os piracuneiforme of Cameron and Carlier
- 10 Os uncinatum
- 11 Astragalus secundarius
- 12 Os subtibiale
- 13 Os sustentaculum proprium
- 14 Peroneal process of the os calcis
- 15 Sesamum peroneum
- 16 Sesamoid of the flexor hallucis brevis
- 17 Trochlear process of the head of the astragalus
- 18 Process from the middle of the upper surface of the astragalus
- 19 Spurs of the os calcis
- 20 Spurs of the phalanges

The *phalangeal spurs* are found on any of the distal phalanges especially those of the great toe. They may grow from either side of the base of the phalanx and rarely if ever cause symptoms.

JOINTS AND LIGAMENTS

Six tarsal joints will be discussed (Fig 699)

1 The *talocalcaneal joint* is situated between the large facet on the lower surface of the talus and the corresponding facet

on the middle of the upper surface of the calcaneus. It possesses a capsular ligament which is attached to the margins of the articular areas of the two bones. Anteriorly, its capsule blends with the interosseous ligament, which firmly binds the two bones together. This ligament is attached to the inferior surface of the neck of the talus above and to the upper surface of the calcaneal joint. The capsular ligament, which is attached to the bones near its margins of the articular facet, is divided into anterior, posterior, lateral and medial talocalcaneal ligaments. They are composed of short fibers except the anterior which is a continuation of the interosseous talocalcaneal ligament.

2 The *talocalcaneonavicular joint* is considered the most important of the tarsal joints. It is situated between the rounded head of the talus and a socket formed for it by the posterior surface of the navicular, the upper surface of the spring ligament and the sustentaculum tali. The medial end of the ligamentum bifurcatum completes the lateral side of the socket. This ligament extends between the anterior part of the superior surface of the calcaneus and the lateral side of the navicular. This three-boned joint conforms to a ball and socket variety, unlike other joints of that variety, its socket is not rigid. The joint is situated at the summit of the longitudinal arch of the foot. Its maintenance in a normal position is dependent upon the structures which protect the longitudinal arch. The plantar calcaneonavicular (spring) ligament passes between the anterior border of the sustentaculum tali and the navicular and is in contact with the inferomedial part of the head of the talus. Some authors prefer to talk about the 'subastragaloid' joint which is a large region of articulation between the talus above and the calcaneus and the navicular below and in front. The talus is not a keystone bone since it is not wedged in between the calcaneus and the navicular, free movement is possible. In the talocalcaneal segment the under surface of

the distal articulates with the inferior and the posterior facets of the calcaneus. The anterior talocalcaneal joint is continuous with the talonavicular joint. The two parts of the joint are separated by the strong anterior talocalcaneal ligament.

bridge over the groove in which the peroneus longus tendon lies. The short plantar ligament is attached to a groove at the under surface of the calcaneus and to the ridge forming the posterior boundary of the groove on the cuboid.




FIG. 699 The six tarsal joints. Some of the associated ligaments also are shown.

3 The *calcaneocuboid joint* is a distinct joint formed by the anterior surface of the calcaneus which articulates with the posterior surface of the cuboid. Its cavity does not communicate with the cavities of neighboring joints. It has a capsular ligament which is strengthened inferiorly by the long and the short plantar ligaments. The long plantar ligament which lies superficial to the short is attached posteriorly to the plantar surface of the calcaneus as far forward as its anterior tubercle (Fig. 700). In front it attaches to the ridge of the cuboid but some fibers are continued onward to the bases of the third, the fourth and the fifth metatarsal bones and thus

The talocalcaneonavicular and the calcaneocuboid joints together form the *transverse tarsal joint*. This articulation plus the talocalcaneal joint are involved in the movements of inversion and eversion. The two joints which form the transverse tarsal joint do not communicate with each other; they lie in almost the same coronal plane. This plane is indicated by a line drawn from a point immediately behind the tuberosity of the navicular to a point half an inch behind the base of the fifth metatarsal.

4 The *cuneonavicular joint* is formed by the navicular bone behind and the three cuneiforms in front. Its cavity is continuous with the joint cavity of the metatarsals.

cuneiform and the corresponding intermetatarsal joints. When the navicular and the cuboid bones contact each other, the cubo-cuneiform joint also is continuous with the joint cavity of the cuneonavicular. The capsular ligament of the joint is

fifth joints. Because of the shortness of the intermediate cuneiform, the base of the second metatarsal projects farther backward between the medial and the lateral cuneiform bones, the line being interrupted at this point. The bases of the first three,




FIG. 700 The ligaments and other supporting structures of the foot. (A) The right foot seen from below. (B) The peroneus longus tendon. (C) The spring ligament and the plantar aponeurosis.

strengthened by the dorsal and the plantar ligaments.

5 The *cubometatarsal joint* articulates with the two lateral metatarsal bones. In this way the joint is placed between the cuboid bone behind and the bases of the fourth and the fifth metatarsal bones in front.

6 The *tarsometatarsal joint* exists between the base of the big toe metatarsal and the first cuneiform. Like the corresponding joint of the hand it is an independent joint with a separate synovial lining.

The *tarsometatarsal joints* form an oblique line which runs laterally and backward across the foot from the first to the

the fourth and the fifth cuneiforms articulate with the cuboid. The metatarsals are attached firmly to the cuneiform and the cuboid bones by the dorsal, the plantar and the interosseous ligaments.

The *metatarsophalangeal joints* are formed between the heads of the metatarsal bones and the bases of the proximal row of phalanges. The capsular ligament which surrounds the joint is attached to the bone near the margins of the articular surface and is reinforced at the side to form the collateral ligaments. Its plantar part is thick, forming the so-called plantar ligament, its dorsal part is thin and is fused with the extensor tendon so that the latter

as in effect the dorsal ligament of the first metatarsophalangeal joint

The *interphalangeal joints* are those which exist between the phalanges of the toes; they resemble those of the fingers. The ligaments that unite them include in

so called 'spring' ligament, extends from the sustentaculum tali to the navicular bone (Fig. 700). It is situated under the head of the talus and is an important factor in supporting the arch of the foot.

3 The *long plantar ligament* is attached




FIG. 701 The longitudinal arch of the foot

addition to the articular capsule the collateral the dorsal and the accessory plantar.

The *ligaments* which as a rule unite adjacent bones are the dorsal the plantar and the interosseous (Figs. 699 and 700). The plantar ligaments situated in the concavity of the arches of the foot are stronger than the dorsal. Besides those which already have been discussed certain ligaments require special mention.

1 The *interosseous talocalcaneal ligament* is a strong band lying in the tarsal sinus and separating the posterior talocalcaneal joint from the talocalcaneal navicular joint.

2 The *inferior calcaneonavicular* or the

posterior to the under surface of the os calcis and anteriorly to the cuboid and to the bases of the second, the third and the fourth metatarsals. It therefore converts the groove of the peroneus longus into a canal.

4 The *short plantar ligament* is about one inch long. It runs under cover of the long plantar from the front of the under surface of the os calcis to the cuboid.

5 The *bifurcate ligament*, or the so called Y-shaped ligament of Chopart, arises by its stem from the front of the upper surface of the os calcis and divides into two branches which pass to the upper surfaces of the cuboid and the navicular.

It crosses the line of the Chopart amputation (intertarsal)

ARCHES

The feet have acquired arches for four main reasons (1) to distribute the body weight properly (2) to give elasticity and spring to the step (3) to break the shock that results from running walking and jumping (4) to provide space for soft tissues which lie in the arch and thereby prevent undue pressure. The longitudinal and the transverse arches are described (Fig 701)

The *longitudinal arch* is divided into two columns namely a *medial column* and a *lateral column*, both of which rest upon a common pillar posteriorly namely the tuberosity of the calcaneus. The *inner* or *medial column* of the longitudinal arch is made up of the calcaneus the talus the navicular the three cuneiforms and the three inner metatarsals (Fig 701C). This inner arch is high and is easily seen if normal. It is absent in individuals with flat feet but is increased in pes cavus. It consists of more segments than the outer arch has more elasticity and is essentially the "arch of movement". The *outer* or *lateral column* of the longitudinal arch is formed by the calcaneus the cuboid and the two outer metatarsals. This arch is low, so that the outer border of the foot touches the ground along its entire length. The inner arch being high only touches the ground behind at the tuberosity of the calcaneus and in front at the head of the first metatarsal bone (ball of the great toe). The parts of the foot which normally bear the body weight and transmit it to the ground are arranged in tripod fashion at the tuberosity of the calcaneus the head of the first metatarsal and the head of the fifth metatarsal. In the young child the arching of the foot may be masked by a plantar fat pad so that the baby's foot looks flat.

The *transverse arches* are a series of arches which extend from the arch formed

by the heads of the metatarsals and backward to the arch formed by the navicular and the cuboid bones. The metatarsals and the tarsal bones are arranged so that their convexity is on the dorsum and the concavity is on the plantar aspect. If the transverse arch formed by the heads of the metatarsals becomes flattened the digital vessels and nerves which normally are protected by it are pressed upon and pain results.

The arches must be maintained or supported by definite structures. These supporting structures are (1) the muscles and the tendons (2) the ligaments (3) the fasciae and (4) the bones.

Supporting Tendons. Of the tendons which support the arches two are important. They are the peroneus longus and the tibialis posterior. The *peroneus longus tendon* passes down the lateral side of the leg and across the lateral side of the foot turns at right angles on itself and continues across the sole of the foot from lateral to medial (Figs 700 and 701). In this part of its course it lies in a tunnel formed by the cuboid and the long plantar ligament. It is inserted into the outer side of the first cuneiform bone and the base of the first metatarsal. It therefore acts as a sling for the longitudinal arch about its middle. It also forms a bolstering across the transverse arch thus supporting it. As it abducts and everts the foot it lowers the longitudinal arch. It is believed by some anatomists that paralysis of this muscle increases the arch. The *tendon of the tibialis posterior* has its main insertion about the middle of the longitudinal arch to the under surface of the navicular. Additional support is given to this arch as it sends a tendinous slip into every bone of the tarsus except the talus and also the bases of the second the third and the fourth metatarsal bones. The function of the tendon of the tibialis posterior is similar to that of the peroneus longus and balances it on the inner side. It supports the spring ligament and adducts and inverts the foot.

Muscles. The *muscles* which support the arches do so by pulling the two pillars of the arches closer together or directly upward. Those muscles which adduct and invert the foot increase the longitudinal arch while those which abduct and evert flatten it. Therefore the long flexors of the toes and the short muscles of the foot pull the pillars together and increase the arch. The short muscles can withstand the strain better than the ligamentous structures. So powerful are these short muscles as arch maintainers that they may increase the arch and produce a *pes cavus*. The transverse arch is maintained mainly by the transverse head of the adductor hallucis and to a lesser degree by its oblique head.

Ligaments. The *ligaments* which are associated with arch support are weak over the *dorsum* of the foot but are powerful over the sole. All the ligaments in this region are important but a few require special mention (Fig. 700). The *inferior calcaneoscler (spring) ligament* is an important structure in the support of the longitudinal arch. It is placed under the weakest point (the head of the talus) and thereby prevents it from sinking between the calcaneus and the navicular. When weight falls upon the talus this strong ligament gives a little but being very elastic pulls the head of the bone immediately back into position when the superimposed weight is removed. The *long plantar ligament* is a powerful structure which is attached to the under surface of the calcaneus and to the inferior surface of the cuboid whence it continues forward to the bases of the second, the third and the fourth metatarsal bones. The *short plantar (calcaneocuboid) ligament* passes obliquely forward and medially from the under surface of the calcaneus to the posterior part of the cuboid where the long plantar ligament conceals it. The transverse arch is maintained by the support of the plantar intertarsal and the tarsometatarsal ligaments.

Fascia. The *fascia* also plays its part in supporting the arches. The intermediate



FIG. 702 The toes

portion of the *plantar aponeurosis* is attached to the extremities of the arch namely the posterior part of the calcaneus behind and the head of all the metatarsals and the proximal phalanges in front (Fig. 700C). In this way it holds the extremities of the arch together.

The form of the bones also has a supporting value. They are broader in the *dorsum* of the foot thus making less support necessary than if the reverse were true.

INVERSION AND EVERSION OF THE FOOT

Rotating the sole of the foot inward (inversion) around the long axis of the foot is performed by the tibialis anterior and the posterior muscles assisted by the flexors of the toes. Rotating the sole outward (eversion) around the long axis of the foot is brought about in the following way: when the foot is plantar flexed it is produced by the three peronei (longus, brevis and tertius). When the foot is dorsiflexed the movement is performed by the extensor digitorum longus. This last statement may be verified if the foot is plantar flexed and everted strongly. In this position the strain is felt on the outer side of the leg over the peronei muscles. If the foot is everted and dorsiflexed no strain is felt over the peronei but the strain is taken by the extensor longus which can be seen and felt. Orthopedic surgeons utilized this fact when they found that if the extensor longus digitorum were paralyzed the foot could be everted in plantar flexion but not in dorsiflexion.

TOES

The toes or digits are numbered from the medial to the lateral side (Fig. 702). The first toe is called the hallux and the fifth toe is called the digitus minimus. The bones of the toes are the phalanges. The big toe has only two—a proximal and a distal, but the others have three—proximal, middle

on the plantar aspect of the foot and the two dorsal spaces.

The four median plantar spaces (Fig. 703).

1 The first space is located between the plantar aponeurosis and the flexor digitorum brevis.

2 The second space is situated be-




FIG. 703 The four plantar spaces of the foot. (A) Longitudinal section. (B) cross section. (C) alternate incisions for space drainage.

and distal. Each proximal phalanx articulates with the head of a metatarsal bone and in this way forms the metatarsophalangeal joint. The middle phalanx articulates with the two other phalanges to form the interphalangeal joint. The proximal end of the phalanx is called its base and its distal end is called its head. The toes are involved in various conditions which will be discussed subsequently.

SURGICAL CONSIDERATIONS

INFECTIONS OF THE FOOT

Infections of the foot are less common than those of the hand but they can be approached and drained as effectively. Grodinsky has emphasized the clinical importance of the four median fascial spaces

between the flexor digitorum longus (with its associated lumbricales muscles) and the oblique head of the adductor hallucis.

3 The third space is found between the flexor digitorum longus (with its associated lumbricales muscles) and the oblique head of the adductor hallucis.

4 The fourth and deepest space is situated between the oblique head of the adductor hallucis muscle and the second and the third metatarsal bones and their interosseous muscles. These spaces are bounded both laterally and medially by dense connective tissue septa along which an infection may travel from one space to another. There is nothing in the foot which corresponds to the radial and the ulnar bursae of the hand since the sheaths of all the flexor tendons of the toes end proximal to the




FIG. 704 Four varieties of talipes

distal head of the metatarsal bones the heath of the flexor hallucis longus extends a little higher than the rest. Therefore infections within the sheaths either may remain local or break into one of the four spaces.

Two lateral spaces have been described but the care of little anatomic or clinical importance.

The two dorsal spaces subaponeurotic and subcutaneous are similar to those found in the hand and are treated in the same way. Infections in any of these spaces may be the result of extension along fascial or tendon planes or may result from direct penetrating wound into a given space.

Treatment. The four medial fascial spaces can be approached best from the inside of the foot so that a scar is not left upon the plantar or weight bearing surface. Such an incision should be made along the inner border of the first metatarsal bone and should be carried between that bone and the flexor hallucis longus muscle. This incision follows the inferior surface of the bone and separates it from the flexor hallucis brevis. In this way access is gained to the septum which forms the medial wall of all four spaces; the tendon of the flexor hallucis longus also is protected. At times a counter incision may be necessary if so it is made along the outer edge of the plantar surface (FIG. 703C).

DEFORMITIES OF THE FOOT

The general term talipes is used to designate foot deformities. Four forms of

talipes are described: equinus, calcaneus, valgus and varus (FIG. 704).

Talipes equinus is caused by a contracted tendon of Achilles which prevents the foot from being placed squarely on the ground. The forepart of the foot is in contact with the ground in severe forms of equinus, the foot may form almost a straight line with the leg. Usually a contracture of the plantar aponeurosis is associated with the condition; this results in a deep hollowing of the sole known as talipes cavus. The condition usually can be corrected by stretching the calf muscles or by cutting the Achilles tendon.

Talipes calcaneus constitutes an acute flexion of the foot on the leg. It is caused usually by an involvement of the calf muscles following infantile paralysis.

In *talipes valgus* the medial border of the foot is depressed and is in contact with the ground. If of congenital origin the peronei are shortened and the anterior and the posterior tibial muscles are stretched. In the acquired form the deformity is brought about by a paralysis of the tibialis anterior and the posterior muscles.

In *talipes varus* the foot is twisted upon itself in a position of adduction and inversion. The dorsum of the foot is directed somewhat forward and the sole is directed backward.

HALLUX VALGUS

Hallux valgus or bunion, is a condition in which the big toe deviates laterally, and the head of the first metatarsal becomes




FIG 705 Hallux valgus

prominent (Fig 705). The joint surface of the head of the metatarsal pushes obliquely and laterally. An adventitious bursa, which is a bunion, usually develops over the projecting head of the bone. Numerous operations have been devised to cure this condition; however, their aim is essentially the same. The head of the first metatarsal is reduced by removing part of its medial surface and reconstructing its articular alignment. The bursa that is present usually is dissected away and the tendon of the extensor hallucis is displaced medially and maintained in position by suturing, so that by its contraction the great toe is kept in alignment.

HAMMER TOE

In this condition the involved toe contracts and produces a sharp angulation. The




FIG 706 Hammer toe

toes that usually are involved are the second or the third (Fig 706). The common extensor muscle is stretched, resulting in an elevation of the proximal phalanx but leaving the other phalanges in flexion. The proximal interphalangeal joint is flexed acutely but the metatarsophalangeal and the distal interphalangeal joints are hyperextended. The operative correction of this condition attempts to divide the dorsal expansion of the extensor tendon which covers the dorsum of the joint. In this way the joint is opened widely, and after division of the lateral ligament the head of the first phalanx is dislocated into the wound and is excised.

SECTION I LN

VERTEBRAL COLUMN
VERTEBRAL (SPINAL) CANAL
SPINAL CORD




FIG 705 Hallux valgus

prominent (Fig. 705). The joint surface of the head of the metatarsal pushes obliquely and laterally. An adventitious bursa, which is common, usually develops over the projecting head of the bone. Numerous operations have been devised to cure this condition, however their aim is essentially the same. The head of the first metatarsal is reduced by removing part of its medial surface and reconstructing its articular alignment. The bursa that is present usually is dissected away and the tendon of the extensor hallucis is displaced medially and maintained in position by suturing, so that by its contraction the great toe is kept in alignment.

HAMMER TOE

In this condition the involved toe contracts and produces a sharp angulation. The




FIG 706 Hammer toe

toes that usually are involved are the second or the third (Fig. 706). The common extensor muscle is stretched, resulting in an elevation of the proximal phalanx but leaving the other phalanges in flexion. The proximal interphalangeal joint is flexed acutely, but the metatarsophalangeal and the distal interphalangeal joints are hyperextended. The operative correction of this condition attempts to divide the dorsal expansion of the extensor tendon which covers the dorsum of the joint. In this way the joint is opened widely, and, after division of the lateral ligament the head of the first phalanx is dislocated into the wound and is excised.

SECTION TEN

VERTEBRAL COLUMN

VERTEBRAL (SPINAL) CANAL

SPINAL CORD

Vertebral Column, Vertebral (Spinal) Canal, and Spinal Cord

THE VERTEBRAL COLUMN

The spinal column serves many remarkable functions. It supports the weight of the head, acts as the central pillar of the body, connects the upper and the lower segments of the trunk, gives attachments to the ribs, reduces shock transmitted from various parts of the body, forms a complete tube for the reception of the spinal cord and permits a wide range of most complicated movements and balancing. It consists of 33 vertebrae which are grouped according to region (Fig. 707). The moveable (true) vertebrae are the 7 cervical, the 12 thoracic and the 5 lumbar. The fixed (false) vertebrae are the 5 sacral fused in adults to form the sacrum and usually the 4 coccygeal fused to form the coccyx. If the bony column is examined as a whole from front or back it seems to form a straight line but when it is seen from the side it presents definite curves.

Viewed from the side the vertebral column reveals four curvatures: the cervical and the lumbar curves are convex forward, the thoracic and the sacrococcygeal curves are concave forward. At birth only the thoracic and the sacral curves exist. These early thoracic and sacral curves are called the *primary curves*. The *secondary curves* (compensatory) develop after birth: they are the cervical and the lumbar. The cervical curve results from elevation and extension of the head in infancy and the lumbar from assumption of the erect posture when the child begins to walk. The lumbar curve is more pronounced in women

than in men and in youth than after middle age.

In the midthoracic region the tips of the spines are below the level of the bodies of the corresponding vertebrae. The intervertebral foramina increase in size down to the fifth lumbar vertebra. In the sacrum they diminish from above downward. The transverse processes are in front of the articular processes in the cervical region and in line with the intervertebral foramina but in the thoracic region they are behind both; in the lumbar region they are behind the foramina but in front of the articular processes. Viewed from in front the bodies of the vertebrae increase in breadth from the second cervical to the first thoracic but diminish from the first to the fourth thoracic. They increase from the fourth thoracic to the first sacral, below which they reduce rapidly in size. The transverse processes of the atlas are wide and stand out, but those of the next vertebrae are short and nearly equal in length. Those of the seventh are long, nearly as long as the first thoracic. They diminish gradually down to the twelfth thoracic where they are represented only by tubercles. In the lumbar region they stand out again, the third being the longest. The column is widest at the sacrum and below this it diminishes gradually at first but abruptly increases at the third sacral piece and becomes greatly accentuated opposite the fifth.

The vertebral column is usually about 28 inches long in men and 24 inches long in women; however this is subject to great

The *lumbar vertebrae* are larger than the thoracic and their transverse processes do not give attachment to the ribs. They are distinguished by the absence of foramina in the transverse processes and also by the absence of their costal facets.

The *cervical vertebrae* are easily distinguished from the others by their transverse processes which are unusually wide and contain a canal for the transmission of the vertebral artery (11, 109). The seventh cervical vertebra has been distinguished further by its prominent spinous process which is known as the *vertebra prominens*. The first two cervical vertebrae are so markedly different from the others that they require special mention. The *first* or *atlas* has no body and no spine but consists only of a pair of lateral masses united by anterior and posterior arches. It resembles a large ring. Its cavity is divided by a transverse ligament into two compartments: a larger posterior one for the spinal cord and a smaller anterior one for the odontoid process (dens) of the second cervical vertebra. The upper surface of the bone reveals two smooth oval areas for articulation with the under surface of the skull. A rocking movement of the skull forward and backward, takes place on these areas. In turning, the head from side to side the atlas moves with the skull and the two turn on the second cervical vertebra with the odontoid process as the center of rotation. The *second* cervical vertebra also called the *axis* (epistropheus) differs from the others in that its body is much reduced in size and projecting upward from it is a prominent elevation called the *odontoid process* (dens). This toothlike dens passes through a special canal in the first cervical vertebra and forms the axis of rotation for the skull and the first vertebra.

The Intervertebral Disks Between the vertebrae there is a fibrocartilaginous disk which acts as a shock absorber. Each disk is composed of two parts: a central *nucleus pulposus*, a relic of the notochord, and an




FIG 703 The distinguishing features of the vertebrae

variations The bodies of the vertebrae form a column for the support of the trunk and the head, the vertebral foramina provide a canal for the spinal cord and its membrane The spines and the transverse

vertebral foramen The anterior surface of the body is convex from side to side, but the posterior surface is slightly concave On its external surface the arch has three processes, one pointing backward, the




FIG. 707 The spinal column (A) Posterior view (B) anterior view (C) lateral view

processes provide attachments for muscles and form three ridges that bound a pair of grooves of which the laminae (ventral arch) form the floors These grooves are occupied by muscles which move the vertebral column

The *thoracic vertebra* consists of a short cylindrical anterior portion called the body, the posterior aspect of which is attached to a bony arch (Fig 708) Enclosed within these two portions is an opening called the

spinous process, and the other two extending laterally, the *transverse processes* The spinous processes mark the midline of the back, and the rounded tips can be felt beneath the skin The transverse processes give partial attachment to the ribs Four small articular processes which interlock with similar elevations on the vertebrae above and below are found also The *vertebral canal* formed by the series of vertebral foramina contains the spinal cord

tion is composed of most of the parts of the five fused vertebrae and the lateral part also called the lateral masses represents the fused costal and the transverse processes. These lateral masses contain the

border is the triangular entrance to the sacral canal. The two lateral parts are called the alae, which are fan shaped and represent the fused costal and transverse processes. Each ala is crossed by the con-




FIG. 710 The intervertebral disks seen in sagittal section

auricular surfaces for articulation with the ilium. The laminae of S5 and usually S4 fail to meet in the median plane because of this, they form the opening to the sacral canal called the *sacral hiatus*. The sacral canal contains the cauda equina, the filum terminale and the meninges down to the middle of the third sacral vertebra (Fig. 716). At this level the meninges end and the lower portion of the canal contains only the nerve roots of the lower sacral and coccygeal nerves, together with the coverings they acquire from the meninges. The base of the sacrum is formed by the upper surface of the first sacral vertebra; it is divided into a median and two lateral parts. The median part is the oval upper surface of the body of the first sacral vertebra, the anterior border of which forms an important forward bulging landmark called the promontory of the sacrum. Behind its posterior

constituent parts of the lumbosacral trunk, the ilio-lumbar artery, the obturator nerve and the psoas muscle. The concave anterior surface of the sacrum is crossed by four ridges which mark the sites where fusion took place between the bodies of the five sacral vertebrae before the twenty-first year. Lateral to these ridges, on each side, the four anterior sacral foramina are placed. These foramina become progressively smaller from above downward through them the anterior rami of the upper four sacral nerves pass laterally.

The *coccyx* is that bone which results from the three, four or five rudimentary coccygeal vertebrae which are attached to the tip of the sacrum. They are believed to represent the bony remnants of the tail of lower animals. It is triangular in shape and constitutes the terminal segment of the spine. The lateral margins of it and its tip




FIG 709 The seven cervical vertebrae

outer ring the *annulus fibrosus* (Fig 710). The nucleus is a very elastic semifluid tissue mass which lies more posteriorly than centrally. The annulus forms the major part of the disk and gives form and strength to it and is the main weight bearing portion. Each disk is attached to the compact rim of the superior and the subjacent vertebral bodies. The nucleus has been likened to a water cushion which allows the overlying vertebrae to rock about on it, while the strong annular fibers act as stays which prevent displacement of the vertebral bodies. When the usual stress and strain is placed upon the spinal column the disks bulge in all directions but return to their normal positions when the stress has been removed. They are maintained in their positions chiefly by the anterior and the posterior longitudinal vertebral ligaments. If an un-

usual strain is placed upon the vertebral column, the disk proper or its nucleus may be extruded beyond its normal limits and fail to return to position. Posterior protrusion may cause root pain because of pressure of the disk upon one or more of the spinal nerves. More marked protrusion may cause signs and symptoms similar to those found in transverse lesions of the cord or the cauda equina. These lesions have been mistaken for intraspinal neoplasms. One of the most common locations for such a lesion is low in the lumbar region and one of the most common symptoms is sciatic pain. If such an abnormal protrusion is present, it can be diagnosed by injecting lipiodol into the subarachnoid space, since the protruded disk will impinge on the column of radio opaque oil and will indent or displace it. Complete obstructions to the passage of the oil have also been observed. After the age of 60 these disks begin to atrophy, their disappearance giving rise to the bowed back of old age.

The adjacent vertebrae articulate with each other by their bodies through the intervention of the intervertebral disks and through their *articular processes*. Each vertebra has upper and lower articular processes which are arranged for the most part vertically, except in the cervical region where they are more transverse. Because of these anatomic facts it is only possible for a vertebral dislocation without fracture to take place in the neck. Anywhere else in the spinal column a pure dislocation can not occur because the articular processes must break off before the body can be moved.

The adult *sacrum* results from the fusion of five sacral vertebrae which diminish in size from above downward (p 550). It is triangular in shape, possessing a base or upper surface, an apex or lower end and dorsal pelvic and two lateral surfaces. It is divided by paired rows of foramina on the dorsal and the pelvic surfaces into median and lateral parts. The median por-

tion is composed of most of the parts of the five fused vertebrae, and the lateral part is called the lateral mass, represents the fused costal and the transverse processes. These lateral masses contain the

border is the triangular entrance to the sacral canal. The two lateral parts are called the ala which are fan shaped and represent the fused costal and transverse processes. Each ala is crossed by the con-




FIG. 710 The intervertebral disks seen in sagittal section

auricular surfaces for articulation with the ilium. The laminae of S5 and usually S4 fail to meet in the median plane because of this, they form the opening to the sacral canal called the *sacral hiatus*. The sacral canal contains the cauda equina, the filum terminale and the meninges down to the middle of the third sacral vertebra (Fig. 716). At that level the meninges end, and the lower portion of the canal contains only the nerve roots of the lower sacral and coccygeal nerves together with the coverings they acquire from the meninges. The base of the sacrum is formed by the upper surface of the first sacral vertebra; it is divided into a median and two lateral parts. The median part is the oval upper surface of the body of the first sacral vertebra, the anterior border of which forms an important forward bulging landmark called the *promontory* of the sacrum. Behind its posterior

parts of the lumbosacral trunk, the ilio-lumbar artery, the obturator nerve and the psoas muscle. The concave anterior surface of the sacrum is crossed by four ridges which mark the sites where fusion took place between the bodies of the five sacral vertebrae before the twenty-first year. Lateral to these ridges on each side the four anterior sacral foramina are placed. These foramina become progressively smaller from above downward through them the anterior rami of the upper four sacral nerves pass laterally.

The *coccyx* is that bone which results from the three, four or five rudimentary coccygeal vertebrae which are attached to the tip of the sacrum. They are believed to represent the bony remnants of the tail of lower animals. It is triangular in shape and constitutes the terminal segment of the spine. The lateral margins of it and its tip




FIG 711 The spinal meninges. Transverse section through the spinal cord and the meninges (diagrammatic). (A) Section through a thoracic vertebra. (B) Section through a lumbar vertebra.

continue to the wide origin of the sacro tuberos ligament and afford attachments to the muscles of the pelvic floor.

Ligaments. The *anterior longitudinal ligament* lies on the front of the body of the vertebrae from the sacrum to the axis where it is continued upward as the *anterior atlanto-axial ligament* (Fig 710). The *posterior longitudinal ligament* is placed on the backs of the bodies of the vertebrae inside of the spinal canal. The *ligamenta flava* connect the deep surfaces of the laminae; they are made up of yellow elastic fibers. The *interspinous ligaments* unite adjacent spines.

Sacralization of the fifth lumbar vertebra means the fusion of the transverse processes

of the fifth lumbar vertebra with the sacrum, such a fusion may be bilateral (symmetrical) or unilateral (asymmetrical). In symmetrical sacralization the bony structure is sounder and more able to resist stress and strain, but in asymmetrical sacralization a scoliosis may result and, although not necessarily severe, may alter muscle balance, lead to arthritic changes and pain. "Lumbarization" of the first sacral vertebra is noted when this vertebra takes on lumbar characteristics. This, too, may be unilateral or bilateral.

THE VERTEBRAL (SPINAL) CANAL

Together the vertebral foramina make a continuous canal in the spinal column. The anterior wall is closed by the posterior surfaces of the bodies of the vertebrae and their disks; the posterior longitudinal ligament passes over these. The posterior and the lateral walls are made up of the superimposed bony arches; the interspaces of which are covered behind by the *ligamenta flava* but remain open laterally as the *intervertebral foramina*. It is lined entirely by ligamentous and periosteal structures. The canal is approximately circular where it is continuous with the foramen magnum but becomes triangular through the cervical region, it becomes round again in the thoracic region and finally assumes a triangular form in the lumbar region. Within the sacrum it flattens and expands laterally and in the flexible cervical and lumbar regions it shows distinct enlargements to accommodate the cervical and the lumbar enlargements of the spinal cord.

The Spinal Meninges. These are three tubular fibrous membranes which are named from without inward: the *dura mater*, the *arachnoid mater* and the *pia mater* (Fig 711). They are continuous with the corresponding meninges of the brain. The space which is situated between the *dura mater* and the walls of the vertebral canal is called the *epidural space*; it is filled with loose areolar tissue and a semiliquid fat, a network of




FIG 712 Diagrammatic presentation of the levels of the termination of the spinal cord the cauda equina the subarachnoid space and the extradural space




FIG 713 The spinal cord and the meninges seen from behind

veins and small arteries to the bones. The dura is the most complicated of the three membranes. It is recalled that in the cranial cavity this membrane consists of two layers, namely an outer layer constituting the lining perosteum of the skull, and an inner layer which invests the brain and by its duplications forms cranial venous sinuses. At the foramen magnum the outer layer blends with the periosteal and the ligamentous linings of the vertebral column, but the inner layer forms the dural sac which invests the more delicate meninges of the cord and the emerging nerve roots. Within the vertebral canal the dura mater forms a loose envelopelike covering outside of the arachnoid. Although firmly connected to the second and the third cervical vertebrae it is not intimately associated with the periosteum elsewhere. It extends five vertebrae lower than the spinal cord proper, it ends at the second sacral vertebra with a prolongation of it investing the filum terminale which ends at the back of the coccyx (Figs

711B and 712). Although firmly attached to the second and the third cervical vertebrae, this covering is loosely attached at the upper and lower parts of the vertebral canal to the posterior longitudinal ligament. The anterior and the posterior nerve roots which pierce it carry tubular dural prolongations which are attached to the periosteum of the bone at the intervertebral foramina. At the level of the second sacral vertebra where it ends, it forms a cul de sac which is pierced by the filum terminale, the latter carrying its dural prolongation and becoming attached to the coccyx.

The *spinal arachnoid* is a thin transparent and fragile membrane. It ends a little below the second sacral vertebra, posteriorly, it is connected to the pia mater by an incomplete posterior median septum in the cer




FIG 714 Development of the spinal cord

vical region. The dura and the arachnoid move freely upon one another in the capillary interval which exists between them.

The *subarachnoid space* lies between the arachnoid and the pia mater and contains the cerebrospinal fluid. It is traversed by septa lined with flat arachnoidal cells and also by the vessels going to the brain and the spinal cord. It communicates with the corresponding intracranial space, therefore an increase of pressure from hemorrhage or swelling in the brain may be diagnosed by lumbar puncture.

The *pia mater* in the vertebral canal is closely applied to the spinal cord and dips into the anterior median fissure. It is a delicate vascular membrane which is attached to the surfaces of the cord and carries blood vessels into its substance. Along the lateral side of the spinal cord the pia is attached to the dura by a thin membrane called the dentate ligament. These ligaments are twenty toothlike processes which extend from the pia to the dura; they push the arachnoid ahead of them (Fig 713). They leave the pia midway between the anterior and the posterior nerve roots and serve to suspend the cord in the midline. The lowest one of these ligaments is forked (Von Elsberg's forked denticulation) and is placed just above the exit of the first lumbar vertebra. It acts as the surgeon's guide to this nerve, giving him a nerve root of known number from which he may determine the position of others. The anterior and the posterior nerve roots are separated by the ligaments.

THE SPINAL CORD

During the first days of intra uterine existence, a dorsal groove, the neural groove,




FIG 715 Development of the neural arch of a vertebra around the spinal cord

appears on the body surface (Fig 714). It becomes closed off from the neural canal, and from its walls the central nervous system arises. Its lumen persists as the central spinal canal. The neural canal becomes separated from the epidermal covering of the body by an ingrowth of mesoderm; anterior to the canal a solid rod of cells forms known as the notochord (Fig 715). Around this notochord the vertebral bodies develop. Until the fourth month of intra uterine life the spinal cord extends the whole length of the vertebral canal, but as the development proceeds, owing to the greater growth of the vertebral column, the cord extends only as far as the sacrum at the sixth month and to the lumbar vertebra at birth. In adults, however, the cord extends to the upper border of the second lumbar vertebra.

The spinal cord is represented as a cylindrical mass of nervous tissue which measures about 18 inches in length and about one half inch thick (Fig 716). In the adult it lies in the upper two thirds of the vertebral canal. Since its diameter is much less than that of the vertebral canal, the back bone can be bent and twisted without any strain being put upon the cord proper. It begins at the foramen magnum where it is continuous with the medulla oblongata opposite a point midway between the union and the spine of the axis. A strong glistening threadlike structure called the *filum terminale* which is composed mainly of pia mater, attaches the end of the cord to the back of the coccyx. The filum pierces the arachnoid and the dura mater and emerges




FIG 716 The spinal cord




FIG 714 Development of the spinal cord




FIG 715 Development of the neural arch of a vertebra around the spinal cord

vical region. The dura and the arachnoid move freely upon one another in the capillary interval which exists between them.

The *subarachnoid space* lies between the arachnoid and the pia mater and contains the cerebrospinal fluid. It is traversed by septa lined with flat arachnoidal cells and also by the vessels going to the brain and the spinal cord. It communicates with the corresponding intracranial space; therefore an increase of pressure from hemorrhage or swelling in the brain may be diagnosed by lumbar puncture.

The *pia mater* in the vertebral canal is closely applied to the spinal cord and dips into the anterior median fissure. It is a delicate vascular membrane which is attached to the surfaces of the cord and carries blood vessels into its substance. Along the lateral side of the spinal cord the pia is attached to the dura by a thin membrane called the dentate ligament. These ligaments are twenty toothlike processes which extend from the pia to the dura; they push the arachnoid ahead of them (Fig 713). They leave the pia midway between the anterior and the posterior nerve roots and serve to suspend the cord in the midline. The lowest one of these ligaments is forléd (Von Elsberg's forléd denticulation) and is placed just above the exit of the first lumbar vertebra. It acts as the surgeon's guide to this nerve, giving him a nerve root of known number from which he may determine the position of others. The anterior and the posterior nerve roots are separated by the ligaments.

THE SPINAL CORD

During the first days of intra uterine existence, a dorsal groove, the neural groove,

appears on the body surface (Fig 714). It becomes closed off from the neural canal, and from its walls the central nervous system arises. Its lumen persists as the central spinal canal. The neural canal becomes separated from the epidermal covering of the body by an ingrowth of mesoderm anterior to the canal; a solid rod of cells forms known as the notochord (Fig 715). Around this notochord the vertebral bodies develop. Until the fourth month of intra uterine life the spinal cord extends the whole length of the vertebral canal; but as the development proceeds, owing to the greater growth of the vertebral column, the cord extends only as far as the sacrum at the sixth month and to the lumbar vertebra at birth. In adults, however, the cord extends to the upper border of the second lumbar vertebra.

The spinal cord is represented as a cylindrical mass of nervous tissue which measures about 18 inches in length and about one half inch thick (Fig 716). In the adult it lies in the upper two thirds of the vertebral canal. Since its diameter is much less than that of the vertebral canal, the back bone can be bent and twisted without any strain being put upon the cord proper. It begins at the foramen magnum where it is continuous with the medulla oblongata opposite a point midway between theinion and the spine of the axis. A strong glistening threadlike structure called the *filum terminale*, which is composed mainly of pia mater, attaches the end of the cord to the back of the coccyx. The filum pierces the arachnoid and the dura mater and emerges

at the sacral hiatus to blend with the perios teum on the dorsum of the coccyx. In the adult the subarachnoid and the subdural spaces extend to the body of the second sacral vertebra, but the cord proper ends at the second lumbar. Hence, between L 2 and S 2 there is no cord, but instead, the filum terminale and the roots of the lower spinal nerves. These roots resemble a horse's tail and therefore have been given the name of *cauda equina*. A needle which enters the subarachnoid space above L 2 may permanently damage the spinal cord, but if it enters at a lower level it would encounter only terminal nerves. The spinal cord is protected in a water cushion of subarachnoidal fluid plus its membranes and is anchored by the dentate ligaments. Opposite the fifth and the sixth cervical vertebrae and again opposite the lower two thoracic vertebrae, the spinal cord reveals two enlargements. These are the cervical and the lumbar enlargements which are associated with the origins of the great plexuses to the superior and the inferior extremities.

In the spinal cord the gray matter is placed centrally and the white matter peripherally. The gray matter is "H"-shaped and contains anterior and posterior limbs known as the anterior and the posterior horns or gray columns. These divide the white matter on each side into anterior lateral and posterior white columns. A groove in front, the anteromedian fissure, and a septum behind, the posteromedian septum separate the right and the left sides of the white matter. The transverse limb of the "H" constitutes the gray commissure and surrounds the central canal of the spinal cord. In the thoracic region there is, in addition, a lateral horn which projects opposite the central canal.

From the large cells of the anterior horn the fibers of the *anterior nerve roots* (motor) stream out and leave the cord at its antero lateral aspect. Opposite the tip of the posterior horn, the fibers of the *posterior nerve roots* (sensory) enter the spinal cord. This too, further divides the white matter into

three white funiculi (columns). The *anterior* white column lies between the anterior median fissure and the anterior nerve roots, the *lateral* white column lies between the anterior and the posterior nerve roots, the *posterior* white column lies between the posterior nerve roots and the posteromedian septum. Anterior nerve rami and their branches communicate with adjacent rami to form plexuses. Close to the vertebral column the anterior rami of nerves C 1 and 4 form the cervical plexus, those of C 5 and Th 1 the brachial plexus, L 1 and 4 the lumbar plexus, L 4 and S 4 the sacral plexus, and S 4 and Co 1 the coccygeal plexus. On each posterior root the *ganglion* is found, which is composed of cells giving origin to central and peripheral fibers. The ganglia of all except the sacral and the coccygeal nerves occupy the intervertebral foramina. Those of the sacral and the coccygeal nerves lie within the vertebral canal. Near the intervertebral foramen each pair of nerve roots unite to form a spinal nerve, which divides into anterior and posterior branches or primary divisions. Both of these divisions are mixed (sensory and motor) nerves. Distal to the division the spinal nerve gives off a minute recurrent branch to the meninges and the cord, after uniting with the branch from the sympathetic trunk. Each nerve root receives a covering from the pia mater and one from the arachnoid before it meets the dura. Within the subarachnoid space the roots are bathed in cerebrospinal fluid, but outside of the space they are encased in a tubular sheath of dura which includes the ganglion on the posterior root.

The nerve fibers which constitute the white matter are divided into two main groups: (1) the ascending and (2) the descending (Fig 717). The ascending fibers are arranged in fasciculi (tracts) which become larger as they are followed upward because of the addition of new fibers at each ascending level. The descending fibers form fasciculi also which become smaller as they are traced downward since they

of the midbrain occupying approximately the middle third. In the ventral part of the pons the tract is broken into a large number of small bundles by the nuclei pontis and the transverse fibers of the pons. In the upper part of the medulla oblongata a compact tract is re-established and forms a surface projection on the anterior aspect called the pyramid which lies lateral to the anterior median fissure. In the lower part of the medulla oblongata the majority of the fibers decussate with the fibers of the opposite side in the decussation of the pyramid and then take their final position in the middle of the lateral right column of the spinal cord. The *lateral cerebrospinal (cross pyramidal) tract* becomes smaller as it passes downward for it is constantly giving off fibers which terminate by arborizing around the large motor cells in the anterior horn. The fibers of these cells form the anterior nerve roots of the spinal nerve. Those fibers which do not decussate in the medulla oblongata form the *anterior cerebrospinal (direct pyramidal) tract* which descends in the anterior white column close to the anterior median fissure. Before their termination these fibers also cross the median plane and end as do the fibers of the cross tract by arborizing around the large motor end cells of the anterior horn. As the fibers of the cerebrospinal tract descend they give off fibers to the motor nuclei of the cranial nerves of both sides.

The *estibulospinal tract* which is the efferent part for equilibrium reflexes has its origin in the lateral vestibular nucleus in the pons of the medulla oblongata. It descends near the surface of the spinal cord in the anterior white column and terminates uncrossed around the motor cells of the anterior horn.

The *rubrospinal tract* begins in the red nucleus of the midbrain. It decussates with its fellow of the opposite side and descends through the dorsal part of the pons and the dorsolateral part of the medulla oblongata to reach the lateral white column of the spinal cord where it lies close to the lateral




FIG 718 Spinal (subarachnoid) anesthesia

cerebral spinal tract. Its fibers end in association with the motor cells of the anterior horn of the same side. It is an efferent part from the cerebellum and the corpus striatum and is concerned with the maintenance of postural tone.

The *tectospinal tract* together with the ascending spinotectal tract provides a pathway for visual reflexes and begins in the superior corpus quadrigeminum of the midbrain. It decussates with its fellow of the opposite side in front of the aqueduct of the midbrain. It then passes downward in the anterior white column of the spinal cord and its fibers end in the same manner as those of the rubrospinal tract.

ANESTHESIA

Spinal (Subarachnoid) Anesthesia

This injection produces a nerve root block. The patient may be placed in either a lateral recumbent or sitting position (Fig 718). Some surgeons particularly Babcock prefer the space between the first and the second lumbar vertebrae. The fourth lumbar interspace is another favorite site and is found readily by drawing an imaginary line between the crests of the ilia. Since the spinal cord per se ends at a higher level than the fourth interspace there is little danger of striking it. The selected interspace is anesthetized, and a needle is

their second neurons ascend in the posterior white column for a few segments before crossing the median plane and turning upward in the anterior spinothalamic tract which lies in the anterior white column.

The *spinal lemniscus* forms in the medulla oblongata by the union of the anterior and the lateral spinothalamic tracts and conveys all the thermal, painful, pressure and crude tactile sensations from the spinal nerves of the opposite side of the body. In the pons the spinal lemniscus becomes associated with the *medial lemniscus* with which it ascends through the tegmentum of the midbrain and the subthalamus to end by arborizing around cells in the thalamus. These cells give rise to new fibers which ascend through the posterior limb of the internal capsule and reach the cerebral cortex of the postcentral gyrus.

The proprioceptive fibers convey sensations of movements, active or passive, and have their parent cells situated in the spinal ganglia. The centrally directed fibers of these ganglion cells enter the spinal cord and turn upward in the posterior white column. They constitute the *fasciculus gracilis* (Goll) and the *fasciculus cuneatus* (Burdach). These two, therefore, are functionally identical, the former is placed more medially and in the upper region and contains fibers which arise from the ganglion cells of the posterior roots of the sacral, the lumbar and the lower thoracic nerves. The *fasciculus cuneatus* occupies the lateral half of the posterior white column and is made up of fibers arising from the upper thoracic and the cervical nerves. In the medulla oblongata these fibers end by arborizing around cells in the gracile and cuneate nuclei. These nuclei are two masses of gray matter situated side by side in the dorsal region of the medulla oblongata. The second neuron fibers, internal arcuate fibers pass ventrally around the central gray matter and cross the median plane where they decussate with corresponding fibers of the opposite side in the sensory decussation. They then ascend, pass through the pons

and the midbrain and to the thalamus where they end. A third neuron arises in the thalamus and extends through the posterior limb of the internal capsule to the postcentral gyrus. These impressions are appreciated by consciousness.

Many fibers which originate in the spinal ganglia reach the cerebellum. They form the afferent part of the paths for spino-cerebellar reflexes. On entering the spinal cord they terminate in the cells of the nucleus thoracicus, which extends throughout the thoracic segments of the spinal cord, and lie at the medial part of the base of the posterior column of the gray matter. The second neuron fibers ascend in the lateral white column of the same side. Here they are arranged in two principal groups called the posterior and the anterior spino-cerebellar tracts.

Some of the posterior nerve root fibers connect with the lower visual center. These connections are brought about by the spino-tectal tract. The entering fibers end in the cells of the posterior horn. The second neuron fibers cross the median plane and form a small bundle which ascends medial to the anterior spinocerebellar tract. The spino-tectal tract thus formed ascends through the medulla oblongata and the pons to the midbrain where it ends in the superior quadrigeminal body.

The Descending Tracts These are the tracts which pass downward through the spinal cord and are concerned with the production of movements, both voluntary and visceral, and also form the efferent paths for cerebellar, equilibratory, visual and other reflexes.

The *cerebrospinal (pyramidal) tracts* are associated with voluntary motor impulses which travel from the cortex. The cells of origin of these fibers are found in the cortex of the precentral gyrus and pass through the corona radiata where they are intercepted by fibers of the corpus callosum. They enter the posterior limb of the internal capsule and at its lower end pass as a compact bundle into the basis pedunculi

Index

- Abdomen 161 543
walls, anterior 160 39
anatomy surface 163 364
arteries 167
boundaries, 363
fascia 165 16 1, 8 350
hernia incisional 3 6 3 9
lymph vessels, 366 368 369
muscles, 169 1 1
nerves, 364 366
regions, 161 164
inguinal *See* Inguinal
region
umbilical *See* Umbilical
region
urgery of 1 0 3, 6
incisions 3 0 3 6
veins 366 368
posterolateral 39, 412
kidneys *See* Kidneys
muscles 39 404
nerves, 404
region ilioacetal 39 412
lumbar 163 364 397 412
vein 404
- Abducens nerve 65 88 89 103
- Abduction of fingers, 11
of foot arches 896 897
of hand 732 735 53
of hip joint 800 812
of shoulder joint 690
of thigh 96
of thumb 35 714 85
of toes, 886 887
- Abductor digiti minimi muscles, 72
885
- Abductor digiti quinti muscle of
foot 772 8 0
- Abductor hallucis muscle 8 0 813
875 878 882 884 885
- Abductor pollicis muscle brevis
164 772 775
longus 730 134 735 43 44
750 752 172
- Abcess of appendix vermiform
469
collar button 780
of gums subperiosteal 150
of hand subcutaneous, 7, 8
involving bulbo urethral glands
633
chiorectal 491
of kidney right 473
of liver 474
of lymph glands submental 180
parotid gland 107 129 134
in pelvis 469 4 0 664
perigastric 513
- Abcess (Continued)
of prostate gland 5 7 5 8
subphrenic drainage 514 515
subtemporal 112
subungual 184
of teeth 151 152
of thenar space 81
- Accessory nerve 24 69 127 130
131
facial 0 1 156 144 1 6 184
186 231 244 245
- Acetabular artery 607 93
- Acetabular ligament 550 93 95
- Acetabulum 547 550 95 97 98
- Achilles tendon *See* Tendo calcaneus
- Acoustic nerve *See* Auditory nerve
- Acromioclavicular joint 265 691
692
- Acromioclavicular ligament 656
- Acromion 111 680 688 691 697
00
angle 694
process *See* Acromion
- Acromiothoracic artery 613 677
6 8 689
- Adam's 531
- Adam's apple *See* Prominence
laryngeal
- Adams 441
- Adduction of fingers 771
of foot arches 897
of hand 4 733 154
of hip joint 800
of shoulder joint 690
of toes 886 887
- Adductor brevis muscle 554 555
196 812 816 817 825 826 831
- Adductor hallucis muscle 832 886
887 889 897 898
- Adductor hiatus 816 819 877
- Adductor longus muscle 554 555
796 805 808 809 812 813 815
819 822 825 826 831
- Adductor magnus muscle 554 555
94 196 800 805 812 816 821
824 827 831 833 840
osseo aponeurotic openings 81,
818
- Adductor minimus muscle 96 803
821 830
- Adductor pollicis muscle 159 160
1 0 172 173 787
- Adductor region of thigh 816
- Adenoids 227 229
- Adenoma of prostate gland middle
lobe 575 5 6
- Adenopathy axillary lymph 275
- Aditus to antrum 110 117
- Adrenal gland 38, 540 596
- Ager nasi 11 94
- Air cells, ethmoidal 86 93
- Air canals 9
- Ala nasi 178
- Ala vomeris 90
- Alae of sacrum 907
- Albarra 5 5
- Alcock canal of 480 481 487, 495
558 560 607 630 654 657 659
- Alcohol injection of nerves with
121 123 125
- Alexander 353
- Allantois 394 67 677 628
- Allen 832
- Alveolar artery 13 139 147 194
- Alveolar bone 151
- Alveolar nerves, 67 64 131 133, 141
- Alveolar process, 95 1 0
- Alveoli 1,
- Amatua 4
- Amnion 396
- Ampulla of fascia endopelvic 559
of inner ear 116
of rectum 4 9 484 60 599
of uterine tube 591 59
of vas deferens 5 25 4 5 9 638
of Vater 518 521 5 3 5 536
537 39
carcinoma 539
- Amputation of ankle 8 9
of forearm 147 14,
of knee supracondylar 849 851
of leg 866-868
Progoof of ankle 8, 9
tump painful 360
- Synes through ankle joint 8, 9
at wrist joint 58
- Anal canal 415 480 483 590 678
65 659
arteries 481 483-487
columns of Morgagni 48 487
crypts of Morgagni 491
fissure 487
lines 487 491
lymphatics, 494 495 609
muscles, 480 482 483
nerve 617
papillae 487
valves 487
veins 481 48 48 490
- Anal membrane 487
- Anatomical collateral between in
ternal and external carotid ar
teries 197
crucial 793 827




FIG 719 Caudal anesthesia

passed through the median line. When the subarachnoid space is entered spinal fluid escapes upon removal of the obturator.

Sacral Block Anesthesia Lundy includes caudal and transsacral block under the term "sacral block anesthesia." This is extradural and reaches the nerves within the sacral canal. In *caudal anesthesia* the needle is passed through the sacrococcygeal ligament and into the sacral hiatus (Fig 719). The position of the needle is then changed and is passed upward along the axis of the sacral canal for about an inch or an inch and a half. The anesthetic agent




FIG 720 Transsacral anesthesia

is then injected. If the needle has been placed improperly it usually fails to enter the sacral canal and passes superficial to the posterior aspect of the sacrum. *Transsacral anesthesia* is produced by injecting about the sacral nerves via the posterior sacral foramina (Fig 720). The postero-superior iliac spine makes a good landmark for this type of anesthesia. About one cm medial to and just below these spines, the second sacral foramina usually are found. The first pair of sacral foramina can be located on a line opposite the tip of the transverse process of the fifth lumbar vertebra. The distance between the foramina is approximately one inch.

- Anastomosis (Continued)**
 portacaval 431
 capular 689 690
 of small intestine 461 462
 utero ovarian 605
- Anastomotica magna** 105
- Anatomic nuff box** 134 717 738
 149 752 169
- Anconeus artery** 71 716
- Anconeus muscle** 681 710 16 717
 19 721 124 133 745
- Andrus** 7
- Anemia** plenic 531
- Anesthesia** caudal 916
 from the ions of trigeminal nerve 121
 sacral block 552 553 916
 spinal 91 916
 subarachnoid 915 916
 transsacral 553 916
- Aneurysm** 343
 aortic 358
 arteriovenous in axillary region 673
 of cavernous sinus 55
 of carotid artery 201 07 203
 cirroid 7 8
 femoral 611
 gluteal 611
 of iliac artery, external 609
 popliteal ligation of femoral artery for 822
- Angina** Ludwigs 152 163
- Angina pectoris** 189
- Angioma** 201
- Angle(s) of acromion** 681 682 694
 carrying ' of elbow joint 16
 colic 413 414 416
 costovertebral 295
 declination of femur 877
 duodenojejunal 438 440 441 446
 of inclination of femur 798
 of kidney 407
 of Loui 263 264 348
 of Ludwig 263 264
 neck shaft vertical of femur 827
 recto anal 577
 scalenovertebral 257
 of scapula inferior 400 441
 sternal 259 63 264 321
 superior of scapula 619 680
 thyroid 240
 of uterus suprolateral 592
See also Flexure
- Angular notch (incisura angularis)** 425 427
- Angular vein** 48 51 119 153 154 162
- Ankle** 869 880
 arteries 873 874
 binding bands 810 872
 bones navicular 815
 fascia deep 810 873
 fatty areolar tissue 869 871
- Ankle (Continued)**
 joint 869 874 880
 bones 876
 dislocations 819 880
 dorsiflexion 876
 flexion plantar 876
 ligaments 816 877
 membrane synovial 817
 movements 878 879
 nerves 877
 skin 869
 surgery of 819 880
 dislocations of joint 819 880
 Pirogoff amputation 879
 Symes amputation through ankle joint 879
 tunnel osteo aponeurotic 810
- Annular ligament** anterior See Flexor retinaculum
 posterior See Extensor retinaculum ligament
- Annulus fibrosus** 906 907
- Annulus ovalis** 339 340
- Anoxemia** from pulmonary stenosis or atresia 353
- Ansa hypoglossi** 184 186 191 195
- Ansa subclavia** 186 420 423
- Anson** 130 277 383 386 394 405 407 417 510
- Anterior ligament of elbow** 710
- Anterior vein of heart** 336
- Antihelix** 105
- Antitragus** 105
- Antrotomy** 112 114
- Antrum of Highmore** See Sinus maxillary
- pyloric** 425 427
- tympanic** 21 23 38 54 110 114
- aditus** 110 112
- fenestra ovalis** 112
- semicircular canals** 106 112
- urgery** 112 114
- walls** 112
- Anus** 478 501 560 578 586 638 650 652 657 659
 lymphatics 609
 skin 658
 sphincter muscles external 501
- Aorta** 269 309 324 327 328 336 337 340 342 343 351 353 355 357 406 409 413 414 474 446
 abdominal 449 451 457 464 481 484
 arch of 205 208 221 307 320 322 323 336 338 341 343 350 353 419 422
 ascending 320 331 338 343 345 350 352
 descending 306 320 324 329 338 343 346 347 357 421 441 443 510 530 536 598 605 609 617 618
 inus 344 347
 surgery 353
- Aortectomy** 353
- Aortic lymph glands** 592 93 607 610
- Aortic plexus** 593 612 644
- Aperture** laryngeal 236
- Apical lymph glands** 159, 160
- Aponeurosis(es)** bicipital 718
 brachial 696
 dorsal 716
 epicranial 314 19
 of muscle abdominal 263 555
 oblique 264 265
 transversus 264 265
 palatal 154 155
 palmar 751 759 163 165 168
 phalangeal 163 164 166
 pharyngeal 231
 plantar 883 885 887 889 894 897 899
- Apoplexy** artery of 50
- Appendectomy** 310 377 375 410 471
- Appendices epiploicae** of large intestine 465 467
- Appendicitis** 469 515
- Appendicular artery** 469 484 485 543
 testis 581
- Appendix auricular** 338
 vermiform 465 471 543
 ab cess 469 470
 mesentery 469 471 543
 position 468
 site of 468 469
 surgery of appendectomy 410 471
 incisions McBurney 310 372 375 471
- Aqueduct of cochlea** 115 117
 of Fallopius 112
 of Sylvius 33 35 38 42 44
 of vestibule of inner ear 21 26 116 117
- Arachnoid** 4 37 40 41 52 59 60 87 908
 granulations 37 39 41 53
 pinal 909 910
- Arc parieto occipital** 32 33
 villi 53
- Arcade(s) inguinal** 385 386
 of pancreas 453 454
- Arch(es) of aorta** See Aorta arch of
 of atlas 46
 axillary 669 670
 of azygos vein 318 320
 carpal dorsal 736 779
 coraco acromial 684 694
 costal 441 511
 of foot 895 897
 fascia 897
 ligaments 897
 longitudinal 895 896
 muscle 897
 tendons 896

Artery (ies) (Continued)

lenticulostriate 50
 lienal *See* Splenic artery
 lingual *See* Lingual artery
 lip 120 144 145
 of liver 510 511
 lumbar 404 610
 of lungs 313
 macular 91
 malleolar 8/4
 mammary external *See* Thoracic artery
 internal *See* Mammary artery
 internal
 marginal of Drummond 486 542
 masseteric 137 138
 maxillary *See* Maxillary artery
 median 31
 medial 347
 meningeal *See* Meningeal artery ✓
 me enteric *See* Mesenteric artery
 metacarpal palmar 7/0
 metatarsal plantar, 887
 midcolic 498
 muscular 196
 musculophrenic 2/0 271 290
 mylohyoid 137
 nasal 81 82 95
 of nose 90 95 139
 obturator *See* Obturator artery
 occipital *See* Occipital artery
 ophthalmic *See* Ophthalmic artery
 of orbit 53 88 138 139
 ovarian 591 593 596 603 605 610
 of ovary 593
 of palate hard 153
 soft 157
 palatine 95 138 139 155 164
 palmar superficial 763 769
 of pancreas 536 537 540 543
 pancreatic 451
 pancreatoduodenal *See* Pancreaticoduodenal artery
 of parotid gland 150
 of pelvis 600 606
 of penis 575 602 629 630 633 634 636 637 639
 perforating 593 805 821
 pericardial 347
 pericardiophrenic 2/1 290 325
 pericranial 52
 perineal 602 633 654 657
 peroneal 853 856 860 861 864 867 871 874
 pharyngeal 24 139 157 164 194 197
 of pharynx 139
 phrenic 290 325 353 4 0 421 443
 plantar 8 0 874 8/8 882 883 886 887
 popliteal *See* Popliteal artery
 princeps pollicis 563 769

Artery (ies) (Continued)

profunda brachii 697 702 705 715 716
 profunda femoris 811 813 815 817 826 827
 profunda linguae 160
 of prostate gland 577 580 581 607
 pterygoid 138
 of pterygoid canal 95 138, 139
 pubic 602
 pudendal *See* Pudendal artery
 pudic *See* Pudendal artery
 pulmonary *See* Pulmonary artery
 radial *See* Radial artery
 of radiocarpal joint 753
 rectal *See* Hemorrhoidal artery
 of rectum 479 481 483 487 540 603
 recurrent of eyeball 87
 interosseous, 105
 radial 105
 ulnar 105
 renal 405 407 597 598 605
 of retina central, 77 81 82 85 87
 retroduodenal 452 453
 of ribs 261 262
 sacral 4/8 481 484 487 567 600 601 610 621
 saphenous 833
 of scalp 5 6 150
 scapular 246 675 677 679 689 690
 scrotal 602
 of seminal vesicles 573 603
 sigmoid 474 481 484 486 493 497
 permeatic 379 406 500 599 643
 phenopalatine 95 138 139
 pinal anterior 47
 of spleen 531
 See Splenic artery
 sternocleidomastoid 196 206
 of stomach 428 479 450 540 541
 subclavian *See* Subclavian artery
 subcostal 2/0 347 473
 sublingual 148 164
 submental 194
 subscapular 286 400 673 674 677 6/9 689 690
 supraduodenal 452 453
 supra orbital 5 7 86
 suprarenal 325 406
 suprascapular 188 246 248 251 253 689 690 702
 supratrochlear 5 86 715 718
 of teeth 99 137 138
 temporal *See* Temporal artery
 of temporal and infratemporal regions 137 139
 testicular 382 473 573 596 597 647 643 645
 thoracic 278 280 286 673 674 677 679 689 690

Artery (ies) (Continued)

thoraco acromial 278 2/9 6 0 672 674 6/9
 thoracodorsal 675
 of thumb 769
 of thymus gland 220
 thyrocervical trunk 252 253, 689
 thyroid *See* Thyroid artery
 of thyroid gland 206
 thyroidea ima 177
 tibial *See* Tibial artery
 of tongue 158 160
 of tonsils 164
 of tube uterine 592 605
 tympanic anterior 137 138
 ulnar *See* Ulnar artery
 umbilical *See* Umbilical arteries
 ureteral 597 603 608
 urethral 629 654
 uterine 589 590 592 593 595 597 601 603 605 608 610
 of vagina vestibule bulb 589 590 657
 vaginal 590 603
 of vas deferens, 602 603 643
 vasa brevia 325 428 429 529 530 532 533 541
 vertebral *See* Vertebral artery
 vesical *See* Vesical artery
 vidian *See* Pterygoid canal artery of
 of viscera pelvic 600 605 603 vitelline 414 415
 zygomatic 86
 Arthritis 189 360
 Arthrodesis of wrist joint 57
 Arthroplasty of elbow joint 722
 Articular capsule of temporomandibular joint 141
 Articular ligament of shoulder joint 686 688
 Articular process 906
 Articularis genu 824 831
 Articulation carpometacarpal 754
 condylar 838 839
 intercarpal 754
 patellar 838 839
 pisiform 754
 pollicis carpometacarpal 754
 radiocarpal 754
 radio ulnar distal 754
 sacro iliac 553
 Aryepiglottic muscle 235 237 238 240
 Arytenoid cartilage 1/0 211 231 233 240
 Arytenoid muscles 233 235 237 240
 Aspiration of elbow joint 722
 of foreign body 316
 Astereognosis 32
 Asterion 18
 A thma bronchial 189
 Atlanto axial ligament anterior 907 908

- [illegible]

- Bone(s) (*Continued*)
 lacrimal 14 16 75 92
 lunate *See* Lunate bone
 malar resection 161
 mandible *See* Mandible
 mastoid temporal 22
 maxilla *See* Maxilla
 metacarpal *See* Metacarpal bones
 metatarsal 882 889 891 895
 896
 multangular *See* Multangular bone
 nasal 14 17 90 92 94 121 128
 navicular *See* Navicular bone
 occipital *See* Occipital bone
 os magnum *See* Capitate bone
 palatine *See* Palatine bone
 parietal *See* Parietal bone
 pelvic 547 555
 phalanges of foot 889 892 898
 pisiform *See* Pisiform bone
 premaxilla 119
 pubis *See* Pubis
 ribs *See* Ribs
 scaphoid *See* Navicular bone
 semilunar *See* Lunate bone
 sesamoid of foot 886 891 892
 sphenoid *See* Sphenoid bone
 sternum *See* Sternum
 talus 887 889 890 892 897
 temporal *See* Temporal bone
 of toes phalanges 897 898
 trapezium *See* Multangular bone
 greater
 trapezoid *See* Multangular bone
 lesser
 triquetrum 748 750 754 772
 turbinate 45 75 91 92
 unciform *See* Hamate bone
 vomer 90 92 93 139 228
 zygoma *See* Zygoma
- Border falciform 814
- Brachial artery 673 679 697 699
 '03 70' '06 '13 715 721 728
 729
 surgery of 706 708
 ligation '07
- Brachial plexus 179 190 244 246
 249 272 284 673 675 678 699
 711 911 917
 branches 675 677
 cords 673 677
 divisions 675 676
 palsy 678 679
 Klumpke 678 679
 relation to axillary artery 677
 678
 roots 675 676
 surgery 678 679
 syndrome radicular 678 679
 trunks 675 676
- Brachial region 696 713
- Brachial veins 672 697 699 '06
 713
- Brachial venae comites 679
- Brachialis muscle 249 678 680 681
 696 698 700 '01 '03 '05 710,
 713 715 719 722 724 728 729
- Brachioradialis muscle, 249 678 680
 696 697 '01 710 713 716 719
 726 728 730 732 750
- Bradley 432
- Brain 30 58
 abscess 114
 arteries 47 49 50
 convolutions 30
 embryology, 30
 exposure of osteoplastic craniot-
 omy 24 26
 trephining operation 24 26
 hemispheres 30 36
 lobes 30 36
 central 30 34 50
 frontal 31 32 36
 occipital 30 33 34
 paracentral, 33 35
 parietal 30 32 33
 tumor 32 33
 temporal 30 33
 mass intermediate 33
 proper 30 36
 surface inferior 33 36 39
 veins 48 55 57
 weight 30
- Bramwell 333
- Breast 274 286
 abnormalities congenital 274 276
 amastia 274
 gynecomastia 274
 polymastia 274 276
 polythelia 274 276
 abscess 281 282
 accessory tissue 274
 areola 276 277
 arteries 277 280
 lymphatics 279 281
 axillary 279 280
 axillary 279 281
 bronchopulmonary 280
 cephalic gland 281
 cervical set deep 279 281
 cutaneous 279 280
 pectoral plexuses 281
 sternal 280
 zones of cancer spread 281
- malformations embryologic 274
 276
- mastectomy radical 281 286
 anatomic steps 281 283 286
 incisions 281 283 285
 milk line 274 275
 nerves 281
 nipple 274 277 280 281
 tumor malignant 275
 veins 280
 See also Mammary gland
- Breast bone *See* Sternum
- Breathing abdominal (diaphrag-
 matic) 257
 intercostal (thoracic) 257
- Bregma 11
- Broad ligament of uterus 581 585
 587 590 593 603 621 623 674
 659 661 663
- Broca's area 31
- Bronchial arteries 347 420 422
- Bronchial lymph nodes 420 422
- Bronchial veins 334
- Bronchiectasis 316
- Bronchoesophageal muscle 320
- Bronchus(1) 170 221 303 305
 307 313 316 323 325 422 423
 arteries of 313 325
 eparterial 305 307 313 319 320
 extrapulmonary 319 320
 hyparterial 305 307 313 319 320
 lymph glands 322 323
 nomenclature 310
 primary 303 318 319
- Bronchial veins 354
- Buccal artery *See* Buccinator artery
- Buccal glands mucous 149
- Buccal nerve 64 67 121 124 127
 129 132 136 138 140 146 149
- Buccinator artery 138
- Buccinator muscle 5 67 119 120
 122 124 129 132 135 136 138
 139 149 152 163 250
- Buccopharyngeus muscle 153
- Buck fascia of 635 637
- Bulb carotid 195
 of penis artery to 631 634
 of vestibule 652 654
 artery of 654 657
 vein of 654
- Bulbar artery 602
- Bulbocavernosus artery 637
- Bulbocavernosus muscle 501 565
 575 579 589 627 629 631 638
 651 658
- Bulbospongiosus muscle *See* Bulbo-
 cavernosus muscle
- Bulbo urethral artery 633
- Bulbo urethral glands *See* Cowper
 glands of
- Bulbus urethrae 638
- Bulla ethmoidalis 91 93
- Bundle Helweg's 913
- Burdach fasciculus cuneatus 913
 914
- Bunion 899 900
- Burns space of 175 176 178
- Bursa(e) of ankle 870 871
 anserine 853
 of elbow joint 717
 of knee joint 845 848
 obturator 797
 olecranon 719 721
 omental 473 424 426 434 537
 prepatellar subcutaneous 839
 psaos '97 799
 radial 766 782 783
 infection '80 781
 subacromial 683 684 687 689
 subdeltoid 683 684 687 690 692

Cartilage (Continued)

- corniculate 233 235 237 239
- costal *See* Costal cartilage
- cricoid *See* Cricoid cartilage
- cruciform 233 235 239
- hyaline 318 739 827
- of knee joint 847 844
- of larynx 33 235
- Meckel's 150
- of nose 90 95
- of Reichert 150
- ring of trachea 150
- of Santorini 235 239
- semilunar *See* Semilunar cartilage
- thyroarytenoid 233
- thyroid *See* Thyroid cartilage
- triangular segment 247
- triticeous 1
- of Wrisberg 235 239
- Cartilago triticea* 36
- Caruncle 12 14
- hymenal 651
- lacrimal 83
- ulbicular 146 148
- Carunculae myrtiliformes 651 664
- Cataract 83
- Cattell 356
- Cauda equina 311 907 908 911 917
- Caldwell 150 405
- Causalgia 189 360
- Cave articular of sacro iliac region 557
- of Meckel 62
- Cavernous artery 637
- Cavernous plexus 89
- Cavernous sinus 12 50 51 53 55 57 58 82 119 120 140 152 154 162 195 197
- thrombosis 55 57 119 153 154 167
- Cavity (ies) alveolar 149 151 157
- articular of hip joint 97
- buccal 143 148 149 153
- condylar 846
- glenoid of scapula 659 680 684 686 688 698
- of larynx 238 239
- mandibular 19
- nasal 153
- oral 152
- orbital 16
- patellar 846
- pericardial 324 332 335
- peritoneal 537
- pleural 294-302 324 441
- pulp of teeth 151
- synovial 142
- thoracic 250
- of tunica vaginalis testis 642
- tympanic 22 139
- See also* Foramen
- Cavum trigeminale 62
- Cecal artery 484

Cecostomy 495

- Cecum 374 414 458 459 465 468 472 498 617 618
- carcinoma of 492 93
- embryology of 462 465 467
- frenulum 466
- resection of 492 493
- taenia coli 467
- Celiac artery 424 478 434 540 541
- Celiac lymph glands 420 431 511
- Celiac plexus 69 420 433 453 459 494 495 497
- Cells ethmoid 86 93 101 104
- Cellulitis orbital 105
- Celom 303
- Cement of teeth 151
- Centers sensory projection 32
- Central artery of retina 77 81 82 85 87
- Central vein of retina 87
- Cephalic vein 283 285 60 612 673 618 691 696 697 699 717 716 719 724
- of Treves 737
- Ceratocarcinoid ligament 233
- Cerebellar artery 47
- Cerebellar veins 50 52 53
- Cerebellum 24 33 36 39 46 47 50 914
- abscess, 54
- Cerebral artery 40 50
- anterior 47 49 50 86 195
- middle 41 47 195
- posterior 36 47 49 50
- Cerebral veins 34 40 50 52 54
- of Galen 53
- Cerebrospinal fluid 73 40 44 47 53 910 911
- blood in 41 42
- Cerebrum 38 50
- areas motor and sense 31 50
- capsule internal 50
- centers motor and sense 30
- convolutions 50
- cortex 31 50
- visual 59 60
- hemispheres surface 50
- hemorrhage 50
- lobes frontal 23 42 47
- occipital 34 39 42 50
- paracentral 50
- parietal 32 47
- temporal 33 39 41 42 47 59
- temporoparietal 50
- tumors 47
- Ceruminous glands of ear external 107
- Cervical artery deep 201 246
- superficial 246
- transverse 188 201 246 248 251 253 679 689 690
- Cervical chain of lymph nodes deep 146 147 160 164
- Cervical fascia (deep) 156 180 243 245 330

Cervical fascia (deep) (Continued)

- buccopharyngeal 179 180
- layers deep 174 180
- enveloping 154 158 180
- general investing 154 178 180
- middle 174 159
- prethyroid 177 178
- pretracheal 154 179
- prevertebral 154 180
- superficial 154 158 180
- Cervical ganglion 68 119 185
- Cervical glands deep 95
- Cervical ligament transverse 582 585
- Cervical lymph nodes 6 420
- Cervical nerves 67 124 127 154 155 184 191 193 248 249 675 676 678 679
- sympathetic 185 187
- Cervical plexus 184 185 911 912
- Cervical rib surgery for 247 248
- Cervical sinus 151
- Cervical vein 48 183 197 245 252
- Cervical vertebrae 169 356
- Cervicofacial nerve 66 67 132 133
- Cervicovaginal artery 603 605
- Cervix of uterus 560 581 584 589 595 598 619 672 661 662 664
- arteries 603
- displacement 584
- external 587 591
- Chalazion 73
- Charcot Jean Martin 50
- Chassagnac tubercle of 252
- Cheek(s) 147 148
- arteries 149
- layers 148 149
- lymphatics 149
- mucous membrane 136 138 140 149
- muscle 126 129 136
- nerves 121 149
- skin 148
- Chest a piration 298 299
- Chiasma optic 33 36 55 58 60 87
- Chin 17 18
- lymphatics 180
- muscles 126 129
- nerves 67 121 124
- Choanae of nose 11 12 228
- Cholecystectomy 525 527
- Cholestylin 515
- Cholecystoduodenal ligament 519 522 525 526
- Cholecysto enterostomy 528
- Cholecystogastrostomy 528
- Cholecystojejunostomy 538 539
- Cholecystostomy 525
- Cholecholestostomy 527 528
- Choledochal fistula 881 895 896
- Chorda tympani nerve 20 65 108 310 112 140 142 158
- See also* Facial nerve
- Chordae tendinae 340 341 343
- Choroid tela 41

- [illegible]

- Connexus, interthalamic 35
 Conoid ligament 686
 Constriction broncho aortic 418
 duodenopyloric 421
 Constrictor muscle(s) of auditory
 tube 136
 of pharynx 196 231
 inferior 195 205 208 209 222
 223 226 230 231 233 234
 236
 middle 159 224 226 230 231
 236
 superior 12 163 164 226 230
 231
 of trachea inferior 319
 Contracture Dupuytren's 762
 Volkmann's 712 718
 Conus elasticus 233 236
 Conus medullaris of spinal cord
 911
 Convulsions 201
 Cooper ligaments of 77 277 381
 383 714
 Coraco acromial ligament 687 686
 690
 Coracobrachialis muscle 249 283
 669 671 673 675 676 679 682
 684 686 690 696 698 700 704
 705 709 711
 Coracoclavicular ligament 686
 Coracohumeral ligament 686 687
 710
 Coracoid process of scapula 283
 285 669 670 673 675 684 692
 694 696 698 699
 Coraco umbilical line 283 285
 Cord(s) oblique 715
 spermatic *See* Spermatic cord
 pinal 908 915
 umbilical hernias 396 397
 vocal 234 235 238 239 242
 false 233 236 240
 true 233 236 240
 Corneo clerical junction 78
 Corniculate cartilage 233 235 237
 239
 Corniculopharyngeal ligament 233
 Cornua coccygeal 551 553
 of hyoid bone 10 173 226 233
 236
 sacral 551 553
 of uterus, 585 586 623 674
 Corona of glans penis 633 635
 636
 Coronary artery of stomach *See*
 Gastric artery left
 Coronary ligament(s) of knee
 joint 842 844 845
 of liver *See* Ligament triangular
 of liver
 Coronary vein 323 420 489
 Coronoid process 17 18 20 134
 714 715 740
 Corpus(ora) callosum 30 33 35
 59
 Corpus(ora) (*Continued*)
 cavernosum of penis 630 634
 635 653
 cavernosus muscle 589
 mammariae 217
 mamillariae 38
 quadrigeminum 38 59
 pongiosum of penis 631 634
 635 638
 of uterus 591
 Corpuscles touch of tongue 158
 Cortex cerebral functional locali-
 zations 31
 Corti organ of 116 118
 Co tae *See* Ribs
 Costal cartilage 257 262 263 265
 267 333 343 348 363, 441 511
 Costocervical trunk of nerves 190
 Costoclavicular ligament 264 266
 Costocoracoid ligament 669 670
 672
 Costocoracoid membrane 281 669
 670 672 679 716
 Costotransverse ligament 260
 Cowler 614 615
 Cowper glands of (bulbo urethral
 glands) 575 630 634 638
 639 657
 excretory duct 639
 orifice 639
 Cranial fossa anterior 16 21 23
 30 36 91 92
 middle 21 23 24 30 36 114 137
 posterior 21 24 26 38 43 116
 Cranial nerves 41 58 71 130 184
 186
 Craniectomy 28
 Craniotomy osteoplastic 24 26
 Cranium 4 9 30 37
 Creae of skin *See* Skin creases
 Cremaster muscle 384 388 392
 393 640 642
 Cremasteric artery 644
 Crepitus 746
 Crest falciform of ischium 549
 of ilium 363 476 547 549 552
 618 589 590 794
 infratemporal 19
 lacrimal 127
 median of sacrococcygeal re-
 gion 551
 obturator 550 555
 occipital 12 13 39
 pubic 363 369 549 550
 supramastoid 18 20
 trochanteric 798 827 828
 urethral 566 577 637 638
 Crico arytenoid muscle 211 233
 235 236 238
 Cricoid cartilage 10 172 174 178
 20 211 221 228 229 231 233
 235 240 241 243 318 319 418
 419
 Cricopharyngeal muscle 222
 Cricothyroid artery 196 236 241
 Cricothyroid cartilage 236
 Cricothyroid ligament 233 319
 Cricothyroid membrane 172 174
 211 234 236 240 241
 Cricothyroid muscle 170 205 209
 231, 235 238 319
 Cricotracheal ligament 234
 Cricovocal membran 233
 Crista galli 15 21 22, 39 44
 Crista terminalis 339 340
 Crista urethralis 575
 Cruciate ligament 879 832 839
 840 842 844 846 847 854 857
 863 870 873
 Crural ligaments 288 289 870 871
 873
 Crural muscle 876
 Crus (crura) antihelicus 105
 of clitoris 652, 653 655
 helicus 105
 of penis 575 575 631 633 635
 Crusta pedunculi of inferior surface
 of brain 35 38
 Crusta petrosa 131
 Crypt(s) of gorgagni 491
 tonsillar 163
 Cryptitis 482
 Cubital vein 717 725
 Cubitus valgus 716
 Cubitus varus 716
 Cuboid bone 882 889 891 893 896
 Cuboid ligament calcaneus dorsalis
 875
 Cuboid midtarsal joint 881
 Cubometatarsal joint 893 894
 Cul de sac of Douglas *See* Pouch
 of Douglas
 of vestibule of mouth 148
 Cuneiform bone of foot 887 889
 891 893 895 896
 of wrist *See* Triquetrum bone
 Cuneiform cartilage 233 235 239
 Cuneocuboid ligament interosseous
 893
 Cuneonavicular joint 893 894
 Cuneus 33 36
 Cushion eustachian 228
 Cutaneous nerve(s) of abdominal
 wall anterior 272
 antibrachial 669 699 718 719
 of arm 670 675 682 696 698
 700 702 713
 of external ear 107
 of foot 881 883
 of forearm 669 670 700 717
 724 725 736 737
 of gluteal region 789 790
 of hand 774
 lateral 473
 of neck 107 181 185 244 245
 perforating 613 614
 perineal branch 655
 of shoulder 670
 of thigh 804 806
 intermediate 804 806 811, 813

- Cutaneous plexus (s) (Continued)
 of thigh (Continued)
 lateral 80 87 91 94 809
 811 819 816
 medial 804 808 811 819 852
 854
 posterior 814 80 91 91
 97 819 811 81 811 840
 81 814
 of thorax anterior 2
 Cyst(s) branchial 11
 of canal cranio-pharyngeal 57
 intestinal 195
 of jaw 150
 of mesentery 459
 of mouth 148
 "mucous," 145
 pancreatic 519
 of Rathke's pouch 57
 tarsal 11
 thyroglossal 94 216 218
 urachal 562 565
 Cysterna chyli of thoracic duct 608
 609
 Cystic artery 432 519 5 7 52
 541
 Cystic lymph glands, 431
 Cystocele repair of 651 661 663
 664
 Cystotomy, suprapubic 50 571

 Dacryocystitis, 75 1
 Dartos muscle 358 381 628 639
 641
 Darwin's tubercle 105
 Dascler 366 510 574
 David V. C. 494 665
 Davie 412 431
 Deafness, 110 228
 DeBlakes 247 617
 Decompression subtemporal 28
 Decortication pulmonary 102
 Defecation muscles of 309
 Deferent artery of testis 642
 Deferent vein of testis 642
 Deformity silver fork 746
 Deltoid ligament of ankle 863 875
 893
 Deltoid muscle 243 249 281 675
 6 8 680 685 687 690 694 93
 708 710 713
 Deltoid region 682 684
 fascia deep 682
 muscles 682 687
 skin 682
 Denonvilliers fascia of 564 567
 573 576 579 604
 Dens 905 906
 Dental artery. See Alveolar artery
 Dental nerve. See Alveolar nerve
 Dental veins 142 152 154
 Dentate ligament 909 910 912
 Dentine 150 151
 Dentition periods of 150

 Deter in cardiac in lung 107
 302
 Deter uer angulor otis (triangularis)
 muscle 121 1 1 1 8
 Detrusor latii inferioris (quad-
 ratus) muscle 1 6 128 2 6
 Detrusor ejil na i muscle 178
 Descemet's membrane 8 9
 Deterlin- 316
 Detrusor muscle 519
 Deyer 475
 Deviation of radio-carpal joint ra-
 dial 1 53 54
 ulnar 754
 Devine 476
 colostomy 495 476
 Diaphragm 221 764 81 93 101
 105 306 104 121 127 129
 312 315 357 409 419 441
 443 450 451 4 1 505 511
 513 515 540 609
 arteries 80
 attachments of liver 96
 crura 88 87 792 4 8 4 9
 410
 embryology 247
 foramina 90 97
 aortic 90 97
 conophrenic recess 92
 esophageal 90 292
 inferior vena cava 290 292
 hernia 291 291 98
 acquired 292
 congenital 292
 traumatic 292
 hernioplasty 291 291
 abdominal route 291 293
 tran thoracic route 291 293
 le ions 292
 muscle 264 407
 nerves 290
 origin 287 289
 costal 288 289
 crural 288 289
 sternal 288 289
 pelvic. See Pelvic diaphragm
 proper 287 290
 septum transverse 287
 tendon central 287 310
 urogenital. See Urogenital dia-
 phragm
 Diaphragma sellae 37 39 40 58
 Diaphragmatic veins 190
 Diaphysis, of finger 778
 of humerus 109 711
 of ulna 741
 Digastric muscle 133 142 147 152
 192 193
 anterior belly 62 127 131 134
 135 138 141 180 182 191 192
 224
 posterior belly 65 122 131 132
 159 164, 177 173 181 182
 186 191 192 195, 196 224
 226 227

 Diastolic trian le. See Submaxil-
 lary trian le
 Diastolic artery (ies) 7 6 771 782
 dorsal 779
 palmar 7 6 118
 velar common 7 9
 Digital nerves 64 717 779 780
 dorsal 717
 palmar 737 60 61 7 6
 Digital process of palmar fascia,
 662
 Diitus minimum 891 898
 Dilator naris muscle 128
 Dilator pupillae muscle 80
 Diploe 9
 Diploic vein(s) 40 42 57 54 120
 Diplopia 91
 Disarticulation carpometacarpal
 758
 Disease. See under individual names
 and parts
 Disk, articular of radio ulnar joint
 742
 of temporal bone 141 147
 of wrist 754
 intersvertebral 905 908
 Dislocation of elbow joint 71 722
 of fingers 785
 of lunate bone 756
 of phalanges, 185
 of radio ulnar joint 757
 of thumb 85
 of wrist 756 757
 Diverticulectomy 222 223 461
 Diverticulum duodenal 447
 esophageal 272 223
 hepatic 504
 of Meckel 395 459-461
 Dixon 353
 radical anterior resection of recto-
 sigmoid and sigmoid colon 489
 Dorsal artery of clitoris, 607 654
 658
 of penis, 603 629 633 634 636
 617 639
 Dorsal nerve of clitoris, 589 614
 of penis, 481 575 614 629 634
 616 637 639
 Dorsal region of hand 759 774 716
 Dor al vein of clitoris 606
 of penis 516 577 606
 Dorsalis linguae artery 164
 Dorsalis p dis artery 855 874 878
 881 882 883
 Dorsiflexion of foot 854 855 876
 878 897
 Dorsum ili 548
 Dorsum sellae 57
 Douglas cul de sac of. See Doug-
 las pouch of
 line of 367 1 0
 pouch of 516 586 588 662 663
 Dragstedt 329
 Drummond marginal artery 486,
 542

- Duct(s) bile common 427 428
 448 449 452 503 516
 528 536 539
 embryology 518
 parts, 521 528 542
 re section of lower end 539
 types of union with pan
 creatic duct 523
 cochlear 67 106 116 117
 cystic 518 522 523 527
 deferent 571 573
 ejaculatory 563 565 573, 574
 5, 6 577 581 618 639
 of Gartner 581 582
 gastric 429 434
 hepatic 431 07 508 518 523
 526 577 536
 intestinal omphalo (vitello) 460
 lacrimal 72 75
 surgery 76
 lactiferous 277
 mesonephric 581 582 627 628
 mullerian 581 587
 mesentery 581
 nasolacrimal 73 5 91 93
 omphalomesenteric 394 414 416
 pancreatic 519 522
 accessory of Santorini 450
 534 537
 types of union with common
 bile duct 523
 of Wirsung 334 536
 pancreatoduodenal 429 434
 paramesonephric 581 582
 para urethral 651
 parotid 127 129 134 136 138
 148 149
 prostatic 638
 semicircular of inner ear 67 117
 of Skene 651
 spermatic 81
 Stensen's See Duct parotid
 sublingual 148
 submandibular 140
 submaxillary glands lymph 146
 salivary 148 226 227
 thoracic See Thoracic duct
 thyroglossal 204 216 218
 embryology 216 217
 tumors 216
 vitello intestinal 364 394 414
 415
 Wharton's See Duct submaxil
 lary
 wolffian 562 581 582
 Ductules efferent of testis 641 642
 Ductus arteriosus 351 353 415 417
 of fetus, 343
 Ductus choledochus See Duct bile
 common
 Ductus deferens See Vas deferens
 Ductus endolymphaticus 116 117
 Ductus utriculosaccularis 116 117
 Ductus venosus 415 417 507 508
 Dullness cardiac area of, 297 307
 Duodenal ulcers, 329
 Duodenum 414 424 425 426 430
 438 440 444 454 457 458 473
 498 506 509 516 519 521, 524
 526 536 538
 arteries of 452 453 540
 diverticulum, 447
 divisions of 447-450
 embryology 418 445 448
 lymphatics 453
 mesentery 447 450
 nerves of 453
 parts 447 450
 resection of 539
 Dupuytren's contracture 762
 Dura mater 4 24 25 28 30 37 39
 41 46 52 53 57 60 62 64 87
 140 908 909 911
 arteries 137
 venous sinuses 50 53 55 57 58
 Duval Barastay incision for exposure
 of heart 349 352
 Dy pareunia 651
 Dyspnea 210 236 237
 Ear 105 118
 conchae 105 107
 drum See Tympanic membrane
 external See External ear
 internal See Internal ear
 middle See Middle ear
 Ectoderm 169 170 910
 Edema of face 119
 infectious about the throat lar
 yngotomy for 242
 of larynx laryngotomy for 242
 tracheotomy for 242
 of lips 143
 Effusion pleural 298
 Elbow 714 722
 back of arteries 721
 joint 714 716
 arteries 715 716
 arthroplasty 722
 a piration of 722
 bursa 717
 capsule articular 721 722
 carrying angle 716
 dislocation 721 722
 extension 714 716
 fat pads 714
 flexion 714 716
 humero radial part 714
 humero ulnar part 714
 ligaments, 710 714 715
 movements 716
 nerves, 715
 relations, 715 717
 surgery of 721 722
 approaches 720 721
 arthroplasty 722
 a piration 722
 dislocation 721 722 [722]
 fracture of olecranon process
 minors 721
 Elbow (Continued)
 region 716 720
 arteries 720
 fascia 716
 veins 716 718
 skin 721
 Elkin D C 352
 Von Flsberg's forked denticulation
 910
 Embolism 313
 Embolus pulmonary Trendelen
 burg operation 335
 of bladder urinary 394 562 563
 of brain 30
 of breast malformations 274 276
 of cecum 462 465, 467
 of diaphragm 287
 of duct bile 518
 thoracic 356 357
 thyroglossal 216 217
 of duodenum 418 445 448
 of esophagus 418
 of face 119 120
 of gallbladder 518
 of gastro intestinal tract 413 417
 of gland thymus 220
 thyroid 203 204 206
 of hypopharynx is 55 57
 of intestine large 462 464
 of liver 504 507
 of lungs 303 418
 of mammary gland 274 275
 of neck 169 173
 of pancreas 534 535
 of perineum 627
 of rectum 384
 of skull 9 10
 of spinal cord 910
 of spleen 529
 of sternum 262 263
 of stomach 418 422 424
 of tongue 304
 of vagina 394
 of viscera pelvic female 581 582
 Eminence arcuate 21 23
 frontal 14 15
 hypothecar 748 749 759 767
 781
 muscles 773 776
 ilio pubic 548 550
 intercondylar of tibia proximal
 end 862 863
 parietal 10 58
 pectineal 549
 thenar 759 760 769 773 774 781
 muscles 773 774
 Emissary veins 22 48 50 51 53 54
 condylar 54
 of foramen caecum 50
 mastoid 26 48 50 54
 ophthalmic 50
 parietal 48 50
 Emphysema 102 298
 Empyema 299 4 0
 of maxillary sinus antrum 101
 nontuberculous chronic 302

Eye (*Continued*)

canthus, inner 119
 cataract formation 83
 cell, bipolar 82
 ganglion 87
 visual 82
 chamber 17 9 82
 choroid 77 79 81 87
 coats, fibrous 17 78
 intraciliary choroidal tunic 79
 nervous 77 78
 pigmented 11 18
 uveal tract 19
 vascular tunic 19 80
 cornea 77 79 81 87
 corneoscleral junction 18 80
 dangerous area 80
 disk choked 88
 optic, 81 87 88
 Fontana's spaces 79
 glaucoma 83
 iris 11 80 82 87
 intra 80
 lacrimal apparatus 13 16
 lamina cribrosa 18
 lens 17 82 83
 capsule 9 80 82
 power of accommodation 82 83
 ligaments, 18 19 82 83
 lumbus, 78
 media aqueous humor *See* Eye aqueous humor
 lens 77 78
 vitreous humor *See* Eye vitreous humor
 membrane(s) 9
 Descemet's 18 79
 elastic, posterior 78 19
 hyaloid 82
 muscles, 18 80 83 84
 nerves, 19 60 80
 ora serrata 77 9 80
 papilledema 88
 presbyopia, 83
 process, ciliary 87
 pupil, 80 82
 dilated 61
 retina, 77 80 82 83 87 88
 "blind spot" 81
 central artery 77 81 82 85 87
 detachment 82
 fovea centralis 81
 lesions, 60
 macula lutea 81
 nerves, 19
 yellow spot 81
 rods and cones 82
 Schlemm's canal, 18 79 82 87
 sclera, 77 9 81 87
 sinus venosus sclerae 8 19 82
 space, of Fontana, 19
 zonular 9
 strabismus, external, 89
 stratum nigrum 9

Eye (*Continued*)

urgery enucleation 88 89
 synchysis 80
 vein, 78 82 87
 vitreous humor 71 18 82
 Eyeball 16 83
 conjunctiva 79
 Eyebrows muscles 128
 Eyelids, 72
 Eyelids 72 73
 arteries 73
 commissure 127
 glands of Moll 72 74
 sebaceous 72 74
 sweat 72 74
 of Zeis 72 74
 layers 72 74
 lymph drainage 13 131
 mucous membrane 12 14
 nerves, 63 64 72 73 120 121
 ptosis 61 73 89
 veins 73

Fabella 838

Face 119 166

arteries, 119 120
 boils, 119
 carbuncles 119
 dangerous area 48 119 144
 defects 119
 edema 119
 embryology 119 120
 glands sebaceous 119
 sweat, 119
 lymph vessels, 6 7
 muscles 126 129
 arteries of 130
 neuralgia 121 125
 nerves 120 123
 paralysis permanent from middle ear infection 110
 skin 119
 tumors 201
 vein, 120

Facial artery 90 119 120 127 136
 144 145 149 157 164 170 186
 196 197

submental branch 227
 transverse 130 131

Facial muscles, reflex pasm 121

Facial nerve(s) 37 47 63 67 73
 106 107, 110 113 114 122 127
 129 133 146 149 161 170 172
 183 193

canal for 112

cervical branch 120 226 243

paralysis, 136 144

See also Chorda tympani nerve

Facial vein(s) 57

anterior 5 48 50 51 120 127
 131 136 140 147 152 154 198
 199 226
 common 5 48 51 127 130 131
 147 154 172 195 198 199 0
 03

Facial vein(s) (*Continued*)

deep 1 0 140
 posterior 130 131 139 147
 183 195 197 199 245
 transverse 198
 Falciiform process, of acrotuberous ligament 333
 Fallopian tube *See* Uterine tube
 Fallopius aqueduct, 112
 Falx inguinal aponeurotic *See* Tendons conjoined
 Falx cerebelli 37 39 40 57
 Falx cerebri 22 30 37 39 40 54
 Fascia of abdominal walls upper
 ficial anterior 363 367 378 380
 of ampulla endopelvic, 559
 anal 559 657 659
 of ankle 810 873
 of arm 696 699 719
 axillary 275 281 669 670
 bicipital 718
 buccopharyngeal 129 149 179
 180 231
 of Buck 635 637
 of the bulb 83 85
 of Camper 366 378 380 388 389
 393 652 804
 cervical 142
 deep *See* Cervical fascia (deep)
 clavipectoral 669 670 672
 of Colles 363 366 380 388 389
 589 628 629 633 651 652 656
 colli 176 180 *See also* Cervical fascia (deep)
 criniform 803
 of deltoid region deep 692
 of Denonvilliers 564 567 573
 576 579 604
 of diaphragm layer visceral 6 7
 pelvic, 557 561
 urogenital 557 560
 elbow region 116
 endo abdominal 385
 endothoracic, 294
 of foot 883 885 897
 of forearm 719 737
 of gluteal region 189 790 807
 hypotheran 161
 iliac 554 560 809 810
 iliopectoral, 809 810
 infundibuliform *See* Fascia perineal, internal
 ischiorectal 657
 of knee joint, 840
 lata 365 366 380 555 628 630
 637 651 652 810 879 849
 of leg 843 852 854 856
 levator 659
 of lips superficial 143 144
 lumbar 290 402 410
 lumbodorsal, 401 404 411 553
 618
 lunata 558 560 654 659
 masseter 135 136
 muscular middle 160

Fascia (Continued)

of neck superficial 181 142 243
 of thorax 4, 8 554 560 542 631
 656 657 97
 orbital 83 85
 palmar 23 7, 8
 palpebral 11 17
 parietal 557 553 657
 parotidomastic 110
 pectineus 555 97 408 810 814
 pectoral 2, 5 50 169 6 2
 pelvic 501 557 561
 diaphragmatic 557 559 560
 layers 55, 559 560
 encephalic 557 553 561
 parietal layer 55, 559 657
 visceral 55 559 561 5 0
 perineal superficial 557
 pharyngeal buccal 136 142
 pharyngeal buccal 31
 of penis 615 615 617
 of perineum inferior 631 652
 653
 superficial 62 6 9 631 656
 layers 6 8 6 9 651 653
 popliteus 407 845 836 840 843
 preperitoneal 403 404
 pretracheal 1, 4 1 9 193 06
 215 244
 prevertebral 1, 4 140 193 195
 215 243 244 246 673
 of prostate gland superficial 575
 575, 90
 pubocervical 649
 rectal 560
 rectovaginal 569 659
 rectovesical 561 564 567 572
 5 4 5 8 5, 9
 renal 403 405 410
 retrorenal 403 411
 of Scarpa 365 366 3 8 380 388
 393 628 630 652 804
 of scrotum superficial 639
 of Sibson 189 257 258 294 304
 spermatic external 183 358 393
 internal 387 188 642
 of sphincter ani muscle 559
 subartorial 822
 temporal 19 20 28 121 130 134
 thenar 761
 of thigh 804 807 808
 transversus, 368 371 373 375
 3, 6 378 379 387 390 392 394
 402 405 412 515 554 555 558
 565 570 599 632 641 810
 triangular 383
 umbilical 3, 6
 uterovaginal 560
 vasto adductoria 822
Fasciculus cuneatus (Burdach)
 913 914
 gracilis (Golt) 913 914
 proprius 913
 sulcamarginal 913
See also Tract

Fat pad acetabular 793

of elbow joint 714
 of foot 883
 of fava ichthyorectal 656 659
 ileal 4, 0 471
 infrapatellar 839 841 846 847
 plantar 846
 retropubic 564
 pararenal 401 405 410 411 498
 perirenal 403 405 410 412 616
 preperitoneal 3, 4 3, 8 3, 9 388
 3, 0
 prevesical 5, 0
 proportionate 3, 6 391 394 502
 retrorenal 401 405 411
Fauces, larynx, 143 155
 pillars of nerves 68
Felon 1, 84
Femoral artery 167 3 9 380 401
 76 197 199 805 406 807
 815 817 819 822 8 9 832 849
 850
 circumflex 93 821, 830 831
 deep 805 817
 hemorrhage from 611
 lateral 97
 ligation of 815 822
 superficial 829
Femoral nerve 387 466 473 611,
 96 197 199 807 805 809 817
 819 848
 cutaneous branches 805 807
 819 8 6
Femoral vein 368 3 9 96 797
 197 801 805 806 809 811 815,
 81, 822 879 832 849 850
 ligation of 829 832
Femoris muscle 802
Femur 198 873 875 821, 836 838
 839 847 845 850
 angles, 799 827
 attachments 824 825 831 832
 condyles 827 829 832 834 841
 844 846
 crest trochanteric 195 827
 diaphysis 198
 distal end 829 830
 epicondyles 841 842
 epiphysis 798, 830
 groove 829
 head 793 795 197 798 807 803
 827
 lines 825 827 830 832
 measurements of length 823 827
 metaphysis 828 829
 neck 198 827 828
 notch intercondylar 829 845
 846
 pit 879
 proximal end 827 829
 reflection capsular 828
 shaft 824 825 830 833
 surgical approach 831 834
 surfaces 827 830
 surgery of 829 834

Femur (Continued)

trochanter greater 194 97, 198
 801 824 825 828 831 832
 834
 lesser 195 824 9 8 830 831
 surgical approach 830 832
 833
 tubercle adductor 823 8 4 827
 8 9 834
 quadrate 825 831
 tuberosity gluteal 8 5 830 831
fenestra cochlea 109 117
fenestra ovalis 106 112
fenestra rotunda 106
fenestra vestibuli 109 117
Fibers intercostal 503
 nerve 913 914
Fibrocartilag. semilunar 838
 of symphysis pubis 550
Fibula 84, 849 857 853 856 857
 863 869 875 8 6 8 9 873
 attachments 865
 end distal 864 865
 proximal 863
 epiphyses, 865
 head 863 865
 line epiphyseal 865
 malleolus, lateral 864 865, 876
 8, 8
 neck 863 865
 shaft 863 865
 borders, 863 865
 crest medial 864
 fracture 868
 surfaces 864 865
 styloid process (apex) 863 865
 urgency of approach 865 866
Fibular artery 838
Filum terminale 553 90, 909 911
 912
Fimbriae of uterine tube 591 592
Finger(s) abduction 771
 adduction 771
 diaphysis 7, 8
 dropped 785 786
 epiphysis 79
 extension 72 735 771 7, 6
 felon 784
 loose ball 785
 nail 777 7, 8
 nerves 160 164 7, 0
 phalanges, 77
 run around 784
 skin of flexor surface 777
 tendon sheath fibrous 164 166
 webs 162
 whitlow, 784
Fissure anteromedian of pupil
 cord 912
 for ductus venosus 507 508
 infra orbital, 19 20
 for ligamentum teres 507 508
 for ligamentum venosum 434
 405 508 510
 of lip lower 119

Fissure (*Continued*)

- longitudinal 30
- of lung 307 309
- orbital 14 16 21 23 140
- palpebral 72
- parieto occipital 32 33 50
- petrotympanic 137
- pterygomaxillary 19 20 137
- of Rolando *See* Sulcus central
- sphenoidal 99
- squamous tympanic 111
- of Sylvius *See* Sulcus cerebral lateral
- transverse of liver 505 507

See also Porta hepatis

Fistula(e) branchial 171 173

- fecal congenital 460
- umbilical 395
- parotid division of auriculotemporal nerve 140
- rectovaginal 664 665
- thyroglossal 204 218
- umbilical urinary 394
- urovaginal 663 664

Fistula in ano 487 490 491

Fistulectomy 491

Fits uncinate gyrus 59

Flexion of elbow joint 714 716

- of foot 858 859 876 878 879 888 897
- of forearm 723 732
- of hand 723 724 748 753 762
- of hip joint 800 819 822
- of knee joint 822 826 842 844 848 858 859
- of shoulder joint 690
- of thumb 774
- of toes 859 886

Flexor accessorius digitorum (quadratus plantae) muscle 882 884 885 887 889

Flexor carpi radialis muscle 723 724 726 728 733 772

Flexor carpi ulnaris muscle 715 717 719 721 723 724 726 727 745 750 766 772

Flexor digiti minimi muscle 772

Flexor digiti quinti brevis muscle of foot 882 884 886 887 889 of hand 773 775

Flexor digitorum brevis muscle 882 884 885 889 898

Flexor digitorum longus muscle, 853 859 861 863 865 872 873 875 882 884 885 887 889 898

Flexor digitorum profundus muscle 724 726 729 753 772 776 786

Flexor digitorum sublimis muscle 715 724 727 729 751 753 772 776

Flexor hallucis brevis muscle 882 884 886 887 889

Flexor hallucis longus muscle 853 859 861 864 865 872, 873 875 889

Flexor pollicis brevis muscle 764 772 774

Flexor pollicis longus muscle 724 727 750 753 766, 772

Flexor retinaculum 714 715 717, 723 739 740 746 750 755, 761 766 769 774 781

Flexor tendon common 710

Flexure colic left (plenic), 465 476 497

- carcinoma of 492 493
- resection of 492 493
- right (hepatic) 472 473 492 493 498 510
- carcinoma 493
- duodenojejunal 445 450 451 454 596

hepatic *See* Flexure colic right
splenic *See* Flexure colic left
See also Angle

Floating kidney 412

Fluid cerebrospinal 23 40 44 47 53 910 911

- blood in 41 42
- endolymph of inner ear 116 117
- perilymph of inner ear 116
- ubarachnoid 42

Fold alar 839 846 aryepiglottic 227 231 235 237 239 240

axillary 280 671 691 696

bloodless of Treves 468

of buttock 789

epiglottic 238

gastropneumatic 429 540

glossal epiglottic median 239

gluteal transverse 804

infrapatellar 839 845 846

interarytenoid 239 240

labioscrotal 639

pancreaticogastric 438

peritoneal 434

sacrogenital 564

salpingopharyngeal 227 229

sublingual 148

synovial 839 840 845 846 871

triangular 229

urorectal 562

ventricular of larynx 239

vesical transverse 564 585

vestibular of larynx 240

Follicles graafian 593

Fontana spaces of 79

Fontanelle(s) 9 10

anterior 9 11

anterolateral 10

posterior 9 10 22

posterolateral 10

Foot 881 900

arch(es) 895 897

abduction 896 897

adduction 897

fascia 897

ligaments 897

venous, dorsal 806 807

Foot (*Continued*)

arteries 887 888

apical medial 881

bones 889 892

accessory 890 892

sesamoids 886 891 892

deformities surgical treatment 899

dorsiflexion 854 855 878 897

dorsum 881

eversion 858 879 883 893 896

897

extension 854 855 878

fascia 883 885

fat pad 883 896

flexion 858 859 888

plantar 818 819 897

infections surgical treatment 898 899

inversion 854 855, 859 878 879

888 893 897

joints 892 893

ligaments 893 896

margin lateral 881

muscles 884 889

arches 897

insertions 889

origins 889

nerves 887 889

cutaneous 881 883

phalanges 889 892 897 898

skin 881

sole (plantar surface) 881 889

spaces 898 899

surgery, of 898 900

for deformities 899

for hallux valgus 899 900

for hammer toe 900

for infections 895 900

tendons 884 888

toes 891 897 898

Foramen acetabular 795 798

apical 151

caecum 21 22 54 157 158 203

204 216 217

emissary veins of 50

linguae 158

of diaphragm 290 292

epiploic (of Winslow) 423 434

521 524 5 6

ethmoidal 14 16 21 22

incisive lateral 139

infra orbital 14 16 17 121 128

intervertebral 34 42 44

intervertebral 600 912

jugular 12 13 21 24 54 10 197

lacerum 12 13 21 23 51 154

of Langer 275 276

of Luschka 42 44

of Magendie 41 44

maxillary 12 13 21 24 39 40

10 908 910

mandibular 18 136 137 141 142

mastoid 12 13 21 6

mental 14 17 18 121 141

Peramem (C. ninnud)

of Monro See Peramem Inter

Ventricular

nutrient of humerus 67

of tibia 843

obturator 342 350 356 602 836

optic 14 16 71 21 59 87

ovale of heart 139 415 417 507

of pithenoid 1 21 23 109 125

140 154

pulvinate 185

parietal 11 48, 50

rotundum 71 21 109

sacral 552 561 600 707 916

of Scarpa 92

sciatic 550 556 91 91 94

greater 552 60 606 614 657

658

lesser 552 602 657 658

phenolalinate 139

span sum 12 21 23 13 140

of Stensen 92

of sternum 6

stylomastoid 12 13 112 121

124 130

supra orbital 14 15 63

vertical 704

of Vesalius, 51

of Winlow (epiplex) 421 434

521 524 5 6

zygomatofacial 17

Forearm, major and minor 34

Forearm 723 747

amputations, 46 47

arteries, 28 731

compartments 776 736

extension 733

fascia deep 719 723

flexion 723 732

fractures, 45

membrane interosseous 741 45

muscles anterior (volar) region

723 74 7 6 30

posterior (dorsal) region 732

735

nerves 725 726 728 730

cutaneous 723 725

lateral 697 698 717 724

725 736

medial 6 0 673 675 677

688 697 698 705 707 717

724 725 737

posterior 670 677 697 698

717 725 737

Pronation 723 726 732 753

Region anterior (volar) 723 731

muscles 723 724 726 730

surgery of 731

exposure of radial nerve

731

ligation of radial and ulnar

arteries 731

extensor (dorsal) 736 738

fascia 737

skin 736 737

F *Forearm (Continued)*
region (Continued)
 posterior (dorsal) 723 31
 736
 muscles 732 733
 nerves 32 735
 supination 732 735 753
Foregut 540
Forehead *See* Frontal region
Foreskin of penis *See* Prepuce of penis
Fornix(es) 33 34
 conjunctival 73
 of uterus 587
Fossa(e) acetabular 95 798 99
 anterior 716 717
 articular 12 18 141 142
 areal 465
 cerebellar 40
 cornoid 680 68-710 714 739
 cranial *See* Cranial fossa
 cubital 712 716 718 720 72
 732
 for ductus venosus, 603
 digital 136
 duodenal 453 454
 duodenojejunal 453 454
 of gallbladder 510
 glenoid 694
 hypophyseal 40
 ileocecal 468
 ileocolic 468
 iliac 548 549 554 600
 incisive 11 12
 infraclavicular 682
 infra-pinnous 681 685 689 690
 infratemporal 12 16 19 70 99
 intercondylar 36 38
 intersigmoid 462 477 594 596
 hernia 462 477
 ischiorrectal 478 491 560 577
 578 614 629 634 656 659
 fat pad 659
 hernia into 559 659
 lacrimal 16 74 75
 limbus, 339 340
 malleolar 865
 mesentericoparietal 454
 hernia 454
 nasal 90
 navicular 638 639 650
 occipital 40
 olecranon 681 708 710 714 720
 ovalis, 339 609 807 809 814
 ovarian 592
 palatine 11 12
 paraduodenal 453 454
 hernia 453
 pararectal 571
 pericecal 467 468
 piniform 209
 popliteal 817 826 835 836, 838
 pterygoid 12
 pterygomaxillary 20
 pterygopalatine 99 137

Fossa(e) (Continued)
 radial 680 07 710 714
 retrocecal 467 468
 retrogastric 462
 hernia 462
 retrotrigonal 566 568
 Rosenmüller's 227 229
 scaphoid 155
 subcecal 468
 sublingual 148
 subscapular 631 656
 supraclavicular 281
 suprapubic 681 644 683
 suprasternal 162 166
 temporal 19 134
 terminal of urethra 638-639
 tonsillar, 163
 trans iliac, 105
 trochanteric, 556 16, 816 825
 8 & 831
 for vena cava 508
 of Waldeyer 45 454
 zygomatic 143
See also Cavity and Recess and Space
Fovea central 17
Fovea capitis, 93 97 98
Fracture(s) Bennett's, 185
 Colles 146 747
 reverse 147
 of fibula shaft 868
 of forearm 145
 of fossa cranial 23 24 26
 of frontal bone orbital plate 23
 over frontal sinus 107
 of humerus 716
 of jaw accompanying tooth ex-
 tractions, 151
 of meatus, auditory external an-
 terior wall 107
 of metacarpal bones 84 85
 of navicular bone 126
 of nose 96
 of olecranon process, 116 722
 of phalanges, 18 86
 Pott's 879 880
 of radius 745 146
 of skull confused with diploic
 markings on roentgenogram
 52
 Smith's, 747
 of phenoid bone 92
 of temporal bone squamous por-
 tion 51
 of tibia shaft 868
 of ulna 745 746
Frankenhauser plexus of 612
Frazer 204 216
Frazier 125
Frenulum of cecum 466
 of clitoris, 650
 of lips 155
 of penis 633 635 636
 of tongue 146 148 153 227
Frenum of clitoris 654

Fis ure (*Continued*)

- longitudinal 30
- of Lanz 307 309
- orbital 14 16 21 23 140
- palpebral 72
- parieto occipital 32 33 50
- petrotympanic 137
- pterygomaxillary 19 20 137
- of Rolando *See* Sulcus central
- phenoidal 99
- squamotympanic, 111
- of Sylvius *See* Sulcus cerebral
- lateral
- transverse of liver 505 507

See also Porta hepatis

- Fistula(e) branchial 171 173
- fecal congenital 460
- umbilical 395
- parotid division of auriculotem-
poral nerve 140
- rectovaginal 664 665
- thyroglossal 04 218
- umbilical urinary 394
- vesicovaginal 663 664

Fistula in ano 487 490 491

Fistulotomy 491

Fits uncinate gyrus 39

Flexion of elbow joint 714 716

- of foot 888 889 816 818 897
- 888 897
- of forearm 723 732
- of hand 773 724 748 753 762
- of hip joint 800 819 822
- of knee joint 822 826 842 844
- 848 858 859
- of shoulder joint 690
- of thumb 774
- of toes 859 886

Flexor accessorius digitorum (quad-
ratus plantae) muscle 882 884

885 887 889

Flexor carpi radialis muscle 723

724 726 728 733 772

Flexor carpi ulnaris muscle 715

717 719 721 723 724 726 727

745 750 66 772

Flexor digiti minimi muscle 772

Flexor digiti quinti brevis muscle of

foot 882 884 886 887 889

of hand 773 775

Flexor digitorum brevis muscle 882

884 885 889 898

Flexor digitorum longus muscle 853

859 861 863 865 812 873 875

882 884 885 887 889 898

Flexor digitorum profundus muscle

724 726 729 733 712 716 716

Flexor digitorum sublimis muscle

715 724 727 729 751 753 772

716

Flexor hallucis brevis muscle 882

884 886 887 889

Flexor hallucis longus muscle 853

859 861 864 865 872 873 815

Flexor pollicis brevis muscle 764

772 774

Flexor pollicis longus muscle, 724

727 750 753 766 772

Flexor retinaculum 714 715 717

723 739 740 746 750 755 761

766 769 774 781

Flexor tendon, common 710

Flexure colic left (plenic) 465

476 497

carcinoma of 492 493

resection of 492 493

right (hepatic) 472-473 492

493 498 510

carcinoma 493

duodenojejunal 445 450-451 454

596

hepatic *See* Flexure colic, right

plenic *See* Flexure colic, left

See also Angle

Floating kidney 412

Fluid cerebrospinal 23 40 44 47

53 910 911

blood in 41 42

endolymph of inner ear 116 117

perilymph of inner ear 116

subarachnoid 42

Fold alar 839 846

aryepiglottic 227 231 235 237,

239 240

axillary 280 671 691 696

bloodless of Treves 468

of buttock 789

epiglottic, 238

gastropneumatic 429 540

glossal epiglottic median 239

gluteal transverse 804

infrapatellar 839 845 846

interarytenoid 239 240

labioscrotal 639

pancreaticogastric 438

peritoneal 434

acrogenital 564

salpingopharyngeal 227 229

sublingual 148

synovial 839 840 845 846 871

triangular 229

urorectal 562

ventricular of larynx 239

vesical transverse 564 585

vestibular of larynx 240

Follicles graafian 593

Fontana paces of 79

Fontanelle(s) 9 10

anterior 9 11

anterolateral 10

posterior 9 10 22

posterolateral, 10

Foot 881 900

arch(es) 895 897

abduction 896 897

adduction 897

fascia 897

ligaments 897

venous, dorsal, 806 807

Foot (*Continued*)

- arteries 887 888
- apert medial, 881
- bones 889 892
- accessory 890 892
- sesamoids 886 891 892
- deformities surgical treatment 899
- dorsiflexion 854 855 818 897
- dorsum 881
- eversion 858 879 888 893 896 897
- extension 854 855 878
- fascia 883 885
- fat pad 883 896
- flexion 858 859 888
- plantar 878 819 897
- infections surgical treatment 898 899
- inversion 854 855 859 878 879 888 893 897
- joints 892 895
- ligaments 893 896
- margin lateral 881
- muscles 884 889
- arches 897
- insertions, 889
- origins 889
- nerves 887 889
- cutaneous 881 883
- phalanges 889 892 897 898
- skin 881
- sole (plantar surface) 881 889
- spaces 888 899
- surgery of 898 900
- for deformities 899
- for hallux valgus 899 900
- for hammer toe 900
- for infections 898 900
- tendons 884 888
- toes 891 897 898
- Foramen acetabular 795 798
- apical 151
- caecum 21 22 54 157 158 203
- 04 216 217
- emissary veins of 50
- linguae 158
- of diaphragm 290 292
- epiploic (of Winslow) 423 434
- 521 524 526
- ethmoidal 14 16 21 22
- incisive lateral 139
- infra orbital 14 16 17 121 128
- interventricular 34 42 44
- intervertebral 600 912
- jugal 12 13 21 24 54 10 197
- lacerum 12 13 21 23 51 154
- of Langer 275 276
- of Luschka 42 44
- of Magendie 41-44
- magnum 12 13 21 24 39 40
- 10 908 910
- mandibular 18 136 137 141 142
- mastoid 12 13 21 26
- mental 14 17 18 121 141

- Gland(s) (Continued)
 pretitcheal 111
 prostate *See* Prostate gland
 retroauricular 107
 salivary 13 14 15 16
 See also Submaxillary glands
 and Lacrimal gland
 sebaceous, of ear external 107
 of eyelid 4
 of face 14
 of hand of maltration 6
 of labia majora 643
 of lip 143 144
 mamomian *See* Tarsal glands
 of neck 181
 of penis 135
 serous, of t. n. ur 18
 subcervical 55
 sublingual 65 146 144, 15 160
 27
 submandibular lymph 159 160
 160
 salivary 145
 submaxillary lymph 6 7 144
 14 150
 salivary 65 19 150 143 16
 submental lymph *See* Submental
 gland lymph
 subtrigonal 55
 suprarenal 403 406 407 412
 516
 sweat of eyelid 72 74
 of face 114
 of hand 759
 tarsal 2 75
 thymus *See* Thymus gland
 thyroid *See* Thyroid gland
 tonillar of Wood 165
 urethral of Cowper 638 639
 vestibular greater 651 652 654
 655 657
 of Zeis, 72 74
 Glandular artery 196
 Glans clitoridis 650 653 658
 Glans penis 633 635 636 638 646
 corona 635 636
 Glaucoma 83
 Glenohumeral ligament 686 688
 Glenoid labrum 686 688
 Glossopalatine muscle 154 155 158
 164
 Glossopharyngeal nerve 24 37 47
 67 10 130 158 159 165 170 172
 184 186 231 232
 Glottis 238 250
 Gluteal artery 567 601 602 604
 613 792 794 800 800
 Gluteal nerve 613 614 792 794
 803 815 820
 Gluteal region 789 796
 boundaries 789
 fascia 789 790
 lymph vessels 789
 muscles 790 792
 structures, superficial 789
 Gluteus maximus muscle 554 602
 627 629 654 658 87 792 796
 800 803 805 800 821 830 832
 Gluteus medius muscle 549 554
 613 792 794 796 97 800 802
 801 800 821 825 831
 Gluteus minimus muscle 549 554
 613 792 794 796, 797 800
 84
 Coll. fasciculus gracilis, 913 914
 (omotheca of urethra) prostatic
 518
 Goose's foot plexus 66
 (racilia muscle) 555 796 800 805
 809 812 813 816 818 800 806
 831 836 840 845 847 861 864
 Graham R R 313 502
 Grant 250 385 386
 Graves Amos 515
 (ray) 531
 (reat vein of heart) 336
 Grinning muscle" *See* Risorius
 muscle
 Grodin ky 898
 Groove(s) auriculoventricular 335
 bicipital 669 683 687 658 646
 05 07 708 710 712 713
 carotid 21 23
 claviculothoracic 285
 deltopectoral 281 283 285 640
 691 716
 esophageal of liver 405
 infra orbital 14 16
 intertubular 688
 interventricular 335 347
 longitudinal, of hand 759
 in lunas 305 107 346
 musculo spiral 00 05
 mylohyoid 18
 oblique for radial nerve 709
 obturator 550
 olecranon lateral 721
 optic 21 23
 para olecranon 70
 radial of humerus 698 08
 sigmoid 21 26
 spiral of humerus 681 698 08
 709
 tracheo esophageal 209 238
 transverse 21 26
 for vena cava inferior in liver
 510
 See also Sulcus
 Gross 353
 Gubernaculum ovarii 581 583 585
 Gubernaculum testis 386 581
 Gums 147 149 151 153 155
 abscess subperiosteal 150
 arteries 138
 boil 150
 lymphatics 180
 nerves 62 140 141
 pyorrhea alveolaris 153
 Gutter paracolic 472 496
 Gynecomastia 274
 Cyrus annular, 32 33
 cun uli 33 35 36
 frontal 31 33 35
 fusiform 36
 hippocampal 35 36
 lingual 33 35 36
 occipital 33
 occipitotemporal 35 36
 orbital 35 36
 postcentral 31 32
 postparietal 32
 precentral 31 32
 rectus 35
 supramarginal 32
 temporal 32 33 35 36 50
 Hallux 891 898
 valvus 892 900
 Hamate bone 48 750 752 754 771
 hook 749 753 772
 Hammer toe surgical treatment
 900
 Hamstring muscles 800 800 871
 806 835 836
 Hamulus, pterygoid 12 19 155
 230 231
 Hand, 59 86
 abduction 32 35
 adduction 24 33
 claw " 249 69 71
 deviation radial 23
 dorsum nerves cutaneous 4
 extension 732 76
 extensor (dorsal) region infec
 tions 38
 kin 737
 urgery 738
 flexion 723 724 767
 glands sebaceous 76
 sweat 759
 head waiter's tip 749 618
 hollow 759
 nerves cutaneous of dorsal re
 gion 774 76
 of palm 70
 palmar region 759 92
 phalanges, 749 759 771 773 776
 780
 dislocation 785
 pronation 739 742
 region dorsal 759 774 776
 extensor (dorsal) 36 738
 septum fibrous 767 68
 skin 759 760
 creases 759 761 763 764 777
 778 781
 paces *See* Spaces of hand
 supination 739 742
 surgery of 780 786
 callosity suppurating 778 80
 dislocation of metacarpophal
 angeal joints 785
 felon 784
 fractures of metacarpal bones
 784 785
 of phalanges 785 786

- Freshman's nerve 859
 Frontal artery 5
 Frontal bone 10 11 14 16 18 19
 78 90 92 101 104 126 134
 abscess 102
 orbital plates 42
 fracture of 23
 Frontal gyrus 31 33
 Frontal nerve 5 63
 Frontal process of superior maxilla
 75 92
 Frontal region 6 7 121 126
 Frontal sinus 14 16 20 37 63 75
 91 97 99 101 102 105
 fracture over 102
 surgery 102 103
 Frontal vein 5 7
 Frontalis muscle 66 124 126
 Frontonasal process 119 120
 Fundus of bladder urinary 564
 568
 oculi 75
 of stomach 425 427
 of uterus 585 586 591 660 662
 Funicular process 387 390
 Funiculi of spinal cord *See* Col
 umns of spinal cord
 Furcolo 410
 Furuncles on lips 143
 on neck 181
 Furunculosis 90
 Fusiform gyrus 36
- Gage 247
 Galea aponeurotica 3
 Galen 547
 vein of 37 53
 Gallbladder 431 449 450 474 505
 509 518 528 536
 body 518 520
 carcinoma of 396
 embryology 518
 fundus 518 519
 lymphatics 525
 neck 518 520
 surgery of 525 528
 cholecystectomy 525 527
 cholecysto enterostomy 528
 cholecystogastrostomy 528
 cholecystostomy 525
 choledochostomy 527 528
 Gallstones 414 527
 Ganglion (ganglia) Arnold's 63
 carotid 185 187
 celiac 433
 cervical 68 119 185 189 211
 253 359
 ciliary 61 64 87 89
 gasserian 57 62 63 140
 injection with alcohol and
 procaine 123 125
 geniculate 115
 inferior 186 187
 Langley's 62 65
 Meckel's, 64
 Ganglion (ganglia) (*Continued*)
 mesenteric superior 495
 middle 185 187
 otic 62 64 110 140 157
 semilunar 61 63 158
 sphenopalatine 16 62 64 92 95
 137 157
 spinal 908 912 914
 spiral of inner ear 116
 stellate 186 189 190
 submaxillary 62 64 65 147
 superior 185 187
 sympathetic 211
 cervical 324 420 426
 of spinal nerve 269
 thoracic 189 360 420, 434
 thyroid 185 187
 trigeminal 24 62 65 137
 of vagus 420
 vertebral 186 187
 Ganglionectomy, stellate, 189 190
 Garlock 325 441
 Gartner duct of 581 582
 Gasserian ganglion 57 62 63 140
 injection with alcohol and pro
 caine 123 125
 Gaster *See* Stomach
 Gastrectomy 438 440 543
 Gastric artery 290 322 323 325
 332 335 336 341 343 345 347
 420 421 424 427 429 432 434
 438 439 452 510 523 536 540
 541
 Gastric ligaments 434
 Gastric lymph glands 431 432
 Gastric nerves 433 441
 See also Vagus nerve
 Gastric veins 420 421 429 430
 431 489 490
 Gastrocnemius muscle 820 825 831
 835 836 840 841 845 847 853
 857 858 860 861 864 876
 Gastrocolic ligament 429 444 543
 Gastrocolic omentum 325
 Gastroduodenal artery 428 429
 432 439 449 452 510 519 521
 523 536 538 539 541
 Gastro enterostomy anterior 438
 Gastro epiploic artery 325 424
 427 429 432 438 439 451 453
 519 523 530 531 536 541
 Gastro epiploic vein 325 427 430
 432 487 489 530 531
 Gastrohepatic ligament 70 325
 Gastro intestinal tract 413 503
 embryology 413 417
 fetal circulation 415 417
 rotation and fixation 413 417
 Gastrojejunal ulcers 329
 Gastrojejunostomy 436 438 538
 539 543
 Gastrolinal ligament 325
 Gastrophrenic ligament 429
 Gastrosplenic ligament 424 427
 429 432 529 532
- Gaucher's disease 531
 Gemelli muscles 554 555 792 794
 797 800 803 821 824 831
 Genicular artery 872 836 838
 Geniculate anastomotic magna, su
 perior 822
 Genioglossus muscle 146 152 157
 162 164 204 218 229
 Geniohyoid muscle 134 142 157
 157 159 161 164 185 216 218
 229
 Genitalia external anesthesia of
 553
 female 649 655
 clitoris *See* Clitoris
 hymen 650 652
 labia *See* Labia
 male 635 646
 penis *See* Penis
 scrotum *See* Scrotum
 spermatic cord *See* Sper
 matic cord
 testis *See* Testis
 surgery of 645 646
 circumcision 646
 hydrocelelectomy 645 646
 varicocelelectomy 645
 Genitocrural nerve 594 596
 Genitofemoral nerve 473 594 596
 611 616 618 644 804 806
 Genu 33 34
 Gerota's space of 403 405
 Gibson 353
 Gilchrist 494
 Gimbernat ligament of *See* Lacu
 nar ligament
 Gingivae *See* Gums
 Gingival nerves 62
 Gitlow 353
 Glabella 14
 Gland(s) adrenal 540 596
 areolar of Montgomery 276 277
 of Bartholin *See* Vestibular
 glands greater
 bulbo urethral *See* Glands of
 Cowper
 ceruminous of ear external 107
 cervical deep 95
 of Cloquet 807
 of Cowper (bulbo urethral) *See*
 Cowper glands of
 lacrimal *See* Lacrimal gland
 lingual 146 206
 of lips mucous 144 145
 mammary *See* Mammary gland
 mastoid 107
 of Moll 72 74
 of nose mucous membrane 94
 of palate hard 153 155
 parathyroid 110 210 218 220
 parotid *See* Parotid gland
 pineal *See* Pineal body
 pituitary *See* Hypophysis
 preauricular 107
 prelingual 211

- [illegible]

Hand (*Continued*)

- surgery of (*Continued*)
 - infection of bursa radial 780 781
 - ulnar 779 781
 - of space midpalmar 783 784
 - thenar 780 782
 - paronychia 784 785
 - tenosynovitis 780 781
 - web space infections 778 780
 - whitlow 784
 - tendons dorsum 775
 - tissue subcutaneous 759 760 762
- Harclip 119 146
 - surgery for 145 146
- Harrington 293 353
- Harris H A 262
- Hartmann pouch of 518 520 525 526
- Head 1 166
 - Head waiter's tip hand 249 678
- Heart 322 333 335 353 431 443
 - apex 322 348
 - arteries 343 347
 - compartments 339 343
 - auricle left *See* Atrium of heart
 - right *See* Atrium of heart
 - right
 - exposure of 352
 - and great vessels thoracic projection 346 350
 - infundibulum 335 340 341 343 344
 - lesions 332 333
 - nerves 347
 - pericardectomy 353
 - proper 335 347
 - surgery of aorta 353
 - incision Duval Barasty 349 352
 - Spangaro's 350 352
 - mediastinotomy superior exploratory 353
 - patent ductus arteriosus 351 353
 - pericardectomy 353
 - valve aortic 343 348 352
 - bicuspid 341 343 344
 - mitral 341 343 348 352
 - pulmonary 348 352
 - semilunar 340 344
 - sounds of areas of maximum audibility 348 350 352
 - tricuspid 344 348 352
 - veins 343 347
 - ventricle right 331 335 340 343 349 415 417
 - left 331 335 341 343 350
 - wounds 352 353
 - hemorrhage 352 353
 - tamponade 352
- Heister spiral valve of 518 520
- Helix 58 105
- Helweg's bundle 913

Hematemesis 431

- Hemianopsia homonymous 34 60
- Hemiazzygos vein 292 323 324 347 354 357 406 419 421 488
- Hemicolotomy right 496 497 498
- Hemiplegia 201
- Hemorrhage from artery carotid 174
 - femoral 611
- cerebral 42 50
 - exsanguinating of esophagus 490
 - with heart wounds 352
 - as indication for ligation of common carotid artery 201
- intracranial 28 29 41 42
- from meatus auditory external 107
 - from middle ear infection 110
- in phrenic avulsion operation, 271
- from phrenicopneural vessels lesions of 189
- in prostatectomy 519
- subconjunctival 23
- in tonillectomy 166
- from ulcer duodenal 453
- in visceral vascular fascial space 162
- Hemorrhoidal artery inferior 479 482 484 487 501 602 629 654 657
 - middle 479 481 484 487 499 567 568 573 577 590 597 601 603 604
 - superior 474 477 482 484 486 497 500 618
- Hemorrhoidal nerve inferior 482 495 497 614 629 655 658
- Hemorrhoidal plexus 487
- Hemorrhoidal vein 481 482 485 488 490 499 501 509 606 608 618 621 654
- Hemorrhoids 453 487 490 491
 - esophageal 490
 - external 482 491
 - internal 482 490 491
- Hemorrhoidectomy 491
- Hepar *See* Liver
- Hepatic artery 424 427 429 434 449 452 504 505 507 508 510 511 516 517 519 521 524 538 541
- Hepatic duct 431 507 508 518 523 526 527 536
- Hepatic lymph glands 431 453
- Hepatic plexus 70
- Hepatic vein 430 488 490 504 506 511 524 536
- Hepatoduodenal ligament 424
- Hepatogastric ligament 424
- Hernia(s) of bladder urinary
 - diaphragmatic 291 293 298
 - femoral 475 602
 - surgical anatomy and repair 812 814 815
 - of fossa intersigmoid 462

Hernia(s) (*Continued*)

- into fossa ischiorectal 559 659
- me entericoparietal 454
- paraduodenal 454
- retrosigmoid 462
- incisional of abdominal wall anterior 316 379
- inguinal 475 641 643
 - of abdominal walls surgery of, 391 394
 - direct 394
 - indirect surgery of 391 393
 - types 389 391
- intraperitoneal intersigmoid 474
- sliding 502 503
- strangulated into intersigmoid recess 477
- umbilical 364 475
 - of adults 396
 - congenital of children 396 397
 - normal 462
 - surgery for 397
 - types 396 397
 - ventral 475
- Hernioplasty diaphragmatic 291 293
- Hesselbach ligament of *See* Ligament interfoveolar
- triangle of 385
- Heuer osteoplastic flap of 58
- Hiatus adductor 816 819 822 832
 - esophageal 221 325 441
 - sacral 551 553 907 916
 - of Schwalbe 559 560 659
 - for superficial petrosal nerve 21 23 24
- tendineus *See* Hiatus adductor
- Highmore antrum of *See* Maxillary sinus
- Hilton white line of 480 482
- Hilus of kidney 405
 - of lung 307
 - of ovary 605
 - of thorax 257
- Hindgut 540 562
- Hip 789 803
 - bone 547 550
 - joint 797 801
 - arteries 800
 - capsule 794 831
 - dislocations 800 801
 - ligaments 795 798 799
 - movements abduction 800 822
 - adduction 800
 - extension 800 826
 - flexion 800 819 822
 - rotation 800 822 826
 - nerves 800
 - relations 800 801
 - surgery of 801 803
 - approaches anterior 801 802
 - iliofemoral anterior 802
 - lateral 807 803
 - posterior 802 803
- Hollow of hand 759

- Ilium (*Continued*)
 spine of 364 372 381 478 547
 550 552 554 555 789 801
 803 819 823 827 916
 surfaces 548 549
 tuberosity 548 549 554
- Impression colic on liver 505
 duodenal on liver 505
 esophageal on liver 505
 gastric of liver 505 509
 renal on liver 505 510
 suprarenal on liver 505
 trigeminal 21 24
- Incision *See individual names*
- Incisors 149 151
- Incisura 108
 angularis *See* Notch angular
 cardiaca *See* Notch cardiac
 intertragica 105
 semilunaris *See* Notch trochlear
- Incisure of larynx interarytenoid 227
- Incus 106 108 111 115 170
 lentiform nodule 111
 ligaments 110 111
 processes of 110
- Infarct pulmonary 313
- Infection *See under individual names*
- Infrahyoid artery 196 206
 Infrahyoid muscle 191 199 250
 Infrahyoid region 169
 Inframandibular nerve 132
 Infra orbital artery 99 138
 Infra orbital nerve 16 62 64 75
 99 121 146 149 151
 Infra orbital vein 99
 Infraspinus muscle 249 676 678
 681 683 692 694 701 702 708
 710
- Infratemporal and temporal regions 134 141
- Infratrochlear nerve 63 64 121
- Infra umbilical lymph vessels 368 369
- Infundibulopelvic ligament 582 585
 591 593 603 605 621 623 653
 654
- Infundibulum 36 40 55 57 58 102
 518 520
 ethmoidale cavi nasi 91 93
 of heart 335 340 341 343 344
 of nose 100
 of uterine tube 591 592
- Inguinal ligament 363 365 367
 370 380 383 385 389 390 392
 394 401 548 550 554 555 599
 609 610 629 630 804 808 810
 813 815
- Inguinal lymph glands 366 369
 482 494 495 591 608 609
- Inguinal region of abdominal walls
 anterior 3 9 391
 layers 378 386
 nerves 384 385
- Inguinofemoral region 808 811
- Inion *See* Protuberance occipital external
- Innominate artery, 187, 250 251
 265 309 319, 320 322 331 336
 344 346 353
- Innominate bone 547 548 789
- Innominate vein 48 197 207 208
 221 250 252 265 266 270 271
 304 305 309 318 320 322 326
 337 344 346 348 350 355, 357
 420 421 488 672
- Insula *See* Brain lobes central
- Interarticular ligament, of ribs 260
- Interarytenoid muscle 238
- Intercarpal joints 753 755
 articulation 754
 infection of 766
 nerves 755
- Intercavernous sinus 53 58
- Interclavicular ligament 264 266
- Intercolic membranes 474 476
- Intercostal arteries 251 266 269
 271 290 299 347 353 367 404
 420 422 610 679 690
- Intercostal membranes 266 269
 271 272
- Intercostal muscles 266 269 271
 272 280 437 441
- Intercostal nerve 266 269 272 273
 281 292 299 367 369 370 373
 379 400 682
- Intercostal vein 266 271 306 354
 355 357 406 490
- Intercostobrachial nerve 272 669
 670 698
- Intercostohumeral nerve 280 281
- Intermediate nerve 67
- Intermediate tendon 191 193
- Intermesenteric nerves 495 497
- Intermetacarpal joint 755
- Internal ear 115 118
 ampulla 116 118
 canalis reuniens 116 117
 canals semicircular 106 115 117
 cochlea 115 118
 aqueduct of 115
 common crus 117
 duct cochlear 106 116 117
 semicircular 116 118
 ductus endolymphaticus 116 117
 ductus utriculosaccularis 116 117
 endolymph 116 117
 fenestra cochlear 117
 vestibuli 106 116 117
 ganglion spiral 116
 labyrinth bony 115 116
 membranous 116
 lamina spiral 116 118
 membrane vestibular 116
 modiolus 115 116 118
 nerves 67
 organ of Corti 116 118
 perilymph 116
 pyogenic involvement 118
- Internal ear (*Continued*)
 recessus ellipticus 117
 recessus phaeicus 117
 sacculle 116 118
 saccus endolymphaticus 116 117
 scala tympani 106 115 117
 scala vestibuli 106 115 117
 utricle 116 118
 vestibule 116
- Interosseal muscles of foot 853 882
 884 886 887 889
 of hand 59 760 768 773 775,
 776 778 786
- Interosseous artery 715 717
 724 726 728 730 733 735 733
 ligament of 747
- Interosseous ligament of knee 850
 of wrist 755
- Interosseous membrane of leg 853,
 856 857 859 863
 of forearm 715 724 739 741,
 745 747
- Interosseous nerve 726
 anterior 728 729 733 755
 dorsal 724 734 742 743
 posterior 701 715 718 732 735,
 753 755 776
- Interphalangeal joints of foot 886
 891 895 898 900
 of hand 756 781
 ligaments 756
- Intersigmoid fossa 462
- Interpinous ligaments 907 908
- Intertransversalis muscle 185
- Interventricular artery of descending 347
- Intervertebral vein 406
- Intestine large *See* Large intestine
 small *See* Small intestine
- Intrapubic ligament 636
- Intussusception 467 472
- Inversion of foot 854 855 859
 878 879 888 893 897
 of toe great 859
- Iris 64
- Irtis 80
- Ischiatic nerve 832
- Ischioapsular ligament 800
- Ischiocavernosus muscle 554 555
 575 579 589 627 629 631 635
 639 651 653 655 658
- Ischiofemoral ligament 795 798
 799
- Ischium 548 550 79 798
 body 549
 muscles 554 555
 ramus 549 550 627
 spine 548 550 557 558 572 789
 793 794
 muscles of 555
 surfaces 549
 tuberosity 549 552 554 630
 650 652 658 794 95 821 826
- Island of Reil *See* Brain lobes, central

- J**
- Jabiric artery** 16
Jacobson's (circulate) system 31 36
 See also 413 418
 Fauces 313 315
 of pharynx 156
 of parotid gland 1 1 0 134
 of pharynx 8
 of thyroid gland 69 69 11
 of uterine tube 502
 of uterus 141
- Jacken** 311
 See **metatarsal** 1 46 468
- Jaegerian equis** 3 13
- Jaeger** 168
 See **pharynx** 313
- Jaw slakers** 142
 locking 142
 margin, alveolar 149
- Jejunal artery** 454 459 542
- Jejunum ileum** 444 454 460
 arteries 459
 localization of 456
 lunettes 45
 lymphatic 459
 See also **Ileum** and **Jejunum**
- Jejunotomy** 462
- Jejunum** 41 415 440 444 445
 451 454 458 45 458
 See also **Jejunum ileum**
- Jelly Whist** 16
- Jennings** 374
- Joint(s)** actinomycetous 265
 611 612
 ball and socket 64 (40 8)
 calcaneocuboid 893
 carpal transverse 54 55
 carpometacarpal articulation 754
 ligaments dorsal 756
 of Chopart 881
 cubometatarsal 893 894
 cuneonavicular 893 894
 elbow. *See* **Elbow joint**
 enarthrodial 687
 of foot 892 895
 glenohumeral 714
 hip 14
 hip. *See* **Hip joint**
 humero-radial 714
 humero-ulnar 714
 intercarpal 753
 articulation 754
 infection of 766
 nerves 754
 interphalangeal of foot 886 891
 of hind 771 81
 ligaments 756
 knee. *See* **Knee joint**
 of Li Franc 881
 mandibular. *See* **Temporomandibular joint**
 manubriosternal level of 322 324
- Joint(s) (Continued)**
 metacarpal 771
 metacarpophalangeal dislocation 85
 hamate 755 756
 metatarsophalangeal 856 887
 of 894 895 899 900
 multicarpal. *See* **Carpal transverse**
 multitarsal cuboid 881
 pulim 54
 radiocarpal. *See* **Radiocarpal joint**
 radiohumeral 739
 radio-ulnar. *See* **Radio-ulnar joint**
 acet iliac 543 551
 sternoclavicular 1 1 250 64
 66 65 544 550
 sternocostal 67
 sternomanubrial 64
 sul astragaloid 89
 talocalcaneal 882 883 895
 talocalcaneonavicular 891 893 894
 tarsometatarsal 881 893 894
 temporomaxillary. *See* **Temporomandibular joint**
 tibiofibular 846 848 850
 transverse tarsal 893
 of wrist 553 756
 carpometacarpal 754 755
 intercarpal 754 755
 intermetacarpal 755
 interphalangeal 56
 metacarpophalangeal 755 756
 pisiform 754
 radiocarpal 753 754
 transverse 754 755
 xiphosternal 294 97
- Jones** 353
- Jones and Naffziger surgery of orbit** 78
- Jugular lymph nodes** 183
- Jugular vein** 6 134 174 231 357
 anterior 48 168 183 193 197
 199 213 243 245
 external 5 48 51 107 127 130
 131 154 178 183 188 193
 197 199 243 246 252 304
 internal 13 24 26 48 51 95 110
 112 113 120 129 131 134
 139 186 190 193 197 200
 202 203 205 212 214 216
 244 248 250 252 265 304
 319 346 348 357 358 422
 672
 ligation of 201 203
 thrombosis septic 162
 oblique 245
 posterior 183 197 198 245
- Jugulo-digastric lymph gland** 159 165
- Jugulo-omohyoid lymph gland** 159 160
- Junction costochondral** 293 315
- duodenopyloric** 426
- ileocolic** 468
- See also** **In le**
- Kanavel** 68
- Kenton** 353
- Kidney(s)** 387 400, 402 412, 447 449 464 473 530, 536, 540 598
- abscess** 473
- anale** 407
- areas of** 409
- capsules** 405
- fascial relations lumbo-dorsal** 403 404
- renal** 404 405
- lat planes** 403 405
- "floating"** 412
- hilum** 405
- "horseshoe"** 408
- lymph vessels** 407
- mucosal** 472
- muscles** 407
- nerves** 407
- poles** 406 407
- sinus** 405
- surface anterior relations of** 40, 407
- surgery of** 407-412
- approaches** 409 411
- nephrectomy** 410-412
- nephropexy** 412
- veins** 406 407
- Kienboch's disease** 756
- Kumpke paralysis of lower arm** 249 6 8 6 9
- Knee** 835 851
- housemaid's** 847
- joint** 838 848
 anastomosis 838
 articulation 838 839
 capsule 835 836 840 841 850
 cartilage 842 844
 femur. *See* **Femur**
 intertrochanteric 845 846
 ligaments 841 845
 membrane synovial 834
 movements extension 819 822
 824 842 844 848
 flexion 822 826 842 844,
 848 858 859
 rotation 822 844 848
 patella. *See* **Patella**
 tibia. *See* **Tibia**
 nerves 835 837 848
 region popliteal 835 838
 surgery of 850 851
 amputation supracondylar 849 851
 exposure of joint 850 851
 tibiofibular joints 848 850
- Kocher** 691 803
- method of treatment of dislocations of shoulder joint** 694
- subcostal incision of** 370 372, 375
- Kronlein's operation** 76 77

- Labia majora 582 584 586 589
 609 639 649 651
 commisure anterior 649 650
 nerves 193 804
 sebaceous glands, 649
 Labia minora 586 588 589 609
 649 652
 Labial artery 120 144 602 654
 Labial nerve 63 64 121 655, 658
 Labial vein 654
 Labrum acetabulare 827
 Lacertus fibrosus 05 717 720 723
 Lacinate ligament 869 872
 Lacrimal apparatus 73 76
 Lacrimal artery 16 17 23 76
 Lacrimal bone 14 16 75, 92
 Lacrimal duct 72 75
 surgery 76
 Lacrimal gland 16 62 63 73 75
 84 86
 surgery of 75 76
 Lacrimal nerve 63 121
 Lacrimal sac 72 75 83 138 139
 surgery of 76
 Lactiferous ducts 277
 Lactiferous sinuses 277
 Lacunae laterales 54
 Lacunae of Luschka 562 563
 Lacunae urethrales 577 639
 Lacunar ligament 797 814
 Lacus lacrimalis 72
 Lambda 11 22
 Lamina cribrosa 77 78
 interosseous dorsal 737
 intertendinous 737
 papyracea of ethmoid bone 16,
 105
 prethyroid 174
 pretracheal 174
 profunda 852 856
 pterygoid lateral 136
 spiral of inner ear 116 118
 terminalis 34 36
 Lane 477
 ileal membrane of 467
 Langer 316
 foramen of 275 276
 Langley's ganglia 62 65
 Laparotomy 503
 Large intestine 462 503
 anal canal *See* Anal canal
 appendices epiploicae 465 467
 arteries 481 483 487
 cecum *See* Cecum
 colon ascending *See* Colon as-
 cending
 descending *See* Colon de-
 scending
 pelvic *See* Colon pelvic
 transverse *See* Colon trans-
 verse
 embryology 462 464
 hernia umbilical normal',
 462
 flexure colic *See* Flexure colic
- Large intestine (*Continued*)
 lymphatics 482
 membrane mucous 465
 proper 463 465
 rectum *See* Rectum
 size 465
 surgery of 495 503
 cecostomy 495
 colostomy 495 496
 Devine 495 496
 loop 496
 hemicolectomy right 496 497
 498
 Mikulicz procedure 496 497
 499
 resection of colon 492 493
 496 497
 abdominoperineal (Miles)
 497 499 502
 veins 481 485 487 490
 See also Colon
 Laryngeal arteries 196 206 208
 232 236 238
 Laryngeal framework 170
 Laryngeal muscles external 173
 Laryngeal nerve external 69 205
 206 208 209 230 231 238
 fold of, 227
 internal 69 208 209 230 232
 236 238 319
 inferior *See* Laryngeal nerve re-
 current
 recurrent 10 177 184 205 210
 214 216 218 230 232 236 238
 315 318 319 322 323 338
 343 419 420 422 423
 superior 170 184 203 206 208
 209 211 212 215 238
 Laryngeal prominence 172 173 235
 Laryngeal vein 236 238
 Laryngopharynx 227 229 231
 Laryngoscopic examination 239
 240
 Laryngotomy 240 241
 Larynx 156 170 192 206 232 243
 aperture 236 239
 arteries 238
 articular facet 233
 cartilages 233 235
 cavity 238 239
 compartment infraglottic 240
 fold aryepiglottic 237
 epiglottic 238
 glossio epiglottic 234
 pharyngo epiglottic 234
 ventricular 233 235 239
 vocal 233 235
 foreign bodies removal of 240
 242
 horns 235
 inlet 239
 line oblique 233 235
 lymphatics 238
 membranes mucous 209 210
 233 238 240
- Larynx (*Continued*)
 muscles 170 235 236 238
 nerves 238
 process muscular 233
 vocal 233
 tubercle superior 235
 tuberculosi 240
 tumors 240
 ventricle 239
 vestibule 239 240
 vocal cords false, 236
 true 236
 Lateral artery 811
 Lateral ligament of elbow 710
 of knee 840 842 848
 of wrist *See* Collateral ligament
 radial
 Lateral process 119 120
 Lateral sinus *See* Transverse sinus
 Latissimus dorsi muscle 249 283,
 285 397 398, 400 403, 409 411
 554 669 671 672 674 678 680
 689 690 700 701 708 710 712
 Leg 852 868
 arteries 855 856 860 861
 compartments 852 856
 fascia deep 852 854 856
 muscles 854 861
 anterior (extensor) 854 857
 lateral (peroneal), 856 858
 posterior 858 861
 nerves 852, 854 856 859 860
 surgery of 865 868
 amputation 866 868
 approaches to tibia and fibula
 865 866
 fractures of shaft of tibia and
 fibula 868
 Lemniscus medial 914
 spinal 913 914
 Lenticular process 115
 Lenticulostrat artery 50
 Lesions *See* Individual names
 Levator anguli oris (caninus)
 muscle 120 126 128
 Levator ani muscles 478 479 483
 485, 501 502 509 554 560 564
 565 572 574 575 578 579 589
 590 608 613 614 653 654 657
 659 661 664
 Levator costarum muscle 272
 Levator glandulae thyroideae muscle
 205 06
 Levator labii superioris alaeque nasi
 muscle 126 128
 Levator labii superioris muscle 120
 121 126 128 138
 Levator palati muscle 154 156 230
 Levator palpebrae superioris muscle
 61 72 74 84 86 89
 Levator scapulae muscle 185 187
 243 244 246 679 681
 Levator veli palatini muscle 155
 Lewin 786
 Lewis Ivor 325, 326

Ligament(s) (Continued)

- ovarian 581 583 587 591 593 603 619 621 623
- palmar of interphalangeal joint 756
- of metacarpophalangeal joint 755 756 762 773
- transverse superficial, 762
- palpebral median 75 121 126 127
- patellar 825 840 841 845 847 850 853
- pectineal 548
- pelvic transverse 630 639 656
- of penis suspensory 635 636
- perineal 611 656 658
- pharyngeal 476 530 532
- plantar 882 884 888 893 895 897
- popliteal 832 840 843
- posterior of ankle joint 871
- of elbow joint 710 714
- Poupart's See Inguinal ligament
- pre capular 245
- pterygomandibular 12 230 231
- pubic 369 553 631 636 656
- pubocapsular 800
- pubofemoral 553 795 798 799
- puboprostatic 555 559 564 567 574 632
- pubovesical 564 567 578 604
- pulmonary 294 295 303 306 313 329 441
- radiocarpal 757
- rectal lateral 603
- of rectum suspensory 479
- retinacular 835 836
- round of liver 364 395 396 415 417 504 505 507 508 513 602
- of uterus 581 587 590 609 619 624 629 661 663
- sacroccygeal 553 557 559 916
- sacro iliac 478 552 554
- sacrospinous 548 550 552 553 555 633 789 94
- sacrospinous 478 548 550 552 555 557 627 629 658 789 791 876
- scrotal 386
- semilunar 830
- of shoulder joint 686 688 710
- phenomandibular 142
- pleno aortic 529
- splenorenal See Ligament lienorenal
- stapes 110 111
- of sternoclavicular joint 264 266
- sternopericardial 330
- stylohyoid 13 170 225 230 231
- stylomandibular 13 130 141 142 226
- suprascapular 197 679
- suprapineous 907

Ligament(s) (Continued)

- suspensory of axilla 669 670 672
- of eyeball 79 80 81
- of Lockwood 84
- of ovary See Infundibulopelvic ligament
- of symphysis pubis 530
- talocalcaneal 875 878 882 892 895
- talofibular 863 875 878
- of ovary 875
- tarsal 73
- temporomandibular 142
- thyro epiglottic 234
- thyroid 233 234 236
- of thyroid gland suspensory 178
- thyrothyroid 177 178
- of tibialis muscle posterior 875
- tibiofibular 848 850 863 865 875
- transverse See Transverse ligament
- trapezoid 686
- of Treitz 437 438 440 451 457 539
- triangular of liver See Urogenital diaphragm
- umbilical 393 415 417 563 564 567 572 597 600 607 604
- utero ovarian 622 623
- uterosacral 582 584 586 594 597 619 659 663
- vaginal 717
- of vertebral column 908
- vesico uterine 594 595
- of viscera pelvic female 582 585
- vocal 211 233 236
- of Wrisberg 842 844
- of wrist 755
- of Zinn 85
- Ligamentum(a) arteriosum 336 338 343 344 415 417
- flava 907 908
- mucosum See Fold synovial in frapatellar
- nuchae 176 246
- patellae See Patellar ligament
- pectinatum lridis 18 79
- teres 793 795 796 799 802 827 831
- hepatis See Ligament round of liver
- venosum 415 417 433 507 508 510
- fissure for 434 503 508 510
- Limb phantom 360
- Limbus fossae 339 340
- Line(s) anocutaneous 480 482
- anorectal 482
- arcuate 370
- coraco umbilical 283 285
- costodiaphragmatic of pleural resection 296 297 307
- dentate of anal canal 482 491
- of Douglas 367 370

Line(s) (Continued)

- epicondylar of femur 830
- epiphyseal of femur 828 829
- of fibula 865
- of humerus 688 708 709 714
- of radius 740
- glutal 549 794
- of Hilton 480 482
- iliopectineal 547 548 558 594
- intercondylar of femur 830
- of olecranon region 720
- intersphincteric 480 482
- intertrochanteric 799
- midaxillary 508
- midasacral of femur 832
- midsternal 257 258
- milk 274 275
- mylohyoid 18 177
- nuchal 13 14 22 174 177 243
- parasternal 257 258
- paravertebral of thorax 258
- pectinate of anal canal 482 491
- pectineal 549 550 555 556 559
- puriformis 791
- popliteal (soleal) of tibia 835 843 862 863
- scapular of thorax 258
- spiral of femur 825 827 830
- supracondylar of femur 825 831
- temporal 18 19
- of thorax axillary 258
- conventional longitudinal 257 258
- mammary, 257 258
- midaxillary 258 297 299 311
- midsternal 257 258
- parasternal 257 258
- paravertebral 258
- scapular 258
- trochanteric 798 824 827 831
- vertical of tibia 862 863
- white See Linea alba
- Linea alba 264 363 364 367 369 372 375 404 558 635
- aspera 805 807 808 816 817 823 825 830 831 850
- semilunaris 364 367 370 382
- terminalis 558
- Lingual artery 146 158 160 164 172 173 186 194 196 197 227
- Lingual gland 46 206
- Lingual nerve 63 65 131 138 140 147 148 158 227
- resection of 141
- Lingual thyroids 204 206 216
- Lingual tonsils 158 164
- Lingual vein 48 146 148 158 160 198 199 703
- Lingula 18 306
- Lingulectomy in bronchiectasis 316
- Linton 515 832
- Lip(s) 143 147
- acetabular 793 795 798
- arteries 170 144 145
- carcinoma 146 147

Lap(s) (Continued)

- c nmi ure 143 144
- cyst muc u " 145
- clima 143
- clitellum 143
- facia superficial 143 144
- fi ure 113
- ferulum 159
- furuncle 143
- glands, mucous 144 145
- schacra 143 144
- glercal See Lap, acclabular
- Infections 167 163
- layers, 143 144
- Ludwigian ma 163
- lymphatics, 144 146 160
- membrane mucous, 144 146
- mac 144
- muscles, 1 6 1 8 1 9 136
- nerves, 61 64 66 6 121 1 4
- 1 6
- nevi 145
- ricularis muscle 143 144
- philtrum 119
- reaction 143 147
- setum median fascial 162 163
- skin 143 144
- ti ue submucous 144 146
- tumors, vascular 145
- veins 145
- I lfranc joint of 881
- tubercle of 241 61
- I lter dorsal radial tubercle of 0
- I liver 97 393 410 431 442 444
- 477 504 517 519 5 0 536 537
- access 474
- anatomy surface 511
- arteries, 510 511
- bare area, 489 490 505 508 510
- 513 514
- cirrho is 292 4 0 431 489
- diaphragmatic attachments 506
- embryology 504 507
- liaments 293 364 441 447 505
- 506 511 602
- triangular See Urogenital dia
- phragm
- lobes 505 508
- lymph glands 511
- nerves 511
- portal obstruction 431
- portacaval shunts 515 517
- proper 504 511
- puncture by broken rib 298
- size 504
- paces suprahepatic 512 513
- ubphrenic 511 515
- su faces, 505 508 510
- surgery of abscesses subphrenic
- drainage 514 515
- portacaval shunts 515 517
- veins 511
- viability 510 511
- Livingston 615

- Lobe(s) lungs, 2/6 107 311
- of pit late gland See Lr late
- gland lobes
- thyroid 418
- Lobectomy 315
- Lockjaw 114
- Lockwood su pen ory diam nt of 54
- Lon i sinus muscle 319 402
- Longitudinal liament 1 5 1 9
- 107 508
- Longitudinal muscle 146 158 434
- Lorius capitis muscle 148 185
- 18 135
- L n u cervicis muscle See Lon us
- colli muscle
- Lorius colli muscle 1 8 185 187
- 06 22 251 418 6/6
- Loop umbilical 414
- Louis, angle of 163 64 348
- Lufwa angina of 152 163
- angle of 263 64
- Lumbar artery 404 610
- Lumbar lymph glands, 608 609 646
- Lumbar nerves, 364 366 402 404
- 40 612 89
- Lumbar plexus, 811 911 912
- Lumbar region 363 364 397-412
- Lumbar sympathetic chain of
- nerves of plic viscera female
- 614 617
- Lumbar vein 354 404 406 490
- 610
- Lumbarization of first sacral verte
- brae 908
- Lumbo inguinal nerve 804 806
- Lumbricales muscles, of foot 887
- 884 886 898
- of hand 59 60 64 68 7 0
- 118 81 783 86
- Lumen of bladder urinary allan
- toic 562
- of rectum 4/9
- Lunate bone 148 749 754 756
- 757 66 712
- dislocation 756
- Lundy 916
- Lunettes of jejuno ileum 457
- Lung(s) 303 317 327 328 330
- 333 342 343 443
- absce s 316 317
- drainage with co tectomy 316
- intercostal 316
- two stage operation with rib
- resection 316 317
- apex 296 304 309
- arteries 313
- base 304 305
- borders 305 307
- bronchus(i) 303 303 307 313
- 316 323 325 422 423
- depression cardiac, 306 307
- embryology 303 418
- fissures 307 309
- lesions 303 316

Luna(s) (Continued)

- lobes 2/6 106 311
- azygos vein (Wusberg) 308
- 317
- Infradiaciac 312
- variations 311 312
- lymph glands 313
- mesozoy 312
- nerves 61
- nomenclature 310
- notch cardiac 311
- proper 303 313
- puncture by broken rib 298
- root 2/5 312 313
- segments 107 311
- surface 306 307 09
- surface markings 15 297
- veins, 313
- Luschka foramen of 42-44
- lacunae of 562 563
- Luxatio erecta 6/4
- Lymph glands aortic 592 593 603
- 609
- apical 159 160
- axillary 366
- of bladder urinary 569 603
- celiac 4 0 431 511
- of cervical chain deep 146 147
- 160 164
- cystic 431
- of fossa popliteal 838
- gastric 431 432
- hepatic 431 453
- hypogastric 487 495 608 609
- of ileum 457
- iliac common 591 608 609
- external 568 590 608 609 644
- internal 568 590-591 609
- inguinal 366 369 482 494 495
- 591 608 609 806 808
- jugulodistal 159 165
- jugulo omohyoid 159 160
- of liver 511
- lumbar 608 609 646
- of mediastinum 372 511
- mesenteric 459 491 494 495
- occipital 6 7
- pancreatic superior 443
- pancreaticoduodenal 453
- pancreaticohenal 431
- pancreaticoplemic 431
- paratracheal 319 4 0 427
- parotid region 131
- pectoral 369
- pelvic 482 607
- postauricular 6 7
- preaortic 431 432 453 494 495
- 608 609
- preauricular 6 7 107
- pretracheal 07 11
- pulmonary 307
- retro aortic 608 609
- retropharyngeal 179
- of Rosenmüller 607
- sacral 482, 577, 591

- Lymph glands (Continued)**
 splenic 431
 sublingual 366 607 609 635
 submaxillary *See* Submaxillary glands
 lymph
 submental *See* Submental glands, lymph
 subpyloric 431
 of thigh 806 807
 of tongue 159 160 180
 of tonsils 164
 tracheobronchial 318 319
 vestibular of vagina 589 590
See also Lymph nodes and Lymph vessels and Lymphatics
- Lymph nodes** bronchial 420 422
 cervical 6 420
 of Cloquet 607
 colic 491
 of esophagus 420 422
 ileocolic 491
 jugular 183
 mediastinal 420 422
 paracolic 491
 suprapancreatic 420
See also Lymph glands and Lymph vessels and Lymphatics
- Lymph vessels of abdominal walls**
 anterior 366 368 369
 of bladder urinary 568 608
 infra umbilical 368 369
 of kidneys 497
 of ovary 593
 of penis 636
 of prostate gland 577
 supra umbilical 368 369
 of thyroid gland 207 211 216
 of uterine tubes 592 609
 of uterus 609
 of vagina 590 608
 of vulva 608
See also Lymph glands and Lymph nodes and Lymphatics
- Lymphadenitis** 7
 me enteric 459
- Lymphadenopathy** inguinal 482
- Lymphangitis** 806
- Lymphatics (Continued)**
 of anus 609
 of breast 279 281
 of cheeks 149
 of chin 180
 of clitoris 607
 of colon 491 493 495
 of duodenum 453
 of ear external 107 131
 of esophagus 40 422
 of eyelids, 73 131
 of face 6 7
 of gallbladder 525
 of gums 180
 of jejunum ileum 459
 of large intestine 482
 of larynx 238
 of lips 144 146 180
- Lymphatics (Continued)**
 of lungs 313
 of mouth 180
 of nasopharynx 131
 of pancreas 537
 of pelvis female 607 609
 of rectum 494 495 609
 of scapula 6 7 131
 of seminal vesicles 573
 of spermatic cord 644
 of stomach 431 432
 of teeth 151
 of testis 644
 of thoracic duct 356 357
 of thymus gland 220
 of thyroid gland 207 211 216
 of viscera pelvic female 607 608 610
 of vulva 608
See also Lymph glands and Lymph nodes and Lymph vessels
- MacAusland incision** 721
- McBurney incision** 370 372 375 471 495
 point of 469
- Macewen's triangle** *See* Triangle suprarenal
- McCormack** 130
- McGregor** 892
- Mackenrodt ligament of** 560 561 587 585 588 594 595, 659 661
- McNealy** 184
- Macrostoma** 119
- Macular artery** 81
- McVay** 383
- McWhorter** 130 132
- Magendie foramen of** 41 44
- Magnum foramen** 12 13 21 24 39 40 70
- Main en griffe** 771
- Malar bone resection** 161
- Malleolar artery** 874
- Malleolus lateral of fibula** 869 872 876 878
 medial of tibia 863 865 869 871 875 876 878
- Malleus** 106 108 111 115 110
 ligaments 110 111
 manubrium of 110 111
- Mammary artery** internal 187 220 250 251 267 271 277 281 332 353 610 679 689
- Mammary gland** 274 286
 acini 275
 corpus mammae 277
 ducts 275 277
 embryology 274 275
 lobes 275
 lobules 275
 proper 274 281
 sinuses lactiferous, 277
 stroma 277
See also Breast
- Mammary line** 257 258
- Mammary vein** internal 220 252, 268 270 271, 368
- Mandible** 10 17 18 134 136, 141 143 180 181 224
 abscess 152
 angle of 18
 base of 17
 body of space of 160
 space of, surgery 160
 coronoid process 0
 molars of, different from those of maxilla 151
 neck of 137
 ramus of 129 134 137 161 163
 veins 152 153
- Mandibular joint** *See* Temporomandibular joint
- Mandibular nerve** 12 20 23 62 65 67 110 120 121 124 134 140 151 163 169 170
 injection with alcohol and procaine 122 125
- Mandibular process** 119 120
- Manubrio sterni joint level of** 322 324
- Manubrium of malleus** 110 111
 sterna 174 177 191 192 207 221 257 259 262 265 295 318 321 347 348
- Margin acetabular** 549
 costal 325 363 375 515
 falciform 808
 subcostal 262
- Marginal artery of Drummond** 486 542
- Marginal vein** medial 878
- Marshall** 441
- Mastoid muscle** 5 18 20 64 65 119 122 127 137 142 143 148 149 157 162
- Mastoid artery** 137 138
- Mastoid nerve** 140
- Mastication muscles of** 134 136 170
- Mastoid acellular** 112
 air cells 54 110 117 113 140
 disease 50
 glands 107
 process 12 18 20 22 107 112 132 135 174 177 187 243 246
 temporal bone 22
 vein 26
- Mastoidectomy** 112 114
- Mastoiditis** 110
 surgery 112 114
- Maunsell mesenteric stitch** 461
- Maxilla** 14 17 19 92 127 137 138
 alveolar border 14 17
 alveolar border of different from those of mandible 151
 nasal crest 90 92
 palatine process 17 153
 superior 75 98 104

- Maxilla (Continued)
 tubercle of 136
 vena, 152 154
 Maxillary artery 142 15 196
 external 5 119 135 137 164
 1 0 1 2 177 6 See also
 Facial artery
 Internal 0 95 3 0 130 136
 137 153 164 176
 Maxillary nerve 16 1 35 6 64
 96 1 0 121 1 114 137 154
 151 16
 Injects n with alcohol and pro-
 caïne 1 15
 Maxillary process, 119 1 0 1 0
 Maxillary sinus, 16 17 0 62 15
 1 9 9 10 138 152
 abscess, 15
 alveolar margin 97
 antrum 100-101
 discus of 77 101 105
 empyema drainage 97 101
 irritation 101
 surgery 100 101
 wall orbital 15
 Maxillary vein 136 137 142
 Mayo 3, 6
 vein of 4 7 430 431
 Meatus auditory external 12 18-
 0 46 49 105 107 121 129
 137 140
 internal, 21 24
 nasal 1 8 7 9
 urinary external, female 651
 internal male 5 5
 Meckel cartilage of 1 0
 cave of 62
 diverticulum of 395 459 461
 ganglion of 64
 Medial ligament of elbow joint 710
 of knee 839 840 842 844 865
 of wrist See Collateral ligament
 ulnar
 Medial process 119 1 0
 Median artery 751
 Median nerve 6 3 6 6 677 688
 676 699 04 08 712 713 715
 717 7 0 724 726 728 730 150
 753 756 759 61 163 64 167
 communicating branch 764
 deep branch 64
 digital branches, 763 774 183
 lateral division 164
 lumbrical branch 164
 motor branch 781
 palmar cutaneous branch 759
 161
 recurrent branch 63 764 773
 774
 Median vein 716 718
 basilic 716
 cephalic 716
 Mediastinal arteries 347
 Mediastinal lymph nodes 420 422
 Mediastinal veins, 354 355
 Mediastinitis 323
 Mediastinotomy 353
 Mediastinum (interpleural space)
 162 2 2 238 14 435, 3 1
 3 9 351 419 4 0 431
 abscess drainage of 323 3 6
 anterior 321 3 2
 boundaries 321
 lymph glands 3 2 353
 middle 3 1 3 3 330
 posterior 321 323 324 441
 superior 314 321 32 374
 testis 641
 Medulla oblongata 13 24 33 36
 39 4 110 113 115
 spinalis 40
 Metacolon lumbar sympathectomy
 for 618
 Melanocarcinoma 7
 Membranaceae muscle See Sphincter
 urethrae muscle
 Membrane(s) anal 462
 aponeurotic 3-4
 arachnoid See Arachnoid
 cloacal 462
 costocoracoid 261 669 6 0 6, 2
 6 9 16
 cricothyroid 142 144 234 236
 240 41
 cricovocal 233
 Descemet's 18 19
 diaphragma sellae 37 39 40
 dura mater See Dura mater
 of eye 3 9
 falx cerebelli 37 39 40, 57
 falx cerebri 30 37 39 40 54
 hyaloid 82
 ileal of Jackson 461-468
 of Lane 467
 interclitic 414 4 6
 intercostal 266 69 271 242
 interosseous, of leg 856 857 859
 863
 of forearm 715 724 739 141
 745 747
 lamina cribrosa 77 18
 of larynx 235 236
 mesocolicojejunal 475-4 6
 mesosigmoid 477
 mucous See Individual organs
 and parts
 obturator 548 550 556 589 799
 816
 perineal 555 628 634 637 652
 656
 periodontal 151
 pia mater See Pia mater
 root of teeth 150
 Shrapnell's 108
 yonovial 142
 tentorium cerebelli 30 36 40 54
 thyrohyoid 172 173 207 209
 233 235
 thyroid 238 240 319
 tympanic See Tympanic mem-
 brane
 vestibular of inner ear 116
 Meningeal artery 41 52 63 15
 accessory 12 23 137 138
 middle 16 19 23 28-29 40 51
 52 125 135 138 140 144
 small See Meningeal artery ac-
 cessory
 Meningeal vein 41 52
 Meningeal 73 39 42
 arteria 146
 parietal 101 910
 Meningitis 73 57 92 102 105 107
 110 114 162
 Meningocele 92
 Meningeal (1) lateral 839 844 845
 medial 839 842 844
 Mental nerve 63 121 137 141 146
 149
 Mentalis muscle 126 149
 Mesenteric artery 413 414 481
 inferior 419 484 485 610 611
 618 621
 superior 446 447 449 452-454
 458-460 467 464 483 4 6 510
 519 573 531 536 544 594 596
 Mesenteric lymph glands, 4 9 491
 494 595
 Mesenteric plexus 453 483 495-497
 Mesenteric vein inferior 430 453
 454 481 485 487 490 511 531
 596 618 621
 superior 479 430 449 457 459
 481 48 489 511 511 519 536
 538 539
 Mesentery 435 446 447 463 496
 of appendix vermiformis 469 471
 543
 of colon 463
 common dorsal 414
 convolutions 455
 cyst 459
 of duodenum 447 450
 posterior 414 416
 prearterial 414
 proper 457
 root 455 457 472 481
 sigmoid 403
 tumor 459
 of uterine tubes, 591
 Meo appendix 469
 Mesocolicojejunal membrane, 475-
 476
 Mesocolon 511, 513
 ascending 445 446 447 463 464
 472
 descending 446 447 462-464
 472 487
 pelvic 474 477 500 596
 sigmoid 472
 transverse 424 435 436 438 440
 445 446 449 451 464 472
 474 483 487 513 534 535
 537 539 543
 Mesoderm 169 1 0 910
 Mesoduodenum 414 424 445 446-
 448 463 464
 Meo-esophagus 423 424

- Metacarpal trium 413 414 423 424
 435 529
 Mesonphros 628
 Metapharynx See Oropharynx
 Metatarsal ligament 583 585 587
 591 603 622 623
 Mesometoid 462 477
 Metatarsal tendon 165
 Mesometatarsal ligament 583 585 587
 591 603
 Metacarpal arteries palmar 710
 Metacarpal bone(s) 749 750 754
 756 755 760 770 773, 775, 776
 base 711
 first 759 773
 fractures 784 785
 Lennett's 785
 of fingers only 784 785
 of thumb 785
 ligaments transverse deep 755,
 756
 medial 755
 shafts 773
 of thumb 755 777
 Metacarpal joints 771
 Metacarpal ligament 755 756 762
 771
 Metacarpophalangeal joints dislo-
 cation 785
 ligaments 755 756
 Metaphros 628
 Metaphysis of femur 828 829
 of humerus 709 710
 of ulna 740 741
 Metatarsal artery plantar 887
 Metatarsal bones 882 889 891 895
 896
 Metatarsophalangeal joints 886
 887 891 894 895 898 900
 Metatarsus 881 891
 Michels N A 510
 Microstoma 119
 Midaxillary line of thorax, 258 297,
 299 311
 Midbrain 39 914
 Midcarpal joint See Carpal joints
 transverse
 Midcolic artery 498
 Middle arm lesions 249
 Middle ear 54 106 107 109 115
 137
 aditus 110
 auditory tube See Auditory tube
 chorda tympani 110
 eustachian tube See Auditory
 tube
 fenestra cochlea, 109
 rotunda 106
 scutuli 109
 floor 109
 foramen ovale 109 111
 foramen rotundum 109
 incus 106 109 111 115
 infection 107 111 118
 inflation of Politzer method 114
 Valvassini method 114
 Middle ear (Continued)
 lymph drainage 131
 malleus 106 109 111 115
 mucous membrane 111
 muscles 110 111
 nerves 67
 ossicles 106 109 110 111
 processus cochleariformis 110
 prominence of facial canal 109
 promontory 109
 pyramid 110
 recess epitympanic 109 112
 roof 109
 tensor tympani 110 112
 tympanic antrum 110 112
 umbo 111
 walls 109 110
 Middle vein of heart 336
 Midgut 414 340
 Mikulicz procedure in surgery of
 large intestine 496 497, 499
 Miles W E 481 493
 resection abdominoperineal one
 stage 497 499 502
 Milk line 274 275
 Milk teeth 149
 Miller 433
 Millin 579
 Miner's elbow 721
 Mitchell G A G 405
 Modiolus 115 116 118
 Molars 149 151 163
 Moll glands of 72 74
 Mons veneris 649 650
 Montgomery, areolar glands of 276
 277
 Morgagni columns of 482 487 491
 Morrison pouch of, 507
 Moschowitz 502
 Mosher 173
 Motor nerve sides of safety and
 danger 733
 Mouth 91
 angle of 126 128 129, 136
 cysts 148
 lymphatics 180
 mucous membrane 140
 proper 147 160
 ranula 148
 regions of 143 160
 vestibule 147 148
 Movements abduction See Abduc-
 tion
 adduction See Adduction
 of ankle joint 878 879
 circumduction of radio carpal
 joint 754
 of shoulder joint 699
 deviation of radiocarpal joint
 radial 723 753 754
 ulnar 754
 dorsiflexion of foot 854 855 856
 878 897
 eversion of foot 858 878 879
 888 893 896 897
 extension See Extension

- Movements (Continued)
 flexion See Flexion
 of hip joint See Hip joint move-
 ments
 inversion of foot 854 855 859
 878 859 888 893 897
 of toe great 859
 of knee joint See Knee joint,
 movements
 pronation of forearm 723 726
 732 753
 of hand 739 742
 rotation See Rotation
 of shoulder joint 690
 supination of forearm 732 735,
 753
 of hand 739 742
 Mucoperitoneum 58 95 153
 Mucous glands of lips 144 145
 Mucous membrane See individual
 organs and parts
 Multangular bone greater 748 750
 752 755 771 774
 lesser 748 750 754, 771 772
 Multifidus muscle 399 402
 Mumps 178
 Muscle(s) of abdominal walls an-
 terior 369 372
 posterolateral 397 404
 abductor digiti minimi 772 885
 abductor digiti quinti of foot
 810
 of hand 772 773 775
 abductor hallucis 870 873 875
 878 882 884 885
 abductor pollicis brevis 764 772
 775
 longus 730 734, 735 743 744
 750 752 772
 adductor brevis 554 555 796
 812 816 817 825 826 831
 adductor hallucis 882 886 887
 889 897 898
 adductor longus See Adductor
 longus muscle
 adductor magnus See Adductor
 magnus muscle
 adductor minimus 796 803 821
 830
 adductor pollicis 759 760 770
 772 773 782
 anconeus See Anconeus muscle
 of arm 696 01
 aryepiglottic 235 237 238 240
 arytenoid 233 235 237 240
 auricular 65 66
 biceps See Biceps muscle
 brachialis See Brachialis muscle
 brachioradialis See Brachioradia-
 lis muscle
 bronchoesophageal 320
 buccinator See Buccinator muscle
 buccopharyngeus 155
 bulbocavernosus, 501 565 575
 579 589 627 629 631 638
 651 658

Muscle(s) (Continued)

pulis pugnator *See* Muscle pul
 buccinatorius
 caninus, 1 0 1 6 1 9
 of cheek 1 0 1 2 116
 of chin 1 6 1 9
 ciliary 61 8 80 89
 coccygeus 4, 4 2 484 485 554
 555 56 611 64
 compressor naris 1 9
 cinctricor *See* Cinctricor
 muscle
 coracobrachialis *See* Coracobra-
 chialis muscle
 corpus cavernosus, 589
 crotacet 364 5 4 39 371 640
 642
 cricoarytenoid 11 31 215
 216 218
 cricoharyngeal
 cricothyroid 1 0 05 04, 211
 31 235 19 112
 crural anterior 8 6
 cruratus, 388 349 624 619 641
 of defecation 169
 deltid *See* Deltoid muscle
 depressor anguli oris 121 1 6
 1 8
 depressor labii inferioris 1 6 128
 depressor septi nasi 1 8
 detrusor 569
 diaphragm 64 407
 pelvic 556 55 557
 diastolic *See* Diastolic muscle
 dilator naris, 1 8
 dilator pupillae 80
 of ear external 107
 middle 110 111
 of eminence hypothetnar 3 7 6
 thenar 773 774
 epicranial 3
 extensor carpi radialis *See* *See*
 Extensor carpi radialis mus-
 cle brevis
 longus *See* Extensor carpi radi-
 alis muscle longus
 extensor carpi ulnaris *See* Exten-
 sor carpi ulnaris muscle
 extensor digiti quinti proprius
 774 734 775
 extensor digitorum brevis, 853
 8 8 881 882 889
 extensor digitorum communis *See*
 Extensor digitorum communis
 muscle
 extensor digitorum longus *See*
 Extensor digitorum longus mus-
 cle
 extensor hallucis brevis 878 882
 889
 longus 853 855 857 865 871
 882 889
 extensor indicis proprius 724 730
 734 735 775 776
 extensor minimi digiti *See* Ex-
 tensor digiti proprius muscle

Muscle(s) (Continued)

extensor pollicis *See* Extensor
 pollicis muscle
 of eye 8 0 81 84
 of eyebrows 128
 of face 121 1 6 129
 of facial expression 1 0
 femoris 802
 flexor accesorius (diatorum
 quadratus plantae) muscle 882
 884 885 887 889
 flexor carpi radialis *See* Flexor
 carpi radialis muscle
 flexor carpi ulnaris *See* Flexor
 carpi ulnaris muscle
 flexor digiti minimi 72
 flexor digiti quinti brevis of foot
 882 884 88 889
 of hand 773 775
 flexor digitorum *See* Flexor di-
 gitorum muscles
 flexor hallucis *See* Flexor hallucis
 muscles
 flexor pollicis *See* Flexor pollicis
 muscles
 of foot *See* Foot muscles
 of forearm reaction anterior
 (volar) 723 724, 726 710
 posterior (dorsal) 737 735
 frontalis, 124 126
 gastrocnemius *See* Gastrocnem-
 ius muscle
 gemelli 554 555 592 94 97
 800 803 821 824 831
 geniohyoid *See* Geniohyoid
 muscle
 geniohyoid *See* Geniohyoid
 muscle
 glossoepalating, 154 155 158 164
 of gluteal region 90 92
 gluteus *See* Gluteus muscles
 gracilis *See* Gracilis muscle
 hamstring 800 820 821 826 835
 836
 hypoglossus 140 148 157 160
 164 185 193
 hypothetnar 770
 iliacus, 401 473 497 799 801
 803 808 812 813
 ilioacoccygeus 556 559
 iliocostalis 399 402
 iliofemoral 497
 iliopsoas 382 466 548 611 618
 796 800 802 816 824 826
 831
 of ilium 544
 infrahyoid 191 199 250
 infrapinatus *See* Infra pinatus
 muscle
 interarytenoid 238
 intercostal 441
 internal 266 269, 271 272 280
 437
 interossei *See* Interossei muscles
 intertransversalis 185

Muscle(s) (Continued)

lachrymatorius 554 555 575
 579 589 627 631 633 635 637
 631 633 635 638
 of ischium 554 555
 of larynx 1 0 236
 laryngeal external 173
 latissimus dorsi *See* Latissimus
 dorsi muscle
 of leg *See* Leg muscles
 levator anuli oris 1 0 126 128
 levator ani *See* Levator ani mus-
 cles
 levator costarum 217
 levator glandulae thyroideae 05
 06
 levator labii superioris, 121 126
 128 138
 alaeque nasi 176 128
 levator palati 154 156 230
 levator palpebrae superioris 61
 72 74 84 86, 89
 levator scapulae 185, 187 243
 244 246 6 9 681
 levator veli palatini 155
 of lips, 126 1 5 129 136
 longissimus 399 402
 longitudinal 146 158 434
 longus capitis, 1 8 185 187 195
 longus cervicis *See* Muscles
 longus colli
 longus colli 1 8 185 187 196
 222 253 418 419 696
 lumbicals of foot 882 884 886
 898
 of hand 759 60 64 68 7 0
 118 181 183 86
 masseter *See* Masseter muscle
 of mastication 177 134 136 1 0
 membranaceae *See* Muscle
 phincter urethrae
 mentalis 126 129
 mouth angle of 136
 multus 399 407
 mylohyoid *See* Mylohyoid mus-
 cle
 of neck 191 193
 of nose 126 128
 oblique *See* Obliquus muscle
 obturator externus abdominis
 554 555 557 589 607 596
 800 816 818 925 831
 obturator internus abdominis
 554 558 560 561 564 565
 572 575 637 658 791 793
 794 796 797 803 821 824 831
 occipitofrontalis 3 4 66 128
 omohyoid *See* Omohyoid muscle
 opponens digiti quinti 712 773
 775
 opponens pollicis 764 710 777
 774
 orbicularis oculi 77 74 8 126
 128
 orbicularis oris 67 124 128 136,
 143 144

Muscle(s) (Continued)

of orbit 84 85
 of palate soft 154
 palatoglossus 134 157 163 164
 palatopharyngeal 155 156 163
 164 231 236
 palmaris brevis 761 767
 palmaris longus 723 724 726 728
 papillary 340 343
 pectinate 339 340
 pectineus 401 550 554 555
 pectoralis *See* Pectoralis muscle
 pectifemoral group 556
 of pelvis 6 5 658
 perineal *See* Perineal muscles
 of perineum 655 658
 peroneus *See* Peroneus muscles
 pharyngeus 211
 pharyngopalatinus 15 164
 of pharynx 129 136 156 226
 227 231
 constrictor *See* Constrictor
 muscles of pharynx
 piriformis *See* Piriformis muscle
 plantaris 823 835 836 840 841
 859 861 871
 platysma *See* Platysma muscle
 popliteus 835 836 843 853 859
 861 863 865
 prethyroid 212 216
 procerus 128
 pronator quadratus 724 727 729
 745
 pronator teres 249
 psoas *See* Psoas muscle
 pterygoid *See* Pterygoid muscle
 of pubis 554 555
 pubococcygeus 556 559
 pyramidalis, 272 310 372 376
 555 570
 quadrangular of larynx 735
 quadratus femoris 549 554 614
 796 800 803 816 821 830 832
 quadratus labii inferioris 226
 quadratus lumborum 288 397
 398 400 403 407 410 473 54
 618
 quadratus plantae 878
 quadriceps extensor 841
 quadriceps femoris *See* Quadri-
 ceps femoris muscle
 radial extensors long of wrist
 697
 rectococcygeus 559
 recto urethralis 577 604
 rectus abdominis *See* Rectus ab-
 dominus muscle
 rectus capitis 183 187
 rectus femoris *See* Rectus femoris
 muscle
 rectus oculi 61 63 65 77 83 85
 89
 rhomboideus 246 247 359 360
 616 679 681
 ribbon of pharynx 210 221
 of thyroid gland 205

Muscle(s) (Continued)

risorius, 120 126 128 148 181
 rotatores 399 402
 sacrospinalis (erector pinae) 369
 397 399 401-404 408 410 554
 618
 salpingopharyngeus 228
 sartorius *See* Sartorius muscle
 scalenus *See* Scalenus muscle
 scalp 3 4 122
 semimembranosus *See* Semimem-
 branosus muscle
 semispinalis capitis 244
 semispinalis dorsa 399 402
 semitendinosus *See* Semitendino-
 sus muscle
 serratus *See* Serratus muscles
 soleus 853 858 861 864 866 876
 881 134
 sphincter *See* Sphincter muscles
 spinalis dorsa, 399 402
 plenius capitis 243 246
 stapedius 65 110 111 127
 sternocleidomastoid *See* Sterno-
 cleidomastoid muscle
 sternocostalis 266 267 330
 sternohyoid *See* Sternohyoid
 sternothyroid *See* Sternothyroid
 muscle
 of sternum 264 265
 of stomach 434
 styloglossus 15 140 157 158 163
 164 172 188
 stylohyoid *See* Stylohyoid mus-
 cle
 stylopharyngeus *See* Stylopha-
 ryngeus muscle
 subclavius 669 671 673 676 677
 694 700
 subcostal 267 269 272
 subscapularis *See* Subscapularis
 muscle
 supinator *See* Supinator muscle
 suprhyoid 147 236
 supra pinatus *See* Supra pinatus
 muscle
 tail 556
 temporal *See* Temporal muscle
 tensor fasciae latae *See* Tensor
 fasciae latae muscles
 tensor palati *See* Tensor veli pala-
 tini muscles
 tensor tarsi, 126 127
 tensor tympani 62 65 106 108
 110 157
 tenor veli palatini *See* Tensor
 veli palatini muscles
 teres major *See* Teres major mus-
 cle
 teres minor *See* Teres minor
 muscle
 thenar 678 764 768
 of thigh *See* Thigh muscles
 thyro arytenoid 211 233 235
 236 238
 thyro epiglottic, 233 238

Muscle(s) (Continued)

thyrohyoid 174 183, 186, 234
 236
 thyroid superior, 238
 tibialis anterior *See* Tibialis an-
 terior muscle
 anticus *See* Tibialis anterior
 muscle
 posterior *See* Tibialis posterior
 muscle
 posticus *See* Tibialis po tenor
 muscle
 of tongue 157 158
 trachealis 318 319
 transversus 810
 transversus abdominis *See* Trans-
 versus abdominis muscle
 transversus linguae 158
 transversus perinei 502
 transversus perinei superficialis
 579
 transversus spinalis 399 402
 transversus thoracis, 264 266 269
 271 272
 trapezius *See* Trapezius muscle
 triangulus (depressor anguli
 oris) 121 126 128
 triceps brachii *See* Triceps brachii
 muscle
 triceps urae 876
 uvular 154 156
 vastus intermedius 805 812 818
 822 825 831 834 840
 vastus lateralis 802 805 812
 818 820 822 826 831 834 840
 vastus medialis 805 811 813 818
 819 822 826 831 833 849
 verticalis linguae 158
 vocal 211 238
 of zygomatic area 126 128
 zygomatcus 5 120 126 128 148
 Muscular artery 196
 Muscular vein 406
 Musculo aponeurotic tendon 556
 Musculocutaneous nerve 673 675
 677 679 688 697 699 715 719
 736
 of leg *See* Peroneal nerve super-
 ficial
 Musculophrenic artery 290
 Musculospiral nerve *See* Radial
 nerve
 Myenteric plexus 434
 Mylohyoid artery 137
 Mylohyoid muscle 62 134 135
 141 142 147 148 152 159 180
 216 218 224 227 230
 Mylohyoid nerve 18 63 64 227
 Myometrium of uterus 588
 Myringotomy 108 109
 Naffziger syndrome of 247
 Naffziger and Jones surgery of or-
 bit 77 78
 Nail of finger 777 778
 Nasopharynx 227 229

- Nasal artery 81 82 95
 Nasal bone, 14 16 20-9 94 121
 18
 Nasal cavity 139 153
 alveoli, 152
 Nasal nerve 64 20 1 1
 Nasal process 112 1 0
 Nasal septum 14 1 45 86 99
 60 64 5 91 9 112 1 0 112
 derivative 9
 submucous resection 2
 Nasal pit 1 1
 Nasal vein 5
 Nasus 14 18 46 49
 Nasomaxillary nerve (1 85 88
 See also Infratrochlear nerve and
 Nasal nerve
 Nasopalatine nerve 97
 Nasopharynx 110 140 153
 lymph drainage 151
 Natis 89
 Navel *See* Umbilicus
 Navicular bone (scaphoid) of foot
 5 5 583 511 893 816
 of hand 48 50 15 54 5
 2 4
 fracture 56
 Neck 169 190
 anterolateral region 181 49
 carbuncles, 181
 embryology 169 1 1
 fascia deep 1 6 150 *See also*
 Cervical fascia (deep)
 superficial 181 18 43
 framework bones and cartilagi-
 nous 1 1 4
 furuncle 181
 gland salivaceous, 181
 muscles 191 191
 nerves 181 183 190
 cutaneous anterior 181 185
 244 245
 superficial 183 184
 root 250 254
 skin 181
 triangle anterior 177 178 181
 243
 posterior 1 6 178 243 249
 tumors 201
 viscerovascular plexus involve-
 ment of 162
 Nelson 316
 Nerve(s) of abdominal walls 364
 366 404
 abductors 65 88 89 103
 accessory *See* Accessory nerve
 acoustic *See* Auditory nerve
 alveolar 62 64 131 137 141
 of anal canal 612
 of ankle joint 877
 of arm *See* Arm nerves
 auditory *See* Auditory nerve
 auricular *See* Auricular nerve
 auriculotemporal *See* Auriculo-
 temporal nerve
 axillary *See* Axillary nerve
 Nerve(s) (Continued)
 of bladder urinary 569 612
 of breast 81
 buccal *See* Buccal nerve
 of buttock 614
 cardiac 69 344
 carotid tympanic 68
 cervical *See* Cervical nerves
 cervicofacial 66 6 132 133
 cheek 1 1 149
 of chin 6 121 124
 chorda tympani *See* Chorda tym-
 pani nerve and Facial nerve
 ciliary 64 80
 circumflex *See* Axillary nerve
 clitordi-dorsal 587 614 655
 65 654
 coccygeal 4 9 553 911 912
 cochlear 6 106 115 116 118
 of colon 494 417
 costocervical trunk 190
 cranial 4 58 71 130 184 156
 cutaneous *See* Cutaneous nerves
 dental *See* Alveolar nerve
 of diaphragm 240
 digital *See* Digital nerves
 of duodenum 453
 of ear external 6 107 140
 internal 67
 middle 67
 of epiglottis 68
 of esophagus, 4 0 42* 423
 ethmoidal 22 63 95
 of eye 59 60 80
 of eyelids 63 64 12 73 1 0-121
 of face 1 0-125
 facial *See* Facial nerve
 femoral *See* Femoral nerve
 fibers 913 914
 of fingers, 160 164 710
 of foot 881 883 887 889
 of forearm *See* Forearm nerves
 freshman's, 859
 frontal 5 63
 gastroic, 433 441
 See also Vagus nerve
 genitocrural 394 396
 genitofemoral 473 594 596 611
 616 618 644 804 806
 glossopharyngeal *See* Glossophar-
 yngcal nerve
 gluteal 613 614 92 194 803
 815 820
 of gums 62 140 141
 of hand *See* Hand nerves
 of heart 347
 hemorrhoidal inferior 432 495
 497 614 629 655 658
 of hip joint 800
 hypogastric 612
 hypoglossal *See* Hypoglossal
 nerve
 iliohypogastric 366 379 382 404
 407 473 618 789 190
 ilioinguinal 366 3 9 382 392,
 404 407 473 618 804
 Nerve(s) (Continued)
 inframandibular 132
 infraorbital 16 11 64 5 97
 1 1 146 147 151
 of infrapariotemporal space 92 94
 infratrochlear 63 64 121
 of inguinal region 384 185
 intercostal *See* Intercostal nerve
 interostechial 2, 669 6 0
 615
 interoscapular 80 281
 intermediate 67
 intermesenteric 475 477
 interosseous *See* Interosseous
 nerve
 ischiatric, 832
 of joint elbow 715
 intercarpal 55
 knee 835 83 848
 shoulder 640
 of kidneys 407
 labial 63 64 121 655 658
 of labium majus, 93 804
 labial, 63 121
 laryngeal *See* Laryngeal nerve
 of larynx 238
 of leg 852 854 856 859 860
 lingual *See* Lingual nerve
 of lip 63 64 66 6 121 124
 146
 of liver 511
 lumbar 364 166 40 404 40,
 617 189
 lumboinguinal 504 806
 of lungs, 69
 mandibular *See* Mandibular
 nerve
 maseteric, 140
 maxillary *See* Maxillary nerve
 of meatus, auditory external, 140
 median *See* Median nerve
 mental 63 121 137 141 146 149
 motor sides of safety and
 "danger" 33
 musculocutaneous *See* Musculo-
 cutaneous nerve
 of leg *See* Peroneal nerve
 upercular
 musculoparal *See* Radial nerve
 mylohyoid 18 63 64 227
 nasal 64 90 121
 nasosiliary 63 85 88
 See also Infratrochlear nerve
 and Nasal nerve
 nasopalatine 92
 of neck *See* Neck nerves
 of nose 59 60 64 66 95 96 121
 obturator *See* Obturator nerve
 occipital greater 5 7
 lesser 7 107 127 183 185 244
 245
 oculomotor *See* Oculomotor
 nerve
 olfactory 22 23 36 37 59 92
 95 96
 ophthalmic *See* Ophthalmic nerve

Muscle(s) (Continued)

of orbit 84 85
 of palate soft 154
 palatoglossus 1 4 157 163 164
 palatopharyngeal 155 156 163
 164 231 236
 palmaris brevis 761 762
 palmaris longus 723 724 726 728
 papillary 340 343
 perizone 339 340
 pectineus 401 530 534 535
 pectoralis See Pectoralis muscle
 pelvifemoral group 536
 of pelvis 635 638
 perineal See Perineal muscles
 of perineum 635 638
 peroneus See Peroneus muscles
 pharyngeus 711
 pharyngopalatinus 155 164
 of pharynx 129 1 6 156 226
 271 231
 constrictor See Constrictor
 muscles of pharynx
 piriformis See Piriformis muscle
 plantaris 825 835 836 840 841
 859 861 871
 platysma See Platysma muscle
 popliteus 835 836 843 853 859
 861 863 865
 prethyroid 212 216
 procerus 128
 pronator quadratus 724 727 729
 745
 pronator teres, 249
 psoas See Psoas muscle
 pterygoid See Pterygoid muscle
 of pubis 554 555
 pubococcygeus 536 539
 pyramidalis 272 370 372 376
 555 550
 quadrangular of larynx 233
 quadratus femoris 549 554 614
 96 800 803 816 821 830 832
 quadratus labii inferioris 226
 quadratus lumborum 288 397
 398 400 403 407 410 473, 554
 618
 quadratus plantae 878
 quadriceps extensor 841
 quadriceps femoris See Quadri-
 ceps femoris muscle
 radial extensor long of wrist
 697
 rectococcygeus 539
 recto urethralis 577 604
 rectus abdominis See Rectus ab-
 dominis muscle
 rectus capitis 135 187
 rectus femoris See Rectus femoris
 muscle
 rectus oculi 61 63 65 77 83 86
 89
 rhomboideus 246 247 359 360
 616 679 681
 ribbon of pharynx 210 221
 of thyroid gland 205

Muscle(s) (Continued)

risorius 1 0 126 128 148 181
 rotatores 399 407
 sacrospinalis (erector pinae) 369
 397 399 401 404 408 410 554
 618
 salpingopharyngeus 228
 sartorius See Sartorius muscle
 scalenus See Scalenus muscle
 scalp 3 4 122
 semimembranosus See Semimem-
 branosus muscle
 semispinalis capitis 244
 semispinalis dorsa 399 402
 semitendinosus See Semitendino-
 sus muscle
 serratus See Serratus muscles
 soleus 853 858 861 864 866 876
 palm 134
 sphincter See Sphincter muscles
 spinalis dorsa 399 402
 plenus capitis 243 246
 capedius 65 110 111 122
 sternocleidomastoid See Sterno-
 cleidomastoid muscle
 sternocostalis 266 267 330
 sternohyoid See Sternohyoid
 sternothyroid See Sternothyroid
 muscle
 of sternum 264 265
 of stomach 434
 styloglossus 13 140 157 158 163
 164 172 188
 stylohyoid See Stylohyoid mus-
 cle
 stylopharyngeus See Stylopha-
 ryngeus muscle
 subclavius 669 671 673 676 677
 694 700
 subcostal 267 269 272
 subscapularis See Subscapularis
 muscle
 supinator See Supinator muscle
 suprihyoid 147 236
 supraspinatus See Supra pinatus
 muscle
 tail 536
 temporal See Temporal muscle
 tensor fasciae latae See Tensor
 fasciae latae muscles
 tensor palati See Tensor veli pala-
 tini muscle
 tensor tarsi 126 127
 tensor tympani 62 65 106 108
 110 157
 tenor veli palatini See Tensor
 veli palatini muscles
 teres major See Teres major mus-
 cle
 teres minor See Teres minor
 muscle
 thenar 678 764 768
 of thigh See Thigh muscles
 thyro arytenoid 211 233 235
 236 238
 thyro epiglottic, 233 238

Muscle(s) (Continued)

thyrohyoid, 174 185, 186 234,
 236
 thyroid superior, 238
 tibialis anterior See Tibialis an-
 terior muscle
 anticus See Tibialis anterior
 muscle
 posterior See Tibialis posterior
 muscle
 posticus See Tibialis posterior
 muscle
 of tongue 157 158
 trachealis, 318 319
 transversus 810
 transversus abdominis See Trans-
 versus abdominis muscle
 transversus linguae 158
 transversus perinei 502
 transversus perinei superficialis
 579
 transversus pinalis 399 402
 transversus thoracis 264 266 269
 271 272
 trapezius See Trapezius muscle
 triangulares (depressor anguli
 oris) 121 126 128
 triceps brachii See Triceps brachii
 muscle
 triceps urae 876
 uvular 154 156
 vastus intermedius 805 812 818
 822 825 831 834 840
 vastus lateralis 802 805 812
 818 820 822 826 831 834 840
 vastus medialis 805 811 815 818
 819 822 826 831 833 849
 verticalis linguae 158
 vocal 211 238
 of zygomatic area 126 128
 zygomatatus 5 120 126 128 148
 Muscular artery 196
 Muscular vein 406
 Musculo aponeurotic tendon 556
 Musculocutaneous nerve 673 675
 677 679 688 697 699 715, 719
 736
 of leg See Peroneal nerve super-
 ficial
 Musculophrenic artery 290
 Musculopirral nerve See Radial
 nerve
 Myenteric plexus 434
 Mylohyoid artery 137
 Mylohyoid muscle 62 134 135
 141 142 147 148 152 159 180
 216 218 224 227 230
 Mylohyoid nerve 18 63 64 227
 Myometrium of uterus 588
 Myringotomy 108 109
 Naffziger syndrome of 247
 Naffziger and Jones surgery of or-
 bit 77 78
 Nail of finger 77 778
 Nasopharynx 227 29

- Notch (Continued)**
 supraorbital 14 65 10
 supraorbital (jugal) 62 63
 65 66 14 110
 tentorial 39
 thyroid 1 1 1 15 14 235
 trochlear of ulna 92 114 715
 40
 tympanic 105
Notch of 910
Notch canal of 581 583
Nucleus, pulposus 205 207
 of inferior surface of brain
 35 38
 thoracicus 914
Nymphae See *Labia minora*
- Obliquus abdominis muscle** 2 2
 365 366 3 1 1 3 1 5 1 8 184
 3 6 155 180 39 391 137 338
 400 404 405 411 471 515 511
 618
 external 554 555 599 810
 internal 579 810
Obliquus oculi muscle 61 63 84
 86 89
Obliquus tendon superior 84
Obturator artery 550 56 564 572
 592 595 601 60 604 76
 800
 abnormal 60 604
 of lateral 604
Obturator canal 55 559
Obturator crest 550
Obturator externus abdominis mus-
cle 554 555 557 602 76 800
 810 816 818 825 831
Obturator fascia 631 656 659
Obturator foramen 549 550
Obturator internus abdominis mus-
cle 554 555 560 561 564 565
 5 2 575 589 614 657 658 91
 793 794 96 797 803 810 821
 824 831
Obturator membrane 799 816
Obturator nerve 572 592 96 797
 800 815 818 848 907
 cutaneous branch 90 806 813
Obturator region 816
Obturator vein 572 592 604
Occipital artery 5 7 24 26 131
 186 194 197 01
Occipital bone 10 11 18 22 24
 38 246
 basilar process 103 228 229
 transverse sinus 40
Occipital lymph glands 6 7
Occipital nerve greater 5 7
 lesser 7 107 127 183 185 244
 245
Occipital region 6 7 184 245
Occipital vein 5 7 48 50 52 54
 198
Occipito atlantal ligament 46 49
Occipitofrontalis muscles 3 4 66
 128
- Ochloer Alton** 247 313 353 515
 61
Oculomotor nerve 16 3 33, 35
 17 47 55 60 62 64, 73 80 88
 87 103
Olfactory process of axis 0
Olecranon 101 103 107 723
 fossa 714
 process 14 717 721 722 740
 fracture 716 72
 region 7 0 721
Olfactory bulb 35 36 47 59 60
Olfactory nerve 22 23 36 37 59
 92 95 96
Olfactory pit 119 10
Olfactory roots 36
Olfactory sulcus 35
Olfactory tract 35 16 59
Ollier 691 502
Omentum(a) 434 437 449 472
 bursa 423 424 4 6 434 537
 gastroduodenal 325 539
 gastrophilic 429
 gastrophilic See *Omentum*
 lesser
 gastrophilic 529, 541
 greater 427 4 9 432 434 436
 438 439 444 445 445 466
 506 537 541 543
 lesser 424 428 4 9 432 434
 436 438 439 448 505 506
 510 513 517 521 572 524
 527 529 536 537 539 541
Omohyoid muscle 1 147 159 172
 1 4 177 181 182 185 186 188
 193 195 199 201 206 07 211
 213 215 223 236 243 247
 6 9
Opicula 34
Ophthalmia sympathetic 80
Ophthalmic artery 16 59 73 8
 85 86 90 95 119 121
Ophthalmic nerve 16 55 62 64 79
 81 86 89 92 96 1 0-122
Ophthalmic vein 16 73 50 53 57
 73 82 86 90
 inferior 48 86 140 153 154
 superior 6 48 55 86 119 10
 153 154
Opponens digiti quinti muscle 772
 773 775
Opponens pollicis muscle 764 70
 772 774
Optic chiasma 33 36 38 55 58 60
 87
Optic foramen 14, 16 21 23 59
 83 85 87
Optic groove 21 23
Optic nerve 16 35 37 47 56 58
 60 77 78 81 83 87 103
Optic radiations 59 60
Optic tract 36 38 59 60
Orbicularis oculi muscle 72 74 85
 126 128
Orbicularis oris muscle 67 124 128
 136 143 144
- Orbit** 0 45 16 19 83 79 120
 arteries 85 88 138 139
 cyrus 35 16
 ligaments 93 84
 muscles 84, 85
 nerves 85 88
 septum 13
 surgery of 16 78
 decompression intracranial ap-
 proach 77 78
 Kronlein's operation 6 77
 lateral temporal approach 76
 77
 tumors 6 77
 veins 85 88
Orbital nerve 64 86
Orbital sulcus 35 36
Orifice anal 659
 atriocuticular 339 342 343
 of bladder ureteral 595
 of bulbo urethral gland 639
 cardiac 425 426
 of duct ejaculatory, 577
 ophthalmic 228
 ileocecal 466
 pharyngeal 228
 pulmonary 341
 pyloric See *Pylorus*
 tricuspid 339 340
 of ureter 562
 female 650 652
 male 566 639
 urethral internal 566 568
 vaginal 650 651
 vesical 580
Oropharynx 2 7 729 231
O of cervix of uterus 587 591
 magnum See *Capitate bone*
Oscles auditory 106 110 111
Osteomyelitis 10 162
Otium abdominal 591
 maxillary 100
 uterine 591
Otic ganglion 62 64 110 140 157
Otitis media 108
Ovarian artery 591 593 596 603
 605 610
Ovarian ligaments 582 585 587
 591 593 619 6 1
Ovarian plexus 592
Ovarian vein 591 593 606 60
 610
Ovary (ies) 582 583, 585 586 591
 593 601 605 608 619 621
 623
 adhesions from pendulous trans-
 verse colon 474 475
 arteries 593
 ectopic 581
 gubernaculum 582 583 585
 hilus 605
 ligament 581 603 623
 suspensory See *Infundibulo*
 pelvic ligament
 lymph vessels 593
 nerves, 593 612

Nerve(s) (Continued)

optic *See* Optic nerve
 of orbit 85 88
 orbital 64 86
 of ovary 593 612
 of palate 68 124 136 157
 palatine 62 64 139 157
 palpebral 64 121
 parasympathetic of colon 495
 of stomach 432
 parotid gland 130 140
 pectoral 673 677
 pelvic 495
 of penis 481 575 614 629 634
 616 631 639 604
 perineal 481 613 614 629 632
 655 651 658
 peroneal *See* Peroneal nerve
 petrosal 17 73 65 68 115
 pharyngeal 64 68 69 139 184
 phrenic *See* Phrenic nerve
 plantar 810 878 881 883 885
 887 889
 pneumogastric *See* Vagus nerve
 popliteal 835 837
 external *See* Peroneal nerve
 common
 internal *See* Tibial nerve
 lateral *See* Peroneal nerve
 common
 medial *See* Tibial nerve
 presacral 612 618
 pterygoid 64 140
 of pterygoid canal 55 64 95
 pudendal *See* Pudendal nerve
 pudic *See* Pudendal nerve
 radial *See* Radial nerve
 of radiocarpal joint 733
 of rectum 612
 recurrent 140 190 306
 sacral 495 553 561 612 789
 91 916
 saphenous *See* Saphenous nerve
 scalp 6 7 121
 scapular dorsal 616
 sciatic *See* Sciatic nerve
 of scrotum 793 804
 sensory of nasal cavity 96
 of shoulder cutaneous 670
 joint 690
 of hip of buttocks 365 366
 of forehead 121
 of small intestine 459 460
 perimastic external 379
 phenopalatine 11 67 92
 pinal 269 271 273 912 915
 rami 269 272 789 190
 thoracic 359 360
 plantar *See* Splanchnic nerves
 of stomach 68 69 432 434
 subclavian 676
 subcostal 272 292 401 473 806
 sublingual 147
 subcapular 616 6 9 684 690
 supraclavicular 187 18 244 245
 247 669 610 687 698

Nerve(s) (Continued)

supra orbital 5 7 62 63 85 86
 120
 of suprapiriformic space 194
 suprascapular 249 676 679 684
 690
 upratrochlear 5 6 63 85 86
 121
 sural 820 836 837 856 857 871
 sympathetic *See* Sympathetic
 nerves
 of teeth 64 99 141 151
 temporal 64 66 124 127 139
 140
 of temporal and infratemporal
 regions 140 141
 temporofacial 65 132 134
 of thigh cutaneous *See* Cutan-
 eous nerves of thigh
 thoracic *See* Thoracic nerves
 thoracic abdominal 272
 thoracodorsal 284 285 400 675
 677
 of thumb 164
 of thyroid gland 211
 thyrocervical trunk 187 190 205
 207 208 248
 tibial *See* Tibial nerve
 of tongue 64 65 67 68 71 123
 140 158 159 184 185
 of tonsils 68 165
 tragus 28 105
 trigeminal *See* Trigeminal nerve
 trochlear 16 23 37 47 55 61
 69 103
 ulnar *See* Ulnar nerve
 of ureter 597
 of urethra 612
 of uterine tube 592
 of uterus 612
 of vagina 612
 vagus *See* Vagus nerve
 vasomotor sympathetic 119
 vestibular 67 115 117 118
 of Vidian *See* Pterygoid canal
 nerve of
 of viscera pelvic female *See* Vis-
 cera pelvic female nerves
 zygomatic 16 17 66 127
 zygomaticofacial 64 121
 zygomaticotemporal 19 64
 Nervus ergens (nervi erigentes)
 479 495 497 612
 Nervus spinosus *See* Recurrent
 nerve
 Neuralgia 90
 amputation stump 189
 facial 121 125
 intractable injection of nerves
 with alcohol 121
 resection of nerve 11 140
 trigeminal 121 125
 Neurectomy, presacral (superior hy-
 pogastric) 618 621
 Nevitis, retrobulbar 87 103
 Nervi of lips 145

Nipple 274 277 280 281

supernumerary, 214 216
 Nissen 313
 Nordland 238
 Norma frontalis 10 14 18
 regions frontal 11 15
 mandibular 14 17 18
 maxillary 14 17
 nasal 14 17
 orbital 14 17
 zygomatic, 14 17
 Nose 89 105
 arteries 90 95 139
 atrium 91 93
 auditory tube pharyngeal orifice
 91
 bullae ethmoidalis 104
 canal incisive 90 91
 cartilage 90 95
 cavities 90 93 95
 choanae 90 93 228
 concha 17 75 91 93 139 227
 229
 dorsum 89 90
 epistaxis 96
 external 89 90
 fractures 96
 gland of mucous membrane 94
 hatus, semilunar 91 93 102 104
 internal 90 95
 lamina pterygoid 93
 lymph drainage 95
 meatus 75 91 95 104
 mucous membrane 23 94
 muscles 126 128
 nares 90 93 94
 nerves 59 60 64 66 95 96 121
 polyp 92 94 96
 recess sphenoid ethmoidal 91 93
 rhinoscopy 90
 septum *See* Nasal septum
 skin 90
 urgency 96 97
 turbinate 104
 veins 90 95
 vestibule 90 91 93
 vomer 12 90 92 93
 Notch acetabular 550 798
 angular (incisura angularis) 425
 4 7
 cardiac (incisura cardiaca) 296
 306 308 311 330 425 427
 clavicular 262 263 265
 costal 263
 fibular of tibia 863
 inferolateral 551
 interarticular 240
 intercondylar of femur 829 845
 846
 jugal 202
 mandibular 18 136 137
 radial of ulna 739 140 42
 sacrocoecal 551
 sciatic 545 550 600 789 791
 semilunar *See* Notch trochlear
 sternal 172 181 215

Ovary (ies) (*Continued*)

- veins 593
- zones 593
- Overholt 313 316
- Pachoman bodies 37 41
- Pad fat buccal 129 136
 - infrapatellar 839 841 846 847
 - uctorial 129 140 149
- Palate 149
 - cleft 119
 - with harelip 146
 - surgery for 153 156 157
 - hard 11 12 91 92 139 147, 153, 155 228 229
 - arteries 153
 - glands 153
 - median raphe 153
 - mucous membrane 153
 - palatine rugae 153
 - nerves 123
 - soft 55 65 147 153 157 162 164 196 228 229
 - arteries 157
 - lymph drainage 131
 - muscles 154
 - nerves 68 156 157
 - tendons 154
- Palatine artery 95 138 139 155 164
- Palatine bone 12 14 15 92 104
 - crest na al 90
 - plates 90 92 153
- Palatine gland 153 155
- Palatine nerve 67 64 139 157
- Palatine process of maxilla 12 90 97 153
- Palatoglossus muscle 154 157 163 164
- Palatopharyngeal muscle 155 156 163 164 31 36
- Palpebrae *See* Eyelids
- Palp brail ligament median 75 121 126 127
- Palpebral nerves 64 121
- Palmar artery, superficial 763 769
- Palmar ligament(s) of interphalangeal joint 756
 - of metacarpophalangeal joint 755 756 762 773
 - transverse superficial 762
- Palmar region 759 776
 - layers 759 773
 - nerves 759 762
- Palmaris brevis muscle 761 762
- Palmaris longus muscle 723 724 726 728
- Palsy, Bell's 67
 - of brachial plexus 678 679
- Pampiniform venous plexus 630 607 609 641 643 645
- Pancreas 428 431 435 439 445 446 448 449 452 453 457 483 506 509 516 521 522 527 531 539
 - arcade of, 453

Pancreas (*Continued*)

- arteries of 536 537 540 543
- body 534 535
- cyst of 539
- ducts 536 539
 - accessory of Santorini 537
 - Wirsungs 534 536
- embryology 534 535
- head 534 535
 - carcinoma 539
 - resection 539
- lymphatics 531
- neck 534 535
- surgery of 537 539
 - approaches 537 539
 - pancreaticojejunostomy 539
 - for pancreatitis 539
 - pancreatoduodenectomy, 538 539
 - resection of head 539
 - tail 534 535
 - veins 537
- Pancreatic artery superior 452
- Pancreatic lymph glands superior 453
- Pancreatic vein 488
- Pancreaticoduodenal artery, 527
 - inferior 452 454 459 521 537 542
 - superior 427 428 430 452 453 459 521 523 536 537 541 542
- Pancreaticoduodenal lymph glands 453
- Pancreaticoduodenal vein 489
- Pancreatoduodenectomy 538 539
- Pancreaticolienal lymph glands 431
- Pancreatico plenic lymph glands 431
- Pancreatitis surgery for 539
- Pancreatoduodenectomy 538 539
- Panhysterectomy 620 622
- Panniculus adiposus *See* Camper's fascia
- Papilla(e) of anal canal 482
 - duodenal 519 523
 - niliform 158
 - tungiform 157 158
 - lacrimal 72 74
 - lenticular 157
 - sublingual 221
 - of tongue 148 157 158
 - umbilical 396
 - of Vater 536
- Papillary muscles 340 343
- Papilledema 60 88
- Papillitis 482
- Papilloma 364
- Paracentesis of tympanic membrane 108 109
- Paracolic lymph nodes, 491
- Parametrium 585 586 587
- Paranasal sinuses 97 99
- Parasympathetic nerves of colon 495
 - of stomach 432

- Parathyroid glands 1,0 210 218-220
 - tumor 219
- Paratracheal lymph glands 319, 420 422
- Para umbilical veins 368
- Parietal bone 11 15 18 19 22, 41, 54 134 137
- Parietal pelvic lymph glands 607
- Parietal region 6 7
- Parietal spider 552
- Parietal (temporal) vein 7 48 50 51 107 127 139 198
- Paras pace retroflexor 166 769, 781
- Paronychchia 784 785
- Paroophoron 581 582
- Parotid gland 5 18 66 107 121 123 124 127 129 134 142 147 149 151 161 162 178 184 195 196 245
 - abscess 107 129 134
 - arteries 130
 - capsule fibrous 130
 - isthmus 123 130 134
 - lobes 123 129 132
 - nerves 130 140
 - socia parotidis 130 132
 - surgery 130 132 134
 - swellings 130 131
 - tumors 130 132
 - vein 130
- Parotid region 129 134
 - lymph glands 131
- Parotidectomy 132 134
- Pars flaccida 108
- Pars intermedia 654
- Patches of Peyer 457
- Patella 804 821 825 827 838 841 845 847 849 850
- Patellar ligament 825 840 841 845 847 850 853 862 864
- Patellar plexus 804
- Pecten 480 482
- Pectinate muscles 339 340
- Pectinial ligament 548
- Pectineus muscle 401 550 554 555 796 797 799 800 803 809 811 813 818 825 826 831
- Pectoral fascia 275 280
- Pectoral lymph gland 369
- Pectoral nerve 673 677
- Pectoral region 669 679
- Pectoralis major muscle 243 249 263 264 271 272 274 281 283 286 351 367 669 671 673 676 678 680 688 690 694 695 697 700 710 712
- Pectoralis minor muscle 278 280 283 286 669 676 678 680 694 700 704
- Pectoralis minor artery 677
- Pedicle plenic 529 530
- Peduncles cerebral 36 38 41

- [illegible]

Ovary (ies) (Continued)

- veins 593
- zones 593
- Overholt 313 316
- Pachonian bodies 37 41
- Pad fat buccal 129 136
 - infrapatellar 839 841 846 847
 - suctorial 129 140 149
- Palate 149
 - cleft 119
 - with harelip 146
 - surgery for 151 156 157
 - hard 11 12 91 92 139 147 153, 155 228 229
 - arteries 153
 - glands 153
 - median raphe 153
 - mucous membrane 153
 - palatine rugae 153
 - nerves 123
 - soft 55 65 147 153 157 162 164
 - 196 228 229
 - arteries 157
 - lymph drainage 131
 - muscles 154
 - nerves 68 156 157
 - tendons 154
- Palatine artery 95 138 139 155 164
- Palatine bone 12 14 15 92 104
 - crest *na al* 90
 - plates 90 92 153
- Palatine gland 153 155
- Palatine nerve 62 64 159 15, 92 153
- Palatine process of maxilla 12 90 92 153
- Palatoglossus muscle 154 157 163 164
- Palatopharyngeal muscle 155 156 163 164 31 36
- Palpebrae *See* Eyelids
- Palpebral ligament median 15 121 126 127
- Palpebral nerves 64 121
- Palmar artery superficial 763 769
- Palmar ligament(s) of interphalangeal joint 756
 - of metacarpophalangeal joint 755 756 762 773
 - transverse superficial 762
- Palmar region 759 776
 - layers 759 773
 - nerves 759 762
- Palmaris brevis muscle 161 762
- Palmaris longus muscle 723 724 726 7 8
- Palsy Bells 67
- of brachial plexus 678 679
- Pampiniform venous plexus 606 607 609 641 643 645
- Pancreas 428 431 435 439 445 446 448 449 452 453 457 481 406 509 516 521 522, 527 531 539
 - arcades of 453

Pancreas (Continued)

- arteries of 536 537, 540 543
- body 534 535
- cyst of 539
- ducts 536 539
 - accessory of Santorini 537
 - Wirsung's 534, 536
- embryology 534 535
- head, 534 535
 - carcinoma 539
 - resection 539
- lymphatics 537
- neck 534 535
- surgery of 537 539
 - approaches 537 539
 - pancreatoduodenostomy 539
 - for pancreatitis, 539
 - pancreatoduodenectomy 538 539
 - resection of head 539
 - tail 534 535
 - veins 537
- Pancreatic artery superior 452
- Pancreatic lymph glands superior 453
- Pancreatic vein 488
- Pancreaticoduodenal artery 527
 - inferior 452 454 459 521 537 542
 - superior 427 428 430 452 453 459 521 523 536 537 541 542
- Pancreaticoduodenal lymph glands 453
- Pancreaticoduodenal vein 489
- Pancreatoduodenectomy 538 539
- Pancreaticolienal lymph glands 431
- Pancreaticosplenic lymph glands 431
- Pancreatitis surgery for 539
- Pancreatoduodenectomy 538 539
- Panhysterectomy 620 622
- Panniculus adiposus *See* Camper's fascia
- Papilla(e) of anal canal 482
 - duodenal 519 523
 - filiform 158
 - lingiform 157 158
 - lacrimal 72 74
 - lenticular 157
 - sublingual 227
 - of tongue 148 157 158
 - umbilical 396
 - of Vater 536
- Papillary muscles 340 343
- Papilledema 60 88
- Papillitis 482
- Papilloma 364
- Paracentesis of tympanic membrane 108 109
- Paracolic lymph nodes 491
- Parametrium 585 586 587
- Paranasal sinuses 97 99
- Parasympathetic nerves of colon 405
 - of stomach 432

- Parathyroid glands 170 210 218 220
 - tumor 219
- Paratracheal lymph glands 319 420 422
- Para umbilical veins 368
- Parietal bone 11 15 18 19 22, 41 54 134 137
- Parietal pelvic lymph glands 607
- Parietal region 6 7
- Parietal pider 552
- Parietal (temporal) vein 7 48 50 51 107 127 139 198
- Parona space retroflexor 766 769, 781
- Paronychia 784 785
- Paroophoron 581 582
- Parotid gland 5 18 66 107 121 123 124 127 129 134 142 147 149 151 161 162 178 184 195 196, 245
 - ab cess 107 129 134
 - arteries 130
 - capsule fibrous 130
 - isthmus 123 130 134
 - lobes 123 129 132
 - nerves 130 140
 - socii parotidis 130 132
 - surgery 130 132 134
 - swellings 130 131
 - tumors 130 132
 - vein 130
- Parotid region 129 134
 - lymph glands 131
- Parotidectomy 132 134
- Pars flaccida 108
- Pars intermedia 654
- Patches of Peyer 457
- Patella 804 823 825 827 838 841 845 847 849 850
 - 847 850 853 862 864
- Patellar plexus 804
- Pecten 480 482
- Pectinate muscles 339 340
- Pectineal ligament 548
- Pectineus muscle 401 550 554 555 796 797 799 800 808 809 811 813 818 825 826 831
- Pectoral fascia 275 280
- Pectoral lymph glands 369
- Pectoral nerve 673 677
- Pectoral region 669 679
- Pectoralis major muscle 243 249 263 264 271 272 274 281 283 286 351 367 669 671 673 676 678 680 688 690 694 69 697 00 10 71
- Pectoralis minor muscle 278 280 283 286 669 676 678 680 694 700 704
- Pectoralis minor artery 677
- Pedicle splenic 529 530
- Peduncles cerebral 36 38 41

- [illegible]

- Phrenic nerve 185 187 190 193
207 244 248 251 253 250 287
290 293 305 307 314 315, 318
322 323 325 338 353
avulsion of 188 189
Phrenic vein 406 441
Phrenocostal sinus 305
Pia mater 4 37 39 42, 59 60, 87
908 910
Pick 405
Picque 553
Pierson 4 3
Piles *See* Hemorrhoids
Pineal body 33 35 38
Pineal gland *See* Pineal body
Piriformis muscle 478 479 554
556 559 561 613 614 791 794
796 800 803 824 830 831
Piriformis sinus 209 227 231 238
239
Pirogoff amputation of ankle 8/9
Pisiform bone 724 748 750 752
754 772
articulation 754
joint 754
Pit olfactory 119 120
Pituitary body *See* Hypophysis
Pituitary 57
Placenta 415 507
Plantar artery 870 874 878 882
883 886 887
Plantar ligament 882 884 888 893
895 897
Plantar nerve 870 878 881 883
885 887 889
Plantaris muscle 825 835 836 840
841 859 861 871
Plate(s) alveolar 152
cribriform of ethmoid bone 21
23
orbital 20
pterygoid 12 19
Platysma muscle 67 120 123 124
126 142 148 170 173 174 176
180 183 188 198 199 203 213
225 243 244 247
Pleura(e) 294 302 330 441
cavity 294 302 324 441
cervical (cupola) 294 295
costal 294 295 324
diaphragmatic 294 295 308
fissures 296
hilar 315
lesions 304
mediastinal 294 295 314 316
325 327
parietal 294 295 327
pericardial 309
pulmonary 324
puncture by broken rib 298
surface markings 295 297
visceral 294 295
Pleural effusion 298
Pleural reflection *See* Reflection
pleural
Pleurisy 304
Plexus aortic 593 612, 644
basilar 37
brachial *See* Brachial plexus
cardiac superficial 344
carotid external, 197
cavernous 89
celiac 69 420 433 453 459 494
496 497
cervical 184 185 911 912
choroid 33 44
coccygeal 614 911 912
esophageal nervous 68 70
venous 420 421
of Frankenhauser 612
goose's foot 66 124 130 132
hemorrhoidal 487
hepatic 70
hypogastric 495 497 569, 597
612 618 627
lumbar 311 911 912
mesenteric 453 483 495 497
mesenteric 434
ovarian 592
pampiniform venous 606 607
609 641 643 645
patellar 804
pelvic 495 496 612
perivesical 568
pes anserinus 66 124 130 132
pharyngeal 152 154 164 165
231
prostatic venous 565 576 577
605 606 636
pterygoid *See* Pterygoid plexus
pubdental venous 576 604 608
658
pulmonary 68 70 320 422 432
rectal 495 606
renal 69 593 597 612 644
sacral 497 561 612 614 791 911
912
solar *See* Celiac plexus
splanchnic 69
subareolar of Sappey 219 280
submucous 434
suboccipital 54
subpectoral 281
subsartorial 822
testicular 597
tympanic 68
uterine 592 606
uterovaginal 595 606 608
vaginal venous 605 606
vesical venous 497 564 565 595
606 608 630
vesicoprostatic 568 575
Plica(e) circulares 456 457
colliculi 577
semilunaris 72 74
triangularis 162
Pneumatization 112
Pneumogastric nerve *See* Vagus
nerve
Pneumectomy 313 316
Pneumonia postoperative suscep-
tibility to 257
Point critical of Sudcock 486
of Erb 678
of McBurney 469
Pole(s) of kidney 406 407
occipital 35
Poltzer method for inflation of
middle ear 114
Polymastia 274 276
Polyp nasal 92 94 96
Polythelia 274 276
Pomum Adams *See* Prominence
laryngeal
Pons 914 915
variolu 24 33 36 38 39 47
Popliteal artery 815 818 820 821
831 833 836 838 840 853 860
861 864
Popliteal ligament 832 840 843
Popliteal nerves 835 837
external *See* Peroneal nerve com-
mon
internal *See* Tibial nerve
lateral *See* Peroneal nerve com-
mon
medial *See* Tibial nerve
Popliteal region 835 838
Popliteal vein 818 820 821 831
833 836 837 840 853
Popliteus muscle 835 836 843 853
859 861 863 865
Porta hepatis 434 436 507 511
521 541
See also Fissure transverse of
liver
Portal vein 415 420 421 427 429
430 434 449 451 457 459 487
490 504 505 507 509 511 515
517 519 521 522 524 531 535
536 538 539
Postauricular lymph glands 6 7
Posterior ligament of ankle joint
871
of elbow 710 714
Posterior vein left ventricle 336
Pott's 353
Pott's fracture 819 880
Pouca of Douglas 576 586 588
662 663
of Hartmann 518 520 525 526
hepatorenal 507
Morison's 507
perineal deep 627 629 634
superficial 629 631 652
Rathke's 57
recto uterine of Douglas 576
586 588 662 663
rectovesical 564 571
utero vesical 585 587
visceral of neck 169 170
Poupart ligament of *See* Ligament
inguinal
Praeortic lymph glands 429 434
454 494 495 608 609
Praeauricular lymph glands 6 7 107
Precuneus 33 35
Pregnancy ectopic ruptured 664

- Rectum (Continued)**
 surgery of 471 475
 excision 611
 hemorrhoidectomy 491
 ischioanal abscess and fistula 491
 resection 492 493
 veins, 481 485 487 490
Rectus abdominis muscle 63 65
 2 85 286 364 366 373, 3 5
 3 6 3 4, 38* 188 194 554 555
 5 0 5 9
Rectus capitis muscle 185 187
Rectus femoris muscle 547 554
 15 9 800 0 803 811 813
 818 819 822 823 826 831 833
 840
Rectus gyms, 35
Rectus oculi muscle 61 64 65 6
 83 86 89
Rectus sheath 2 284 36 311
 3 3 375 3 6 385 394 513
 parts of 169 3 0
Recurrent artery of eyeball 8
 interosseous posterior 05
 radial 05
 ulnar 05
Recurrent nerve 140 190 306
Reflection(s) capsular of hum-
 erus 09
 pleural c. todiaaphragmatic line
 216 97 309
 costomediastinal line 295
 mediastinal line 307
 sternal 294 295
 vertebral 294 295
Region(s) of abdominal wall's
 anterior 363 364
 adductor of thigh 816
 axillary 669 6 9
 brachial 696 113
 deltoid *See* Deltoid region
 dorsal of hand 759 4 116
 elbow *See* Elbow region
 epigastric 212 363 364 425
 frontal 6 7 121 126
 gluteal *See* Gluteal region
 hypochondriac 363 364 425 426
 hypogastric 363 364
 iliac 363 364
 ilio-costal of abdominal wall's, 397
 412
 infrahyoid 169
 infratemporal and temporal 134
 141
 inguinal *See* Inguinal region of
 abdominal wall's anterior
 inguinofemoral 808 811
 lip 143 147
 lumbar 363 364 397 412
 of mouth 143 160
 of neck anterolateral 181 249
 obturator 816
 occipital 6 7 184 245
 olecranon 720 721
 palmar *See* Palmar region
- Region(s) (Continued)**
 parietal 6 7
 parotid 1 9 134
 pectoral 669 6 9
 pelvesfemoral 189
 popliteal 835 838
 retro orbital 82
 sacrococcygeal *See* Sacrococ-
 cygeal region
 sacro iliac 557 553
 scapular *See* Scapular region
 sulcus 146 147
 submandibular 185
 submaxillary abscess 152
 supraclavicular 185
 temporal *See* Temporal region
 thoracocervical 250
 umbilical *See* Umbilical region
 urgenital 649 655
Reich 664
Reichert cartilage of 1 0
Reid 7
 base line of 28 29
Reil 1 land of *See* Brain lobes,
 central
Renal artery 405 407 591 598 605
Renal plexus 69 593 59 61 644
Renal vein 354 355 406 407 516
 517 593 607 644
Resection of colon abdominopar-
ineal (Miles) one stage 491
 499 502
 recto sigmoid Dixon's, 486
 sigmoid Dixon's, 486
 gastric 453
Rete testis, 641 642
Retina central vein 87
Retinacular ligament 835 836
Retinaculum(a) 799
 extensor inferior 854 857 863
 871
 superior 852 857 863 865 873
 flexor 860 863 871
 peroneal inferior 858 8 0 872
 873
 superior 865 8 0 8 3
Retro aortic lymph glands 603 609
Retro auricular glands, 107
Retrooduodenal artery 452 453
Retro orbital region 82
Retropontoneal veins, 490
Retropharyngeal lymph glands
 179
Retrosigmoid fossa 462
Retrolateral vein 13
Retzius space retropubic 564 567
 574 577 580 604 632
 veins of 490 407
Rhinitis acute with ethmoiditis
 105
Rhinorrhea cerebrospinal 23
Rhinotomy, 96
Rhomboideus muscles 246 247 359
 360 676 679 681
Rib(s) 257 262 294
 blood supply 261
- Rib(s) (Continued)**
 cartilages, 257 58 260-263 265
 267 294
 cervical 678
 sur cry for 247 248
 eleventh 407 408 611
 false 258 259
 first (superlative) 2 0 257
 61 264 294 95 304 319
 669 6 0 689
 floating 258 259
 fractures 97 298
 intervertebral disk 60
 ligaments interarticular 260
 marrow blood form-in 262
 resection 300-307 316-317 325
 second to sixth 669 611
 pical 260
 and plean relations, 531
 true 258
 twelfth 400 407 409, 403 410,
 411 473 515 519 616 618
 typical, 260
 veins, 61 62
Ribbon muscles of pharynx 210
 221
Ridge interureteric 566 568
 supracondylar 681 08 710 737
Rienhoff 313 517
Rima glottidis 236 238 240
Rin- abdominal external. *See* Ring
 inguinal superficial
 internal, 318
 femoral 38 812
 inguinal abdominal (deep) 389
 571
 external 393
 internal 387
 subcutaneous *See* Ring in
 inguinal superficial
 superficial 318 381 383 389
 513
 of uterus 583 584
 of trachea 1 0 740 243
 umbilical, 396
 Waldeyer's 158
Riolan avascular area of 474 481
 483
Risorius muscle 1 0 126 128 148
 181
Robillard 453 523
Rolando fissure of *See* Sulcus, cen-
 tral
Root(s) of brachial plexus 615
 616
 of clitoris 658
 of lung 295 312 313
 membrane of teeth 150
 of mesentery 455 457 472 481
 of neck 250 254
 olfactory 36
 penis 631
 of tongue 157 158
Rosenmuller fossa of 227 279
 lymph gland of 607
Rostrum 33 34

- Pudendum 649
 Pudic artery *See* Pudendal artery
 internal
 Pudic nerve *See* Pudendal nerve
 Pudic vein *See* Pudendal vein
 Pulmonary abcess 313
 Pulmonary artery 305 306 313
 315 320 322 324 331 335 336
 337 340 345 351 353 417 507
 Pulmonary infarct 313
 Pulmonary ligament 294 295 305
 306 313 329 441
 Pulmonary lymph glands 307
 Pulmonary orifice 341
 Pulmonary pleura 324
 Pulmonary plexus 68 70 320 422
 437
 Pulmonary segmental resection 316
 Pulmonary tuberculosis 316
 Pulmonary valve 348 352
 Pulmonary vein 305 306 307 313
 316 320 322 325 335 338 341
 342 417 507
 Pulmones *See* Lungs
 Pulp of teeth 151 152
 Pulse 151
 Pulvar 38
 Puncta lacrimalia 72 75
 Puncture cisternal 46 48 49
 lumbar 910
 ventricular 28
 Pyloric artery *See* Gastric artery
 right
 Pyloric vein 489
 Pylorus 325 425 427 431 442 444
 obstruction of 436 441
 resection 539
 sphincter of 427 434
 stenosis congenital 434
 Pyorrhea alveolaris 153
 Pyramid of tympanum 110
 Pyramidalis muscle 272 3 0 372
 376 555 510 571
 Quadrangular membrane of larynx
 233
 Quadratus femoris muscle 549 554
 614 796 800 803 816 821 830
 832
 Quadratus labii inferioris muscle
 See Depressor labii inferioris
 muscle
 Quadratus lumborum muscle 288
 391 398 400 403 407 410 473
 554 618
 Quadratus plantae muscle 878
 Quadriceps extensor muscle 841
 Quadriceps femoris muscle 794 796
 800 803 811 813 816 819 821
 822 830 832 845 846 850 864
 Radial artery 105 716 720 721
 724 726 728 729 731 734
 737 749 752 763 769 770
 carpal branch 728 753
 collateral 697 699 716
 Radial artery (*Continued*)
 indica 763 69 770
 ligation 731 738 747
 palmar branch superficial 728
 recurrent 105 715 716 728
 superficial branch 753
 Radial extensor muscle long of
 wrist 697
 Radial nerve 675 678 688 697
 699 705 708 709 711 713 715
 717 720 725 726 728 729 732
 733 736 738 747 751
 deep branch 717 718 724 733
 742 743
 digital branch dorsal 774
 exposure of 731
 paralysis 249
 superficial branch 724 729 750
 761 774
 surgery of 701 702
 terminal part 760
 Radial vein 724
 Radiations optic 59 60
 Radiocarpal joint 753 754
 adduction 753
 adduction 754
 arteries 753
 articulation 754
 capsule 757
 circumduction 753
 deviation radial 753 754
 ulnar 754
 disk articular 754
 extension 753
 flexion 753
 nerves 753
 Radiohumeral joint 739
 Radio ulnar joint 739 741 742
 inferior (distal) 741 747
 disk articular 742
 dislocation 757
 ligament capsular 742
 membrane synovial 742
 movements pronation 742
 rotation 742
 supination 742
 recess sacciform 741 742
 superior (proximal) 714 741 742
 Radius 714 716 722 724 726 739
 741 745 749 754 756 757 772
 distal fourth exposure of 742
 44
 epiphysis distal 754
 fracture above and below inser-
 tion of pronator teres 745 746
 head 709 721 722 729 741 742
 and neck fracture 746
 and humerus epiphyseal line 714
 ligament annular 714 715
 metaphysis 739 740
 neck 739
 and head fracture 746
 process styloid 758
 shaft 739
 exposure of 742 743
 styloid process 760
 Radius (*Continued*)
 surfaces 740
 urgency of 742 747
 tubercle dorsal of Lister 740
 tuberosity 739
 and ulna fractures 745 746
 Rami communicantes 359 360 497
 569
 Ramus (i) ischiopubic 629 631 635
 of ischium 627
 of mandible 129 134 137 161
 163
 primary of spinal nerves 789 790
 of pubis 627 639
 Ranula 148
 Raphe anococcygeal 557
 median of hard palate 153
 of pharynx 224 225 227 231
 of tongue 160
 palpebral lateral 127
 perineal 627 631 639
 pterygomandibular 129
 Rathke's pouch 57
 Recess costodiaphragmatic 294
 295 307
 costophrenic 292
 epitympanic 109 112
 ileocecal 469
 intersigmoid 474 477
 pharyngeal 171 227 229
 pheno ethmoidal 104
 piriform 227 231 238
 retrocecal 466
 saciform 754
 spheno ethmoid 91 93 104
 See also Fossa
 Recessus ellipticus 117
 Recessus sacciformis 742
 Recessus sphaericus 117
 Rectal artery *See* Hemorrhoidal
 artery
 Rectal ligament lateral 603
 Rectal plexus 495 606
 Rectal vein 606 609
 Rectocele repair 664
 Rectococcygeus muscle 559
 Rectosigmoid colon 497
 carcinoma of 497
 Recto urethralis muscle 577 604
 Rectum 414 435 467 465 472
 475 47 480 497 499 501 558
 562 564 565 570 572 576 579
 586 589 590 598 601 604
 603 608 613 619 623 627
 628 632 638 659 661 662
 ampulla 479 484 560 599
 arteries 4 9 481 483 487 540
 603
 carcinoma 482 492 493
 curves 479
 embryology 394
 fistulas 479
 ligaments suspensory 479
 lumen 479
 lymphatics 494 495 609
 nerves 612

- Rectum (Continued)**
 surgery of 441 443
 extension, 613
 hemorrhoidectomy 471
 ischioanal pouches and fistula, 471
 resection 471 475
 stricture 441 455 457 460
Rectus abdominis muscle 33 65
 2 85 46 364 367 3 3 3 4
 3 6 1 4, 342 355 358, 444 553
 5 0 5 9
Rectus capitis muscle 185 187
Rectus femoris muscle 447 544
 15 1 300-02 805 811 813
 818, 819 82 821 826 831 833
 840
Rectus gyris 33
Rectus oculi muscle 61 63 65 6
 83 1 07
Rectus sheath 2 2 54 36 3 1
 3 3 3 5 3 6 385 3 4 533
 parts of 163 3 0
Recurrent artery of eyeball 8
 inferior, posterior 05
 radial 05
 ulnar 05
Recurrent nerve 140 140 106
Reflection(s) carpal of humerus 109
 pleural, costodiaphragmatic line
 2 6-9 309
 costomediastinal line 75
 mediastinal line 30
 sternal, 94 95
 vertebral, 94 95
Region(s) of abdominal wall
 anterior 363 364
 adductor of thigh 816
 axillary 679 6 9
 brachial 646-13
 deltoid See Deltoid region
 dorsal, of hand 59 4-6
 elbow See Elbow region
 epigastric 2 2 363 364 475
 frontal 6 7 121 1 6
 gluteal See Gluteal region
 hypochondriac 363 364 425 4 6
 hypogastric, 363 364
 iliac, 363 364
 ilioacostal of abdominal wall, 391
 412
 infrahyoid 169
 infratemporal and temporal, 134
 141
 inguinal. See Inguinal region of
 abdominal wall anterior
 inguinofemoral, 808-811
 lip, 143 147
 lumbar 363 364 39 412
 of mouth 143 160
 of neck, anterolateral 181 249
 obturator 816
 occipital 6 7 184 245
 olecranon 7 0-721
 palmar See Palmar region
- Region(s) (Continued)**
 parietal 6 1
 parietal 1 2 134
 pectoral 657 6 9
 pectoral 59
 popliteal 835 838
 retro-orbital 8
 sacro-cervical See Sacrococ-
 cygeal region
 sacro iliac 552 553
 scapular See Scapular region
 sublingual 146 14
 submandibular 185
 submaxillary abscess 15
 supraclavicular 183
 temporal See Temporal region
 thoracocervical 59
 umbilical See Umbilical region
 urogenital, 647 655
Reich 664
Reichert cartilage of 1 0
Reid, "
 base line of 8, 9
Reil, island of See Brain lobes,
 central
Renal artery 405-40 59 593 605
Renal plexus 67 593 5, 61 644
Renal vein 354 355 406 40 516
 51 593 60 644
**Resection, of colon, abdominoperi-
 teal (Miles) one take** 424
 47 502
 recto-uterine Dixon's, 486
 sigmoid, Dixon's, 486
 gastric 453
Rete testis 641 64
Retina central vein 87
Retinacular ligament 835 836
Retinaculum(a) 99
 extensor inferior 854 85 863
 8 1
 superior 832 857 863 865 8 3
 flexor 560, 563 8 1
 peroneal, inferior 833 8 0, 8 7
 8 3
 superior 863 8 0-8 3
Retro-aortic lymph glands 603 609
Retro-auricular gland 10
Retrooduodenal artery 42 453
Retro-orbital region 8
Retropontal veins 470
Retropharyngeal lymph glands,
 1 9
Retro-igmoal fossa 467
Retrotarsal vein 3
Retzius space retropubic 564 567
 5 4 577 580 604 632
 veins of 450 507
Rhinitis acute with ethmoiditis,
 105
Rhinorrhea cerebro-pinal 23
Rhinotomy 96
Rhomboideus muscles, 46 247 359
 360 6 6 6 9 631
Rib(s) 5 6 294
 blood supply 261
- Ris(s) (Continued)**
 carpal, 23 58 40-63 6
 6 24
 cervical, 6 8
 surgery for 4 48
 eleventh 407 408 611
 false 558-59
 first ("superlative") 0, 23
 61 64 4 5 104 317
 67 6 0, 637
 float 55, 59
 fractures, 75 73
 in vertebral axis 60
 ligaments, interarticular 60
 marrow blood formation
 resection, 300-30 316-317 3 5
 second to sixth 669 6 1
 penial, 60
 and s, ven, relations, 531
 true 53
 twelfth, 400-402 40 403 410,
 411 4 3 515 577 616 618
 typical, 60
 veins, 61 6
Ribbon muscles, of pharynx 710,
 1
Ranz interarteric, 66 663
 supracondylar 631 63-10, 1
Rienhoff 313 14
Rima glottidis 36 33, 40
Rinz abdominal, external See Rinz
 internal, superficial
 internal, 373
 femoral 38 312
 inguinal, abdominal (deep) 387
 571
 external, 393
 internal, 357
 umbilicous See Ring in-
 guinal, superficial
 superficial, 3 3 351 383 389
 5 1
 of uterus 83 54
 of trachea, 1 0 40, 243
 umbilical, 5 6
 Waldeyer's 153
Riolan avascular area of 4 4 431
 433
Risorius muscle 1 0, 1 6 1 3, 145
 181
Robillard 433 3 3
Rolando fissure of See Sulcus, cen-
 tral
Root(s) of brachial plexus, 6
 6, 6
 of clitoris 6, 8
 of lung, 29 312 313
 membrane, of teeth 1 0
 of mesentery 433 4 4 4 431
 of neck, 230-234
 olfactory 36
 penis, 631
 of tongue 15 1 3
Rosenmuller fossa of 1 9
 lymph gland of 60
Rostrum, 33 34

- Rotation of hip joint 800 822, 876
 of knee joint 822 844, 848
 of radio ulnar joints 742
 of shoulder joint 690
 of thigh 818
 of thumb 714
- Rotatores muscle 399 402
- Round ligament(s) of liver 607
 of uterus 581 587 590 609 619
 624 639 661 663
- Rousselot 489
- Roux 577
- Rugae palatine 153
- Run around on finger 784
- Sac hernial 383 394
 lacrimal 72 75 83 127 138 139
 pericardial 330 331 333
 peritoneal 474 448 449
- Saccule 67 116 118
- Saccus endolymphaticus 116 117
- Sacral anesthesia 557 553
- Sacral artery lateral 478 484 567
 600 601
 middle 478 481 484 487 610
 621
- Sacral lymph glands 482 577 591
- Sacral nerves 495 553 561 612
 789 912 916
- Sacral plexus 497 561 612 614 791
 911 91
- Sacral vein middle 478 481 509
 606 607
- Sacralization of fifth lumbar vertebrae 908
- Sacrocccygeal ligament 553 557
 559 916
- Sacrocccygeal region 551 553
 canal 553
 median crest 551
 skin over 553
 spinous tubercles 551
- Sacro iliac articulation 553
- Sacro iliac joint 548 553
- Sacro iliac ligament 552 554
- Sacro iliac region 552 553
 articular cave 557
- Sacro iliac strain 557
- Sacro pinalis muscle (erector spinae) 369 397 399 401 404
 408 410 554 618
- Sacro pinous ligament 548 550
 552 553 55 633 789 794
- Sacro tuberosus ligament 548 555
 557 627 629 658 789 791 826
- Sacrum 497 01 548 553 557 564
 570 600 790 903 904 906 907
 ala 548 907
 apex 552
 body 548
 canal 551 553
 cornua 551 553
 foramina 552
 hiatus 551 553
 parts lateral 552
 promontory 548 553, 907
- Sacrum (*Continued*)
 ridges transverse 552
 surfaces 552
- Sagittal sinus inferior 37 39 48
 53 54
 superior 11 37 39 41 48 50
 52 54 57
- Salivary glands 123 179 137 176
- parotid *See* Parotid gland
- sublingual 65 140 146 148 152
 160 227
- submaxillary 65 129 130 148
 176 226 227
- excision 1 8
- Salpingectomy 622 623
- Salpingo oophorectomy 622 623
- Salpingopharyngeus muscle 228
- Santorini accessory pancreatic duct
 of 534 537
- cartilages of 235 239
- tubercle of 227
- Saphenous artery 833
- Saphenous nerve 805 807 811 813
 822 833 834 852 854 856 866
 871 872
- Saphenous vein 796 879
 anterior 806 807
 great 805 853 856 866 881
 internal 805 808 849 850
 long 365 379 806 809 811 833
 871 8
- posterior 806 807
- short 856 871
- mall 820 835 837 853 881
- Sappey subareolar plexus 279 280
- Sartorius muscle 554 796 797 800
 807 805 808 809 811 813 815
 817 819 822 826 831 834 840
 845 847 849 850 863 864
- Scala tympani 106 115 117
- Scala vestibuli 106 115 116
- Scalenus muscle, anterior 178 179
 185 187 190 195 207 244
 246 248 250 251 753 261
 304 357 676 689
- injection of procaine 247
- tenotomy of 247
- medium 178 185 187 190 244
 246 251 253 261 673 676
- posterior 178 187 246 251 261
 676
- Scalenus syndrome surgery for 247
 248
- Scalp 3 8 37
 arteries 5 6 130
 circoid aneurysm 7 8
 dangerous area 4
 lymphatics 6 7 131
 muscles 3 4 122
 nerves 6 7 121
 surgery of 7 8
 tissue layer of 3 5
 veins 6
- Scaphoid bone *See* Navicular bone
- Scapula 177 192 245 258 259 325
 669 670 672 679 682 684
- Scapula (*Continued*)
 angles 400 441 680 681
 borders 679 680
 coracoid process 669 670
 ligament transverse superior 686
 neck 694
 processes 681 682
 acromion 687
 coracoid 680 682 684
 spine 681 683 685, 691 692
 surfaces 681
 winging of 400
- Scapular anastomoses 689 690
- Scapular artery 246 675 677 679
 689 690
- Scapular nerve dorsal 676
- Scapular region 684 687
- Scapular vein transverse 245
- Scarpa fascia of 365 366 378 380
 388 393 628 630 652 804
 femoral triangle of 805 811
 foramen of 92
 triangle of 274
- Schlemm canal of 78 79 82 87
- Schwalbe hiatus of 559 560 659
- Sciatic nerve 478 514 658 792 794
 796 797 803 805 815 821 826
 830 833 850
- Scrotal artery 602
- Scrotum 581 630 639 641 643
 fascia superficial 639
 layers 640 641
 nerves 793 804
 septum 640 642
 skin 639 641
- Sebaceous glands of ear external
 107
 of eyelids 72 74
 of face 119
 of hand dorsal region 776
 of lips 143 144
 of labia majora 649
 meibomian *See* Tarsal glands
 of neck 181
 of penis 635
- Segment colic terminal 414
- Sella(ae) tuberculum 21 23
 turcica 20 21 23 45 51 55 57
 58 99
- Semilunar bone *See* Lunate bone
- Semilunar cartilage lateral 840
 842 846 850 863
 medial 839 840 842 844 863
- Semilunar ligament medial 850
- Semimembranosus muscle 554 805
 820 821 826 831 833 835 836
 840 843 845 847 849 850 860
 863 865
- Seminal vesicles 475 564 566 570
 574 576 579 599
 arteries 573 603
 lymphatics 573
 vein 573
- Semispinalis capitis muscle 244
- Semispinalis dorsalis muscle 399 402

[illegible]

- Small intestine (*Continued*)
 embryology 463 464
 ileum *See* Ileum
 jejunum *See* Jejunum
 length 444
 membrane mucous 456
 nerves 4-9 460
 surgery of 460 462
 anastomosis closed aseptic
 method 461 462
 open method 460 461
 enterotomy 462
 ileostomy 462
 jejunotomy 462
 Small vein of heart 336
 Smegma 63
 Smiling muscle *See* Zygomaticus
 major muscle
 Smith 23
 Smith Elliott 659
 Smith fracture of 747
 Smith J W 49
 Smith Peter en 5-3 802
 Smithwick 560
 Snail box anatomic 734 737 738
 49 769
 Snail parotid 130 132
 Solar plexus *See* Celiac plexus
 Soleus muscle 8-3 8 8 861 864
 866 8 6
 Space(s) of arm quadrangular
 698 699 707 708
 triangular 699 707
 axillary 758
 of Burn 175 176
 cricothyroid 241
 epidural 908 909
 extradural 52
 extrapontal 513
 of Fontana 79
 of foot 898 899
 of Gerota 403 405
 thenar 68 110 782 783
 infections 738 780 782
 web 63
 of hand closed distal 777 778
 commissural 163
 interosseous 778
 midpalmar 768 769 779 783
 infections 783 784
 palmar deep 759 760 767
 769
 retroflexor of Parona 66 769
 781
 subaponeurotic dorsal 775
 776
 treatment of infection
 738
 subcutaneous dorsal 773 777
 treatment of infections
 738
 subtendinous 777
 subungual 777 778
 infrapalmar 511 513
 infrapalmar 597
 nerves 797 794
 Space(s) (*Continued*)
 intercostal 266 267 269 278
 337 347 348 354
 arteries 269 271
 muscles 266 269
 veins 2 0 2/1
 intracranial 41 42 910
 extradural 3 41
 intracerebral 3 41 42
 subarachnoid 37 41 42
 subdural 37 41
 thoracic 559 560
 mandible body of 160 161
 surgery 160
 masticator 161
 muscular facial 160 161
 parotid 161 162
 pelvic 559 560
 perforated 38
 periosteal 513
 popliteal 83 836
 peritrectal 5 6
 prethyroid 1 4
 prevascular 564 567 570 604
 retro-esophageal 222
 retropharyngeal 222
 retroprostatic of Proust 5-6
 retropubic of Retzius 564 567
 574 577 580 586 604 632
 retrorectal 561
 subarachnoid 37 40 44 53 59
 60 909 910 912
 injection of lipiodol into 906
 subdural 52 912
 subphrenic of liver 511 515
 superficial in floor of mouth 162
 suprahepatic 512 513
 suprapubic 794
 suprasternal of Burns 178
 supratentorial 558 560 659
 temporal deep 161
 thyroid 1 4 178
 of Traube 426
 vascular visceral 160 162
 vertebrovaginal 595
 zonular of eyeball 77 79
 Spangaro's incision for exposure of
 heart 350 352
 Spasm of muscles 134
 reflex of facial muscles 121
 Spaulding 68
 Spence axillary tail of 274 276
 Spermatheca 379 406 500 599
 643
 Spermatheca cord 365 366 379 381
 388 392 393 371 637 638
 641 646 97 808 810
 arteries 643 644
 coats 642
 lymphatics 644
 peritoneal fatty areolar tissue
 643
 prostate vaginal peritonea 643
 veins 643 644
 Spermatheca nerve external 379
 Spermatheca vein 406 500 509
- Sphenoid bone 14 18 57 92 102
 104 142 155 228
 clinoid process 40
 fracture 92
 pterygoid plate 92
 wings 10 15 16 19 22 23 99
 134 136 137 140
 Sphenoid sinus 15 16 20 51 55
 56 58 90 93 97 99 102 104
 229
 drainage 104
 sinus 103
 surgery 104
 Sphenomandibular ligament 142
 Sphenopalatine artery 95 132 139
 Sphenopalatine nerve 11 62 92
 Sphenoparietal sinus 51 53 57 63
 Sphincter ani muscle external 4 8
 480 482-484 490 491 501 559
 560 59 86 614 627 629
 630 637 638 652 654 65
 657 659 661
 internal 480 482 638
 Sphincter muscle(s) of bladder
 urinary 567 569 577 578
 of cloaca 627
 of iris 88
 of pupil 61 60 89
 of pylorus 427 434
 urethrae membranacea 554 555
 632 638 639 656 658
 Sphincter vaginae 656
 Sphincter vesicae 632
 Spina bifida 43
 Spinal anesthesia 915 916
 Spinal artery 47
 Spinal canal *See* Canal, vertebral
 Spinal column *See* Column, ver-
 tebral
 Spinal cord 38 39 908 915
 columns (funiculi) white an-
 terior 912 915
 lateral 912 913
 posterior 912 914
 commissure gray 912 913
 white 913
 embryology 910
 fissure anteromedian 912
 ganglia 912 914
 horns 912
 matter gray 912
 white 912
 meninges 910
 nerves fibers 913 914
 rami 912
 roots 912
 plexus 911 912
 septum anteromedian 912
 tracts (fasciculi) 912 915
 Spinal nerve(s) 269 271 273 912
 915
 arrangement of 271 273
 ganglion 269 272
 rami anterior and posterior 269
 272
 thoracic 359 360

- S**
S. alalis dorsal muscle 399 402
S. p. of hum 164 312 211 418
 41, 410 452 554 555 589
 601 603, 819 8 1 827 916
 of *hum* 4 8 350, 557 584
 5 2 67 91 94
 muscles of 555
 nasal 14 17
Spirous process 4 9 404 408
Spiral canal 67
Spiracle Vincent's, a piration of
 with foreign body or 11 3 316
Splachnic nerves 9 07 319
 4 0 413 413 434 435 497 569
 614 6
Splanchnic plexus 69
Solen 3, 4 4 444 4 2 109
 416 5 9 533 536 541
arteria, 531
 embryolgy 5 9
 pedicle 5 9 410
 puncture by broken rib 98
 surfaces 530
 surgery of 5 0 3 2 315 531 513
 veins, 531
S. rectoria, 531 533
Splenic artery 4 1 414 4 9 4 9
 432 423 4 9 513 440-541
Splenic lymph glands, 431
Splenic vein 4 1 4 9 430 459 458
 487 511 516 531 536 537 596
Splernum 31 34 38
Splenius capitis muscle 43 246
Splenomegaly 487 531
Spurs, of phalanx of foot 872
Squama temporalis 19
Squamous epithelium of tonsils
 163
 visceral arches of embryo 169
 171
Stall(s) hepatic 438
 rectal 4 9 561 603
Stapedius muscle 65 110-111 122
Stapes, 106 109 111 115 116 1 0
 ligaments 110 111
Staphylococci hy 147
Status, coeli, 412
Status lymphaticus, 2 0
Steno is, pulmonary 353
 pyloric congenital 434
Stensen foramen of 12
Sternoclavicular joint 171 250
 264 266 295 344 350
 articular disk 164
 dislocation 266
 ligaments 264 266
 sternocostal articulations 264
Sternoclavicular ligament 266
Sternocleidomastoid artery 195 06
Sternocleidomastoid muscle 5 10
 71 131 132 147 172 186 188
 195 198 203 210 213 215 222
 223 243 244 248 263 264 294
 524 604 605
Sternocostal joints, 67
Sternocostalis muscle 266 267 330
Sternohyoid muscle 71 1 4 177
 185 180 192 193 199 06 211
 211 215 223 233 236 241 253
 61 65 69 318 350
Sternomanubrial joint 164
Sternopericardial ligaments 330
Sternothyroid muscle 71 173 174
 185 186 180-192 193 206 03
 212 13 215 223 233 234 236
 235 53 63 65 169 318 350
Sternum 173 175 219 257 260
 62 267, 294 295 307 330 332
 333 348 349 352 669 672
 articular relations, 65
 body 62 263
 cartilaginous plates, embryonic,
 62 63
 embryology 262 63
fractures 265
 muscles 64 65
 notches) clavicular 62 263
 65
 costal 63
 supra sternal (jugular) 62
 63 65 266
 xiphoid process. See Xiphoid
 process
Sternebrae 62 163
Stitch mesenteric Maunsell 461
Stomach 111 292 327 414 422
 444 449 452 412 105 109
 513 519 530 533 537
 arteries 4 8, 419 540 541
 attachments 434-436
 bed 426
 body of 4 6 427
 carcinoma of 396 441 443
 cardia 211 419 424 426
 cardiac end surgery of incision
 Kocher's subcostal, 310, 372
 375
 coats, 434
 curvatures, 221 425-427 437
 438 440 442 444 536
 collar area 441 444
 embryology 418 422-424
 fundus, 425 427
 lymphatics 431 432
 muscles 434
 nerves 68 69 412 434
 pylorus See Pylorus
 subdivisions 426
 surface 426
 surgery of 436 444
 carcinoma of cardiac end and
 of lower third of esophagus,
 441 443
 closure of perforated peptic ul-
 cer 441-442 444
 gastrectomy 438 440
 gastrojejunostomy 436-438
 transabdominal vagus nerve
 section 441 442
 vagotomy 441 442
 veins 429 431
Stomodeum 55 57 119 120
Strabismus 61 65 89
Straight line 37 40 48, 53 54
Strid 4 0
Sty 72 73
Styloglossus muscle 13 140 151
 158 163 164 112 225
Styloglossal ligament 13 110 225
 230 231
Stylohyoid muscle 13 65 122 131
 157 159 111, 172 116 226 227
Styloid process 12 19 110 130
 131 141 142 157 1 0 195 756
 of radius, 758 160
 of ulna 758
Stylomandibular ligament 13 130,
 141 142 2 6
Stylopharyngeus muscle 13 155
 163 1 0 111 184 179 226 227
 230-231 236
Subarachnoid anesthesia 915 916
"Subastragaloid" joint 892
Subcervical glands, 5 5
Subclavian artery 1 9 187 190,
 01 05 06 218 11 238
 247 248, 210-754 61 2 0 218
 304 306 307 309 317 323
 327 331 316 346 353 616
 611 619 689 610
 left 344-446 418, 420
 mammary 250 251
 postscalene portion 250-252
 prescalene portion 250 251
 retroscalene portion 250 251
 thyrocervical trunk, 250 251
 vertebral branch 250 251
Subclavian nerve 6 6
Subclavian vein 48, 183 190 197
 198 05 07 245 251 253 61
 265 2 0 304 306 319 322 323
 346 347 356 358 672 716
Subclavius muscle 669 611 673
 6 6 617 694 00
Subconjunctival vein 73
Subcostal artery 2 0 34 413
Subcostal muscle 67 269 212
Subcostal nerve 212 292 407 473
 806
Subcostal veins, 354 355 404
Sublingual artery 148 164
Sublingual gland, lymph 336 607
 609 635
 salivary 65 146-148 152 160
 227
Sublingual nerve 147
Sublingual region 146 147
Sublingual vein, 148
Submandibular glands, lymph 159
 160 180
 salivary 142
Submandibular region 185
Submaxillary glands lymph 6 7
 144 147 180
 excision 147
 salivary 65 129, 130 145 1 6
 226 227
 excision 178

Small intestine (Continued)

- embryology 463 464
- ileum *See* Ileum
- jejunum *See* Jejunum
- length 444
- membrane mucous 456
- nerves 459 460
- surgery of 460 462
 - anastomosis closed aseptic method 461 462
 - open method 460 461
- enterostomy 462
- ileostomy 462
- jejunostomy 462
- Small vein of heart 336
- Smeyma 635
- Smiling muscle *See* Zygomaticus major muscle
- Smith 353
- Smith J Holt 639
- Smith fracture of 747
- Smith J W 479
- Smith Petersen 553, 802
- Smithwick 560
- Snuff box anatomic 734 737 738, 741 752 769
- Socia parotiditis 130 132
- Solar plexus *See* Celiac plexus
- Soleus muscle 853 858 861 864 866 876
- Space(s) of arm quadrangular 698 699 702 708
 - triangular 639 702
- axillary 258
- of Burns 174 176
- cricothyroid 241
- epidural 908 909
- extradural 52
- extraperitoneal 513
- of Fontana 79
- of foot 838 899
- of Gerota 403 405
 - thoracic 768 770 782 783
 - infections 738 780 782
 - vein 763
- of hand closed distal 777 778
- commisural 763
- intrascapular 778
- midpalmar 768 769 779 783
 - infections 783 784
- palmar deep 759 760 767 769
- retroflexor of Larsona 766 769 781
- subaponeurotic dorsal 775 776
 - treatment of infections 738
- subcutaneous dorsal 775 777
 - treatment of infections 738
- subtendinous 777
- subtubular 777 778
- infrapalmar 511 513
- infrapitiformis 792
- nerves 792 794

Space(s) (Continued)

- intercostal 266 267 269, 278, 337 347 348 354
 - arteries 269 271
 - muscles 266 269
 - veins 270 271
- intraorbital 41 42 910
 - extradural 37 41
 - intraorbital 37 41 42
 - subarachnoid 37 41 42
 - subdural, 37 41
- ischiofemoral 559 560
- mandible body of 160, 161
 - surgery 160
- masseter 161
- muscular fascial 160 161
- parotid, 161 162
- palmar 559 560
- perforated 38
- pericardiac 513
- popliteal 835 836
- prepectal 576
- prethyroid 174
- prevascular 564 567 570, 604
- retro esophageal 222
- retropharyngeal 222
- retroprostatic of Proust 576
- retropubic of Retzius 564 567 574 577 580 586 604, 612
- retrorectal 561
- subarachnoid 37 40 44 53 59, 60 909 910 912
 - injection of lipiodol into 906
- subdural 52 912
 - sulphuric of liver 511 515
 - superficial in floor of mouth 162
 - suprathalpic 512 513
 - suprapitiformis 794
 - suprasternal of Burns 178
 - supratraguminal 558 560 659
 - temporal deep 161
 - thyroid 174 178
 - of Truibe 426
 - vascular cleaved 160 162
 - vesicovaginal 525
 - zonular of eyeball 77 79
- Spiracle & incision for exposure of heart 350 352
- Spiracle of muscles 134
- reflex of facial muscles 121
- Sprauling 768
- Spence axillary tail of 274 276
- Spermatic artery 379 406 500 599 643
- Spermatic cord 365 366 379 381 388 392 493 571 637 638 641 646 797 808 810
 - arteries 643 644
 - coats 642
 - lymphatics 644
 - peritoneal fatty articular tissue 643
 - processus vaginalis peritonei 643
 - veins 641 644
- Spermatic nerve external 379
- Spermatic vein 406 500 509

- Sphenoid bone 14 18 57 92 102 104 147 151, 228
 - clinoid process 40
 - fracture, 92
 - pterygoid plate 92
 - wings 10 13 16 19 22 23, 99 134 136, 137, 140
- Sphenoid sinus 15 16 20, 51, 55 56 58 90 91 97 99, 107 101, 229
 - drainage 104
 - sinusitis 103
 - surgery 104
- Sphenomandibular ligament 142
- Sphenopalatine artery 95 138 139
- Sphenopalatine nerve 11 62, 92
- Sphenoparietal sinus 51 53 57, 63
- Sphincter ani muscle external 478 480 482 484 490 491 501 559 560, 579 586 614 627 629, 630 637 638 652 654, 655, 657 659 661
 - internal 480 482, 638
- Sphincter muscle(s) of bladder urinary 567 569, 577, 578
 - of clitoris 627
 - of iris 88
 - of pupil 61, 80 89
 - of pylorus 427 434
 - urethrae membranacea, 554, 555 632 638 639 656 658
- Sphincter vaginae 656
- Sphincter vesicae 632
- Spina bifida 43
- Spinal anesthesia 915 916
- Spinal artery 47
- Spinal canal *See* Canal vertebral
- Spinal column *See* Column vertebral
- Spinal cord 38 39 908 915
 - columns (funiculi) white, anterior 912 913
 - lateral 912 913
 - posterior 912 914
 - commisure gray 912 913
 - white 913
 - embryology 910
 - fissure anteromedian 912
 - ganglia 912 913
 - horns 912
 - miter gray 912
 - white 912
 - measurments 910
 - nerves fibers 913 914
 - rami 912
 - roots 912
 - plexus 911 912
 - septum posteromedian 912
 - tracts (funiculi) 912 913
- Spinal nerve(s) 261 271 273 912 915
 - arrangement of 271 273
 - ganglion 261 272
 - rami anterior and posterior 261 272
 - thoracic 357 360

100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000

- Submaxillary region abscess 152
 Submental artery 194
 Submental glands lymph 144 145
 159 160 180
 abscess 180
 surgery of 147
 Submucous plexus 434
 Suboccipital plexus 54
 Subpectoral plexus 281
 Subpyloric lymph glands 431
 Subsartorial plexus 822
 Subscapular artery, 286 400 673
 674 677 679 689 690
 Subscapular vein 286
 Subscapularis muscle 249 283 285
 286 669 671 674 678 680 681
 686 692 694 699 700 702 708
 710
 Substance perforated 35 36
 Substantia gelatinosa of pinal
 cord 913
 Substantia nigra 33 35 38
 Subtrigonal glands 375
 Sudic critical point of 486
 Sulcus atrioventricular 347 349
 basilar 38
 bicipital 680 696 698 707 708
 710
 calcaneal 33 35 36 59 60
 central 30 32
 cerebral 30 33, 50
 cinguli 33 35
 circular 34
 collateral 35 36
 coronary 335
 frontal 31 32
 hippocampal 35
 horizontal 31 32
 intertubercular 683 707, 708 710
 interventricular 347
 intraparietal 32
 lateral 31 32 35, 36
 of tibia 863
 longitudinal 35 36 335
 occipital 32 33
 occipitotemporal, 35
 olfactory 35
 orbital 35 36
 parieto occipital 32 33 35 36
 postcalcaneal 59 60
 postcentral 32
 preauricular of ischium 549
 precentral 31 32
 retromalleolar 870
 rhinal 35 36
 sigmoid 115
 temporal 37 33
 terminalis atru dextru 339
 terminalis linguae 157 158
 See also Groove
 Supination of forearm 3 735
 753
 of hand 739 742
 Supinator muscle 249 678 710
 715 717 724 728 730 734 735
 742 743 745
 Supraclavicular nerve 182 185 244,
 245 247 669 670 682 698
 Supraclavicular region 185
 Supraclavicular veins 178
 Supraduodenal artery 452 453
 Suprahyoid muscle 147 236
 Supra orbital artery 5 7 86
 Supra orbital nerve 5 7, 62, 63 85
 86 120
 Supra orbital vein 6 7 51 120
 Suprapancreatic lymph nodes 420
 Suprarenal artery 325 406
 Suprarenal glands 403 406 407,
 412 536
 Suprarenal vein 325 406
 Suprascapular artery 188 246 248
 251 253 689 690 702
 Suprascapular ligament, 192, 679
 Suprascapular nerve 249 676 679
 684 690
 Suprascapular vein 183 197, 252
 Supraspinatus muscle 249 676 678
 680 683 688 690 692 694 701
 708 710 712
 Supra pinous ligament 907
 Supratrochlear artery 5 86 715 718
 Supratrochlear nerve 5 6 63 85
 86 121
 Supratrochlear vein 6 120
 Supra umbilical lymph vessels 368
 369
 Sural nerve 820 836 837 856 857
 871
 Surface sternocostal 350
 Surgery See individual parts of
 body
 Suspensory ligament of axilla 669
 670 672
 of clitoris 653 654
 of eyeball 79 80 82
 of Lockwood 84
 of ovary See Infundibulopelvic
 ligament
 of penis 635 636
 Sustenaculum tali 875 876 881 890
 Suture coronal 10 11 15, 20 51
 137
 internasal 94
 lambdoid 9 10 20 22 40 44 51
 metopic 9
 occipitomastoid 22
 palatine 155
 sagittal 9 11 22
 Sweat glands eyelids 72 74
 of face 119
 of hand 759
 Sweet 325 441
 Sylvius aqueduct of 33 35 38 42
 44
 fissure of See Sulcus cerebral
 lateral
 Sympathectomy thoracic 359 360
 Sympathetic nerves 193 195 207
 250 292 324 359 360 433
 434 478 479 511
 of colon 494 495 497
 Symphysis menti 17
 Symphysis pubis 363 364 366 475
 558 559 565, 571 576 579
 586 589, 604 627 635 653
 fibrocartilage 550
 ligaments 550
 Syndrome of Banti 489
 of Naffziger 247
 radicular middle 678 679
 scalenus surgery for 247 248
 Synchia 80
 Synovial membrane 14 683 687
 689 753 793 795 796 798
 799 839 841 843 845 847, 850
 of joints ankle 877
 elbow 714 715, 717
 knee 834
 metacarpal, 755
 pisiform 754
 radiocarpal 753
 radio ulnar 742
 shoulder 683 687 689 696
 Symes amputation through ankle
 joint 879
 La Tabatiere anatomique of Clo
 quet 734 737 738
 Taenia coli of cecum 463 464
 467
 Tahpes 899
 Talocalcaneal joint 882 883 885
 Talocalcaneonavicular joint 892
 893 895
 Talocalcaneous ligament 875 878
 882
 interosseous 892 895
 Talofibular ligament 865 875 878
 Talonavicular ligament 875
 Talus 869 875 876 878 882 889
 890 892 897
 Tamponade with heart wounds,
 352
 Tapetum 34
 Tarsal gland 72 73
 Tarsal ligament 73
 Tarsometatarsal joint 881 893 894
 Tarsus 881
 Taste buds 158
 Taussig 353
 Taylor G Gordon 491
 Tear lake 72
 Tearing 16 96
 Teeth 17 150 153
 abscess 151 152
 arteries 99 137 138
 bicuspids 149 151
 canine 149 151
 canines 154
 cavity alveolar 150 152
 deciduous 150
 eye See Teeth canine
 fractures accompanying extrac
 tions 151
 incisors 149 151
 infected as cause of disease in
 maxillary sinus 99 101

- [illegible]

- Tenosynovitis suppurative 767
of thumb 766
- Tensor fasciae latae muscle 554
613 790 794 796, 797 800 802,
850
- Tensor palati muscle See Tensor
veli palatini muscle
- Tensor palati tendon 12
- Tensor tarsi muscle 126 127
- Tensor tympani muscle 62, 65 106
108 110 157
- Tensor veli palatini muscle 62 65
114 140 154 155 157 230 232
- Tentorium cerebelli 30 36 40 54
- Teres major muscle 249 281 286
669 671 674 678 680 681 683
685 689 690 695 697 699 701
703 705 708 710 712
- Teres minor muscle 676 677 681
683 685 692 698 703 708, 710
- Testicular artery 382, 473, 573, 596,
597 642 643 645
- Testicular plexus 597
- Testicular vein 382, 607, 642 643
645
- Testicle See Testis
- Testis 387 388 572, 581, 638 639
641 643
appendix 581
artery deferent 642
coverings 388
descent of 386 389
epididymis 571 581 641 643
gubernaculum 386 581
lymphatics 644
sinus 642
tubules 642
veins 642 643
- Tetanus 134
- Thalamus 36 914
optic 38
- Thebesius valve of 339, 340
- Theca 763
- Thenar muscles 678 764, 768
- Thigh 804 834
abductors 796
adduction 816 818
extension 818 819 827 826
fascia deep 807 808
lata 832 833
superficial 804
flexion 826 827
front 804 815
lymph gland 806 807
movements rotation 818
muscles 815 826
adductor group 816 818
anterior 825 826
extensor group 818 819 822
826
flexor group 826 827
movements 815
nerves cutaneous See Cutane-
ous nerves of thigh
surgery of 812 814 815
- Thoracic aorta descending 313
- Thoracic artery, 278 280 286, 673,
674 677 679 689, 690
- Thoracic cavity 250
- Thoracic duct 253, 254 280, 306,
322 325 347 356 358, 418
cysterna chyli 608 609
embryology 356 357
lymph trunks, 356 357
- Thoracic nerves 247 249 272, 284
286 292 359 364 366 370 384
385 404, 407, 670 672, 675 676
679 789
- Thoracic projection of heart and
great vessels 346 350
- Thoracic sympathectomy, 359 360
- Thoracic vein 280 286 367 368
- Thoracic vertebrae 356
- Thoracic abdominal nerves 272
- Thoraco acromial artery 278 279,
670 672 674 679
- Thoraco acromial vessels 283 285
- Thoracocervical region 250
- Thoracodorsal artery 675
- Thoracodorsal nerve 284 285, 400,
675 677
- Thoraco epigastric vein 367 368
- Thoracoplasty 301 302
- Thoracotomy 299 302
closed method 299 300
open method 300 302
- Thorax 257 360
aperture diaphragm of, 257, 258
inferior 257
superior 257 259
bony, 257 273
lines conventional longitudinal
257 258
shape 257 259
- Thrombectomy 829 832
- Thrombophlebitis of pterygoid
plexus 153 154
septic from middle ear infection
110
- Thrombosis of internal jugular vein
162
of sinus 54 55 57 105 119 153
154 162 203
of vena cava superior 353
- Thumb 759 773
abduction 735 774
in fracture of metacarpal 785
arteries of 769
bones metacarpal 755
dislocation 785
extension 735
fascia 761
flexion 774
metacarpal 777
fracture of 785
nerves 764
phalanges 776
rotation 774
tendon sheath fibrous, 764 766
tenosynovitis 766
- Thymus gland 219 220 308 318
322 344 34 350
- Thymus gland (*Continued*)
adult 219
arteries, 220
embryology, 219
lymphatics 220
- Thyro arytenoideus cartilage, 233
- Thyro arytenoideus muscle 211
233, 235 236, 238
- Thyrocervical trunk artery, 689
- Thyrocervical trunk nerves 187,
190 205, 207 208 248
- Thyro epiglottic ligament 234
- Thyro epiglotticus muscle 233, 238
- Thyrohyoid ligaments 234 236
- Thyrohyoid membrane 173 207
209, 233 235
- Thyrohyoid muscle 174 185 186
191 192 208 209 211, 230 233,
234, 236
- Thyroid accessory 216
angle 240
artery 689
accessory 207
arcuate branch 205, 207 208
inferior 177 187 195 201 202
205 207 209 210 214 216
218 222 223 238 250 251
253 325 418 420 421
ligation of 212 215
superior, 172, 177 178 186 195
196 199 202 205 208 215
238
ligation of 211 214 216
- cartilage 170 172 173 184 197
194 204 207 211 213 214
221 229, 233 236 239 241
243 319
- Adam's apple See Larynx
prominence
- cricoid 174
- horns (cornua) 210 214 234
236
- laminae 172 235 236 238
- laryngeal prominence 172 173
235
notch 172 173 214 234 235
oblique line 230 231 234
- ectopic 16
- ganglion 183 187
- gland 170 174 175 177 178
192 193 195 198 200 203
220 222 223, 229 318 319
324
- accessory 204
arteries 206
carcinoma 216
cartilage 178 184 203 206
embryology 203 204 206
isthmus 205 208 211 214 216
240 242 243
ligaments 178
lingual 204 206 216
lobes 205 206 214 216 234
lymph vessels 207 211 216
nerves 211
pole superior 207

- Uterine artery 05 16 0, 1
 24 7 6 8-10, 147 53 63
 carpal branch 8, 753
 collateral 697 699 16 714 0
 cutaneous branch dorsal 8
 deep branch 69
 ligation 731 747
 recurrent 05 715 17 730
 Uterine nerve 6 3 6 5 677 688, 699
 04 06 07 09 712 715 717
 719 721 724 726 728 729 747
 749 753 759 760 62 64 769
 7 0
 communicating branch 61
 cutaneous branch palmar 60
 deep branch 753 755 61 163
 67 710 771 773 75
 digital branch 163 774
 dorsal branch 724 737 750 753
 755 774
 ram, dorsal 776
 superficial branch 761 162 770
 volar branch 724
 Uterine vein 724
 Umbilical artery 363 364 388 394
 396 507 567 568 601 602

- Transverse ligament (*Continued*)
 of biceps brachii muscle 696 710
 of humerus 606 710
 of knee 842 844 852
 of leg 852
 of plantar fascia 883
 superficial 883
 superior of scapula 686
- Transverse process of coccyx 551
 of vertebrae 187 402 904 906
- Transverse sinus of dura mater 37
 40 41 48 50 53
 thrombosis of 54
See also Sigmoid sinus
 of pericardium 335 337 338
- Transverse tarsal joint 893
- Transversus abdominis muscle 267
 268 272 289 363 367 371 373
 375 379 382 384 386 388 390
 392 397 398 401 404 407 409
 410 471 473 554 599 618 810
- Transversus linguae muscle 158
- Transversus perinei muscles 502
 73
- Transversus pinalis muscle 399
 402
- Transversus thoracis muscle 264
 266 269 271 272
- Trapezium bone *See* Multangular bone greater
- Trapezius muscle 10 173 176 182,
 184 185 243 246 359 360 680
 681 684 694 695 700 701
- Trapezoid bone *See* Multangular bone lesser
- Trapezoid ligament 686
- Traube space of 426
- Treitz arch of vascular 450
 ligament of 437 438 440 451
 452 539
- Trendelenburg operation for pulmonary embolus 335
- Trephining operation for exposure of brain 24 26
- Treves cephalic vein of 737
 fold of bloodless 468
- Triangle anal 628 658 661
 posterior 649 650
 avascular 438
 of Calot 522 524
 carotid 152 181 182 250
 epigastric 281
 esophageal 328 329 441 443
 femoral 835 836
 of Scarpa 808 811
 gastric 476
 Heibach's 382 385
 lumbar 381 400
 Macewen's (suprameatal) 18 21
 105
 of neck, anterior 177 178, 181
 243
 carotid 181 182 250
 digastric *See* Submaxillary triangle
 angle
 muscular 181 187
- Triangle (*Continued*)
 of neck (*Continued*)
 occipital 182, 243
 posterior 178 182 243 249
 subclavian, 182
 submental 177 178 180 181
 occipital 243
 Petit's 381 397, 400, 402
 of Scarpa 274
 Simon's 210
 submaxillary 181 182 224 228
 submental of neck 177 178 180
 181
 supraclavicular 243
 suprameatal (Macewen's), 18, 21,
 105
 tibial 835 836
 urogenital 627 634 652
 anterior 649 650
 fascia inferior 637
 vertebral 253
 of vertebral artery 250
- Triangular ligament of liver *See* Urogenital diaphragm
- Triangularis (depressor angulorum) muscle 121 126 128
- Triceps brachii muscle 283 683,
 696 698 700 702 707 708 711
 713 715 716 719 723
 lateral head 681 685 692 697
 698 702 703 710
 long head 679 681 684 692 697
 699 701 705 718
 medial head 681 697 698 703
 709 710
 short head 701
- Triceps surae muscle 876
- Trigeminal nerve 7 16 37 47 61
 65 120 121 134 146 149 193
 ganglia of 62 65
 maxillary division 103
 neuralgia 121 125
 ophthalmic branch 23 96 103
 surgery of 125 126
- Trigone of bladder urinary 566
 568 569 596
 femoral 808 809
 lumbar *See* Triangle Petit's
 urogenital 478
- Triquetrum bone 748 750 754 772
- Triradiate segment of cartilage 547
- Trismus 134
- Triticaceous cartilage 253
- Trochanter of femur 556 794 795
 797 798 802 824 825 828 830
 832 834
- Trochlea of humerus 680 708 709
 714
 of orbital region 16
- Trochlear nerve 16 23 37 47 55
 61 89 103
- Trochlear process 878
- Tube auditory 23 91 92 106 110
 111 114 116
 eustachian *See* Tube auditory
 fallopian *See* Uterine tube
- Tube (*Continued*)
 laryngotomy, 241
 pharyngotympanic *See* Tube auditory
 uterine *See* Uterine tube
- Tuber cinereum 36 38, 58
- Tuber omentale 505 509, 535 536
- Tubercle, carotid 222 252
 of Chassaignac 252
 corniculate 227 237
 cuneiform, 227
 Darwin's 105
 epiglottic 235 239, 240
 of larynx superior, 235
 Lusitane 247 261
 of navicular bone 748
 pubic 383 393, 643
 Santorini's 227
 scalene 247 261
 thyroid 253
 of tibia 862 863
 Wisberg's 227
- Tuberculosis of larynx 240
 pulmonary 316
- Tuberosity calcaneal 870
 deltoid 682 696 698 707 708, 710
 of humerus 707 708 710 712
 ischial 630 650 652 658
 occipital internal 20
 omental 505 509 535 536
 radial 696
 of scapula infraglenoidal 679,
 680 698
 supraglenoidal 681 683 696
- Tubule(s) seminiferous 642
 of testis seminiferous 642
 straight 642
- Tumor(s) axillary 275
 of brain lobe parietal 32, 33
 of breast 275
 of cerebrum 47
 of corpus callosum 34
 of duct thyroglossal 216
 of epulis 150
 of face 201
 of glands parathyroid 220
 parotid 130 132
 of hypophysis 56
 of larynx 240
 of lips vascular 145
 of mesentery 459
 of neck 101
 of orbit 76 77
 of osseous facial 129
 of sinus, maxillary 100 101
 of skull 201
- Tunica albuginea 636 640 642
- Tunica dartos 638 641
- Tunica vaginalis testis 386 388
 638 640 641 646
 cavity 642
 layers 640
- Tunnel carpal 753 765
 digital 765 771 9
 osteoaponeurotic of ankle 870

(3) (Continued)

liver 511
 mbar 354 404 406 470 610
 lunas, 313
 mammary internal 0, 52 69
 2 0 71 368
 mandible 152 153
 maxillary 136 139 14
 maxilla 152 154
 maxillary 136 139 14
 Mayo 427 410 431
 median 16 18
 mediastinal 354 355
 meningeal 41 52
 mesenteric See Mesenteric vein
 middle of heart 336
 muscular 406
 nasal 57
 nose 90, 95
 obturator 571 592 604
 occipital, 5 44 50 52 54 193
 ophthalmic See Ophthalmic vein
 of orbit 85 88
 ovarian 591 593 606 607 610
 of ovary 591
 of pancreas 517
 palmar 458
 pancreaticoduodenal 487
 para umbilical 368
 parietal (temporal) 7 48, 50 51
 107 124 139 198
 of parotid gland 130
 of penis, dorsal, 5 6 577 606 631
 633 635 639
 perforating 805
 pericardial 354 355
 pericardiophrenic, 3 5
 peroneal 853 856 867
 pharyngeal 48 19 198
 phrenic 406 441
 popliteal 818 870 821 831 833
 836 837 840 853
 portal See Portal vein
 posterior of left ventricle 336
 pyloric 427 430 431
 profunda brachii 718
 profunda femoris 813
 of prostate gland 517
 pudendal See Pudendal vein
 pudic See Vein pudendal
 pulmonary See Pulmonary vein
 pyloric 489
 radial 724
 rectal 606 609
 of rectum 481 485 487 490
 renal 354 355 406 407 516 517
 593 607 644
 of retina central 87
 retroperitoneal 490
 retrotarsal 73
 of Retzius, 490 507
 of ribs 261 262
 sacral middle 4 8 481 509 606
 607

Vein(s) (Continued)

apheous See Apheous vein
 scalp 6
 of seminal vesicle 573
 stapedial 481 48 509
 of sinus, petrosal 191 198
 small, of heart 313
 spermatic 406 500 579
 of spermatic cord 643 644
 splenic 421 4 9 430 452 489
 489 511 516 531 53 536
 of stomach 4 9 411
 subclavian See Subclavian vein
 subconjunctival, 3
 subcostal 334 335 404
 sublingual 144
 subscapular 256
 supraclavicular 1 8
 supra orbital 6 7 51 1 0
 suprarenal 3 5 406
 suprascapular 183 197 52
 supratrochlear 6 1 0
 of teeth 99 154
 temporal See Temporal vein
 of temporal and infratemporal re-
 gions, 139 140
 testicular 38 607 64 643
 thoracic 280, 86 36 363
 thoraco epigastric 36 368
 thyroid See Thyroid vein
 thyroidea ima 06 07
 thyrolingual facial trunk, 193
 tibial anterior 853 854 856 867
 8 1
 posterior 85 853 856 867
 871 8 878
 of tongue 159 160
 of tonsils 164
 ulnar 4
 umbilical 363 364 394 396 415
 417 507
 uterine 595 597 608
 of uterus, 606 608
 of vagina 590
 vaginal 595 597
 vertebral 48 05 250 252 253
 356 406
 of Vesalius, 15 154
 vesical 568 5 0
 of viscera pelvic 606 607 609
 Vellum See Falate soft
 Vena cava 315 409
 anastomoses with portal system
 sites of 489 490
 inferior 288 290 292 309 323
 335 342 346 348 357 369
 406 409 415 417 430 449
 451 457 464 483 488 489
 504 508 511 515 517 524
 525 527 530 536 538 593
 607 608 616 618 644
 anomalies of 609
 ligation of 609 610 [610]
 extraperitoneal approach
 transperitoneal operation
 609 610

Vena cava (Continued)

superior 157 25 2 0 105 307
 319 3 0, 3 3 4 331 335
 344 346 348 354 355 35
 168 421 488
 thrombosis, 353
 Vena cava magna (inferior) 37
 Vena cava magna 4 8
 Vena comitantes, epigastric su-
 perior 71
 of mammary artery internal, 0
 71
 musculophrenic 1
 Venae comitantes, brachial, 679
 Venous ligament 513
 sclerae inus, 5-9
 Venous dural sinuses, 50, 53 55, 57
 Ventricular system 4 44
 Ventricle first 4
 fourth 38 41 45
 of larynx 39
 lateral, 41 43 45 47
 left 311 335 341 343 350
 right 331 335 340-343 347 415
 417
 second 4
 third 38 41 43 45 48 55 57
 Ventricleulography 44 4 48
 Ventricleul. See Stomach
 Vermis, 38
 Vertebra(e) atlas (first) 205 906
 axis (epistropheus second) 90
 206
 cervical, 75, 258 94 356, 418,
 419 903 906
 coccygeal 903
 false (fixed) 903
 lumbar 402 4 6 903 905 908
 mediastinal 146
 movable (true) 903
 prominens, 903
 sacral 478 552 903 908
 thoracic 2 7 259 61 264 96
 297 371 376 418 4 0, 903 908
 thoracic tuberculous, 404
 true (movable) 903
 Vertebral artery 47 49 186 187
 190 193 19 197 01 05 750,
 252 254 659
 Vertebral canal 904 907
 Vertebral column See Column ver-
 tebral
 Vertebral vein 48 05 250 2
 253 406
 Vertex of skull 11 1 0
 Verticalis linguae muscle 1 0
 Verumontanus, 577
 Verumontanum 575 577
 Vesalius vein of 152 154
 Vesical artery 567 568 573 577
 595 597 598 601 604 608 610
 643
 Vesical plexus nervous of anal canal
 and rectum 497
 venous 564 565 595 606 608
 630

Uterus (*Continued*)

- ligament broad 581 585, 587
 - 590 593 605 621 623 624, 659 661 663
- round 581 587 590 609 619
 - 623 659 661 663
- lymph vessels 609
- malformations 588
- membrane mucous, 585
- neck *See* Uterus cervix
- nerves 612
 - on 587 591
- partitioned 588
- prolapse 584 659 661
- ectodysplasia surgery for, 623
 - Billy Webster operation, 623
 - Coffey operation 624
 - Cullen operation 623
 - Olshausen operation, 623 624
- simplex 588
- veins 606 608
- Utricle 67, 116 118
 - prostatic 573 577 581, 638
- Uvula 154 155 227, 228
 - of bladder urinary, 566, 568
- Uvular muscle 154 156
- Vagina 475 558 559, 581, 584, 585, 588 591 620 622
 - arteries, 590, 603
 - coats 591
 - embryology 394
 - formix, 581 590
 - lymph vessels 590, 608
 - nerves, 612
 - partitioned, 588
 - relations 589 590
 - veins 590
 - vestibule 589 650 651 653, 656 657 661
 - bulb of 589 590
 - artery of 590
 - wall, 588 589
- Vaginal artery 510 603
- Vaginal ligament 777
- Vaginal plexus venous, 605, 606
- Vaginal vein 535 597
- Vagotomy 328 329 441 442
- Vagus nerve 24 37 47 68 70 130
 - 174, 175, 179 184 186 190
 - 193 200 205 207 209 212 231
 - 238, 253, 290, 304 306 315 317
 - 322 324 328 329 338 347, 351, 353 420 422 423 432 433 441, 459 455 511
 - auricular branch 107 108
 - auriculotemporal branch 107
 - ganglia 420
 - section transabdominal, 437, 441 443
 - trans thoracic splanchnic branch 328 329
- See also* Gastric nerve
- Vallecula cerebelli 38
- epiglottica, 234

- Valves method for inflation of middle ear, 114
- Vilva(s) anal, 182
- aortic, 343, 348, 352
- bicuspid, 341, 343, 344
- coronary, 339, 340
- cuspid, 339 340
- of heart areas of maximum audibility of sounds and their thoracic projection, 348, 350, 352
- mitral, 341, 343 348, 352
- semilunar 340, 344
- of Houston 479
- skorral 444 466
- pulmonary 348 352
- spiral of Helix, 518 520
- of Triculus 339 340
- tricuspid 339 341 344, 348, 352
- of vena cavi, inferior 339
- Varices esophageal 420
- Vasocoele 644 645
- Vasocoelectomy, 645
- Vas deferens 382 564, 565, 570 574, 581 599 677 641 645
 - ampulla 572 574 579, 638
 - artery 602 603 643
- Vasa brevia arteria 325, 428, 429, 529 530 532, 533 541
- Vasa efferentia of testis 641 642
- Vasa recta, 452, 453, 457, 521, 537 542
- Vasomotor nerves sympathetic, 119
- Vasospasm 181
- Vastus intermedius muscle 805, 812
 - 818 822 825 831 834 840
- Vastus lateralis muscle 802, 805, 812, 818 820 822 826, 831 834 840
- Vastus medialis muscle 805, 811
 - 813 818, 819, 822 826, 831, 833, 849
- Vater ampulla of, 518, 521 523, 527, 536 537, 539
- Carcinoma 539
- Vein(s), of abdominal wall an
 - terior 366 368
 - posterolateral 404
 - of anal canal 481 483, 487 490
 - angular, 48 51, 119 153, 154, 162
 - anterior of heart 336
 - of arm 706
 - auditory 24
 - auricular 50 127 131, 183, 197, 198 245
 - axillary 252 281 283 286 366 670 672 673 678, 679 688 706, 716 718
 - azygos *See* Azygos vein
 - basilic 672 679 696 697, 699 706 707 716 719 724
 - of bladder urinary, 568
 - brachial 672 697 699 706 713
 - of brain 48 55 57
 - of breast 280
 - bronchial 354

Vein(s) (*Continued*)

- capsular, 406
- cardiac 341, 345, 347
- cephalic *See* Cephalic vein
- cerebellar, 50, 52 53
- cerebral, 34 40 50, 52 54
 - of Cerebrum 53
- cervical, 18 183 197 215, 252
- ciliary 82
- chlorid dorsal 606 651 656, 658
- profunda, 654
- colic, 481 185 488, 501
- of colon 481, 485, 487 490
- communicating, 191, 717
- coronary 323, 420, 489
- cubital median 717, 725
- dental 142 152, 154
- diaphragmatic, 430
- diaphic, 40 49 52 51 110
- of elbow region, 716 718
- emissary *See* Emissary vein
- epiblastic 366 367, 370 378, 379
 - 470 806, 807
- esophageal 354
- of esophagus 420, 421, 431
- ethmoidal 95
- of eye 78, 82, 87
- of eyelids 73
- of face, 120
- facial *See* Facial vein
- femoral *See* Femoral vein
- frontal 3, 7
- of Galen 37, 53
- gastric, 420, 421 429, 430, 431 481 490
- gastro epiploic 325 427, 430 432 487 489 530 531
- great of heart, 336
- of head, 48 55 57
- of heart 343 347
- hemilarynx 292 323 324 347 354 357 406 419 421 488
- hemorrhoidal *See* Hemorrhoidal vein
- hepatic, 430 488 490, 504 506 511 524, 536
- hypogastric *See* Iliac vein, in femoral
- ileocolic 181 488 509
- iliac *See* Iliac vein
- iliolumbar, 490 600
- infra orbital 99
- innominate *See* Innominate vein
- intercostal 276 271 306 354 355 357 406, 490
- intervertebral 406
- of intestine large 481 485, 487 490
- jugular *See* Jugular vein
- of kidney 406 407
- labial 654
- lingual 236 238
- lingual 48 146 148 158 160 179 203
- of lip, 145

Vein(s) (Continued)

- of liver 311
- lumbar 354 404 406 470 610
- of lungs, 313
- mammary internal 0, 5 68
 - 2 0 71 368
- of mandible 15 153
- marginal, medial 818
- maxillary 6
- of maxilla 152 154
- maxillary 136 139 142
- of Mayo 42 430 431
- median 716 18
- mediastinal 354 355
- meridional 41 52
- mesenteric *See* Mesenteric vein
- middle of heart 336
- muscular 406
- nasal, 57
- of nose 90, 95
- obiturator 5 2 592 604
- occipital, 5 7 48 50 57 54 198
- ophthalmic *See* Ophthalmic vein
- of orbit 83 88
- ovarian 591 593 606 607, 610
- of ovary 593
- of pancreas 537
- parietal 488
- pancreaticoduodenal 482
- para umbilical 368
- parietal (temporal) 7 48, 50 51
 - 10, 17, 139 143
- of parotid gland 130
- of p. jvi 606 608
- of penis, dorsal 516 517 606 631
 - 613 635 639
- perforating 805
- pericardial 354 355
- pericardiophrenic, 1 5
- peroneal 853 856 867
- pharyngeal 48 197 198
- phrenic 406 441
- popliteal 818 820 871 831 833
 - 836 837 840 853
- portal *See* Portal vein
- posterior of left ventricle 336
- prepyloric 427 430 431
- profunda brachii 118
- profunda femoris, 813
- of prostate gland 577
- pudendal *See* Pudendal vein
- pudic *See* Vein pudendal
- pulmonary *See* Pulmonary vein
- pyloric 489
- radial 724
- rectal 606 609
- of rectum 481 485 487 470
- renal 354 355 406 407 516 517
 - 593 607 644
- of retina central 87
- retropontoneal 490
- retrotarsal 73
- of Retzius 490 507
- of ribs 261 262
- sacral middle 478 481 509 606
 - 607

Vein(s) (Continued)

- apophenous *See* Apophenous vein
- scalp 6
- of seminal vesicles, 575
- sinusoidal 481 485, 07
- of sinus, petrosal 19, 198
- small of heart 336
- spermatic 406 500 577
- of spermatic cord 641 644
- splenic 421 429 430 459 488,
 - 459 511 516 531 537 596
- of stomach 4 9 431
- subclavian *See* Subclavian vein
- subconjunctival 13
- subcostal 354 355 404
- sublingual 148
- subscapular 286
- suprascapular 118
- supra orbital 6, 5 1 2 0
- supratrenal 3 5 406
- suprascapular 183 197 252
- supratrochlear 6 1 0
- of teeth 99 154
- temporal *See* Temporal vein
- of temporal and infratemporal regions, 139 140
- testicular 342 607, 647 643
- thoracic 50, 786 36 368
- thoraco epigastric 36 368
- thyroid *See* Thyroid vein
- thyroidal ima 06 07
- thyrolingual facial trunk 193
- tibial anterior 853 854 856 867
 - 871
- posterior 852 853 856 867
 - 871 872 878
- of tongue 159 160
- of tonsils, 164
- ulnar 124
- umbilical 61 364 394 396 415
 - 417 507
- uterine 595 597 608
- of uterus, 606 608
- of vagina, 590
- vaginal 595 597
- vertebral 48 05 250 252 253
 - 336 406
- of Vesalius 152 154
- vesical 568 570
- of viscera pelvic 606 607 607
- Vellum *See* Palate
- Vena cava 315 409
 - ana. tomoses with portal system
 - sites of 489 490
 - inferior 283 290 292 309 373
 - 335 342 346 348 373 368
 - 406 409 415 417 430 449
 - 451 457 464 485 488 489
 - 504 508 511 515 517 524
 - 525 527 530 536 538 593
 - 607 608 616 618 644
 - anomalies of 609
 - ligation of 609 610 [610]
 - extraperitoneal approach
 - transperitoneal operation
 - 609 610

Vena cava (Continued)

- superior 177 252 2 0 305 307
 - 319 3 0 322 324 331 335
 - 344 346 349, 354 355 357
 - 364 421 488
- thrombosis, 333
- Vena cerebri magna (galeni) 37
- Vena vortiosa 18 87
- Venae comitantes, epigastric su
 - prior 211
- of mammary artery internal, 2 0
 - 211
- musculophrenic 271
- Venae comites, brachial 6, 9
- Venous ligament 513
- sclerae sinus, 18- 9
- Venous dural sinuses, 50 53 55 57
- Ventricular system 42-44
- Ventricle first 42
 - fourth 38 41 45
 - of larynx 239
 - lateral 41 43 45-47
 - left, 331 335 341 343 350
 - right 131 335 340-343 342 415
 - 417
 - second 47
 - third 38 41 43 45 48 52 57
- Ventriculography 44 4 48
- Ventriculus *See* Stomach
- Vermis 38
- Vertebra(e) atlas (first) 905 906
 - axis (epistropheus second) 905
 - 906
 - cervical, 257 258 294 356 418
 - 419 903 906
 - coccygeal 903
 - false (fixed) 903
 - lumbar 40, 4 6 903 905 908
 - mediastinal 346
 - movable (true) 903
 - prominens, 905
 - sacral 418 557 903 908
 - thoracic 5, 259 61 264 96
 - 297 321 3 6 418-4 0 903 905
 - thoracic, tuberculous, 404
 - true (movable) 903
- Vertebral artery 47 49 186 187
 - 190 193 195 197 201 0 250
 - 2 2 754 689
- Vertebral canal 904 907
- Vertebral column *See* Column vertebral
- Vertebral vein, 48 20 250 75
 - 753 406
- Vertex of skull 11 110
- Vetrical linguae muscle 1 5
- Verumontanus 577
- Verumontanum 575 517
- Vesalius vein of 152 154
- Vesical artery 567 568, 573 577
 - 595 597 598 601 604 608 610
 - 643
- Vesical plexus nervous of anal canal
- and rectum 497
- venous, 564 565 59 606 608,
 - 630

- Vesical vein 568 570
 Vesicle seminal *See* Seminal vesicle
 Vesicoprostatic plexus 568 570
 Vesico uterine ligament 594, 595
 Vesiculitis, seminal 577
 Vestibular glands, greater 651 652
 654 655 657
 lymph of vagina 589 590
 Vestibular ligament of larynx 240
 Vestibular nerve 67 115 117 118
 Vestibule of inner ear 116 117
 of larynx 240
 of mouth 147 149
 of nose 90 91 93
 of vagina 650 651
 bulb 652 654
 Vidian artery *See* Pterygoid canal
 artery of
 Vidian nerve *See* Pterygoid canal
 nerve of
 Villae arachnoid 44
 Vincent's spirochete aspiration of
 with foreign body or blood 316
 Vincula 166
 Viscera (pelvic) 562 593
 arteries 600 605 608
 female 581 593
 embryology 581 582
 ligaments 582 585
 broad of uterus 581 58
 587 590 593 604 621 623
 624 659 661 663
 cardinal 560 582 585 588
 cervical transverse 582 585
 infundibulopelvic 582 585
 591 593 603 604 621 623
 Mackenrodt 560 561 582
 585 588 594 595 659 661
 ovarian 582 585 587 591
 593 619 621
 round of uterus 581 587
 590 610 619 624 659 661
 663
 uterosacral 587 584 586
 594 597 619
 lymphatics 607 608 610
 nerves 612 618 621
 lumbar sympathetic chain
 614 617
 surgery of 616 621
 lumbar sympathectomy
 616 618 621
 lumbar sympathetic block
 616 618
 presacral (superior hypo
 gastric) neurectomy
 619 621
 ovary *See* Ovary
 surgery of ligation of iliac
 artery 609 611 612
- Viscera (pelvic) female ovary
 (Continued)
 surgery of ligation (Cont.)
 of inferior vena cava
 608 610
 uterus 584 588
 vagina *See* Vagina
 lymphatics 607 608 610
 male 570 581
 ducts deferent 571 573
 prostate gland 572 580
 seminal vesicles 572 574 576
 veins 606 607 609
 Visual center lower 38
 Vitelline artery 414 415
 Vitello intestinal duct 364 394
 Vocal cords 234 235 238, 239 242
 false 233 236 240
 true 233 236 240
 Vocal ligaments 211 233 236
 Vocal muscle 211 238
 Volkmann's ischemic contracture
 712 718
 Volvulus 467 472
 Vomer bone 90 92, 93 139 228
 Vulva, 588 649
 lymphatics 603
 prunitus 655
 Wakeley 468
 Waldeyer fossa of, 454
 ring of 158
 Walters 432
 Walton 719
 Watson Jones 802
 Weaver's bottom 791
 Web(s) of fingers 762
 space 761
 of hand infections, 778 780
 Weber 353 799
 Wharton duct of *See* Duct sub
 maxillary
 jelly of 396
 Whipple 515 539
 White 360
 Whitlow 784
 Wilkey 664
 Willis circle of 41 47 49 197 203
 253
 Wilson 432
 Winslow foramen of 423 434 521
 524 576
 Wirsung pancreatic duct of 534
 536
 Wisdom teeth 134 150 152
 Wolff 277
 Wolfian body 387
 Wood tonsillar gland of 165
 Wright 277
 Wrisberg cartilages of 235 239
 ligament of 842 844
- Wrisberg (Continued)
 lobe of azygos vein lung 308
 tubercle of, 227
 Wrist 748 758
 abduction 732
 distal skin crease 750 753
 structures distal 752 753
 layers 751 752
 proximal 750 752
 extension, 732 733
 flexion 748
 infection 766 779 781
 joints, 753 756
 carpometacarpal 754, 755
 intercarpal 754 755
 intermetacarpal 755
 interphalangeal 756
 metacarpophalangeal 755 756
 pisiform 754
 radiocarpal 753 754
 transverse 754 755
 ligaments 755
 surgery of, 756 758
 amputation 758
 arthrodesis 757
 disarticulation 758
 dislocations 756 757
 fracture of navicular bone 756
 tendons dorsum 775
 Wolcott 800
- Xiphoid (ensiform) process 258
 267 264 333 349 352 363 375
 441 511
 Xerger 614 615
 Xylemas 160
- Zeis glands of 72 74
 Zieman 383 384 412
 Zimmerman 383
 Zinn ligament of 85
 zonule of 79
 Zona orbicularis *See* Zone orbicu
 lar
 Zone orbicular 793 795, 796 798
 Zonula ciliaris 87
 Zonule of Zinn 79
 Zygozoma bone 10 17 14 16 18 70
 28 99 121 124 130 131 134
 136 177 178
 resection 161
 Zygomatic area muscles 126 128
 Zygomatic artery 86
 Zygomatic nerve 16 17 66 127
 Zygomatic process 15 19 98
 Zygomaticofacial nerve 64 121
 Zygomaticotemporal nerve 19 64
 Zygomaticus muscles 5 120 126
 128 148

